



**Automotive Industry** 



Shipbuilding Industry



Railway Industry



# Index

Index



# 2022-2023 KORLOY CUTTING TOOLS



Turning



Milling



Holemaking



Endmilling

### **CONTENTS**

# GRADES & CHIP BREAKERS

### A Grades

A02 KORLOY grades system

#### **Turning Grades**

A04 Turning grade selectionsA05 CVD coated gradesA10 PVD coated grades

A12 Uncoated Carbide grades

A13 Cermet grades

A15 Coated Cermet grades

#### Milling Grades

A16 Milling grade selectionsA17 CVD coated grades

A18 PVD coated grades

A23 Uncoated Carbide grades

A24 Cermet grades

### A Solid Endmills & Solid Drills

A25 Solid Endmills grade selections

A26 Solid Endmills grades

A27 Solid Drills grade selections

A28 Solid Drills grades

### Others (Turning/Milling/Endmills)

A29 Diamond coated grades

A30 DLC coated grades

A31 cBN inserts grades

A36 PCD inserts grades

#### **Chip Breakers**

A37 Chip Breaker for Turning

A42 Chip Breaker for Milling

A49 Chip Breaker for Drilling

### **TURNING**

### B Turn

### **Turning Chip Breakers**

**B02** Application range of KORLOY main Chip Breakers

**B04** Recommended Chip Breakers for workpiece

**B16** Feature of Chip Breakers

#### **Inserts**

**B34** Turning Insert Code System (ISO)

**B36** Turning Insert (Negative)

B73 Turning Insert (Positive)

B102 Aluminum Insert (Positive)

B110 cBN Inserts

B113 PCD Inserts

#### **Save Turn**

**B114** Technical Information for Save Turn

B115 Save Turn (Insert)

B116 Save Turn (Holder)

B119 Save Turn (Boring Bar)

### **Auto Tools**

**B121** Technical Information for Auto tools

B122 ISO type

B127 KHP Coolant

B136 Blade type

B139 Multi Utility type

B142 KGT/MGT type

B145 MSB Tool

B151 Sleeve

### Multi Turn

**B152** Technical Information for Multi Turn

B154 Multi Turn

### **B** Bearing Solutions

**B155** Technical Information for Bearing Solutions

**B156** Bearing Solutions

**B161** Special Order Form for Bearing Inserts

#### **External Tool Holder**

B162 External tool Holder Code System (ISO)

**B163** Index for External Holder

**B166** Instruction of External Holder assembly

B167 Double Clamp System

B172 Lever Lock System

B179 Wedge Clamp System

B181 Clamp on System

B183 Multi Lock System

B190 Screw on System

B197 Ceramic Holder

### **High Pressure Coolant**

B199 Technical Information for KHP Coolant

**B202** KHP Coolant

### **Boring Bar**

B204 Boring Bar Code System (ISO)

B205 Index for Boring Bar

B207 Instructions of Boring Bar assembly

**B208** Double Clamp System

B210 Lever Lock System

B212 Clamp on System

Data Maria I G

B213 Multi Lock System

B215 Screw on System

B225 Compact Mini

### **TURNING**

B HSK/KM Tooling system

**B228** Technical Information for HSK/KM Tooling System

B230 Index for HSK/KM Tooling System

B231 HSK Tooling systemB237 KM Tooling system

**B** Cartridges

**B241** Cartridge Code System (ISO)

**B242** Index for Cartridge

B243 Clamp on System

B245 Screw on System

### MULTI FUNCTIONAL TOOLS

C Application Example

C02 Application Example

C04 Technical Information for Multi Functional tools

KGT

**C07** Technical Information for KGT

C12 KGT

C25 KGT Blade for Parting off

**MGT** 

C26 Technical Information for MGT

C28 MGT

C36 MGT (Face grooving)

KGT/MGT Cartridge

C39 Technical Information for KGT/MGT Cartridge

C40 KGT/MGT Cartridge Holder

C41 KGT Cartridge

C42 MGT Cartridge

**MGT Aluminum Wheel Series** 

C43 Technical Information for MGT Aluminum Wheel

C44 MGT Aluminum Wheel

ТВ/ТВ-М

C47 Technical Information for TB/TB-M

C51 TB/TB-M

C K Notch

C55 Technical Information for K Notch

C57 K Notch

Saw Man

C60 Technical Information for Saw Man

C61 Saw Man

Saw Man-X

C63 Technical Information for Saw Man-X

C65 Saw Man-X

**Fine Tools** 

C67 Technical Information for Fine Tools

C68 Fine Tools

**Grooving/Parting off** 

C70 IGH

C70 DBH

C71 GFIP

**Special Order Form** 

C72 Special Order Form for MGT

C73 Special Order Form for V-Pulley Insert

#### **THREADING**

Threading Code System

**D02** Threading Holder/Insert Code System

**Technical Information for Threading** 

D03 Technical Information for ThreadingD09 Threading Insert with Chip Breaker

**Thread Inserts** 

D10 Partial profile 60°D11 Partial profile 55°

D12 ISO Metric

Thread Inserts

D16 American UN (UN, UNC, UNF, UNEF, UNS)

D18 Whitworth (BSW, BSF, BSP, BSB)

**D22** British Standard Pipe Thread (BSPT)

D22 National Pipe Thread (NPT)

D23 National Pipe Threads-Dryseal (NPTF)

D23 Round DIN405 (RD)

D24 Trapez DIN103 (TR)

D24 American ACME (ACME)

D25 Stub ACME (STACME)

### **CONTENTS**

#### **THREADING**

Thread Inserts

**D26** UNJ (Unified Constant Thread)

D28 American Buttress (ABUT)

D28 British Buttress (BBUT)

D29 Metric Buttress (SAGE)/API

D30 API Buttress Casing (BUT)

D30 API Round Casing & Tubing (APIRD)

D30 Extreme Line Casing (EL)

### Thread Holders

D31 External Holder

D32 Internal Holder

D33 Vertical Type Holder

#### **Thread Milling**

D34 Technical Information for Thread Milling

D44 Thread Milling InsertD49 Thread Milling Holder

### **MILLING**

Insert

**E02** Milling Insert Code System (ISO)

E04 Milling Inserts

E34 KORLOY Cutters

E42 KORLOY Shanks

**E45** KORLOY Modular Adaptors

### **Face Milling Cutters**

E47 Mill-max (ISO)/Mill-max Plus (E48, E54)

E57 Mill-max Heavy

E59 Turbo Mill

E62 Double Mill

E64 Power Buster

E71 Rich Mill

E147 Aero Mill-Aero Mill-Plus/Aero Mill-Mini

E156 PCD face cutter

#### **Cutters for Molds**

E157 Alpha Mill/Alpha Mill Nick

E193 Alpha Mill-X

E201 Future Mill/Future Mill P-Positive

E254 Triple Mill

E262 HFMD

**E277** HFM

E284 HRMDouble

E300 HRM

E307 Tank Mill

E308 TP2P

E317 Laser Mill/GBE/BRE

E337 HAVE(Multi-edge, Single-edge)

**E341** Technical Information for BT/HSK Tooling System

**E342** BT Tooling System (Alpha Mill, Mono-Tool)

E353 HSK Tooling System (Alpha Mill, Mono-Tool, Pro-V Mill)

E364 O-ring Cutter

E366 Chamfer Tool (Multi-functional, Solid)

E374 T-Cutter(TFE)

### E Milling Cutter for Aluminum

E375 Technical Information for Pro-A Mill/

Pro-X Mill/Pro-L Mill/Pro-XL Mill/Pro-V Mill

E385 Pro-A Mill

E388 Pro-X Mill

E394 Pro-L Mill

E398 Pro-XL Mill

E401 Modular Adaptor (MAT/BT/HSK)

#### **Side Milling Cutters**

**E405** Technical Information for Side Milling Cutters

**E407** Side Milling Cutters

E411 Side Cutter

E414 Wind Mill

### Milling Cutter for Cast iron at high feed

E418 Technical information for High feed Cutter

**E420** Technical information for Cube Mill

E421 Technical information for Couple Mill

E423 Technical information for Shave Mill

E425 Technical information for Shave Mill Ultra

### **Detail Information of Milling Cutter** and **Arbor**

E426 Actual Designation of Milling Cutter and Arbor

#### **Gear Tools**

**E429** Technical information for Gear Cutter Tools

E430 Gear Cutter Table

E431 Gear Cutter

E439 Gear Cutter Order Form

E440 Indexable HOB

E441 Indexable HOB Cutter Order Form

### **DRILL**

**Technical Information for Drills** 

F02 **KORLOY Drills** F54 F03 Available Insert F63 TPDB-F

**Indexable Drills** 

F05 King Drill King Drill (for through coolant system F20

with a lathe) King Drill (for large diameter drilling) F24

F26 KED Plus Drill TPDC Plus Drill F37

**Indexable Drills** 

TPDB Plus Drill

TPDB-H F68

F75 Technical information for WPDC

F78 Center Drill **WPDC** F79

Reamer

F82 Indexable Reamer

### **TOOLING SYSTEM**

**Tooling System** 

G02 Tooling System Index

G04 DHE/S G07 DHE

DHC/DHJ Collet G11

G12 DSC G20 NPM G23 DCS/DC/TC Collet Chuck Series

G25 SDC/P G30 DSK

G32 GSK G34 **GERC** G36 ER

G37 ER/L G38 RTJW

G40 NPU G41 DST

G43 TER Tap Collet

G44 DTN

G46 TCA Tap Adaptor

G47 SLA

G **Tooling System** 

G49 **FMA** 

G50 **FMC** 

G52 MD G54

**EXT Bar** RDC Bar G54

**G55** FBH/B

DBCA G62

**G66** DBC

**G68 SMB** 

**KMB** G70 G72 SMH

**TBCA** G74

G79 TBC

FBC G82

**G85** SAH

G86 Angular Head

G94 DZC G95 DCJ

G96 DCL

**G97** DAMPING PRO

G104 Others

### **PARTS**

**Parts** 

H02 Shim

Cartridge/Chip Breaker

H03 Chip Cover/Clamp

Coolant Bolt/Wrench Bolt H04

H04 Lever

H05 Locator/Nut

# H05

**Parts** Pin/Screw

H06 Shim Pin

H07 Spring/Wrench

Stop Ring/Washer H07

H07 Stopper/Nozzle

# **CONTENTS**

# TECHNICAL INFORMATION

### General Information I

I 02 Workpiece material grades

I 06 Steel, Non-ferrous metal symbol list

I 07 SI unit conversion table

108 Hardness calculating table

I 09 Properties of Korloy grades

### **Technical Information**

I 10 Technical Information for Turning

I 20 Technical Information for Milling

### Technical Information

I 24 Technical Information for Tapers

I 27 Technical Information for Endmills

I 30 Technical Information for Drill

#### **General Information II**

I 36 The comparision of chip breakers

I 37 KORLOY Grades

I 40 The comparision of grades for Turning/Milling

# OLD-FASHIONED PRODUCT INFORMATION

# Old-fashioned product information

J02 Grade

J02 External Holder

J02 Fine Tool

J03 Threading Tool

### J Old-fashioned product information

J03 Mill-Max

J04 Cen-Mill

J04 Jip Drill

J04 LPD/SPD/NPD

### **INDEX**



### SAFETY GUIDE OF CARBIDE PRODUCTS

KORLOY Inc. is continuously trying to develop safer and higher quality products Please be aware of the safety guidelines below prior to using KORLOY Inc. products

- It is generally accepted that the proper handling of cemented carbide tools requires awareness of safety as noted above. For more information, please contact us.
- · KORLOY does not accept any responsibility for any accident caused by inappropriate use, abuse of tools, or changes to the products.

### 1. PL (Product Liability)

In accordance with the PL (Product Liability) law, we have attached a WARNING label on the case of KORLOY products.

There is no warning on the surface of the tools. Please read this safety guidelines before using carbide tools and provide safety education to all users.

#### 2. Basic characteristics of CEMENTED CARBIDE tools

Cemented carbide tools are made of carbides, nitrides, carbonitrides, oxides of Tungsten (W), Titanium (Ti), Alluninyum (Al), Silicon (Si), Tantalum (Ta), Boron (B) etc. and metal component like Cobalt (Co), Nickel (Ni), Chrom (Cr), Molybdenum (Mo) as binder. Cemented carbides tools have high hardness and specific gravity. Generally there's no smell but according to usage and treatment, appreance and color could be changed

### 3. Precaution for CEMENTED CARBIDE tools

- 1) Cemented carbides are extremely hard and brittle at the same time. Impact shock or excessive clamping power could cause fracture or breaking of the tool.
- 2) Cemented carbides have large specific gravity, thus they require special attention as a heavy material when you handle big sizes or large quantities.
- 3) Cemented carbides have different thermal expansion coefficient with steel and ferrous materials. Shrink fit or swell fit products may cause trouble if they are used at undesirable conditions like extremly high or low temperatures.
- 4) There are several cemented carbide products having sharp cutting edges. Be careful not to handle the tools with bare hands which may cause cuts or injury, especially when removing the tools from the case, do not touch the cutting edge and be careful not to drop it.
- 5) Storing carbide tools in a corrosive atmosphere may cause erosion which can reduce toughness.
- 6) Please refer to the catalouge safety guidance prior to handling the tools.
- 7) Do not absue tools under inappropriate conditions.


### 4. Precaution for machining (grinding, welding, EDM) of CEMENTED CARBIDE tools


- 1) Surface condition can affect the toughness of the tool, so it is recommended to use a diamond grinding wheel.
- 2) Grinding of cemented carbide creates mist and dust. It contains harmful compositions like Cobalt (Co), thus it is recommended to use a mask, mist collection, and other protective facilities. If the dust gets in your skin or eye, rinse immeditely with continously running water.
- 3) In case of grinding with coolant, coolant contains harmful metal components which cause environmental problems. Handle the coolant according to the manufacturer's recommendations.
- 4) Check for cracks after re-grinding carbide tool and reuse.
- 5) Marking with laser or electric pen may cause cracks on the carbide tool. The crack can shortened tool life.
- 6) EDM of carbide may cause residual cracks on the carbide tool, so if necessary, remove the crack with a grinding process.
- 7) Brazing of carbide tools at extremly high or low temperatures compare with the melting point of brazing materials may cause loosening or breakage.
- 8) Overheating a oil base coolant may cause a fire or flames, thus be prepared for fire prevention.

#### 5. METALCUTTING SAFETY

	DANGEROUS FACTOR	SAFETY COUNTERPLAN
	· Sharp cutting edge of cutting tools may cut your bare-hand	· Use gloves when pulling out the insert from the case or mounting it on the machine
	$\cdot$ Inappropriate conditions or usage may cause fragmentation and expel parts of tools which may cause injury	Use glasses or safety cover for your safety     Use the tools within the recommended range     Please refer to catalogue and safety guidelines first
	$\cdot$ Severe load on tool and premature wear of cutting edge may bring excessive cutting force on tool, causing fracture of the tool and may cause injury	Use glasses or safety cover for your safety     Change the tool as required before excessive wear or fracture
sloc	$\cdot$ Chips evacuated during cutting are hot and sharp and maycause burns and cuts	Use glasses or safety cover for your safety     Stop machining and put safety glove on and use a hook tool to remove chips
gtc	$\cdot$ Touching the workpiece immediately after cutting may cause burns	· Use gloves or safety cover for your safety
Cutting tools	$\cdot$ Be aware of sparks, fire, or explosion of hot chips generated during the cutting operation	Do not use at the place where having explosive materials     Prepare for fire extinguishments
	$\cdot$ In case of high RPM machining, vibration and chattering may occur due to the improper balance of the machine	Use glasses or safety cover for your safety     Check first if there's any chattering, vibration or strange noises prior to your main cutting operation
	$\cdot$ Touching a burr remaining on the workpiece with a bare-hand may cause a cut	· Do not touch the burr with bare-hand · Use gloves or safety cover for your safety
	$\cdot$ Loose clamping of the workpiece may cause the tool to fracture and result in damage to the cutter body and possible injury	· Clamp the workpiece tightly
	· Tools are operated to right-hand direction normally · Left-hand direction operation can cause fracture of tool and body damage	Do not use left-hand direction without notice     Check the package of product to check the availability of left-hand operation
s sple	$\cdot$ Loose clamping of inserts and parts may result in ejection of the tool during cutting and may cause serious injury	Check the clamping of inserts and parts prior to machining,and use original parts only
Indexable tools	$\cdot$ Over loaded clamping of inserts by a lever (such as a pipe) may cause dangerous fracturing of parts and inserts	· Do not use lever inappropriately
	$\cdot$ In case of high speed machining, parts and inserts can be forced out by centrifugal force	· Use within recommended condition · Use glasses or safety cover for your safety
	$\cdot$ Since cutter has sharp cutting edges touching with a bare-hand may cause a cut	· Use gloves or safety cover for your safety
sloc	· It is dangerous to use glove with rotating machine · Contact with body or clothes is dangerous with rotating parts	Do not wear gloves when you work with rotating machine     Keep your body and clothes away from rotating machine
Rotating tools	· Vibration generated by balancing trouble may cause a fracture and ejection of the tool which may cause serious injury	RPM should be controled within recommended condition     Check the balance of rotating part periodically
Rotat	· In case of drilling, the uncut bottom core can fly out of the part with high speed and cause serious injury	· Use gloves or safety cover for your safety
	· The edges of small diameter drill are sharp and easy to break	Concentrate on safety regulation in using tools.     Use glove or safety cover for your safety.
Brazed	· Fragmentation and ejection of brazed carbide tip may cause injury	Check the brazed tip before using     Do not use at high temperature cutting condition
ETC	· There's a possibility of breaking the carbide tip after several brazing	· Do not use brazing a tip that has been brazed several times
<u> </u>	· Abusing may cause fragmentation of tool and is very dangerous	· Stick to safety regulations and guidelines

### **KORLOY Inc. Code System**





### Terminology of tool formula

TERM	CODE	UNIT		
Tool diameter	D	mm		
Cutting speed	vc	m/min		
Revolution per minute	n	min <sup>-1</sup>		
Feed per minute	vf	mm/min		
Feed per revolution	fn	mm/rev		
Feed per tooth	fz	mm/t		
Tooth	z			
Axial depth of cut	ар	mm		
Radial depth of cut	ae	mm		
Peak feed	pf	mm		

TERM	CODE	UNIT
Horse power requirement	Pc	kW
Specific cutting resistance	kc	MPa
Torque	Mc	N.m
Thrust	Tc	N
Cycle time	tc	min
Tool life	Т	min
Flank wear	VB	mm
Crater wear	Kt	mm
Nose radius	r	mm

### **Introduction of Digital Catalogue**


1. Connect to the digital catalogue on PC or mobile

https://catalog.korloy.com

### 2. Guideline for main screen

Special tooling

For special tooling such as gear, edge miller, railway, non-standard indexable & facemill



### 3. Details


### Sub application




### Item group




### Item



ltem data, 2/3D modeling, etc.





#### **Grades**

A02 KORLOY grades system

### **Turning Grades**

A04 Turning grade selections
A05 CVD coated grades
A10 PVD coated grades
A12 Uncoated Carbide grades
A13 Cermet grades
A15 Coated Cermet grades

### **Milling Grades**

A16 Milling grade selections
A17 CVD coated grades
A18 PVD coated grades
A23 Uncoated Carbide grades
A24 Cermet grades

#### **Solid Endmills & Solid Drills Grades**

A25 Solid Endmills grade selections
 A26 Solid Endmills grades
 A27 Solid Drills grade selections
 A28 Solid Drills grades

### Others (Turning/Milling/Endmills)

A29 Diamond coated grades
A30 DLC coated grades
A31 cBN inserts grades
A36 PCD inserts grades

### **Chip Breakers**

A37 Chip Breaker for TurningA42 Chip Breaker for MillingA49 Chip Breaker for Drilling



### **Grades system**

### Cutting tool

	Р	Steel	ST10	ST20	ST30A
	M	Stainless steel	U20		
Uncoated	K	Cast iron	H01	H05	G10
carbide	S	Titanium alloy	H01	H05	
	N	Aluminum ally/Copper ally	H01	H05	
	Н	Hardened steel	H01		

	Р	Steel	NC3215	NC3225	NC3120	NC3030	NC5330	PC5300	PC5400	PC3035			
	M	Stainless steel	PC8105	PC8110	PC8115	PC8120	NC9115	NC9125	NC5330	NC9135	PC5300	PC9030	PC5400
Coated carbide	K	Cast iron	NC6310	NC6315	NC5330	PC5300	PC5400						
for turning	S	Heat resistant alloy	PC8105	PC8110	PC8115	PC8120	NC9125	NC9135	PC5300	PC5400			
	N	Non-ferrous metal	ND3000	PD1005	PD1010								
	Н	Hardened steel	PC8105	PC8110	PC8115								

Multi- functional S	P	Steel	NC3210	NC3225	NC3030	NC5330	PC3035
	M	Stainless steel	PC9030	PC5300			
	K	Cast iron	NC6315	PC5300			
	S	Heat resistant alloy	PC8110	PC5300			
	N	Non-ferrous metal	H01	H05			
	Н	Hardened steel	PC8110	PC5300			

	Р	Steel	NC5330	NCM535	PC3700	PC5300	PC5400	NCM545
	M	Stainless steel	NC5330	PC5300	PC9530	PC5400	PC9540	
Coated		Cast iron	PC6510	NC5330	NCM535	PC5300	PC5400	NCM545
carbide for milling	S	Heat resistant alloy	PC5300	PC5400	PC9540			
	N	Non-ferrous metal	ND3000	PD1005	PD1010			
	Н	Hardened steel	PC2005	PC2010	PC2015	PC210F	PC2505	PC2510

	Р	Steel	PC3700	PC5300	PC5335	PC9530	PC9540	NC5330	NCM535
Coated	M	Stainless steel	PC5300	PC5335	PC9530	PC9540			
carbide for drills, endmills	K	Cast iron	PC6510	PC5300					
	S	Heat resistant alloy	PC5300	PC9530	PC9540				
	N	Non-ferrous metal	H01						

### **Grades system**

### Cutting tool

Turning	Р	Steel	CN1500	CN2500					
cermet	K	Cast iron	CN1500	CN2500					
Coated carbide for	P	Steel	CC1500	CC2500					
turning cermet	K	Cast iron	CC1500	CC2500					
Milling cermet	Р	Steel	CN2500	CN30					
	P M K	Steel	PC203F	PC215F	PC303S	PC310U	PC315E	PC320	PC320S
Solid	S	Heat resistant alloy	PC320	PC320S	SL				
endmills	N	Non-ferrous metal	ND3000	ND2100	PD1005	PD1010	PC210C	H01	H05S
	Н	Hardened steel	PC203F	PC303S	PC310U				
	P M K	Steel	PC325U	PC215G	PC315G	PC230F			
Solid drills	S	Heat resistant alloy	PC325T						
	N	Non-ferrous metal	FG2	FA1	ND2100				
	K	Cast iron	DBN500	DBN700A					
cBN	S	Heat resistant alloy	DBN700						
	Н	Hardened steel	DB1000	DB2000	DBNX20	DBN250	DBN350	DBN400	
Coated cBN	Н	Hardened steel	DNC100	DNC250	DNC350	DNC400			
PCD	N	Non-ferrous metal	DP90	DP150	DP200				


### Wear resistance tool

Ultra fine grain cemented carbide	Z	Ultra fine grain cemented carbide	FS1	FA1	FCC	
Uncoated carbide	٧	Wear parts	D1	D2	D3	G5
	1	Corrosion resistance	IN10	IN20	IN40	

### Mining tool

Uncoated carbide	Е	General	GR10	GR20	GR30	GR35	GR40

### Application range




Feed rate, fn (mm/rev)




# A Turning Grades


### **Turning grade selections**


### Selection system





### Application range of turning grades

















### NC3215/NC3225

- Universal grade especially for machining forged automobile components and bearing steel both in continuous and interrupted cutting
- Available for all kinds of steels carbon steel, alloy steel, rolled steel, tool steel, mild steel, bearing steel and other special kinds of steel
- New coating technology increases welding resistance and chipping resistance, which leads to longer tool life

#### Features

- · Stable tool life
  - → Higher production stability
- · Longer tool life & Higher removal rate
- → High cutting conditions and shorter cutting time available
- · Ideal combination of a grade and chip breakers
- → Prolongs tool life
- → Wide applications ranging from roughing to finishing



NC3215/NC3225

Unstable tool life

Flaking



Competitor


edge Little VB wear







NC3215/NC3225 Competitor


ullet Disperse cutting force ullet Reduce chipping ullet Increase tool life ullet Improved productivity





### Application range









CVD coated grade for high efficiency and quality turning of cast iron

NC6310 W/ NC6315 W


- CVD coating with improved wear resistance and chipping resistance.
- Solutions for the most common issues in cast iron machining: Preventing excessive wear on rake and flank surfaces of insert, chipping and burr

#### Features of NC6310







### Recommended machining range for each grade



#### Features of NC6315







Turning grades for stainless steel


# NC9115 (MC9125 (MC9135 (MC9135

- Optimized for reducing built-up edges, notch wear, plastic deformation and burrs, and for machining stainless steel
- Ideal combination of a grade and MM/RM chip breakers for stable tool life and wide applications ranging from roughing to finishing
- Stable tool life even at high speeds, feeds and depth of cuts (for STS316, vc over 150 m/min available), shortening cutting time
- · Excellent versatility responding to workpiece change, covering the austenite, the martensite and the ferrite
- NC9115 is for P20 class, mild steel and forged steel machining.

#### Features

· Improved surface finish thanks to the new lubricative CVD coating


### Lubricative coating layer to prevent built-up edge







Existing coating



- Top coat with improved welding resistance
- Alumina coating layer for high speed cutting
- H Titanium coating layer with stronger resistance to chipping
- Tough substrate optimized for continuous cutting and both light & heavy interruption

- Lubricative coating layers  $\rightarrow$  Improves welding resistance

### Inhibited built-up edge and blade damage




NC9125 (M25)




Competitor (M25)

 Coated layers of stronger chipping resistance and the substrate of high toughness → Inhibits notch wear creation

### Inhibited wear on notch and relief surface








Competitor (M35)



### Grades line up



### Recommended grade and chip breaker per stainless steel type

#### [Austenitic stainless steel]

Grade	Cutting speed (m/min)									
	50	10	100		150		200		250	
NC9115					160		220			
NC9125					150	200				
NC9135			100	150						

#### [Duplex stainless steel]

Cuada	Cutting speed (m/min)									
Grade	50		10	00	150		200		250	
NC9115					120 1	60				
NC9125				100	140					
NC9135		60	100							

#### [Ferritic/Martensitic stainless steel]

Ounds	Cutting speed (m/min)									
Grade	50		10	00	15	50	20	00	25	0
NC9115						150			250	1
NC9125					120			220		
NC9135				100	150					

#### [Precipitation hardened (PH) stainless steel]

				_						
Ounds	Cutting speed (m/min)									
Grade	50	100	150	200	250					
NC9115	50	110								
NC9125	40	110								
NC9135	30	100								

### Selection system of CVD coated grade

	Workpiece	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range
		Continuous cutting	NC3215	295 (170~420)	P10	
			NC3225	260 (150~370)	P15	NC3215
Р	Steel		NC3223	200 (150~370)	P20	NC3225 NC3120
		Interrupted cutting	NC3120	260 (120~370)	P25	NC3120
			NC3030	205 (120~290)	P30	NC3030 NC5330
			NC5330	185 (110~260)	P35	1400000
		Continuous	NC9115	240 (220~260)	M10	NC9115 new
М	Stainless	cutting	NC9125	_	M20	NC9125 NC5330
	steel	Interrupted			M30	NC9135
		cutting	NC9135	_	M40	new)
		Continuous cutting	NC6310	380 (300~500)	K10	NC6310 NC6315
K	Cast iron	Interrupted	NC6315	280 (200~400)	K20	100010
		cutting	NC5330	190 (110~270)	K30	NC5330
S	HRSA	Continuous cutting	NC9125	40 (20~60)	S10	NC9125
3	IIIOA	Interrupted cutting	NC9135	40 (20~00)	S20	NC9135

### The features of CVD coated grades

CVD Coated grades	ISO	Features
NC3215	P10~P15	Continuous machining of general steel and forged steel at high speed     Substrate with excellent thermal crack/plastic deformation resistance, coating with improved chipping resistance for continuous machining     MT-TiCN + Al <sub>2</sub> O <sub>3</sub> + TiN
NC3225	P20~P25	Universal grade for general steel and forged steel     1st recommended grade for general machining with the use of high toughness substrate and coating layer with improved welding/chipping resistance     MT-TiCN + Al <sub>2</sub> O <sub>3</sub> + TiN
NC3120	P20~P25	Medium to roughing for steel     Combining excellent fracture resistance substrate with chipping resistance and heat resistance Al <sub>2</sub> O <sub>3</sub> increased stability     MT-TiCN + TiC + Al <sub>2</sub> O <sub>3</sub>
NC3030	P25~P35	Medium to low speed machining of steel and interrupted roughing     Harmony between substrate with excellent wear/fracture resistance and Al2O3 film with excellent thermal/chipping resistance     Increased stability in wide ranges of cutting conditions     MT-TiCN + TiC + Al2O3 + TiN
NC5330	P30~P35 M25~M35 K15~K25 S15~S25	Stainless Steel - General cutting for mild steel & forging steel Excellent cutting performance in hard to cut materials which are vulnerable to built up edge, due to the high tough substrate with improved fracture resistance and the coated layers  MT-TICN + Al <sub>2</sub> O <sub>3</sub> + TIN
NC9115	M10~M20	High speed cutting for ferritic and martensitic stainless steels     MT-TiCN + Al <sub>2</sub> O <sub>3</sub> + TiN
NC9125	M20~M30	General cutting of stainless steel and heat resistant alloys     MT-TiCN + Al <sub>2</sub> O <sub>3</sub> + TiN
NC9135	M30~M40	Interrupted cutting of stainless steel and heat resistant alloys     MT-TiCN + Al <sub>2</sub> O <sub>3</sub> + TiN
NC6310 (ew)	K01~K10	High speed and continuous cutting of grey cast iron     Increased tool life due to coating layer with high wear resistance     MT-TiCN + Al <sub>2</sub> O <sub>3</sub> + TiN
NC6315	K10~K20	Universal grade for ductile and gray cast Iron     Excellent performance thanks to the alumina (Al <sub>2</sub> O <sub>3</sub> ) coating's improved grip on the tough substrate     MT-TiCN + Al <sub>2</sub> O <sub>3</sub>

# A Turning Grades

### **PVD** coated grades

### Turning grade for heat resistant alloy and stainless steel

### PC8105

- · Micro grain carbide minimizes chipping of cutting edge due to enhanced edge strength
- · Latest PVD coating technology with high hardness and high temperature oxidation resistance
- · Excellent tool life when finishing heat resistant alloys and stainless steels at high speeds

### **PC8110**

- Substrate with superior wear resistance and plastic deformation resistance at high temperature
- PVD coating technology with high hardness and oxidation resistance at high temperature
- Long tool life when machining heat resistant alloy and stainless steel at high speed

### PC8115

- Ultra fine matrix technology increases wear resistance and chipping resistance
- PVD coating technology with high hardness and oxidation resistance at high temperature
- · Strong cutting edge and excellent chipping resistance guarantees stable machining
- · Long tool life when machining heat resistant alloy and stainless steel at middle to low speed and medium cutting to roughing

# PC8120



- Control technology for uniform ultra-fine substrate increases wear resistance and chipping resistance
- The new PVD dioxide film enhances oxidation resistance and heating resistance
- Special technology of coating surface treatment prevents chipping and realizes stable machining


#### Features

### Features of PC8105/10/15 series It prevents wear at a high temperature to apply excellent surface roughness and coating with oxidation resistance and high hardness I It improves wear resistance

to equalize submicron matrix, secure stability between corners and improve chippingand wear resistance

### PC8120 PVD multi-layer → Reducing cracks 0 PVD oxidation layer → Good oxidation resistance and heating resistance PVD nitride → Good wear resistance Substrate Laver

### Grades line up



### Selection system of PVD coated grade

,	Workpiece	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range
		Continuous cutting	PC5300	175 (100~250)	P30	PC5300
P	Steel	Interrupted	FC5500	145 (80~120)	P40	PC5400
		cutting	PC5400	125 (80~160)	P50	
			PC8105	175 (120~230)	M01	
		Continuous cutting	PC8110	160 (110~210)	M10	PC8105 PC8110
М	Stainless		PC8115/8120	150 (100~200)	M20	PC8115 PC8120 PC5300
IVI	steel		PC5300	135 (80~190)	M30	PC9030 PC5400 P
		Interrupted cutting	PC9030	130 (80~180)	M40	100400
			PC5400	110 (80~140)	M50	
		Continuous cutting	PC8110	135 (95~180)	K10	PC8110
K	Cast iron		1 00110	100 (95~100)	K20	PC5300
K	Cast IIOII	Interrupted cutting	PC5300	105 (75~140)	K30	PC5400
			PC5400	90 (65~120)	K40	100400
			PC8105	55 (40~70)	S01	PC8105
	Heat	Continuous cutting	PC8110	50 (35~65)	S10	PC8110 PC8120 PC8120
S	resistant		PC8115/8120	45 (30~60)	S20	PC5300
	alloy	Interrupted	PC5300	40 (20~60)	S30	PC5400
		cutting	PC5400	35 (20~50)	S40	
			PC8105	110 (80~140)	H01	PC8105
Н	Hardened	Interrupted cutting	PC8110	100 (70~130)	H05	PC8110
			PC8115	90 (65~115)	H10	PC8115

### The features of PVD coated grades


PVD Coated grades	ISO	Features					
PC8105	M05~M15 S01~S10 H01~H05	For high speed and continuous finishing of hard-to-cut materials and STS     Excellent cutting performance with high wear resistance and oxidation resistance     Ultra fine substrate and the new TiAIN coating layer					
M10~M20 K10~K20 S05~S15 H05~H10		For high speed and continuous medium cutting of hard-to-cut materials and STS     Excellent tool life with high wear/plastic deformation resistance at high temperature     New TiAIN coating layer and substrate with excellent thermal resistance					
PC8115	M15~M25 S10~S20 H10~H15	For medium to low speed and medium to rough cutting of hard-to-cut materials and STS     Excellent tool life with high wear resistance and chipping resistance     Ultra fine substrate and the new TiAIN coating layer					
PC8120 M15~M25 S10~S20		For hard-to-cut materials and STS roughing     Applied ultra-fine substrate and new PVD oxidation layer     Better chipping resistance and fracture resistance than PC8115					
PC5300	P30~P40 M20~M30 K20~K25 S15~S25	Universal grade for stainless,HRSA,steel and interrupted cast iron machining     High chipping and welding resistance for longer tool life     New TIAIN coating and ultra fine grain substrate adopted					
PC9030	M25~M35	Medium,roughing and heavy interrupted cutting for stainless steel     TiAlN coating and ultra fine grain substrate adopted     High chipping and welding resistance for stable machining					
PC5400	P35~P45 M30~M40 K30~K35 S25~S35	For medium cutting for hard-to-cut materials, stainless steel, steel, and cast iron at medium or low speed     Stable machinability with chipping resistance, fracture resistance and welding resistance     Ultra fine substrate with high toughness and new AlCiN layer					

### **Uncoated carbide grades**

### Uncoated carbide grades for turning application of titanium


### **H01**

- Increased wear resistance and chipping resistance with the use of ultra fine substrate
- Improved welding resistance and chipping resistance with the use of special surface treatment and sharp cutting edge of VP chip breaker
- Excellent tool life when finishing titanium alloy at high speed




### **H05**

- The 1st recommended grade for machining titanium alloy in a variety of cutting conditions
- Improved welding resistance and chipping resistance with the use of special surface treatment and sharp cutting edge of VP chip breaker
- Ideal for medium cutting of titanium alloy



### Grades line up



### Selection system of uncoated carbide grades

	Workpiece	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range
		ST10	110 (70~140)	P10	ST10
P	Steel	ST20	80 (50~110)	P20	ST20
		ST30A	70 (40~90)	P30	ST30A
M	Stainless steel	U20	70 (40~90)	M25	U20
		H01 105 (60~140) K01	H01		
K	Cast iron	H05	105 (60~140)	K10	H05
		G10	90 (50~120)	K20	G10
N	Aluminum alloy	H01	600 (450~750)	N10	H01
IN	Copper alloys	H05	425 (320~530)	N20	H05
s	Titonium allau	H01	55 (40~70)	S01	H01
5	Titanium alloy	H05	50 (35~65)	S10	H05
Н	High hardness steel	H01	80 (55~105)	H10	H01

### Main composition and application range

Workpiece Composition		Features	Workpiece		
Р	WC-TiC-TaC-Co	Heat resistance, excellent plastic deformation resistance	Carbon steel, Alloy steel, Stainless steel		
M	WC-TiC-TaC-Co	General tools stable heat resistance with strength	Carbon steel, Alloy steel, Stainless steel, Cast steel		
K	WC-Co	High strength and superior wear resistance	Cast iron, Non-ferrous metal, Plastic, etc.		
S	WC-Co	Excellent wear resistance and chipping resistance	Titanium alloy		

### The physical properties of uncoated carbide grades

Workpiece	Grade	Hardness (HRA)	TRS (kgf/mm²)	Young's modulus (103kgf/mm2)	Thermal expansion coefficient (10-6/°C)	Thermal conductivity (cal/cm · sec·°C)	
	ST10	92.1	175	48	6.2	25	
P	ST20	91.9	200	56	5.2	45	
	ST30A	91.3	230	53	5.2	-	
M	U20	91.1	210	-	-	88	
IVI	ST30A	91.3	230	53	5.2	-	
К	H01	92.9	210	66	4.7	109	
K	G10	90.9	250	63	-	105	
s	H01	92.9	210	66	4.7	109	
5	H05	91.8	250	-	-	-	

 $1KPa = 102kgf/m^2$ ,  $1w/mk = 2.39 \times 10^{-3} cal/cm \cdot sec \cdot ^{\circ}C$ 

### **Cermet grades**

### Solution for turning application of steel

### **CN1500**

- For continuous machining of cold/hot forged steel and Sintered ferrous alloy at high speed and low depth of cut
- Excellent wear resistance and crater resistance
- Improved surface roughness acquired by optimized cutting edges


### **CN2500**


- For high interrupted machining of cold/hot forged steel and Sintered ferrous alloy at high feed and high depth of cut
- Excellent resistance against chipping, fracture and thermal crack
- Improved surface roughness acquired by optimized cutting edges



			_				
Division	Workpiece	Grade	Recommended cutting speed (m/min)				
DIVISION	workpiece	Grade	Minimum	Recommended	Maximum		
	SM10C,	CN1500	150	270	400		
	SS440	CN2500	130	240	350		
БL	SM45C	CN1500	150	250	350		
Turning	3101430	CN2500	130	220	300		
7	SCM440, Sintered	CN1500	120	220	300		
	Fe ferrous alloy	CN2500	100	200	250		

### Grades line up









### **Cermet grades**

### Chip breakers line up





### Selection system of cermet grades

W	orkpiece	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range
		Continuous	CN1500	500 250 (150~350)		CN1500
P	Steel				P20	CN2500
		Interrupted cutting	CN2500	220 (130~300)	P30	CN2300

### Comparison of chip breakers

Insert	Machining	Application yours	Chip breakers						
types	types	Application range	KORLOY	Competitor A	Competitor B	Competitor C	Competitor D		
	Continuous cutting	For machining mild steel with enhanced chip control	VL	FA	GP	TF	FA		
Nega	General cutting	VB	FG	XP CQ	TSF TS	LU SE			
type	General cutting	For medium cutting to finishing at low interruption	VQ	MC	HQ	AS, ZM	SU		
	Interrupted cutting	For medium cutting to roughing at high interruption		MT	HS	TM	GU		
	Continuous cutting	For machining mild steel with enhanced chip control	VL	FA	GP	PF	FP		
Posi	Continuous cutting	Enhanced chip control when machining internal diameter with stronger cutting edges than VL chip breaker	VF	FG-PC	HQ	PS	LU		
type	General cutting	For medium cutting to finishing at low interruption	MP	FG	HQ	PS	LU		
	Interrupted cutting	For medium cutting to roughing at high interruption	C25	MT	GK	24	SC		

### Coated cermet grades

### Coated cermet for machining carbon steel, alloy steel and sintered ferrous components

# CC1500 \*\*\*

- Maximized resistance to built-up edge and oxidation in continuous cutting at high speeds and low depth of cuts
- Superior wear resistance vs. existing tools in continuous cutting of carbon steel and alloy steel


# CC2500 rew

- Maximized resistance to built-up edge and oxidation in interrupted cutting at high feeds and high depth of cuts
- Superior impact resistance vs. existing tools in interrupted cutting of carbon steel and alloy steel


### Recommended cutting condition

Division	Workpiece	Grade	Recommended cutting speed (m/min)				
DIVISION	workpiece	Grade	Minimum	Recommended	Maximum		
	SM10C,	CC1500	200	350	450		
	SS440	CC2500	180	290	400		
бL	SM45C	CC1500	200	300	400		
Turning	SIVI43C	CC2500	180	270	350		
Ē	SCM440, Sintered	CC1500	180	270	350		
	Fe ferrous alloy	CC2500	150	250	300		


### Chip breakers line up




### Features



### Grades line up





### Selection system of coated cermet grades

	•		•			
Workpiece	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range	
	Continuous cutting	CC1500	325 (200~450)	P10	CC1500	
P Steel				P20		
	Interrupted cutting	CC2500	265 (180~350)	P30	CC2500	
Coot ivon	Continuous cutting	CC1500	270 (180~350)	K10	CC1500	
K Cast iron	Interrupted cutting	CC2500	250 (150~300)	K20	CC2500	


### The features of coated cermet grade

Coated cermet	ISO	Features			
CC1500	P10~P20 / K05~K15	• PVD coated Cermet	Light cutting for steel and cast iron in high speed machining	Optimized for precision boring	
CC2500	P20~P30 / K10~K20	• PVD coated Cermet	• Light cutting for steel and cast iron in medium or high speed machining	• Dry and wet cutting are available	


# A Milling Grades

### Milling grade selections

### Selection system



### Application range




PD: DLC/DP: PCD (Uncoated)

Milling Solutions for Steel and Cast Iron




- Improved chipping resistance / heat and crack resistance: Applied after treatment with good chipping resistance and heat and crack resistance
- Improved wear and heat resistance: Applied high toughness substrate and high functional CVD alumina

#### Features



### Guideline for grade application



### Selection system of CVD coated grades

	Workpiece	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range
		Continuous	NC5330	200 (150~250)	P20	Norsee
P	Steel	Interrupted	NCM535	300 (200~400)	P25 P30	NC5330
	Sieei		ing	300 (200~400)	P35	NCM535
				200 (150~250)	P40	NCM545
		cutting	140101010	200 (100* 200)	P45	
M	Stainless	Continuous	NC5330	150 (120~180)	M10	NC5330
10	steel	cutting	1403330	130 (120~100)	M20	1403330
		Continuous cutting NC5330	NCESSO	200 (150~250)	K10	
K	Cast iron		INCOOOU	200 (150~250)		NC5330 NCM535
			NCM535 @	<b>2</b> 50 (200~300)	K30	NCM535 NCM545

### The features of CVD milling grades

CVD Coated grades	ISO	Features					
NC5330	P20~P30 M20~M30 K15~K25	For high speed milling of steel and stainless steel     Superior wear resistance and chipping resistance grade for steel and stainless steel     MT-TiCN + Al2O3 + TiN					
NCM535	P30~P40 K20~K30	Rising CVD milling grade for high productivity in large steel and cast iron machining at high speed     High toughness and thermal conductivity substrate and high functional CVD coating layer with heat resistance     High chipping resistance and heat and crack resistance from excellent after treatment     MT-TiCN + Al2O3					
NCM545	P40~P50 K30~K40	For steel and cast iron milling with high toughness     High toughness substrate and high functional CVD coating layer     High chipping resistance and heat and crack resistance from excellent after treatment     MT-TiCN + Al <sub>2</sub> O <sub>3</sub>					




### PVD coated grades for finishing high hardened steel


### PC2005/PC2010/PC2015

- Finishing grade lineup for tool steel and plastic die steel
- PC2005 with extremely hard substrate and coatings
- PC2010 with high hardened cutting edges, ideally suited for pre-hardened steel and interrupted cutting
- PC2015 for carbon steel and casting machining, demonstrating excellent performance in hard-to-cut materials

### Application guideline per workpiece



### Features



- · Heat shield coating was applied to prevent thermal crack.
- · Ultra fine WC was combined with high contents cobalt to be optimized for machining pre hardened steel.


#### PVD coated grades for roughing high hardened steel

- Roughing grade series for high hardened steel
- PC2505 with excellent wear resistance, ideal for machining die steel and high hardened steels over HRC50
- PC2510 with stabilized toughness, ideal for interrupted cutting of high hardened steel and wet cutting accompanied by massive thermal shock

### Application guideline per workpiece

#### Recommended grade Cutting speed, vc (m/min) 280 PC3700 PC3600 240 PC5300 200 160 PC5400 120 PC2510 80 PC2505 40 30 40 60 Workpiece hardness (HRC)

### Features




### Milling grade specialized for steel




- Excellent chip removal rate due to a tough substrate specialized for steel, and lubricative PVD coating of high-hardness
- · A highly chipping-resistant grade for minimized deviation and extended tool life under various cutting conditions

### Features


- · Smooth surface due to special surface treatment
- → Smooth chip evacuation, improved chipping resistance and surface finish of the workpiece



· Substrate for general milling applications of steel and PVC coating treatment



### Application range






### **Universal PVD grade**

### **PC5300**


- · Advanced PVD coating with high hardness and high temp stability
- High tough substrate and coating films produce excellent surface finish
- Universal tooling capability covering P, M, K, S with this single grade, PC5300
- Stable machining resulting from excellent edge hardness and chipping resistance

### Features



- Latest PVD coating technology developed by KORLOY
- New concept of coating equipped with high temperature oxidation resistance and high hardness


### High temp properties




### **PC5400**

- New PVD coating layer with high toughness and lubrication
- High adhesive strength and toughness between the substrate and coating layer
- Excellent cutting edge strength and chipping resistance ensure stable machinability for P, M, K, S.

### Features





### Crack creation on the coating surface after leaving an indentation by 60kg



Normal coating



High toughness coating




### Optimal PVD grade for medium to rough cutting and highly interrupted milling in stainless steel


PC9540 @W

- Longer tool life due to higher breakage resistance applying high toughness substrate controlling crack growth
- Excellent and new PVD dioxide film with oxidation and heat resistance overcoming the limit of hard-to-cut materials machining
- Stable machinability by preventing welding and chipping due to applying special coating surface treatmen


#### Features




#### New PVD dioxide film (comparison of thermal conductivity)



#### Special coating surface treatment technology






PC9540

Existing grade

### Application range



# A Milling Grades

### Selection system of PVD coated grades

١	Vorkpiece	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range		
		Continuous	PC3600	235 (180~290)	P20	PC3600		
Р	Steel	cutting	PC3700 @	235 (180~290)	P30	new		
	Sieei	Interrupted	PC5300	195 (150~240)	P40	PC3700 PC5300 PC5400		
		cutting	PC5400	145 (80~210)	P50			
		Continuous	PC5300	130 (100~160)	M20	PC5300		
М	Stainless	cutting	PC9530	130 (100~160)	M30	PC9530		
IVI	steel	Interrupted	PC5400	120 (95~155)	M40	PC5400 PC9540		
		cutting	PC9540 @	110 (80~140)	M50			
		Continuous	S DOCE 10	DC6F10	PC6510	180 (140~230)	K01	POCE40
K	Cast iron		PC0510	160 (140~230)	K10	PC6510		
	Cast Iron	Interrupted cutting	PC5300	145 (110~180)	K20	PC5300		
			PC5400	125 (85~160)	K30	PC5400		
		Continuous	PC5300	55 (40~70)	S10			
S	HRSA	cutting	F03300	55 (40~70)	S20	PC5300		
3	IIIOA	Interrupted	PC5400	40 (30~50)	S30	PC5400 PC9540		
		cutting	PC9540 @	40 (30~50)	S40	103340		
			PC2005	60 (40~80)	H01	PC2005 PC2505 1eV 1eV		
н	High hardness	Continuous	PC2010	55 (40~70)	H10	PC2010 PC2510 PC2015 PC210F		
П	steel	cutting	PC2015	50 (35~65)	H20	PG2013 PG210F		
			PC210F	50 (35~65)	H30			

### The features of PVD coated grades

PVD Coated grades	ISO	Features				
PC3600	P20~P30	Milling grade for medium and roughing of steel     New coating layer with superior wear resistance and oxidation resistance with high toughness substrate				
PC3700 (1eW)	P30~P40	• Exclusive grade for milling grade • Lubricated and high hardness multi-layered coating				
PC5300	P30~P40 K20~K30 M20~M30 S15~S25	Superior universal grade for steel, cast iron, hard to cut material, stainless steel     New coating and ultra fine grain provide wear resistance and oxidation resistance     TIAIN Series new coating				
PC5400	P35~P45 K25~K35 M30~M40 S25~S35	<ul> <li>Universal grade for interrupted machining of steel, cast iron, hard-to-cut materials and stainless steel with stable machinability</li> <li>New coating layer with high toughness and lubrication on ultra fine grain substrate with high toughness</li> <li>AlCiN series new coating</li> </ul>				
PC6510	K05~K15	High speed milling grade for cast iron and aluminum     K-Gold coating				
PC9530	M25~M35 S20~S30	Medium to rough cutting of hard to cut materials such as stainless steel, Cr-Ni steel, etc.     The toughest sub-micron substrate provides excellent cutting performance at high feed     TiAIN coating				
PC9540 100V	M35~M45 S30~S40	Exclusive high toughness grade for stainless steel milling     PVD dioxide film with good heat resistance				
PC2005	H01~H10 P01~P10 K01~K10	• Exclusive for Laser Mill in milling of high hardness workpieces and press mold steel • Utmost wear resistance due to high hardness substrate and coating • Ultra high hardness K-Brown coating				
PC2010	H05~H15	Exclusive for Laser Mill in milling of pre hardened steel and plastic mold steel     High hardness enhanced cutting edges due to ultra fine WC and high contents binder for expanding application range to high hardness steel and pre hardened steel     Ultra high hardness K-Brown coating				
PC2015	H10~H20	• Exclusive for Laser Mill in milling of carbon steel and cast • Highly lubricative K-SILVER coating • Lubricative coating layer and high contents substrate for machining mild steel and hard-to-cut cast material				
PC210F	H10~H20 P25~P35 K15~K25 M15~M25 S10~S20	High speed milling grade for hardened steel, cast iron, and stainless steel(Laser Mill)     New coating and ultra fine grain provide wear resistance and oxidation resistance     TIAIN Series new coating				
PC2505 10W	H01~H10	Roughing grade for high hardened steel and pressed die steel     Excellent wear resistance ideal for machining die steel and high hardened steel over HRC50				
PC2510 1000	H05~H15	Roughing grade for pre-hardened steel and plastic die steel     Stabilized toughness ideal for interrupted cutting of high hardened steel and wet cutting accompanie by massive thermal shock				


### **Uncoated carbide grades**

### Features

 Due to KORLOY's advanced sintering technology, our uncoated carbide grades have a fine alloy structure which is necessary to get superior quality from a uncoated cutting tool

### Advantages

- Consist of P,M,K carbide grades and can be used in all kinds of workpiece
- Excellent quality at machining with coolant, due to the superior thermal crack resistance of the carbide
- Due to the special design of carbides, it has fine micro structure and low affinity with workpiece
- It has excellent toughness and produces lower cutting loads



### Selection system of uncoated carbide grade

	Workpiece	Grade	Recommended cutting speed (m/min)	ISO	Application range
Р	Steel	ST20	90 (70~110)	P20	ST20
	Steel	ST30A	80 (60~100)	P30	ST30A
	Otainless steel	LIOO	00 (70, 110)	M20	U20
M	Stainless steel	U20	90 (70~110)	M30	020
	Cast iron	H01, H05	150 (110~190)	K10	H01 H05
K	Cast Iron	G10	120 (90~150)	K20	G10
	Aluminum alloy	H01	600 (450~750)	N10	Lind
N	Copper alloys	H05	425 (320~530)	N20	H01 H05

### Main composition and application range

Workpiece	Composition	Features	Workpiece		
P	WC-TiC-TaC-Co	Excellent thermal shock resistance and plastic deformation resistance	Carbon steel, Alloy steel, Stainless steel		
М	WC-TiC-TaC-Co	General grades with thermal shock resistance and hardness	Carbon steel, Alloy steel, Stainless steel, Cast steel		
K	WC-Co	High hardness and superior wear resistance	Cast iron, Non-ferrous metal, Non metal		

### The physical properties of uncoated carbide grades

Workpiece	Grade	Hardness (HRA)	TRS (kgf/mm²)	Young's modulus (10 <sup>3</sup> kgf/mm <sup>2</sup> )	Thermal expansion coefficient(10-6/°C)	Thermal conductivity (cal/cm·sec·°C)
	ST10	92.1	175	48	6.2	25
Р	ST20	91.9	200	56	5.2	45
	ST30A	91.3	230	53	5.2	-
M	U20	91.1	210	-	-	88
V	H01	92.9	210	66	4.7	109
К	G10	90.9	250	63	-	105



### **Cermet grades**

### Features

- High hardness substrate ensures long tool life in high speed milling
- High toughness cutting edge ensures long tool life even in high impact machining
- Chemically stable substrate provides excellent surface finish of the workpiece

### Selection system of cermet grades

Workpiece		Machining types	Grade	Recommended cutting speed (m/min)	ISO	Application range
_	Ctool	Continuous cutting	CN2500	250 (200~300)	P20	CN2500
	Steel	Interrupted cutting	CN30	150 (100~200)	P30	

### The features of cermet grades

Cermet Grade	ISO	Features	
CN2500	P20~P30	<ul><li>Universal grade from finishing to roughing of steel</li><li>Functionally gradient material</li></ul>	
CN30	P25~P35	For milling of steel     Cermet with high toughness	

### The physical properties of cermet grades

Workpiece	Grade	Hardness (Hv)	TRS (kgf/mm²)	SG (g·cm <sup>-3</sup> )
Р	CN2500	< 1800	210 <	6.8~7.0
	CN30	< 1500	240 <	7.0~7.3




### Solid endmills grade selection

## PC303S/PC310U

- Ultrafine substrate & high hardness coatings for excellent wear resistance
- Special surface treatment provides higher chipping resistance

#### Features




Exceptional wear resistance resulting from extremely hard coating layers

### SL

 Applied high lubrication coating and special surface treatment technology

#### Features




Enhanced welding resistance, chipping resistance and machining stability due to surface treatment technology

## **PC315E**

Fine substrate & lubricative coatings for stable machinability

#### Features




 Lubricative coatings for excellent machinability

## **PC305H**

• Enhanced wear resistance and stability from frictional heat due to high hardness substrate and high hardness coating

#### Features



#### Selection system

١	Vorkpiece	Grade	ISO	Application range
		PC303S	P01	
		PC310U	P10	PC303S
Р	Steel	Steel	P20	100100
		PC315F	P30	PC315E         PC320         PC215F         PC215F
		PC320	P40	
		PC303S	M01	
М	Stainless	PC310U	M10	PC303S
IVI	steel	PC320S	M20	PC320S PC315E PC320 PC215F
		PC315E	M30	PG313E PG320 PG213F
	Cast iron	PC303S	K01	
		PC310U	K10	PC303S
K			K20	
		PC315E	K30	PC315E PC320 PC215F
		PC320	K40	
s	HRSA	PC320S	S20	PC320S PC315E PC320 PC215F SL
3	ппон	PC315E	S30	1 CO 10L 1 CO20 10L
		ND3000 new	N01	ND3000 new new new
N	Nonferrous	ND2100 💖	N05	ND2100 PD1005 PD1010 PD1010 H01 H05S
IN	Nomenous	PD3000	N10	ND2100 PD1005 PD1010 H01 H05S PC210C
		H01	N20	P62100
	High	PC303S	H01	
н	hardness	PC203F	H10	PC303S         PC203F         PC305H           PC310U
	steel	PC310U	H20	F03100

# Solid endmills grade

### **ᢒ** Grade information for each product

Item	Grade			
iteiii	Coated	Uncoated		
H-Star Endmill	PC305H	-		
V Endmill	PC215F	-		
Z Endmill	PC315E	-		
F Endmill	PC203F	-		
T Endmill	PC2510, ND3000	H01		
I <sup>+</sup> Endmill	PC320	-		
Z <sup>+</sup> Endmill	PC320U	-		
S+ Endmill	PC320S	-		

Item	Carl	bide	HSS		
iteiii	Coated	Uncoated	Coated	Uncoated	
R+ Endmill	PC10T, PC20T PC30T, PC40T	FN30T	HC10T, HC20T, HC30T	HN20T, HN30T	
Aluminum Solid Endmill	PD1005, PD1010	H01	-	-	
A <sup>+</sup> Endmill	-	H05S	-	-	
M+ Endmill	PC40T	-	-	-	
C-Max	PC210C	-	-	-	
Super Endmill	SL	-	-	-	
D Endmill	ND3000	-	-	-	
Composite Router Endmill	ND2100	-	-	-	
Brazed Endmill	PC221F	FCC	-	-	

### The features of Coated grades

Workpiece	ISO	Features				
PC305H	P05~P15, M05~M15, K05~K15, H05~H15	• Grade with higher Si, enhanced wear resistance and stability from frictional heat due to applying the new AITiSiN series layer				
PC315E PC320	P20~P35, K20~K35	• Excellent wear/welding resistance in high speed machining due to the combination of ultra fine substrate and PVD coating • For low/medium speed machining of general steel • New film applied with excellent chipping/wear resistance				
PC320S	M20~M30, S20~S30	Low to medium speed cutting of stainless steel and heat resistant alloys     Advanced coating layers with increased resistance to built-up edge and oxidation     Excellent resistance to wear and built-up edge at high speeds due to the ultrafine substrate and dedicated coating layers				
SL	S20~S30	• Exclusive Endmill for Inconel • Coating layer with oxidation resistance and high hardness • Reducing fracture on cutting edge and enhancing wear resistance				
PC210C	N10~N20	Medium to high speed cutting of copper and copper electrode     Medium to high speed cutting of acrylic materials     K-Silver coating with excellent lubrication and wear and chipping resistant substrate				
ND3000*10	N01~N05	For electrode machining of graphite at medium to high speeds     Dia. coating layer with high wear resistance and lubrication				
ND2100*	N03~N08	For composite materials     Diamond-coated layers with excellent adhesion				
PD1005	N05~N10	For Non-ferrous metals(Aluminum alloy) machining     DLC(Diamond Like Carbon) coating layer with high wear resistance and lubrication				

<sup>\*:</sup> CVD

#### Features of KORLOY endmills

Index	Features
H-Star Endmill (Endmill for high hardness steel)	Carbide endmill for high hardness (HRC50~63) steel     Suitable for precision cutting due to high precision tolerance on radius and tool diameter
Z Endmill / I <sup>+</sup> Endmill (Endmill for general cutting)	• Excellent in machining various workpieces such as carbon steel, alloy steel, cast iron, pre hardened steel, etc. under HRC45 • Longer tool life with the use of ultra fine substrate and new coating technology
<b>T Endmill</b> (For dental purpose)	Endmill for dental prostheses made of zirconia, titanium, Co-Cr, wax, PMMA, and glass ceramic     Custom-made tools for each type of milling machines for dental purpose
Z⁺ Endmill	Universal endmill applicable to a variety of workpiece materials under HnC47     Roughing and finishing availability     Improved tool life thanks to the new substrate and the most advanced coating     Inhibited chipping and longer cutting time due to the optimized blade design
SSEA / A <sup>+</sup> Endmill (Endmill for aluminum)	Suitable for high speed machining in aluminum and other Non-ferrous materials     Can accomplish excellent surface finishing, superior chip removal in high feed rate
M⁺ Endmill (Multi-functional endmill)	Various cutting with one Endmill: Drilling, Ramping, Slotting and Side Milling     Reducing cutting resistance and enhancing surface finish due to high tool rigidity
S <sup>+</sup> Endmill (Endmill for hard-to-cut materials)	Sharp cutting edge and high rake angle with streamline chip pocket shows good cutting performance in stainless steel machining where work hardening is a problem
R⁺ Endmill	High efficient roughing endmill for medium to rough cutting     Excellent machining efficiency thanks to the high efficient roughing edge design     Reduced cutting force thanks to specifically designed corners, and irregular flute spacing and lead angle
D Endmill	Diamond-coated endmill for graphite and ceramic     Excellent wear resistance thanks to the diamond coating of high hardness and high purity     Optimized for high speed and heavy duty cutting thanks to the strong grip of coating     Excellent cutting performance and finish thanks to the optimized blade design of high rake
Composite Router Endmill	Router endmill for machining composite materials (CFRP & GFRP)     Minimized machining defects thanks to its design to prevent flaking, peeling off and burrs     Excellent resistance to wear and flaking thanks to the nano-crystalline diamond coating of high hardness and high purity
C-Max	Ideally suited for machining copper, brass, bronze, and Non-ferrous materials thanks to the optimized combination between K-Silver coating with excellent lubrication and resistance to wear and chipping, and the dedicated substrate
Super Endmill	High lubricated coating and special surface treatment     Improved welding and chipping resistance and machining stability due to surface treatment technology




### Solid drills grades selection

#### **Grades for Mach Solid Drill (MSD)**

### **PC325U**

- Special surface treatment provides improved lubrication and reduced cutting loads
- Stable tool life thanks to increased welding resistance

#### Features




Increased welding resistance in medium to high speed cutting due to highly lubricative coating layers Increased wear resistance in carbon steel machining

#### Grades for Mach Solid Drill (MSD)

# PC325T rew

- Good wear resistance in HRSA machining at high temperature
- Good surface finish reduces friction resistance and increases chip evacuation

#### Features



High heat and oxide resistance increase tool lifeIncreased wear.


Good surface finish coating layer ensures lubrication and high quality in machining.

#### **Grades for Mach Long Drill (MLD)**

# PC215G/PC315G

- Improved wear resistance due to the ultrafine substrate
- Reduced friction resistance and smooth chip flow due to improved coating lubrication

#### Features



H Exceptional wear resistance due to the ultrafine substrate

#### Selection system

١	Norkpiece	Grade	ISO	Application range
		PC215G	P01	
Р	Charl	PC315G	P10	
-	Steel	PC325U	P20	PC215G PC315G
		PC230F	P30	PC325U PC230F
		PC215G	M01	
М	Stainless	PC315G	M10	
IVI	steel	PC205F	M20	PC215G PC315G PC325U
		PC325U	M30	1 00230
		PC215G	K01	
К	Cast iron	PC315G	K10	
	Castilon	PC205F	K20	PC215G PC315G
		PC325U	K30	PC325U
		ND2100 💖	N05	ND2100
N	Nonferrous FG2 N10	FG2 FA1		
		FA1	N20	T GZ FAT
s	HRSA	PC325T rew	S20	PC325T PC325T
-3	ппэн	1 00201	S30	1 00231



# Solid drills grades

### Grade information for each product

Hom	Grade				
Item	Coated	Uncoated			
MSD Plus	PC325U	FG2			
MSD Plus-S	PC325T	-			
MSD Plus CFRP	ND2100	-			
MSFD	PC325U	-			
MLD Plus	PC215G, PC315G	FG2			
VZD	PC230F	-			
ESD Plus	PC325U	FG2			
SSD Plus	-	FA1, FG2			

### The features of PVD coated grades

Workpiece	ISO	Features
PC325U	P20~P35 M20~M30 K20~K35	Universal grade for machining steel, cast iron, stainless steel, etc.     Stable cutting performance with excellent wear/chipping resistance     Increased welding resistance due to lubricative new coating at medium to high speed
PC325T	M20~M30 S20~S30	Good wear resistance realizes HRSA machining at high temperature     Good wear and chipping resistance ensure stable machinability
PC215G	P15~P30 M15~M25 K15~K30	Universal grade for machining steel, cast iron, etc. Stable cutting performance with excellent wear/chipping resistance
PC315G	P15~P30 M15~M25 K15~K30	<ul> <li>Universal grade for machining steel, cast iron, stainless steel, etc.</li> <li>Stable cutting performance with excellent wear/chipping resistance</li> <li>Increased welding resistance due to lubricative new coating at medium to high speed</li> </ul>
• Stable cutting performance with exc		For machining general steel at medium to high speed     Stable cutting performance with excellent wear/chipping resistance
		For machining composite materials     Diamond-coated layers with excellent adhesion
FG2 / FA1	N05~N25	Increased wear/chipping resistance with the use of ultra fine substrate

#### Features of KORLOY drills

Index	Features
MSD Plus	<ul> <li>Increased welding resistance in medium to high speed cutting due to highly lubricative coating layers</li> <li>Increased wear resistance in carbon steel machining</li> <li>Reduced friction resistance around corners and flutes</li> </ul>
MSD Plus-S	<ul> <li>Exclusive for HRSA grooving with good wear resistance at high temperature and chipping resistance.</li> <li>New coating layer with good surface finish reduces frictional resistance and increases chip evacuation.</li> <li>Preventing chipping on the cutting edge and fracture of tool ensures high productivity.</li> </ul>
MSD Plus CFRP	<ul> <li>The best tool for hole making of CFRP workpieces</li> <li>Excellent wear resistance due to the diamond-coated grade</li> <li>Reduced burr creation in CFRP machining due to high rake cutting edges</li> </ul>
MSFD	High quality hole making capability with 180° point angle Improved anti-chipping and welding resistance by edge honing and chamfering Minimized creation of burrs compared to general drills
MLD Plus	<ul> <li>Higher rigidity due to straight-edge design</li> <li>Smooth chip flow due to wider chip pockets and improved surface finish on flutes</li> <li>Double margin system for stable machinability</li> </ul>
ESD Plus	Lubricative coating layer improves welding resistance at middle to high speed. Increase wear resistance in machining carbon steel Increased welding resistance and wear resistance with new PC325U grade applied.
SSD Plus	New shape increases chip control     Surface finish and improved shape realize high quality of machining     Stable tool life increases productivity

### **Diamond coated grades**

#### Grade for graphite and ceramic


# ND3000

- SP3-crystalline diamond coatings of high purity and high hardness
- Improved adhesion between coated layers and the substrate that is specialized for diamond coatings
- Excellent tool life when machining graphite and ceramic

#### Surface of ND3000



Cross section of ND3000's coated layers




#### **Grade for composite materials**



- Improved surface finish and wear resistance due to the control technology of nano-crystalline diamond particles
- Improved flaking resistance due to the substrate that is specialized for diamond coatings
- High quality and high precision machining availability thanks to sharp edges
- Excellent tool life when machining composite materials


#### Surface of ND2100







#### Application range



#### Selection system

	Workpiece		Grade	ISO	Application range
		Graphite/ Ceramic	ND3000 🕬	N01	ND3000 new
N	Nonferrous	Al alloy	ND3000 100 ND2100 1100 1100 1100 1100 1100 1100 1100	N05	ND2100
		Composite materials	ND2100 🚭	N10	

#### The features of diamond coated grades

Grade	ISO	Features
ND3000 NO1~N05 • Exceptional cutting performance due to high resistant		<ul> <li>For continuous roughing of graphite, ceramic, and Al alloy at high speeds</li> <li>Exceptional cutting performance due to high resistance to wear and flaking</li> <li>High hardness diamond coatings of high purity SP3-crystalline structure</li> </ul>
ND2100 🕪	N05~N10	For continuous finishing of composite materials and AI alloy at high speeds     Stable machinability due to durable sharp edges     Nano-crystalline diamond coatings under particle control




### **DLC** coated grades


#### **DLC-Coated Inserts for Non-Ferrous Metals**


# PD1005 @ / PD1010 @

- High hardness and low friction DLC coating technology
- Lubrication and maximized wear resistance increases machinability and machining quality.
- Optimal substrate for each workpiece ensures stable and long tool life
- For non-ferrous metals such as aluminum, Al-Si alloy, copper and etc. machining


#### Features







### Application range



#### Selection system

		Grade	ISO	Application range	
		Aluminum and copper (Soft non-ferrous metals)	PD1005	N05	PD1005
N	Non-ferrous metals		PD1005		
		Al-Si alloy (Hardened non-ferrous metals)	PD1010	N15	PDIOIO

#### The features of DLC coating grades

Grade	ISO	Features
PD1005 (1647)	N05	For high speed and continuous machining of Aluminum and copper     High wear and welding resistance realize good machinability     High performance of DLC coating with high hardness and low friction
PD1010 🕬	N10	<ul> <li>For medium to high and interrupted machining of aluminum alloy and Al-Si alloy</li> <li>Stable tool life due to substrate with chipping resistance</li> <li>High performance DLC coating with high hardness and low friction</li> </ul>

### cBN inserts grades

#### Features

- Excellent hardness and thermal resistance by sintering KORLOY's main constituents and special ceramic binder at high pressure and high temperature
- Excellent hardness and wear resistance for higher productivity in machining cast iron and heat-treated alloy at high speed

#### ► Insert type

High presicion		Wear resistance		Productivity	
		•		0	
For regrinding type	One use type	Multi-corner type	Multi-corner type (coated)	Solid type	Grooving type

#### cBN inserts



• Price per edge is more reasonable compare to normal single cornered, one-used type

2NU-CNGA120408


- · Insert with several brazed cBN
- · Wide application of continuous to interrupted machining




CNMA120408

- · Long tool life
- · Excellent wear resistance, High hardness
- Saved tool cost due to the regrinding insert 3~4 time

#### cBN application range



#### Coated cBN application range





#### Cutting condition of cBN grades


W	orkpiece	Gr	ades	Insert color	Application	Cutting speed, vc (m/min)	Feed, fn (mm/rev)	Depth of cut, ap (mm)	
		DNC100 Continuous cutting at high speed 180 300		0.03~0.3	0.03~0.3				
		DNC250		Continuous and low interrupted cutting at high speed	120 220	0.05~0.3	0.05~0.3		
		Coated	DNC300		Medium and low interrupted cutting	90 250	0.05~0.2	0.05~0.2	
			DNC350	0	Medium and high interrupted cutting	90 150	0.05~0.3	0.05~0.3	
н	High hardness			0.05~0.3	0.05~0.5				
П	steel		DB1000		Continuous cutting at high speed	130 250	0.03~0.15	0.03~0.2	
		DB2000	Medium and low interrupted cutting	80 200	0.03~0.2	0.03~0.3			
			DBNX20		Highly efficient cutting	120 150	0.03~0.3	0.03~0.5	
			Non coated	DBN250	0	Medium and low interrupted cutting	80 120	0.03~0.2	0.03~0.3
			DBN350		High interrupted cutting	120 220	0.03~0.2	0.03~0.3	
s	HRSA		DB7000		Continuous cutting at high speed	100 300	0.05~0.2	0.1~1.0	
K	Cast iron		DBN700A		Continuous cutting at high speed	500 2000	0.10~0.4	0.1~0.4	

#### Coated cBN

# **DNC100**


#### Features

- Excellent thermal resistance
- Coating layer with high hardness, oxidation resistance and chipping resistance





### Application range



### Recommended cutting condition

Cutting speed vc (m/min)	180 300	
Feed fn (mm/rev)	0.03	
Depth of cut per time ap (mm)	0.03	


- Increased oxidation resistance and wear resistance due to high hardness coating layer
- Dramatically improved fracture resistance and chipping resistance


#### Multi-corner coated cBN for high efficient cutting of heat-treated alloy

# **DNC250**


#### Features

- Stable and long tool life
- · Cost effective by multi-cornered one-use insert





#### Application range



### Recommended cutting condition

Cutting speed vc (m/min)	120 220
Feed fn (mm/rev)	0.05
Depth of cut per time ap (mm)	0.05

#### Coated cBN


# **DNC300**

#### Features

- 1st recommended grade for low to medium interrupted cutting
- Enhanced chipping resistance and wear resistance comparing to competitor's grade
- . Minimizing flaking of coating by stable coating



#### Application range



#### Recommended cutting condition

Cutting speed vc (m/min)	90 200
Feed fn (mm/rev)	0.05
Depth of cut per time ap (mm)	0.05

- Enhanced oxidation resistance and wear resistance due to high hardness layer
- Highly increased chipping resistance, fracture resistance and wear resistance





#### Coated cBN for high interrupted cutting

## **DNC350**


#### Features

- Excellent tool life and productivity in interrupted cutting
- New PVD coating applied with high hardness and oxidation resistance





#### Application range



#### Recommended cutting condition

Cutting speed vc (m/min)	90 150
Feed fn (mm/rev)	0.05
Depth of cut per time ap (mm)	0.05

#### Solid type coated cBN



#### Features


- For machining heat-treated steel in continuous and medium interrupted cutting
- Longer tool life due to coating layer
- · Solid type for universal purpose

#### Features of solid type cBN

- Increased productivity at high speed and high depth of cut
- Ideal for removing cemented layer and the welds
- Better welding stability due to 3-face blazing
- Excellent cutting performance at varying depth of cuts



#### Application range



#### Recommended cutting condition

	DNC400	0.05	}
Feed fn (mm/rev)	DNC250	0.05	3
	DNC350	0.05	3
Depth of cut per time ap (mm)	DNC400	0.05	0.5
	DNC250	0.05	3
	DNC350	0.05	3

#### Non-coated cBN

# **DB1000**

#### Features

- Non-coated cBN with the highest wear resistance at high speed
- Excellent tool life in continuous to light interrupted cutting
- Improved fracture resistance along with high wear resistance
  - Higher thermal resistance and hardness due to pure TiCN ceramic binder



#### Non-coated cBN


## **DB2000**

#### Features


- Universal grade for overall machining of heat-treated
  - Stable tool life in continuous to low/medium interrupted cutting
- Both fracture resistance and wear resistance acquired with the use of pure ceramic binder
- Stable surface roughness



#### New technology of high purity ceramic binding materials




DB2000 dramatically minimizes impurities with the use of high purity ceramic binding materials and enhances thermal resistance and toughness.



Impurities included in conventional grade's ceramic binder caused inferior thermal resistance and hardness of sintered compounds, which led to crack (fracture) and wear

### Application range



#### Recommended cutting condition (DB1000)

Cutting speed vc (m/min)	130 250		
Feed fn (mm/rev)	0.03		
Depth of cut ap (mm)	0.03		

#### **②** Recommended cutting condition (DB2000)

Cutting speed vc (m/min)	80 200
Feed fn (mm/rev)	0.03
Depth of cut ap (mm)	0.03



## PCD inserts grades

#### Features

KORLOY PCD products are manufactured by using high quality PCD tips under ultra high temperatures and pressure. The PCD tip is welded on the qualified KORLOY carbide insert KORLOY high quality PCD products meet a wide range of application needs in turning, milling, and endmills.

- · Excellent tool life for aluminum alloy and copper alloy
- Excellent tool life for Ceramic, high-silicon aluminum and rock or stone
- Excellent tool life for rubber, carbon, graphite and wood


#### PCD grade


Grade	Features	Application	Grain size (μm)	Hardness (Hv)	TRS (kgf/mm²)
DP90	Coarse diamond grain has been used to get excellent wear resistance enough to machine cemented-carbide, high Si aluminum alloy	Cemented carbide Ceramic roughing High Si aluminum alloy Rock, Stone	25~30	50~65	≒1.10
DP150	By use of fine diamond grain having good bonding property, it is suitable for machining of Non-ferrous metal, graphite	High Si aluminum alloy Copper, Bronze alloy Rubber, Wood, Carbon	5~10	50~60	≒1.95
DP200	By use of ultra fine diamond grain, it is possible to make sharp cutting edge. Thus it is appropriate grade to machine Non-ferrous material	Plastic Wood Precise finishing of aluminum	~2	45~55	≒2.45


#### Recommended cutting condition

Worknings	Cutting and (m/min) Food (mm/m)	Double of out (mm)	Recommended grade		
Workpiece	Cutting speed (m/min)	Feed (mm/rev)	Depth of cut (mm)	1 <sup>st</sup>	2 <sup>nd</sup>
Aluminum alloy (4%~8% Si)	1000~3000	0.1~0.6	~3	DP150	DP200
Aluminum alloy (9%~14% Si)	600~2500	0.1~0.5	~3	DP150	DP200
Aluminum alloy (15%~18%Si)	300~700	0.1~0.4	~3	DP150	DP200
Copper, Bronze alloy	~1000	0.05~0.2	~3	DP150	DP200
Reinforced plastic	~1000	0.1~0.3	~2	DP150	DP200
Wood	~4000	0.1~0.4	-	DP150	DP200
Cemented carbide	10~30	~0.2	~0.5	DP90	DP150


#### Cutting performance












Notice: Application ranges are based on main cutting material





							А	pplica	ation	range	е					
	Geometry	Cutting edge	0.04	0.063	0.1	0 0.16		0.4	0.63		1.6	2.5	4.0	6	.3	Features
			0.1	0.16	0.2	5 0.4	0.63	depth o	1.6		4.0	6.3	10.0	) 1	.6 13	
	VP1	12			0.05~	-0.20 0.1~1	.5									High positive cutting edge     Reduced contract chip minimizes temperature to improve tool life
	VP2				$\parallel$											For Medium to finish cutting
		2.5				0.05~0.	40	0.	5~4.(	0						Stable chip control and high machinability in copying with various depths of cut
	VP3															For Medium cutting
V series		0.5			0	.05~0.4	15	0.	5~4.5	5						High positive cutting edge with wide land Stable cutting performance in interrupted machining with high toughness Stable machinability and chip control in machining with high depth of cut
	VP4															For Roughing
		2.6 0.17 8° 18°					0.15~0	.45	1.	.0~4.5						The first recommended chip breaker for inconel cutting High hard and resistant rake angle to prevent notch wear in roughing of rugged surfaces
	VR															For Roughing
	•	0.32					0.	25~0.5	55	1.2~	7.0					High feed machining with the combination of wide land and pockets     Shallow chip breaker design prevents chip blocking at high feed     Decreased wear on major cutting edge due to special treatment on blade
	LP															For Medium to finish cutting
		0.13				0.10	0~0.40	0.5~2	2.5							Angle land decreases cutting resistance for better surface roughness     Special dot design prevents chip blocking by clear chip breaking
	MP															For Medium cutting
-P series		0.2 5° 18°					0.15~0		.5~4.	.5						Increased productivity due to excellent chip control in various conditions     Stable tool life by reducing cutting load at high speed and high feed
	СР				$\dagger \dagger$									$\dagger$		For Medium to finish cutting
		0.15				0.1	2~0.35		i~3.5							Chip breaker with strong cutting edge in high interrupted finishing and medium cutting Effective chip control in low depth of cut to high depth of cut due to 2-step rear angle






Notice: Application ranges are based on main cutting material





												ange	!						
	Geometry	Cutting edge	0.04	0.0	63	0.10	0.16		0.	rate fr 4 ( h of cu	0.63	1.0	1.6	2.5	. 4	1.0	6.3		Features
C-Posi series	C25	0.15 1.9 0.15°	0.1	0.1	16	0.25	0.4	0.63 ~0.35		0	1.6	2.5	4.0	6.3	1	0.0	11.6	13	For Roughing  - Suitable for interrupted cutting and cast iron machining - Good surface finish due to low cutting force - Suitable for both boring and outer diameter turning
H-Posi series	НМР	0.15					0.08-	-0.40		0.5~3	3.5								For Medium cutting  • Excellent chip control at wide range of cutting conditions  • Machining versatility over a wide range of materials
series	VF	0.6 0.1 1.5 0.6 1.5			0.	05~(	0.25 0.1~1.	5											For Finishing  Improved surface finish and size accuracy due to stable inner boring
V-Posi series	VL	0.6			0.0	5~0. 0.1	~1.0												Superior chip control in low carbon steel, pipes, and steel plates
P-Posi series	MP	0.2 7°- 15°			(	0.05~	~0.30		0.3~3	3.0									Sharp cutting edge and wide chip pocket for low cutting load     Stable chip control at varying depth of cuts     Excellent cutting performance when machining automobile components
	FP	20°		0	.01~	0.20	~1.0												For Finishing  For chip control in low depth of cut mild cutting  Enhanced surface finish and reduced cutting load
AL series	AK	25°			C	0.03~	~0.40	0.1~4	.0										For Medium to finish cutting  • Exclusive chip breaker for aluminum and aluminum alloy cutting
	AR	13°				0.0	05~0.	50		0.5~	4.0								For Medium to finish cutting     High stability of cutting edge secures great performance in high speed and interrupted machining     High speed of medium and interrupted operation




Notice: Application ranges are based on main cutting material





								Α	ppl	icati	ion ra	nge	)					
	Geometry	Cutting edge	0.05	0.10	0.1	5 0.:	20				n (mm/ 0.35		0.80	1.2	0	1.40	1.60	Features
			0.1	0.5	1	2	2	3		th of c	ut ap (n 5	nm) 6	8	10		15	20	
MX series	MX					0.10		0.0~5.	.0									Possible to increase productivity through increase feed and depth     Excellent heat resistance due to the special chip breaker design of top face of insert
	ММ																	For Roughing
Mill-max Heavy	<b>\oint_{\int_{\int_{\oint_{\oint_{\oint_{\int_{\oint_{\oint_{\oint_{\oint_{\oint_{\oint_{\oint_{\inttile\tinnet\int_{\inttilent_{\inttilent_{\int_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\inttilent_{\intilent_{\intilent_{\intilent_{\inttilent_{\intilent_{\intilent_{\intilent_{\inttilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\intilent_{\innt\iint_{\intiilent_{\intilent_{\intilent_{\intiint_{\intilent_{\intilent_{\intilent_{\intiile</b>							0	.20-	~0.40	2.0~1	4.0						Specialized tool for high depth of cut roughing with high rigidity cutting edge ensures stable machining.
	MA																	For Aluminum machining
						0.	05~(	0.40	1.0	~8.0								Sharp cutting edge for low cutting load, which is ideal for machining steel, hard-to-cut materials and aluminum
3M3	ML																	For machining hard-to-cut materials
Rich Mill series-RM3					0.0	05~0.3	30		1.0	~8.0								Low cutting resistance for light cutting and machining hard-to-cut materials with excellent tool life and surface roughness
	ММ																	For General cutting
						0.05~	-0.3		1.0	~8.0								Available for most of applications with universal design for general milling
	MA																	For Aluminum machining
				0	.05~	0.25			0.3	3~14.	.0							Sharp cutting edge design ensures low cutting resistance and excellent machining in difficult- tocut materials, aluminum and light machining
M4	MF																	For Light cutting
Rich Mill series-RM4					0.0	95~0.3	80		0.	.5~14	4.0							Low cutting force chip breaker design ensures longer tool life and excellent machining in difficult-to-cut material and light machining
	ММ										+				$\dagger$			For General cutting
	9				0.0	05~0.3	30			1.	.0~14	.0						Suitable geometry design for general milling has wider ranges of machining






Notice: Application ranges are based on main cutting material





								pplica			)				
	Geometry	Cutting edge	0.05	0.10	0.15	0.2		0.30 depth of	0.35	0.40	0.80	1.20	1.40	1.60	Features
Rich Mill series-RMT8	MM		0.1	0.5	0.05	5~0.3	0	6~8.0	5	6	8	10	15	20	For General cutting  • Suitable geometry design for general milling has wider ranges of machining
Ä	ML				0.09	5~0.3	0								For Machining hard-to-cut materials
	6					1.0~									Stable tool life and good cutting quality in hard-to-cut material cutting due to double reverse positive relief surface and low cutting load chip breaker
X-8W	MM														For high hardness cutting
Rich Mill series-RM8-X	SAGX				0.05	1.0~									Stable tool life and good cutting quality due to double reverse positive relief surface and high rigidity chip breaker
	ММ														For General cutting
	SNMX					1.0~									For general cutting range with optimal shape for general milling
	ML														For HRSA cutting
series-RM14	Neutral				0.05	1.0~									Excellent cutting performance in heat resistance STS cutting from neutral type flat cutting edge and sharp chip breaker
Aill se	ML														For cast iron and STS cutting
Rich Mill	Right-handed				0.05	1.0~									Excellent cutting performance in general STS and cast iron cutting from right-handed helix cutting edge and sharp chip breaker
	MA														For Aluminum machining
Rich Mill series-RM16	•				0.05	5~0.30 0	0 .3~5.5								Sharp cutting edge design ensures low cutting resistance and excellent machining in difficult- tocut materials, aluminum and light machining
ill sei	MF									$\dagger \dagger$					For Light cutting
ich M															
ä							.3~5.5								Low cutting force chip breaker design ensures longer tool life and excellent machining in difficult-to-cut material and light machining




Notice: Application ranges are based on main cutting material





							Δ	pplica	tion	range	<b>!</b>				
	Geometry	Cutting edge	0.05	0.10	0.15	0.2		feed rate 0.30			0.80	1.20	1.40	1.60	Features
			0.1	0.5	1	2	3	depth of	cut ap	(mm) 6	8	10	15	20	
Alpha Mill series	MN				0.10	0~0.2	5	0.5	i~16						For Roughing (nick)  Design for easy chip cutting ensures high machinability in toughing
	ММ														For General cutting
Alpha Mill-X series					(	0.05~	0.35		1.0~1	6.5					Shape for general milling with most cutting range
ha Mill	ML														For Hard-to-cut material machining
Alp					0.08	5~0.3	0		1.0~1	6.5					Chip breaker for cutting with low cutting load guarantees long tool life and qualified machining in light cutting and HRSA machining
	MF														For Light cutting
	•			0.05	i~0.20		5~5.0								Special design for light cutting of gummy materials like stainless steel and hard to machine material provide fine surface finish and longer tool life
	ММ														For General cutting
Mill series	•				0.05	5~0.3	1.0~5	.0							Chip breaker design to cover general cutting condition provides wide available application range     Ground type and as sintered type is available
ure Mi	MR														For Roughing
Future	•					0.05~	0.35	<b>-</b> 5.0							Strongest cutting edge strength provide stable tool life even in case of severe cutting with heavy intermittent and heavy roughing
	MA														For Aluminum machining
	•						0~0.35 5~5.0								Sharp cutting edge and lubricated top face show excellent chip flow and welding resistance in aluminum machining
isod	MA														For Aluminum machining
Future Mill series P-posi							0.3~6.0		0.30~	0.60					Excellent surface roughness due to buffed surface in machining aluminum




Notice: Application ranges are based on main cutting material






							A	pplica	ition	range	)					
	Geometry	Cutting edge	0.05	0.10	0.15	0.20		feed rate 0.30			0.80	1.20	1.40	1	.60	Features
			0.1	0.5	1	2	3	depth of	f cut ap 5	(mm) 6	8	10	15		20	
	ML			0.2~1	.0				0.30	~0.80						For Hard-to-cut material machining     Chip breaker for cutting with low cutting load and hard cutting edge ensure high qualified machining
	MF															For Light cutting
HFMD				0.2~1	.0				0.	30~1.0	0					Chip breaker for cutting with low cutting load is for light cutting
	ММ															For General cutting
				0.2~1	.0				0	.30~1	.20					Shape for general machining with high feed is available for most machining range
	MA															For Aluminum machining
				C	0.05~0	0.25			1.0~1	6.5						Sharp cutting edge for aluminum machining ensures good machinability     Buffed surface realizes chip flow and welding resistance
	ML															For Hard-to-cut material machining
TP2P				0	.05~0	.25										Chip breaker for cutting with low cutting load guarantees
									1.0~1	6.5						long tool life and qualified machining in light cutting and HRSA machining
	ММ															For General cutting
				0	.05~0	.25										
	6								1.0~1	6.5						Specialized shape for general slotting is applicable in most cutting ranges
	MA															For Aluminum machining
M	4			0.05	i~0.20											
Pro-XL Mill	3			0.00	3.20									10~	57	Sharp cutting edge with buffing on the surface for aluminum machining ensures chip flow and welding resistance
	MA				+		+			+			$\parallel$		+	For Aluminum machining
■																
Pro-V Mill						0.10~0	0.30		1.0~	17						Shape for general slotting is applicable in most cutting ranges.
<b>a</b>																ranges



Notice: Application ranges are based on main cutting material

# **TURNING**

Korloy turning tools cover a wide application range with a full line-up of ISO tools that produce high quality and high precision parts all for manufacturers' requirements.




Transit	on Ohin Braskara	A.da	Toolo	Halada	Dwaren Content
Iurnii	ng Chip Breakers	Auto	IOOIS	High	Pressure Coolant
B02	Application range of KORLOY	B121	Technical Information for Auto Tools	B199	Technical Information
	Main Chip Breakers	B122	ISO Type		for KHP Coolant
B04	Recommended Chip Breakers for workpiece	B127	KHP Coolant	B202	KHP Coolant
B16	Feature of Chip Breakers	B136	Blade Type		
2.0	. Calaire of one products	B139	Multi Utility Type		
		B142	KGT/MGT Type	Borin	g Bar
la a a ul		B145	MSB Tool	B204	Boring Bar Code System (ISO)
Insert	S	B151	Sleeve	B205	Index for Boring Bar
B34	Turning Insert Code System (ISO)			B207	Instruction of Boring Bar assembly
B36	Turning Insert (Negative)			B208	Double Clamp System
B73	Turning Insert (Positive)	Multi	Turn	B210	Lever Lock System
B102	Aluminum Insert (Positive)	B152	Technical Information for Multi Turn	B212	Clamp On System
B110	cBN Insert	B154	Multi Turn	B213	Multi Lock System
B113	PCD Insert			B215	Screw On System
				B225	Compact Mini
		Beari	ng Solutions		
SAVE	TURN				
B114	Technical Information for SAVE TURN	B155	Technical Information for Bearing Solution	HSK/I	KM Tooling System
B114 B115	Technical Information for SAVE TURN SAVE TURN Insert	B156		HSK/I B228	KM Tooling System  Technical Information for
B115 B116	SAVE TURN Insert SAVE TURN Holder		Bearing Solution		Technical Information for HSK/KM Tooling System
B115	SAVE TURN Insert	B156	Bearing Solution Bearing Solution	B228 B230	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156	Bearing Solution Bearing Solution	B228 B230 B231	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161	Bearing Solution Bearing Solution	B228 B230	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts	B228 B230 B231 B237	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  nal Tool Holder  External Tool Holder	B228 B230 B231	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161 Extern	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  nal Tool Holder  External Tool Holder Code System (ISO)	B228 B230 B231 B237	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161 Exterior B162 B163	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  Pal Tool Holder External Tool Holder Code System (ISO) Index for External Holder	B228 B230 B231 B237	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161 Extern B162 B163 B166	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  Pal Tool Holder  External Tool Holder Code System (ISO) Index for External Holder Instruction of External Holder Double Clamp System Lever Lock System	B228 B230 B231 B237  Cartri B241	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System  KM Tooling System  dges  Cartridge Code System (ISO)
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161 Extern B162 B163 B166 B167	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  Tool Holder  External Tool Holder Code System (ISO) Index for External Holder Instruction of External Holder Double Clamp System Lever Lock System Wedge Clamp System	B228 B230 B231 B237 Cartri B241 B242	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System  Cartridge Code System (ISO) Index for Cartridge
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161 Extern B162 B163 B166 B167 B172 B179 B181	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  Tool Holder  External Tool Holder Code System (ISO) Index for External Holder Instruction of External Holder Double Clamp System Lever Lock System Wedge Clamp System Clamp On System	B228 B230 B231 B237 Cartri B241 B242 B243	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System  Catridge Code System (ISO) Index for Cartridge Clamp On System
B115 B116	SAVE TURN Insert SAVE TURN Holder	B156 B161 Exteri B162 B163 B166 B167 B172 B179	Bearing Solution Bearing Solution Special Order Form for Bearing Inserts  Tool Holder  External Tool Holder Code System (ISO) Index for External Holder Instruction of External Holder Double Clamp System Lever Lock System Wedge Clamp System	B228 B230 B231 B237 Cartri B241 B242 B243	Technical Information for HSK/KM Tooling System Index for HSK/KM Tooling System HSK Tooling System KM Tooling System  Catridge Code System (ISO) Index for Cartridge Clamp On System

B190 Screw On SystemB197 Ceramic Holder




## Applications range of chip breakers

### Negative inserts



# Applications range of chip breakers

#### Positive inserts







Materials: SM10C, SM15C, SM25C, SS400, SCr415, SCM415, etc. Soft steel

Hardness: under 180HB

D	epth of			F		Cutting			Insert	shape		
	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	(80°)	<b>√</b> 55°	90°	60°	35°	80°
	0.2 ~ 0.8 ~ 1.5 Finishing	VL	0.1	0.10 ~ 0.20 ~ 0.35	NC3215 NC3225 CN1500 CN2500	305 250 260 230	p. B36	DNMG  p. B43	p. B50	TNMG  p. B58	p. B66	<b>WNMG</b> p. B68
	0.5 ~ 1.0 ~ 2.0 Finishing	VB	0.1	0.15 ~ 0.20 ~ 0.40	NC3215 NC3225 CN1500 CN2500	340 250 240 210	D. B36	DNMG  p. B43		TNMG p. B58		p. B68
	0.5 ~ 1.0 ~ 1.5 Finishing	VF	3 15	0.05 ~ 0.15 ~ 0.35	NC3215 NC3220 NC3225 NC5330	305 270 270 210	D. B36	DNMG p. B43	p. B50	D. B58	p. B66	WNMG p. B68
	0.5 ~  1.5  ~ 3.5  Medium to finishing	VC	0.2	0.12 ~ 0.25 ~ 0.45	NC3215 NC3220 NC3225 NC5330	285 250 255 200	p. B36	DNMG p. B44	p. B50	p. B59	P. B66	<b>WNMG</b> p. B68
ative	0.5 ~  1.0  ~ 3.5  Medium to finishing	LP	1.6 0.13 6° 1.2	0.10 ~ 0.25 ~ 0.40	NC3215 NC3225 NC5330	300 250 200	p. B36	DNMG p. B43	p. B50	D. B58	P. B66	wnmg p. B68
Negat	0.5 ~  1.3  ~ 3.5  Medium to finishing	VQ	0.13	0.12 ~ 0.2 ~ 0.42	NC3215 NC3225 NC5330	300 250 200	p. B38	DNMG p. B45	p. B52	p. B60	p. B67	p. B70
	0.5 ~  1.3  ~ 3.5  Medium to finishing	CP	0.15	0.1 ~ 0.28 ~ 0.35	NC3215P NC3225P	285 250	p. B36	DNMG p. B44	p. B50	D. B50	P. B66	wnmg p. B68
	0.5 ~  1.5  ~ 4.5  Medium cutting	MP	0.2	0.15 ~ 0.30 ~ 0.45	NC3215 NC3225 NC5330	300 265 200	CNMG  p. B37	DNMG p. B44	SNMG p. B51	TNMG p. B59	VNMG p. B66	p. B69
	1.0 ~  2.5  ~ 5.0  Medium cutting	VM	0.25 1.3 0.1 1.18°	0.10 ~ 0.25 ~ 0.50	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	295 260 260 205 220 200	D. B37	DNMG p. B45	p. B51	D. B59	P. B67	WNMG p. B69
	1.5 ~  2.5  ~ 5.5  Medium cutting	HM	0.25	0.12 ~ 0.28 ~ 0.52	NC3215 NC3225 NC5330	300 265 200	CNMG  p. B37	DNMG p. B44	SNMG  p. B51	TNMG p. B59	VNMG p. B66	wnmg p. B69





Workpiece P


Materials: SM10C, SM15C, SM25C, SS400, SCr415, SCM415, etc. Soft steel

Hardness: under 180HB

	Depth of					Cutting			Insert	shape		
	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	80°	(55°)	90°	60°	35°	80°
	1.0 ~ 3.0 ~ 4.5 Roughing	GR	0.28	0.20 ~ 0.35 ~ 0.50	NC3125 NC3225 NC5330	180~370 150~330 130~280	CNMG p. B38	DNMG  D. B45	p. B52	D. B60		wnmg p. B69
egative	3.0 ~ 7.0 ~ 11.0 Heavy	GH	0.28	0.30 ~ 0.80 ~ 1.30	NC3125 NC3225 NC5330	180~370 150~330 130~280	p. B38  CNMM  p. B42	p. B45	p. 852  SNMM   © 00000 %  © 00000 %  © 00000 %  P. B57	р. вои		p. 869
Ned	6.0 ~ 10.0 ~ 15.0 Heavy (General)	VH	203 289	0.70 ~ 1.00 ~ 1.40	NC3215 NC3030 NC500H NC5330	50~250 50~150 50~150 50~150	D. B42		p. B57			
	7.0 ~ 12.0 ~ 17.0 Heavy (High feed cutting)	VT	200 200	0.75 ~ 1.20 ~ 1.60	NC3215 NC3030 NC500H NC5330	50~250 50~150 50~150 50~150	D. B42		p. B57			

•: The first recommended cutting condition

### P Negative








Materials: SM10C, SM15C, SM25C, SS400, SCr415, SCM415, etc. Soft steel

Hardness: under 180HB

г	Depth of					Cutting			Insert	shape		
	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	80°>	<b>₹</b> 55°	90°	60°	35°	80°
	0.1 ~ 0.5 ~ 1.0 Finishing	FP	200	0.01 ~ 0.06 ~ 0.20	NC3215 NC3225 CN1500 CN2500	350 270 260 240	р. В73	DCMT  p. B79	p. B84	р. В88	<b>VB(C)MT</b> p. B94	
	0.1 ~ 0.5 ~ 1.0 Medium to finishing	VL VL	0.6	0.05 ~ 0.10 ~ 0.20	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	305 270 270 210 260 240	p. B73	<b>р.</b> В79	p. B84	тсмт р. В88	p. B94	
itive	0.1 ~ 0.5 ~ 1.5 Medium to finishing	VF	0.1	0.05 ~ 0.15 ~ 0.25	NC3215 NC3220 NC3225 NC5330 CC1500 CN1500 CN2500	305 270 270 210 260 250 230	p. B73	DCMT	p. B84	D. B88	vB(C)MT	
Pos	0.6 ~ 1.5	HMP	0.15	0.10 ~ 0.20 ~ 0.30	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	320 285 285 225 240 220	p. B73	DCMT  p. B79	p. B84	TCMT  p. B88	VB(C)MT	
	0.6 ~ 1.0 ~ 2.5 Medium cutting	MP	0.2	0.10 ~ 0.20 ~ 0.30	NC3215 NC3225 CN1500 CN2500	300 250 240 200	р. В73	p. B79	p. B84	p. B88	vB(C)MT  p. B94	
	0.8 ~ 2.0 ~ 3.0 Roughing	C25	0.15	0.12~ 0.25 ~ 0.32	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	320 285 285 225 230 210	p. B74	p. B80	p. B84	р. В89		

•: The first recommended cutting condition

### P Positive



Workpiece P

Materials: SM45C, SM55C, SCM430, SCM440, etc. General steel

Hardness: under 180~260HB

_	epth of					Cutting			Insert	shape		
	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	180°	(155°)	90°	60°	35° →	80°
	0.5 ~ 1.0 ~ 2.0 Finishing	VB	0.1	0.15 ~ 0.20 ~ 0.40	NC3215 NC3225 CN1500 CN2500	340 250 230 190	p. B36	DNMG p. B43		P. B58		p. B68
	0.5 ~ 1.0 ~ 1.5 Finishing	VF	0.9	0.08 ~ 0.15 ~ 0.35	NC3215 NC3225 NC5330	305 270 250	CNMG p. B36	DNMG p. B43	SNMG p. B50	TNMG p. B58	VNMG p. B66	WNMG p. B68
	0.5 ~ 1.0 ~ 3.5 Medium to finishing	VC	0.2 1.7 6° 15°	0.12 ~ 0.25 ~ 0.45	NC3215 NC3220 NC3225 NC5330	285 255 250 200	CNMG  D. B36	DNMG p. B44	SNMG  p. B50	TNMG p. B59	VNMG p. B66	WNMG p. B68
	0.5 ~ 1.0     ~ 2.5 Medium cutting	LP	1.6 0.13 6° 22°	0.10 ~ 0.25 ~ 0.40	NC3215 NC3225 NC5330	300 250 200	CNMG  p. B36	DNMG p. B43	SNMG p. B50	TNMG p. B58	VNMG p. B66	WNMG p. B68
Negative	0.5 ~ 1.5   ~ 4.5 Medium cutting	MP	0.2	0.15 ~ 0.30 ~ 0.45	NC3215 NC3225 NC5330	300 250 200	D. B37	DNMG p. B44	SNMG p. B51	TNMG p. B59	VNMG p. B66	WNMG p. B69
	1.0 ~ 2.5 ~ 5.0 Medium cutting	VM	0.25 1.3 0.1 1.89	0.15 ~ 0.25 ~ 0.50	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	260 245 245 205 210 170	CNMG  p. B37	DNMG p. B45	SNMG p. B51	TNMG p. B59	VNMG p. B67	WNMG p. B69
	1.0 ~ 3.0 ~ 4.5 Medium to roughing	GR	3.1	0.20 ~ 0.35 ~ 0.50	NC3125 NC3225 NC5330	180~370 150~330 130~280	CNMG p. B38	DNMG p. B45	SNMG p. B52	TNMG p. B60		WNMG p. B69
	6.0 ~ 10.0 ~ 15.0 Heavy (General)	VH	20 25 28°	0.70 ~ 1.00 ~ 1.40	NC3215 NC3030 NC500H NC5330	50~250 50~150 50~150 50~150	CNMM  p. B42		SNMM p. B57			
	7.0 ~ 12.0 ~ 17.0 Heavy (High feed cutting)	VT	20° 20°	0.75 ~ 1.20 ~ 1.60	NC3215 NC3030 NC500H NC5330	50~250 50~150 50~150 50~150	CNMM p. B42		D. B57			

<sup>•:</sup> The first recommended cutting condition





Materials: SM45C, SM55C, SCM430, SCM440, etc. General steel

Hardness: under 180~260HB

Г	Depth of					Cutting			Insert	shape		
٠	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	180°	(55°)	90°	60°	35°	80°
	0.1 ~ 0.5 ~ 1.0 Finishing	FP	20 0.5	0.01 ~ 0.06 ~ 0.20	NC3215 NC3225 CN1500 CN2500	350 270 260 240	CCMT	DCMT	SCMT	TCMT	VB(C)MT	
							p. B73	p. B79	p. B84	p. B88	p. B94	
	0.4 ~ 0.5 ~ 1.0 Medium to finishing	VL .	0.6	0.05 ~ 0.10 ~ 0.25	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	345 310 310 240 250 210	р. В73	р. В79	p. B84	тсмт р. В88	vB(c)MT	
Positive	0.1 ~ 0.5 ~ 1.5 Medium to finishing	VF	0.1	0.05 ~ 0.15 ~ 0.25	NC3215 NC3220 NC3225 NC5330 CC1500 CN1500 CN2500	265 300 300 230 260 240 210	р. В73	р. В79	p. B84	тс(Р)МТ р. В88	vB(c)MT	
	0.6~  1.5  ~ 2.5  Medium cutting	MP	0.2 7° 15°	0.10 ~ 0.15 ~ 0.30	NC3215 NC3225	300 250	р. В73	р. В79	p. B84	тс(Р)МТ р. В88	vB(C)MT  p. B94	
	0.8 ~ 2.0 ~ 3.0 Roughing	C25	0.15 1.9 0.15 1.5°	0.12 ~ 0.15 ~ 0.32	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	320 285 285 225 230 200	р. В74	р. В80	p. B84	тсмт р. В89		

•: The first recommended cutting condition

Workpiece

Materials: SNC415, SNC815, SNCM240, SNCM439, STS12, STS61, etc

SCM440, Hardened steel

Hardness: 260~350HB

Depth of						Cutting	Insert shape						
	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	80°	(55°)	90°	60°	35°	80°	
Negative	0.5 ~ 1.0 ~ 2.0 Finishing	VB	0.1	0.15 ~ 0.20 ~ 0.40	NC3215 NC3225 CN1500 CN2500	200 148 220 200	CNMG p. B36	DNMG p. B43		TNMG p. B58		WNMG p. B68	
	0.5 ~ 1.0 ~ 1.5 Finishing	VF	0.1	0.08 ~ 0.15 ~ 0.30	NC3215 NC3220 NC3225	180 159 159	D. B36	DNMG p. B43	SNMG p. B50	TNMG p. B58	VNMG p. B66	WNMG p. B68	
	0.5 ~ 1.5 ~ 3.5 Medium to finishing	VC	6-1-15	0.12 ~ 0.25 ~ 0.45	NC3215 NC3220 NC3225 NC5330	168 148 150 200	CNMG  P. B36	DNMG p. B44	SNMG p. B50	TNMG p. B59	VNMG p. B66	WNMG p. B68	
	0.5 ~ 1.0 ~ 2.5 Medium cutting	LP	1.6 0.13 6 20°	0.10 ~ 0.25 ~ 0.40	NC3215 NC3225 NC5330	250 200 200	CNMG p. B36	DNMG p. B43	SNMG p. B50	TNMG p. B58	vnmg p. B66	WNMG p. B68	
	0.5 ~ 1.5  ~ 4.5 Medium cutting	MP	0.2	0.15 ~ 0.25 ~ 0.45	NC3215 NC3225 NC5330	250 200 200	P. B37	DNMG p. B44	p. B51	D. B59	P. B66	wnmg p. B69	
	1.0 ~  2.5  ~ 5.0  Medium cutting	VM	0.25 1.3 2.2 0.1 1.8 5.1	0.15 ~ 0.25 ~ 0.50	NC3215 NC3220 NC3225 CN1500 CN2500	174 153 153 120 100	CNMG p. B37	DNMG p. B45	SNMG p. B51	TNMG p. B59	VNMG p. B67	<b>WNMG</b> p. 869	
	1.0 ~  3.0  ~ 4.5  Medium to roughing	GR	3.1	0.20 ~ 0.35 ~ 0.50	NC3125 NC3225 NC5330	180~370 150~330 130~280	CNMG p. B38	DNMG p. B45	SNMG p. B52	TNMG  p. B60		WNMG p. 869	
	6.0 ~ 10.0 ~ 15.0 Heavy (General)	VH	20° 228°	0.70 ~ 1.00 ~ 1.40	NC3215 NC3030 NC500H NC5330	50~250 50~150 50~150 50~150	CNMM p. B42		SNMM  p. B57				
	7.0 ~ 12.0 ~ 17.0 Heavy (High feed cutting)	VT	200 200	0.75 ~ 1.20 ~ 1.60	NC3215 NC3030 NC500H NC5330	50~250 50~150 50~150 50~150	CNMM p. B42		9. B57				

<sup>•:</sup> The first recommended cutting condition





Materials: SNC415, SNC815, SNCM240, SNCM439, STS12, STS61, etc

SCM440, Hardened steel

Hardness: 260~350HB

Depth of cut (mm)		C/B	Cutting edge	Feed (mm/rev)	Grades	Cutting Speed (m/min)	Insert shape						
							80°	(55°)	90°	60°	35°	80°	
Positive	0.1 ~ 0.5 ~ 1.0 Finishing	FP	20' 4	0.01 ~ 0.06 ~ 0.20	NC3215 NC3225 CN1500 CN2500	350 270 260 240	p. B73	DCMT  D. B79	D. B84	D. B88	vB(C)MT		
	0.4 ~ 0.5 ~ 1.5 Medium to finishing	VL	0.6	0.05 ~ 0.10 ~ 0.25	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	305 310 310 240 210 190	<b>CCMT</b> p. B73	p. B79	p. B84	тсмт р. В88	vB(C)MT		
	0.1 ~ 0.5 ~ 1.5 Medium to finishing	VF	0.1	0.05 ~ 0.15 ~ 0.25	NC3215 NC3220 NC3225 NC5330 CC1500 CN1500 CN2500	330 300 300 230 260 250 240	р. В73	р. В79	p. B84	TC(P)MT  p. B88	vB(C)MT  p. B94		
	0.6 ~ 1.5 ~ 2.5 Medium cutting	MP	7-4 15	0.10 ~ 0.15 ~ 0.30	NC3215 NC3225 NC5300 CN1500 CN2500	305 285 225 240 220	p. B73	p. B79	р. В84	p. 888	vB(c)MT  p. B94		
	0.8 ~ 2.0 ~ 3.0 Roughing	C25	0.15	0.12 ~ 0.15 ~ 0.32	NC3215 NC3220 NC3225 NC5330 CN1500 CN2500	320 285 285 225 100 80	p. B74	p. B80	р. В84	p. B89			

•: The first recommended cutting condition

Workpiece M Stainless steel

Materials: STS304, STS316, STS430, STS630


Ferrite, austenite, martensite, precipitation hardening stainless steels

Hardness: 135~300HB

Г	epth of					Cutting			Insert	shape		
_	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	80°	(55°)	90°	60°	35°	80°
	0.5 ~ 1.5 ~ 4.0 Medium to finishing	VP2	2.5	0.10 ~ 0.20 ~ 0.40	PC8105 PC8110 PC8115 PC5300 PC5400	185 170 160 135 120	D. B41	DNMG p. B47	p. B55	p. B63		WNMG p. B71
tive	1.0 ~ 2.0 ~ 4.5 Medium cutting	MP	0.2 5°-1 18°	0.15 ~ 0.23 ~ 0.45	PC8105 PC8110 PC8115 PC5300 PC5400	175 160 150 130 110	D. B37	DNMG D. B44	p. B51	D. B59	VNMG p. B66	WNMG
Negative	0.5 ~ 3.0     ~ 5.5 Medium cutting	MM	0.3 2.1 0.1 10 20°	0.12 ~ 0.25 ~ 0.45	NC9115 NC9125 NC9135 PC8110 PC8115 PC5300	190 170 130 160 150 130	p. B40	DNMG p. B46	p. B54	TNMG p. B62	P. B67	p. B71
	2.0 ~ 4.0 ~ 6.0 Roughing	RM	2.6 0.31 7° 18°	0.15~ 0.30 ~ 0.55	NC9115 NC9125 NC9135 PC8110 PC8115 PC5300	190 170 130 160 150 130	p. B40	DNMG p. B47	p. B55	p. B63	p. B67	WNMG  p. B71

•: The first recommended cutting condition

#### M Negative







Materials: STS304, STS316, STS430, STS630


Ferrite, austenite, martensite, precipitation hardening stainless steels

Hardness: 135~300HB

Г	Depth of					Cutting			Insert	shape		
•	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	80°>	<b>√</b> 55°	90°	60°	35°	80°
	0.1 ~ 0.5 ~ 1.0 Finishing	VL	5°	0.05 ~ 0.10 ~ 0.20	PC8105 PC8110 PC8115 PC5300 PC5400 NC5330 NC9025	215 195 190 165 135 165 165	p. B73	p. B79	p. B84	р. В88	vB(c)MT	
tive	0.3 ~ 1.0 ~ 2.0 Medium to finishing	НМР	0.15	0.05 ~ 0.10 ~ 0.25	PC8105 PC8110 PC8115 PC5300 PC5400 NC5330 NC9025	190 175 170 135 120 150	p. B73	DCMT	p. B84	P. B88	vB(C)MT  p. B94	
Posi	0.3 ~ 1.5 ~ 3.0 Medium to finishing	МР	1.7	0.05 ~ 0.15 ~ 0.35	PC8105 PC8110 PC8115 PC5300 PC5400 NC5330 NC9025	190 175 170 135 120 150	p. B73	р. В79	p. B84	тс(Р)МТ р. В88	vB(C)MT p. B94	
	1.0 ~  1.5  ~ 3.0  Medium cutting	C25	0.15	0.08 ~ 0.13 ~ 0.25	PC8110 PC5300 PC9030	170 155 155	p. B74	p. B80	p. B84	р. В89		

•: The first recommended cutting condition

#### M Positive




K


Materials: GC250, GC300, GCD400, GCD700, etc : Gray cast iron, Ductile cast iron


Hardness: 135~185HB

Tensile strength: under 450N/mm<sup>2</sup>



•: The first recommended cutting condition










Materials: Aluminum alloy Hardness: 20~110HB


Г	Depth of					Cutting	Insert shape						
•	cut (mm)	C/B	Cutting edge	Feed (mm/rev)	Grades	Speed (m/min)	80°>	(55°)	90°	60°	35°	80°	
Negative	0.5 ~ 2.0 ~ 6.0 Medium cutting	НА	9. 13°	0.10 ~ 0.20 ~ 0.50	H01	500	p. B41	DNMG p. B48	p. B56	p. B63	p. B67	p. B72	
tive	0.1 ~ 1.0 ~ 4.0 Medium to finishing	AK	250	0.03 ~ 0.20 ~ 0.40	H01 ND1000 PD1000	1000 1000 1000	p. B103	p. B104	p. B106	p. B107	vB(C)GT  p. B108	p. B105	
Posi	0.5 ~  1.5  ~ 4.0  Medium cutting	AR	1130	0.05 ~ 0.30 ~ 0.50	H01 ND1000 PD1000	1000 1000 1000	p. B103	p. B104	p. B106	тсет р. В107	vB(C)GT  p. B108	P. B105	


Materials: Copper, Bronze alloy

Hardness: 20~110HB



•: The first recommended cutting condition







**Turning** 


Workpiece S Heat resistant alloy


Materials: Inconel, Nimonic, Stellite, Ti alloy

Hardness: 160~350HB

Г	epth of				Grades	Cutting			Insert	shape		
_	cut (mm)	C/B	Cutting edge	Feed (mm/rev)		Speed (m/min)	\$80°	(55°)	90°	60°	35°	80°
	0.1 ~ 0.5 ~ 1.5 Finishing	VP1	1.2	0.05 ~ 0.10 ~ 0.20	PC8110 PC5300 NC5330	60 50 50	D. B40	DNGG p. B47				
egative	0.5 ~ 1.5 ~ 4.0 Medium to finishing	VP2	2.5	0.10 ~ 0.20 ~ 0.40	PC8110 PC5300	60 45	p. B41	DNMG p. B47	p. B55	D. B63		p. B71
Neg	0.05 ~ 2.0 ~ 3.0 Medium cutting	VP3	0.5	0.05 ~ 0.15 ~ 0.25	PC8110 PC5300	60 40	p. B41	DNMG p. B47	p. B55	p. B63	p. B67	p. B71
	1.0 ~ 2.5 ~ 4.0 Roughing	VP4	0.17	0.15 ~ 0.20 ~ 0.35	PC8115	60 40	D. B41	DNMG p. B48	SNMG p. B55	D. B63		wnmg p. B71
	0.5 ~ 2.0 ~ 4.0 Medium cutting	VP1	1.2	0.05 ~ 0.23 ~ 0.30	PC8110 PC5300	60 45	p. B74	DCGT p. B81			vcgt p. B98	
Positive	0.2 ~ 1.0 ~ 2.5 Medium cutting	MS	12°	0.03 ~ 0.10 ~ 0.25	PC8110 PC5300	60 45	p. B74	p. B80			<b>VCGT</b> р. В98	
	0.1 ~ 0.8 ~1.5 Finishing	FS	16°	0.01 ~ 0.08 ~ 0.20	PC8110 PC5300	60 45	p. B74	p. B80		р. В89	<b>VCGT</b> р. В98	

•: The first recommended cutting condition






# CP Chip Breaker [For medium to finishing]

- · Chip breaker with strong cutting edge for heavy interrruption in the range of medium to finishing
- Effective chip control in the range from low depth of cut to high depth of cut due to 2-stepped back angle
- Stable chip evacuation and breaking long chip in deep cutting by side rake angle and continuous bumps

#### Features of CP chip breaker



- · Strong cutting edge in interrupted roughing
- · Keeping the balance between continuous cutting and interrupted cutting
- · Expanded versatility



#### ▶ 2-steped back side

- · Better chip control in low depth of cut machining
- · Improved chip evacuation in high feed machining
- Expanded versatility by 2-steped rake angle





#### ► Side rake angle + continuous bumps

- · Enhanced surface finish
- · Improved chip evacuation
- · Breaking long chips

#### Performance evaluation


CP

#### V-T (Vc-Tool life)

■ Workpiece Alloy steel (SCM440), External machining

vc (m/min) = 250, 300, 350, fn (mm/rev) = 0.3, Cutting condition ap (mm) = 0.5, wet


Insert: CNMG120408-RM (NC9115) ■ Tools Holder: PCLNL2525-M12



2500

2000






Competitor A

Competitor B

#### Application range




#### D-T (Depth of cut-Tool life)

■ Workpiece Alloy steel (SCM440), External machining


Cutting vc (m/min) = 250, fn (mm/rev) = 0.2,condition ap (mm) = 0.50, 0.75, 1.00, 1.25, 1.50, wet

Insert : CNMG120408-CP (NC3215P) ■ Tools

Holder: PCLNL2525-M12







Competitor A

Competitor B

В

**Turning** 

# FP Chip Breaker [For chip control in finishing]

- Chip breaker applied on one side of insert controls chip in mild steel machining with low depth of cut
- Chip control in poor machining (with lower depth of cut than nose R, in machining minor cutting edge and in back cutting)
- Decreased cutting load and excellent surface finish due to 3-dimensional cutting edge and side rake angle

#### Features of FP chip breaker

#### ► Concave form of semicircle-shaped bump

- · Better chip curling in mild steel machining
- · Enhanced chip control in low depth of cut and low feed machining

#### ▶ Semicircle-shaped bump

- · Enhanced chip control in low depth of cut machining
- · Advanced chip control in machining of minor cutting edge
- Improved chip control in machining with lower depth of cut than nose R



#### ▶ 3-dimensional side rake angle

· Ensuring surface finish and guiding chip to right diretion

#### ▶ Assistant bump on flank surface

- · Better chip curling in high depth of

- · Cutting long chip
- cut and low feed machining
- · Preventing chip twist

#### Performance evaluation


#### Chip control

■ Workpiece Mild steel (SM20C), Ø40 Internal machining


■ Cutting condition vc (m/min) = 200, n (rpm) = 1,600, fn (mm/rev) = 0.03, ap (mm) = 0.5, wet

Insert: CCMT09T304-FP (NC3215) ■ Tools

Holder: S16M-SCLCR-M09



#### Application range




#### Surface finish

■ Workpiece Mild steel (SM20C), Ø30 External machining

■ Cutting condition vc (m/min) = 200, n (rpm) = 2,000, fn (mm/rev) = 0.08, ap (mm) = 0.8, wet

■ Tools Insert: CCMT09T304-FP (NC3215)

Holder: SCLCR1616-M09











## FS Chip Breaker [For finishing]

- Chip breaker for ultra-precision automatic Swiss lathe machining (for lower depth of cut and lower feed cutting range than VP1 and MS)
- Available for various workpieces, P, M and S
- Reduced cutting load and good surface finish due to sharp cutting edge


#### Features of FS chip breaker



#### Performance evaluation



#### Application range





#### Wear resistance

■ Workpiece Alloy steel (SCM440)

■ Cutting condition vc (m/min) = 100, n (rpm) = 1,000, fn (mm/rev) = 0.05, ap (mm) = 0.5, wet

■ Tools Insert : CCGT09T304-FS (PC8110)








**Turning** 


## MS Chip Breaker [For medium to finishing]



- Sharp cutting edge with welding resistance reducing the cutting heat is necessary for machining hard-to-cut materials
- Chip evacuation is increased in low to high feed cutting conditions

#### Features of MS chip breaker





- · Improved chip curl and chip control in low feed cutting range
- · Better chip evacuation in high feed cutting range
- · Reduced cutting resistance
- · Protected cutting edge without chip blockage

#### Performance evaluation

#### Wear resistance

■ Workpiece

Pure titanium (Grade4)

■ Cutting condition vc (m/min) = 100, n (rpm) = 3,500, fn (mm/rev) = 0.03, ap (mm) = 0.5, wet

■ Tools


Insert: VCGT1203008FN-MS (PC8110)


Holder: SVJCR1212-X12A




ensurestable tool life.

Competitor






#### Application range



#### **Dimension precision**



▶ Changing tool offset in switching insert corners and items is not necessary using MS chip breaker due to tight dimension deviation management.

## LP Chip Breaker [For medium to finishing]

- Chip breaker for forged steel of automobile parts and normal steel
- Quad dots improve productivity through efficient chip control at high feed
- Angle land minimizes cutting force


#### Features of LP chip breaker

#### ▶ Front dot


- · Higher stability of chip curls at high feed
- · Excellent chip control when copying
- · Lower cutting force at low depth of cut and high feed

#### ▶ Variable land

- · Less crater wear
- · Prevents chipping on minor cutting edge



#### ▶ Flat zone




- · Larger chip pocket for better chip evacuation at high feed
- · Reduced cutting force with larger contact surface of chips


#### Performance evaluation (Evaluation of cutting force)

■ Workpiece SM45C, Ø100, External machining


■ Cutting condition vc (m/min) = 250, ap (mm) = 1.0, fn (mm/rev) = 0.25/0.40, wet

■ Tools CNMG120408-□□





#### Application range



# MP Chip Breaker [For medium cutting]

- Chip breaker for forged steel of automobile parts and all other steels
- Quad dots improve productivity through efficient chip control at high feed
- Angle land minimizes cutting force

#### Features of MP chip breaker


#### ▶ Front two step dot

- Higher stability of chip curls at high feed
- · Excellent chip control when copying
- · Lower cutting force at high depth of cut

#### ▶ Variable land

- · Less crater wear
- · Prevents chipping on minor cutting edge
- · Higher toughness at high depth of cut and interrupted cutting

#### ▶ Flat zone




- · Larger chip pocket for better chip evacuation at high feed
- · Reduced cutting force with larger contact surface of chips


#### Performance evaluation

■ Workpiece Alloy steel (SCM440), Ø100, External machining


■ Cutting condition vc (m/min) = 280, ap (mm) = 1.5, fn (mm/rev) = 0.25/0.40, wet

■ Tools CNMG120408-□□





#### Application range



## MM Chip Breaker (For medium cutting ]

- The 1st recommended chip breaker for stainless steel machining
- Change to: A dual land achieves sharp cutting performance and insert toughness
- Wide chip pockets for stable chip evacuation at high feeds/depths of cut

#### Features of MM chip breaker

#### ▶ Variable Land

- · Excellent chip control and sharp cutting at low depths of cut
- · Delays crater wear
- · Prevents plastic deformation

#### **▶** Dual Land

- Balance between requirements of sharp and tough cutting edges
- · Sharp cutting edge for high speed machining
- · Prevents chipping in interrupted machining

#### **▶** Wide Chip Pocket

- Stable chip evacuation at high speeds/feeds
- Improved surface finishes by reduced workpiece scratches caused by work-hardened chips at high depths of cut
- · Prevents built-up edge

#### Performance evaluation

#### **Built-up edge**

■ Workpiece STS405 (Ferrite)

■ Cutting vc (m/min) = 180, fn (mm/rev) = 0.3, ap (mm) = 3.0, wet

■ Tools Insert : CNMG120408-MM (NC9125) Holder: PCLNL2525-M12








#### Plastic deformation


■ Workpiece STS316 (Austenite)

■ Cutting vc (m/min) = 200, fn (mm/rev) = 0.35, ap (mm) = 2.0, dry


■ Tools Insert : CNMG120408-MM (NC9135)

Holder: PCLNL2525-M12





C9135) Competitor





## RM Chip Breaker [For roughing]

- The 1st recommended chip breaker for rough and interrupted machining of stainless steel
- Prevents notch wear and burrs at high feeds and depths of cut
- Reduced cutting force extends tool life in high feed machining

#### Features of RM chip breaker

#### ▶ Variable Land


- · Excellent chip control and sharp cutting at low depths of cut
- · Delays crater wear
- · Prevents plastic deformation

#### ▶ Wide land & Gentle front angle

- Sharp cutting edges and a wide land reduce cutting force
- Reduced burrs
- · Dispersed cutting load enables higher toughness

#### ▶ Stepped Design

- Stepped design makes chip evacuation easier
- · Smooth chip evacuation prevents plastic deformation



#### Performance evaluation

#### **Notch wear**

■ Workpiece STS410 (Martensite)

■ Cutting vc (m/min) = 150, fn (mm/rev) = 0.25, ap (mm) = 3.0, wet

■ Tools Insert : CNMG120408-RM (NC9115)

Holder: PCLNL2525-M12



Burr

■ Workpiece Duplex

■ Cutting vc (m/min) = 120, fn (mm/rev) = 0.2, condition ap (mm) = 2.0, dry

■ Tools Insert : CNMG120408-RM (NC9125)

Holder: PCLNL2525-M12





# MK Chip Breaker [For medium cutting]

- · Ideally suited for continuous cutting of ductile cast iron and gray cast iron
- · Angle lands provide upgraded surface finish

#### Features of MK chip breaker

#### ► Angle land

- · Angle lands provide sharper cutting performance
- · Maximized wear resistance in continuous cutting
- · High quality results in surface finish



Application range

#### ▶ Wide supporting area

- · Higher clamping stability
- Prevents chipping at vibrations during operation

#### Performance evaluation

#### Wear resistance

■ Workpiece GCD500(KS), Ø90 (Spherical tube) → Ø30 machining

■ **Cutting** vc (m/min) = 400, fn (mm/rev) = 0.35,

**conditions** ap (mm) = 2.5, wet

■ Cutting time 30 passes with results of normal wear on rake/flank

surface

■ Tools Insert: CNMG120408-MK (NC6315)


Holder: DCLNR2525-M12




MK (NC6315)



Existing product







# RK Chip Breaker (For roughing)

- Ideally suited for high speed / high feed cutting of ductile cast iron and gray cast iron
- Flat lands provide upgraded toughness and chipping resistance

#### Features of RK chip breaker

#### ▶ Flat land

- · Flat lands provide upgraded toughness and chipping resistance
- · Stable machining availability under high cutting loads at high depth of cuts or interrupted
- · Optimized land width for high feed machining



#### ▶ Wide supporting area

- · Higher clamping stability
- · Minimizes vibration and chipping.

#### Performance evaluation

#### Impact resistance

GCD500 (KS), Ø90 (Triangular tube) → Ø30 machining ■ Workpiece

vc (m/min) = 380, fn (mm/rev) = 0.35,■ Cutting

conditions ap (mm) = 2, wet

15 passes with results of normal rake surface wear and ■ Cutting time good chipping resistance


Insert: CNMG120408-RK (NC6315) ■ Tools Holder: DCLNR2525-M12




**RK(NC6315)** 



Existing product



#### Application range





## VP1 Chip Breaker [For finishing]

- Cutting edges designed in high-positive
  - Reduced contact area between rake surface and chip minimizes cutting heat and improved tool life
- Recommended cutting conditions: fn (mm/rev) = 0.05~0.2, ap (mm) = 0.1~1.5

#### Features of VP1 chip breaker

#### ▶ Optimized design for finishing

 Obtains excellent cutting performance and quality surface finish at low depth of cut and high speed



# 0

#### ► High-positive blade design

- Minimizes cutting heat by reducing the contact area between flank surface and chips
- · Prevents built-up edge and extends tool life

## VP2 Chip Breaker [For medium to finishing]

- High-positive cutting edge design/Side rake angle applied
  - Stable chip control improves machinability when ball machining at variable depths of cut
- Recommended cutting conditions: fn (mm/rev) = 0.1~0.4, ap (mm) = 0.5~4.5

#### Features of VP2 chip breaker

#### ▶ Sharp blades and wide chip pockets

- Increase productivity
- · Ideal for medium to finish cutting



# 0

#### ▶ High-positive blade design

 Improves cutting performance with its stable chip control at varying depth of cuts

## VP3 Chip Breaker [For medium cutting]


- High-positive cutting edge design/Wide land applied
  - Improved stability at interrupted cutting when toughness is required. Stable chip control and machinability at high depth of cut
- Recommended cutting conditions: fn (mm/rev) =  $0.1 \sim 0.45$ , ap (mm) =  $0.5 \sim 5.0$

#### Features of VP3 chip breaker

#### ▶ Chip pocket design leading to a R-shaped cutting edge

· Creates a stepped space between edge and land to make smooth chip flow at low and high depth of cuts





#### ▶ High-positive blade design / Wide land

- · Minimize heat concentration at high depth of cut
- · Improves stability in interrupted machining of a tough workpiece

## VP4 Chip Breaker [For roughing]



- The 1st recommended chip breakers for machining Inconel which remains highly resistant to and hard at high temperature
- · Rough machining stability resulting from reinforced cutting edges and wide chip pockets

#### Features of VP4 chip breaker


#### ▶ Rake angle design resistant to high hardness cutting

- · Reinforces cutting edges and prevents notch wear in rough surface machining
- · Prevents chipping in interrupted cutting



#### ▶ Wide chip pockets

· Reduce cutting loads and improve stability even at high depth of cut in roughing



## **Single-sided VL Chip Breaker**

[ For finishing ]

- The sharp flank surface and the chip breaker design significantly improve chip control when machining tough materials such as low carbon steel, pipe steel, and iron plates
- Sharp cutting edges reduce cutting resistance and provide excellent chip control at low depth of cuts, leading to stable machining on automated production lines




#### Features of VL chip breaker

- · Sharp cutting edges
- High rake cutting edges provide improved surface finishes
- Low cutting resistance reduces cutting heat
- · 2-step rear rake angle
- Stable chip control regardless of varying feed rates
- Excellent machinability even when machining mild workpieces

#### Chip control test

■ Workpiece SCM440(Alloy steel), Ø50, Internal diameter turning
■ Cutting condition vc = 250 m/min, ap = 0.3~1.5 mm, fn = 0.05~0.25 mm/rev

■ Tools CCMT09T304-VL



## **Single-sided MP Chip Breaker**

[ For medium to finishing ]

- · For continuous cutting of forged steel at high feed
- · Turning insert for internal machining of automobile components

#### Features of MP chip breaker

- · Three-dimensional 2 step chip breaker
- Stable chip control in unstable internal machining
- Prevents chip blocking at internal diameter at varying depth of cut and feed.
- · Stronger cutting edge and wide chip pocket
  - Increased chipping resistance in unstable internal machining


#### Chip control test

■ Workpiece SCM440

■ Cutting condition vc = 200 m/min, ap = 0.5~2.5 mm, fn = 0.05~0.25 mm/rev

■ Tools CCMT09T304-MP





feed, fn (mm/rev)

## VL Chip Breaker [For finishing]

- Improved chip control for machining material that have high toughness such as low carbon steel, pipe, steel plate etc
- mproved chip control and decreased cutting load on external, facing, and copying applications
- Improved strength of the cutting edge for measurable efficiency in automated production



#### Features of VL chip breaker

- · 2 steps designed chip-breaker Suitable Mild steel
  - Stable chip control on the low feed and cutting depth
- · Designed with special dots
- Stable chip breaking on the low cutting depth
- · Applied side rake angle
- Improved chip control on facing, copying applications
- Decreased cutting load and better surface finish

#### Chip control test

■ Workpiece SM20C

Cutting vc = 250 m/min, ap = 0.5 mmconditions fn = 0.2 mm/rev (Side), dry

DNMG150408-VL ■ Tools



VL

**Chip Breakers** 

Competitor A






Competitor C

#### FEM Cutting simulation analysis in the design

- · For design of geometry, chip shapes and chip flow are
- Optimal chip breaker design by various cutting conditions and workpieces







## VB Chip Breaker [For finishing]

Competitor B

- 3-dimensional chip breaker achieves lower cutting resistance, high rigidity of the cutting edge, and longer tool life
- Stable chip control in copying and internal machining

# • Excellent chip evacuation in continuous and high speed machining of various workpieces

#### Features of VB chip breaker

- · 6 bumps on the insert corner
- Superior chip control and chip cutting in copying with various depths of cut
- · Side rake angle
- Superb chip cutting in facing and copying. Superior tool life due to improved surface roughness and lower cutting resistance
- Cutting edge on 100° part for medium machining (For CNMG)
- Excellent chip evacuation and toughness in machining with high depth of cut

#### Performance

Better machining Better Chip control



**VB Chip Breakers** 

Longer tool life







Conventional chip breaker



## VC Chip Breaker [For medium to finishing]

- Superior chip evacuation in high speed and continuous machining of various workpieces (carbon steel, alloy steel etc)
- KORLOY 3 dimensional chip breaker ensures longer tool life due to low cutting load and improved cutting edge strength
- Stable chip control in copying and internal machining

#### Features of VC chip breaker

- · 4 bums on the insert corner
- Excellent chip control in various depths of cut and superb chip cutting in external, internal, copy machining and facing

#### Evaluation of chip control (Copying)

**VC Chip Breakers** 









## VQ Chip Breaker [For medium to finishing\_For cermet]

- · Excellent cutting performance and reinforced cutting edges
- Improved chip control at low depth of cuts

#### Features of VQ chip breaker

- · Three dimensional rake angle
- Improved surface finish thanks to sharp cutting performance
- Less cutting heat and longer tool life thanks to low cutting resistance
- · Beveled protruding structure
- Smooth chip flow at low depth of cuts
- Wide application range

#### Performance evaluation


■ Workpiece SCM440(Alloy steel), Ø100,


External diameter turning

Cutting vc = 280 m/min, ap = 1.5 mm,

conditions fn = 0.25 mm/rev

■ Tools CNMG120408-VQ (CN2500)







## VH/VT Chip Breaker [For heavy duty machining]

- Heavy duty chip breaker suitable for Heavy machining in the ship building and power plant industries
- Suitable for large vertical machines when machining shafts, rollers, rotors and optimal for the big flange machining

#### Features of VH chip breaker

#### ▶ For good chip control in heavy machining (comprehensive type)



- Designed from the study of heavy cutting mechanism
- Smooth chip control from the high rake angle
- Wider cutting edge land provides stronger cutting
- Unique cutting edge treatment provides smooth cutting
- Optimized chip pocket design provides smooth chip flow


#### Features of VT chip breaker

#### ▶ For long tool life and stable cutting (higher feeds, big depth) in heavy machining



- Designed from the study of heavy cutting mechanism
- Strong edge design provides long and stable cutting (2 step rake angle of cutting edge)
- Varied cutting edge land strengthens the cutting edge
- The positioning of the chip breaking convex dot deflect the machining heat, optimizes inserts wear & absorb shock


#### Applications range of chip breakers



## LW/VW Chip Breaker [For high feed cutting]

- · Improved productivity with higher feed rates and surface finishes
- · Improved wear resistance and toughness

#### Features of LW chip breaker



- · Curvilinear cutting edge Reduces cutting force
- Cutting edge design able to handle deeper depth of cuts lower cutting load & reduces heat
- Greater chip control at shallow depths of cuts Chip pocket design improves smooth chip flow
- For shallow depth cutting and low speed machining 3D design at the corner


[For medium cutting]


#### Features of VW chip breaker




- Excellent Finishing applications Excellent chip control
- Insert design great for stable clmaping Chip breaker designed close to the cutting edge
- Similar cutting edge to C/B for medium strong cutting edge
- · 3 Dimensional dot design on cutting corner
  - reduces cutting force and good chip control at shallow depth of cut

#### Applications range of chip breakers





- High productivity
- · Improved surface roughness
- · High feed-reducing machining time
- Improved tool life due to reduce cutting force




## SR/SH Chip Breaker [For machining a shaft]



- Specialized for machining slender bars and thin walls
- · High rake helix angle to reduce cutting resistance
- For machining steel and stainless steel

#### Features of SR chip breaker



- The first recommended chip breaker for machining a shaft
- · For continuous finishing
- Improved chip and heat evacuation due to high rake cutting edge and 3-dimensional shape
- · Good surface finish
- · Preventing fracture due to chamfering on the cutting edge

#### Features of SH chip breaker



- · Specialized for interrupted and medium cutting
- Efficient heat evacuation due to concave shaped back side of insert


[For medium cutting]



SR chip breaker

Other chip breakers


#### Applications range of chip breakers




Machining	C/B	ap (mm)	fn (mm/rev)
Medium to rough cutting	-None	1.5~5.0	0.20~0.55
Medium cutting	SH	1.5~5.0	0.15~0.50
Finish cutting	SR	1.0~4.5	0.12~0.45



## Cutting Edge Length, Diameter of Inscribed Circle **Insert Shape Relief Angle Cross Section Type Tolerance Insert Shape Relief Angle** 2





				(mm)
Class	d	<b>m</b>	- 1	t
Α	±0.025	±0.005		±0.025
С	±0.025	±0.013		$\pm 0.025$
Н	±0.013	±0.013		$\pm 0.025$
E	±0.025	±0.025		$\pm 0.025$
G	±0.025	±0.025		±0.13
J *	±0.05~±0.15	±0.005		±0.025
K *	±0.05~±0.15	±0.013		$\pm 0.025$
L*	±0.05~±0.15	±0.025		±0.025
M *	±0.05~±0.15	$\pm 0.08 \sim \pm 0.20$		$\pm$ 0.13
N *	±0.05~±0.15	±0.08~±0.18		±0.025
U *	±0.08~±0.25	±0.13~±0.38		±0.13


<sup>\*</sup> Sides are based on unground insert

#### Tolerance on C, H, R, T, W Insert Shape (Exceptional case)

d	Tolera	nce	on d	Tolerance on m			
u	J, K, L, M, N	1	U	M, N	- 1	U	
6.35	±0.05	1	$\pm 0.08$	±0.08	-	±0.13	
9.525	±0.05	1	$\pm 0.08$	±0.08	- 1	$\pm$ 0.13	
12.7	±0.08	1	$\pm 0.13$	±0.13		$\pm$ 0.20	
15.875	±0.10	1	$\pm 0.18$	±0.15	- 1	$\pm 0.27$	
19.05	±0.10	1	$\pm 0.18$	±0.15		$\pm$ 0.27	
25.4	±0.13	1	$\pm$ 0.25	±0.18	- 1	$\pm$ 0.38	

#### Tolerance on D Insert Shape (Exceptional case)

d	Tolerance on d	Tolerance on m
6.35	±0.05	±0.11
9.525	$\pm 0.05$	±0.11
12.7	$\pm 0.08$	$\pm 0.15$
15.875	±0.10	±0.18
19.05	$\pm 0.10$	$\pm 0.18$



**Height of Cutting Edge** 

Nose "r"

**Chip Breaker for Turning** 

	Cutting Edge Length, Diameter of Inscri	ped Circle
5	C N M G 12 04 08 -	MP


Symbol								
С	d	S	T	R	V	- W	Inch	IC
			Metric					d (mm)
03	04	03	06	03	-	02	1.2 (5)	3.97
04	05	04	08	04	08	S3	1.5 (6)	4.76
05	06	05	09	05	09	03	1.8 (7)	5.56
-	-	-	-	06	-	-	-	6.00
06	07	06	11	06	11	04	2	6.35
08	09	07	13	07	13	05	2.5	7.94
-	-	-	-	08	-	-	-	8.00
09	11	09	16	09	16	06	3	9.525
-	-	-	-	10	-	-	-	10.00
11	13	11	19	11	19	07	3.5	11.11
-	-	-	-	12	-	-	-	12.00
12	15	12	22	12	22	08	4	12.70
14	17	14	24	14	24	09	4.5	14.29
16	19	15	27	15	27	10	5	15.875
-	-	-	-	16	-	-	-	16.00
17	21	17	30	17	30	11	5.5	17.46
19	23	19	33	19	33	13	6	19.05
-	-	-	-	20	-	-	-	20.00
22	27	22	38	22	38	15	7	22.225
-	-	-	-	25	-	-	-	25.00
25	31	25	44	25	44	17	8	25.40
32	38	31	54	31	54	21	10	31.75
-	-	-	-	32	-	-	-	32.00
					( )	Symbol fo	r small s	ize insert






S	ymbo	l	N	ose "ı	r"
Metric	- 1	Inch	Metric	- 1	Inch
003	- 1	0.1	0.03		0.0012
005	1	0.13	0.05		0.002
01	1	0.2	0.1		0.004
02	1	0.5	0.2	1	0.008
04	1	1	0.4		1/64
08	1	2	0.8	1	1/32
12	1	3	1.2	1	3/64
16	1	4	1.6		1/16
20	1	5	2.0	1	5/64
24	1	6	2.4	1	3/32
28	I	7	2.8	I	7/64
32	1	8	3.2	1	1/8
00	-	-	Round	d insert	(Inch)
MO	- 1	-	Round	insert (	(Metric)

Height of Cutting Edge  CNMG 12 04 08 - MP											
t											
	t		t t								
	ymbol		tting Edge (t)								
Metric	Inch	mm	Inch								
01	1 (2)	1.59	1/16								
T0	1.125	1.79	9/128								
T1	1.2	1.98	5/64								
02	1.5 (3)	2.38	3/32								
T2	1.75	2.78	7/64								
03	2	3.18	1/8								
T3	2.5	3.97	5/32								
04	3	4.76	3/16								
05	3.5	5.56	7/32								
06	4	6.35	1/4								
07	5	7.94	5/16								
09	6	9.52	3/8								
11	7	11.11	7/16								
12	8	12.70	1/2								
		( ) Symbo	ol for small size insert								



## B Turning Insert (Negative)





	Dimensio	ons (mm)	
Size	d	t	d₁
09	9.525	3.18	3.81
12	12.7	4.76	5.16
16	15.875	6.35	6.35

## Rhombic 80° Negative

	Steel	Р		#			3	•		#	#	#	•	•	3		#							Machining types
8	Stainless steel	M								3	3	3				3	#	•	3	3	#			3 7/1-1
cpie	Cast iron	K		#	•	\$ 3		3				\$	\$	3								•	3	<ul><li>Continuous cutting</li></ul>
¥	Non-ferrous metal	N																					3	General cutting
×	Heat resistant alloy, Titanium alloy	S															•	•		3			3	# Interrupted cutting
	Hardened steel	Н																•	3	3			3	- Interrupted cutting

							ated								Coa										Unc	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215P	NC3225P	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC8105	PC8110	PC8115	PC9030	亨	H05	fn (mm/rev)	ap (mm)
	VB	CNMG	120404-VB	•	•		•			•	•				•												0.15~0.35	0.30~2.00
Finishing	VB		120408-VB	•	•		•			•	•				•												0.15~0.45	0.50~2.00
hish			120412-VB							•	•				•												0.20~0.50	0.50~2.00
走																												
		CNMG	090304-VF								•																0.07~0.30	0.50~1.50
	VF		090308-VF																								0.10~0.30	0.50~1.50
ng	VF		120404-VF									•			•												0.07~0.30	0.50~1.50
Finishing	100		120408-VF												•												0.10~0.40	0.50~1.50
ᇤ			120412-VF																								0.10~0.50	0.60~1.50
	VL	CNMG	120404-VL	•	•										•												0.05~0.25	0.10~1.00
ing	VL		120408-VL	•	•					•	•				•												0.10~0.35	0.20~1.50
Finishing	VI (1)		120412-VL																								0.10~0.35	0.20~1.50
造	The second																											
5		CNMG	090304-LP																									0.30~1.50
iệ	LP		090308-LP							•	•																	0.30~1.50
iji	new		120404-LP								•				•												0.10~0.35	0.30~2.00
5			120408-LP							•	•				•													0.50~2.50
Medium to finishing	A. C.		120412-LP							•	•				•												0.13~0.45	0.80~3.00
		CNMG	090304-CP																									0.40~3.00
			090308-CP																									0.40~3.00
<u> </u>			090404-CP																									0.40~3.00
Shir	CP		090408-CP																									0.40~3.00
fil	A PARTY OF THE PAR		120404-CP						•																			0.50~3.50
Medium to finishing	100		120408-CP						•																			0.50~3.50
를			120412-CP						•																			0.80~3.50
ž			160608-CP						•																			0.80~4.50
			160612-CP																								0.18~0.40	1.00~4.50
		CNMG	120404-VC							•	•				•												0.10~0.35	0.30~2.00
shin	VC		120408-VC							•	•				•												0.15~0.40	0.50~3.00
fini	40		120412-VC							•	•																0.15~0.45	0.50~3.00
n to											-																	
Medium to finishing																												
Me																												
				_																					_			

ullet : Stock item


	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173



**③** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15

**ᢒ** Code system **B34~B35** 





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	4.76	5.16
16	15.875	6.35	6.35
19	19.05	6.35	7.93

## Rhombic 80° Negative

	Steel		Р		#		\$	3	\$ #	#	#	•	•	\$	#									Machining types
ဗ္ဗ	Stainless steel		M						3	3	3			3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	\$ 3				3	3	3									•	3	<ul> <li>Continuous cutting</li> </ul>
높	Non-ferrous metal	•	N																				3	<b>♣</b> General cutting
×	Heat resistant alloy, Titanium alloy		S												•	3	#	•	3	3			3	# Interrupted cutting
	Hardened steel		Н															•	3	3			3	- interrupted cutting

				Cer	met	Coa	ated							(	Coa	ted								Unc	pated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC3300	PC5400	PC8105	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		CNMG	090304-HM		_	Ť	_	_		_													Ī	Π	Π	0.12~0.40	0.50~3.80
			090308-HM																							0.15~0.40	0.80~3.80
ting	HM		120404-HM						•	•	•															0.05~0.30	0.90~5.00
3			120408-HM						•		•															0.10~0.50	1.00~5.00
Medium cutting			120412-HM																				•			0.18~0.50	1.00~5.00
Med			190612-HM							•																0.13~0.60	1.30~7.00
		CNMG	090304-MP					•	•				•				•									0.10~0.40	0.40~3.80
			090308-MP					•	•				•				•									0.15~0.40	0.50~4.00
			090312-MP																							0.15~0.50	0.80~4.20
			090404-MP																							0.10~0.40	0.40~3.80
			090408-MP																							0.15~0.40	0.50~4.00
			090412-MP																							0.15~0.50	0.80~4.20
5	MP		120404-MP					•	•				•	•	_	•	•	•			• •	•				0.10~0.40	0.40~4.00
ŧ	new		120408-MP					•	•		•		•	•	_	•	•	•			• (	•				0.15~0.45	0.50~4.50
Medium cutting			120412-MP					•	•				•		_	•	•	•		-	• •					0.15~0.50	0.80~5.00
i i i i			120416-MP					•	•				•			•	•	•	_							0.28~0.55	1.00~5.00
₹	Ĭ		160608-MP					•	•				•		_	•	•	•				_				0.15~0.50	0.50~7.00
			160612-MP						•				•				•	•	_							0.18~0.60	0.80~7.00
			160616-MP						•	_			•		_		_		-							0.15~0.60	1.00~7.00
			190608-MP							•																0.15~0.60	0.50~8.50
			190612-MP							•					-	•	•		-		_					0.10~0.40	0.40~3.80
			190616-MP														•									0.15~0.40	0.50~4.00
		CNMG	090304-VM																							0.05~0.30	0.90~3.50
			090308-VM							•	•															0.10~0.45	1.00~3.50
			120404-VM	•	•					•	•		•							•			•			0.05~0.30	0.90~5.00
			120408-VM	•	•				•		•		•							•			•			0.10~0.50	1.00~5.00
			120412-VM								•		•							•						0.13~0.60	1.30~5.00
	VM		120416-VM										•													0.20~0.60	1.50~5.50
ting	VIVI		160608-VM										•													0.10~0.50	1.00~6.70
D.			160612-VM																							0.13~0.60	1.30~6.70
Medium cutting	1		190608-VM								•															0.13~0.65	1.30~7.00
Med			190612-VM										•													0.15~0.70	1.50~7.00
			190616-VM																							0.18~0.75	1.80~7.00

**③** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15


€ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173



# B Turning Insert (Negative)





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	4.76	5.16
16	15.875	6.35	6.35
19	19.05	6.35	7.93
25	25.4	9.52	9 12

## Rhombic 80° Negative

	Steel		Р		#	3		3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							\$	3	3				3	#	3	#	•	1	3	#		
pie	Cast iron	4	K		#	3	3					3	3	3											<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S															3	#	•	3	3		3	# Interrupted cutting
	Hardened steel		Н																	•	3	3		3	* Interrupted cutting

				Cer	met	Coa	ated								Coa	ited									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500		NC3215	NC3225	NC3120	NC3030	NC3935	NC5330	NC6310			NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	030		H05	fn (mm/rev)	ap (mm)
		CNMG	120404-B25	0	0	S	O	2	Z	Z	2	Z	2 2	Z	z	Z	Z	2	<b>D</b>	<u>а</u>	Д	<u></u>	<b>-</b>	Д.	I	工	0.17~0.45	1.00~5.00
		Oitimo	120404-B25	•				•	•	•	•		•							•							0.23~0.60	1.50~5.00
			120412-B25		•			•	•	Ť	•		•														0.25~0.60	2.00~5.00
ing	<b>B25</b>		160608-B25		Ť			•	•		•		•										T				0.25~0.60	2.00~6.50
Medium to roughing			160612-B25					•	•		Ť		•														0.27~0.60	2.00~6.50
5			160616-B25					•	•				•						Т				T				0.27~0.60	2.00~6.50
Ē			190604-B25								•		•										T				0.20~0.45	3.00~8.00
edii			190608-B25					•	•	•	•		•														0.25~0.60	3.00~8.00
2			190612-B25					•	•	•	•		•					-	•	•							0.30~0.60	3.00~8.00
			190616-B25					•	•																		0.23~0.70	3.00~8.00
		CNMG	120408-GR						•	•	•		•	•	•												0.20~0.50	1.00~7.00
			120412-GR						•	•	•		•	•	•												0.25~0.50	1.30~7.00
			120416-GR																								0.25~0.60	1.80~6.00
			160608-GR						•	•	•																0.20~0.70	1.00~8.00
	GR		160612-GR						•	•	•		•	•	•												0.25~0.70	1.30~8.00
ing	GR		160616-GR						•	•	•																0.25~0.75	1.80~8.00
Roughing	602		190608-GR							•	•		•														0.20~0.70	1.70~10.00
8	1		190612-GR						•	•	•		•	•													0.30~0.75	1.70~10.00
			190616-GR						•	•	•		•														0.30~0.80	1.80~10.00
			190624-GR																								0.35~0.85	2.00~12.00
			250724-GR																		_						0.40~1.00	2.30~15.00
			250924-GR								•		•				_		_				_				0.40~1.00	2.30~15.00
		CNMG	090304-VQ																								0.05~0.30	0.50~3.50
5			090308-VQ																				T				0.08~0.30	0.80~4.00
shin	VQ		090408-VQ										•														0.05~0.30	0.50~3.50
fij.	40		090412-VQ										•						т				Т				0.08~0.30	0.80~4.00
ם			120404-VQ	•	•	•	•																T				0.05~0.30	0.80~4.00
Medium to finishing	1		120408-VQ	•	•	•	•																				0.08~0.40	0.80~4.00
≥	[Cermet]		120412-VQ																								0.10~0.40	0.80~4.00
											_																	
		CNMG	120404-MK												•												0.05~0.30	0.90~4.00
			120408-MK											•	•												0.10~0.50	1.00~5.00
			120412-MK											•	•												0.13~0.60	1.30~5.00
Medium cutting	MK _		120416-MK																								0.15~0.60	1.30~5.00
no u	new		160608-MK																									1.80~7.00
lium			160612-MK																									2.00~8.00
Mec	100		160616-MK																									2.00~8.00
			190608-MK												•													2.50~9.00
			190612-MK												•								_					2.60~9.50
			190616-MK																								0.35~0.80	2.60~10.00


Cutting edge geometry A37~A49

<sup>• :</sup> Stock item

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173

<sup>◆</sup> Code system B34~B35





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	4.76	5.16
16	15.875	6.35	6.35
19	19 05	6.35	7 93

## Rhombic 80° Negative

	Steel		Р		#	\$		3	3	#	#	#	•	•	3		#								Machining types
ဗ္ဗ	Stainless steel		M							3	3	3				3	#	3	#	•	3	3	#		
bje	Cast iron	4	K		#	\$	3					3	3	\$										0 3	<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	•	N																					0 3	General cutting
ĕ∣	Heat resistant alloy, Titanium alloy	<b>-</b>	S									•					•	3	#	•	3	3		0 3	# Interrupted cutting
	Hardened steel		Н																		3	3		0 3	- Interrupted cutting

				Cer	met	Coa	ted								Coa	ted								U	nco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500		CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	2	H05	fn (mm/rev)	ap (mm)
		CNMA	090308																						П		0.10~0.30	0.50~3.00
			120404												•												0.15~0.60	1.00~5.00
			120408												•												0.15~0.60	1.00~6.00
			120412												•												0.15~0.70	1.50~6.00
			120416												•												0.20~0.80	2.00~6.00
			160608																								0.15~0.70	2.00~6.00
ing			160612												•												0.15~0.70	2.00~6.00
Roughing			160616												•												0.15~0.70	2.00~6.00
윤			190608												•												0.15~0.70	2.00~10.00
			190612												•												0.15~0.70	2.00~10.00
			190616																								0.20~1.00	3.00~10.00
Roughing	RK	CNMG	120404-RK 120408-RK 120412-RK 120416-RK 160608-RK 160612-RK 160616-RK 190612-RK											•	•												0.20~0.47 0.20~0.50 0.28~0.53 0.28~0.63 0.28~0.70 0.28~0.72 0.28~0.74 0.35~0.78 0.35~0.80	1.30~6.00 1.50~6.00 1.80~6.00 2.00~6.00 1.80~7.00 2.00~8.00 2.00~8.00 2.60~9.50 2.60~10.00
		CNMG	120404-VR																					$\perp$			0.20~0.50	1.00~6.50
		3.11113	120408-VR				$\exists$														+						0.25~0.55	1.20~7.00
			120412-VR																								0.30~0.60	1.50~7.00
			120416-VR																								0.35~0.65	1.70~7.00
			120508-VR																						T		0.25~0.55	1.20~7.00
	VR		120512-VR																				T				0.30~0.60	1.50~7.00
ghing			160612-VR																								0.35~0.70	2.00~8.00
Rough			160616-VR																									2.20~8.00
œ			190612-VR					•	•																			2.00~10.00
			190616-VR					•	•																		0.35~0.75	2.20~10.00


→ Cutting edge geometry A37~A49

**ᢒ** Code system **B34~B35** 

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173

## **B** Turning Insert (Negative)





	Dimensio	ons (mm)	
Size	d	t	d₁
09	9.525	3.18	3.81
12	12.7	4.76	5.16
16	15.875	6.35	6.35
19	19.05	6.35	7.93
25	25.4	9.52	9.12

## Rhombic 80° Negative

	Steel		Р		#	3		3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							\$	3	3				3	#	3	#	•	1	3	#		
pie	Cast iron	4	K		#	3	3					3	3	3											<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S															3	#	•	3	3		3	# Interrupted cutting
	Hardened steel		Н																	•	3	3		3	* Interrupted cutting

				Cer	met	Coa	ated							(	Coat	ed								Uncoa	ted	Cuttina (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330			NC9115 NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115			H05	fn (mm/rev)	ap (mm)
		CNMG	090304-MM																							0.08~0.35	0.50~5.00
			090308-MM													•							•			0.10~0.40	0.50~5.00
			090312-MM																							0.12~0.45	0.50~5.00
			090404-MM																							0.08~0.35	0.50~5.00
			090408-MM																							0.10~0.40	0.50~5.00
			090412-MM																							0.12~0.45	0.50~5.00
	MM		120404-MM													•		•			•	•	•			0.10~0.40	0.50~5.50
tting	Alle		120408-MM													• •		•				•	•			0.12~0.45	0.50~5.50
ᇹ			120412-MM													• •	•	•			•	•	•			0.15~0.60	0.50~5.50
<u>.</u>			120416-MM													•	•	•				•				0.20~0.65	0.50~5.50
Medium cutting			160608-MM													•		•				•				0.12~0.45	0.50~7.00
			160612-MM													•	•	•				•	•			0.15~0.60	0.50~7.00
			160616-MM													•	•	•				•	•			0.18~0.65	0.50~7.00
			190608-MM													•	•	•				•				0.12~0.45	0.50~8.50
			190612-MM													•	•	•			•	•	•			0.15~0.60	0.50~8.50
			190616-MM													•	•	•				•	•			0.18~0.65	0.50~8.50
Roughing	RM	CNMG	120404-RM 120408-RM 120412-RM 120416-RM 160608-RM 160612-RM 190608-RM 190612-RM 190612-RM 190616-RM 250924-RM																				•			0.10~0.50 0.15~0.55 0.20~0.60 0.25~0.70 0.15~0.55 0.20~0.60 0.25~0.70 0.15~0.55 0.20~0.60 0.25~0.70 0.25~0.70 0.25~0.70 0.40~1.20	2.00~6.00 2.00~6.00 2.00~6.00 2.00~6.00 2.00~8.00 2.00~8.00 2.00~8.00 2.00~10.00 2.00~10.00 4.00~14.00
Finishing	VP1	CNMG	120404-VP1 120408-VP1																	•				•		0.05~0.15	0.10~1.50 0.10~1.50
		CNGG	120402-VP1																		•					0.01~0.10	0.10~1.00
	VP1	31100	120402-VP1						-		-									Н	•	+				0.05~0.15	0.10~1.50
hin			120404-VP1																			+				0.03~0.13	0.10~1.50
Finishing			120100 11 1																							5.010.20	0.10-1.00

Outting edge geometry A37~A49


ullet : Stock item

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173



<sup>→</sup> Code system B34~B35





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
12	12.7	4.76	5.16
16	15.875	6.35	6.35
19	19.05	6.35	7.93

## Rhombic 80° Negative

	Steel	4	Р		#				•	#	#	#	•	3		#										Machining types
8	Stainless steel		M							3	\$	3		•	\$	#	3	#	•	3	3	3	#			
Bi.	Cast iron	4	K		#	•	3	3				3	\$											•		<ul> <li>Continuous cutting</li> </ul>
춪	Non-ferrous metal	4	N																						3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S									•			•	•	3	#	•	3	3	3		•	3	# Interrupted cutting
	Hardened steel	$\overline{}$	Н																•	3	3				3	Therrupted cutting

				Cei	rmet	Coa	ated							C	oate	d									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC8120	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		CNMG	120404-VP2						•									•	•	•	•	•			•		0.05~0.30	0.10~3.00
hing	VP2		120408-VP2																•	•	•	•					0.10~0.40	0.50~4.50
inis	<u> </u>		160608-VP2																								0.12~0.45	0.80~5.00
to t			190608-VP2																								0.12~0.50	1.00~5.20
<u>E</u> .			190612-VP2																								0.15~0.50	1.20~5.50
Medium to finishing			190616-VP2																								0.18~0.50	1.50~5.50
		CNMG	120404-VP3																•	•	•	•			•	•	0.05~0.30	0.10~3.00
			120408-VP3																•		•	•			•	•	0.10~0.40	0.50~4.50
			120412-VP3																•	•	•	•			•	•	0.12~0.50	0.50~5.00
ng	VP3		120416-VP3																								0.25~0.45	1.00~4.00
Medium cutting			160608-VP3																								0.15~0.35	0.80~6.00
Ē			160612-VP3																								0.20~0.40	1.00~6.00
edir			160616-VP3																								0.20~0.40	1.00~6.00
2			190608-VP3																								0.20~0.50	1.00~7.00
			190612-VP3																								0.25~0.55	1.00~8.00
			190616-VP3																								0.30~0.60	1.00~8.00
ng	VP3	CNGG	120404-VP3																	•	•	•			•		0.05~0.30	0.10~3.00
Ħ	VIS		120408-VP3																	•	•				•		0.10~0.40	0.50~4.50
Ę			120412-VP3																		•						0.12~0.50	0.50~5.00
Medium cutting																												
		CNMG	120408-VP4																			•	•				0.15~0.35	1.00~4.00
	VP4		120412-VP4																			•	•				0.20~0.40	1.00~4.00
_	VP4		160608-VP4																								0.20~0.45	1.00~6.50
Roughing			160612-VP4																								0.25~0.50	1.50~6.50
ond			190608-VP4																			•	•				0.15~0.45	1.00~8.00
<u>~</u>			190612-VP4																			•	•				0.20~0.50	1.20~8.50
gui	НА	CNMG	120404-HA																					•	•		0.05~0.20	0.80~3.50
sini			120408-HA																		•			•	•		0.10~0.40	0.80~3.50
n to f	-		120412-HA																					•			0.13~0.55	0.80~3.50
Medium to finishing	700																											
		CNMG	120404-VW																								0.10~0.30	0.50~3.00
g	VW		120408-VW					•																			0.15~0.50	0.50~4.00
Finishing			120412-VW																								0.20~0.55	1.00~4.50
Finis	-																										5.25 5.55	1.00 1.00
	[Wiper	]																										

→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

€ Code system B34~B35

ullet : Stock item

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173

## **B** Turning Insert (Negative)



	Dimens	sions (mm)	
Size	d	t	d₁
12	12.7	4.76	5.16
16	15.875	4.76~6.35	6.35
19	19.05	6.35	7.93
25	25.4	7.94~9.52	9.12

## Rhombic 80° Negative

	Steel	Р		#			3	#	#	#	•	•		#									Machining types
8	Stainless steel	M						3	3	3			3	#	3	#		3	3	#			
bje	Cast iron	K		#	•	\$ 3				3	3	\$									•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N																				3	<b>♣</b> General cutting
×	Heat resistant alloy, Titanium alloy	S								•				•	3	#	•	3	3			3	-
	Hardened steel	Н															•	3	3		•	\$	# Interrupted cutting

					Coa									Coa										Unc	oated	Cutting (	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
DG .	LW	CNMG 120408-LW						•				•														0.15~0.60	1.00~5.00
iĦ		120412-LW					•	•								•										0.20~0.70	1.00~6.00
Medium cutting	[Wiper]																										
		<b>CNMM</b> 120408-GR																								0.20~0.50	1.00~7.00
ting	GR	120412-GR																								0.25~0.50	1.30~7.00
ct	-	190612-GR								•																0.30~0.75	1.70~10.00
<u>i</u>	C. Carre	190616-GR																								0.30~0.80	1.80~10.00
Medium cutting																											
		CNMM 120408-GH						•		•		•														0.30~0.60	2.50~8.00
		120412-GH						•	•	•																0.30~0.70	2.50~8.00
		160412-GH																								0.30~0.70	2.50~8.00
		160424-GH																								0.30~1.20	2.50~8.00
		160612-GH																								0.30~0.90	2.50~8.00
	GH	160616-GH																								0.30~1.20	2.50~8.00
	621	160624-GH																								0.30~1.50	2.50~8.00
Heavy		190608-GH										•														0.30~0.60	2.50~8.00
포	ALL SO	190612-GH							•	•		•														0.30~0.70	3.00~8.00
		190616-GH							•	•		•														0.45~0.90	3.00~8.00
		190624-GH							•			•														0.55~1.20	4.00~9.00
		250716-GH																								0.50~1.00	4.50~10.00
		250724-GH							•																	0.55~1.20	5.00~12.00
		250924-GH							•	•		•														0.55~1.20	5.00~12.00
		<b>CNMM</b> 190612-VH					•																			0.50~0.90	5.00~10.00
	VH	190616-VH																								0.50~1.10	5.00~10.00
>	<b>VII</b>	190624-VH																								0.60~1.20	6.00~12.00
Heavy		250724-VH																								0.70~1.40	6.00~15.00
		250924-VH																								0.70~1.40	6.00~15.00
		<b>CNMM</b> 190612-VT					•			•		•														0.60~1.00	6.00~13.00
	VT	190616-VT					•																				5.00~10.00
	VI	190624-VT					•																			0.60~1.60	7.00~13.00
Heavy		250724-VT					•																			0.75~16.0	7.00~17.00
I		250924-VT					•																			0.75~16.0	7.00~17.00
	[ High feed cutting ]																										

ullet : Stock item

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173




<sup>€</sup> Cutting edge geometry A37~A49 € Recommended chip breaker B04~B15

<sup>€</sup> Code system B34~B35







	Dimens	sions (mm)	
Size	d	t	d₁
11	9.525	3.18~4.76	3.81
15	12.7	4.76~6.35	5.16

## Rhombic 55° Negative

	Steel		Р		#				#	#	#	•	•		#									Machining types
ల్ల	Stainless steel		M						3	3	3			3	#	3	#		3	3	#			
cpie	Cast iron	•	K	•	#	3	3				3	\$	\$									•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal		N																				3	General cutting
×	Heat resistant alloy, Titanium alloy		S								•				•	\$	#	•	3	3			3	# Interrupted cutting
	Hardened steel		Н															•	3	3			3	- interrupted cutting

				Ce	rme	Co	ated								Coa	ited									Unco	nated	Cutting (	Condition
	lma aut -		alamatia -						52	0	2	32	20				i D	င္သ	0	0	2	0	2	0	Unio	aivu		
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		DNMG	110404-VB																								0.05~0.25	0.30~2.00
			150404-VB	•	•	•	•	•	•																		0.10~0.35	0.30~2.00
	VB		150408-VB	•	•	•	•	•	•				•									•					0.15~0.45	0.50~2.00
<u>i</u> g	V D		150412-VB					•	•																		0.15~0.45	0.50~2.00
Finishing			150604-VB	•	•	•	•	•	•				•														0.10~0.35	0.30~2.00
匝			150608-VB	•	•	•	•	•	•				•						•								0.15~0.45	0.50~2.00
			150612-VB					•	•				•														0.20~0.50	0.50~2.50
		DNMG	110402-VF																								0.05~0.20	0.20~1.00
			110404-VF										•														0.07~0.30	0.50~1.50
			110408-VF																								0.10~0.40	0.50~1.50
	VF		150404-VF																								0.07~0.30	0.50~1.50
ing			150408-VF																								0.10~0.40	0.50~1.50
Finishing			150412-VF																								0.15~0.50	0.60~1.50
造			150604-VF							•			•														0.13~0.30	0.50~1.50
			150608-VF							•			•														0.10~0.40	0.50~1.50
			150612-VF																								0.15~0.50	0.60~1.50
		DNMG	110408-VL						_																		0.05~0.20	0.10~1.00
			150404-VL					_	•				•														0.05~0.25	0.10~1.50
	VL		150408-VL					•	•				•														0.05~0.30	0.20~1.50
guir			150412-VL	_																							0.10~0.30	0.25~1.50
Finishing	The state of the s		150604-VL	•				_	_				_						_								0.05~0.25	0.10~1.50
ΙŒ			150608-VL	•				•	•				•														0.05~0.30	0.20~1.50
			150612-VL																								0.10~0.30	0.25~1.50
		DNMG	110402-LP																								0.06~0.30	0.25~1.20
			110404-LP					•	•																		0.07~0.30	0.30~1.50
			110408-LP																								0.10~0.40	0.30~1.50
<u>S</u>			110504-LP																								0.07~0.30	0.30~1.50
shir	LP		110508-LP																								0.10~0.40	0.30~1.50
Medium to finishing	new		150404-LP					•	•				•						T								0.10~0.35	0.30~2.00
10			150408-LP					•	•				•						T								0.10~0.40	0.50~2.50
diur			150412-LP					•	•				•														0.13~0.45	0.80~3.00
Me			150604-LP					•	•				•														0.10~0.35	0.30~2.00
			150608-LP					•	•				•														0.10~0.40	0.50~2.50
			150612-LP					•	•				•														0.13~0.45	0.80~3.00


Outting edge geometry A37~A49

**③** Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173

## **Turning Insert (Negative)**





	Dimens	sions (mm)											
Size													
11	9.525	3.18~4.76	3.81										
15	12.7	4.76~6.35	5.16										

## Rhombic 55° Negative

	Steel		Р		#		\$	\$ •	\$ 3	#	#	#	•	•	3		#							Machining types
8	Stainless steel		M							3	3	3				3	#		3	3	#			
cpie	Cast iron	<b>-</b>	K		#	•	\$ 3	\$				3	\$	3								•	3	<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																				3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S														•	•	3	3			3	# Interrupted cutting
	Hardened steel	<b>-</b>	Н															•	3	\$		•	3	- Interrupted cutting

				Cer	met	Coa	ated							Coa	ated								Unco	oated	Cuttina (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215P	NC3225P	NC3215	NC3225	NC3120 NC3030	NC3235		NC6310	NC6315	NC9115	NC9125	NC9135	PC8105	PC8115	PC9030		H05	fn (mm/rev)	ap (mm)
		DNMG	110404-CP		_		_		_				Ī	Ė	_								_	_	0.08~0.30	0.40~3.00
			110408-CP																						0.10~0.30	0.40~3.00
			110504-CP																						0.08~0.30	0.40~3.00
ing			110508-CP																						0.10~0.30	0.40~3.00
isis	CP		150404-CP					•	•																0.10~0.35	0.50~3.50
ţ.	new		150408-CP					•	•																0.12~0.35	0.50~3.50
Medium to finishing	- LO		150412-CP						•																0.13~0.35	0.80~3.50
Med			150604-CP					•	•																0.10~0.35	0.50~3.50
_			150608-CP																						0.12~0.35	0.50~3.50
			150612-CP						•																0.13~0.35	0.80~3.50
- D		DNMG	150404-VC							•	•														0.10~0.35	0.30~2.00
Medium to finishing			150408-VC								•			•											0.15~0.40	0.50~3.00
finis	VC		150412-VC							•	•														0.15~0.45	0.50~3.00
5			150604-VC								•														0.10~0.35	0.30~2.00
<u><u></u></u>			150608-VC								•			•											0.15~0.40	0.50~3.00
Med			150612-VC								•														0.15~0.45	0.50~3.00
		DNMG										•										•			0.05~0.50	0.80~4.00
_			110408-HM																			•			0.10~0.50	1.00~4.00
Medium cutting	НМ		150404-HM								•														0.05~0.30	0.90~5.00
20			150408-HM								(	•													0.10~0.50	1.00~5.00
į			150604-HM								(	• •				•						•			0.05~0.30	0.90~5.00
Mec			150608-HM							-	•	• •										•			0.10~0.50	1.00~5.00
			150612-HM									•													0.18~0.50	1.00~5.00
		DNMG	110404-MP								•			•			•								0.10~0.40	0.40~3.80
			110408-MP								•			•			•								0.15~0.40	0.50~4.00
			110412-MP																						0.15~0.50	0.80~4.20
			110504-MP																						0.10~0.40	0.40~3.80
			110508-MP																						0.15~0.40	0.50~4.00
g	MP		110512-MP																						0.15~0.50	0.80~4.20
慧	new		150404-MP								•			•			•				)				0.10~0.40	0.40~4.00
Medium cutting			150408-MP								•			•			•			•	)				0.15~0.45	0.50~4.50
edic			150412-MP								•			•			•			•	)				0.15~0.50	0.80~5.00
Σ			150416-MP																						0.15~0.50	0.85~5.00
			150604-MP								•			•	•		•			• •	)				0.10~0.40	0.40~4.00
			150608-MP								•			•	•		•			• •	)				0.15~0.45	0.50~4.50
			150612-MP							•	•			•			•			• •	)				0.15~0.50	0.80~5.00
			150616-MP																						0.15~0.55	0.85~5.00

Cutting edge geometry A37~A49


→ Recommended chip breaker B04~B15

€ Code system B34~B35









	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
11	9.525	4.76	3.81
15	12.7	4.76~6.35	5.16

## Rhombic 55° Negative

	Steel		Р		#	•				#	#	#	•	•		#									Machining types
8	Stainless steel		M							<b>3</b>	3	3			3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	3	3				3	\$	3									•	3	<ul> <li>Continuous cutting</li> </ul>
춪	Non-ferrous metal	•	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S													•	3	#	•	3	3			3	
	Hardened steel	<	Н																	3	3			3	# Interrupted cutting

				Cer	met	Coa	ated								Coa	ted									Unco	ated	Cuttina (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330				NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115		H0-1	H05	fn (mm/rev)	ap (mm)
		DNMG	110404-VM		_			_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	0.05~0.30	0.90~4.00
			110408-VM							•			•														0.10~0.50	1.00~4.00
			110412-VM																								0.13~0.50	1.30~4.00
0			150404-VM	•									•						•	•							0.05~0.30	0.90~5.00
Medium cutting	VM		150408-VM	•	•						•		•						•	•							0.10~0.50	1.00~5.00
5 E			150412-VM										•						•	•							0.13~0.60	1.30~5.00
ğ			150604-VM	•	•					•	•		•						•	•				•			0.05~0.30	0.90~5.00
ž			150608-VM	•					•	•	•		•						•	•				•			0.10~0.50	1.00~5.00
			150612-VM										•						•	•							0.13~0.60	1.30~5.00
		DNMG	150404-B25		•			•	•				•														0.17~0.45	1.00~4.00
gu	B25		150408-B25		•			•	•				•														0.17~0.55	1.50~4.00
Medium to roughing			150412-B25					•	•				•														0.25~0.55	1.50~4.00
5			150604-B25						•		•		•														0.17~0.55	1.50~4.00
ᆵ			150608-B25						•		•		•														0.17~0.55	1.50~4.00
ā			150612-B25						•				•														0.25~0.55	1.50~4.00
<u>M</u>																												
		DNMG	150408-GR					•			•																0.20~0.50	1.00~7.00
	GR		150412-GR																								0.25~0.90	1.30~7.00
<sub>D</sub>	(1) (a) (b)		150416-GR																								0.30~0.75	1.80~7.00
g	-		150608-GR						•	•	•		•	•													0.20~0.50	1.00~7.00
Roughing			150612-GR						•		•																0.25~0.70	1.30~7.00
Ī			150616-GR										•														0.20~0.75	1.80~7.00
		DNMG	110404-VQ		•																						0.05~0.30	0.50~3.50
			110408-VQ																								0.08~0.40	0.80~4.00
			110412-VQ																_								0.10~0.40	1.00~4.00
	VQ		110508-VQ										•														0.08~0.40	0.80~4.00
guit	100		110512-VQ										•														0.10~0.40	1.00~4.00
nis	Carrie		150404-VQ	•	•																						0.05~0.30	0.80~3.50
Medium to finishing	[Cermet]		150408-VQ	•	•		•										_										0.08~0.40	0.80~4.00
E			150412-VQ 150604-VQ				•												_								0.10~0.40	0.50~4.20
Medi			150604-VQ 150608-VQ	•	-																						0.05~0.30	0.80~4.00
			150608-VQ 150612-VQ		_																						0.08~0.40	0.80~4.00
			130012-70																								0.10~0.40	0.30~4.20

**ᢒ** Cutting edge geometry **A37∼A49** 

→ Recommended chip breaker B04~B15


**ᢒ** Code system **B34~B35** 

	Available tool holders												
Designation	Page	Designation	Page										
MCKNR/L	B183	MCRNR/L	B184										
MCLNR/L	B183	PCBNR/L	B172										
MCMNN	B183	PCLNR/L	B173										



# B Turning Insert (Negative)





	Dimensions (mm)											
Size	d	t	d <sub>1</sub>									
11	9.525	3.18~4.76	3.81									
15	12.7	4.76~6.35	5.16									
19	19.05	6.35	7.93									

## Rhombic 55° Negative

	Steel	Р		#		\$	3	\$ #	#	#	•	•	\$	#									Machining types
8	Stainless steel	M						3	3	<b>3</b>			3	#	3	#		3	3	#			
cpie	Cast iron	K		#	•	\$ 3				<b>3</b>	\$	3									•	3	<ul> <li>Continuous cutting</li> </ul>
ork.	Non-ferrous metal	N																			•	3	General cutting
×	Heat resistant alloy, Titanium alloy	S								•			•	•	\$	#	•	3	3			3	# Interrupted cutting
	Hardened steel	Н															•	3	3			3	** Interrupted cutting

				Cer	met	Coa	ated								Coa	ted								Unco	oated	Cutting (	Condition
Inserts Designation																						2		Juliou			
	inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		DNMG	150404-MK												•											0.05~0.30	0.90~5.00
gu			150408-MK												•											0.10~0.50	1.00~5.00
ij	MK		150412-MK																							0.13~0.60	1.30~5.00
Ē	new		150604-MK											•	•											0.05~0.30	0.90~5.00
Medium cutting			150608-MK											•	•											0.10~0.50	1.00~5.00
Σ			150612-MK												•											0.13~0.60	1.30~5.00
		DNMA																								0.17~0.45	0.80~3.00
			150404																							0.17~0.55	0.40~4.00
			150408																							0.25~0.55	0.80~4.00
Roughing			150412												•											0.25~0.65	0.50~4.00
ugh			150604																							0.17~0.55	0.40~4.00
윤			150608												•											0.25~0.55	0.80~4.00
			150612												•											0.25~0.65	1.20~4.00
			190608																							0.30~0.80	2.50~13.00
	DV	DNMG	150408-RK																							0.15~0.50	1.50~5.00
Roughing	RK		150412-RK												•											0.20~0.60	1.80~5.00
and			150608-RK											•	•											0.15~0.50	1.50~5.00
8			150612-RK												•											0.20~0.60	1.80~5.00
		DNMG	150408-VR																							0.25~0.55	1.20~7.00
g	VR		150412-VR														_		_							0.30~0.60	1.50~7.00
ghir			150608-VR														_		_							0.25~0.55	1.20~7.00
Roughing			150612-VR												_											0.30~0.60	1.50~7.00
			100012 111																							0.00 0.00	1.00 1.00
		DNMG	110404-MM																				•			0.08~0.35	0.50~5.00
			110408-MM														•	•								0.10~0.40	0.50~5.00
			110412-MM																							0.12~0.45	0.50~5.00
			110504-MM																							0.08~0.35	0.50~5.00
			110508-MM																							0.10~0.40	0.50~5.00
g	MM		110512-MM																							0.12~0.45	0.50~5.00
闄	new		150404-MM														•	• (				•				0.10~0.40	0.50~6.40
Medium cutting			150408-MM													•	•	•	•			•	•			0.12~0.45	0.50~6.40
ediu			150412-MM													•	•	•	•							0.15~0.60	0.50~6.40
Ξ			150416-MM																							0.15~0.60	0.50~6.00
			150604-MM														•	•	•			•	•			0.10~0.40	0.50~6.40
			150608-MM													•	•	•	•			•	•			0.12~0.45	0.50~6.40
			150612-MM													•	•	•	•			•	•			0.15~0.60	0.50~6.40
			150616-MM																							0.18~0.65	0.50~8.00

Outting edge geometry A37~A49

<sup>• :</sup> Stock item


	Available tool holders													
Designation	Page	Designation	Page											
MCKNR/L	B183	MCRNR/L	B184											
MCLNR/L	B183	PCBNR/L	B172											
MCMNN	B183	PCLNR/L	B173											

Recommended chip breaker B04~B15

**ᢒ** Code system **B34~B35** 







	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
15	12.7	4.76~6.35	5.16

## Rhombic 55° Negative

	Steel	Р	•	#		3		3	\$ #	#	#	•	•	<b>\$</b>		#									Machining types
ဗ္ဗ	Stainless steel	M							3	3	3				3	#	3	#		3	3	#			
bje.	Cast iron	K	•	#	•	3	3				\$	3	3											3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N																						3	General cutting
Š	Heat resistant alloy, Titanium alloy	S									•				•	•	3	#	•	3	\$			3	# Interrupted cutting
	Hardened steel	Н																	•	\$	\$		•	3	Thire in upled culling

				Cer	met										Coa										Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		DNMG	150404-RM	0	0	0	0	Z	_	z	Z	z		Z	Z	Z	2	2	•				•	<u>п</u>	I		0.10~0.50	2.00~6.00
			150408-RM													•	•	•	•				•				0.15~0.55	2.00~6.00
			150412-RM														Ť		•				•				0.20~0.60	2.00~6.00
Б	RM		150416-RM																_								0.25~0.70	2.00~6.00
Roughing	new		150604-RM														•	•	•				•	•			0.10~0.50	2.00~6.00
Bou			150608-RM													•	•	•				•		•			0.15~0.55	2.00~6.00
			150612-RM													•	•	•									0.20~0.60	2.00~6.00
			150616-RM																								0.25~0.70	2.00~6.00
		DNMG	150404-VP1																		•	•	•		•		0.05~0.15	0.10~1.50
jg	VP1		150408-VP1																		•	•	•		•		0.07~0.20	0.10~1.50
Finishing			150604-VP1																		•	•	•		•		0.05~0.15	0.10~1.50
Hini			150608-VP1																		•	•	•		•		0.07~0.20	0.10~1.50
		DNGG	150404-VP1																								0.05~0.15	0.10~1.50
<u>S</u>	VP1		150408-VP1																								0.07~0.20	0.10~1.50
Finishing			150604-VP1																								0.05~0.15	0.10~1.50
Fini			150608-VP1																								0.07~0.20	0.10~1.50
<b>D</b>		DNMG	150404-VP2																•	•	•	•	•		•		0.05~0.30	0.10~3.00
shin	\/D0		150408-VP2																•	•	•	•	•		•		0.10~0.40	0.50~4.50
fil	VP2		150604-VP2																•	•	•	•	•		•		0.05~0.30	0.10~3.00
Medium to finishing			150608-VP2						•										•	•	•	•	•		•		0.10~0.40	0.50~4.50
Medi																												
		DNMG	150404-VP3																•	•		•	•		•	•	0.05~0.30	0.10~3.00
ng			150408-VP3																•				•			•	0.10~0.45	0.50~5.00
ishi	VP3		150412-VP3																•	•	•	•	•		•		0.12~0.50	0.50~5.00
o fin	110		150604-VP3																•	•	•	•	•			•	0.05~0.30	0.10~3.00
Ē			150608-VP3																•	•	•	•	•		•	•	0.10~0.45	0.50~5.00
Medium to finishing			150612-VP3																•		•		•		•	•	0.12~0.50	0.50~5.00
																					-		_		_			
		DNGG	150404-VP3																		•	•	•		•		0.05~0.30	0.10~3.00
g			150408-VP3																				•		•		0.10~0.45	0.50~5.00
Medium cutting	VP3		150412-VP3																				•				0.12~0.50	0.50~5.00
E			150604-VP3																			-	•		•		0.05~0.30	0.10~3.00
ediu			150608-VP3																		•		•		•		0.10~0.45	0.50~5.00
Š	-		150612-VP3																								0.12~0.50	0.50~5.00


→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

€ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173

## **3** Turning Insert (Negative)





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
15	12.7	4.76~6.35	5.16

## Rhombic 55° Negative

	Steel	Р		#		3		3	#	#	#	•	3		#										Machining types
පු	Stainless steel	M							3	3	3			3	#	3	#		3	3	3	#			
pie	Cast iron	K		#	•	\$	3				3	3											•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N																					•	3	General cutting
- 8 ∣	Heat resistant alloy, Titanium alloy	S												•	•	3	#	•	3	3	3		•	3	# Interrupted cutting
	Hardened steel	Н																•	3	3				3	- Interrupted cutting

	Harder	ned steel	н																		3	Ŧ				Ŧ		
				Cer	met	Coa	ated							С	oate	d									Unco	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC8120	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		DNMG	150408-VP4																								0.15~0.35	1.00~4.00
g	VP4		150412-VP4																								0.20~0.40	1.00~4.00
Roughing	new		150608-VP4																			•	•				0.15~0.35	1.00~4.00
8			150612-VP4																			•	•				0.20~0.40	1.00~4.00
	Sec. of Sec.	DNIMC	150404-HA																					•	•		0.05~0.30	0.80~3.50
ilig		DINING	150404-HA										-										-				0.10~0.40	0.80~3.50
iji	HA		150604-HA										-								•		-				0.10~0.40	0.80~3.50
E E	000		150604-HA																_		_		_		•		0.10~0.40	0.80~3.50
Medium to finishing	1		150000-ПА																								0.10~0.40	0.60~3.30
		DNMG	150404-VW																								0.10~0.35	0.30~3.00
	vw		150408-VW																								0.10~0.40	0.30~3.00
hing,	VVV		150604-VW																								0.10~0.35	0.30~3.00
Finishing			150608-VW																								0.10~0.40	0.30~3.00
	[Wiper]																											
		DNMG	150408-LW																								0.15~0.50	0.70~4.50
<u>.</u>	LW		150412-LW																								0.20~0.60	1.00~5.00
Ħ	LVV		150608-LW					•	•														П				0.15~0.50	0.70~4.50
Medium cutting			150612-LW					•	•														П				0.20~0.60	1.00~5.00
Mec	[Wiper]																											
		DNMX	150404R-SR																								0.10~0.40	0.70~4.50
			150408R-SR																				П				0.12~0.45	1.00~4.50
guir	SR _		150604R-SR																								0.10~0.40	0.70~4.50
Medium to finishing	SK new		150608R-SR																								0.12~0.45	1.00~4.50
tof			150404L-SR																								0.10~0.40	0.70~4.50
<u>=</u>			150408L-SR																								0.12~0.45	1.00~4.50
Med	[Shaft]		150604L-SR																								0.10~0.40	0.70~4.50
			150608L-SR																								0.12~0.45	1.00~4.50
		DNMX	150404R-SH																								0.15~0.30	1.00~4.00
			150408R-SH																				4				0.15~0.50	1.50~5.00
	611		150604R-SH																				_				0.15~0.30	1.00~4.00
Medium cutting	SH		150608R-SH																				_				0.15~0.50	1.50~5.00
2 E			150404L-SH																		_		4				0.15~0.30	1.00~4.00
diu	100		150408L-SH																		4		4				0.15~0.50	1.50~5.00
₩	[Wiper]		150604L-SH					•													_		_				0.15~0.30	1.00~4.00
			150608L-SH																				4				0.15~0.50	1.50~5.00
																											1	

Cutting edge geometry A37~A49




	Available	tool holders	
Designation	Page	Designation	Page
MCKNR/L	B183	MCRNR/L	B184
MCLNR/L	B183	PCBNR/L	B172
MCMNN	B183	PCLNR/L	B173

<sup>€</sup> Code system B34~B35

<sup>• :</sup> Stock item







	Dimensions (	mm)
Size	d	t
16	9.525	4.76

### Parallelogram 55° Negative

	Steel		Р		#		3		3	3	#	#	#	•	•	3		#								Machining types
ల్ర	Stainless steel		M								3	3	3				3	#	3	#	•	3	3	#		3 7/70
pie	Cast iron		K	•	#	•	3	3					3	\$	3										• 3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	•	N																						• \$	General cutting
×	Heat resistant alloy, Titanium alloy		S										•				•		\$	#	•	3	3		• \$	# Interrupted cutting
	Hardened steel		Н																		•	3	\$		• \$	- interrupted cutting

				Cei	rmet	Coa	ated								Coa	ited									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
5	11	KNUX	160405R-11						•	•	•		•														0.20~0.35	1.00~6.00
1			160410R-11					•	•		•		•														0.30~0.60	1.50~6.00
Medium cutting	The		160405L-11						•	•	•		•														0.20~0.35	1.00~6.00
Š			160410L-11						•		•		•														0.30~0.60	1.50~6.00
-	12	KNUX	160405R-12					•	•		•		•														0.25~0.35	1.50~6.00
<u> </u>	12		160410R-12						•		•		•														0.40~0.70	1.50~6.00
Roughing			160405L-12																								0.25~0.35	1.50~6.00
Œ			160410L-12								•																0.40~0.70	1.50~6.00

Cutting edge geometry A37~A49

€ Code system B34~B35

• : Stock item

	Available	tool holders	
Designation	Page	Designation	Page
CKJNR/L	B181	CKUNR/L	B212
CKNNR/L	B181		







	Dimens	ions (mm)	
Size	d	t	d₁
09	9.525	3.18	3.81
12	12.7	4.76	5.16
15	15.875	6.35	6.35
19	19.05	6.35	7.93
25	25.4	6.35~9.52	9.12
31	31 75	0.52	12.7


## O Round **Negative**

	Steel		Р		#	3		3	3	#	#	#	•		3		#			П						Machining types
8	Stainless steel		M							\$	3	3				3	#	3	#	•	3	3	#			- masiming types
pie	Cast iron	-	K		#	3	3					\$	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	4	N																					•	3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>—</b>	S									•					•	3	*	•	3	3		•	3	
_	Hardened steel	_	Н																	•	3	3		•	3	# Interrupted cutting

			Cei	rmet	Coa	ated								Coa	ted									Unco	ated	Cutting (	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H0.1	H05	fn (mm/rev)	ap (mm)
		<b>RNMG</b> 090300-B25																								0.90~4.50	0.09~0.90
	<b>B25</b>	120400-B25								•																1.20~4.80	0.12~1.20
छ	<b>D</b> 20	150600-B25								•																1.15~1.50	1.50~7.50
General		190600-B25																								1.90~7.60	0.19~1.90
ඊ		250600-B25																								2.50~10.0	0.25~2.50
		250900-B25								•																2.50~10.0	0.25~2.50
		310900-B25																								3.50~13.0	0.30~2.50

→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

**③** Code system B34∼B35



	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	4.76	5.16

## Square 90° Negative

	Steel	Р	•	#		\$	3	•	\$	#	#	#	•	•		#							Machining types
ဗ္ဗ	Stainless steel	M								<b>3</b>	3	3			3	#	•	3	3	#			
pie	Cast iron	K		#	•	\$ 3		\$				3	\$	3							•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N																			•	3	General cutting
×	Heat resistant alloy, Titanium alloy	S														•	•	3	3		•	3	# Interrupted cutting
	Hardened steel	Н															•	3	3			3	* interrupted cutting

	Harden	ned steel	Н														_		_		•	3	3		•	3	+ interrup	tou cutting
				Cer		Coa										oate										coated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215P	NC3225P	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
	VB	SNMG	120404-VB				•			•	•																0.15~0.35	0.30~2.00
Finishing			120408-VB	•	•	•	•			•	•																0.15~0.40	0.50~2.00
		SNMG	090304-VF																								0.07~0.30	0.50~1.50
			090308-VF																								0.07~0.30	0.50~1.50
	VF		120404-VF																								0.07~0.30	0.50~1.50
Finishing			120408-VF												•												0.10~0.40	0.50~1.50
nisi			120412-VF																								0.20~0.50	0.50~1.50
nishing Finishing	VL LP		120408-VL 090308-LP 090408-LP 120404-LP							•	•				•							•					0.10~0.35 0.10~0.30 0.10~0.30 0.10~0.35	0.20~1.50 0.30~1.50 0.30~1.50 0.30~2.00
Medium to finishing		SNMG	120408-LP 120412-LP							•	•				•												0.10~0.40 0.13~0.45 0.08~0.30	0.50~2.50 0.80~3.00 0.40~3.00
		SIMING	090304-CP																								0.08~0.30	0.40~3.00
			090404-CP																								0.08~0.30	0.40~3.00
hin	CP		090408-CP														-		-								0.10~0.30	0.40~3.00
Medium to finishing	232/46		120404-CP					•	•																		0.10~0.35	0.50~3.50
n to	The state of the s		120408-CP					•	•																		0.12~0.35	0.50~3.50
diu			120412-CP					•	•																		0.13~0.35	0.80~3.50
		SNMC	120408-VC																								0.15.0.40	0.50, 0.50
Medium to finishing	VC	SHIVIG	120400-VC								•				•												0.15~0.40	0.50~3.50


Cutting edge geometry A37~A49

→ Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ol holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	3.18~4.76	5.16
15	15.875	4.76~6.35	6.35
19	19.05	4.76~6.35	7.93

## O Square 90° Negative

	Steel		Р		#	3	•	\$ \$	#	#	#	•	•	<b>\$</b>		#								Machining types
8	Stainless steel		M						<b>3</b>	3	3				3	#	3	#		3	3	#		
pie	Cast iron		K		#	3	3				3	\$	3										3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	•	N																				3	<b>♣</b> General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S													•	3	#		3	3			# Interrupted cutting
	Hardened steel		Н																•	3	\$		3	- interrupted cutting


						Coa									Coa										Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		SNMG	120404-HM																					•			0.15~0.42	0.60~4.20
,			120408-HM					•		•	•				•									•			0.10~0.50	1.00~5.00
į	HM		120412-HM					•																•			0.18~0.50	1.00~5.00
Medium cutting																												
		SNMG	090304-MP					•	•				•														0.10~0.40	0.40~3.80
			090308-MP						•				•														0.15~0.40	0.50~4.00
			090312-MP																								0.15~0.50	0.80~4.20
			090404-MP																								0.10~0.40	0.40~3.80
			090408-MP																								0.15~0.40	0.50~4.00
			090412-MP																								0.15~0.50	0.80~4.20
			120404-MP					•	•				•			•	•	•			_	•					0.10~0.40	0.40~4.00
2	MP <sub>2</sub>	new)	120408-MP					•	•				•			•	•	•			•	•					0.15~0.45	0.50~4.50
#			120412-MP					•	•				•			•	•	•						4			0.15~0.50	0.80~5.00
Medium cutting			120416-MP					•	•				•								_			_	_		0.18~0.60	0.80~7.00
Į.	Y		150608-MP																		_				_		0.15~0.50	0.50~7.00
_			150612-MP																_		_			4	_		0.18~0.60	0.80~8.50
			190608-MP																								0.15~0.50	0.50~8.50
			190612-MP																								0.18~0.60	0.80~8.50
		SNMG	090304-VM																								0.05~0.30	0.90~3.50
			090308-VM																								0.10~0.50	1.00~3.50
			120404-VM	•									•						•	•							0.05~0.30	0.90~5.00
			120408-VM							•	•		•						•			•		•			0.10~0.50	1.00~5.00
			120412-VM										•						•								0.13~0.60	1.30~5.00
i i	VM		190612-VM																								0.25~0.60	2.50~7.50
į			190616-VM																								0.25~0.60	2.50~7.50
Saith 2 milled																												

→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177

## SNO



	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	3.18~4.76	5.16
15	15.875	4.76~6.35	6.35
19	19.05	6.35	7.93
25	25.4	7.94~9.52	9.12

## Square 90° Negative

	Steel		Р		#	3		3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							\$	3	3				3	#	3	#	•	1	3	#		
pie	Cast iron	4	K		#	3	3					3	3	3											<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S															3	#	•	3	3		3	# Interrupted cutting
	Hardened steel		Н																	•	3	3		3	* Interrupted cutting

_																												
					met										Coat										Unc	ated	Cutting (	Condition
	Inserts	Desig	ınation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		SNMG 09	90308-B25																								0.17~0.45	0.80~3.50
		12	20404-B25	•							•																0.17~0.45	1.00~3.50
		12	20408-B25																					•			0.23~0.60	1.50~5.00
		12	20412-B25						•		•																0.25~0.60	2.00~5.00
		12	20416-B25						•		•		•														0.35~0.70	2.50~5.00
		12	20420-B25																								0.40~0.70	3.00~5.00
<u>B</u>	B25	15	50608-B25																								0.25~0.60	1.50~6.00
ig		15	50612-B25																								0.25~0.60	2.00~6.00
ē		15	50616-B25						•																		0.35~0.70	2.00~6.00
<u>ء</u>		19	90608-B25																								0.25~0.60	3.00~8.00
Medium to roughing		19	90612-B25						•		•																0.30~0.60	3.00~8.00
ž		19	90616-B25						•		•											•					0.35~0.70	3.00~8.00
		25	50716-B25																								0.35~0.70	4.00~12.00
		25	50724-B25																								0.50 ~1.00	5.00~12.00
		25	50924-B25																								0.50~1.00	5.00~12.00
Roughing	GR	12 15 15 19 19 19 25	20404-GR 20408-GR 20412-GR 50608-GR 50612-GR 90612-GR 90612-GR 90624-GR 50724-GR					•	•	•	•		•	•	•												0.45~1.20	0.08~6.00 1.00~7.00 1.00~7.00 1.00~7.00 1.40~7.00 1.70~9.00 1.70~9.00 1.90~12.30 2.00~12.50 2.60~14.00
Medium to finishing	VQ [Cermet]	09 09 12	90304-VQ 90408-VQ 90412-VQ 20404-VQ 20408-VQ	•	•								•														0.05~0.30 0.08~0.30 0.10~0.30 0.05~0.30 0.08~0.40	0.50~3.50 0.80~4.00 1.00~4.00 0.80~4.00 0.80~4.00


Cutting edge geometry A37~A49

<sup>•:</sup> Stock item

		Available to	ol holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177

<sup>€</sup> Code system B34~B35





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	3.18~4.76	5.16
15	15.875	4.76~6.35	6.35
19	19.05	4.76~6.35	7.93
25	25.4	6.35~9.52	9.12

## O Square 90° Negative

	Steel		Р		#	3		3	3	#	#	#	•		3		#									Machining types
စ္မ	Stainless steel		M							3	3	3				3	#	3	*	•	3	3	#			
bje	Cast iron	4	K		#	3	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	•	N																					•	3	<b>♣</b> General cutting
ĕ∣	Heat resistant alloy, Titanium alloy	<b>-</b>	S														•	\$	#	•	3	3		•	3	# Interrupted cutting
	Hardened steel	_ <	Н																		3	3			3	- interrupted cutting


					Cer	rme	Coa	ated								Coa	ited									Unco	nated	Cutting (	Condition
		lassata		-1						22	0	0	22	00				22	22	0	0	2	0	2	0	JIICC	Juicu		
		Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
			SNGG	090304R																								0.12~0.35	1.00~3.00
				090308R																								0.15~0.35	1.00~3.00
				120404R																								0.15~0.35	1.00~4.00
	g			120408R																								0.15~0.35	1.00~4.00
ŀ	Medium cutting			120412R																								0.15~0.35	1.00~4.00
	<u> </u>			090304L																								0.12~0.35	1.00~3.00
:	ᇙ			090308L																								0.15~0.35	1.00~3.00
ı	Š			120404L																								0.15~0.35	1.00~4.00
				120408L																								0.15~0.35	1.00~4.00
				120412L																								0.15~0.35	1.00~4.00
			SNMG	090308-MK																								0.17~0.45	0.80~3.50
				120404-MK																								0.08~0.45	0.80~4.00
				120408-MK												•												0.10~0.50	1.00~5.00
	_	8417		120412-MK												•				_								0.13~0.60	1.30~5.00
	֓֞֟֟֟֝֟֝֟֝֟֝֟֝	MK		120416-MK																								0.15~0.63	1.50~6.00
	릴	new		150608-MK																								0.25~0.60	1.80~6.00
	Medium cutting			150612-MK																								0.20~0.70	1.80~7.00
:	ĕ ≅			150616-MK																								0.23~0.70	2.00~7.50
				190608-MK																								0.31~0.75	2.30~9.50
				190612-MK												•												0.33~0.78	2.50~10.00
				190616-MK																								0.35~0.78	2.70~10.00
			SNMA	090304		_																						0.10~0.45	0.50~4.50
			SINIMA	090304																								0.10~0.43	0.50~4.50
				090308																								0.15~0.50	0.50~4.50
				120402																								0.10~0.50	1.00~4.50
				120402																								0.15~0.60	1.00~4.50
				120408												•		_		-								0.15~0.00	1.00~5.00
				120412												•												0.20~0.80	1.50~6.00
				120416												•		-		-								0.30~1.00	2.00~6.00
	Roughing			120420														-		-								0.30~0.70	2.50~5.00
•	g			150612																								0.20~0.80	2.00~8.00
4	운			150616												•												0.25~0.85	2.50~10.00
		•		190608														_		-								0.20~0.80	2.00~10.00
				190612												•												0.20~0.80	2.00~10.00
				190616											•	•												0.25~0.85	2.50~10.00
				190624																								0.25~0.00	3.00~10.00
				250724																								0.40~1.00	3.00~10.00
				250724																								0.40~1.00	3.00~13.00
				200327																								0.40~1.00	0.00~10.00

Cutting edge geometry A37~A49

Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177



	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.81
12	12.7	4.76	5.16
15	15.875	6.35	6.35
19	19.05	6.35	7.93
25	25.4	7.94	9.12

## Square 90° Negative

	Steel		Р		#	3		3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							\$	3	3				3	#	3	#	•	1	3	#		
pie	Cast iron	4	K		#	3	3					3	3	3											<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S															3	#	•	3	3		3	# Interrupted cutting
	Hardened steel		Н																	•	3	3		3	* Interrupted cutting


				Co	met	Coa	ated								Coat	hed								Uncoated	Cutting	Condition
								2	ιΩ	0	0	ιΩ	0				וט ו	o c		טו	0	2	0			
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	DC5300	PC5400	PC8105	PC8110	PC811	PC9030	H01	fn (mm/rev)	ap (mm)
		SNGA	090304																						0.17~0.50	0.50~4.50
			090308																						0.17~0.50	0.50~4.50
			120404																						0.15~0.60	1.50~8.00
<u>6</u>			120408																						0.15~0.60	1.50~8.00
ghir			120412																						0.20~0.80	1.50~8.00
Roughing			150608												_											2.00~10.00
			150616																							2.00~10.00
			190608																							3.00~12.00
			190612																						0.20~0.80	3.00~12.00
		SNMG	120404-RK																						0.15~0.50	1.20~6.00
			120408-RK												•										0.23~0.53	1.50~6.00
	RK		120412-RK												•										0.28~0.53	1.80~6.00
ing	new		120416-RK												•										0.28~0.53	2.00~6.00
Roughing			150612-RK																						0.20~0.70	1.80~7.00
윤			150616-RK																						0.23~0.70	
			190612-RK																							2.50~10.00
			190616-RK																						0.35~0.78	2.70~10.00
	\/D	SNMG	120408-VR																						0.25~0.55	1.20~7.00
ō	VR		120412-VR																						0.30~0.60	1.50~7.00
Roughing			120416-VR																						0.35~0.60	2.00~7.00
jnog			190612-VR					•	•																0.35~0.70	2.00~10.00
			190616-VR						•																0.35~0.75	2.20~10.00
		SNMG	090304-MM																						0.08~0.35	0.50~5.00
			090308-MM																						0.10~0.40	0.50~5.00
			090312-MM																						0.12~0.45	0.50~5.00
			090404-MM																						0.08~0.35	0.50~5.00
			090408-MM																						0.10~0.40	0.50~5.00
_	ММ		120404-MM													•	•					•	•		0.10~0.40	0.50~6.40
Medium cutting	new		120408-MM													•	•				•	•	•		0.12~0.45	0.50~6.40
חטר			120412-MM														• (					•	•		0.15~0.60	0.50~6.40
diu	The state of the s		120416-MM																						0.18~0.65	0.50~6.40
Me			150608-MM																						0.12~0.45	0.50~8.00
			150612-MM														•					•	•		0.15~0.60	0.50~8.00
			150616-MM														• (					,_			0.18~0.65	0.50~8.00
			190608-MM														• (					•			0.12~0.45	0.50~9.50
			190612-MM														• (					•	•		0.15~0.60	0.50~9.50
			190616-MM														• (						•		0.18~0.65	0.50~9.50
			250924-MM																						0.20~0.80	1.00~10.00

→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

→ Code system B34~B35

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177





	Dimensi	ions (mm)	
Size	d	t	d <sub>1</sub>
12	12.7	4.76	5.16
15	15.875	6.35	6.35
16	9.525	3.18~4.76	3.81
19	19.05	6.35	7.93
25	25.4	7.94	9.12

## O Square 90° Negative


	Steel		Р		#	3		3	3	#	#	#	•	\$	#									Machining types
8	Stainless steel		M							3	3	3		3	#	3	#		3	3	3	#		
pje.	Cast iron	4	K		#	\$	3					3	3										3	<ul> <li>Continuous cutting</li> </ul>
Ž	Non-ferrous metal		N																				3	General cutting
×	Heat resistant alloy, Titanium alloy		S									•		•		3	#		3	3	3		3	-
	Hardened steel		Н															•	3	\$			3	# Interrupted cutting

				Cei	rmet	Coa	ated							C	oate	ed									Unc	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500		CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC8120	PC9030	된	H05	fn (mm/rev)	ap (mm)
		SNMG	120404-RM												•	•	•	•				•					0.10~0.50	2.00~6.00
			120408-RM												•		•				•						0.15~0.55	2.00~6.00
			120412-RM														•										0.20~0.60	2.00~6.00
			120416-RM																								0.25~0.70	2.00~6.00
	RM		150608-RM																								0.20~0.60	0.20~6.00
ing	new		150612-RM														•										0.20~0.60	2.00~8.00
Roughing	de la		150616-RM																								0.25~0.70	2.00~8.00
윤	V		190608-RM														•										0.20~0.60	2.00~10.00
			190612-RM														•										0.20~0.60	2.00~10.00
			190616-RM														•										0.27~0.70	2.00~10.00
			190624-RM																								0.30~0.75	3.00~10.00
			250924-RM																								0.40~1.20	4.00~14.00
<u>ii</u>	VP2	SNMG	120404-VP2																•	•	•	•			•		0.05~0.35	0.10~3.00
inish			120408-VP2						•										•	•	•	•			•		0.10~0.45	0.50~4.50
ntofi			120412-VP2															•	•	•	•	•			•		0.10~0.50	0.50~5.00
Medium to finishing																												
_		SNMG	120404-VP3																							•	0.05~0.30	0.10~3.00
		SINING	120404-VP3 120408-VP3														-				-	-				•	0.05~0.30	1.00~5.00
			120400-VP3																							•	0.10~0.43	1.00~5.00
			120412-VP3																_		_						0.12~0.30	0.50~4.00
i E	VP3		160608-VP3														-				-		_				0.15~0.35	0.80~6.00
Medium cutting			160612-VP3														-				-					-	0.20~0.40	1.00~6.00
Ē	-		160616-VP3																								0.20~0.40	1.00~6.00
Mec			190608-VP3																								0.20~0.40	0.80~7.00
			190612-VP3																								0.20~0.40	1.00~7.00
			190616-VP3																								0.25~0.45	1.00~7.00
																											0.20 0.40	1.00-7.00
	VP3	SNGG	120404-VP3																		•				•		0.05~0.30	0.10~3.00
Ę	VP3		120408-VP3																	•	•	•			•		0.10~0.45	1.00~5.00
200			120412-VP3																	•	•	•					0.12~0.50	1.00~5.00
Medium cutting	-		120112 11 0																								0.12 0.00	1.00 0.00
₹																												
		SNMG	120408-VP4														П					•	•				0.15~0.35	1.00~4.00
	VP4	3	120412-VP4																			•	•				0.20~0.40	1.00~4.00
<u> </u>	new		150612-VP4																			•	•				0.20~0.45	1.00~5.00
Roughing			190608-VP4																			•					0.20~0.50	1.00~9.00
Bou			190612-VP4																			•	•				0.23~0.55	1.00~9.00
			190616-VP4																				•				0.27~0.60	1.00~9.00
																							_				5.2. 0.00	1.00 0.00
		1		1																							1	

**→** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177



	Dimens	sions (mm)	
Size	d	t	d₁
09	9.525	3.18	3.81
12	12.7	4.76	5.16
15	15.875	6.35	6.35
19	19.05	6.35	7.93
25	25.4	7.94~9.52	9 12

## Square 90° Negative

	Steel		Р		#	3		3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							\$	3	3				3	#	3	#	•	1	3	#		
pie	Cast iron	4	K		#	3	3					3	3	3											<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S															3	#	•	3	3		3	# Interrupted cutting
	Hardened steel		Н																	•	3	3		3	* Interrupted cutting


				Cer	met	Coa	ated								Coa	ted									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500		225	120	030	235	330	310			125	135	300	400	105	9	PC8115	030			fn	ар
				SN	CN2	50	CCS	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	8	PC9(	亨	H05	(mm/rev)	(mm)
<u>S</u>		SNMG	120404-HA					_																•	•	_	0.10~0.35	0.80~3.50
shir	HA		120408-HA																					•	•		0.10~0.40	0.80~3.50
量	100		120412-HA																								0.13~0.55	0.80~3.50
Medium to finishing																												
		SNGN																									0.05~0.30	0.50~4.00
			090304																								0.10~0.35	0.50~4.00
			090308																								0.10~0.40	1.00~4.00
			120304																								0.13~0.50	1.30~5.00
			120308																								0.15~0.60	1.50~6.00
			120312																								0.17~0.60	1.70~6.00
			120402																								0.10~0.45	1.00~5.00
			120404																								0.13~0.50	1.30~5.00
			120408																								0.15~0.60	1.50~6.00
g			120412																								0.17~0.60	1.70~6.00
Roughing			120424																								0.20~0.65	2.00~6.00
S			150402																_								0.10~0.50	0.50~6.00
			150408																								0.15~0.60	1.50~8.00
			150412																								0.17~0.60	2.00~8.00
			150416																								0.20~0.65	2.50~8.50
			190402																_								0.10~0.60	2.00~8.50
			190412																_									2.50~10.00
			190416																									2.50~10.00
			250604 250616																_								0.30~0.80	3.00~12.00 4.00~12.00
		CMIIM	120408																								0.23~0.60	1.50~5.00
5		314014	120406																_								0.25~0.60	2.00~5.00
į			190412																								0.30~1.00	
ono.			120412TN																								0.25~0.60	2.00~5.00
후			250724TN																									3.00~12.00
Medium to roughing			200121111																								0.00 1.120	0.00 12.00
	_	SNMX	120408R																								0.15~0.35	1.00~4.00
Medium cutting	0																											

ullet : Stock item

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177

② Cutting edge geometry A37~A49
③ Recommended chip breaker B04~B15
③ Code system B34~B35





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
12	12.7	4.76	5.16
15	15.875	6.35	6.35
19	19.05	6.35	7.93
25	25.4	7.94~9.52	9.12

## O Square 90° Negative

	Steel		Р		#	3		\$ 3	#	#	#	•		3		#									Machining types
8	Stainless steel		M						3	3	3				3	#	3	#		3	3	#		_	
bje	Cast iron	4	K		#	3	3				\$	\$	3										0 1		<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	•	N																				• 1		General cutting
ĕ∣	Heat resistant alloy, Titanium alloy	<b>-</b>	S								•				•	•	\$	#	•	3	3		• 1		- 0
	Hardened steel		Н																	3	\$		• 1		# Interrupted cutting


		T Steel																			_							
							ated								Coa										Unco	ated	Cutting (	Condition
	Inserts		esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		SNGX	120408R																								0.15~0.35	1.00~4.00
Medium cutting	0																											
	CD	SNMM	120408-GR																								0.20~0.50	1.00~7.00
5	GR		120412-GR								•																0.25~0.65	1.30~7.00
Roughing	550		190612-GR								•																0.25~0.65	1.30~11.50
onog			190616-GR																								0.32~0.85	1.80~11.50
		SNMM	120408-GH								•		•														0.30~0.60	2.50~8.00
			120412-GH						•		•																0.30~0.70	2.50~8.00
			150612-GH								•																0.30~0.70	2.50~8.00
	GH		190612-GH					•			•		•														0.30~0.70	3.00~8.00
>	Su		190616-GH					•		•	•		•														0.45~1.00	4.00~9.00
Heavy			190624-GH					•			•		•														0.55~1.20	4.00~9.00
	1000		250724-GH					•		•	•		•														0.55~1.20	
			250924-GH								•																0.55~1.20	5.00~12.00
		CNINANA	100010 1/11																								0.50.000	500 40 00
		2MININ	190612-VH					•							_		_											5.00~10.00
			190616-VH 190624-VH					•							-													5.00~10.00 6.00~12.00
	VH		250716-VH												-													6.00~12.00
Heavy			250710-VII					•			•																	6.00~14.00
운			250920-VH								_				-		-											6.00~15.00
			250924-VH					•							-													6.00~15.00
	[General]																											
		SNMM	190612-VT					•					•															6.00~13.00
			190616-VT					•			•																	6.00~13.00
			190624-VT					•																				7.00~13.00
	VT		250716-VT					_																				7.00~15.00
Heavy			250724-VT					•			•				_													7.00~15.00
ヹ			250920-VT												_													7.00~15.00
			250924-VT								•																0.75~1.60	7.00~17.00
	[High feed cutting]																											

€ Cutting edge geometry A37~A49 € Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MSBNR/L	B185	MSRNR/L	B186	PSDNN	B175
MSDNN	B185	MSSNR/L	B187	PSKNR/L	B176
MSKNR/L	B186	PSBNR/L	B175	PSSNR/L	B177





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.40
16	9.525	3.18~4.76	3.81
22	12.7	4.76	5.16

	Steel	Р		#		3		<b>\$</b>	•	\$ 3	#	#	#	•	•	3		#						Machining types
ဗ္ပ	Stainless steel	M									3	3	3				3	#	•	3	3	#		
pie	Cast iron	K	•	#	•	\$	3		\$				\$	\$	3								• 3	<ul> <li>Continuous cutting</li> </ul>
, Y	Non-ferrous metal	N																					• 3	General cutting
×	Heat resistant alloy, Titanium alloy	S																	•	3	3		• 3	# Interrupted cutting
	Hardened steel	Н																	•	3	3		• 3	- Interrupted cutting

		Harden	ea steel	Н		-																	E 1	,		•	•		
					Ce	rmet	Coa	ated								C	oate	d								Unco	ated	Cutting (	Condition
		Inserts	D€	esignation	CN1500			CC2500	NC3215P	NC3225P	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC8105	PC8110	200	PC9030	H01	H05	fn (mm/rev)	ap (mm)
			TNMG	160404-VB	•	•	•	•			•	•																0.10~0.35	0.30~1.50
		VB		160408-VB	•	•	•	•			•	•				•												0.15~0.45	0.50~7.00
2	7	A		160412-VB							•	•																0.18~0.45	0.80~3.00
Finishina				220408-VB								•				•												0.15~0.45	0.50~2.50
i	1	200		220412-VB																								0.20~0.50	0.70~2.50
	ľ																												
			TNMG	160404-VL	•						•																	0.05~0.25	0.10~1.00
		VL		160408-VL	•						•	•				•												0.10~0.35	0.20~1.50
2	9	VL		160412-VL							•																	0.15~0.40	0.20~1.50
Finishina				220408-VL																								0.10~0.35	0.20~1.50
i ii		THE PLAN		220412-VL																								0.10~0.35	0.50~2.00
	Ľ																												
			TNMG	110304-VF	•	_							_			•							_	_				0.05~0.20	0.20~1.00
				160404-VF	•						_		•			•							•					0.07~0.30	0.50~1.50
		VF		160408-VF							•		•			•												0.10~0.40	0.50~1.50
Finishina		A		160412-VF																				4				0.15~0.50	0.50~1.50
2				220404-VF 220408-VF												•					_		_	_ '	•			0.10~0.40	0.50~1.50 0.50~1.50
			TNMG	110304-LP																				_				0.07~0.30	0.30~1.50
2	7			110308-LP							_																	0.10~0.30	0.30~1.50
nio.		LP		160404-LP							•	•				•		_		_		_				_		0.10~0.35	0.30~2.00
i e		A		160408-LP							•	•				•			_					_	_	_	_	0.10~0.40	0.50~2.50
Medium to finishing	İ			160412-LP								•																0.13~0.45	0.80~3.00
			TNMG	110304-CP																								0.08~0.26	0.40~2.50
				110308-CP																T		T						0.10~0.26	0.40~2.50
9	p			160404-CP					•	•										T		T						0.10~0.30	0.50~3.00
Medium to finishina		CP		160408-CP					•	•																		0.12~0.30	0.50~3.00
fi		new		160412-CP					•	•																		0.13~0.30	0.80~3.00
5		320 550		220408-CP					•	•																		0.15~0.35	0.80~4.00
į	1	EXXX		220412-CP					•	•												T						0.18~0.35	1.00~4.00
Me																													


Cutting edge geometry A37~A49

→ Recommended chip breaker B04~B15

€ Code system B34~B35

		Available too	ol holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.40
16	9.525	3.18~4.76	3.81
22	12.7	4.76	5.16
27	15.875	6.35	6.35

## 


	Steel		Р		#	3		3	\$ #	#	#	•	•			#									Machining types
8	Stainless steel		M						3	3	3			•	3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	3	3				3	\$	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	-	N																					3	General cutting
×	Heat resistant alloy, Titanium alloy		S								•				•	•	\$	#	•	3	3			3	- 0
	Hardened steel	4	Н																•	3	\$		•	3	# Interrupted cutting

				Cer	rmet	Coa	ated								Coa	ted								Ur	coat	ed	Cutting (	Condition
	Inserts	De	esignation						52	20	30	35	30				52	32	0 1	8	92	은 ;	0 6		Jul		fn	ар
			<b>3</b>	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8113	2 5		20	(mm/rev)	(mm)
		TNMG						•	•				•													-	0.10~0.35	0.30~2.00
<u>B</u>	7		160408-VC					•	•				•													_	0.15~4.00	0.50~3.00
ish	VC		160412-VC					•	•				•				_									_	0.15~4.50	0.50~3.00
i ii			220408-VC					•	•																	_	0.15~0.40	0.50~3.00
Medium to finishing	484		220412-VC					•	•																		0.15~0.45	0.50~3.00
Me																												
		TNMG	110308-HM							•																	0.17~0.40	1.50~3.00
			160404-HM						•		•								•								0.05~0.30	0.90~4.00
ē	НМ		160408-HM						•		•																0.10~0.50	1.00~4.00
闄	A		160412-HM																								0.13~0.60	1.30~4.00
Ē			220404-HM						•																		0.15~0.45	0.60~5.00
Medium cutting	2 2 2 2		220408-HM						•		•																0.18~0.48	0.80~5.80
2			440000 140																								0.45.0.40	0.50.0.50
		TNMG	110308-MP					•	•					_			_	_				_			_	-	0.15~0.42	0.50~3.50
			160404-MP					•	•				•	•		•	•				•	•		_		_	0.10~0.40	0.40~3.50
			160408-MP						•				•			-	•	_			•					_	0.15~0.45	0.50~4.00
			160412-MP 160416-MP						_							_	•				_		_			+	0.15~0.50 0.18~0.50	0.80~4.50 1.00~4.50
ii.	MP		220404-MP						•				•					_			-		_		-		0.10~0.35	0.40~5.00
150			220404-MP																		-				-	_	0.10~0.35	0.40~5.00
Medium cutting			220406-MP										•														0.15~0.45	0.80~6.00
Med			220412-MP					•					•										_		-		0.20~0.55	1.00~6.00
			270612-MP														-				-				_	_	0.28~0.60	1.20~8.00
			270012 1011																							+	0.20 0.00	1.20 0.00
		TNMG	110308-VM																								0.05~0.30	0.80~4.00
			160404-VM	•						•	•		•						•	•							0.05~0.30	0.90~5.00
			160408-VM	•	•			•	•	•	•		•						•	•							0.10~0.50	1.00~5.00
0	VM		160412-VM	•				•		•									•	•						_	0.13~0.60	1.30~5.00
Medium cutting	VIVI		220404-VM																•	•						_	0.05~0.30	0.90~6.60
S			220408-VM							•			•						•	•		•				_	0.10~0.50	1.00~6.60
i	All was		220412-VM																								0.13~0.60	1.30~6.60
Me			-																									

**②** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ol holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		



	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.40
16	9.525	4.76	3.81
22	12.7	4.76	5.16
27	15.875	6.35	6.35
33	19.05	9.52	7.93

	Steel		Р		#	3		<b>\$</b>	3	#	#	#	•		3		#									Machining types
8	Stainless steel		M							\$	3	3				3	#	\$	#	•	1	3	#			
pie	Cast iron	4	K		#	3	3					3	3	3											3	<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					•	3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S													•	•	3	#	•	3	3		•	3	-
	Hardened steel		Н																	•	3	\$			3	# Interrupted cutting


				Cor	met	Cos	ated								Coa	ted								Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330				NC9125	NC9135	00000		PC8110	C8115	PC9030		H05	fn (mm/rev)	ap (mm)
		TNMG	110308-B25	O	ပ	ပ	ပ	z	z	z	z	z	z	Z	z	Z	Z	2 0				_	_	エ	エ	0.17~0.40	1.50~3.00
		THUIS	160404-B25		•								•													0.17~0.40	2.00~3.50
			160408-B25	•	•				•		•		•							_			•			0.17~0.55	2.00~3.50
			160412-B25		•			•	•		Ť		•		_											0.25~0.55	2.00~3.50
			160416-B25		Ť				_				Ť													0.30~0.60	2.50~3.00
			220404-B25					•	•		•		•													0.17~0.45	1.50~5.00
hing	<b>D</b> 05		220408-B25					•	•		•		•													0.17~0.55	2.00~5.00
lgnc	B25		220412-B25					•	•		•		•													0.25~0.55	2.00~5.00
Q			220416-B25					•	•				•													0.30~0.60	2.00~5.00
Ę			220424-B25																							0.35~0.70	3.00~7.00
Medium to roughing			220432-B25																							0.40~0.75	3.50~7.00
≥			270608-B25								•															0.17~0.55	2.00~5.00
			270612-B25						•		•		•													0.25~0.55	3.00~7.00
			270616-B25																							0.30~0.60	3.00~7.00
			330716-B25						•																	0.35~0.70	3.00~9.00
			330924-B25																							0.40~0.80	3.00~9.00
		TNMG	160408-GR						•		•															0.20~0.50	1.00~7.00
			160412-GR						•																	0.23~0.54	1.20~8.00
			220408-GR						•		•		•													0.22~0.61	1.10~7.80
	GR		220412-GR						•	•	•															0.28~0.78	1.20~7.80
ing			220416-GR								•															0.31~0.75	1.50~7.80
Roughing			270608-GR								•															0.31~0.75	1.50~7.80
윤	4 - 11		270612-GR						•	•	•															0.31~0.75	1.50~7.80
			270616-GR								•															0.36~1.00	1.60~7.80
			330924-GR								•															0.40~1.00	2.00~9.00
		TNGG	160402R-SC																							0.03~0.20	0.10~1.50
	SC	11133	160404R-SC																							0.05~0.25	0.10~1.50
ing	A		160404H-SC												-		-		-							0.03~0.20	0.10~1.50
Finishing			160404L-SC												_											0.05~0.25	0.30~2.00
造			1004042 00																							0.03 -0.23	0.00*-2.00
		TNMG	110304-VQ																							0.05~0.30	0.50~3.00
guir	1/0		160404-VQ	•	•	•	•																			0.05~0.30	0.80~3.50
nish	VQ		160408-VQ	•	•	•	•																			0.08~0.40	0.80~3.50
to fii			160412-VQ		Ť		Ė																			0.10~0.40	0.80~3.50
Ē	A COL		220404-VQ																							0.05~0.35	0.80~4.00
Medium to finishing																											
Σ	[Cermet]																										

Cutting edge geometry A37~A49
 Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ool holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		





	Dimens	ions (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.40
16	9.525	3.18~4.76	3.81
22	12.7	4.76	5.16
27	15.875	6.35	6.35
33	19.05	9.52	7.93


	Steel		Р		#		\$		3	3	#	#	#	•	•	3		#								Machining types
ဗ္ပ	Stainless steel		M								3	3	3				3	#	3	#		3	3	#		, , , , , , , , , , , , , , , , , , ,
pie	Cast iron		K		#	•	3	3					\$	3	3										• 3	<ul><li>Continuous cutting</li></ul>
춪	Non-ferrous metal	•	N																						• 3	■ General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S															•	3	#	•	3	3		• 3	# Interrupted cutting
	Hardened steel	<b>-</b>	Н																		•	3	3		• 3	- interrupted cutting

					Cer	mei	Co	ated								Cos	ated									Unco	nated	Cutting (	Condition
		lassada	D-	!						22	0	2	22	0	0			22	22	0	0	D.	0	2	0	Onoc	Juliou		
		Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	192	fn (mm/rev)	ap (mm)
			TNGG	110304R																								0.05~0.30	0.50~2.50
				160402R																								0.08~0.30	0.50~3.50
				160404R	•																							0.12~0.30	1.00~3.50
				160408R																								0.15~0.35	1.30~3.50
				220404R																								0.12~0.30	1.00~5.00
	g			220408R																								0.15~0.35	1.30~5.00
	Medium cutting			220412R																								0.17~0.40	1.50~5.00
	<u> </u>			110304L																								0.05~0.30	0.50~2.50
•	ۊ			160402L																								0.08~0.30	0.50~3.50
	Ž			160404L	•																							0.12~0.30	1.00~3.50
				160408L																		_						0.15~0.35	1.30~3.50
				220404L																								0.12~0.30	1.00~5.00
				220408L																								0.15~0.35	1.30~5.00
				220412L																_		_						0.17~0.40	1.50~5.00
			TNMG	160404-MK											•													0.05, 0.20	0.90~3.50
			INIVIG													•												0.05~0.30	1.00~4.00
				160408-MK 160412-MK												•		-										0.10~0.50	1.20~4.50
	g l	MK _		160412-WK												_		_	_	-		-						0.12~0.60	1.20~4.50
ŀ	<u> </u>	new		220404-MK																								0.13~0.00	1.50~4.50
	Medium cutting			220408-MK																								0.21~0.50	1.30~5.50
1	ۊ	View V		220412-MK																								0.23~0.52	1.40~5.50
ŀ	2			220416-MK																		_						0.25~0.53	1.60~6.00
				270612-MK																		T						0.25~0.55	3.00~7.00
			TNMA	110308																								0.05~0.30	0.50~3.00
				160404											•	•												0.10~0.30	1.00~4.00
				160408											•	•												0.10~0.40	1.00~4.00
				160412												•												0.10~0.50	1.50~4.50
				160416												•												0.15~0.55	1.50~4.50
				220404																								0.10~0.35	1.00~4.00
	<u></u>			220408												•												0.15~0.40	1.50~5.00
:	틆			220412												•												0.20~0.50	1.50~5.00
	Roughing			220416												•												0.25~0.55	1.50~5.00
	"			220420																								0.30~0.65	2.00~5.00
				220432																								0.35~0.70	2.00~5.00
				270608																								0.20~0.45	2.00~7.00
				270612																								0.25~0.55	3.00~7.00
				270616																		_						0.30~0.65	3.00~7.00
				330924																								0.35~0.75	3.00~9.00

**→** Cutting edge geometry A37~A49 **→** Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ol holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		



	Dimens	ions (mm)	
Size	d	t	d₁
11	6.35	3.18	2.40
16	9.525	4.76	3.81
22	12.7	4.76	5.16
27	15.875	6.35	6.35

	Steel		Р		#		\$		3	3	#	#	#	•	•	3		#									Machining types
8	Stainless steel		M								3	3	3				3	#	3	*	•	3	3	#			
pie	Cast iron	4	K		#	•	3	3					\$	\$	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal		N																						•	3	General cutting
×	Heat resistant alloy, Titanium alloy		S														•	•	\$	#	•	3	3		•	3	-
	Hardened steel		Н																		•	3	3		•	3	# Interrupted cutting


						Coa								Coa										Uncoated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01 H05	fn (mm/rev)	ap (mm)
		TNGA	110302																						0.05~0.30	0.20~3.00
			110304																						0.05~0.30	0.40~3.00
			160304																						0.10~0.35	0.40~4.00
			160402																						0.10~0.30	0.20~4.00
			160404																						0.10~0.35	0.40~5.00
0			160408																						0.12~0.40	0.50~5.00
Roughing			220304																						0.10~0.35	0.50~5.00
inog			220402																						0.05~0.30	0.20~3.00
			220404																						0.10~0.35	0.40~5.00
			220408																						0.10~0.40	0.50~5.00
			220412																						0.12~0.45	1.00~5.50
			270612																						0.12~0.45	1.00~7.00
			270624																						0.20~0.55	2.00~7.00
													_													
		TNMG	160408-RK										•	•						_					0.23~0.53	1.50~5.00
	<b>D</b> 17		160412-RK										•	•											0.28~0.53	1.80~5.00
Б	RK		160416-RK				_							•											0.28~0.53	1.80~5.00
Roughing			220408-RK				_							•						_					0.23~0.53	1.50~6.00
2 S	100		220412-RK											•						_					0.28~0.53	1.80~6.00
			220416-RK											•											0.28~0.63	2.00~6.00
		TNMG	160404-VR																						0.20~0.50	0.80~7.00
			160408-VR																						0.25~0.55	1.20~7.00
	VR		160412-VR																						0.35~0.65	1.70~7.00
ing	<b>A</b>		160416-VR																						0.35~0.70	2.00~10.0
Roughing			220408-VR																						0.35~0.70	2.00~10.0
8			220412-VR																						0.35~0.70	2.00~10.0
			220416-VR																						0.35~0.75	2.20~10.0
		TNMG	160404-MM												•	•	•	•				•			0.10~0.40	0.50~4.80
			160408-MM												•	•	•	•				•			0.12~0.45	0.50~4.80
			160412-MM													•	•	•				(			0.18~0.65	0.50~4.80
ting	MM		160416-MM																						0.18~0.65	0.50~4.80
cut	new		220404-MM																						0.10~0.40	0.50~6.50
<u>E</u>	P		220408-MM													•	•	•			-	•			0.12~0.45	0.50~6.50
Medium cutting			220412-MM													•	•	•				•	D		0.15~0.60	0.50~6.50
			220416-MM																						0.18~0.65	0.50~6.50

Cutting edge geometry A37~A49
 Recommended chip breaker B04~B15

€ Code system B34~B35

		Available too	ol holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		





	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
16	9.525	4.76	3.81
22	12.7	4.76	5.16


	Steel		Р		#		3		3	\$ #	#	#	•	\$	#										Machining types
8	Stainless steel		M							3	3	3		3	#	3	#		3	3	3	#			3 7/1-1
pje	Cast iron		K		#	•	\$	3				3	\$										•	3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal		N																					3	General cutting
×	Heat resistant alloy, Titanium alloy		S									•		•	•	3	#		3	3	3			3	# Interrupted cutting
-	Hardened steel	4	Н															•	\$	3			•	3	- Interrupted cutting

					rmet										oate										Unco	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC8120	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		TNMG	160404-RM												•	•	•	•			•	•		•			0.10~0.50	2.00~5.50
			160408-RM												•	•	•	•			•	•		•			0.15~0.55	2.00~5.50
g	RM		160412-RM													•	•										0.20~0.60	2.00~5.50
Roughing	A		220408-RM													•	•	•				•					0.10~0.50	2.00~7.50
30.	HOL		220412-RM													•	•					•					0.15~0.55	2.00~7.50
			220416-RM																								0.25~0.70	2.00~7.50
		TNMG	160404-VP2															•	•	•	•	•			•		0.05~0.30	0.10~3.00
hing	VP2		160408-VP2															•	•	•	•	•			•		0.10~0.45	0.50~5.00
inisi			160412-VP2																•	•	•	•			•		0.13~0.55	0.80~3.30
to f			220404-VP2															•	•		•						0.05~0.30	0.80~5.00
Medium to finishing			220408-VP2															•	•		•						0.10~0.40	0.80~5.00
		TNMG	160404-VP3															•	•	•	•	•			•		0.05~0.30	0.10~3.00
			160408-VP3															•	•	•	•	•			•	•	0.10~0.45	0.50~5.00
ΒC	VP3		160412-VP3																								0.20~0.40	0.50~3.50
靊			220404-VP3																								0.20~0.30	0.80~4.00
Ē			220408-VP3																								0.25~0.35	0.80~5.00
Medium cutting			220412-VP3																								0.30~0.40	1.00~5.00
Σ			220416-VP3																								0.30~0.40	1.00~5.00
D D	VP3	TNGG	160404-VP3																	•	•	•			•		0.05~0.30	0.10~3.00
Medium cutting			160408-VP3																	•	•	•			•		0.10~0.45	0.50~5.00
	VP4	TNMG	160408-VP4																			•	•				0.15~0.35	1.00~4.00
ing	new		160412-VP4																			•	•				0.20~0.40	1.00~4.00
Roughing																												
		TNMG	160404-HA																		•			•	•		0.05~0.30	0.80~3.50
ning	на		160408-HA																		•			•	•		0.10~0.40	0.80~3.50
nish	ПА		160412-HA																								0.13~0.55	0.80~3.50
Medium to finishing			220408-HA																					•			0.10~0.40	0.80~5.30
Medi																												

**③** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ol holders		
Designation	Page	Designation	Page		
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		



	Dimens	sions (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.40
16	9.525	4.76	3.81
22	12.7	4.76	5.16
27	15.875	6.35	6.35

	Steel	Р		#	3		\$ 3	#	#	#	•	•	3		#								Machining types
8	Stainless steel	M						3	3	3				3	#	3	#	•	3	3	#		
pie	Cast iron	K		#	3	3				3	3	3										3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N																				3	General cutting
- 8 ∣	Heat resistant alloy, Titanium alloy	S								•				•	•	3	#	•	3	3		3	# Interrupted cutting
	Hardened steel	Н																•	3	\$		3	- Interrupted cutting

				Co	rmet	Coa	tod								Coa	tod									Unco	atod	Cutting	Condition
								2	2	0	0	2	0				2	2	0	0	2	0	2	0	UTICC	ated		Jonation
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
	VW	TNMG	160404-VW																								0.10~0.35	0.30~3.00
ing			160408-VW																								0.10~0.40	0.30~3.00
Finishing	[Wiper]																											
5	LW	TNMG	160408-LW																								0.15~0.50	0.70~4.50
튵	LVV		160412-LW																								0.20~0.60	1.00~5.00
Medium cutting	[Wiper]																											
		TNGN	110302																								0.05~0.25	0.20~2.50
			110304																								0.10~0.30	0.50~2.50
			110308																								0.10~0.30	0.80~2.50
			160302																								0.05~0.30	0.20~3.00
			160304																								0.10~0.30	0.50~4.00
			160308																								0.10~0.40	0.80~4.00
ing			160404						_																		0.10~0.40	0.50~4.00
Medium cutting			160408																_								0.10~0.40	1.00~4.00
E			160412						_										_								0.10~0.50	1.50~4.50
/edi			220404																								0.10~0.35	1.00~4.00
			220408						_										_								0.15~0.40	1.50~5.00
			220412						_										_								0.20~0.50	1.50~5.00
			220416																_								0.25~0.55	1.50~5.00
			220424						_																		0.30~0.65	2.00~5.00
			270630																								0.35~0.70	2.00~5.00
5		TNMX	160404R-SR																								0.10~0.35	0.70~3.50
shin	SR _		160408R-SR																_								0.12~0.40	1.00~3.50
Ē.	new		160404L-SR																_								0.10~0.35	0.70~3.50
ם			160408L-SR																								0.12~0.40	1.00~3.50
Medium to finishing	[Shaft]																											
		TNMX	160404R-SH					•	•																		0.15~0.30	0.50~4.00
<u>g</u>	SH		160408R-SH					•	•																		0.15~0.45	1.00~4.00
ŧ	3H		160404L-SH					•	•																		0.15~0.30	0.50~4.00
E			160408L-SH					•	•																		0.15~0.45	1.00~4.00
Medium cutting	[Shaft]																											


Outting edge geometry A37~A49

→ Recommended chip breaker B04~B15

€ Code system B34~B35

		Available too	ol holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		





	Dimens	sions (mm)	
Size	d	t	d₁
16	9.525	4.76	3.81
22	12.7	4.76	5.16
27	15.875	6.35	6.35
33	19.05	7.94~9.52	7.93

	Steel		Р		#		\$	3	\$ #	#	#	•	•	3		#									Machining types
8	Stainless steel		M						3	3	3				3	#	3	#		3	3	#			
pie	Cast iron		K		#	•	\$ 3				3	\$	3										•	3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	•	N																					3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S														3	#	•	3	3			3	# Interrupted cutting
	Hardened steel	<b>-</b>	Н																•	3	3		•	\$	- interrupted cutting

				Cer	met	Coa	ated								Coa	ited									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500				NC3215	NC3225	NC3120	NC3030	NC3235	NC5330				NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	C8115	C9030		H05	fn (mm/rev)	ap (mm)
		TNMX	160402R		•			_	_	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_		0.10~0.30	0.50~3.00
			160404R						•	•	•		•														0.12~0.30	1.00~3.50
			160408R						•	•	•																0.15~0.35	1.30~3.40
			220404R																								0.12~0.30	1.00~5.00
ס			220408R																								0.15~0.35	1.30~5.00
i			160404L						•	•	•																0.12~0.30	1.00~3.50
ono			160408L							•	•																0.15~0.35	1.30~3.40
Medium to roughing																												
		TNMM	220408-GR																								0.22~0.61	1.10~7.80
			220412-GR																								0.28~0.78	1.20~7.80
			220416-GR																								0.31~0.75	1.50~7.80
Roughing	GR																											
		TNMM	160408-GH																								0.20~0.50	1.00~7.00
			220408-GH																								0.25~0.60	1.30~7.00
			220412-GH						•																		0.20~0.50	1.00~8.00
			220416-GH																								0.25~0.60	1.30~8.00
			270616-GH																								0.32~0.70	1.80~8.00
	GH		270624-GH																								0.35~0.50	1.80~13.00
>			330924-GH																								0.35~0.70	2.30~13.00
Heavy																												


Cutting edge geometry A37~A49
 Recommended chip breaker B04~B15

€ Code system B34~B35

		Available to	ol holders		
Designation	Page	Designation	Page	Designation	Page
MTENN	B187	PTFNR/L	B177	WTJNR/L	B179
MTFNR/L	B187	PTGNR/L	B178	WTXNR/L	B179
MTGNR/L	B188	PTTNR/L	B178		
MTJNR/L	B188	WTENN	B179		







	Dimension	ons (mm)	
Size	d	t	d₁
16	9.525	4.76	3.81

## Rhombic 35° Negative

	Steel	Р		#		3	•	•	\$ 3	#	#	#	•	•			#							Machining types
8	Stainless steel	M								3	3	3			•	3	#		3	3	#			3 7,77
bje	Cast iron	K		#	•	\$	3	3				3	\$	3								•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N																					3	General cutting
×	Heat resistant alloy, Titanium alloy	S														•	•	•	3	\$			3	-
-	Hardened steel	Н																•	3	\$		•	3	# Interrupted cutting

				Cer	rmet	Coa	ated								C	oate	d								Unc	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215P	NC3225P	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC8105	PC8110	PC8115	PC9030	191	H05	fn (mm/rev)	ap (mm)
		VNMG	160404-VB	•	•	•	•			•	•				•												0.10~0.35	0.30~1.50
ing	VB		160408-VB	•	•	•	•			•	•				•												0.15~0.45	0.50~2.00
Finishing			160412-VB							•	•																0.20~0.45	0.80~2.50
ш.																												
		<b>VNMG</b>	160402-VF									•															0.06~0.20	0.30~1.00
<u>ng</u>	VF		160404-VF									•			•							•					0.08~0.30	0.50~1.50
Finishing			160408-VF								•	•			•												0.10~0.40	0.50~1.50
亡			160412-VF																								0.15~0.50	0.50~1.50
		VNMG	160404-VL	•	•					•	•				•												0.05~0.20	0.10~1.00
g	VL		160408-VL		•					•	•																0.10~0.25	0.20~1.50
Finishing	1000000000		160412-VL							•																	0.15~0.30	0.50~2.00
iT.																												
<u>e</u>		VNMG	160404-LP							•	•																0.10~0.35	0.30~1.50
nish	LP 🚙		160408-LP							•	•																0.10~0.40	0.50~2.00
it of	new		160412-LP							•	•																0.10~0.45	0.80~2.50
Medium to finishing   Medium to finishing   Medium to finishing	-																											
ling .		VNMG	160404-CP					•	•																		0.10~0.35	0.5~3.0
inis	CP rew		160408-CP					•	•																		0.12~0.30	0.5~3.0
n to f	100		160412-CP					•	•																		0.13~0.30	0.8~3.0
Mediur																												
gui		VNMG	160404-VC	•		•				•	•																0.10~0.35	0.30~2.00
inis	VC		160408-VC	•						•	•																0.15~4.00	0.50~3.00
n to f	THE RESERVE		160412-VC							•	•																0.15~0.40	0.80~3.00
Mediur																												
Б		VNMG	160404-HM									•	•											•			0.13~0.40	0.80~3.80
Ħ	НМ		160408-HM								•	•	•											•			0.20~0.45	0.80~4.50
E I	-0-		160412-HM								•																0.10~0.60	1.00~4.00
Medium cutting																												
		VNMG	160404-MP							•	•				•			•	•	•	•	•					0.10~0.40	0.40~3.50
ting	MB		160408-MP							•	•				•	•		•	•	•	•	•					0.15~0.45	0.50~4.00
cut	MP		160412-MP							•	•				•												0.15~0.50	0.80~4.50
Medium cutting	1		160416-MP																								0.18~0.50	1.00~4.50
Med																												




	Available	tool holders	
Designation	Page	Designation	Page
MVJNR/L	B188	MVVNN	B189
MVQNR/L	B189	MVUNR/L	B214

**<sup>→</sup>** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

**ᢒ** Code system **B34~B35** 

<sup>• :</sup> Stock item





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
16	9.525	4.76	3.81
22	12.7	4.76	5.16

## Rhombic 35° Negative


	Steel		Р		#		\$	\$ \$	#	#	#	•	•	\$	#								Machining types
ဗ္ဗ	Stainless steel		M						3	3	3			3	#	3	#	•	3	3	#		
pie	Cast iron	4	K		#	•	\$ 3				3	3	3									3	<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	•	N																			3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S								•			•		\$	#	•	3	3		3	# Interrupted cutting
	Hardened steel	<b>-</b>	Н															•	3	3		3	- interrupted cutting

				Cer	met	Coa	ated								Coa	ted									Uncoa	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		VNMG	160404-VM	•							•		•						•	•							0.08~0.45	0.50~3.50
E S			160408-VM	•							•		•						•	•				•			0.10~0.50	1.00~4.00
E .	VM		160412-VM																								0.20~0.50	1.50~4.00
<u>=</u>	-		220404-VM																								0.08~0.45	1.00~5.00
Medium cutting			220408-VM																								0.10~0.50	1.50~5.00
g		VNMG	160404-VQ	•	•	•	•																				0.10~0.40	0.50~3.50
ië.			160408-VQ	•	•	•	•																				0.12~0.45	0.50~3.50
ij	VQ		160412-VQ				_																				0.15~0.45	0.80~3.50
Medium to finishing	[Cermet]																											
		VNMG	160404-MK												•												0.08~0.45	0.50~3.00
툍	MK		160408-MK											•	•												0.10~0.50	1.00~3.50
Ξ Ε	new		160412-MK												•												0.20~0.50	1.50~4.00
Medium cutting																												
Бſ		VNMG	160404-MM														•	•	•				•	•			0.10~0.40	0.50~4.80
曹	MM		160408-MM														•		•				•	•			0.12~0.45	0.50~4.80
Medium cutting	new		160412-MM																								0.15~0.60	0.50~4.00
		VNMG	160404-RM																								0.10~0.50	2.00~5.00
ij.	DM.	7111110	160408-RM																								0.15~0.55	2.00~5.00
200	RM		160412-RM						_																		0.20~0.60	2.00~5.00
Medium cutting			10041211111																								0.20 0.00	2.00 0.00
Б		VNMG	160404-VP3																•	•	•	•	•			•	0.05~0.30	0.10~3.00
Ħ	VP3		160408-VP3																•	•	•	•	•		•	•	0.10~0.45	0.50~5.00
Medium cutting			160412-VP3																								0.20~0.40	0.50~3.50
		VNGG	160404-VP3																		•	•	•		•		0.05~0.30	0.10~3.00
i H	VP3		160408-VP3																								0.10~0.45	0.50~5.00
Medium to finishing   Medium cutting	VF3																											
gui		VNGG	160408-HA																			•					0.10~0.40	0.80~3.50
Medium to finish	HA																											


**→** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

€ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
MVJNR/L	B188	MVVNN	B189
MVQNR/L	B189	MVUNR/L	B214







	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
06	9.525	4.76	3.81
08	12.7	4.76	5.16



## 

	Steel	Р		#		\$	3	•	\$ 3	#	#	#	•	•	3		#							Machining types
8	Stainless steel	M								3	3	3				3	#	•	3	3	#			
pie	Cast iron	K		#	•	\$ 3		\$				3	\$	3								•	3	<ul> <li>Continuous cutting</li> </ul>
y.	Non-ferrous metal	N																				•	3	General cutting
×	Heat resistant alloy, Titanium alloy	S															•	•	3	3		•	3	-
	Hardened steel	Н																•	3	3			3	# Interrupted cutting

				met										oate									Unco	ated	Cutting (	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215P	NC3225P	NC3215 NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
	VB	<b>WNMG</b> 080404-VB							• •				•												0.10~0.35	0.30~1.50
ing	Dr.	080408-VB							• •				•												0.15~0.45	0.50~2.00
Finishing		080412-VB							• •																0.18~0.45	0.80~2.50
		WNMG 060404-VF											•												0.07~0.30	0.50~1.50
	VF	060408-VF																							0.10~0.40	0.50~1.50
<u>g</u>	VI	080404-VF								•	)		•												0.07~0.30	0.50~1.50
Finishing		080408-VF											•												0.10~0.40	0.50~1.50
뜐	VEV	080412-VF																							0.20~0.50	0.50~1.50
	VL	<b>WNMG</b> 060404-VL																							0.05~0.25	0.20~1.50
ng	<u>~</u>	080404-VL																							0.05~0.25	0.10~1.00
Finishing	2	080408-VL							•				•												0.10~0.35	0.20~1.50
		WNMG 06T308-LP																							0.07~0.30	0.30~1.50
_		060404-LP																							0.07~0.30	0.30~1.50
ΞĚ	LP _	060408-LP							• •																0.10~0.30	0.30~1.50
finis	new	080404-LP							• •				•												0.10~0.35	0.30~2.00
9	5	080408-LP							• •				•												0.10~0.40	0.50~2.50
Medium to finishing	Cooks	080412-LP							• •				•												0.13~0.45	0.80~3.00
		WNMG 060404-CP																							0.08~0.30	0.40~3.00
		060408-CP																							0.10~0.30	0.40~3.00
hing	CP	080404-CP					•	•																	0.10~0.35	0.50~3.50
inis	new	080408-CP					•	•																	0.12~0.35	0.50~3.50
to	37 55	080412-CP					•	•																	0.13~0.35	0.80~3.50
Medium to finishing	THE PARTY OF	080416-CP					•	•																	0.14~0.35	0.80~3.50
<u> </u>		WNMG 080404-VC							• •																0.15~0.40	0.15~4.00
shir	VC	080408-VC							• •																0.15~0.45	0.15~4.50
Medium to finishing		080412-VC							• •				•												0.15~0.45	0.15~4.50


→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

→ Code system B34~B35



	Available	tool holders	
Designation	Page	Designation	Page
MWLNR/L	B189	WWLNR/L	B180
PWLNR/L	B211		





	Dimensio	ons (mm)	
Size	d	t	d <sub>1</sub>
06	9.525	4.76	3.81
80	12.7	4.76	5.16



## 

	Steel		Р		#		\$	3	\$ #	#	#	•	•	\$	#									Machining types
ဗ္ဗ	Stainless steel		M						3	3	<b>3</b>			3	#	3	#		3	3	#			
pie	Cast iron	4	K		#	•	\$ 3				<b>3</b>	3	3									•	3	<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	•	N																				3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S													3	#		3	3			3	<u></u>
	Hardened steel		Н															•	3	3		•	3	# Interrupted cutting

					Coa									Coa										Unco	ated	Cutting C	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		<b>WNMG</b> 060404-HM												•												0.15~0.43	0.42~3.00
g	НМ	060408-HM							•	•													•			0.10~0.50	1.00~4.00
闄	A	080404-HM							•	•													•			0.15~0.42	0.50~4.20
Ē	50	080408-HM					•	•	•	•		•											•			0.10~0.50	1.00~5.00
Medium cutting	HE TELL	080412-HM																					•			0.10~0.50	1.00~5.00
		<b>WNMG</b> 06T304-MP																								0.10~0.40	0.40~2.80
		06T308-MP																								0.15~0.45	0.50~3.00
		060404-MP					•	•				•				•										0.10~0.40	0.40~2.80
Бſ	MP _	060408-MP						•				•				•										0.15~0.45	0.50~3.00
曹	new	060412-MP																								0.15~0.50	0.80~3.20
E		080404-MP						•				•				•	•			•		•				0.10~0.40	0.40~4.00
Medium cutting		080408-MP					•	•				•				•	•			•		lacktriangle				0.15~0.45	0.50~4.50
ž		080412-MP						•				•				•	•			•						0.15~0.50	0.80~5.00
		080416-MP					•	•				•														0.18~0.55	0.10~5.00
		<b>WNMG</b> 060404-VM										•					(	•	•							0.10~0.45	1.00~3.50
		060408-VM						•				•					(	•	•							0.10~0.50	1.00~4.00
		060412-VM																								0.13~0.60	1.30~4.00
ij.	VM	080404-VM										•					(	•	•							0.05~0.30	0.90~5.00
<u> </u>		080408-VM						•	•	•		•					(	•	•		•		•			0.10~0.50	1.00~5.00
Medium cutting	A.C.	080412-VM							•			•					(	•	•							0.10~0.50	1.00~5.00
Med		080416-VM																								0.10~0.50	1.20~5.00
<b>E</b>		<b>WNMG</b> 080404-B25						•				•														0.17~0.45	1.00~5.00
nin Bu	<b>B25</b>	080408-B25					•	•		•		•						+								0.17~0.45	1.50~5.00
ono.	<b>D</b> 25	080408-B25 080412-B25										•		_				+								0.25~0.60	2.00~5.00
Medium to roughing		000412 B23																								0.23-0.00	2.00 -0.00
		WNMG 080404-GR																								0.15~0.50	0.08~6.00
	GR	080408-GR						•	•	•		•	•													0.20~0.50	1.00~7.00
ng	GR	080412-GR					•	•	•	•		•	•													0.25~0.50	1.30~7.00
Roughing		080416-GR																								0.25~0.60	1.80~6.00

**→** Cutting edge geometry A37~A49 **→** Recommended chip breaker B04~B15


→ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
MWLNR/L	B189	WWLNR/L	B180
PWLNR/L	B211		



## B Turning Insert (Negative)





		Dimension	ons (mm)	
Size	9	d	t	d₁
06		9.525	4.76	3.81
08		12.7	4.76	5.16



## 

	Steel	Р		#		\$	3	\$ #	#	#	•	•	\$	#								Machining types
8	Stainless steel	M						3	3	<b>3</b>			<b>3</b>	#	3	#		3	3	#		
cpie	Cast iron	K		#	•	\$ 3				<b>3</b>	\$	3									3	<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	N																			3	General cutting
×	Heat resistant alloy, Titanium alloy	S													3	#	•	3	3		3	-
	Hardened steel	Н															•	3	\$		3	# Interrupted cutting

		ed steel																									
				met										Coat										Unco	oated	Cutting C	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		<b>WNMG</b> 060404-VQ																								0.05~0.30	0.50~4.00
DG .	VQ	060408-VQ																								0.08~0.30	0.80~4.00
is	VQ	060412-VQ																								0.10~0.30	1.00~4.00
Ē		080404-VQ		•	•																					0.05~0.30	0.50~4.00
Medium to finishing	A-A	080408-VQ		•	•																					0.08~0.40	0.80~4.00
텵		080412-VQ																								0.10~0.35	0.80~3.50
ĕ	[Cermet]																										
		<b>WNMG</b> 060408-MK											•	•												0.08~0.30	0.80~2.50
DG .	MK_	080404-MK												•												0.10~0.45	1.00~3.00
慧	new	080408-MK												•												0.10~0.50	1.00~3.50
Ē		080412-MK												•												0.10~0.50	1.00~4.00
Medium cutting		080416-MK																								0.13~0.50	1.20~4.20
2																											
		WNMA 060404																								0.10~0.30	0.50~3.00
		060408												•												0.10~0.30	0.50~3.00
		060412																								0.10~0.40	1.00~3.00
ing		080404												•												0.15~0.60	1.00~5.00
Roughing		080408												•												0.15~0.60	1.00~6.00
&		080412												•												0.15~0.70	1.50~6.00
		080416																_								0.15~0.70	1.50~6.00
		<b>WNMG</b> 060408-RK																								0.10~0.40	1.00~3.50
		060412-RK																								0.23~0.40	1.50~5.00
	RK_	080404-RK												•												0.23~0.50	1.50~6.00
ing	THE STATE OF THE S	080408-RK												•												0.23~0.53	1.50~6.00
Roughing		080412-RK												•												0.28~0.53	1.80~6.00
8		080416-RK												•												0.25~0.60	2.00~6.00
		<b>WNMG</b> 060408-VR																								0.20~0.40	1.00~6.00
		080404-VR																								0.20~0.50	0.80~7.00
5	VR	080408-VR																								0.25~0.55	1.20~7.00
hin		080412-VR																								0.30~0.60	1.50~7.00
Roughing		080416-VR																								0.40~0.60	1.50~4.00

Cutting edge geometry A37~A49


→ Recommended chip breaker B04~B15

€ Code system B34~B35



	Available	tool holders	
Designation	Page	Designation	Page
MWLNR/L	B189	WWLNR/L	B180
PWLNR/L	B211		





	Dimension	ons (mm)	
Size	d	t	d₁
06	9.525	4.76	3.81
08	12.7	4.76	5.16
13	19.05	6.35	7.93

## 

	Steel		Р		#		\$	3	3	#	#	#	•	\$	#									Machining types
ဗ္ဗ	Stainless steel		M							3	3	3		3	#	3	#		3	3	3	#		
pie	Cast iron		K		#	•	\$ 3					3	3										3	<ul><li>Continuous cutting</li></ul>
춫	Non-ferrous metal	•	N																				3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S											•		3	#		3	3	3		3	# Interrupted cutting
	Hardened steel	4	Н															•	3	3			3	- interrupted cutting

				met									Coate										coated	Cutting (	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	20013	02000	2000	H05	fn (mm/rev)	ap (mm)
		<b>WNMG</b> 06T304-MM																						0.08~0.35	0.50~4.00
		06T308-MM																						0.10~0.40	0.50~4.00
		06T312-MM																						0.12~0.45	0.50~4.00
<u>p</u>	MM	060404-MM																						0.08~0.35	0.50~4.00
Medium cutting		060408-MM												•	•									0.10~0.40	0.50~4.00
E	S. Com	060412-MM													•									0.12~0.45	0.50~4.00
edin	CHANGE OF THE PARTY OF THE PART	080404-MM													•	•			• (					0.10~0.40	0.50~4.00
Ž		080408-MM											•		•	•								0.12~0.45	0.50~4.00
		080412-MM											•		•									0.15~0.60	0.50~4.00
		<b>WNMG</b> 060404-RM												•	•									0.10~0.50	1.50~3.00
	RM _	060408-RM													•									0.15~0.55	1.50~3.00
0	new	060412-RM												•	•									0.20~0.60	1.50~3.00
뼕		080404-RM													•	•								0.10~0.50	2.00~4.00
Roughing	Che La	080408-RM											•	•	•				•					0.15~0.55	2.00~4.00
"		080412-RM											•		•	•								0.20~0.60	2.00~4.00
Đ.	VP2	<b>WNMG</b> 080404-VP2														•	•		•		_			0.10~0.45	0.50~5.00
ishir	VP2	080408-VP2						•								•	•	•	• (					0.12~0.50	0.50~5.00
to fin		080412-VP2														•	•	•	• (					0.05~0.30	0.10~3.00
Medium to finishing																									
		WNMG 060408-VP3															_					-		0.06~0.38	0.40~3.50
ing	VP3	060412-VP3													_		_				_	_		0.06~0.38	0.40~3.50
ŧ		080404-VP3													_	•	•	•	• (				•	0.10~0.45	0.50~5.00
Ē		080408-VP3														•	•	•	• (				•	0.12~0.50	0.50~5.00
Medium cutting		080412-VP3														•	•	•	• (			•		0.05~0.30	0.10~3.00
2		130612-VP3															_							0.20~0.40	1.00~5.00
gui	VP3	<b>WNGG</b> 080404-VP3																						0.10~0.45	0.50~5.00
Medium cutting																									
	VP4	WNMG 080408-VP4																						0.15~0.35	1.00~4.00
Б	VP4	080412-VP4															T				_			0.20~0.40	1.00~4.00
Roughing		33772 77 4																							

**→** Cutting edge geometry A37~A49 **→** Recommended chip breaker B04~B15


→ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
MWLNR/L	B189	WWLNR/L	B180
PWLNR/L	B211		



## B Turning Insert (Negative)





	Dimensio	ons (mm)	
Size	d	t	d <sub>1</sub>
06	9.525	4.76	3.81
80	12.7	4.76	5.16
10	15.875	6.35	6.35
13	19 05	6.35	7 93

## 

	Steel		Р		#		3		\$ 3	#	#	#	•	•	3		#									Machining types
ဗ္ဗ	Stainless steel		M							3	3	3				3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	3	3				3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
, Y	Non-ferrous metal	•	N																						3	General cutting
×	Heat resistant alloy, Titanium alloy		S									•				•		\$	#	•	3	3		•	3	# Interrupted cutting
	Hardened steel		Н																	•	3	3			\$	- interrupted cutting


				met									Coa										Unco	ated	Cutting (	Condition
	Inserts	Designation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
_		WNMG 060404-HA																				•	•		0.05~0.30	0.10~3.00
i <u>F</u>	HA	060408-HA																				•	•		0.10~0.40	0.80~3.50
iii Si I		080404-HA																							0.05~0.30	0.80~3.50
<u>ē</u>		080408-HA																							0.10~0.40	0.80~3.50
Medium to finishing		080412-HA																							0.13~0.55	0.80~3.50
		<b>WNMG</b> 060404-VW																							0.05~0.30	0.40~3.00
	VW	060408-VW																							0.08~0.30	0.40~3.50
20		080404-VW																							0.10~0.30	0.50~3.00
i i i		080408-VW																							0.15~0.50	0.50~4.00
Finishing	Alexander Control	080412-VW																							0.18~0.50	1.00~4.00
ш	[Wiper]																									
		<b>WNMG</b> 060408-LW					•	•							•										0.15~0.60	0.50~3.50
g	LW	060412-LW																							0.20~0.70	0.80~3.50
も		080408-LW					•	•			•				•										0.15~0.60	1.00~5.00
Medium cutting	[Wiper]	080412-LW					•																		0.20~0.70	1.00~6.00
		WNMX 080404R-SR																							0.10~0.35	0.70~3.00
ing	SR	080408R-SR																							0.12~0.40	1.00~3.00
list	new	080404L-SR																							0.10~0.35	0.70~3.00
	1	080408L-SR											_												0.12~0.40	1.00~3.00
Medium to finishing	[Shaft]																									
		<b>WNMX</b> 080404R-SH																							0.15~0.30	1.00~4.00
<u>B</u>	SH	080408R-SH																							0.15~0.50	1.50~5.00
豊		080404L-SH																							0.15~0.30	1.00~4.00
E .		080408L-SH																							0.15~0.50	1.50~5.00
Medium cutting	[Shaft]																									
ing	B25	WNMM 100608-B25								•															0.30~0.80	3.00~8.00
hgnc		130612-B25																							0.40~0.90	4.00~10.00
Medium to roughing																										

→ Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15 → Code system B34~B35



	Available	tool holders	
Designation	Page	Designation	Page
MWLNR/L	B189	WWLNR/L	B180
PWLNR/L	B211		





	Dimension	ons (mm)	
Size	d	t	d₁
06	6.35	2.38	2.8
09	9.525	3.97	4.4
12	12.7	4.76	5.5

# Rhombic **80° Positive**Relief Angle: 7°

	Steel		Р		#		3		3	3	#	#	#	•		3		#									Machining types
8	Stainless steel		M								3	3	3			•	3	#	3	#	•	3	3	#			- maximing types
pie	Cast iron	4	K		#	•	\$	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	<b>-</b>	N																							3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S																3	*	•	3	3		•	-	# Interrupted cutting
	Hardened steel	4	Н																		•	3	3		•	3	** Interrupted cutting

				Cer	met	Со	ated	I							Coa	ated									Unco	oated	Cutting (	Condition
	Inserts	De	esignation						225	120	330	235	330	310	315	115	125	135	9	900	105	110	12	330			fn	ар
				CN1500	CN2500	5	CC2500	<u>S</u>	NC3225	S	NC3030	<b>S</b>	NC5330	S	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	ည္က	PC8115	PC9030	듣	H05	(mm/rev)	(mm)
<u></u>		ССМТ	060202-FP		•		Ŭ	•	Ī	Ī	Ī	Ī	_	Ī	Ī	_	_	Ī	_	_	_		_	_	-		0.01~0.10	0.05~0.08
Finishing(Mild steel)	FP _		060204-FP	•	•	•	•		•								•					•					0.01~0.10	0.10~0.90
₽	new		09T302-FP		•			•																			0.01~0.10	0.05~1.00
ng(			09T304-FP	•	•	•	•	•	•								•					•					0.01~0.10	0.10~1.00
ishi			09T308-FP	•	•	•	•	•	•								•					•					0.04~0.12	0.10~1.00
造	[Mild steel]																											
		CCMT	060202-VF						•													•					0.05~0.20	0.30~1.00
	VF		060204-VF	•	•				•													•					0.10~0.25	0.30~1.00
<u>n</u>	VI		09T302-VF						•																		0.04~0.16	0.80~1.50
Finishing			09T304-VF		•				•																		0.05~0.20	0.30~1.50
造			09T308-VF		•				•				•						•								0.10~0.25	0.30~1.50
			120404-VF						•																		0.07~0.22	0.10~2.00
		CCMT	060202-VL																								0.04~0.18	0.20~1.40
			060204-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•				0.04~0.10	0.08~0.90
	VL		060208-VL					•	•				•				•	•									0.06~0.12	0.10~1.00
ing			09T304-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•		•	•	0.05~0.10	0.10~1.00
Finishing			09T308-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•		•	•	0.08~0.15	0.10~1.00
這			120404-VL																								0.06~0.12	0.30~1.50
			120408-VL																								0.08~0.15	0.30~1.50
			120412-VL																								0.08~0.15	0.30~1.50
		CCMT	060202-HMP	•															•			•		•			0.03~0.12	0.10~1.50
			060204-HMP		•					•	•		•						•			•		•			0.06~0.17	0.20~2.40
ing			060208-HMP							•	•		•						•			•		•			0.08~0.23	0.40~2.40
Medium to finishing	HMP		09T302-HMP							_					_				_			•		•			0.07~0.22	0.10~2.00
: <u>≡</u>			09T304-HMP		•					•	•		•		•				•			•		•			0.08~0.23	0.30~3.00
Ē			09T308-HMP		•				_	•	•		•						•			•		•			0.10~0.30	0.50~3.00
<u>8</u>			120404-HMP						•	•	•		_						•					•			0.09~0.27	0.30~3.60
2			120408-HMP							•	•		•						•					•			0.24~0.36	1.00~3.60
			120412-HMP																								0.14~0.43	0.70~3.60
					_	_	_	_	_							_	_	_	_	_	_	_	_					
		ССМТ	060202-MP	•	•	•	•		•				•			•	•	•	•	•	•	•	•				0.04~0.12	0.20~1.50
			060204-MP		•		•		•				•		•					•							0.05~0.15	0.30~1.50
hing	N/ID		060208-MP												•				_								0.07~0.15	
nisi	MP		09T302-MP		•		•		•				•	_	_	•	•	•	•	•	•	•	•				0.07~0.15	
Medium to finisl	CS CO		09T304-MP		•			•	•					•	•	•	•	•	•	•	•	•	•				0.08~0.25	-
E			09T308-MP		•		•		•				•		•		•	•									0.10~0.30	
ledi			120404-MP						•						•		•	•									0.10~0.30	
2			120408-MP						•					•	•		•	_									0.15~0.35	0.80~3.50
			120412-MP														•										0.25~0.40	1.00~3.50


Cutting edge geometry A37~A49

€ Code system B34~B35

	Availa	ble tool holders	
Designation	Page	Designation	Page
SCACR/L	B123, 190	SCLCR/L	B123, 190, 215, 225

## **B** Turning Insert (Positive)






	Dimensio	ons (mm)	
Size	d	t	d₁
06	6.35	2.38	2.8
09	9.525	3.97	4.4
12	12 7	4 76	5.5



# Rhombic **80° Positive** Relief Angle: 7°

	Steel		Р		#	3		<b>\$</b>	3	#	#	#	•		3		#									Machining types
8	Stainless steel		M							\$	3	3				3	#	\$	#	•	1	3	#			
pie	Cast iron	4	K		#	3	3					3	3	3											3	<ul> <li>Continuous cutting</li> </ul>
¥	Non-ferrous metal	1	N																					•	3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S													•	•	3	#	•	3	3		•	3	-
	Hardened steel		Н																	•	3	\$			3	# Interrupted cutting


				Cei	met	Coa	ated								Coa	ted									Unc	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	192	fn (mm/rev)	ap (mm)
		ССМТ	060202-C25	•	•	•	•	•	•	Ī	•	Ī	•	_	_	_	_	_	•	•	_	•	_	_	_		0.03~0.12	0.40~2.00
			060204-C25	•	•	•	•	•	•	•	•		•	•	•				•	•		•		•			0.05~0.15	0.60~2.30
ō	<b>C25</b>		060208-C25	•	•		•	•	•		•		•		•				•	•		•					0.07~0.20	0.80~2.30
曹	<b>C25</b>		09T302-C25																								0.05~0.20	0.50~2.50
Medium cutting			09T304-C25	•	•	•	•	•	•	•	•		•	•	•				•	•		•		•			0.08~0.25	0.80~3.00
ij			09T308-C25	•	•	•	•	•	•	•	•		•	•	•				•	•		•		•			0.10~0.30	1.00~3.00
ž			120404-C25					•	•		•		•	•	•				•	•		•					0.10~0.32	0.80~3.00
			120408-C25	•	•	•	•	•	•	•	•		•	•	•				•	•		•					0.12~0.36	1.20~3.50
			120412-C25					•	•				•		•												0.15~0.40	1.40~3.50
		CCMT	060204-VP1																								0.06~0.12	0.10~1.50
	VP1		09T304-VP1																								0.06~0.20	0.10~1.50
gu			09T308-VP1																								0.08~0.20	0.50~2.00
Finishing			120404-VP1																								0.08~0.22	0.20~2.00
造			120408-VP1																								0.10~0.25	0.50~2.00
			120412-VP1																								0.10~0.30	0.80~2.50
		2007	22224 52																			_					004.040	0.00 4.00
		CCGT	060201-FS																•			•					0.01~0.18	0.03~1.60
	EC		060202-FS																•			•					0.02~0.20	0.04~1.70
Б	FS		060204-FS																•			•					0.04~0.21	0.06~1.80
Finishing			09T301-FS																•			•					0.01~0.20	0.04~1.80
뜶			09T302-FS																•			•					0.02~0.23	0.05~2.00
			09T304-FS 09T308-FS																•			•					0.04~0.23	0.08~2.00
	[High precision]		091306-F3																								0.06~0.25	0.10~2.20
		CCGT	060201MFN-FS																								0.01~0.18	0.03~1.60
			060202MFN-FS																								0.02~0.20	0.04~1.70
	FS		060204MFN-FS																								0.04~0.21	0.06~1.80
Finishing			09T301MFN-FS																								0.01~0.20	0.04~1.80
inis			09T302MFN-FS																								0.02~0.23	0.05~2.00
-			09T304MFN-FS																								0.04~0.23	0.08~2.00
	[ Utra high precision ]		09T308MFN-FS																								0.06~0.25	0.10~2.20
		0007	007004 140																			_					0.00.000	0.05.000
ting	MS	CCGT	09T301-MS																•			•					0.02~0.23	0.05~2.00
ium cutting	new		09T302-MS																•			•					0.03~0.25	0.07~2.50
Medium	[High precision]		09T304-MS																•			•					0.05~0.25	0.09~2.50
		CCGT	09T301MFN-MS																•			•					0.02~0.23	0.05~2.00
i	MS		09T302MFN-MS																•			•					0.03~0.25	0.07~2.50
n Cr			09T304MFN-MS																•			•					0.05~0.25	0.09~2.50
Medium cutting	[Utra high precision]																											





	Availa	able tool holders	
Designation	Page	Designation	Page
SCACR/L	B123, 190	SCLCR/L	B123, 190, 215, 225





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
*03	3.5	1.39	1.9
*04	4.3	1.79	2.3
06	6.35	2.38	2.8
09	9.525	3.97	4.4

\*: The d and t are special dimensions.

# Rhombic **80° Positive**Relief Angle: 7°

	Steel	•	Р		#	•	\$		3	3	#	#	#	•	•	3		#									Machining types
8	Stainless steel	<	M								3	\$	3			•	3	#	3	#	•	3	3	#			
bje	Cast iron	⋖	K		#		3	3					3	3	3											3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	⋖	N																							3	General cutting
×	Heat resistant alloy, Titanium alloy	<	S															•	3	*	•	3	3		•	3	# Interrupted cutting
	Hardened steel	4	Н																		•	3	\$			3	** Interrupted cutting

				Ce	rme	Coa	ated								Coa	ted									Uncoated	Cutting (	Condition
	Inserts	D	esignation			CC1500	CC2500	NC3215	NC3225	120	NC3030	NC3235	NC5330			NC9115	NC9125	NC9135	300	400	105	110	115	PC9030		fn	ар
				CN1500	CN2	5	CC	NG3	SS	NC3120	NG3	SS	NC5	NC6	NC6	65N	65N	S 29	PC5300	PC5400	PC8105	PC8110	PC8115	PC9	년 년 년	(mm/rev)	(mm)
		CCGT	060201-VP1				_												•		•	•	•		•	0.05~0.06	0.06~1.00
			060202-VP1																•		•	•	•		•	0.03~0.10	0.08~1.50
	VP1		060204-VP1																•		•	•	•		•	0.05~0.12	0.10~1.50
5	200		09T301-VP1																•		•	•	•		•	0.03~0.13	0.06~1.00
Finishing	1		09T302-VP1																•		•	•	•			0.04~0.15	0.08~1.50
inis			09T304-VP1																•		•	•	•			0.06~0.20	0.10~1.50
_	4																										
	[High precision]																										
		CCGT	060201MFN-VP1																•			•				0.03~0.06	0.06~1.00
		3001	060201MFN-VP1																-			•				0.03~0.00	0.08~1.50
			060204MFN-VP1												-				•			•				0.05~0.10	0.10~1.50
	VP1		09T301MFN-VP1																•			•				0.03~0.12	0.06~1.00
0			09T302MFN-VP1																•			•				0.04~0.15	0.08~1.50
Finishing			09T304MFN-VP1																•			•				0.06~0.20	0.10~1.50
Ë																											
	[ Utra high precision ]																										
	*	CCET	0301005R																							0.01~0.05	0.10~0.30
			030101R																							0.01~0.05	0.10~0.30
			030102R																							0.01~0.05	0.10~0.30
			030104R																							0.01~0.05	0.10~0.30
			0401005R												_											0.01~0.10	0.10~0.50
			040101R																							0.01~0.10	0.10~0.50
			040102R																							0.01~0.10	0.10~0.50
			040104R												_											0.01~0.10	0.10~0.50
			0301005L																							0.01~0.05	0.10~0.30
hing			030101L																							0.01~0.05	0.10~0.30
Finishing			030102L												_									•	•	0.01~0.05	0.10~0.30
ш	Ť		030104L												_											0.01~0.05	0.10~0.30
			0401005L												_											0.01~0.10	0.10~0.50
			040101L																							0.01~0.10	0.10~0.50
			040102L 040104L												_									•	-		0.10~0.50
			040104L																							0.01~0.10	0.10~0.30
		1		_																							

Outting edge geometry A37~A49


Recommended chip breaker B04~B15

→ Code system B34~B35

	Availa	ble tool holders	
Designation	Page	Designation	Page
SCACR/L	B123, 190	SCLCR/L	B123, 190, 215, 225

## B Turning Insert (Positive)





	Dimension	ons (mm)	
Size	d	t	d₁
*03	3.5	1.39	1.9
*04	4.3	1.79	2.3
06	6.35	2.38	2.8
ng	9 525	3 97	11

 $\bigstar$  : The d and t are special dimensions.

# Rhombic **80° Positive**Relief Angle: 7°

	Steel		Р		#		3		3	3	#	#	#	•	•	\$	#									Machining types
క్ర	Stainless steel	<	M								3	3	3			3	#	3	#		3	3	#			
Bi.	Cast iron	4	K		#	•	3	3					3	\$	3									•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	4	N																						3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<	S														•	3	#		3	3			3	# Interrupted cutting
	Hardened steel	4	Н																	•	3	3			3	- interrupted cutting

				Cer	met	Coa	ited								Coa	ited									Unco	oated	Cuttina (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330		NC6315		NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
	*	CCGT	0301003R-KF			J		_	_	_	_		_	_	_	_	_	_	•	_		•	_	_	_	_	0.01~0.05	0.10~0.30
			030101R-KF																•			•					0.01~0.05	0.10~0.30
			030102R-KF																•			•					0.01~0.05	0.10~0.30
			030104R-KF																•			•					0.01~0.05	0.10~0.30
			0401003R-KF																•			•					0.01~0.10	0.10~0.50
			040101R-KF																•			•					0.01~0.10	0.10~0.50
			040102R-KF																•			•					0.01~0.10	0.10~0.50
			040104R-KF																•			•					0.01~0.10	0.10~0.50
			0602003R-KF																								0.01~0.06	0.04~1.30
			060201R-KF																								0.02~0.08	0.05~1.50
			060202R-KF																								0.03~0.11	0.06~1.70
			09T3003R-KF																								0.02~0.08	0.05~1.50
	KF		09T301R-KF																								0.03~0.11	0.06~1.70
in a	KF		09T302R-KF																								0.04~0.15	0.08~2.00
Finishina			0301003L-KF																•			•					0.01~0.05	0.10~0.30
ū			030101L-KF																•			•					0.01~0.05	0.10~0.30
	[High precision]		030102L-KF																•			•					0.01~0.05	0.10~0.30
			030104L-KF					_											•			•	_				0.01~0.05	0.10~0.30
			0401003L-KF																•			•					0.01~0.10	0.10~0.50
			040101L-KF					_											-			•					0.01~0.10	0.10~0.50
			040102L-KF																•			•	-				0.01~0.10	0.10~0.50 0.10~0.50
			040104L-KF 0602003L-KF																_			_					0.01~0.10	0.10~0.50
			0602003L-KF					_															-				0.01~0.08	0.04~1.50
			060201L-KF																								0.02~0.08	0.05~1.30
			09T3003L-KF					-															_				0.02~0.08	0.05~1.50
			09T301L-KF																				-				0.03~0.11	0.06~1.70
			09T302L-KF																				_				0.04~0.15	0.08~2.00
			0010022111																								0.01 0.10	0.00 2.00
		CCET	0602005MFR-KF																•			•					0.01~0.06	0.04~1.30
			060201MFR-KF																•			•					0.02~0.08	0.05~1.50
			060202MFR-KF																•			•					0.03~0.11	0.06~1.70
			09T3005MFR-KF																•			•					0.02~0.08	0.05~1.50
	KF		09T301MFR-KF																•			•					0.03~0.11	0.06~1.70
hina	, KF		09T302MFR-KF																•			•					0.04~0.15	0.08~2.00
ids			0602005MFL-KF																•			•					0.01~0.06	0.04~1.30
Finis			060201MFL-KF																•			•					0.02~0.08	0.05~1.50
	[ Utra high precision ]		060202MFL-KF																•			•					0.03~0.11	0.06~1.70
			09T3005MFL-KF																•			•					0.02~0.08	0.05~1.50
			09T301MFL-KF																•			•					0.03~0.11	0.06~1.70
			09T302MFL-KF																•			•					0.04~0.15	0.08~2.00

Cutting edge geometry A37~A49


**③** Code system B34∼B35



	Availa	able tool holders	
Designation	Page	Designation	Page
SCACR/L	B123, 190	SCLCR/L	B123, 190, 215, 225







	Dimension	ons (mm)												
Size	Size d t d <sub>1</sub>													
06	6.35	2.38	2.8											
09	9.525	3.97	4.4											

# Rhombic **80° Positive**Relief Angle: 7°

	Steel		Р		#	3		3	3	#	#	#	•	•	\$	#									Machining types
క్ర	Stainless steel		M							3	3	3			3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	3	3					3	3	3									•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	•	N																				•	3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S													•	3	#	•	3	3			3	<u></u>
	Hardened steel		Н																•	3	3		•	3	# Interrupted cutting


				Cer	met	Coa	ated								Coa	ited								U	nco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PCSIIS	PC9030	5	Н05	fn (mm/rev)	ap (mm)
		CCGT	0602003R-KM																•								0.01~0.06	0.04~1.30
			060201R-KM																•								0.02~0.08	0.05~1.50
			060202R-KM																•		(						0.03~0.11	0.06~1.70
			060204R-KM																•								0.04~0.13	0.04~1.70
			09T3003R-KM																•								0.02~0.08	0.06~1.50
			09T301R-KM																•								0.03~0.11	0.06~1.70
			09T302R-KM																•								0.04~0.15	0.08~2.00
hig	KM		09T304R-KM																•		-						0.05~0.16	0.10~2.00
inis			0602003L-KM																•								0.01~0.06	0.04~1.30
tof			060201L-KM																•								0.02~0.08	0.05~1.50
<u>=</u>			060202L-KM																•		(						0.03~0.11	0.06~1.70
Medium to finishing	[High precision]		060204L-KM																•								0.04~0.13	0.04~1.70
_	[9		09T3003L-KM																		(						0.02~0.08	0.06~1.50
			09T301L-KM																lacktriangle								0.03~0.11	0.06~1.70
			09T302L-KM																								0.04~0.15	0.08~2.00
			09T304L-KM																								0.05~0.16	0.10~2.00
		CCET	0602005MFR-KM																•								0.01~0.06	0.04~1.30
		CCEI																	-		_			+	-		0.01~0.06	0.04~1.30
			060201MFR-KM																•		_				-		0.02~0.08	0.05~1.50
			060202MFR-KM 09T3005MFR-KM																•		_				-			0.05~1.70
			09T3005MFR-KM																•						_		0.02~0.08	0.05~1.50
g	KM		09T301WFR-KM																•		_				-	$\dashv$	0.03~0.11	0.06~1.70
ishi			0602005MFL-KM																•		_		-		-		0.04~0.15	0.06~2.00
o fin			0602005WFL-KW																•		_		+		-		0.01~0.00	0.04~1.50
E			060201WFL-KW																•								0.02~0.06	0.05~1.50
Medium to finishing	[ Utra high precision ]		09T3005MFL-KM																•				+		+		0.02~0.08	0.05~1.70
Ž			09T301MFL-KM																•				H		+		0.02~0.00	0.05~1.30
			09T302MFL-KM																•								0.04~0.15	0.08~2.00
			O TOOLINE AM																								0.01	5.50 -2.00

	Availa	ble tool holders	
Designation	Page	Designation	Page
SCACR/L	B123, 190	SCLCR/L	B123, 190, 215, 225



## B Turning Insert (Positive)





	Dimension	ons (mm)	
Size	d	t	d₁
06	6.35	2.38	2.8
08	7.94	2.38	3.4
09	9 525	3 18	44

# Rhombic **80° Positive** Relief Angle: 11°

	Steel		Р		#		3		<b>\$</b>	\$ #	#	#	•	•	\$	#								Machining types
ဗ္ဗ	Stainless steel		M							3	3	3			<b>3</b>	#	3	#	•	3	3	#		
pie	Cast iron	4	K		#	•	3	3				3	\$	<b>\$</b>									3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	4	N																				3	General cutting
×	Heat resistant alloy, Titanium alloy		S												•	•	3	#	•	3	3		3	# Interrupted cutting
	Hardened steel	4	Н																•	3	3		3	- interrupted cutting

					Co	rmet	Car	tod								Cor	ated									Unco	natod	Cutting	Condition
										'n	0	0	ιΩ	0				ď	Ŋ	0	0	J.	0	2		Once	aicu		
	lr	serts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC321	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC903	된	H05	fn (mm/rev)	ap (mm)
			СРМТ	080204-VF																								0.05~0.20	0.30~1.20
				080208-VF																								0.10~0.25	0.30~1.20
		VF		090304-VF										•														0.05~0.20	0.30~1.50
<u>.</u>	n	VF		090308-VF										•														0.10~0.25	0.30~1.50
Einiching																													
			CPMT	080204-VL																								0.03~0.08	0.08~1.00
				080208-VL																								0.04~0.12	0.10~1.00
		VL		090304-VL																								0.05~0.10	0.10~1.00
از ا	ຼາ ≣			090308-VL																								0.08~0.15	0.10~1.00
Finishing																													
	D		CPGT	090308-HMP																								0.05~0.20	0.70~2.00
Medium to finishing		НМР																											
_	n		CPMT	060204-C25																								0.05~0.15	0.60~2.30
Medium cutting		C25																											
			CPGT	080202																								0.06~0.20	
				080204	•																							0.08~0.20	0.30~2.00
				080208																								0.10~0.25	0.50~2.00
				090302	_																							0.04~0.20	0.30~1.50
Finiching				090304	•																							0.06~0.25	0.50~2.00
hoio				090308																								0.08~0.30	0.70~2.50

Cutting edge geometry A37~A49
 Recommended chip breaker B04~B15


◆ Code system B34~B35



Available	tool holders
Designation	Page
SCLPR/L	B216







	Dimension	ons (mm)	
Size	d	t	d₁
07	6.35	2.38	2.8
11	9.525	3.97	4.4

### Rhombic 55° Positive Relief Angle: 7°

	Steel		Р		#		\$	3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							3	3	3				3	#	3	#	•	3	3	#		
pje	Cast iron	4	K		#	•	\$ 3					3	3	3										3	<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	4	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S														•	3	#	•	3	3		3	# Interrupted cutting
	Hardened steel	4	Н																	•	3	3		3	- interrupted cutting

					Cer	rme	Coa	ated								Coa	ated									Unco	oated	Cutting (	Condition
	1	anneto.		o i anotio =						55	02	2	35	2				52	35	0	0	2	0	2	2	Crio	Jasou		
	ın	nserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
			DCMT	070202-FP		•			•																			0.01~0.10	0.05~0.08
				070204-FP	•	•		•		•								lacktriangle										0.01~0.10	0.10~0.90
	n l	FP 🚙		070208-FP																								0.01~0.10	0.10~1.00
Finishing		new		11T302-FP		•																						0.01~0.10	0.05~1.00
غ ا	1			11T304-FP	•	•	•	•		•								•										0.01~0.10	0.10~1.00
"		[Mild steel]		11T308-FP	•	•	•	•	•	•								•										0.04~0.12	0.10~1.00
		[ WIII G SLEET]																											
			DCMT	070202-VF		•				•													•					0.03~0.10	0.06~1.00
				070204-VF		•				•										•			•					0.05~0.20	0.30~1.20
<u> </u>	D .	VF		11T302-VF	•					•																		0.04~0.15	0.08~1.50
Finishing	2	-		11T304-VF	•	•				•										•			•					0.05~0.20	0.30~1.50
i	•			11T308-VF	•	•														•			•					0.10~0.25	0.30~1.50
			DCMT	070202-VL																								0.02~0.10	0.06~0.80
				070204-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•		•	•	0.04~0.10	0.08~0.90
				070208-VL					•	•				•						•								0.06~0.12	0.10~1.00
5	20	VL		11T302-VL																								0.03~0.10	0.07~0.80
Finishing				11T304-VL	•	•	•	•	•	•				•			•	•	•	•	•		•				•	0.05~0.10	0.10~1.00
<u> </u>	•			11T308-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•		•	•	0.08~0.15	0.10~1.00
				11T312-VL																								0.08~0.15	0.30~1.50
			DCMT	070202-HMP								•													•			0.03~0.12	0.10~1.50
5	20			070204-HMP							•	•		•						•			•		•			0.06~0.17	0.20~2.30
i	5	HMP		070208-HMP							•	•											•		•			0.08~0.23	0.40~2.30
į				11T302-HMP								•								•			•		•			0.04~0.22	0.10~2.00
<u> </u>	6			11T304-HMP		•				•	•	•		•						•			•		•			0.08~0.23	0.30~3.00
Medium to finishing				11T308-HMP							•	•		•						•			•		•			0.10~0.30	0.50~3.00
Z																													
			DCMT	070202-MP	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•				0.04~0.12	0.12~1.80
	n D			070204-MP	•	•	•	•	•	•				•				•	•	•	•	•	•	•				0.05~0.15	0.30~1.80
i				070208-MP	•	•	•	•	•	•				•				•	•	•	•	•	•	•				0.08~0.22	0.30~1.80
inio	2	MP		11T302-MP	•	•	•	•	•	•				•				•	•	•	•	•	•	•				0.04~0.15	0.30~2.00
9	4			11T304-MP	•	•	•	•	•	•				•		•		•	•	•	•	•	•	•				0.08~0.20	0.50~2.30
	•			11T308-MP	•	•	•	•	•	•				•	•	•	•	•	•	•	•	•	•	•				0.10~0.30	0.50~2.30
Medium to finishing	3			11T312-MP														•	•									0.25~0.35	0.80~3.00

**→** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15


→ Code system B34~B35

	Available t	tool holders	
Designation	Page	Designation	Page
SDACR/L	B190	SDQCR/L	B217
SDJCR/L	B123, 191	SDUCR/L	B218
SDNCN	B124, 191	SDZCR/L	B219



## **B** Turning Insert (Positive)





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
07	6.35	2.38	2.8
11	9.525	3.97	4.4



### Rhombic 55° Positive Relief Angle: 7°

	Steel		Р		#		3		<b>\$</b>	\$ #	#	#	•	•	\$	#									Machining types
ဗ္ဗ	Stainless steel		M							3	3	<b>3</b>			<b>3</b>	#	3	#	•	3	3	#			
pie	Cast iron	<b>-</b>	K		#	•	\$	3				<b>3</b>	\$	3									•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	1	N																				•	3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S													•	3	#	•	3	3		•	3	# Interrupted cutting
-	Hardened steel	<b>-</b>	Н																•	3	3		•	3	- Interrupted cutting

				Cer	met	Co	ated								Coa	ted									Unco	ated	Cutting (	Condition
									Ŋ	0	0	2	0				2	LC.	0	0	2	0	2	0	JIICO	aicu		Jonation
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC903	된	H05	fn (mm/rev)	ap (mm)
		DCMT	070202-C25	•	•	•	•		•				•						•	•		•					0.03~0.15	0.30~2.00
_			070204-C25	•	•	•	•	•	•		•		•		•				•	•		•		•			0.05~0.20	0.50~2.50
i iii	C25		070208-C25	•	•	•	•	•	•		•		•		•				•	•		•					0.06~0.25	0.80~2.50
Medium cutting	020		11T302-C25	•	•	•	•	•	•				•						•	•		•					0.04~0.25	0.50~2.50
텵			11T304-C25	•	•	•	•	•	•	•	•		•	•	•				•	•		•		•			0.08~0.30	0.80~3.00
Mec			11T308-C25	•	•	•	•	•	•	•	•		•		•				•	•		•		•			0.10~0.30	1.00~3.00
		DCMT	070204-VP1																								0.05~0.12	0.10~1.50
5	VP1	DCWII	11T304-VP1								-				-				_								0.05~0.12	0.10~1.50
hin	VFI		11T304-VP1								-																0.00~0.20	0.10~1.50
Finishing			111300-471																								0.00~0.20	0.10~1.30
		DCGT	070201-FS																•			•					0.01~0.18	0.03~1.60
			070202-FS																•			•					0.02~0.20	0.04~1.70
6	FS 🚙		11T301-FS																•			•					0.01~0.20	0.04~1.80
Finishing	new		11T302-FS																•			•					0.02~0.23	0.05~2.00
i			11T304-FS																•			•					0.04~0.23	0.08~2.00
	[High precision]		11T308-FS																•								0.06~0.25	0.10~2.20
	[g p.co.c.c]																											
		DCGT	070201MFN-FS																								0.01~0.18	0.03~1.60
			070202MFN-FS																								0.02~0.20	0.04~1.70
5	FS 🚙		11T301MFN-FS																								0.01~0.20	0.04~1.80
hir	new		11T302MFN-FS																								0.02~0.23	0.05~2.00
Finishing			11T304MFN-FS																								0.04~0.23	0.08~2.00
	[ Utra high precision ]		11T308MFN-FS																								0.06~0.25	0.10~2.20
	[]																											
		DCGT	11T301-MS																•			•					0.02~0.23	0.05~2.00
ting	MS		11T302-MS																•			•					0.03~0.25	0.07~2.50
E	new		11T304-MS																•			•					0.05~0.25	0.09~2.50
Medium cutting	[High precision]																											
		DCGT	11T301MFN-MS																•			•					0.02~0.23	0.05~2.00
ing	N/C		11T302MFN-MS																•			•					0.03~0.25	0.07~2.50
cutt	MS		11T304MFN-MS																•			•					0.05~0.25	0.09~2.50
Medium cutting																						-						
Mec	[ Utra high precision ]																											

→ Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15


→ Code system B34~B35



	Available t	tool holders	
Designation	Page	Designation	Page
SDACR/L	B190	SDQCR/L	B217
SDJCR/L	B123, 191	SDUCR/L	B218
SDNCN	B124, 191	SDZCR/L	B219







	Dimension	ons (mm)	
Size	d	t	d₁
07	6.35	2.38	2.8
11	9.525	3.97	4.4

### Rhombic 55° Positive Relief Angle: 7°

	Steel		Р		#		\$	3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							3	3	3				3	#	3	#	•	3	3	#		
pje	Cast iron	4	K		#	•	\$ 3					3	3	3										3	<ul> <li>Continuous cutting</li> </ul>
춫	Non-ferrous metal	4	N																					3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S														•	3	#	•	3	3		3	# Interrupted cutting
	Hardened steel	4	Н																	•	3	3		3	- interrupted cutting

				Cer	met	Coa	ited								Coa	ted									Unco	ated	Cutting C	Condition
	Inserts	D	esignation	90	90	200	200	215	225	120	330	235	330	310	315	115	125	35	8	9	02	은	15	30			fn	ар
			_	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	듣	년2	(mm/rev)	(mm)
		DCGT	070201-VP1					_	_	_	_	_	_	_	_	_	_	_	•		•	•	•		•	_	0.03~0.06	0.06~1.00
	VP1		070202-VP1																•		•	•	•		•		0.03~0.10	0.08~1.50
hing	<b>VPI</b>		070204-VP1																•		•	•	•		•		0.05~0.12	0.10~1.50
Finishing			11T301-VP1																•			•					0.03~0.13	0.06~1.00
"	[High precision]		11T302-VP1																•		•	•	•		•		0.04~0.15	0.08~1.50
			11T304-VP1																•		•	•	•		•		0.06~0.20	0.10~1.50
		DCGT	070201MFN-VP1																•			•					0.03~0.06	0.06~1.00
	VD4		070202MFN-VP1																•			•					0.03~0.10	0.08~1.50
<u>in</u>	VP1		070204MFN-VP1																•			•					0.05~0.12	0.10~1.50
Finishing			11T301MFN-VP1																•			•					0.03~0.13	0.06~1.00
Ē	[ Utra high precision ]		11T302MFN-VP1																•			•					0.04~0.15	0.08~1.50
	[ Otta High precision ]		11T304MFN-VP1																•								0.06~0.20	0.10~1.50
		2005	07000000 1/-																_			_					0.04.0.00	0.04 1.00
		DCGT	0702003R-KF														_		•		_	•					0.01~0.06	0.04~1.30
			070201R-KF														_		•		_	•					0.02~0.08	0.05~1.50
			070202R-KF														-		•		_	•					0.03~0.11	0.06~1.50
			070204R-KF 11T3003R-KF														-		•			•					0.04~0.13	0.04~1.70 0.05~1.50
			11T3003R-KF								-						-		•		_	-						0.05~1.50
	KF		11T301R-KF														-		•		-	•		•			0.03~0.11	0.06~1.70
ing			11T302R-KF														-		•			•					0.04~0.15	0.00~2.00
Finishing			0702003L-KF														-		•			•					0.03~0.16	0.04~1.30
匠	[High precision]		0702000L1KF																•			•					0.02~0.08	0.05~1.50
			070202L-KF																•			•					0.03~0.11	0.06~1.50
			070204L-KF																•			•					0.04~0.13	0.04~1.70
			11T3003L-KF																•			•					0.02~0.08	0.05~1.50
			11T301L-KF																•			•					0.03~0.11	0.06~1.70
			11T302L-KF																•			•					0.04~0.15	0.08~2.00
			11T304L-KF																•			•					0.05~0.16	0.10~2.00
		DCET	0702005MFR-KF																•			•					0.01~0.06	0.04~1.30
			070201MFR-KF																•			•					0.02~0.08	0.05~1.50
			070202MFR-KF																•			•					0.03~0.11	0.06~1.70
	KF		11T3005MFR-KF																•			•					0.02~0.08	0.05~1.50
ם	r\r		11T301MFR-KF																•			•					0.03~0.11	0.06~1.70
Finishing			11T302MFR-KF																•			•					0.04~0.15	0.08~2.00
Finis	[ Utra high precision ]		0702005MFL-KF																•			•					0.01~0.06	0.04~1.30
			070201MFL-KF																•			•					0.02~0.08	0.05~1.50
			070202MFL-KF																•			•					0.03~0.11	0.06~1.70
			11T3005MFL-KF																•			•					0.02~0.08	0.05~1.50
			11T301MFL-KF																•			•					0.03~0.11	0.06~1.70
			11T302MFL-KF																•			•					0.04~0.15	0.08~2.00

Cutting edge geometry A37~A49
 Recommended chip breaker B04~B15


€ Code system B34~B35

	Available t	tool holders	
Designation	Page	Designation	Page
SDACR/L	B190	SDQCR/L	B217
SDJCR/L	B123, 191	SDUCR/L	B218
SDNCN	B124, 191	SDZCR/L	B219



## B Turning Insert (Positive)





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
07	6.35	2.38	2.8
11	9.525	3.97	4.4



### Rhombic 55° Positive Relief Angle: 7°

	Steel		Р		#		3		<b>\$</b>	\$ #	#	#	•	•	\$	#								Machining types
ဗ္ဗ	Stainless steel		M							3	3	3			3	#	3	#	•	<b>3</b>	3	#		
pie	Cast iron	4	K		#	•	3	3				3	\$	3									3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	1	N																				3	General cutting
×	Heat resistant alloy, Titanium alloy		S												•	•	3	#	•	3	3		3	# Interrupted cutting
	Hardened steel	4	Н																•	3	3		3	- interrupted cutting

				Cer	met	Coa	ated								Coa	ted								Unc	oated	Cutting (	Condition
	Inserts	D	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC3400	PC8105	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		DCGT	0702003R-KM															•								0.01~0.06	0.04~1.30
			070201R-KM															•				)				0.02~0.08	0.05~1.50
			070202R-KM															•								0.03~0.11	0.06~1.50
			070204R-KM															•								0.04~0.13	0.04~1.70
			11T3003R-KM															•								0.02~0.08	0.05~1.50
			11T301R-KM															•								0.03~0.11	0.06~1.70
ng			11T302R-KM															•								0.04~0.15	0.08~2.00
ishi	KM		11T304R-KM															•								0.05~0.16	0.10~2.00
Medium to finishing			0702003L-KM															•								0.01~0.06	0.04~1.30
E			070201L-KM															•								0.02~0.08	0.05~1.50
텷	[High precision]		070202L-KM															•								0.03~0.11	0.06~1.50
ž	[1.19.1		070204L-KM															•								0.04~0.13	0.04~1.70
			11T3003L-KM															•								0.02~0.08	0.05~1.50
			11T301L-KM															•								0.03~0.11	0.06~1.70
			11T302L-KM															•								0.04~0.15	0.08~2.00
			11T304L-KM															•								0.05~0.16	0.10~2.00
		DCET	0702005MFR-KM															•								0.01~0.06	0.04~1.30
			070201MFR-KM															•								0.02~0.08	0.05~1.50
			070202MFR-KM															•								0.03~0.11	0.06~1.70
			11T3005MFR-KM															•								0.02~0.08	0.05~1.50
ng			11T301MFR-KM															•								0.03~0.11	0.06~1.70
ishi	KM		11T302MFR-KM															•								0.04~0.15	0.08~2.00
Medium to finishing			0702005MFL-KM															(								0.01~0.06	0.04~1.30
E			070201MFL-KM															(								0.02~0.08	0.05~1.50
ediu	[ Utra high precision ]		070202MFL-KM															(				)				0.03~0.11	0.06~1.70
Š			11T3005MFL-KM																							0.02~0.08	0.05~1.50
			11T301MFL-KM															(								0.03~0.11	0.06~1.70
			11T302MFL-KM															•								0.04~0.15	0.08~2.00

**②** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15 **③** Code system B34~B35

	Available tool holders											
Designation	Page	Designation	Page									
SDACR/L	B190	SDQCR/L	B217									
SDJCR/L	B123, 191	SDUCR/L	B218									
SDNCN	B124, 191	SDZCR/L	B219									

### RC C





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
08	8.0	3.18	3.35
10	10.0	3.97	3.6
12	12.0	4.76	4.2
16	16.0	6.35	5.2
20	20.0	6.35	6.5
25	25.0	7.94	7.25
32	32.0	9.52	9.55

# Round **R° Positive** Relief Angle: 7°

	Steel		Р		#	3		3	3	#	#	#			3		#									Machining types
පු	Stainless steel		M							3	3	3			•	3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	3	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal		N																					•	3	General cutting
Š	Heat resistant alloy, Titanium alloy		S									•				•		3	#	•	3	3		•	3	# Interrupted cutting
	Hardened steel	4	Н																	•	3	3		•	3	


				Cei	met	Coa	ited								Coa	ited									Unco	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
	\/B#	RCMT	0803M0-VM																								0.05~0.30	0.80~2.50
ig i	VM		10T3M0-VM																								0.05~0.35	0.90~3.00
Medium cutting	1		1204M0-VM																								0.10~0.50	1.00~3.50
<u>.</u>			1606M0-VM																								0.13~0.60	1.30~6.50
Med																												
		<b>RCMX</b>	1003M0								•																0.25~0.50	1.50~4.00
			1204M0																								0.30~0.60	2.50~5.00
ig i	Carring		1606M0						•		•		•		•												0.40~0.70	3.00~7.00
ᇹ			2006M0								•																0.48~0.90	3.50~9.00
<u>.</u>			2507M0								•				•												0.55~1.20	4.00~12.00
Medium cutting			3209M0								•				•												0.65~1.50	5.00~15.00

→ Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

€ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
PRDCN	B174	PRGCR/L	B175





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.97	4.4
12	12.0	4.76	4.2

# Square **90° Positive**Relief Angle: 7°

				Cer	rmet	Coa	ated								Coa	ted									Uncoated	Cutting (	Condition
	Inserts	De	esignation	CN1500			CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330				NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01 H05	fn (mm/rev)	ap (mm)
	FP _	SCMT	09T304-FP		•			•																		0.01~0.10	0.10~1.00
Finishing	[Mild steel]		09T308-FP	•	•	•	•		•								•					•				0.04~0.12	0.10~1.00
Finishing	VF	SCMT	09T304-VF						•										•							0.05~0.20	0.30~1.50
		SCMT	09T304-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•			0.05~0.10	0.10~1.00
Finishing	VL		09T308-VL	•	•	•	•	•	•				•			•	•		•	•	•	•	•			0.08~0.15	0.10~1.00
		SCMT	09T304-HMP							•	•								•					•		0.08~0.23	0.30~3.00
<u></u>	НМР		09T308-HMP							•	•								•					•		0.10~0.30	0.50~3.00
ishir			120404-HMP																							0.09~0.27	0.30~3.60
Medium to finishing	C. A.		120408-HMP								•								•					•		0.12~0.36	0.60~3.60
		SCMT	09T304-MP					•	•				•		•	•	•	•	•		•	•				0.05~0.25	0.30~2.80
			09T308-MP						•				•		•	•	•	•	•		•	•				0.10~0.30	0.50~2.80
hing	MP _		120404-MP					•	•								•	•	•							0.10~0.30	0.50~2.80
finis	new		120408-MP					•	•						•	•	•	•	•		•	•				0.15~0.35	0.80~3.50
Medium to finishing			120412-MP																							0.25~0.40	1.00~3.50
		SCMT	060204-C25								•															0.08~0.25	0.40~2.50
gu	C25		09T304-C25	•	•	•	•	•	•		•		•		•				•	•		•				0.08~0.25	0.60~3.00
ishir			09T308-C25	•	•	•	•	•	•	•	•		•	•	•				•	•		•				0.10~0.30	1.00~3.00
o fin			120404-C25	•	•	•	•	•	•				•		•				•	•		•		•		0.10~0.30	0.80~3.80
Medium to finishing			120408-C25	•	•	•		•	•	•	•		•	•	•				•	•		•		•		0.12~0.38	1.20~3.80


Outting edge geometry A37~A49



	Available	tool holders	
Designation	Page	Designation	Page
SSBCR/L	B192	SSKCR/L	B193, 219
SSDCN	B192	SSSCR/L	B193, 245

<sup>◆</sup> Code system B34~B35





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
09	9.525	3.18	3.4
12	12.7	4.76	-
15	15.875	4.76	-
19	19.05	4.76	-
25	25.4	6 35	_

# Square **90° Positive** Relief Angle: 11°

	Steel		Р		#		3	•	\$ \$	#	#	#	•	•	•		#									Machining types
8	Stainless steel		M							3	3	3				3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	3	\$				3	\$	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	•	N																						3	General cutting
×	Heat resistant alloy, Titanium alloy		S									•				•	•	\$	#	•	3	3			3	# Interrupted cutting
	Hardened steel	4	Н																	•	3	\$		•	3	- interrupted cutting

																									_			
					rmet	Coa									Coa										Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
	VL	SPMT	09T304-VL																								0.04~0.18	0.20~1.40
ing	<b>V</b> L		09T308-VL																								0.08~0.22	0.20~1.40
Finishing																												
	VF	SPMT	090304-VF																								0.05~0.20	0.30~1.50
ing	No		090308-VF																								0.10~0.25	0.30~1.50
Finishing	C)																											
	F	SPMR	090304-F																								0.05~0.20	0.30~2.00
ng	<b>F</b>		120304-F						•		•																0.10~0.25	0.50~2.00
Finishing																												
	F	SPGR	090304-F																								0.05~0.20	0.30~2.00
ing			120304-F																								0.10~0.25	0.50~2.00
Finishing																												
ing	M	SPMR							•		•																0.10~0.40	1.00~3.50
cut			120308-M						•		•																0.10~0.40	1.50~4.00
Medium cutting			120312-M								•																0.20~0.40	1.50~4.00
ρι	М	SPGR	090308-M																								0.10~0.40	1.00~3.50
ij	141		120308-M																								0.20~0.40	1.50~4.00
Medium cutting																												
		SPUN	120304																								0.10~0.30	1.00~5.00
			120308																						_		0.15~0.40	1.00~5.00
<u>B</u>			120308SN																								0.15~0.40	1.00~5.00
ishii			150412 190412								•																0.20~0.50	1.00~5.00 1.50~7.00
o fin			190412								_																0.25~0.60	2.00~7.00
Medium to finishing			250620																								0.30~0.80	3.00~1.00
edit	*																										3.00 0.00	3.00 10.0
Σ																												

**→** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

**ᢒ** Code system **B34~B35** 

	Available	tool holders	
Designation	Page	Designation	Page
CSDPN	B181	SSKPR/L	B219
CSKPR/L	B182		





# d d

	Dimension	ons (mm)										
Size	d	t	d <sub>1</sub>									
06	<b>06</b> 6.35 2.38											
07	6.35	2.38	2.8									
09	9.525	3.18	3.4~4.4									
12	12.7	3.18	-									
15	15.875	4.76	-									
19	19.05	4.76	-									

### Square 90° Positive

Relief Angle: 1	l1°
-----------------	-----

	Steel		Р		*	3		3	3	*	*	#		3		#								Machining types
စ္ပ	Stainless steel		M							3	3	3		•	3	#	3	#	•	3	3	#		
pie	Cast iron	4	K		#	3	3					<b>3</b>	\$ 3										3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	1	N																				3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S									•					3	#	•	3	3		3	# Interrupted cutting
	Hardened steel	4	Н																•	3	3		3	- Interrupted cutting

						Coa										ated									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		SPGN	070202																								0.03~0.10	0.50~2.00
			070208																								0.10~0.25	0.70~3.00
			090302																								0.03~0.10	0.50~3.00
			090304																								0.08~0.20	0.70~3.50
			090308																								0.10~0.25	0.70~3.50
			120302																								0.03~0.20	0.50~3.00
			120304																								0.08~0.20	1.00~5.00
			120308								•																0.10~0.25	1.00~5.00
			120312																								0.15~0.30	1.00~5.00
			120316																								0.18~0.33	1.00~5.00
			120402																								0.03~0.20	0.50~3.00
_			120404																								0.08~0.20	1.00~5.00
hing			120408																								0.10~0.25	1.00~5.00
inisi			120412																								0.15~0.30	1.00~5.00
to t			120416																								0.18~0.33	1.00~5.00
Medium to finishing			120430																								0.20~0.60	2.00~5.00
Ned			120440																								0.25~0.70	3.00~5.00
_			150404																								0.08~0.20	1.50~7.00
			150408																								0.10~0.25	1.50~7.00
			150412																								0.15~0.30	1.50~7.00
			150416																								0.18~0.33	1.50~7.00
			150420																								0.20~0.45	1.50~7.00
			190404																								0.08~0.20	1.50~9.00
			190408																								0.10~0.25	1.50~9.00
			190412																								0.15~0.45	1.50~9.00
			190416																								0.18~0.60	1.50~9.00
			190424																								0.25~0.70	2.50~9.00
Đ.		SPGA	060204																								0.50~0.25	0.50~2.00
ishi		0.021	090308T	•																							0.10~0.25	0.70~3.00
to ≣i			090308T-Z																								0.10~0.25	
Medium to finishing			* Note: 08T: corner C0,8 08T-Z: corner R0,8																									
<b>Be</b>			001-2. cuillei Ru,o																									
		SPGT	090304R																								0.08~0.23	0.30~3.00
ing			090308R																								0.10~0.30	0.50~3.00
nish			090304L																								0.08~0.23	0.30~3.00
ij o			090308L				$\neg$												T								0.10~0.30	0.50~3.00
Medium to finishing																												

Cutting edge geometry A37~A49




	Available	tool holders	
Designation	Page	Designation	Page
CSDPN	B181	SSKPR/L	B219
CSKPR/L	B182		

<sup>→</sup> Recommended chip breaker B04~B15

<sup>€</sup> Code system B34~B35





	Dimension	ons (mm)													
Size	. , ,														
06	3.97	1.59	2.16												



### Triangular 60° Positive Relief Angle: 5°

0 \* 0 \* 0 \* 1 \* \* \* 0 0 \* Steel Machining types Workpiece Stainless steel • 3 • 3 • 3 Cast iron Continuous cutting Non-ferrous metal General cutting Heat resistant alloy, Titanium alloy # Interrupted cutting Hardened steel


					Cei	met	Coa	ited								Coa	ated									Unco	oated	Cutting C	Condition
		Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		VL	TBMT	060102-VL																								0.03~0.06	0.05~0.60
Daidaiai	811111111111111111111111111111111111111																												
			TBGT	060102L																					•			0.05~0.20	0.10~1.30
١,	- I			060104L																								0.08~0.20	0.10~1.30
Saidaiai																													

● Cutting edge geometry A37~A49 ● Recommended chip breaker B04~B15

**③** Code system B34∼B35

Available	tool holders
Designation	Page
STUBR/L	B225







	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
06	6.35	2.38	2.8
09	5.56	2.38	2.5
11	6.35	2.38	2.8
16	9.525	3.97	4.4
22	127	4 76	_

# Triangular **60° Positive** Relief Angle: 7°

	Steel		Р		#		\$	3	\$ #	#	#	•		\$	#									Machining types
စ္ပ	Stainless steel		M						3	3	3			3	#	3	#	•	3	3	#			
pie	Cast iron	1	K		#	•	\$ 3				3	3	3									•	3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	1	N																				3	General cutting
×	Heat resistant alloy, Titanium alloy		S												•	3	#	•	3	3			3	# Interrupted cutting
-	Hardened steel	<b>-</b>	Н															•	3	\$		•	3	- Interrupted cutting


				Cer	rmet	Coa	ated							Coa	ted									Unco	ated	Cuttina (	Condition
	Inserts	D	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330			NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
	FP _	TCMT	060201-FP		Ť		_		_								_		_			_		_		0.00~0.08	0.05~0.07
ng	new)		110202-FP		•			•																		0.01~0.10	0.05~0.08
Finishing			110204-FP		•																					0.01~0.10	0.10~0.90
듄	[ Mild steel ]																										
	[	TCMT	110202-VF																							0.03~0.13	0.06~0.70
	VF		110204-VF															•								0.05~0.20	0.30~1.20
ē	VF		110208-VF													П		•								0.10~0.25	0.30~1.20
Finishing			16T302-VF																							0.05~0.15	0.10~1.30
듄			16T304-VF						•				•					•								0.05~0.20	0.30~1.50
		TCMT	090208-VL																							0.08~0.20	0.10~1.20
	VL		110204-VL																							0.05~0.15	0.10~1.30
ng	VL		110208-VL																							0.08~0.20	0.10~1.30
Finishing			16T304-VL	•	•		•	•	•						•	•		•	•	•		•				0.05~0.20	0.30~1.50
듄	Attended		16T308-VL	•	•	•	•	•	•				•		•	•		•	•	•	•	•				0.05~0.20	0.30~1.50
		TCMT	090204-HMP							•													•			0.06~0.17	0.20~2.30
5			090208-HMP																							0.08~0.23	0.40~2.30
iri	HMP		110202-HMP																							0.03~0.15	0.10~1.50
fii			110204-HMP		•				•	•	•		•			_		•			•		•			0.06~0.19	0.20~2.50
욛			110208-HMP								•						_	•					•			0.09~0.26	0.40~2.50
Medium to finishing			16T304-HMP		•					•	•							•			•		•			0.08~0.23	0.30~3.00
₹			16T308-HMP								•		•					•					•			0.10~0.30	0.50~3.00
		TCMT	090204-MP												•	•										0.05~0.18	0.10~1.00
			090208-MP												•	•										0.08~0.20	0.10~1.20
			110202-MP					•	•				•		•	•	•			•						0.03~0.12	0.20~1.50
			110204-MP					•	•				•		•	•				•	•					0.05~0.15	0.20~1.50
hig	MP		110208-MP					•	•				•		•	•		•		•	•					0.10~0.28	0.25~2.00
Medium to finishing	(IEW)		16T302-MP																							0.08~0.25	0.20~1.50
9			16T304-MP	•	•	•	•	•	•				•	•	•	•	•	•	•	•	•	•				0.08~0.20	0.30~2.50
i i			16T308-MP	•	•	•	•	•	•				•	•	•	•	•	•	•	•		•				0.10~0.30	0.50~2.50
Mec			16T312-MP					•	•				•													0.20~0.40	0.50~2.50
			220408-MP																							0.20~0.40	0.50~3.50

→ Cutting edge geometry A37~A49
→ Recommended chip breaker B04~B15

→ Code system B34~B35



	Available t	ool holders	
Designation	Page	Designation	Page
STACR/L	B124, 193	STTCR/L	B194, 246
STFCR/L	B194, 245	STWCR/L	B246
STGCR/L	B194		



	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
08	8.0	3.18	3.35
09	5.56	2.38	2.5
11	6.35	2.38	2.8
16	9.525	3.97	4.4

# Triangular **60° Positive** Relief Angle: 7°

	Steel		Р		#	3	•	\$ \$	#	#	#	•	•	\$	#								Machining types
క్ర	Stainless steel		M						3	3	3			3	#	3	#		3	3	#		
pie	Cast iron	4	K		#	3	\$				3	\$	3									3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	•	N																			3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S												•	3	#		3	3			<u></u>
	Hardened steel	4	Н															•	3	\$		3	# Interrupted cutting

				Се	rme	Coa	ated							(	Coat	ed									Unco	ated	Cutting (	Condition
	Inserts	D	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		TCMT	090204-C25	•	•	•	•		•		•		•		•				•	•		•					0.06~0.18	0.40~2.50
			090208-C25	•	•		•		•				•		•				•	•		•					0.08~0.25	0.80~2.50
g	C25		110202-C25		•		•		•				•						•	•		•					0.04~0.12	0.40~2.00
曹			110204-C25		•		•		•		•		•		•					•		•					0.06~0.20	0.60~2.50
Medium cutting			110208-C25	•	•	•	•		•		•		•		•				•	•		•		•			0.08~0.25	0.80~2.50
edin			16T304-C25	•	•	•	•		•		•		•		•				•	•		•		•			0.08~0.28	0.80~3.00
Ž			16T308-C25	•	•	•	•	•	•	•	•		•		•		_			•		•		•			0.10~0.30	1.00~3.00
	VP1	ТСМТ	16T304-VP1																								0.06~0.20	0.10~1.50
ng	VEI		16T308-VP1																								0.08~0.23	0.10~1.50
Finishing																												
		TCGT	110201-FS																•			•					0.01~0.16	0.03~1.40
	FS		110202-FS																•			•					0.02~0.18	0.04~1.50
Finishing	[High precision]		110204-FS																			•					0.04~0.19	0.06~1.60
		TCGT	110201MFN-FS																								0.01~0.16	0.03~1.40
20	FS		110202MFN-FS																								0.02~0.18	0.04~1.50
Finishing	[Utra high precision]		110204MFN-FS																								0.04~0.19	0.06~1.60
		TCGT	090204-VP1																								0.04~0.18	0.10~1.00
	VP1		16T304-VP1																								0.06~0.20	0.10~1.50
Finishing			16T308-VP1																								0.08~0.23	0.10~1.50
		TCGT	0802003R-KF																								0.01~0.06	0.04~1.30
			080201R-KF																								0.02~0.08	0.05~1.50
	KF		080202R-KF																								0.03~0.11	0.06~1.70
<u></u>			0802003L-KF																T								0.01~0.06	0.04~1.30
Finishing			080201L-KF																T								0.02~0.08	0.05~1.50
ΞĪ			080202L-KF																T								0.03~0.11	0.06~1.70
	[High precision]																											


● Cutting edge geometry A37~A49 ● Recommended chip breaker B04~B15

€ Code system B34~B35

ullet : Stock item

	Available t	tool holders	
Designation	Page	Designation	Page
STACR/L	B124, 193	STTCR/L	B194, 246
STFCR/L	B194, 245	STWCR/L	B246
STGCR/L	B194		





	Dimensio	ons (mm)	
Size	d	t	d₁
06	3.97	1.59	2.15
09	5.56	2.38	2.8
14	8.2	3.0	3.8



# Triangular **60° Positive** Relief Angle: 8°

	Steel		Р		#		3		3	3	#	#	#	•		3		#									Machining types
8	Stainless steel		M								3	3	<b>3</b>				3	#	3	#		3	3	#			
- Be	Cast iron	4	K		#	•	\$	3					<b>3</b>	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	4	N																							3	General cutting
×	Heat resistant alloy, Titanium alloy	4	S														•		3	#	•	3	3			3	# Interrupted cutting
	Hardened steel	4	Н																			3	\$			3	W interrupted cutting

				Cei	rmet	Coa	ited								Coa	ted									Unco	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
<u>n</u>		TOEH	060102L																								0.05~0.17	0.10~1.50
finishing			090204L																								0.05~0.20	0.30~2.50
2			140304L																								0.05~0.25	0.30~2.50
Medium																												


•: Stock item

	Available	tool holders	
Designation	Page	Designation	Page
STFPR/L	B221	STUPR/L	B226
CTFPR/L	B182	CTGPR/L	B182





# Triangular **60° Positive** Relief Angle: 11°





	Dimens	sions (mm)	
Size	d	t	d₁
09	5.56	2.38	3.0
11	6.35	3.18	3.4
16	9 525	3 18~4 76	44


	Steel	4	Р		#	3	•	3	3	#	#	#	•	•	<b>\$</b>		#									Machining types
బ్ర	Stainless steel	<	M							3	3	3			•	3	#	3	#	•	3	3	#			masiming types
Bi.	Cast iron	4	K		#	\$	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	•	N																					•	3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>4</b>	S									•						3	#		3	3		•	3	
	Hardened steel	4	Н																	•	3	3		•	3	# Interrupted cutting

				Cer	met	Coa	ated								Coa	ated									Unco	pated	Cutting C	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	_	PC8115	PC9030	HOH	192	fn (mm/rev)	ap (mm)
		<b>TPMT</b>	090202-FP		•		•		•								•										0.01~0.09	0.05~0.07
			090204-FP		•	•	•		•								•										0.01~0.09	0.10~0.08
	- FD		110302-FP		•	•	•		•								•					•					0.01~0.10	0.05~0.08
ng	FP		110304-FP	•	•	•	•		•								•					•					0.01~0.10	0.10~0.90
Finishing			110308-FP		•	•	•		•								•					•					0.04~0.10	0.10~1.00
뜶			160404-FP		•																						0.01~0.10	0.10~1.00
	-		160408-FP		•																						0.04~0.12	0.10~1.00
	[Mild steel]																											



	Available	tool holders	
Designation	Page	Designation	Page
STFPR/L	B221	STUPR/L	B226
CTFPR/L	B182	CTGPR/L	B182





_	7	- <b>J</b> d1
-	t	≠11°

	Dimens	ions (mm)	
Size	d	t	d <sub>1</sub>
09	5.56	2.38	3.0
11	6.35	3.18	3.4
16	9.525	3.18~4.76	4.4
22	12.7	4.76	-

# Triangular **60° Positive** Relief Angle: 11°


	Steel		Р		#		3		3	3	#	#	#	•		3		#									Machining types
8	Stainless steel		M								3	3	3				3	#	3	#		3	3	#			
pie	Cast iron	4	K		#	•	3	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	1	N																							3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S										•						3	#	•	3	3			3	# Interrupted cutting
	Hardened steel	4	Н																		•	3	3			3	Hinterrupted cutting

				Cer	met		ated								Coa	ted								Unco	oated	Cutting (	Condition
	Inserts	De	esignation	8	8	8	000	15	25	20	30	35	330	310	315	115	22	32	8	3 5	2 2	15	30			fn	ар
				CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	2 9	PC8105	PC8115	PC9030	된	년2	(mm/rev)	(mm)
	\/ <b>-</b>	TPMT	110304-VF						•	_			•						•		•	)		1		0.05~0.20	0.30~1.50
<u>B</u>	VF		110308-VF						•				•									)				0.10~0.25	0.30~1.50
Finishing			160404-VF																							0.05~0.20	0.30~2.00
듄			160408-VF																							0.10~0.25	0.30~2.00
		TPMT	090204-VL																							0.04~0.10	0.10~0.90
	VL		090208-VL																							0.06~0.12	0.10~1.00
g g	VL		110304-VL	•	•	•	•	•	•				•			•	• (	•	• (			•				0.05~0.15	0.10~1.30
Finishing			110308-VL					•									• (	•								0.08~0.20	0.10~1.30
ᇤ			160404-VL																							0.05~0.20	0.30~1.50
			160408-VL																							0.05~0.20	0.30~1.50
		TPMT	090202-MP																							0.03~0.15	0.10~1.00
			090204-MP																							0.05~0.18	0.10~1.00
i i i	MP _		110302-MP																							0.03~0.12	0.20~1.50
Medium to finishing	new		110304-MP		•	•	•	•	•								• (		• (							0.05~0.20	0.20~1.50
5			110308-MP					•	•								• (									0.10~0.28	0.30~2.00
<u>.</u> <u></u>	AS-CA		160402-MP																							0.06~0.20	0.30~2.50
Med			160404-MP					•	•																	0.08~0.20	0.30~2.50
			160408-MP					•	•																	0.10~0.30	0.50~2.50
		TPMR	090202-F																							0.05~0.15	0.10~1.00
	F		090204-F																							0.05~0.15	0.10~1.00
<u> </u>	F		110302-F																							0.05~0.15	0.10~1.50
Finishing			110304-F						•	•	•				•								•			0.05~0.20	0.30~1.50
Ë			110308-F								_															0.05~0.25	0.30~1.50
			160304-F						•	•	•		•								•	)	•			0.08~0.25	0.50~2.00
			160308-F																							0.08~0.25	0.50~3.00
		TPGR	110302-F																							0.05~0.15	0.10~1.50
ng	F		110304-F																							0.05~0.20	0.30~1.50
Finishing			160304-F																							0.08~0.25	0.50~2.00
		TPMR	110304-M																							0.10~0.25	0.70~3.00
ing	M		110308-M								•				•											0.13~0.30	1.00~3.00
Medium cutting	.vi		160304-M						_		•				•											0.10~0.25	1.00~5.00
Ē			160308-M						•	•	•				•											0.13~0.30	1.00~5.00
edii			160312-M								•															0.15~0.35	1.00~5.00
2			220408-M																					_		0.13~0.30	1.50~7.00

→ Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

→ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
STFPR/L	B221	STUPR/L	B226
CTFPR/L	B182	CTGPR/L	B182



	dı 11°
t	''

	Dimens	ions (mm)	
Size	d	t	d₁
09	5.56	2.38	-
11	6.35	2.38~3.18	3.4
16	9.525	3.18~4.76	4.4
22	12.7	4.76	-
27	15.875	4.76~6.35	-
33	19 05	7 94~9 52	7 93

# Triangular **60° Positive** Relief Angle: 11°

	Steel		Р		#		3		3	3	#	#	#			3		#									Machining types
ဗ္ဗ	Stainless steel		M								3	3	3				3	#	3	#	•	3	3	#			
pie	Cast iron	1	K		#	•	3	3					3	3	3										•	3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	1	N																							3	General cutting
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S																3	#	•	3	3		•	3	# Interrupted cutting
	Hardened steel	4	Н																		•	3	3			3	- interrupted cutting

				Car	mot	Coa	atod								Coa	tod								llnes	ated	Cutting	Condition
									LC.	0	0	LC	0				LC.	LC	0	- L			0		aleu	Cutting	Jonation
	Inserts	D	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC813	PC8115	PC9030	PC9030	H05	fn (mm/rev)	ap (mm)
<u>g</u>	М	<b>TPGR</b>	110308-M																							0.13~0.30	1.00~3.00
į	IVI		160308-M																							0.13~0.30	1.00~5.00
Medium cutting																											
		TPUN	090308																							0.10~0.30	
			110208																							0.15~0.40	1.00~3.00
			110304																							0.10~0.30	1.00~3.00
			110308																							0.15~0.40	1.00~3.00
			160304								•															0.10~0.30	1.00~5.00
ing			160308								•								•							0.15~0.40	1.00~5.00
Medium to finishing			160308TN																							0.15~0.40	1.00~5.00
<u>≡</u>			160312																							0.20~0.50	1.50~5.00
Ē			160312TN																							0.20~0.50	1.50~5.00
<u>e</u>			220404																							0.10~0.30	1.50~7.00
2			220408								•															0.15~0.40	1.50~7.00
			220412																							0.20~0.50	1.50~7.00
			220412TN																							0.20~0.50	1.50~7.00
			330620																							0.30~0.70	3.00~10.00
		<b>TPGN</b>	090204																							0.07~0.20	0.70~2.00
			110302																							0.05~0.15	0.50~2.00
			110304								•													•		0.07~0.20	0.70~3.00
			110308								•													•		0.10~0.25	1.00~3.00
			160302																							0.05~0.18	1.00~5.00
			160304						•		•													•		0.07~0.20	1.00~5.00
			160308						•		•													•		0.10~0.25	1.00~5.00
<u>B</u>			160310																							0.10~0.25	1.00~5.00
Medium to finishing			160312																							0.15~0.30	1.00~5.00
i ii e			160316																							0.15~0.30	1.00~5.00
Ē			160404																							0.07~0.20	1.00~5.00
agin			220404								•															0.07~0.20	1.50~7.00
Ž			220408								•															0.10~0.25	1.50~7.00
			220412								•															0.15~0.30	1.50~7.00
			220430																							0.30~0.45	1.50~7.00
			220440																							0.30~0.50	1.50~7.00
			270408																							0.15~0.25	3.00~8.00
			270608																							0.15~0.25	3.00~8.00

Cutting edge geometry A37~A49

→ Recommended chip breaker B04~B15


€ Code system B34~B35

ullet : Stock item



	Available	tool holders	
Designation	Page	Designation	Page
STFPR/L	B221	STUPR/L	B226
CTFPR/L	B182	CTGPR/L	B182







	Dimens	sions (mm)	
Size	d	t	d₁
08	4.76	2.38	2.3
09	5.56	2.38	3.0
11	6.35	3.18	3.4
16	9.525	3.18~4.76	4.4



# Triangular **60° Positive** Relief Angle: 11°

	Steel		Р		#	3		3	3	#	#	#	•		3		#								Machining types
8	Stainless steel		M							\$	3	\$				3	#	\$ *	•	3	3	#			
bje	Cast iron	4	K		#	3	3					3	3	3									•	3	<ul> <li>Continuous cutting</li> </ul>
Ž	Non-ferrous metal	<b>-</b>	N																				•	3	General cutting
š	Heat resistant alloy, Titanium alloy	<b>-</b>	S									•					•	\$ #	•	3	3		•	3	-
	Hardened steel		Н																•	3	3		•	3	# Interrupted cutting


		1																										
					rmet										Coa										Unco	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	192	fn (mm/rev)	ap (mm)
		<b>TPGH</b>	080202L																								0.01~0.12	0.06~1.70
ng			080204L	•																							0.01~0.15	0.08~1.70
Finishing			110202L																								0.01~0.12	0.06~2.00
朣			110204L																								0.01~0.15	0.08~2.00
		<b>TPGT</b>	080202R																								0.05~0.20	0.30~1.50
			110302R																								0.05~0.20	0.30~1.50
			110304R																								0.05~0.20	0.50~2.00
			110308R																								0.07~0.25	0.50~2.00
Ping.			160404R																								0.05~0.20	0.70~3.00
inis			160408R																								0.05~0.20	0.70~3.00
Medium to finishing			080202L																						•		0.05~0.20	0.30~1.50
<u>=</u>			110302L																								0.05~0.20	0.30~1.50
Med			110304L	•																							0.05~0.20	0.50~2.00
_			110308L																								0.07~0.25	0.50~2.00
			160404L																								0.05~0.20	0.70~3.00
			160408L																								0.05~0.20	0.70~3.00
ing		<b>TPGX</b>	090202L																								0.10~0.20	0.30~1.00
inish			090204L		•																						0.10~0.25	0.50~1.00
to f			090208L																								0.10~0.30	1.00~1.00
Medium to finishing			110304L																								0.10~0.25	0.50~1.20
8																												

**③** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15

◆ Code system B34~B35

	Available	tool holders	
Designation	Page	Designation	Page
STFPR/L	B221	STUPR/L	B226
CTFPR/L	B182	CTGPR/L	B182





	Dimens	ions (mm)	
Size	d	t	d₁
11	6.35	3.18	2.8
16	9.525	4.76	4.4

### Rhombic 35° Positive Relief Angle: 5°

	Steel		Р		#		\$	3	\$ #	#	#	•		\$	#									Machining types
စ္ပ	Stainless steel		M						3	3	3			3	#	3	#	•	3	3	#			
pie	Cast iron	1	K		#	•	\$ 3				3	3	3									•	3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	1	N																				3	General cutting
×	Heat resistant alloy, Titanium alloy		S												•	3	#	•	3	3			3	# Interrupted cutting
-	Hardened steel	<b>-</b>	Н															•	3	\$		•	3	- Interrupted cutting

				Cer	rmet	Coa	ated								Coa	ted									Unco	ated	Cutting (	Condition
	Inserts	D	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		VBMT						•																			0.01~0.10	0.05~0.08
5	FP new		110304-FP		•			•																			0.01~0.10	0.10~0.90
i	new		110308-FP		•			•																			0.01~0.10	0.10~1.00
Finishing			160404-FP	•	•	•	•	•	•								•					•					0.01~0.10	0.10~1.00
	[Mild steel]		160408-FP	•	•	•	•		•								•										0.04~0.12	0.10~1.00
		VBMT	110302-VB																								0.05~0.15	0.20~1.20
			110304-VB																								0.06~0.18	0.20~1.20
			110308-VB																								0.08~0.20	0.60~1.20
hing	VB		160402-VB																								0.06~0.20	0.05~1.00
Finishing			160404-VB	•	•				•																		0.08~0.20	0.20~1.50
ш			160408-VB	•	•				•																		0.10~0.23	0.50~1.50
			160412-VB																								0.12~0.25	0.80~1.50
		VBMT	160404-VF		•				•				•						•			•					0.05~0.20	0.30~1.00
ing	VF	A DIAL I	160404-VF	-	•														•							_	0.05~0.20	0.30~1.00
Finishing			100400 VI																								0.10-0.25	0.00*1.00
		<b>VBMT</b>	110302-VL																								0.03~0.20	0.20~1.20
			110304-VL																								0.04~0.20	0.20~1.20
_			110308-VL																								0.08~0.20	0.20~1.20
Finishing	VL		160402-VL																								0.03~0.20	0.30~1.50
inis	S. Mary		160404-VL		•		•		•				•				•		•	•		•	•				0.05~0.20	0.30~1.50
"			160408-VL	•	•	•	•	•	•				•			•	•	•	•	•	•	•	•				0.10~0.20	0.30~1.50
			160412-VL													•	•	•			•	•	•				0.10~0.25	0.30~1.50
6		VBMT	110304-HMP							•														•			0.03~0.20	0.15~2.70
shin			110308-HMP							•																	0.05~0.25	0.40~2.70
fini	HMP		160404-HMP							•	•		•		•				•			•		•			0.07~0.20	0.20~2.70
ם			160408-HMP						•	•	•		•						•			•		•			0.09~0.27	0.50~2.70
Medium to finishing			160412-HMP																								0.11~0.32	0.50~2.70
Σ		VBMT	110302-MP																								0.04~0.14	0.20~1.50
		A DIAI I	110302-MP					•	•								•										0.04~0.14	0.20~1.50
ng			110304-MP					•	•																		0.10~0.28	0.20~1.50
ishi			160402-MP																								0.10~0.28	0.30~2.00
o fin	MP		160404-MP											•			•		•				_				0.08~0.10	0.25~2.00
표			160404-MP		•				•				•	•	•	•	•	•	•	•	•	•					0.00~0.20	0.50~2.00
Medium to finishing			160412-MP		•			•	•				•			•	•	•	•	_	•	•	•				0.10~0.25	0.50~2.30
◙																											5.10 0.00	5.00 2.00




	Available t	cool holders	
Designation	Page	Designation	Page
SVABR/L	B195	SVVBN	B196
SVHBR/L	B195	SVQBR/L	B222
SVJBR/L	B125, 195	SVUBR/L	B223

**<sup>→</sup>** Cutting edge geometry A37~A49 **→** Recommended chip breaker B04~B15

<sup>€</sup> Code system B34~B35

ullet : Stock item





	Dimens	ions (mm)	
Size	d	t	d₁
11	6.35	2.38~3.18	2.8~3.4
16	9.525	4.76	4.4

# Rhombic **35° Positive** Relief Angle: 5°

	Steel		Р		#	•	3		3	3	#	#	#	•	•	3		#									Machining types
8	Stainless steel		M								3	3	3				3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	3	3					3	3	3										•	3	■ Continuous cutting
ž	Non-ferrous metal	-	N																							3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	_	S														•	•	3	#	•	3	3				# Interrupted cutting
	Hardened steel	<b>-</b>	Н																		•	3	3			3	- interrupted cutting


					rmet										Coa										Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	191	H05	fn (mm/rev)	ap (mm)
ē		VBMT	160404		_				_	•	•			•						_		_	_	•		_	0.07~0.20	0.50~1.50
nishii			160408						•	•	•				•									•			0.15~0.25	0.70~2.00
Medium to finishing   Medium to finishing																												
<u> </u>		<b>VBGT</b>	160404																								0.07~0.20	0.50~1.50
nish			160408																								0.15~0.25	0.70~2.00
Medium to fi																												
		VBMT	160402-VP1																								0.04~0.20	0.16~1.50
ō	VP1		160404-VP1																								0.05~0.20	0.18~1.80
Finishing	VPI		160408-VP1																								0.06~0.20	0.20~1.80
Ë																												
		<b>VBGT</b>	110301-FS																•			•					0.01~0.16	0.03~1.40
			110302-FS																•			•					0.02~0.18	0.04~1.50
	<b>E</b> 0		110304-FS																•			•					0.04~0.19	0.06~1.60
ing	FS		160401-FS																•			•					0.01~0.16	0.04~1.80
Finishing			160402-FS																•								0.02~0.18	0.05~2.00
匝	[High precision]		160404-FS																•			•					0.04~0.19	0.08~2.00
			44000411511 50																								001.010	0.00 4.40
		VBGT	110301MFN-FS																		_						0.01~0.16	0.03~1.40
			110302MFN-FS				_								_				_		-						0.02~0.18	0.04~1.50
	EG		110304MFN-FS				_												_		-						0.04~0.19	0.06~1.60
i i i	FS		160401MFN-FS				-												-		-						0.01~0.16	0.04~1.80
Finishing			160402MFN-FS 160404MFN-FS				_												-		-		-				0.02~0.10	0.05~2.00
	[ Utra high precision ]		100404WFN-F3																								0.04~0.19	0.00~2.00
		VBGT	110302-VP1																								0.03~0.10	0.08~1.50
			160402-VP1																								0.04~0.20	0.16~1.50
و	VP1		160404-VP1																								0.05~0.20	0.18~1.80
Finishing																												

**→** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

→ Code system B34~B35

	Available t	ool holders	
Designation	Page	Designation	Page
SVABR/L	B195	SVVBN	B196
SVHBR/L	B195	SVQBR/L	B222
SVJBR/L	B125, 195	SVUBR/L	B223





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.8

# Rhombic **35° Positive** Relief Angle: 5°

	Steel		Р		#		3		3	3	#	#	#	•	•	3		#									Machining types
క్ర	Stainless steel		M								3	3	3				3	#	3	#		3	3	#			
çpie	Cast iron	4	K		#	•	\$	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
놋	Non-ferrous metal		N																							3	General cutting
ĕ	Heat resistant alloy, Titanium alloy		S																3	#	•	3	3			3	# Interrupted cutting
	Hardened steel		Н																		•	3	3			3	- interrupted cutting


				Cer	met	Coa	ited								Coa	ited									Unc	oated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		VBGT	1103003R-KF																			•					0.01~0.06	0.04~1.30
			110301R-KF																•								0.02~0.08	0.05~1.50
5	KF		110302R-KF																•								0.03~0.13	0.06~1.70
Finishing			1103003L-KF																•			•					0.01~0.06	0.04~1.30
inis			110301L-KF																			•					0.02~0.08	0.05~1.50
	[ High precision ]		110302L-KF																•								0.03~0.13	0.06~1.70
		<b>VBGT</b>	1103003R-KM																								0.01~0.06	0.04~1.30
ng			110301R-KM																								0.02~0.08	0.05~1.50
ishi	KM		110302R-KM																								0.03~0.13	0.06~1.70
ij	TANI		1103003L-KM																								0.01~0.06	0.04~1.30
Medium to finishing			110301L-KM																								0.02~0.08	0.05~1.50
gin	[ High precision]		110302L-KM																								0.03~0.13	0.06~1.70
Me																												

→ Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15 → Code system B34~B35

	Available t	cool holders	
Designation	Page	Designation	Page
SVABR/L	B195	SVVBN	B196
SVHBR/L	B195	SVQBR/L	B222
SVJBR/L	B125, 195	SVUBR/L	B223







	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
08	4.76	2.38	2.3
11	6.35	3.18	2.8~3.4
16	9.525	4.76	4.4

# Rhombic **35° Positive** Relief Angle: 5°

	Steel		Р		#	•	\$		3	3	#	#	#	•	•	3		#									Machining types
8	Stainless steel		M								3	3	3				3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	3	3					3	3	3										•	3	■ Continuous cutting
ž	Non-ferrous metal	-	N																							3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	_	S														•	•	3	#	•	3	3				# Interrupted cutting
	Hardened steel	<b>-</b>	Н																		•	3	3			3	- interrupted cutting

					met										Coa									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		VCMT	080202-FP					•															Ī			0.01~0.10	0.05~0.08
			080204-FP				•	•																		0.01~0.10	0.10~0.90
ng	FP new		080408-FP				•	•																		0.04~1.00	0.10~1.00
Finishing	The state of the s		160404-FP																							0.01~0.10	0.10~1.00
ᄩ	[Mild steel]		160408-FP	•	•		•	•	•								•									0.04~0.12	0.10~1.00
		VCMT	080202-VF																							0.05~0.20	0.30~1.00
6	VF		080204-VF										•													0.10~0.25	0.30~1.00
ië	VI		110304-VF						•																	0.03~0.18	0.15~1.20
Finishing			160404-VF						•				•													0.04~0.20	0.15~1.50
		VCMT	080202-VL					•	•				•						•							0.03~0.08	0.10~0.80
			080204-VL					•	•				•						•							0.04~0.10	0.10~0.90
	3.00		160404-VL					•	•							•	•	•			• (					0.05~0.20	0.30~1.50
hing	VL		160408-VL					•	•								•	•			• (					0.05~0.20	0.30~1.50
Finishing	-		160412-VL																							0.10~0.25	0.30~1.50
Medium to finishing	НМР	VCMT	160404-HMP 160408-HMP							•	•								•		(		•			0.10~0.25 0.13~0.33	0.30~2.60
		VCMT	080202-MP					•	•																	0.03~0.15	0.10~1.00
			080204-MP					•	•										T							0.05~0.18	0.10~1.00
<u>6</u>			110302-MP																							0.06~0.18	0.20~1.80
Medium to finishing	RAP.		110304-MP																							0.06~0.18	0.20~1.80
fini	MP new		160404-MP					•	•						•	•	•	•			• (					0.08~0.18	0.30~2.00
5			160408-MP					•	•						•	•	•	•	•		• (					0.10~0.23	0.50~2.30
뺽			160412-MP													•	•	•			• (					0.10~0.33	0.50~2.30
Me																											
		VCMT	160404-VP1																							0.05~0.20	0.18~1.80
gu	VP1		160408-VP1																							0.06~0.20	0.20~1.80
Finishing																											


**→** Cutting edge geometry A37~A49 → Recommended chip breaker B04~B15

€ Code system B34~B35

	Available to	ol holders	
Designation	Page	Designation	Page
SVJCR/L	B125, 196, 222	SVQCR/L	B223
SVVCN	B196	SVUCR/L	B223







	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.8~3.4
12	7.5	3.18	2.8
16	9.525	4.76	4.4

### Rhombic 35° Positive Relief Angle: 7°

	Steel		Р		#		3		3	3	#	#	#	•	•	\$	#									Machining types
8	Stainless steel		M								3	3	3			3	#	3	#		3	3	#			
cpie	Cast iron		K		#	•	\$	3					3	3	3									•	3	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	1	N																					•	3	General cutting
×	Heat resistant alloy, Titanium alloy		S														•	\$	#	•	3	3		•	3	# Interrupted cutting
	Hardened steel		Н																	•	3	3			3	- interrupted cutting

				Cer		Coa	ated								Coa										Unco	ated	Cutting (	Condition
	Inserts	D	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	된	H05	fn (mm/rev)	ap (mm)
		VCGT	110301-FS		Ü	0	0	_	_	_	_	_	_	_	_	_	_		•	<u></u>	<u></u>	•		-	_	_	0.01~0.16	0.03~1.40
			110302-FS																•			•					0.02~0.18	0.04~1.50
	=0		110304-FS														Т		•			•					0.04~0.19	0.06~1.60
jing	FS		160401-FS														П		•			•					0.01~0.16	0.04~1.80
Finishing			160402-FS																•			•					0.02~0.18	0.05~2.00
"	[High precision]		160404-FS																•			•					0.04~0.19	0.08~2.00
		VCGT	110301MFN-FS																								0.01~0.16	0.03~1.40
			110302MFN-FS																								0.02~0.18	0.04~1.50
	FC		110304MFN-FS														Т		Т								0.04~0.19	0.06~1.60
Jing	FS		160401MFN-FS														П		Т								0.01~0.16	0.04~1.80
Finishing			160402MFN-FS																								0.02~0.18	0.05~2.00
<b>L</b>	[ Utra high precision ]		160404MFN-FS																								0.04~0.19	0.08~2.00
<b>T</b>		VCGT	110301-MS																•			•					0.02~0.23	0.05~2.00
ŧ	MS		110302-MS																•			•					0.03~0.25	0.07~2.50
no un			110304-MS																•			•					0.05~0.25	0.09~2.50
Medium cutting	[High precision]																											
		VCGT	110301MFN-MS																•			•					0.02~0.23	0.05~2.00
ting			110302MFN-MS																•								0.03~0.25	0.07~2.50
m cul	MS		110304MFN-MS																•			•					0.05~0.25	0.09~2.50
Medium cutting	[ Utra high precision ]																											
		VCGT	1203008FN-MS																•			•					0.02~0.20	0.04~1.80
JG			120301FN-MS																•			•					0.03~0.26	0.06~2.20
曹	MS₁∰		120302FN-MS																•								0.05~0.28	0.08~2.80
Medium cutting	[ Utra high precision ]		120304FN-MS																•			•					0.06~0.30	0.10~2.80
		VCGT	110301-VP1																•		•	•	•		•		0.02~0.15	0.05~0.50
			110302-VP1																•		•	•	•		•		0.02~0.18	0.10~1.00
ng	VP1		110304-VP1																•		•	•	•		•		0.03~0.18	0.15~1.20
Finishing	87		160404-VP1						•																		0.05~0.20	0.18~1.80
蓝	[High precision]		160408-VP1					•																			0.06~0.20	0.20~1.80


Cutting edge geometry A37~A49
 Recommended chip breaker B04~B15

**③** Code system B34∼B35



	Available to	ol holders	
Designation	Page	Designation	Page
SVJCR/L	B125, 196, 222	SVQCR/L	B223
SVVCN	B196	SVUCR/L	B223





	Dimension	ons (mm)	
Size	d	t	d <sub>1</sub>
11	6.35	3.18	2.8~3.4
12	7.5	3.18	2.8

# Rhombic **35° Positive** Relief Angle: 7°


	Steel		Р		#	•	\$		3	3	#	#	#	•	•	<b>3</b>		#									Machining types
8	Stainless steel		M								<b>3</b>	3	3				3	#	3	#	•	3	3	#			
pie	Cast iron	4	K		#	•	3	3					3	3	3										•	3	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	•	N																						•	3	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S														•		3	#	•	3	3				# Interrupted cutting
	Hardened steel		Н																			3	3			3	- interrupted cutting

				Cer	met	Coat	ed								Coa	ted									Unco	ated	Cutting (	Condition
	Inserts	D	esignation	CN1500	CN2500	CC1500	CCS200	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	_	2	fn	ap
		VCCT	440004145111104	5	S	8	3	2	2	2	2	2	2	2	2	2	2			2	2	<u>S</u>	2	2	된	H05	(mm/rev)	(mm)
		VCGT	110301MFN-VP1				-												•			•					0.02~0.15	0.05~0.50
			110302MFN-VP1				$\dashv$		-								-		•		-	•					0.02~0.18	0.10~1.00
ng	VP1		110304MFN-VP1 1203008FN-VP1				$\dashv$										_		•								0.03~0.18	0.15~1.20
Finishing	0		1203006FN-VP1				$\dashv$												-		-						0.03~0.12	0.06~1.20
듄	[ Utra high precision ]		120301FN-VP1 120302FN-VP1				$\dashv$		-						-		-		-		-						0.04~0.15	0.08~1.20
	[ Out might precision]		120302FN-VF1				$\dashv$		-								-		-		-						0.04~0.13	0.00~1.20
			120304FN-VF1				+																				0.00~0.20	0.10~1.50
		VCGX	120300MFR-VP1				$\dashv$												•			•					0.02~0.10	0.05~0.50
			120301MFR-VP1				$\exists$												•			•					0.02~0.15	0.05~0.50
ing	VP1		120302MFR-VP1				$\forall$												•			•					0.02~0.18	0.10~1.00
Finishing			120304MFR-VP1				T												•			•					0.03~0.20	0.12~1.20
i.	[ Utra high precision ]		120308MFR-VP1				T												•			•					0.05~0.20	0.15~1.20
			-																									
		VCGT	1103003R-KF																								0.01~0.06	0.04~1.30
			110301R-KF																								0.02~0.08	0.05~1.50
ng	KF		110302R-KF																					•			0.03~0.13	0.06~1.70
Finishing	0		1103003L-KF																								0.01~0.06	0.04~1.30
造	[High precision]		110301L-KF																								0.02~0.08	0.05~1.50
	[riight precision]		110302L-KF																								0.03~0.13	0.06~1.70
		VCET	1103005MFR-KF														_		•			•					0.01~0.06	0.04~1.30
			110301MFR-KF															_	•			•					0.02~0.08	0.05~1.50
Finishing	KF		110302MFR-KF						_									_	•		_	•					0.03~0.11	0.06~1.70
nist			1103005MFL-KF																•			•					0.01~0.06	0.04~1.30
证	[ Utra high precision ]		110301MFL-KF				4												•			•					0.02~0.08	0.05~1.50
			110302MFL-KF																								0.03~0.11	0.06~1.70
		VOCT	4400000D K**				_																				0.04 0.00	0.04 4.00
		VCGT	1103003R-KM				$\dashv$												-								0.01~0.06	0.04~1.30
- ED-	KM		110301R-KM				$\dashv$		_										_		_			•			0.02~0.08	0.05~1.50 0.06~1.70
Finishing	LZIVI		110302R-KM 1103003L-KM				$\dashv$		-										+		-			_			0.03~0.13	0.06~1.70
inis			1103003L-KM				$\dashv$		-										+		-						0.01~0.06	0.04~1.30
-	[High precision]		110301L-KM				+												H		-						0.02~0.08	0.05~1.50
			110302L-KW				$\dashv$												_								0.00 ~0.10	0.00~1.70
<b>D</b>		VCET	1103005MFR-KM				$\dashv$												•			•					0.02~0.08	0.05~1.50
shin	1/14		110301MFR-KM				$\dashv$												•			•					0.03~0.11	0.06~1.70
finis	KM		110302MFR-KM				$\dashv$												•			•					0.04~0.15	0.08~2.00
n to			1103005MFL-KM				$\dashv$												•			•					0.02~0.08	0.05~1.50
Medium to finishing	[ Utra high precision ]		110301MFL-KM				$\forall$												•			•					0.03~0.11	0.06~1.70
₹			110302MFL-KM																•			•					0.04~0.15	0.08~2.00

● Cutting edge geometry A37~A49 ● Recommended chip breaker B04~B15 ● Code system B34~B35

	Available tool holders												
Designation	Page	Designation	Page										
SVJCR/L	B125, 196, 222	SVQCR/L	B223										
SVVCN	B196	SVUCR/L	B223										





		Dimension	ons (mm)	
İ	Size	d	t	d₁
	08	6.35	2.38	2.3
	11	6.35	3.18	2.8



### Rhombic 35° Positive Relief Angle: 11°


Steel • \* • \* • \* \* \* \* • • \* Machining types Workpiece Stainless steel • Cast iron Continuous cutting Non-ferrous metal General cutting Heat resistant alloy, Titanium alloy # Interrupted cutting Hardened steel

				Cer	met	Coa	ted								Coa	ted									Unco	ated	Cutting (	Condition
	Inserts	De	esignation	CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	돧	H05	fn (mm/rev)	ap (mm)
		VPGT	110301-VP1																•		•	•	•				0.02~0.15	0.05~0.50
ng	VP1		110302-VP1																•		•						0.02~0.18	0.10~1.00
Finishing			110304-VP1																•		•	•	•				0.03~0.18	0.15~1.20
늍	[ High precision ]																											
		<b>VPGT</b>	110301MFN-VP1																•			•					0.02~0.15	0.05~0.50
g	VP1		110302MFN-VP1																•			•					0.02~0.18	0.10~1.00
Finishing			110304MFN-VP1																•			•					0.03~0.18	0.15~1.20
虚	[ Utra high precision ]																											
	KF	VPET	0802005MFR-KF																•			•					0.01~0.12	0.05~0.50
			080201MFR-KF																•			•					0.02~0.15	0.05~0.50
5			080202MFR-KF																•			•					0.02~0.18	0.10~1.00
Finishing	-		0802005MFL-KF																•			•					0.01~0.12	0.05~0.50
iii	[ Utra high precision ]		080201MFL-KF																•			•					0.02~0.15	0.05~0.50
	[ odd nigh prodolom]		080202MFL-KF																•			•					0.02~0.18	0.10~1.00
		VPET	0802005MFR-KM																•			•					0.01~0.12	0.05~0.50
g			080201MFR-KM																•			•					0.02~0.15	0.05~0.50
ishi	KM		080202MFR-KM																•			•					0.02~0.18	0.10~1.00
ofii	-		0802005MFL-KM																•			•					0.01~0.12	0.05~0.50
Medium to finishing	filling blok magaintee 1		080201MFL-KM																•			•					0.02~0.15	0.05~0.50
edic	[ Utra high precision ]		080202MFL-KM																•								0.02~0.18	0.10~1.00
Z																												

Outting edge geometry A37~A49 → Recommended chip breaker B04~B15 → Code system B34~B35

Available tool holders												
Designation	Page	Designation	Page									
SVABR/L	B195	SVVBN	B196									
SVJBR/L	B125, 195											





	Dimension	ons (mm)	
Size	d	t	d₁
02	3.97	1.59	2.2
S3	4.76	2.38	2.4



# Trigon **80° Positive** Relief Angle: 5°

Hardened steel

				Cei	met	Coa	ated								Co	oate	d								Unco	ated	Cutting C	Condition
	Inserts	Designation		CN1500	CN2500	CC1500	CC2500	NC3215	NC3225	NC3120	NC3030	NC3235	NC5330	NC6310	NC6315	NC9115	NC9125	NC9135	PC5300	PC5400	PC8105	PC8110	PC8115	PC9030	H01	H05	fn (mm/rev)	ap (mm)
		<b>WBGT</b>	020102R																								0.01~0.05	0.10~0.30
g			S30204R																								0.01~0.10	0.10~0.50
ishin			020102L																					•	•		0.01~0.08	0.10~0.40
ii.			S30202L																								0.01~0.08	0.10~0.40
E			S30204L																								0.01~0.10	0.10~0.50
Medium to finishing																												

Cutting edge geometry A37~A49

€ Code system B34~B35

Available to	ool holders
Designation	Page
SWUBR/L	B227

### **Technical Information for Aluminum**

### AK special chip breaker for aluminum

- Unique and 3-dimensional rake angle controls chip breaking and chip flow ensuring longer tool life and reducing cutting load
- High rake angle at cutting edge part reduces cutting load to increase tool life
- Buffed finish on top face controls chip flow reducing built-up edge



- High rake angle & tabby pattern chip pocket Low cutting load
- 2 Unique rake angle design Effective chip breaking and good chip flow
- 1 Unique and 3-dimensional top face Longer tool life & Excellent surface roughness
- 4 Tabby pattern & Sharp cutting edge Distributing cutting load, long tool life
- 6 Buffed on top face Excellent machining, Reducing built-up edge, Excellent chip flow


### AR special chip breaker for aluminum

• AR chip breaker ensures reliability and good cutting performance at high feed, speed and interrupted machining




- Flat corner cutting edge improved productivity at high feed machining and ensures good surface roughness and reliability owing to strong cutting edge
- 2 Specially buffed on top face controls chip flow reducing built-up edge
- KORLOY's own technology applied for cutting edge and corner shape controlling chip flow ensures longer tool life
- 4 KORLOY special chip breaker design controls chip flow at high speed machining

### AK and AR chip breaker specially developed for aluminum



	Recommendation range	Grades
AK	ap = 0.1~5.0 mm fn = 0.03~0.5 mm/rev	H01 (Uncoated cemented carbides K10~K20) ND1000 (Diamond coating) PD1000 (DLC coating)
AR	ap = 0.5~6.0 mm fn = 0.05~0.6 mm/rev	H01 (Uncoated cemented carbides K10~K20) ND1000 (Diamond coating) PD1000 (DLC coating)



### Features of H01 and cutting conditions

- Good for aluminum and alloy steel machining Surface treatment reduces built-up edge
- 3-dimensional design reduces cutting resistance and ensures high machinability in high feed and speed machining

Work	piece	Hardness (HB)	kc (MPa)	vc (m/min)	fn (mm/rev)
Aluminum alloy	before heat treatment	50~70	500~600	1000~2500	0.1~0.6
(forged)	after heat treatment	90~110	700~900	300~1000	0.1~0.5
Aluminum alloy	before heat treatment	70~80	700~800	300~1000	0.1~0.6
(cast)	after heat treatment	80~100	800~950	200~600	0.1~0.4
Copper alloy	_	90~110	700	250~600	0.1~0.5
Non-ferrous metal, etc.	Non-ferrous metal, etc. –		1700	150~300	0.1~0.6














	Dimensions (mm)													
Size	d	t	d₁											
06	6.35	2.38	2.8											
09	9.525	3.97	4.4											
12	12.7	4.76	5.5											


	V
Relief Angle: 7°	

	Steel	F	•					
క్ర	Stainless steel	N	VI					$\vdash$
bje.	Cast iron	, I	<b>(</b>					1
Ž	Non-ferrous metal	1	N.	#	•	#	#	1
Š	Heat resistant alloy, Titanium alloy	5						1
	Hardened steel	H	1					

Machining types

- Continuous cutting
- General cutting
- # Interrupted cutting

				Coated		Unco	oated	Cutting (	Condition
Inserts	0	esignation	PC5040	PD1005	PD1010	Ð	H05	fn (mm/rev)	ap (mm)
	CCGT	060202-AK	•			•	•	0.01~0.12	0.05~3.0
		060204-AK	•		•	•	•	0.02~0.15	0.10~3.0
		060208-AK				•	•	0.02~0.20	0.10~4.0
		09T302-AK	•		•	•	•	0.02~0.20	0.05~3.0
		09T304-AK	•		•	•	•	0.02~0.30	0.10~5.0
		09T308-AK	•			•	•	0.03~0.50	0.10~5.0
		120402-AK				•	•	0.02~0.30	0.05~4.0
ΔK		120404-AK	•		•	•	•	0.03~0.50	0.10~5.0
AK		120408-AK				•	•	0.04~0.80	0.10~5.5
	CCGT	060202-AR 060204-AR				•	•	0.02~0.30 0.03~0.35	0.30~4.0 0.50~4.5
		060204-AR						0.04~0.50	0.50~4.5
		09T302-AR				•	•	0.03~0.45	0.30~4.0
		09T304-AR				•	•	0.04~0.50	0.50~4.5
		09T308-AR				•	•	0.05~0.60	0.50~4.0
		120402-AR						0.04~0.50	0.30~5.0
		120404-AR				•	•	0.05~0.60	0.50~6.0
AR		120408-AR				•	•	0.06~0.65	0.50~6.0
AR		120412-AR				_		0.08~0.70	0.50~6.5



→ Recommended chip breaker B04~B15

◆ Code system B34~B35


Available tool holders							
Designation Page Designation Page							
SCACR/L	B123, 190	SCLCR/L	B123, 190, 215				

## B Aluminum Insert (Positive)









Dimensions (mm)							
Size d t d <sub>1</sub>							
07	6.35	2.38	2.8				
11	9.525	3.97	4.4				

Rnombic 33 Positive
Relief Angle: 7°
Charl

	Steel	Р				
8	Stainless steel	M				
Bi.	Cast iron	K				
ž	Non-ferrous metal	N	Þ	#	#	*
×	Heat resistant alloy, Titanium alloy	S				
	Hardened steel	Н				

Machining types

Continuous cutting

**♣** General cutting

# Interrupted cutting

	Hard	dened steel	Н							
					Coated		Unc	oated	Cutting (	Condition
	Inserts	D	esignation	PC5040	PD1005	PD1010	H0.1	H05	fn (mm/rev)	ap (mm)
		DCGT	070202-AK	•			•	•	0.01~0.20	0.05~3.00
			070204-AK	•		•	•	•	0.02~0.30	0.10~4.00
			070208-AK	•			•	•	0.03~0.40	0.10~4.00
			11T302-AK	•		•	•	•	0.02~0.30	0.05~4.00
			11T304-AK	•		•	•	•	0.03~0.50	0.10~5.00
			11T308-AK	•		•	•	•	0.03~0.50	0.10~5.00
			11T312-AK				•	•	0.04~0.60	0.15~5.00
	AK									
		DCGT	070202-AR				•	•	0.02~0.30	0.30~4.00
			070204-AR				•	•	0.03~0.40	0.50~5.00
			070208-AR				•	•	0.04~0.50	0.50~5.00
			11T302-AR						0.03~0.45	0.30~6.00
			11T304-AR				•	•	0.04~0.50	0.50~6.00
			11T308-AR				•	•	0.05~0.60	0.50~6.00
			11T312-AR				•	•	0.08~0.65	0.50~6.50
,	AR									

Cutting edge geometry A37~A49

€ Code system B34~B35



Available tool holders							
Designation Page Designation Page							
SDACR/L	B190	SDQCR/L	B217				
SDJCR/L	B123, 191	SDUCR/L	B218				
SDNCN	B124, 191	SDZCR/L	B219				

## Aluminum Insert (Positive)



# Round **Positive** Relief Angle: 7°





	Dimensions (mm)								
Size d t d <sub>1</sub>									
06	6.0	2.38	2.8						
08	8.0	3.18	3.35						
10	10.0	3.18~3.97	4.4						
12	12.0	4.76	4.4						

	Steel	Р							Г
8	Stainless steel	M							
pje	Cast iron	K							
ž	Non-ferrous metal	N	D	#	•	#	3	#	
×	Heat resistant alloy, Titanium alloy	S							
	Hardened steel	Н							

Machining types Continuous cutting General cutting # Interrupted cutting

	rdened steel	H							
				Coated		Unco	ated	Cutting C	Condition
Inserts	D	esignation	PC5040	PD1005	PD1010	H01	H05	fn (mm/rev)	ap (mm)
	RCGT	0602M0-AK				•	•	0.05~0.20	0.50~2.00
		0803M0-AK				•	•	0.05~0.25	0.50~2.50
		1003M0-AK				•	•	0.10~0.30	1.00~3.00
		1204M0-AK				•	•	0.10~0.35	1.00~3.50
AK									
	RCGT	0602M0-AR 0803M0-AR						0.05~0.20 0.05~0.25	0.50~2.00 0.50~2.50
		1003M0-AR				•	•	0.10~0.30	1.00~3.00
		10T3M0-AR						0.10~0.30	1.00~3.00
		1204M0-AR						0.10~0.35	1.00~3.50
AR									

**②** Cutting edge geometry A37~A49 **③** Recommended chip breaker B04~B15

◆ Code system B34~B35

Available tool holders							
Designation Page Designation Page							
SRDCN	B191	SRGCR/L	B192				



# B Aluminum Insert (Positive)



## di t 7°

Dimensions (mm)							
Size	d	t	d <sub>1</sub>				
09	9.525	3.97	4.4				
12	12.7	4.76	5.5				

### 0

# Square **90° Positive** Relief Angle: 7°

	Steel	<b>4</b>	Р				
ខ្ល	Stainless steel	<	M				<del> </del>
Bi.	Cast iron	4	K				
돌	Non-ferrous metal	<	N	#	#	#	
Š	Heat resistant alloy, Titanium alloy		S				
	Hardened steel		н				1

Machining types

Continuous cutting

**♣** General cutting

# Interrupted cutting

	Hardened steel H							# Interrupt		
				Coated		Unce	oated	Cutting Condition		
Inserts	D	esignation	PC5040	PD1005	PD1010	년 1	H05	fn (mm/rev)	ap (mm)	
	SCGT	09T302-AK	•				•	0.02~0.30	0.10~4.00	
		09T304-AK	•			•	•	0.04~0.40	0.10~5.00	
		09T308-AK				•	•	0.03~0.40	0.10~5.00	
		120404-AK				•	•	0.03~0.50	0.10~5.00	
		120408-AK				•	•	0.04~0.60	0.15~5.50	
		120416-AK						0.04~0.60	0.15~5.50	
AK										
	SCGT	09T302-AR 09T304-AR 09T308-AR				•	•	0.03~0.40 0.04~0.50 0.04~0.50	0.50~5.00 0.50~6.00 0.50~6.50	
		120404-AR				•	•	0.05~0.60	0.50~6.50	
		120408-AR 120416-AR						0.05~0.60 0.05~0.60	0.50~7.00 0.50~7.00	
AR										



<sup>→</sup> Recommended chip breaker B04~B15



Available tool holders									
Designation	Page	Designation	Page						
SSBCR/L	B192	SSKCR/L	B193						
SSDCN	B192	SSSCR/L	B193						


<sup>€</sup> Code system B34~B35

<sup>• :</sup> Stock item









Dimensions (mm)									
Size	d	t	d <sub>1</sub>						
09	5.56	2.38	2.5						
11	6.35	2.38	2.8						
16	9.525	3.97	4.4						

	Steel	Р	$\triangleright$				
စ္တ	Stainless steel	VI					
orkpie	Cast iron	K					
ž	Non-ferrous metal	N	▶	#	#	3	
š	Heat resistant alloy, Titanium alloy	S					
	Hardened steel	Н					

Machining types

- Continuous cutting
- General cutting
- # Interrupted cutting

 Hard	dened steel	Н							
				Coated		Unc	oated	Cutting (	Condition
Inserts	D	esignation	PC5040	PD1005	PD1010	된	H05	fn (mm/rev)	ap (mm)
TCGT	TCGT	090202-AK				•	•	0.01~0.12	0.05~3.00
		090204-AK				•	•	0.02~0.15	0.10~4.00
		110202-AK	•			•	•	0.02~0.20	0.05~4.00
		110204-AK	•			•	•	0.03~0.30	0.10~4.00
		110208-AK				•	•	0.03~0.40	0.10~5.00
		16T302-AK				•	•	0.02~0.30	0.05~5.00
		16T304-AK				•	•	0.03~0.40	0.10~5.50
A 1.7		16T308-AK				•	•	0.03~0.50	0.10~5.50
AK		16T312-AK				•	•	0.04~0.60	0.15~5.50
		16T316-AK				•	•	0.05~0.80	0.15~5.50
		16T325-AK						0.06~0.90	0.20~7.00
	TCGT	090202-AR 090204-AR				•	•	0.02~0.18 0.02~0.25	0.30~3.00 0.30~5.00
		110202-AR						0.02~0.30	0.30~4.00
		110204-AR				•	•	0.03~0.40	0.30~5.00
		110208-AR						0.04~0.45	0.50~6.00
		16T302-AR				•	•	0.03~0.45	0.30~5.00
		16T304-AR				•	•	0.04~0.50	0.50~6.00
		16T308-AR				•	•	0.05~0.60	0.50~6.00
AR		16T312-AR						0.06~0.65	0.50~6.00
		16T316-AR						0.08~0.70	0.50~6.50
		16T325-AR						0.10~0.10	0.80~7.00


Cutting edge geometry A37~A49

◆ Code system B34~B35

Available tool holders									
Designation	Page	Designation	Page						
STACR/L	B193	STTCR/L	B194, 246						
STFCR/L	B194	STWCR/L	B246						
STGCR/L	B194								

## B Aluminum Insert (Positive)





Dimensions (mm)									
Size	d	t	d <sub>1</sub>						
11	6.35	3.18	2.8						
16	9.525	4.76	4.4						



# Rhombic **35° Positive** Relief Angle: 5°

	Steel		Р						Machining types
8	Stainless steel	4	M						
e.	Cast iron	4	K						<ul> <li>Continuous cutting</li> </ul>
춪	Non-ferrous metal	4	N	#	•	#	3	#	General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S						
	Hardened steel		Н						Interrupted cutting

			Coated			Unce	oated	Cutting Condition		
Inserts	n	esignation	9		0	0.100				
inserts	U		PC5040	PD1005	PD1010	Ð	H05	fn (mm/rev)	ap (mm)	
	VBGT	110302-AK				•	•	0.02~0.15	0.05~3.00	
		110304-AK				•	•	0.02~0.15	0.10~4.00	
		110308-AK					•	0.03~0.18	0.10~5.00	
		160402-AK						0.03~0.30	0.05~4.00	
		160404-AK				•	•	0.03~0.40	0.10~5.00	
		160408-AK				•	•	0.03~0.50	0.10~5.00	
		160412-AK					•	0.05~0.60	0.10~5.50	
AK										
	VBGT	110302-AR						0.02~0.35	0.30~3.00	
		110304-AR						0.03~0.45	0.30~4.00	
		110308-AR						0.03~0.50	0.50~6.00	
		160402-AR						0.04~0.45	0.30~5.00	
		160404-AR				•	•	0.04~0.50	0.50~6.00	
		160408-AR				•	•	0.05~0.60	0.50~6.00	
		160412-AR						0.05~0.70	0.50~6.50	
AR										

Cutting edge geometry A37~A49

Recommended chip breaker B04~B15

€ Code system B34~B35



Available tool holders									
Designation	Page	Designation	Page						
SVABR/L	B195	SVVBN	B196						
SVHBR/L	B195	SVQBR/L	B222						
SVJBR/L	B125, 195	SVUBR/L	B223						


## Aluminum Insert (Positive)







# Rhombic **35° Positive** Relief Angle: 7°



Dimensions (mm)										
Size	d	t	d <sub>1</sub>							
11	6.35	3.18	2.8							
13	7.94	3.18	3.4							
16	9.525	4.76	4.4							
22	12.7	5.56	5.6							

	Steel	Р					
စ္တ	Stainless steel	M					
kpie	Cast iron	K					
ork	Non-ferrous metal	N	#	•	#	3	#
×	Heat resistant alloy, Titanium alloy	S					
-	Hardened steel	Н					

Machining types

- Continuous cutting
- General cutting
- # Interrupted cutting

на	rdened steel	Н	1						
				Coated		Unco	ated	Cutting C	Condition
Inserts	D	esignation	PC5040	PD1005	PD1010	H01	H05	fn (mm/rev)	ap (mm)
	VCGT	110301-AK				•		0.02~0.15	0.05~3.00
		110302-AK	•			•	•	0.02~0.20	0.05~3.0
		110304-AK	•		•	•	•	0.02~0.25	0.10~4.0
		110308-AK				•	•	0.03~0.30	0.10~5.0
		130302-AK	•			•	•	0.02~0.35	0.10~5.0
		130304-AK	•			•	•	0.03~0.35	0.10~5.0
		130308-AK						0.04~0.40	0.10~5.0
		160402-AK				•	•	0.02~0.30	0.05~5.0
AK		160404-AK			•	•	•	0.03~0.40	0.10~5.0
		160408-AK			•	•	•	0.03~0.50	0.10~5.0
C)A		160412-AK				•	•	0.03~0.50	0.10~5.0
		220516-AK				•	•	0.03~0.60	0.10~7.0
		220525-AK					•	0.05~0.70	0.10~7.0
		220530-AK				•	•	0.08~1.00	0.10~7.0
	VCGT	110301-AR						0.02~0.20	0 10~3 0
	VCGT	110301-AR						0.02~0.20	0.10~3.0
		110302-AR				•	•	0.02~0.25	0.30~3.0
		110304-AR				•	•	0.03~0.35	0.30~4.0
		110308-AR						0.04~0.45	0.50~6.0
		130302-AR					•	0.02~0.40	0.50~3.0
		130304-AR				•	•	0.03~0.45	0.50~4.0
		130308-AR						0.04~0.50	0.50~5.0
		160402-AR				•	•	0.03~0.40	0.30~5.0
ΛĐ		160404-AR				•	•	0.04~0.50	0.50~6.0
AR		160408-AR				•	•	0.05~0.60	0.50~6.0
		160412-AR						0.06~0.65	0.50~6.5
		220516-AR						0.10~0.65	0.80~6.5
		220525-AR						0.10~0.70	0.80~7.0
		220530-AR				•	•	0.12~0.75	1.00~7.0



€ Cutting edge geometry A37~A49 € Recommended chip breaker B04~B15

◆ Code system B34~B35

Available tool holders									
Designation	Page	Designation	Page						
SVJCR/L	B125, 196, 222	SVQCR/L	B223						
SVVCN	B196	SVUCR/L	B223						



### **CBN**

### **Multi-Corner Type (Negative)**

Dimensions (mm)									
Size	d	t	d <sub>1</sub>						
12	12.7	4.76	5.16						
15	12.7	4.76~6.358	3.4						
16	9.525	4.76	3.81						

Designation	
	Page
2NU-CNGA 120404	B167
120404F ● ● DCLNR/L	B167/B208
120404T	B183
120404W ● MCLNR/L	B183/B213
<b>120404WF</b> ● MCMNN	B183
120408 • • • • • PCBNR/L	B172
120408F ● ● PCLNR/L	B173/B210
120408T ● ● ●	
120408W ● ● ● ●	
120408WF	
CN 120412 • • • •	
80° 120412F • •	
Nega 120412T ● ●	
120412W • •	
120412WT ●	
T-2NU-CNGA 120404 •	
120408 • •	
4NU-CNGA 120404 •	
120408	
120412	
4NS-CNGA 120408	
2NU-DNGA 150404 • • • DDJNR/L	B168
150404F	
150404T • • MDNNN	
150408 • • • • MDQNR/L	
150408F • • MDUNR/L	
150408T • • • PDJNR/L	
150412 • • PDNNR/L	
150412F • • PDSNR/I	
<b>DN</b>	B184 B184 B185 B213 B173 B174 B210 B211
55° 150604 • • •	
Nega 150608 ● ● ●	
<b>4NU-DNGA</b> 150404	
150408 ● ●	
150412 ● ●	
150608 ●	
4NS-DNGA 150608 •	
150612 • DODNOS MODNOS	D.100 D.17
4NU-SNGA 120404 • DSBNR/L MSBNR/L	
SN O MSDNN MSKNR/L MSRNR/L MSRNR/L MSRNR/L	
DODAY DODAY	B186 B187 B175 B176
Nega PSBNH/L PSDNN PSKNR/L	B176/B211
	==
3NU-TNGA 160404	B187 B187/B214
TN 160404T • MTGNR/L MTJNR/L	B188 B188
160408 A PTENRA PTGNRA	B177/B211 B178
160408F • PTTNR/L WTENN	B178 B179
Nega 160408T ● WTJNR/L WTXNR/L	B179 B179
160412	
2NU-VNGA 160404	B188
160404F ● ● MVQNR/L	B189
<b>VN</b>	B214
35° 160408 • • • • MVVNN	B189
Nega 160408F ● ●	
160408T ● ● ●	
T-2NU-VNGA 160408	

### **CBN**

### **Multi-Corner Type (Positive)**

Dimensions (mm)											
Size	Size d t d <sub>1</sub>										
06	6.35	2.38	2.8								
07	6.35	2.38	2.8								
09	9.525	3.97	4.4								
11	9.525	3.97	4.4								
16	9 525	4 76	3.81								

	I			-			_								525 4.76 3.81
					oate					Jnco				Available	tool holders
Inserts	Designa	tion	DNC100	DNC250	DNC300	DNC350	DNC400	DB1000	<b>DB2000</b>	DBN250	<b>DBN350</b>	DBN700A	DBNX20	Designation	Page
			ĕ	N	ă	ă	ă	8	98	98	8	B	180	Doolghation	i ago
	2NU-CCGW	060202		•										SCACR/L	B190
		060202T		•										SCLCR/L	B190/B215/B225
		060204		•					•						
		060204F		•											
		060204T		•											
CCOO (		060208						•							
80°		09T302		•											
Posi		09T304	•	•		•		•		•		•			
		09T304T		•		_									
		09T308	•	•		•			•	•		•			
		09T308T		•						_					
		09T308W		•				_		_				00.400#	D. 0.0
	2NU-DCGW	070204		•				•		_				SDACR/L	B190
		070208		•										SDJCR/L SDNCN	B191
		070208T 11T302						•						SDNCN SDQCR/L	B191 B217
		11T302 11T304	•	•		•		•		•				SDUCR/L	B217 B218
DCOO		11T304 11T304F		•		_		_		_				SDZCR/L	B218 B219
√√55°		11T304F 11T304T												SDZUN/L	טבוט
Posi		11T3041 11T308	•			•				•		•			
		11T308T		•		_									
	T-2NU-DCGW			•						_					
	1 2110 20011	11T308		•		•									
	3NU-TCGW	090204		•										STACR/L	B193
TC O		090204F		•										STFCR/L	B194/B220
<b>△</b> 60°		090204T		•										STGCR/L	B194
Posi														STTCR/L	B194
	3NU-TPGW	110304		•		•		•	•			•			
		110304F		•											
		110304T		•											
		110308		•		•		•	•			•			
•		110308F		•						_					
TP()()	CALLE ED CAL	110308T		•				_	_	_				07500#	D. CO DOLO
<b>△</b> 60°	3NU-TPGN	110308		_				•	•					CTFPR/L	B182/B212
Posi		160304		•						_				CTGPR/L	B182
	2NILTDGD	160308 110304		•										CTFPR/L	B182/B212
	3NU-TPGB	110304 110304T		•						_				CTGPR/L	B182/B212
		1103041								•				OTGITI/L	ם וטב
		110308F		•						_					
•		110308T		•											
	2NU-VBGW	160402		•										SVABR/L	B195
		160404	•	•		•		•		•		•		SVHBR/L	B195
<b>VD</b>		160404F		•										SVJBR/L	B195
VB()		160404T		•										SVQBR/L	B222
<b>35° 35°</b>		160408	•	•		•			•	•				SVUBR/L	B223
Posi		160408F		•											
		160408T		•											
	T-2NU-VBGW					•									
	2NU-VCGW	160404		•		•									
		160404F		•											
V000		160404T		•											
VCOO		160408		•											
35° Posi		160408F		•				_							
Posi	T ONLL VOC	160408T		•				•	•						
	T-2NU-VCGW			•											
		160408		•											
			1												



### **CBN**

### **Regrinding Type (Negative/Positive)**

Dimensions (mm)											
Size	d	t	d <sub>1</sub>								
09	9.525	3.97	4.4								
11	6.35~9.525	3.8~3.97	3.4~4.4								
12	12.7	4.76	5.16								

Dimensions (mm)										
Size d t d <sub>1</sub>										
15	12.7	4.76	5.16							
16	9.525	4.76	3.81~4.4							

				Coated Uncoated									Available tool holders						
Inserts	Doois	nation	8				8	8					20		Available	ooi noiders			
mserts	Desig	gnation	DNC100	DNC250	DNC300	DNC350	DNC400	DB1000	<b>DB2000</b>	DBN250	<b>DBN350</b>	DBN700A	DBNX20	Desig	nation	Pa	Page  67 B183 67/B208 B183/B213 72 B183 73/B210  68 B184 84 B185 13 B173 74 B210 10  87 B187/B214 88 B188 77/B211 B178 78 B179 79 B179  88 89 14 89 90 90/B215/B225		
	CNMA	120404								•				DCBNR/L	MCKNR/L	B167	B183		
		120408								•			•	DCLNR/L	MCLNR/L	B167/B208	B183/B213		
CNOO	T-CNMA	120408								•				PCBNR/L	MCMNN	B172			
80° Nega														PCLNR/L		B173/B210			
	DNMA	150404								•				DDJNR/L	MDJNR/L	B168	B184		
		150408								•	•			MDNNN	MDQNR/L	B184	B185		
DNOO															PDJNR/L	B213			
55° Nega														PDNNR/L PDUNR/L	PDSNR/L	B174 B210	B210		
	TNMA	160404								•				MTENN	MTFNR/L	B187	B187/B214		
		160408								•				MTGNR/L		B188			
TNOO														PTFNR/L	PTGNR/L				
60° Nega														PTTNR/L WTJNR/L	WTENN WTXNR/L	B178 B179			
	T-VNMA	160404								•				MVJNR/L		B188			
	VNMA	160404								•				MVQNR/L		B189			
VNOO		160408								•				MVUNR/L		B214			
35° Nega														MVVNN		B189			
	CCMW	09T304								•				SCACR/L		B190			
CC O 80° Posi														SCLCR/L		B190/B215	/B225		
	DCGW	11T308		П						•				SDACR/L		B190			
DC OO	T-DCGW	11T308								•				SDJCR/L		B191			
50° Posi														SDNCN		B191			
	VBMW	160404								•				SVABR/L		B195			
		160408								•				SVHBR/L		B195			
VBOO														SVJBR/L		B195			
35°	1													SVQBR/L		B222			
Posi														SVUBR/L		B223			
	T-TPGB	110304									•			CTFPR/L		B182/B212			
	TPGB	110304								•	•			CTGPR/L		B182			
TP OO		110308								•									
60° Posi																			
	1															•	: Stock item		

### **PCD**

### **Insert (Negative/Positive)**

	Dimensions (mm)										
Size	d	t	d <sub>1</sub>								
06	6.35	2.38	2.8								
07	6.35	2.38	2.8								
08	7.94	2.38	3.4								
09	9 525	3 18	44								

Dimensions (mm)									
Size	d	t	d <sub>1</sub>						
11	9.525	3.97	4.4						
12	12.7	4.76	5.16						
15	12.7	4.76	5.16						
16	9.525	4.76	3.81						

			09	9.525	3.18		9.525   4.76   3.81
				PCD		Availa	ble tool holders
Inserts	De	signation	DP90	DP150	DP200	Designation	Page
	CNMM	120404		•		DCBNR/L DCLNR	L/L B167 B167
CNOO		120408		•		MCKNR/L MCLNF	R/L B183 B183
80°						MCMNN PCBNF	R/L B183 B172
Nega						PCLNR/L	B173
DNOO	DNMM	150404		•		DDJNR/L MDJNR	R/L B168 B184
		150408		•		MDNNN MDQNF	
55°						MDUNR/L PDJNR	
Nega						PDNNR/L PDSNR	
						PDUNR/L	B210
CC O 80° Posi	CCMW	120404		•		SCACR/L	B190
	CCMT	060202		•		SCLCR/L	B190/B215/B225
		060204		•			
		09T304		•			
	DCMT	09T308 070202		•		SDACR/L	B195
DC 55° Posi	DCMT	070202		•		SDJCR/L	B195
		11T302		•		SDNCN	B191
		11T304		•		SDQCR/L	B217
		11T308		•		SDUCR/L	B218
	DCGT	11T304		•		SDZCR/L	B219
TP 60° Posi	TPGW	080204		•		000000	
		090204		•		-	
		090208		•		-	
		110304		•		-	
		110308		•			
	VBGW	160404		•			
	VBMT	110304		•		SVHBR/L	B195
VD OO		110308		•		SVJBR/L	B195
VBOO		160404		•		SVUBR/L	B223
VC OO		160408		•			
<b>35°</b>	VCMT	110304		•		SVVCN	B196
Posi		110308		•			
		160404		•			
		160408		•			
TP OO	TPGN	110304		•			
60° Posi		110308		•			
	SPGN	090304		•		CSDPN	B181
SP OO						CSKPR/L	B182/B212
90° Posi							
: Stock item							

### Economical small insert with powerful cutting performance

### **SAVE TURN**


- Strongly recommended turning insert for machining smaller diameter than Ø100
- Small but powerful and economical insert which performs the same like standard-sized inserts under the depth of cut of 3.0 mm

### Features

### Comparison of insert sizes 127 mm 9,525 mm **Down Size** 4.76 mm 4.76 mm **[SAVE TURN]** [Standard type]

Optimized size of the same performance like the standard type

### Comparison of cutting performance




· Performs the same like standard type inserts under the depth of cut of 3.0 mm

### Features of chip breaker

Insert shape	Cutting edge	Features
VQ		For finishing steel     Efficient chip breaking and low cutting resistance     Various application available at low depth of cut     Recommended depth of cut: 0.5~2.5 mm
MP		For medium cutting of steel dots for improved chip control in medium cutting to finishing Stable chip evacuation at high depth of cut Stable tool life due to lower cutting loads a high feed Recommended depth of cut: 0.5~4.0 mm
ММ		For medium cutting of stainless steel     Limits plastic deformation caused by heat     Stable tool life thanks to the balanced cutting performance and toughness     Stable chip flow at high speeds and feeds     Recommended depth of cut: 0.5~5.0 mm

### Application area of chip breaker



VQ: Depth of cut, ap = 0.5~2.5 mm/feed, fn = 0.05~0.30 mm/rev **MP**: Depth of cut, ap =  $0.5\sim4.0 \text{ mm/feed}$ , fn =  $0.15\sim0.40 \text{ mm/rev}$ **MM**: Depth of cut, ap =  $0.5 \sim 5.0 \text{ mm/feed}$ , fn =  $0.10 \sim 0.40 \text{ mm/rev}$ 

### Application example

### Alloy steel (SCM440)

Cutting conditions vc (m/min) = 250, fn (mm/rev) = 0.25ap (mm) = 2.0~3.0, continuous cutting, wet

Cutting Result



CNMG090408-HM **SAVE TURN** 




CNMG120408-HM Standard type

### Alloy steel (SCM440)


Cutting conditions

Cutting Result





CNMG090408-HM **SAVE TURN** 



CNMG120408-HM Standard type




**Turning** 


### Insert

Picture Designation	ration d1	tool holders page B116 B119
090412-VQ	<u>t</u>	
CNMG-MP CNMG 090404-MP 9.525 4.76 0.4 3.81 0.50~4.00 0.10~0.40 090408-MP 9.525 4.76 0.8 3.81 0.50~4.00 0.15~0.40 090412-MP 9.525 4.76 1.2 3.81 0.50~4.00 0.15~0.45	<u>t</u> dı	1
090408-MP 090412-MP 9.525 4.76 0.8 3.81 0.50~4.00 0.15~0.40 9.525 4.76 1.2 3.81 0.50~4.00 0.15~0.45	r dı	
80° \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	dı	
80° \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	- 1	B116
0.000 00000 100	t	B119
	<u></u>	
090408-MM 9.525 4.76 0.8 3.81 0.50~5.00 0.10~0.40		B116
090412-MM 9.525 4.76 1.2 3.81 0.50~5.00 0.12~0.45	d1	B119
80° V d	80° d	
DNMG-VQ DNMG 110508-VQ ● 9.525 5.56 0.4 3.81 0.50~2.50 0.08~0.30	<u></u>	D440
110512-VQ • 9.525 5.56 0.8 3.81 0.50~2.50 0.10~0.30	dı	B116 B117 B119 B120
DNMG-MP DNMG 110504-MP 9.525 5.56 0.4 3.81 0.50~4.00 0.10~0.40	<u>/</u>	B116
110508-MP 9.525 5.56 0.8 3.81 0.50~4.00 0.15~0.40 110512-MP 9.525 5.56 1.2 3.81 0.50~4.00 0.15~0.45		B117
110512-MP 9.525 5.56 1.2 3.81 0.50~4.00 0.15~0.45	t Idi	B119 B120
DNMG-MM DNMG 110504-MM 9.525 5.56 0.4 3.81 0.50~5.00 0.08~0.35	<u></u>	
110508-MM 9.525 5.56 0.8 3.81 0.50~5.00 0.10~0.40		B116 B117
110512-MM 9.525 5.56 1.2 3.81 0.50~5.00 0.12~0.45	- · - dı	B119 B120
) <sup>55</sup> \	<u>- t</u> -	
SNMG-VQ SNMG 090408-VQ • 9.525 4.76 0.4 3.81 0.50~2.50 0.08~0.30	<u></u>	
090412-VQ 9.525 4.76 0.8 3.81 0.50~2.50 0.10~0.30	d1	B117 B118 B120
SNMG-MP SNMG 090404-MP 9.525 4.76 0.4 3.81 0.50~4.00 0.10~0.40	ا <del>جاندا</del> عر	
090408-MP 9.525 4.76 0.8 3.81 0.50~4.00 0.15~0.40		B117
090408-MP     9.525 4.76 0.8 3.81 0.50~4.00 0.15~0.40       090412-MP     9.525 4.76 1.2 3.81 0.50~4.00 0.15~0.45	t dı	B118 B120
SNMG-MM SNMG 090404-MM 9.525 4.76 0.4 3.81 0.50~5.00 0.08~0.35		+
090408-MM 9.525 4.76 0.8 3.81 0.50~5.00 0.10~0.40		B117
090412-MM 9.525 4.76 1.2 3.81 0.50~5.00 0.12~0.45	t dı	B118 B120
WNMG-VQ WNMG 060404-VQ 9.525 4.76 0.4 3.81 0.30~2.00 0.06~0.30		
060408-VQ 9.525 4.76 0.8 3.81 0.50~2.00 0.08~0.30	t du	B119
060412-VQ 9.525 4.76 1.2 3.81 0.50~2.00 0.10~0.30	t	B120
WNMG-MP WNMG 060404-MP ● ● ● 9.525 4.76 0.4 3.81 0.50~3.50 0.10~0.40		+
060408-MP		B119
060408-MP • • • • 9.525 4.76 0.8 3.81 0.50~3.50 0.15~0.40 060412-MP 9.525 4.76 1.2 3.81 0.50~3.50 0.15~0.45	d1	B120
WNMG-MM WNMG 060404-MM 9.525 4.76 0.4 3.81 0.50~4.00 0.08~0.35		
<b>060408-MM</b>		B119
060412-MM	td1	B120


## **B** SAVE TURN Holder




Applicable inserts B115




Applicable inserts B115




Applicable inserts B115



Applicable inserts B115




Applicable inserts B115




Applicable inserts B115


## **B** SAVE TURN Holder




Applicable inserts B115



Applicable inserts B115



Applicable inserts B115



<sup>→</sup> Applicable inserts B115

2525-M06

25


25

150


32

25

20



Applicable inserts B115




Applicable inserts B115


# B SAVE TURN Boring Bar

## PDZNR/L



 $\mathsf{DN} \square \square$ 





 R type insert (mm)


Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim pin	Wrench	Shim Pin Punch
S32S-PDZNR/L-11-5N	40	32	30	250	22	30	DN□□1105□□	LV3AN	VHX0617N	SD32N	CDO	HW25L	
S40T-PDZNR/L-11-5N	50	40	38	300	27	50		LVJAIN	VIIVO01/IN	SUSZIN	SP3 I	HVVZOL	


<sup>→</sup> Applicable inserts B115

## **PSKNR/L**



 $SN \square \square$ 





• R type insert (mm)


Designation	ØD	Ød	н	L	s	Q	Insert	Lever	Screw	Shim	Shim pin	Wrench	Shim Pin Punch
S25R-PSKNR/L-09-4N	32	25	23	200	17	32	SN□□0904□□	LV3B	VHX0512B	-	-	HW20L	_
S32S-PSKNR/L-09-4N	40	32	30	250	22	32	3NLL0904LL	LV3N	VHX0617N	SS32N	-	HW25L	_


Applicable inserts B115

# **PWLNR/L**



 $WN \square \square$ 





• R type insert (mm)

Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim pin	Wrench	Shim Pin Punch
S20S-PWLNR/L-06	25	20	18	250	13	40		LV3B	VILIVOETOD				
S25R-PWLNR/L-06	32	25	23	200	17	40	WN□□0604□□	LV3D	VHX0512B	_	_	_	_
S32S-PWLNR/L-06	44	32	30	250	22	45		LV3B	VHX0617B	SW317	SW317	HW25L	LSPS3

<sup>→</sup> Applicable inserts B115

### **Excellent for precision machining**

# **Auto Tools**

- High precision machining of small parts and complex forms, etc.
- High quality products through stable machining
- Exclusive insert for automatic lathes














Application example



### Index

Specification		(	Parting a	nd Grooving	I		2	Back turnii	ng
Holder	SXGNR/L	SXGNR/L	SBHR/L	SBHR/L	MGEHR/L	KGEHR/L	SXGNR/L	SXGNR/L	SBHR/L
Insert	SG	SC	SBG	SBC	MGMN	KGMN	SB	SGB	SBB
Holder size	10~20mm	10~20mm	10~16mm	10~16mm	10~16mm	10~16mm	10~20mm	10~20mm	10~16mm
Insert shape	8	8			3/1	3/1	8		15
Cutting width	1~3mm	1~3mm	0.7~2.0mm	0.7~2.0mm	1.5~2.5mm	1.5~2.5mm	2~4mm	2~3mm	3.18mm
ØDmax	Ø18	Ø18	Ø16	Ø16	Ø32	Ø32	Tmax 8.0	Tmax 8.5	Tmax 8.0
Page	B140	B140	B137	B137	B144	B143	B140	B140	B137


Three	oodina						
SXGNR/L SBHR/L							
SXGNR/L	SBHR/L						
ST	SBT						
10~20mm	10~16mm						
8	1						
Pitch ranges 0.5~1.5 / 1.5~3.0	Pitch ranges 0.2~1.5 / 1.0~2.0						
B140	B137						
	ST 10~20mm Pitch ranges 0.5~1.5 / 1.5~3.0						

Specification	4 Extern	al turning a	and Copy n	nachining	<b>3</b> External turning and Facing					
Holder	SDJCR/L	SDNCN	SVJBR/L	SVJCR/L	SCACR/L	SCLCR/L	STACR/L			
Insert	DC□T	DC□T	VB□T	VC□T	CC□T	CC□T	TC□T			
Holder size	8~16mm	8~16mm	10~16mm	10~16mm	8~16mm	8~16mm	8~10mm			
Insert shape		6		<b>*</b>	<b>O</b>	O				
Feature		Offse	et "0"			Offset "0"				
Page	B123	B124	B125	B125	B123	B123	B124			


Specification		6 Internal	nal turning	(Boring)			
Holder	SCLCR/L	STUBR/L	STUPR/L	SWUBR/L	MSB		
Insert	CC□T	ТВ□Т	TP□T	WB□T	-		
Shank diameter	Ø4~Ø10	Ø8	Ø8	Ø5~Ø8	Ø4~Ø6		
Insert shape	0	0	0	0	Arres 1		
ØDmin	Ø5	Ø8	Ø10	Ø5.5	Ø3.2		
Page	B225	B225	B226	B227	B147~B151		

### Auto Tools (ISO type)

- ISO inserts for automatic lathes
- Precise R shape with the use of minus tolerance of nose R
- Tolerance class precise enough in no need for adjusting tools with the use of accurate cutting edge height
- Sharp blade for excellent chip control and surface roughness with low cutting force
- High precision tools for electrical/ electronics instruments and medical instruments



### Code system (ISO type)



### VP1/MS/FS chip breaker

- Exclusive chip breaker for hard-to-cut materials such as titanium alloy, Inconel, stainless steel, etc.
- Minimized cutting heat by reducing contact area between chips and rake surface with the use of high positive blade



- · Hard cutting edge for medium cutting
- · Optimal width of chip breaker by each depth of cuts realizes wide workpiece machining



- · Good surface finish for medium cutting
- · Preventing welding in titanium machining
- · Increasing chip evacuation in high feed machining
- · Protecting cutting edge due to structure for good chip evacuation



- For finishing (for surface roughness)
- 1st recommended chip breaker for chip control
- · Better surface roughness, surface finish and chip control

### KF/KM chip breaker, ground type for grooving

- Ground chip breaker with sharp cutting edge
- High precision insert of E-class tolerance with accurate nose radius



- · For finishing
- · Low cutting loads with sharp cutting edges
- · Longer tool life due to lower chip evacuation resistance at high speed
- Excellent surface roughness




- · For medium cutting to finishing
- · Better chip flow due to wide chip pockets
- · Longer tool life and better cutting action due to improved chip evacuation
- Excellent surface roughness














 Only SCACR/L1010-X09A is designed as above picture.



• R type insert (mm)


D	esignation (	Н	W	L	s	h	Q	Insert	Screw	Wrench
SCACR/L	0808-X06A	8	8	120	8	8	10	CCTTOGOO	FTKA02565	TW07P
	1010-X06A	10	10	120	10	10	10	CC□T0602□□	F1KAU2505	10076
	1010-X09A	10	10	120	12	10	13			
	1212-X09A	12	12	120	12	12	16	CC□T09T3□□	FTKA0410	TW15P
	1616-X09A	16	16	120	16	16	16			


Applicable inserts B73~B77, B103






CC□T







• R type insert (mm)


[	Designation	н	W	L	S	h	Q	Insert	Screw	Wrench
SCLCR/L	0808-X06A	8	8	120	8	8	10	CC□T0602□□	FTKA02565	TW07P
	1010-X06A	10	10	120	10	10	10	CC_10602	F1KA02505	10076
	1010-X09A	10	10	120	12	10	13			
	1212-X09A	12	12	120	12	12	16	CC□T09T3□□	FTKA0410	TW15P
	1616-X09A	16	16	120	16	16	16			


<sup>→</sup> Applicable inserts B73~B77, B103

## SDJCR/L



 $DC \square T$ 





93°

• R type insert

											, ,
1	Designation	н	W	L	s	h	K	Q	Insert	Screw	Wrench
SDJCR/L	0808-X07A	8	8	120	10	8	2	18	DC□T0702□□	FTKA02565	TW07P
	1010-X07A	10	10	120	10	10	-	15	DG_10702	F1KA02303	10076
	1010-X11A	10	10	120	14	10	4	18			
	1212-X11A	12	12	120	14	12	2	18	DC□T11T3□□	FTKA0410	TW15P
	1616-X11A	16	16	120	16	16	-	22			

<sup>→</sup> Applicable inserts B79~B82, B104


# **B** Auto Tools (ISO type)

### **SDNCN** w S\* \* Only SDNCN1010-X11A is designed as above picture. 62.5° н

• R type insert (mm)

	Designation	н	W	L	S	h	Insert	Screw	Wrench
SDNCN	0808-X07A	8	8	120	4	8	DC□T0702□□	FTKA02565	TW 07P
	1010-X07A	10	10	120	5	10		F1KA02505	TVV 0/P
	1010-X11A	10	10	120	7	10			
	1212-X11A	12	12	120	6	12	DC□T11T3□□	FTKA0410	TW 15P
	1616-X11A	16	16	120	8	16			

<sup>→</sup> Applicable inserts B79~B82, B104



<sup>→</sup> Applicable inserts B88~B89, B107

### SVACR/L W (3) н $VC \square \square$ · R type insert

										(mm)
1	Designation	н	W	L	s	h	Q	Insert	Screw	Wrench
SVACR/L	0808-X12A	8	8	120	8.5	8	26			
	1010-X12A	10	10	120	10.5	10	26	VC□□ T1203□□	FTKA02565	TW07P
	1212-X12A	12	12	120	12.5	12	26	VC 11203	F1KA02505	10076
	1616-X12A	16	16	120	16.5	16	26			
SVACR/L	0808-X12C	8	8	120	8.5	8	26			
	1010-X12C	10	10	120	10.5	10	26	VC□□ X1203□□	FTKA02565	TW07P
	1212-X12C	12	12	120	12.5	12	26	VOLL X1203LL	F1KA02505	10076
	1616-X12C	16	16	120	16.5	16	26			


90°


<sup>→</sup> Applicable inserts B97~B99, B109

## **SVAPR/L**









• R type insert (mm)


[	Designation	Н	W	L	s	h	Q	Insert	Screw	Wrench
SVAPR/L	0808-X11A	8	8	120	8	8	22			
	1010-X11A	10	10	120	10	10	22	VP□□ T1103□□	FTKAOOFOF	TW07P
	1212-X11A	12	12	120	12	12	22	VP 11103	FTKA02565	10076
	1616-X11A	16	16	120	16	16	24			

Applicable inserts B100

# SVJBR/L



 $\mathsf{VB} \square \mathsf{T}$ 





R type insert


										(11111)
	Designation	Н	W	L	s	h	Q	Insert	Screw	Wrench
SVJBR/L	1010-X11A	10	10	120	10	10	22			
	1212-X11A	12	12	120	12	12	22	VB□T1103□□	FTKA02565	TW07P
	1616-Y11A	16	16	120	16	16	24			


<sup>→</sup> Applicable inserts B94~B96, B108

# SVJCR/L



 $VC \square \square$ 





• R type insert

	Designation	н	W	L	S	h	Q	Insert	Screw	Wrench
SVJCR/L	1010-X11A	10	10	120	10	10	22			
	1212-X11A	12	12	120	12	12	22	VC□T1103□□	FTKA02565	TW07P
	1616-X11A	16	16	120	16	16	24			
	0810-X12A	8	10	120	10	8	26			
	1010-X12A	10	10	120	10	10	26	VC□T1203□□	FTKA02565	TW07P
	1212-X12A	12	12	120	12	12	26	VC_11203		TVVO/F
	1616-X12A	16	16	120	16	16	26			
SVJCR/L	0810-X12C	8	10	120	10	8	26			
	1010-X12C	10	10	120	10	10	26	VC□X1203□□	FTKA02565	TW07P
	1212-X12C	12	12	120	12	12	26	VG	F1NA02505	10076
	1616-X12C	16	16	120	16	16	26			


<sup>→</sup> Applicable inserts B97~B99, B109

# **B** Auto Tools (ISO type)

# SVJPR/L









93°

• R type insert


Di	esignation	н	W	L	S	h	Q	Insert	Screw	Wrench
SVJPR/L	0810-X11A	8	10	120	8	10	22			
	1010-X11A	10	10	120	10	10	22	VP□T1103□□	FTKAOOFCE	TW07P
	1212-X11A	12	12	120	12	12	22	VP_11103	FTKA02565	TVVU/P
	1616-X11A	16	16	120	16	16	24			

<sup>→</sup> Applicable inserts B100











72.5°

• R type insert (mm)


	Designation	Н	W	L	s	h	Q	Insert	Screw	Wrench
SVVPN	0808-X11A	8	8	120	4	8	24			
	1010-X11A	10	10	120	5	10	24	VD	FTKARRES	TM/07D
	1212-X11A	12	12	120	6	12	24	VP□T1103□□	FTKA02565	TW07P
	1616-X11A	16	16	120	8	16	28			

Applicable inserts B100

## **Auto Tools (KHP Coolant)**

- KORLOY High pressure coolant for high productivity of automatic lathe
- High pressure coolant holder for high productivity of precise parts machining on automatic lathe
- Improved cooling and chip control due to injecting coolant through two holes to the main cutting edge and nose R
  concentrically
- Two holes with different injection angles each other increase chip control
- Easy clamping system of quick hose adapter and quick hose provides convenient using

### Structure of holder




\* Quick adapter and quick hose are sold separately

### Parts


	Shape	Configuration	Length	Q clamping dimensions	S clamping dimensionss
Quick to straight	HPHZ5/16UNF3/8UNF-500	Q Quick S	500 mm	UNF5/16	-
Quick adaptor	HPAQ5/16UNF	UNF5/16 QUICK	18.5 mm	UNF	-5/16

# **B** Auto Tools (KHP Coolant)

### Features



Max 300 bar											
Workpiece	The minimum pressure	The maximum pressure									
Р	100										
M	120										
K	110	300									
N	100										
S	120										




### Parts

Devision	Designation	Shape								
Adaptor	HPA3/8UNF1/8PF		G1/8 (PF1/8) UNF3/8							
Blank	HPB1/8PF		G1/8 (PF1/8)							
Quick adaptor	HPAQ5/16UNF	4	UNF5/16 QUICK							


### High pressure hose

	length	Q clamping dimensions	S clamping dimensionss	
Quick to straight (HPHZ5/16UNF3/8UNF-500)	Q UNF3/8 Q QUICK S	500 mm	UNF5/16	-






Applicable inserts B66-69, B91



Applicable inserts B71-73, B92



<sup>→</sup> Applicable inserts B86~B87, B97

# **B** Auto Tools (ISO)

				ated		Uncoated		Dime	nsions	(mm)			
Picture	Designation	PC5300	PC8105	PC8110	PC8115	H01	ı	d	t	r	d1	Configuration	on
	0301003R-KF	•		•			3.6	3.5	1.39	0.03	1.9		
	030101R-KF	•		•			3.5	3.5	1.39	0.10	1.9		
	030102R-KF	•		•			3.5	3.5	1.39	0.20	1.9		
	030104R-KF	•		•			3.5	3.5	1.39	0.40	1.9		
	0401003R-KF	•		•			4.4	4.3	1.79	0.03	2.3		
	040101R-KF	•		•			4.4	4.3	1.79	0.10	2.3		
	040102R-KF	•		•			4.3	4.3	1.79	0.20	2.3		
	040104R-KF	•		•			4.3	4.3	1.79	0.40	2.3		
	0602003R-KF						6.6	6.35	2.38	0.03	2.8		
	060201R-KF						6.4	6.35	2.38	0.10	2.8		
	060202R-KF						6.2	6.35	2.38	0.20	2.8		
	09T3003R-KF						9.8	9.525	3.97	0.03	4.4		
CCGT-KF	09T301R-KF						9.6	9.525	3.97	0.10	4.4		
	09T302R-KF 0301003L-KF	•		•			9.2	9.525	3.97	0.20	4.4		
	0301003L-KF			•			3.6	3.5	1.39	0.03	1.9		###
	030101L-KF	•		•			3.5	3.5	1.39	0.10	1.9		
Finishing	030102L-KF			•			3.5	3.5	1.39	0.40	1.9	80° 1	<del>- t-</del>
(High precision)	0401003L-KF	•		•			4.4	4.3	1.79	0.40	2.3		
- '	0401003L-KF	•		•			4.4	4.3	1.79	0.03	2.3	-	
	040101L-KF	•		•			4.3	4.3	1.79	0.20	2.3		
	040104L-KF	•		•			4.3	4.3	1.79	0.40	2.3		
	0602003L-KF						6.6	6.35	2.38	0.03	2.8		
	06020002 TKI						6.4	6.35	2.38	0.10	2.8		
	060201L-KF						6.2	6.35	2.38	0.20	2.8		
	09T3003L-KF						9.8	9.525	3.97	0.03	4.4		
	09T301L-KF						9.6	9.525	3.97	0.10	4.4		
	09T302L-KF						9.2	9.525	3.97	0.20	4.4		
	0602005MFR-KF 060201MFR-KF	•		•			6.6	6.35	2.38	< 0.05	2.8		
	060202MFR-KF	•		•			6.2	6.35	2.38	< 0.20	2.8		
	09T3005MFR-KF 09T301MFR-KF	•		•			9.8	9.525 9.525	3.97	< 0.05	4.4		
CCET-KF	09T302MFR-KF			•			9.2	9.525	3.97	< 0.10	4.4	· /-	
	0602005MFL-KF	•		•			6.6	6.35	2.38	< 0.05	2.8		
	060201MFL-KF	•		•			6.4	6.35	2.38	< 0.10	2.8	<del>  ((-{-}))  </del>  d	
	060202MFL-KF	•		•			6.2	6.35	2.38	< 0.20	2.8		
Finishing	09T3005MFL-KF	•		•			9.8	9.525	3.97	< 0.05	4.4	80° \	- t
Jtra high precision)	09T301MFL-KF	•		•			9.6	9.525	3.97	< 0.10	4.4		
	09T302MFL-KF	•		•			9.2	9.525	3.97	< 0.20	4.4		
	0602003R-KM	•		•			6.6	6.35	2.38	0.03	2.8		
	060201R-KM	•		•			6.4	6.35	2.38	0.10	2.8		
	060202R-KM 060204R-KM			•			6.2	6.35	2.38	0.20	2.8	-	
	09T3003R-KM			•			9.8	9.525	3.97	0.40	4.4	-	
	09T3003H-KW	•		•			9.6	9.525	3.97	0.00	4.4	1	
	09T302R-KM	•		•			9.2	9.525	3.97	0.20	4.4	r	
CCGT-KM	09T304R-KM	•		•			9.2	9.525	3.97	0.40	4.4		
	0602003L-KM	•		•			6.6	6.35	2.38	0.03	2.8		
	060201L-KM	•		•			6.4	6.35	2.38	0.10	2.8	1 ( d	#-
	060202L-KM	•		•			6.2	6.35	2.38	0.20	2.8		
Andium to fini 11	060204L-KM	•		•			6.2	6.35	2.38	0.40	2.8	80°	<del>- t-</del>
Medium to finishing (High precision)	09T3003L-KM	•		•			9.8	9.525	3.97	0.03	4.4		
,g producti)	09T301L-KM	•		•			9.6	9.525	3.97	0.10	4.4		
	09T302L-KM	•		•			9.2	9.525	3.97	0.20	4.4		
	COTOCAL ICM	•		•			9.2	9.525	3.97	0.40	4.4		
	09T304L-KM	_					0.2	0.020	0.07	0.10	7.7		
	091304L-KW						0.2	0.020	0.07	0.10	7.7		

			Coa	ated		Uncoated		Dime	nsions	(mm)		
Picture	Designation	PC5300	PC8105	PC8110	PC8115	H01	ı	d	t	r	d1	Configuration
	0602005MFR-KM	•		•			6.6	6.35	2.38	< 0.05	2.8	
	060201MFR-KM	•		•			6.4	6.35	2.38	< 0.10	2.8	
CCET-KM	060202MFR-KM	•		•			6.2	6.35	2.38	< 0.20	2.8	
0021-Kiii	09T3005MFR-KM 09T301MFR-KM	•		•			9.8	9.525 9.525	3.97	< 0.05	4.4	
	09T302MFR-KM	•		•			9.2	9.525	3.97	< 0.10	4.4	
	0602005MFL-KM	•		•			6.6	6.35	2.38	< 0.05	2.8	
Madison to Calabia	060201MFL-KM	•		•			6.4	6.35	2.38	< 0.10	2.8	7°
Medium to finishing (Utra high precision)	060202MFL-KM	•		•			6.2	6.35	2.38	< 0.20	2.8	80° 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	09T3005MFL-KM	•		•			9.8	9.525	3.97	< 0.05	4.4	
	09T301MFL-KM 09T302MFL-KM	•		•			9.6	9.525 9.525	3.97	< 0.10	4.4	
	060201-FS	•		•			6.3	6.35	2.38	0.10	2.8	
CCGT-FS	060201-FS	•		•			6.2	6.35	2.38	0.20	2.8	<u></u>
The state of the s	060204-FS	•		•			6.0	6.35	2.38	0.40	2.8	
	09T301-FS	•		•			9.8	9.525	3.97	0.10	4.4	d + da
	09T302-FS	•		•			9.6	9.525	3.97	0.20	4.4	7°
Finishing (High precision)	09T304-FS	•		•			9.2	9.525	3.97	0.40	4.4	80°   t
	09T308-FS 060201MFN-FS	•		•			8.8 6.3	9.525 6.35	3.97 2.38	0.80	2.8	
CCGT-FS	060201MFN-FS						6.2	6.35	2.38	< 0.10	2.8	<u></u>
TEV .	060204MFN-FS						6.0	6.35	2.38	< 0.40	2.8	
	09T301MFN-FS						9.8	9.525	3.97	< 0.10	4.4	d + dı
	09T302MFN-FS						9.6	9.525	3.97	< 0.20	4.4	70
Finishing (Utra high precision)	09T304MFN-FS						9.2	9.525	3.97	< 0.40	4.4	80°   t
	09T308MFN-FS						8.8	9.525	3.97	< 0.80	4.4	r
CCGT-MS	09T301-MS 09T302-MS	•		•			9.8	9.525 9.525	3.97	0.10	4.4	
	09T304-MS	•		•			9.2	9.525	3.97	0.40	4.4	
Medium cutting (High precision)												d d d d d d d d d d d d d d d d d d d
CCGT-MS	09T301MFN-MS	•		•			9.8	9.525	3.97	< 0.10	4.4	r
new	09T302MFN-MS	•		•			9.6	9.525	3.97	< 0.20	4.4	
Medium cutting (Utra high precision)	09T304MFN-MS	•		•			9.2	9.525	3.97	< 0.40	4.4	d d <sub>1</sub>
CCGT-VP1	60201-VP1	•	•	•	•	•	6.6	6.35	2.38	0.10	2.8	<u>_r</u>
	60202-VP1	•	•	•	•	•	6.4	6.35	2.38	0.20	2.8	
	60204-VP1	•	•	•	•	•	6.2	6.35	2.38	0.40	2.8	d     d1
	09T301-VP1 09T302-VP1	•	•	•	•	•	9.8	9.525	3.97	0.10	4.4	
Finishing (High precision)	09T302-VP1	•	•	•	•	•	9.6	9.525 9.525	3.97	0.20	4.4	80°
CCGT-VP1	060201MFN-VP1	•		•			6.6	6.35	2.38	< 0.10	2.8	_r_
3331-VF1	060202MFN-VP1	•		•			6.4	6.35	2.38	< 0.20	2.8	
	060204MFN-VP1	•		•			6.2	6.35	2.38	< 0.40	2.8	
	09T301MFN-VP1	•		•			9.8	9.525	3.97	< 0.10	4.4	
Finishing (Utra high precision)	09T302MFN-VP1 09T304MFN-VP1	•		•			9.6	9.525	3.97	< 0.20	4.4	7°
(On a riight precision)	0702003R-KF	•		•			9.2 7.8	9.525	3.97 2.38	< 0.40	2.8	OU I . ,
	0702003H-KF	•		•			7.8	6.35	2.38	0.03	2.8	-
	070202R-KF	•		•			7.8	6.35	2.38	0.20	2.8	
	070204R-KF	•		•			7.8	6.35	2.38	0.40	2.8	
	11T3003R-KF	•		•			11.6	9.525	3.97	0.03	4.4	
DCGT-KF	11T301R-KF	•		•			11.6	9.525	3.97	0.10	4.4	
	11T302R-KF 11T304R-KF	•		•			11.6	9.525 9.525	3.97	0.20	4.4	
	0702003L-KF	•		•			7.8	6.35	2.38	0.40	2.8	
Finishing	07020002 Ki	•		•			7.8	6.35	2.38	0.10	2.8	55°
(High precision)	070202L-KF	•		•			7.8	6.35	2.38	0.20	2.8	
	070204L-KF	•		•			7.8	6.35	2.38	0.40	2.8	
	11T3003L-KF	•		•			11.6	9.525	3.97	0.03	4.4	
	11T301L-KF	•		•			11.6	9.525	3.97	0.10	4.4	
	11T302L-KF 11T304L-KF	•		•			11.6	9.525 9.525	3.97	0.20	4.4	
	IIIJU4L*KF						11.0	a.525	0.87	0.40	4.4	<u> </u>

# B Auto Tools (ISO)

				ated		Uncoated		Dime	nsions			
Picture	Designation	PC5300	PC8105	PC8110	PC8115	H01	ı	d	t	r	d <sub>1</sub>	Configuration
	0702005MFR-KF	•		•			7.8	6.35	2.38	< 0.05	2.8	
	070201MFR-KF	•		•			7.8	6.35	2.38	< 0.10	2.8	
	070202MFR-KF	•		•			7.8	6.35	2.38	< 0.20	2.8	r
DCET-KF	11T3005MFR-KF	•		•			11.6	9.525	3.97	< 0.05	4.4	
	11T301MFR-KF 11T302MFR-KF	•		•			11.6 11.6	9.525 9.525	3.97	< 0.10	4.4	
	0702005MFL-KF	•		•			7.8	6.35	2.38	< 0.20	2.8	
	0702005WFL-KF	•		•			7.8	6.35	2.38	< 0.03	2.8	55.
Finishing Jtra high precision)	070202MFL-KF	•		•			7.8	6.35	2.38	< 0.20	2.8	-
	11T3005MFL-KF	•		•			11.6	9.525	3.97	< 0.05	4.4	
	11T301MFL-KF	•		•			11.6	9.525	3.97	< 0.10	4.4	-
	11T302MFL-KF	•		•			11.6	9.525	3.97	< 0.20	4.4	
	0702003R-KM	•		•			7.8	6.35	2.38	0.03	2.8	
	070201R-KM	•		•			7.8	6.35	2.38	0.10	2.8	
	070202R-KM	•		•			7.8	6.35	2.38	0.20	2.8	
	070204R-KM	•		•			7.8	6.35	2.38	0.40	2.8	
	11T3003R-KM	•		•			11.6	9.525	3.97	0.03	4.4	- r
DCGT-KM	11T301R-KM 11T302R-KM	•		•			11.6 11.6	9.525 9.525	3.97	0.10	4.4	
	11T302R-KW	•		•			11.6	9.525	3.97	0.20	4.4	
	0702003L-KM	•		•			7.8	6.35	2.38	0.40	2.8	
	070200L-KM	•		•			7.8	6.35	2.38	0.10	2.8	55°
Medium to finishing	070202L-KM	•		•			7.8	6.35	2.38	0.20	2.8	-
(High precision)	070204L-KM	•		•			7.8	6.35	2.38	0.40	2.8	-
	11T3003L-KM	•		•			11.6	9.525	3.97	0.03	4.4	
	11T301L-KM	•		•			11.6	9.525	3.97	0.10	4.4	
	11T302L-KM	•		•			11.6	9.525	3.97	0.20	4.4	
	11T304L-KM	•		•			11.6	9.525	3.97	0.40	4.4	-
	070000EMED KM						7.0	0.05	0.00	- 0.05	0.0	
	0702005MFR-KM 070201MFR-KM	•		•			7.8	6.35	2.38	< 0.05	2.8	-
	070201MFR-KM	•		•			7.8	6.35	2.38	< 0.10	2.8	
	11T3005MFR-KM	•		•			11.6	9.525	3.97	< 0.05	4.4	
DCET-KM	11T301MFR-KM	•		•			11.6	9.525	3.97	< 0.10	4.4	
	11T302MFR-KM	•		•			11.6	9.525	3.97	< 0.20	4.4	
	0702005MFL-KM	•		•			7.8	6.35	2.38	< 0.05	2.8	
	070201MFL-KM	•		•			7.8	6.35	2.38	< 0.10	2.8	55.
Medium to finishing  Utra high precision)	070202MFL-KM	•		•			7.8	6.35	2.38	< 0.20	2.8	-
<b>3</b> ,,	11T3005MFL-KM	•		•			11.6	9.525	3.97	< 0.05	4.4	
	11T301MFL-KM	•		•			11.6	9.525	3.97	< 0.10	4.4	
	11T302MFL-KM	•		•			11.6	9.525	3.97	< 0.20	4.4	
	070201-FS	•		•			7.6	6.35	2.38	0.10	2.8	
DCGT-FS	070201-FS	•		•			7.5	6.35	2.38	0.20	2.8	ـــر
new	11T301-FS	•		•			11.6	9.525	3.97	0.10	4.4	
	11T302-FS	•		•			11.6	9.525	3.97	0.20	4.4	
Finishing	11T304-FS	•		•			11.6	9.525	3.97	0.40	4.4	
(High precision)	11T308-FS	•		•			11.6	9.525	3.97	0.80	4.4	55° t
	070004:-7:											
DOOT TO	070201MFN-FS						7.6	6.35	2.38	< 0.10	2.8	
DCGT-FS	070202MFN-FS						7.5	6.35	2.38	< 0.20	2.8	
	11T301MFN-FS 11T302MFN-FS						11.6 11.4	9.525 9.525	3.97	< 0.10	4.4	
1	11T302MFN-FS						11.4	9.525	3.97	< 0.20	4.4	
Finishing  Jtra high precision)	11T308MFN-FS						11.0	9.525	3.97	< 0.40	4.4	55°
a mgn prodototi)												1
DCGT-MS	11T301-MS	•		•			11.6	9.525	3.97	0.10	4.4	/
new	11T302-MS	•		•			11.6	9.525	3.97	0.20	4.4	
	11T304-MS	•		•			11.6	9.525	3.97	0.40	4.4	
Medium cutting												55
(High precision)	11T301MFN-MS	•		•			11 6	0 505	2.07	Z 0 10	1 1	· 1
DCGT-MS	11T301MFN-MS	•		•			11.6 11.6	9.525 9.525	3.97	< 0.10	4.4	
	11T302MFN-MS			•			11.6	9.525	3.97	< 0.20	4.4	
	. I I OU-TIVII IN-IVIO	-					11.0	0.020	0.37	~ 0.40	7.4	
Medium cutting												

				ated		Uncoated		Dime	nsions	(mm)		
Picture	Designation	PC5300	PC8105	PC8110	PC8115	H01	ı	d	t	r	d <sub>1</sub>	Configuration
	070201-VP1	•	•	•	•	•	7.8	6.35	2.38	0.10	2.8	
DCGT-VP1	070202-VP1	•	•	•	•	•	7.8	6.35	2.38	0.20	2.8	r
	070204-VP1	•	•	•	•	•	7.8	6.35	2.38	0.40	2.8	
	11T301-VP1	•		•			11.6	9.525	3.97	0.10	4.4	
Cintalata	11T302-VP1	•	•	•	•	•	11.6	9.525	3.97	0.20	4.4	
Finishing (High precision)	11T304-VP1	•	•	•	•	•	11.6	9.525	3.97	0.40	4.4	55° \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
	070201MFN-VP1	•		•			7.8	6.35	2.38	< 0.10	2.8	
CGT-VP1	070202MFN-VP1	•		•			7.8	6.35	2.38	< 0.20	2.8	<u></u>
	070204MFN-VP1	•		•			7.8	6.35	2.38	< 0.40	2.8	
	11T301MFN-VP1	•		•			11.6	9.525	3.97	< 0.10	4.4	
Finishing	11T302MFN-VP1	•		•			11.6	9.525	3.97	< 0.20	4.4	7
Jtra high precision)	11T304MFN-VP1	•		•			11.6	9.525	3.97	< 0.40	4.4	55°
	0802003R-KF						8.15	4.76	2.38	0.03	2.38	
TCGT-KF	0802003h-KF						8.0	4.76	2.38	0.03	2.38	- 60°
	080201R-KF						7.7	4.76	2.38	0.10	2.38	
	08020003L-KF						8.15	4.76	2.38	0.20	2.38	d\
	08020003L-KF						8.0	4.76	2.38	0.03	2.38	
Finishing	080201L-KF						7.7	4.76	2.38	0.10	2.38	
(High precision)	3302022 111						,	0		0.20		
TCGT-FS	110201-FS	•		•			9.3	6.35	2.38	0.10	2.8	60°
A	110202-FS	•		•			9.1	6.35	2.38	0.20	2.8	
new	110204-FS	•		•			8.6	6.35	2.38	0.40	2.8	
												dı dı
Finishing												7°
(High precision)												
TCGT-FS	110201MFN-FS						9.3	6.35	3.18	< 0.10	3.4	- 60°
new new	110202MFN-FS						9.1	6.35	3.18	< 0.20	3.4	
	110204MFN-FS						8.6	6.35	3.18	< 0.40	3.4	
Cinichina												dı
Finishing Jtra high precision)												7°
	1103003R-KF	•		•			7.8	6.35	2.38	0.03	2.8	
VBGT-KF	110301R-KF	•		•			7.8	6.35	2.38	0.10	2.8	] ,
	110302R-KF	•		•			7.8	6.35	2.38	0.20	2.8	
	1103003L-KF	•		•			11.6	9.525	3.97	0.03	4.4	
Finishing	110301L-KF	•		•			11.6	9.525	3.97	0.10	4.4	35.
(High precision)	110302L-KF	•		•			11.6	9.525	3.97	0.20	4.4	
VBGT-KM	1103003R-KM	•		•			7.8	6.35	2.38	0.03	2.8	-
V DG I-KIVI	110301R-KM	•		•			7.8	6.35	2.38	0.10	2.8	
6	110302R-KM	•		•			7.8	6.35	2.38	0.20	2.8	
	1103003L-KM	•		•			11.6	9.525	3.97	0.03	4.4	5
Medium to finishing	110301L-KM 110302L-KM	•		•			11.6 11.6	9.525 9.525	3.97	0.10	4.4	35° 🗓
(High precision)	I IUJUZE-KIVI						11.0	ø.525	5.97	0.20	4.4	-
	110301-FS	•		•			11.0	6.35	3.18	0.10	2.8	
VBGT-FS	110301-FS	•		•			11.0	6.35	3.18	0.20	2.8	r
VBG1-F3	110304-FS	•		•			11.0	6.35	3.18	0.40	2.8	
	160401-FS	•		•			16.3	9.525	4.76	0.10	4.4	
Finishing	160402-FS	•		•			16.1	9.525	4.76	0.20	4.4	35° t
(High precision)	160404-FS	•		•			15.7	9.525	4.76	0.40	4.4	] <del>  </del>
VBGT-FS	110301MFN-FS						10.8	6.35	3.18	< 0.10	2.8	
new	110302MFN-FS						10.6	6.35	3.18	< 0.20	2.8	
	110304MFN-FS						11.4	6.35	3.18	< 0.40	2.8	
	160401MFN-FS						16.3	9.525	4.76	< 0.10	4.4	
Finishing Itra high precision)	160402MFN-FS						16.1	9.525	4.76	< 0.20	4.4	35° \
	160404MFN-FS						15.7	9.525	4.76	< 0.40	4.4	
VCGT-KF	1103003R-KF						11.0	6.35	3.18	0.03	2.8	_
	110301R-KF 110302R-KF						11.0	6.35	3.18	0.10	2.8	
	110302H-KF 1103003L-KF						11.0	6.35	3.18	0.20	2.8	
Finishing	1103003L-KF						11.0	6.35	3.18	0.03	2.8	35°
(High precision)	110301L-KF						11.0	6.35	3.18	0.10	2.8	· ·
								3.50	5.70	3.20		<u> </u>

# B Auto Tools (ISO)

			Coa	ated		Uncoated		Dime	nsions	(mm)		
Picture	Designation	PC5300	PC8105	PC8110	PC8115	H01	ı	d	t	r	d1	Configuration
	1103005MFR-KF	•		•			11.0	6.35	3.18	< 0.05	2.8	
VCET-KF	110301MFR-KF	•		•			11.0	6.35	3.18	< 0.10	2.8	
	110302MFR-KF	•		•			11.0	6.35	3.18	< 0.20	2.8	
	1103005MFL-KF	•		•			11.0	6.35	3.18	< 0.05	2.8	
Finishing	110301MFL-KF	•		•			11.0	6.35	3.18	< 0.10	2.8	
tra high precision)	110302MFL-KF	•		•			11.0	6.35	3.18	< 0.20	2.8	35°X
	1103003R-KM						11.0	6.35	3.18	0.03	2.8	
/CGT-KM	110301R-KM						11.0	6.35	3.18	0.10	2.8	r
	110302R-KM						11.0	6.35	3.18	0.20	2.8	
	1103003L-KM						11.0	6.35	3.18	0.03	2.8	
edium to finishing	110301L-KM						11.0	6.35	3.18	0.10	2.8	35
High precision)	110302L-KM						11.0	6.35	3.18	0.20	2.8	  -
	1103005MFR-KM	•		•			11.0	6.35	3.18	< 0.05	2.8	
/CET-KM	1103005WFR-KM			•			11.0	6.35	3.18	< 0.10	2.8	
	110302MFR-KM	•		•			11.0	6.35	3.18	< 0.20	2.8	
0	3005MFL-KM	•		•			11.0	6.35	3.18	< 0.05	2.8	
edium to finishing	301MFL-KM	•		•			11.0	6.35	3.18	< 0.10	2.8	35°
ra high precision)	302MFL-KM	•		•			11.0	6.35	3.18	< 0.20	2.8	35 1/2
	110301-FS	•		•			11.0	6.35	3.18	0.10	2.8	
/CGT-FS	110302-FS	•		•			11.0	6.35	3.18	0.20	2.8	
new	110304-FS	•		•			11.0	6.35	3.18	0.40	2.8	
	160401-FS	•		•			16.3	9.525	4.76	0.10	4.4	
Finishing	160402-FS	•		•			16.1	9.525	4.76	0.20	4.4	35°
High precision)	160404-FS	•		•			15.7	9.525	4.76	0.40	4.4	
	110301MFN-FS						10.8	6.35	3.18	< 0.10	2.8	
	110301MFN-FS						10.6	6.35	3.18	< 0.10	2.8	
VCGT-FS	110304MFN-FS						11.4	6.35	3.18	< 0.40	2.8	
	160401MFN-FS						16.3	9.525	4.76	< 0.10	4.4	
Finishing	160402MFN-FS						16.1	9.525	4.76	< 0.20	4.4	
tra high precision)	160404MFN-FS						15.7	9.525	4.76	< 0.40	4.4	35°
	440004 MC			•			10.0	0.05	0.10	0.10	0.0	
/CGT-MS	110301-MS 110302-MS	•					10.8	6.35	3.18	0.10	2.8	·
new	110302-MS	•		•			11.4	6.35	3.18	0.40	2.8	
Medium cutting	110304-1013						11.4	0.55	0.10	0.40	2.0	35°
(High precision)												35 7 1
/CGT-MS_	11T301MFN-MS	•		•			10.8	6.35	3.18	< 0.10	2.8	r
new	11T302MFN-MS	•		•			10.6	6.35	3.18	< 0.20	2.8	
	11T304MFN-MS	•		•			11.4	6.35	3.18	< 0.40	2.8	
Medium cutting tra high precision)												35°
li a High precision)			•	•	•	_			0.40	0.10	2.8	
	110301-VP1	•	•				11.0	6.35	3.18			
	110301-VP1 110302-VP1	•	•	•	•	•	11.0	6.35	3.18	0.10	2.8	
				•							2.8	
7CGT-VP1	110302-VP1	•			•	•	11.0	6.35	3.18	0.20		d
/CGT-VP1	110302-VP1 110304-VP1	•		•	•	•	11.0	6.35 6.35	3.18 3.18	0.20	2.8	35
Finishing (High precision)	110302-VP1 110304-VP1 110301MFN-VP1	•		•	•	•	11.0 11.0	6.35 6.35 6.35	3.18 3.18 3.18	0.20 0.40 < 0.10	2.8	35
Finishing (High precision)	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1	•		•	•	•	11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35	3.18 3.18 3.18 3.18	0.20 0.40 < 0.10 < 0.20	2.8 2.8 2.8	35 d
Finishing (High precision)	110302-VP1 110304-VP1 110301MFN-VP1	•		•	•	•	11.0 11.0	6.35 6.35 6.35	3.18 3.18 3.18	0.20 0.40 < 0.10	2.8	35
Finishing (High precision)  CGT-VP1  Finishing	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1	•		•	•	•	11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35	3.18 3.18 3.18 3.18	0.20 0.40 < 0.10 < 0.20	2.8 2.8 2.8	35
Finishing (High precision)  CGT-VP1  Finishing tra high precision)	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1	•		•	•	•	11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35	3.18 3.18 3.18 3.18	0.20 0.40 < 0.10 < 0.20	2.8 2.8 2.8	d
Finishing (High precision)  CGT-VP1  Finishing tra high precision)	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS	•		•	•	•	11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35	3.18 3.18 3.18 3.18 3.18	0.20 0.40 < 0.10 < 0.20 < 0.40 < 0.08 < 0.10	2.8 2.8 2.8 2.8 2.8	
Finishing (High precision)  CGT-VP1  Finishing training t	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS 120302FN-MS	•		0 0 0 0 0 0	•	•	11.0 11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00 3.00	0.20 0.40 < 0.10 < 0.20 < 0.40 < 0.08 < 0.10 < 0.20	2.8 2.8 2.8 2.8 2.8 2.8 2.8	
Finishing (High precision)  CGT-VP1  Finishing tra high precision)  CGT-MS  Medium cutting	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS	•		•	•	•	11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00	0.20 0.40 < 0.10 < 0.20 < 0.40 < 0.08 < 0.10	2.8 2.8 2.8 2.8 2.8	
Finishing (High precision)  CGT-VP1  Finishing tra high precision)  CGT-MS  Medium cutting	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS 120302FN-MS 120304FN-MS	•		• • • • • • • • • • • • • • • • • • •	•	•	11.0 11.0 11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50 7.50 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00 3.00 3.00	0.20 0.40 < 0.10 < 0.20 < 0.40 < 0.08 < 0.10 < 0.20 < 0.40	2.8 2.8 2.8 2.8 2.8 2.8 2.8	d
Finishing (High precision)  CGT-VP1  Finishing (tra high precision)  CGT-MS  Medium cutting (tra high precision)	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS 120302FN-MS 120304FN-MS	•		• • • • • • • • • • • • • • • • • • •	•	•	11.0 11.0 11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50 7.50 7.50 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00 3.00 3.00 3.00	0.20 0.40 < 0.10 < 0.20 < 0.40 < 0.08 < 0.10 < 0.20 < 0.40	2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8	
Finishing (High precision)  CGT-VP1  Finishing (Trinshing (Trinshi	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS 120302FN-MS 120304FN-MS	• • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • • • • • • • • •	•	•	11.0 11.0 11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50 7.50 7.50 7.50 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00 3.00 3.00 3.18 3.18	<ul> <li>0.20</li> <li>0.40</li> <li>&lt; 0.10</li> <li>&lt; 0.20</li> <li>&lt; 0.40</li> <li>&lt; 0.08</li> <li>&lt; 0.10</li> <li>&lt; 0.20</li> <li>&lt; 0.40</li> <li>&lt; 0.00</li> <li>&lt; 0.10</li> </ul>	2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8	
Finishing (High precision)  CGT-VP1  Finishing tra high precision)  CGT-MS  Medium cutting tra high precision)	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS 120302FN-MS 120304FN-MS 120300MFR-VP1 120301MFR-VP1 120302MFR-VP1	• • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • • • • • • • • •	•	•	11.0 11.0 11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50 7.50 7.50 7.50 7.50 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00 3.00 3.00 3.18 3.18 3.18	0.20 0.40 < 0.10 < 0.20 < 0.40 < 0.08 < 0.10 < 0.20 < 0.40 < 0.20 < 0.40	2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8	
Finishing (High precision)  CGT-VP1  Finishing (tra high precision)  CGT-MS  Medium cutting (tra high precision)	110302-VP1 110304-VP1 110301MFN-VP1 110302MFN-VP1 110304MFN-VP1 1203008FN-MS 120301FN-MS 120302FN-MS 120304FN-MS	• • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • • • • • • • • •	•	•	11.0 11.0 11.0 11.0 11.0 11.0 11.0 11.0	6.35 6.35 6.35 6.35 6.35 7.50 7.50 7.50 7.50 7.50	3.18 3.18 3.18 3.18 3.18 3.00 3.00 3.00 3.00 3.18 3.18	<ul> <li>0.20</li> <li>0.40</li> <li>&lt; 0.10</li> <li>&lt; 0.20</li> <li>&lt; 0.40</li> <li>&lt; 0.08</li> <li>&lt; 0.10</li> <li>&lt; 0.20</li> <li>&lt; 0.40</li> <li>&lt; 0.00</li> <li>&lt; 0.10</li> </ul>	2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8 2.8	d


				ated		Uncoated		Dime	nsions	(mm)		
Picture	Designation	PC5300	PC8105	PC8110	PC8115	H01	ı	d	t	r	d1	Configuration
	080201R-KF	•		•			8.0	4.76	2.38	0.10	2.3	
	080202R-KF	•		•			8.0	4.76	2.38	0.20	2.3	
	1103003R-KF	•		•			11.0	6.35	3.18	0.03	2.8	
	110301R-KF	•		•			11.0	6.35	3.18	0.10	2.8	
	110302R-KF	•		•			11.0	6.35	3.18	0.20	2.8	
VDOT KE	080201L-KF	•		•			8.0	4.76	2.38	0.10	2.3	
VPGT-KF	080202L-KF	•		•			8.0	4.76	2.38	0.10	2.3	
6		_										<u> </u>
	1103003L-KF	•		•			11.0	6.35	3.18	0.03	2.8	
Finishing	110301L-KF	•		•			11.0	6.35	3.18	0.10	2.8	
(High precision)	110302L-KF	•		•			11.0	6.35	3.18	0.20	2.8	35 A
	0802005MFR-KF	•		•			8.0	6.35	2.38	< 0.05	2.3	
	080201MFR-KF	•		•			8.0	6.35	2.38	< 0.10	2.3	
VDET_KE	080202MFR-KF	•		•			8.0	6.35	2.38	< 0.20	2.3	,
VPET-KF	0802005MFL-KF	•		•			8.0	6.35	2.38	< 0.05	2.3	
-	080201MFL-KF	•		•			8.0	6.35	2.38	< 0.10	2.3	d d
Finishing (Utra high precision)	080202MFL-KF	•		•			8.0	6.35	2.38	< 0.20	2.3	35 11°
	080201R-KM 080202R-KM	•		•			8.0	4.76 4.76	2.38	0.10	2.3	
				•								
	1103003R-KM	•					11.0	6.35	3.18	0.03	2.8	
	110301R-KM	•		•			11.0	6.35	3.18	0.10	2.8	
VDCT KM	110302R-KM	•		•			11.0	6.35	3.18	0.20	2.8	
VPGT-KM	080201L-KM	•		•			8.0	4.76	2.38	0.10	2.3	
	080202L-KM	•		•			8.0	4.76	2.38	0.20	2.3	d     d
	1103003L-KM	•		•			11.0	6.35	3.18	0.03	2.8	35*111
Medium to finishing	110301L-KM	•		•			11.0	6.35	3.18	0.10	2.8	,
(High precision)	110302L-KM	•		•			11.0	6.35	3.18	0.20	2.8	
	0802005MFR-KM	•		•			8.0	6.35	3.18	< 0.05	2.8	
	080201MFR-KM	•		•			8.0	6.35	3.18	< 0.10	2.8	
	080202MFR-KM	•		•			8.0	6.35	3.18	< 0.20	2.8	
VPET-KM	0802005MFL-KM	•		•			8.0	6.35	3.18	< 0.05	2.8	
A I. P. ILYIAI	080201MFL-KM	•		•			8.0	6.35	3.18	< 0.10	2.8	d - dı
-	080202MFL-KM	•		•			8.0	6.35	3.18	< 0.20	2.8	35
Medium to finishing (Utra high precision)	COMMENT DE INITIAL						2.0	2.00	5.10	. 0.20		
	110301-VP1	•	•	•	•	•	11.0	6.35	3.18	0.10	2.8	
	110302-VP1	•	•	•	•	•	11.0	6.35	3.18	0.20	2.8	
VPGT-VP1	110304-VP1	•	•	•	•	•	11.0	6.35	3.18	0.40	2.8	
Medium cutting (High precision)												35 d d d d d d d d d d d d d d d d d d d
	110301MFN-VP1	•		•			11.0	6.35	3.18	< 0.10	2.8	
VBCTVS	110302MFN-VP1	•		•			11.0	6.35	3.18	< 0.20	2.8	
VPGT-VP1  Medium cutting	110304MFN-VP1	•		•			11.0	6.35	3.18	< 0.40	2.8	35

## Auto tools (Blade type)

- Blade insert for automatic lathes
- For external machining of precise small parts
- 4 types SSB (for back turning), SGB (for grooving), SBT (for threading), SBC (for parting off)
- Convenient use of one holder to all blade inserts
- Exclusive holder for close cutting action to the sub spindle

### Code system

Insert




### Types of blade insert



# SBHR/L








		-49064								(mm)
	Designation	н	W	L	S	h	Q	Insert	Screw	Wrench
SBHR/L	1010-K25	10	10	125	10	10	27			
	1212-K25	12	12	125	12	12	27	SB□R/L25	FTKA0409S	TW09P
	1616-K25	16	16	125	16	16	27			

# SBHR/L-X (Sub spindle)



SBBR SBGR SBTR SBCR





		-4000									(mm)
	Designation	н	W	L	S1	S2	h	Q	Insert	Screw	Wrench
SBHR/L	1010-K25-X	10	10	125	10	7.5	10	27	SB∏R/L25	FTKA0407S	TW09P
	1212-K25-X	12	12	125	12	7.5	12	27	SD∐N/L23	FIRAU4075	10095

ion				Coa	ated					Dime	ensi	ons (	mm)					
icat	Picture	Designation	PC	8110	PC	5300										range	Configuration	Feed direction
Application			R	L	R	L	ı	α	t	r	La	ar	f	<b>D-</b> мах		Max.		
		SBBR/L 25005	•	•	•	•	25	59	3.18	0.05	-	-	-	-	-	-		
		25010	•	•	•	•	25	59	3.18	0.10	-	-	-	-	-	-		
<u> </u>	400	25020	•	•	•	•	25	59	3.18	0.20	-	-	-	-	-	-	t r	
Back turning	SBBR/L																α <b>1</b>	
		SBGR/L 2505	•	•	•	•	25	-	-	0.05	0.5	1.35	-	-	-	-		
		2510	•	•	•	•	25	-	-	0.05	1.0	2.75	-	-	-	-	La	
0	400	2515	•	•	•	•	25	-	-	0.05	1.5	3.75	-	-	-	-	r	
Grooving	0	2520	•	•	•	•	25	-	-	0.05	2.0	3.75	-	-	-	-	T ar	
<u>o</u>	-	2525	•	•	•	•	25	-	-	0.05	2.5	3.75	-	-	-	-	1	
0	SBGR/L																<u>"                                    </u>	
		SBTR/L 2560-N-005		•	•	•	25	-	-	0.05	-	-	1.59	-	0.2	2.0		
		2560-N-010	-	•	•	•	25	-	-	0.10	-	-	1.59	-	1.0	2.0	<del>-f</del> /r	
g	100	2560-R-005		•	•	•	25	-	-	0.05	-	-	0.6	-	0.2	1.5		
adi		2560-R-010	_	•	•	•	25	-	-	0.10	-	-	0.6	-	1.0	1.5		
Threading	1	2560-L-005		•	•	•	25	-	-	0.05	-	-	0.6	-	0.2	1.5	$\mathbf{H} \mathbf{H} \mathbf{H} \mathbf{I}$	
	SBTR/L	2560-L-010	)	•	•	•	25	-	-	0.10	-	-	0.6	-	1.0	1.5	L N R	4
																	L IN N	



# **B** Auto Tools (Blade type)

### Insert

2				Coa	ated					Dime	ensid	ons (r	nm)					
<u>:</u>	Picture	Designation	PC	3110	PC	5300									Pitch	range	Configuration	Feed direction
Annlication			R	L	R	L	ı	α	t	r	La	ar	f	<b>D</b> -мах	Min.	Max.		
		SBCR/L 250708-N	•	•	•	•	25	0	-	0.05	0.7	4.3	-	8	-	-		_
		251012-N	•	•	•	•	25	0	-	0.05		6.3	-	12	-	-	La	
		251512-N	•	•	•	•	25	0	-	0.05		6.3	-	12	-	-		<del></del>
		252016-N	•	•	•	•	25	0	-	0.05	2.0	8.3	-	16	-	-	ar Dmax	│
		250708-R	•	•	•	•	25	15	-	0.05	0.7	4.3	-	8	-	-		
		251012-R	•	•	•	•	25	15	-	0.05	1.0	6.3	-	12	-	-	La	
		251512-R	•	•	•	•	25	15	-	0.05	1.5	6.3	-	12	-	-		
		252016-R	•	•	•	•	25	15	-	0.05	2.0	8.3	-	16	-	-	α Dmax	│ │ <mark>│ │</mark> <u>†</u> │
Darting off	SBCR/L																	
<u>.</u>	02010/2	250708-L	•	•	•	•	25	15	-	0.05			-	8	-	-		
^		251012-L	•	•	•	•	25	15	-	0.05		6.3	-	12	-	-	La r	
		251512-L	•	•	•	•	25	15	-	0.05		6.3	-	12	-	-	α D <sub>max</sub>	<del></del>
		<u>252016-L</u>	•	•	•	•	25	15	-	0.05	2.0	8.3	-	16	-	-	da la	
		251012-T	•	•	•	•	25	0	-	0.05		6.3	-	12	-	-		
		251512-T	•	•	•	•	25	0	-	0.05		6.3	-	12	-	-	La	
		<u>252016-T</u>	•	•	•	•	25	0	-	0.05	2.0	8.3	-	16	-	-	ar Dmax	


• : Stock item

## **Auto Tools (For multi utility)**


- Multifunctional insert for automatic lathes
- For external machining of precise small parts
- 5 types SB (for back turning), SG (for grooving), ST (for threading), SC (for parting off), SGB (for grooving and back turning)
- Convenient use of one holder to all inserts
- Offset "0" to all ISO type holders

### Code system

B: Back turning G: Grooving C: Parting off T: Threading GB: Grooving and back turning







### Types of multifunctional insert


Possible to apply various types of blade inserts to one holder (Ex: All designations of 06 size inserts can be applied to one 06 size holder.)



### Recommended cutting conditions

		Turi	ning	Groo	oving	Partii	ng off	Back t	urning
	Workpiece	Cutting speed, vc (m/min)	Feed, fn (mm/rev)	Cutting speed, vc (m/min)	Feed, fn (mm/rev)	Cutting speed, vc (m/min)	Feed, fn (mm/rev)	Cutting speed, vc (m/min)	Feed, fn (mm/rev)
В	Carbon steel	50~150	0.01~0.25	50~150	0.02~0.08	50~150	0.01~0.08	50~150	0.01~0.25
-	Free cutting steel	30~150	0.02~0.25	30~150	0.02~0.08	30~150	0.01~0.08	30~150	0.01~0.25
M	Stainless steel	50~120	0.02~0.20	30~120	0.02~0.05	30~120	0.02~0.05	30~120	0.02~0.20
N	Non-ferrous metal	70~200	0.03~0.25	70~200	0.03~0.10	70~200	0.03~0.10	70~200	0.03~0.30

# **B** Auto Tools (For multi utility)



										(mm)
[	Designation	н	W	L	S	h	h1	Insert	Screw	Wrench
SXGNR/L	1010-X06A	10	10	125	10	10	6			
	1212-X06A	12	12	125	12	12	6	S□R/L 06	FTNA 0408	TW 15P
	1616-X06A	16	16	125	16	16	6	3⊔n/L00	F I NA 0406	IW ISF
	2020-X06A	20	20	125	20	20	6			
	1212-X08A	12	12	130	12	12	8			
	1616-X08A	16	16	130	16	16	8	S□R/L 08	FTNA 0411	TW 15P
	2020-X08A	20	20	130	20	20	8			

ou				Coa	ated			Dim	ensi	ons (r	nm)				
Application	Picture	D	esignation	PC	9030									Configuration	Feed
Appl				R	L	b <sub>1</sub>	b	W	L	r	h	Т-мах	ØD		direction
		SBR/L	060520-10-R00			1	2	8	22	0	6	5.5	-		
			060520-10-R05			1	2	8	22	0.05	6	5.5	-		
			060520-10-R10			1	2	8	22	0.1	6	5.5	-		
			060630-20-R00			2	3	8	24	0	6	6.5	-		
<u>n</u>	SBR/L		060630-20-R05			2	3	8	24	0.05	6	6.5	-	W 51 b	
Back turning			060630-20-R10			2	3	8	24	0.1	6	6.5	-	T-MAX	
S T			080630-20-R00			2	3	8	23	0	8	6.5	-	70° L	
Ba			080630-20-R05			2	3	8	23	0.05	8	6.5	-	h	Ĭ
			080630-20-R10			2	3	8	23	0.1	8	6.5	-		101
			080840-20-R00			2	4	8	27	0	8	8.5	-	10°	
			080840-20-R05			2	4	8	27	0.05	8	8.5	-		
			080840-20-R10			2	4	8	27	0.1	8	8.5	-		
		SCR/L	060610-R00			-	1	8	24	0	6	-	11		
			060610-R05	•		-	1	8	24	0.05	6	-	11		
			060610-R10	•		-	1	8	24	0.1	6	-	11		
			060615-R00			-	1.5	8	24	0	6	-	11		
			060615-R05	•		-	1.5	8	24	0.05	6	-	11		
			060615-R10	•		-	1.5	8	24	0.1	6	-	11		
			060620-R00			-	2	8	24	0	6	-	11		
			060620-R05	•		-	2	8	24	0.05	6	-	11	15° ØDmax.	
-	SCR/L		060620-R10	•		-	2	8	24	0.1	6	-	11	W machining diameter	
Parting off			081015-R00			-	1.5	8	31	0	8	-	18	diameter	
Ę			081015-R05			-	1.5	8	31	0.05	8	-	18		1
Pa			081015-R10			-	1.5	8	31	0.1	8	-	18	h	19
			081020-R00			-	2	8	31	0	8	-	18	8	
	_		081020-R05			-	2	8	31	0.05	8	-	18		
			081020-R10	•		-	2	8	31	0.1	8	-	18		
			081025-R00			-	2.5	8	31	0	8	-	18		
			081025-R05	•		-	2.5	8	31	0.05	8	-	18		
			081025-R10	•		-	2.5	8	31	0.1	8	-	18		
			081030-R00			-	3	8	31	0	8	-	18		
			081030-R05	•		-	3	8	31	0.05	8	-	18		
			081030-R10			-	3	8	31	0.1	8	-	18		

### Insert

o				Coa	ated			Dim	ensio	ns (	mm)				
icati	Picture	De	esignation	PCS	9030									Configuration	Feed
Application			ŭ	R	L	b	W	L	r	h	Т-мах	ØD	Pitch	, and the second	direction
		SGR/L	060610-R00			1	8	24	0	6	-	11	-		
			060610-R05	•		1	8	24	0.05	6	-	11	-		
			060610-R10	•		1	8	24	0.1	6	-	11	-		
			060615-R00			1.5	8	24	0	6	-	11	-		
			060615-R05	•		1.5	8	24	0.05	6	-	11	-		
			060615-R10	•		1.5	8	24	0.1	6	-	11	-		
			060620-R00			2	8	24	0	6	-	11	-		
			060620-R05	•		2	8	24	0.05	6	-	11	-	ØDmax.	
<u></u>	SGR/L		060620-R10 081015-R00			1.5	8	24 31	0.1	8		11	-	b machining diameter	
Grooving			081015-R05			1.5	8	31	0.05	8	÷	18	-		
Š.			081015-R10			1.5	8	31	0.03	8	_	18	-	h	
_			081020-R00			2	8	31	0	8		18	-		
			081020-R05	•		2	8	31	0.05	8	-	18	-	0	
			081020-R10			2	8	31	0.1	8	-	18	-		
			081025-R00			2.5	8	31	0	8	-	18	-		
			081025-R05			2.5	8	31	0.05	8	-	18	-		
			081025-R10			2.5	8	31	0.1	8	-	18	-		
			081030-R00			3	8	31	0	8	-	18	-		
			081030-R05			3	8	31	0.05	8	-	18	-		
			081030-R10			3	8	31	0.1	8	-	18	-		
		SGBR/L	0604520-R00			2	8	22	0	6	4.5	-	-		
			0604520-R05			2	8	22	0.05	6	4.5	-	-		
			0604520-R10			2	8	22	0.1	6	4.5	-	-		
g			0604525-R00 0604525-R05			2.5	8	22	0.05	6	4.5	-	-	T-MAX	
			0604525-R10			2.5	8	22	0.05	6	4.5	-	-	b	
5	SGBR/L		0605530-R00			3	8	24	0.1	6	5.5	-	_	w w	
0	-		0605530-R05			3	8	24	0.05	6	5.5	-	_	r	
<u></u>			0605530-R10			3	8	24	0.1	6	5.5		-		
			0805525-R00			2.5	8	24	0	8	5.5	-	-	h	
Grooving and back turning			0805525-R05			2.5	8	24	0.05	8	5.5	-	-		[0]
5			0805525-R10			2.5	8	24	0.1	8	5.5	-	-	8	
			0806530-R00			3	8	26	0	8	6.5	-	-		
			0806530-R05			3	8	26	0.05	8	6.5	-	-		
			0806530-R10			3	8	26	0.1	8	6.5	-	-		
		STR/L	06073215			3.2	8		0.06	6	7		0.5-1.5		
			06073230			3.2	8		0.19		7		1.5-3.0		
			08103215			3.2	8	31			10.5		0.5-1.5		
			08103230			3.2	8	31	0.19	8	10.5	-	1.5-3.0		
Threading	STR/L													60 T-MAX	-


• : Stock item

## AutoTools (KGT/MGT type)


- Grooving insert for automatic lathes
- Exclusive holder for automatic lathes
- · Economic double sided insert
- Strong clamping system secures stable machining and precision.
- A wide selection of chip breakers according to various cutting conditions such as low/high feed, continuous/interrupted machining, etc.

### Code system

· Insert



Holder



### Chip breaker line-up

### **KGT Type**

## KGMN-L · Sharp cutting edge · For low feed machining · For small diameter parts KGMN-T · Sharp cutting edge · Stronger chip control

## KGMR/L-RP

- Strong cutting edge
- For high feed machining
- For iInterrupted cutting Right/Left handed

For turning and grooving



## MGT Type

- · Easier chip control by narrowing chip width with the use of chip breaker on rake surface center
- · Smooth chip flow by small dots in external machining
- · Available for both external machining and grooving

### KGMN-R

- Reinforced cutting edge
   For high feed machining
- · For interrupted cutting

### KGMR/L-LP

- Sharp cutting edge
- For low feed machining

· Alloy steel

· Small diameter component · Right/Left handed

### KGMN-C

- · Improved chip control
- Copying
- Relief · Carbon steel
- Cast iron Stainless

### MGMN-G



- Specially designed chip breaker allows narrower chips to promote better chip flow with the use of
- · Exclusive chip breaker for grooving



**Turning** 

• R type insert

(mm)


# KGEHR/L-D00A



**KGGN KRGN** 

**KGMN KRMN** 

KGMR/L



Dog	lanation.			Dim	ensions (	mm)			Incort	Screw	Wrench
Des	signation	н	w	L1	L	S	h1	ØD_MAX	Insert	9	
KGEHR/L	1010-2-D20A	10	10	19	125	10.2	2	20			
	1212-2-D25A	12	12	19	125	12.2	2	25	KGMN200-□-□   KGMR/L200-□-□		
	1414-2-D25A	14	14	19	125	14.2	-	25	KRMN200-C		
	1616-2-D32A	16	16	24	125	16.2	-	32		ETNA0412	TW15L
	1212-3-D25A	12	12	19	130	12.4	2	25	KGMN300-□-□ KGMR/L300-□-□		
	1616-3-D32A	16	16	24	130	16.4	-	32	KRMN300-C		

# KGEHR/L-D00B

### Grooving, turning, parting off

Insert




**KGGN** KRGN

Designation

**KGMN KRMN** 

KGMR/L



ш	HI	
لا		• R type insert
		(mm)
	Screw	Wrench
	<b>6</b>	
	MHA0512	HW40L

		н	W	L	S	h1	ØD_MAX		(a)	
KGEHR/L	1010-2-D30B	10	10	125	10.2	6.6	30			
	1212-2-D25B	12	12	125	12.5	3.5	25	KGMN200-□-□   KGMR/L200-□-□		
	1212-2-D30B	12	12	125	12.2	3.5	30	KRMN200-C		
	1616-2-D32B	16	16	125	16.2	-	32		MHA0512	HW40L
	1212-3-D25B	12	12	125	12.4	3.5	25	KGMN300-□-□		
	1212-3-D32B	12	12	125	12.4	3.5	32	KGMR/L300-□-□		
	1616-3-D32B	16	16	125	16.4	-	32	KRMN300-C		

Dimensions (mm)

### **⊙** KGT Insert

uo						C	oate	ed				Dime	nsions	(mm)			
Application	Picture	De	esignation	NC3120	NC3225	NC5330	NC6315	PC3035	PC5300	PC9030	b	r	I	d	α°	Configuration	
	KGMN-L	KGMN	200-02-L		•	•		•	•	•	2.0	0.2	20	1.7	-	d <sub>j</sub> b	
ing	KGWIN-L		300-02-L		•	•		•	•	•	3.0	0.2	20	2.3	-	1	
Grooving	1															7. 1	
	KGMN-R	KGMN	200-02-R		•	•		•	•	•	2.0	0.2	20	1.7	-		
ng: off	KGWIN-K		300-02-R		•	•		•	•	•	3.0	0.2	20	2.3	-	d b	
Grooving- Parting off	1															7,	
Ðι	KGMN-T	KGMN	200-02-T		•	•	•	•	•	•	2.0	0.2	20	1.7	-		
Ē	KGIVIN-1		300-02-T		•	•	•	•	•	•	3.0	0.2	20	2.3	-	d	
y-tu			300-04-T		•	•	•	•	•	•	3.0	0.4	20	2.3	-	1	
Grooving-turning																	7.

# **B** Auto Tools (KGT/MGT type)


### KGT Insert

on						C	oate	ed				Dime	nsions	(mm)			
Application	Picture	D	esignation	NC3120	NC3225	NC5330	NC6315	PC3035	PC5300	PC9030	b	r	ı	d	α°	Configuration	
ed)	KGMR-LP	KGMR	200-6D-LP			•			•		2.0	0.2	20	-	6	b	
Parting off (Right handed)			200-15D-LP			•			•		2.0	0.2	20	-	15	<u>a</u> 1 <u>r</u>	
Parti ight			300-6D-LP			•			•		3.0	0.2	20	-	6		
			300-15D-LP			•			•		3.0	0.2	20	-	15	17	
Parting off (Right handed)	KGMR-RP	KGMR	200-6D-RP			•			•		2.0	0.2	20	-	6	b	
ng o			200-15D-RP			•			•		2.0	0.2	20	-	15	<u> </u>	
Parti			300-6D-RP			•			•		3.0	0.2	20	-	6		
_ =			300-15D-RP			•			•		3.0	0.2	20	-	15	-42	
⊯ (pa	KGML-LP	KGML	200-6D-LP								2.0	0.2	20	1.7	6	d b	
ng o					200-15D-LP								2.0	0.2	20	1.7	15
Parting off (Left handed)	4		300-6D-LP								3.0	0.2	20	2.3	6		
=			300-15D-LP								3.0	0.2	20	2.3	15		
# (p	KGML-RP	KGML	200-6D-RP								2.0	0.2	20	1.7	6	d b	
ng o			200-15D-RP								2.0	0.2	20	1.7	15	1 2 1	
Parting off (Left handed)	4		300-6D-RP								3.0	0.2	20	2.3	6		
			300-15D-RP								3.0	0.2	20	2.3	15		
<u>ත</u>	KRMN-C	KRMN	200-C		•	•	•	•	•		2.0	1.0	20	1.7	-	d <sub>j</sub>	
. i		300-C		•	•	•	•	•		3.0	1.5	20	2.2	-			
Copying																7°-	

• : Stock item

# MGEHR/L







R type insert (mm)

										\ /
D	esignation	ØD	H = h	W	L	Q	t	Insert	Screw	Wrench
MGEHR/L	1010-X15A	20	10	10	125	18	1.5	MGMN150-G	ETNA 0412	TW 15L
	1212-X15A	25	12	12	125	19.5	1.5	IVIGIVIIN 150-G	ETNA 0412	TW TOL
	1010-X20A	20	10	10	125	18	2	MCMNIOOO M		
	1212-X20A	25	12	12	125	19.5	2	MGMN200-M MGMN200-G	ETNA 0412	TW 15L
	1616-X20A	32	16	16	125	25	2	IVIGIVIIVZ00-G		
	1010-X25A	20	10	10	125	20	2.5	MOMNIOTO M		
	1212-X25A	25	12	12	125	20	2.5	MGMN250-M MGMN250-G	ETNA 0412	TW 15L
	1616-X25A	32	16	16	125	25	2.5	IVIGIVII\250-G		


### **⊙** MGT Insert

on						Co	oate	da			Un	icoa	ted		Dime	nsions	(mm)		
Application	Picture	Des	signation	NC3120	NC3225	NC3030	NC5330	NC6315	PC5300	PC9030	H01	G10	ST30A	b	r	I	d	t	Configuration
	MGMN-G	MGMN	150-G		•	•			•	•	•			1.5	0.15	16.0	1.2	3.5	d
<u>B</u>		200-G 250-G	•	•	•				•	•			2.0	0.2	16.0	1.6	3.5	b Company	
Grooving	Grooving		250-G		•	•			•	•				2.5	0.2	18.5	2.0	3.85	
	MGMN-M	MGMN	200-M	•	•	•	•		•	•	•			2.0	0.2	16.0	1.6	3.5	d
ing	100	250-M	250-M	•	•	•			•	•				2.5	0.2	18.5	2.0	3.85	<b>్డ్ర</b> ిఫ్
Grooving	4																		7'

## **Auto Tools (MSB tool)**

- High hardness grade guarantees longer tool life
- Various kinds of machining (Fitting, Valve, Medical parts, Automobile component, and Semiconductor equipment) are available
- Various types of MSB tools (Boring, Grooving, Threading)

### Code system



### MSB tool code system

	Types	Appli	cation	Designation	
01		Boi	ring	MBR/L○○☆☆	
02	Boring	Сор	ying	MBCR/L○○☆☆	
03	Bonng	Back	Boring	MBBR/L○○☆☆	
04		Cham	fering	MBFR/L○○☆☆	
05		Square (	Grooning	MGR/L○○☆☆−□□	
06	Grooving	Round (	Grooving	MGRR/L○○☆☆─□□	
07		Face G	rooving	MGFR/L○○00-□□	
08	Throading	Partial	60°	MTR/L○○☆☆-◇60	
	Threading	raniai	55°	MTR/L○○☆☆◇55	

### Details

	00		Shan	k Dia.							
	☆☆		Max. dept	n of boring							
Marks		Width of groove									
IVIAIKS			F	0.25~1.0	72~24						
	$\Diamond$	Pitch/tpi	А	0.5~1.5	48~16						
			AG	0.5~3.0	48~8						

# Auto Tools (MSB tool)

### Grades

Grades	Coating	Application and features
Z12M	Carbide	Ultra fine grain substrate ensures superior wear resistance and toughness Application: Cast iron, Aluminum alloy and Non-ferrous metals machining
PC30M	TiN coating	TiN coated ultra fine grain substrate ensures long tool life Application: Stainless steel, heat resisting alloy and hard-to-cut material machining

### Machining types










### Types










**Boring** Min. dia. of machining: Ø3.2

Copying Min. dia. of machining: Ø4.2

**Back Boring** Min. dia. of machining: Ø3.2


Chamfering Min. dia. of machining: Ø4.2

Grooving






Min. dia. of machining: Ø3.2




**Round Grooving** Min. dia. of machining: Ø3.2



**Face Grooving** Min. dia. of machining: Ø6.0


Threading



**Threading** Min. dia. of machining: Ø3.3

# **Boring**








(mm)


	Twin Ed	ge			Single Ed	dge			Min.dia.		Overal	length	Detailed cu	itting edge
De	esignation	Coated	Uncoated	D	esignation	Coated	Uncoated	Ød	of ma-	Q	ı	_	а	S
	ooigi idaloi i	PC30M	Z12M		ooignaao	PC30M	Z12M		Cilling		Double ended	Single ended	ű	· ·
MBR	0310	•		MBR	0310-1			3.0	3.2	10	40	35	0.5	1.4
	0315	•			0315-1			3.0	3.2	15	50	45	0.5	1.4
	0410	•			0410-1					10	40	35		
	0415	•			0415-1			4.0	4.2	15	50	45	0.6	1.9
	0420	•			0420-1					20	60	50		
	0610	•			0610-1					10	45	40		
	0615	•			0615-1			6.0	6.2	15	55	45	0.75	2.9
	0620	•			0620-1					20	65	50		
	0810	•			0810-1					10	50	45		
	0820	•			0820-1			8.0	8.2	20	70	60	0.8	3.9
	0830				0830-1					30	80	70		
	1015	•			1015-1					15	60	60		
	1025	•			1025-1			10.0	10.2	25	80	70	1.0	4.9
	1035	•			1035-1					35	100	80		

•: Stock item

# Copying








(mm)


	Twin Ed	ge			Single E	dge			Min.dia.		Overal	l length	Detailed cu	utting edge
De	alamatian	Coated	Uncoated	Do	olenation	Coated	Uncoated	Ød	of ma-	Q	I	L		S
De	esignation	PC30M	Z12M	De	signation	PC30M	Z12M		chining		Double ended	Single ended	а	3
MBCR	0410	•		MBCR	0410-1					10	40	35		
	0415	•			0415-1			4.0	4.2	15	50	45	1.0	1.9
	0420	•			0420-1					20	60	50		
	0610	•			0610-1					10	45	40		
	0615	•			0615-1			6.0	6.2	15	55	45	1.3	2.9
	0620	•			0620-1					20	60	50		

# **Back Boring**










(mm)

	Twin Ed	ge			Single E	dge			Min.dia.		Overall	length	Detail	ed cutting	j edge
Da	esignation	Coated	Uncoated	De	aianatian	Coated	Uncoated	Ød	of ma-	Q	ı	_	w		s
De	esignation	РС30М	Z12M	De	esignation	PC30M	Z12M		chining		Double ended	Single ended	VV	а	3
MBBR	0310	•		MBBR	0310-1			3.0	3.2	10	40	35	1.5	0.8	1.4
	0315	•			0315-1			3.0	3.2	15	50	45	1.5	0.6	1.4
	0410	•			0410-1					10	40	35			
	0415	•			0415-1			4.0	4.2	15	50	45	2.0	1.3	1.9
	0420	•			0420-1					20	60	50			
	0610	•			0610-1					10	45	40			
	0615	•			0615-1			6.0	6.2	15	55	45	2.0	1.9	2.9
	0620	•			0620-1					20	65	50			


• : Stock item

# Chamfering










(mm)

	Twin Ed	ge			Single E	dge			Min.dia.		Overall	length	Detail	ed cutting	g edge
D	naismatian	Coated	Uncoated	Do	alamatian	Coated	Uncoated	Ød	of ma-	Q	ı	-	W		s
De	esignation	РС30М	Z12M	De	signation	PC30M	Z12M		chining		Double ended	Single ended	VV	а	5
MBFR	0410	•		MBFR	0410-1					10	40	35			
	0415	•			0415-1			4.0	4.2	15	50	45	8.0	1.0	1.9
	0420	•			0420-1					20	60	50			
	0610	•			0610-1					10	45	40			
	0615	•			0615-1			6.0	6.2 15	55	45	1.4	1.2	2.9	
	0620	•			0620-1					20	65	50			

# **Square Grooving**








(mm)

	Twin Ed	lge			Single E	dge			Min.dia.		Overal	l length	Detail	ed cutting	g edge
D.		Coated	Uncoated	_		Coated	Uncoated	Ød	of ma-	Q		L	w	_	
De	esignation	PC30M	Z12M	D	esignation	PC30M	Z12M		chining		Double ended	Single ended	VV	а	S
MGR	0310-1.0	•		MGR	0310-1.0-1					10	40	35	1.0		
	0315-1.0	•			0315-1.0-1			3.0	3.2	15	50	45	1.0	0.8	1.4
	0310-1.5	•			0310-1.5-1			3.0	3.2	10	40	35	1.5	0.0	1.4
	0315-1.5	•			0315-1.5-1					15	50	45	1.5		
	0410-1.0	•			0410-1.0-1					10	40	35	1.0		
	0420-1.0				0420-1.0-1					20	60	50	1.0		
	0410-1.5				0410-1.5-1			4.0	4.2	10	40	35	1.5	1.4	1.9
	0420-1.5				0420-1.5-1			4.0	4.2	20	60	50	1.5	1.4	1.5
	0410-2.0	•			0410-2.0-1					10	40	35	2.0		
	0420-2.0				0420-2.0-1					20	60	50	2.0		
	0610-1.0	•			0610-1.0-1					10	45	40	1.0		
	0620-1.0	•			0620-1.0-1				20 10	65	50	1.0			
	0610-1.5	•			0610-1.5-1					45	40	1.5	1.8		
	0620-1.5	•			0620-1.5-1			6.0	6.2	20	65	50	1.5	1.8	2.9
	0610-2.0	•			0610-2.0-1			0.0	0.2	10	45	40	2.0		
	0620-2.0	•			0620-2.0-1					20	65	50	2.0		
	0610-2.5	•			0610-2.5-1					10	45	40	2.5	2.0	
	0620-2.5	•			0620-2.5-1					20	65	50	2.0	2.0	
	0820-1.5	•			0820-1.5-1								1.5	2.5	
	0820-2.0	•			0820-2.0-1			8.0	8.2	20	70	60	2.0	2.0	3.9
	0820-2.5	•			0820-2.5-1			0.0	0.2		, ,		2.5	3.5	0.0
	0820-3.0	•			0820-3.0-1				0 10.2				3.0	0.0	
	1025-1.5	•			1025-1.5-1								1.5	2.5	
	1025-2.0	•			1025-2.0-1			10.0 10.2 25 80 70		70	2.0	2.0	4.9		
	1025-2.5	•			1025-2.5-1			10.0		0.0 10.2 25		, ,	2.5	3.5	7.0
	1025-3.0	•			1025-3.0-1									3.0	0.0

• : Stock item

# **Round Grooving**









	Twin Ed	ge			Single E	dge			Min.dia.		Overal	length	Detail	ed cutting	g edge
D	naignation	Coated	Uncoated	De	alanation	Coated	Uncoated	Ød	of ma-	Q		L	w		s
De	esignation	PC30M	Z12M	De	esignation	PC30M	Z12M		chining		Double ended	Single ended	VV	а	5
MGRR	0310-0.8	•		MGRR	0310-0.8-1			3.0	3.2	10	40	35	0.8	0.8	1.4
	0315-0.8	•			0315-0.8-1			3.0	3.2	15	50	45	0.8	0.8	1.4
	0410-1.0	•			0410-1.0-1			4.0	4.2	10	40	35	1.0	1.0	1.9
	0420-1.0	•			0420-1.0-1			4.0	4.2	20	60	50	1.0	1.0	1.9
	0610-1.0	•			0610-1.0-1					10	45	40	1.0		
	0620-1.0	•			0620-1.0-1					20	65	50	1.0		
	0610-1.5	•			0610-1.5-1			6.0	6.2	10	45	40	1.5	2.0	2.9
	0620-1.5	•			0620-1.5-1			0.0	0.2	20	65	50	1.5	2.0	2.9
	0610-2.0	•			0610-2.0-1					10	45	40	2.0		
	0620-2.0	•			0620-2.0-1					20	65	50	2.0		
	0820-1.0	•			0820-1.0-1								1.0		
	0820-1.5	•			0820-1.5-1			8.0	8.2	20	70	60	1.5	2.3	3.9
	0820-2.0				0820-2.0-1			10.0 10.2					2.0		
	1025-1.0	•			1025-1.0-1								1.0		
	1025-1.5	•			1025-1.5-1					10.0 10.2 25	0.0 10.2 25	25	80	70	1.5
	1025-2.0	•			1025-2.0-1								2.0		


• : Stock item

# **Face Grooving**










(mm)

	Twin Ed	ge		Single Edge				Min.dia.	Overall	length	Detailed cutting		g edge		
	a la mation	Coated	Uncoated		olemetics	Coated	Uncoated	Ød	of ma-	I		w		s	
De	esignation	PC30M	Z12M	De	signation	PC30M	Z12M		chining	Double ended	Single ended	VV	а	5	
MGFR	0400-1.0	•		MGFR	0400-1.0-1			4.0	6.0	50	45	1.0	1.5	1.8	
	0400-1.5	•			0400-1.5-1			4.0	6.0	50	45	1.5	2.0	1.0	
	0600-1.0	•			0600-1.0-1							1.0	1.5		
	0600-1.5	•			0600-1.5-1			6.0	8.5	50	45	1.5	2.0	2.9	
	0600-2.0	•			0600-2.0-1							2.0	2.5		
	0800-1.0	•			0800-1.0-1							1.0	1.5	3.9	
	0800-1.5	•			0800-1.5-1							1.5	2.0		
	0800-2.0	•			0800-2.0-1			8.0	10.4	70	60	2.0	2.5		
	0800-2.5	•			0800-2.5-1			6.0	10.4	/0	00	2.5	3.0	3.9	
	0800-3.0	•			0800-3.0-1							3.0	3.5	1	
					0800-3.5-1							3.5	4.0		
	1000-2.0	•			1000-2.0-1							2.0	2.5		
	1000-2.5	•			1000-2.5-1							2.5	3.0		
	1000-3.0	•			1000-3.0-1			10.0	10.4	90	70	3.0	3.5	4.0	
	1000-3.5	•			1000-3.5-1			10.0	12.4	12.4   80   70	80 70	/0	3.5	4.0	4.9
	1000-4.0	•			1000-4.0-1						4.0	4.5	7		
	1000-4.5	•		]	1000-4.5-1							4.5	5.0	]	

# **Threading**








(mm)

Twin Edge Single Edg								Min.dia.		Threading		Detail	ed cutting	g edge	
D	esignation	Coated	Uncoated	D.	esignation	Coated	Uncoated	Ød	of ma-	w	Pitch	θ°	s		
De	esignation	PC30M	Z12M	De	esignation	PC30M	Z12M	chining		VV	/ tpi	ð	3	а	'
MTR	0315-F60			MTR	0315-F60-1			3.0	3.3	1.2	0.5~1.0		1.45	4.0	0.0
	0415-F60	•			0415-F60-1			4.0	4.3	1.2 0.5~1.0		60°	1.95	1.2	0.6
	0615-A60	•			0615-A60-1			6.0	6.2	2.0	0.5~1.5		2.90	2.2	1.0
	0315-F55	•			0315-F55-1			3.0	3.3	1.2	48~24		1.45	4.0	0.0
	0415-F55	•			0415-F55-1			4.0	4.3	1.2	40~24	55°	1.95	1.2	0.6
	0615-A55	•			0615-A55-1			6.0	6.2	2.0	28~16		2.90	2.2	1.0

•: Stock item

## SLEEVE

# SL (SLEEVE)



- /		~			
- (	I	1	ı	I	


										(111111)
Designation	Ød	а	b	С	ØD	н	L	Screw	Wrench	Fig.
SL1603	3	5	-	-	16	14	100	M3	HW15L	
SL1604	4	5	6	-	16	14	100	M4	HW20L	1
SL1605	5	5	8	-	16	14	100	M4	HW20L	
SL1606	6	5	6	6	16	14	100	M4	HW20L	0
SL1607	7	5	6	8	16	14	100	M4	HW20L	2
SL2008	8	5	10	10	20	18	100	M4	HW20L	2
SL2010	10	5	10	10	20	18	100	M5	HW20L	

\* Fine tolerance and surface roughness

## **Multi Turn**

### Code system

Insert




Holder




### Tool design by FEM analysis







 Minimized stress during cutting, prevented damage from vibration and longer tool life Optimized design

### Creative stepping cutting edge





- Special chip formed by edge geometry better chip
- Evacuation due to small radius width of chip curl






Comparison	Multi turn	Competitor A	Competitor B
Feed fn (mm/rev) = 0.08	#	W	V
Feed fn (mm/rev) = 0.10	V	W	V
Chip width (rate)	80%	100%	120%

### User's guide


### External / Internal turning






### **Facing**






### **Drilling**





### Offset (Diameter compensation)

Disignation	Machined diameter (mm)	ØDmin (mm)	ØDmax (mm)
MT10R/L-2.25D	10	9.85	10.35
MT12R/L-2.25D	12	11.85	12.35
MT14R/L-2.25D	14	13.85	14.35
MT16R/L-2.25D	16	15.85	16.35
MT20R/L-2.25D	20	19.85	20.35
MT25R/L-2.25D	25	24.85	25.35
MT32R/L-2.25D	32	31.85	32.35




Drill diameter is adjustable by the offset compensation

# **B** Multi Turn

# $\mathbf{MT}$ (Multi-Turn)







								(mm)
	Designation	ØD	Ød	Q	L	Insert	Screw	Wrench
MT	10R/L-2.25D	10	12	22.5	69.5	QC□T050204	FTNA0204S	TW06P
	12R/L-2.25D	12	16	27.0	78.0	QC□T060204	FTNA02205S	TW06P
	14R/L-2.25D	14	16	31.5	83.5	QC□T070304	FTKA02555	TW07P
	16R/L-2.25D	16	20	36.0	94.0	QC□T080304	FTNA0306	TW09P
	20R/L-2.25D	20	25	45.0	111.0	QC□T10T304	FTNA03508	TW15P
	25R/L-2.25D	25	32	56.5	130.0	QC□T130408	FTNC04509	TW20S
	32R/L-2.25D	32	40	72.0	160.0	QC□T170508	FTNC04511	TW20S


				Coa	ated		Unco	oated		Dime	nsions	(mm)		
Picture	De	signation	NC3120	NC3225	NC6315	PC5300	HO1	H05	ı	d	t	r	Ød1	Configuration
	QCMT	050204-CM		•	•	•			5.0	5.4	2.10	0.4	2.3	<u>r</u>
		060204-CM		•	•	•			6.0	6.4	2.38	0.4	2.5	
		070304-CM		•	•	•			7.0	7.4	3.18	0.4	2.8	d d
		080304-CM		•	•	•			8.0	8.4	3.18	0.4	3.4	
		10T304-CM		•		•			10.0	10.4	3.97	0.4	4.0	7°
		130408-CM		•		•			12.7	13.5	4.76	8.0	5.5	87°
		170508-CM		•	•	•			16.7	17.5	5.56	8.0	5.5	
	QCGT	050204-CA					•		5.0	5.4	2.10	0.4	2.3	
		060204-CA					•		6.0	6.4	2.38	0.4	2.5	r
		070304-CA					•		7.0	7.4	3.18	0.4	2.8	
		080304-CA					•		8.0	8.4	3.18	0.4	3.4	d ++ d <sub>1</sub>
		10T304-CA					•		10.0	10.4	3.97	0.4	4.0	7°
		130408-CA					•		12.7	13.5	4.76	8.0	5.5	87°
		170508-CA					•		16.7	17.5	5.56	8.0	5.5	

RW: Raceway BS: Bearing Shield

## **Bearing Solution**

#### Code system

Insert







# **B** Bearing Solution

## CMSN...F Type









• R type insert (mm)


Des	ignation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Wrench
CMSNR/L	2020B-L12F	20	20 140 21 20 33 MC12□□			CH6R/L1B	PHACEOU	SX42CB	SS0308	HW50L			
	2023B-L12F	20	23	140	24	20	33	MC12□□-BR	CHON/LIB	DHAU020	3A42UD	330306	HWYSUL
	2525B-L15F	25	25	140	26	25	35	MC15□□	CH6R/L1B	BHA0620	SX52CB	SS0408	HW50L


## CMSN...B Type





MC12□□ MC12□□-BR





• R type insert (mm)

• : Stock item


[	Designation	ØD	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Wrench
CMSNR/L	2020B-L12B-D28	28	20	20	140	21	20	33		CH6R/L1B	BHA0620	SX42CB	SS0308	HW50L
	2525B-L12B-D28	28	25	25	140	26	25	33	MC12□□	CH6R/L1B	BHA0620	SX42CB	SS0308	HW50L
	1620B-L12B-D20	20	16	20	140	18	16	32	MC12□□-BR	CH6R/L1B	BHA0620	-	-	HW50L
	2023B-L12B-D28	28	20	23	140	24	20	33	1	CH6R/L1B	BHA0620	SX42CB	SS0308	HW50L

#### Insert

ы			Cermet		Dim	ensions (	(mm)		
Application	Picture	Designation	CN2500	R	θ°	В	d	t	Configuration
		MC0906		0.6	12	1.8	9.525	3.18	
		MC0910		1.0	12	2.4	9.525	3.18	
		MC1206		0.6	18	1.8	12.7	4.76	
		MC1210		1.0	18	2.4	12.7	4.76	
		MC1212		1.2	18	2.2	12.7	4.76	
		MC1215		1.5	18	3.0	12.7	4.76	
<sub>ත</sub>		MC1220		2.0	18	3.8	12.7	4.76	x   ■ B ■ \
ב <u>ֿ</u>	d t	MC1225		2.5	18	2.8	12.7	4.76	$\theta^{\circ}$
ige	1	MC1525		2.5	18	4.0	15.875	5.56	\$/
R-Chamfering		MC1530		3.0	18	4.7	15.875	5.56	B
បុ		MC1540		4.0	20	4.7	15.875	5.56	<u> </u>
-		MC1206-BR		0.6	18	1.8	12.7	4.76	$\theta^{d}$
		MC1210-BR		1.0	18	2.4	12.7	4.76	-
		MC1212-BR		1.2	18	2.2	12.7	4.76	
		MC1215-BR		1.5	18	3.0	12.7	4.76	
		MC1220-BR		2.0	18	3.2	12.7	4.76	
	d t	MC1230-BR		3.0	18	3.7	12.7	4.76	
		MC1235-BR		3.5	18	3.9	12.7	4.76	

#### Special order-form

Designation CN2500 R θ° B d t Configuration



Designation	0112000	•••		<u> </u>	•	Comigaration
MC						





RPGT1203M0 RPGT1604M0 RPGT2004M0









· R type insert (mm)

De	signation	Н	W	L	s	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
SRGPR/L	2020B-L12E	20	20	140	25	20	20	RPGT1203M0	FTKA0410	SR1203S	SHXN0609F	TW15P
	2020B-L16E	20	20	140	25	20	20	RPGT1604M0	FTNA0513	SR16T3S	SHXN0712F	TW20P
	2525B-L20E	25	25	140	32	25	30	RPGT2004M0	FTNA0513	SR20T3S	SHXN0712F	TW20P

#### SRGP...F Type




RPGT1203M0 RPGT1604M0 RPGT2004M0

25

25

140

32







· R type insert (mm)

Shim Screw Wrench Designation Н W L S h Q Insert 9 O THE SRGPR/L 2020B-L12F 140 RPGT1203M0 FTKA0410 SR1203S SHXN0609F TW15P 20 20 25 20 20 2020B-L16F 20 RPGT1604M0 FTNA0513 SR16T3S SHXN0712F TW20P 20 140 25 20 20 2525B-L20F RPGT2004M0 FTNA0513 SR20T3S SHXN0712F TW20P


30


25

#### SRCP...B Type



RPGT0802M0 RPGT1203M0 RPGT1604M0







• R type insert (mm)

	Designation	ØD	н	W	L	s	h	Q	Insert	Screw	Wrench
SRCPR/L	2020B-L08B-D12	12	20	20	140	21.5	15.5	25	RPGT0802M0	FTKA0305	TW09P
	1919B-L12B-D15	15	19	19	140	21	16	25	RPGT1203M0	FTNA0408	TW15P
	2020B-L12B-D20	20	20	20	140	22	15.5	25	RPGT1203M0	FTNA0408	TW15P
	2525B-L16B-D32	32	25	25	140	27	20	30	RPGT1604M0	FTKA0510	TW20P

# **B** Bearing Solution






#### Insert

5			Cermet		Dimension	ons (mm)		
Application	Picture	Designation	CN2500	r	d	d <sub>1</sub>	t	Configuration
		RPGT0802M0		-	8	3.4	2.38	
		RPGT1203M0		-	12	4.4	3.18	
		RPGT1604M0		-	16	5.5	4.76	<del>  ((; ))            </del>   d <sub>1</sub>
		RPGT2004M0		-	20	5.5	4.76	110
								d     t   '
<u> </u>		SPGR120440L		4.0	12.7	-	4.76	r
Internal turning								d 11°
		SPGH090330L		3.0	9.525	3.4	3.18	. r
								di











Н

**KORIC** 


• R type insert (mm)


D	esignation	Н	W	L	s	h	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Wrench
CKFNR/L	2020B-L22RW	20	20	140	12.5	20	KORIC2204R/L	CH6N1B	BHA0620	ST42CB	SS0408	HW50L
	2022B-L27RW	20	22	140	13			CH8R/L1B	BHA0820	ST52CB	SS0408	HW60L
	2025B-L33RW	2025B-L33RW 20 25 140 16 20 KORIC33		KORIC3306R/L	CH8R/L1B	BHA0820	ST62CB	SS0408	HW60L			
	2533B-L44RW	25	33	140	21	25	KORIC4408R/L	CH8R/L1B	BHA0820	ST82CB	SS0408	HW60L






# **Bearing Solution**









#### Machining Race-way

#### S KORIC... R/L Type



		d	t	R	h <sub>1</sub>	h <sub>2</sub>	α°	β°
KORIC	2204R/L	12.7	4.76					
	2704R/L	15.875	4.76					
	3306R/L	19.05	6.0					
	3806R/L	22.225	6.0					
	4408R/L	25.4	8.0					

#### SNGN... WR/L Type



		d	t	R	h <sub>1</sub>	h <sub>2</sub>	α°	β°
SNGN	0903WR/L	9.525	3.18					
	1504WR/L	15.875	4.76					
	1905WR/L	19.05	5.56					

#### **Machining for Bearing shield**

#### S KORIC... R/L Type







R Type





L Type

		d	t	L <sub>1</sub>	L <sub>2</sub>	h <sub>1</sub>	h <sub>2</sub>	R <sub>1</sub>	R <sub>2</sub>	α°	β°
SNGN	0903SR/L	9.525	3.18								
	1204SR/L	12.7	4.76								
	1504SR/L	15.875	4.76								

#### TNGN...SR/L Type















L Type





		d	t	L <sub>1</sub>	L <sub>2</sub>	h <sub>1</sub>	h <sub>2</sub>	R <sub>1</sub>	R <sub>2</sub>	α°	β°
TNGN	02204SR/L	12.7	4.76								


## **B** External tool Holder Code System (ISO)

























## **Double Clamp System**

Cutting Shape		<b>†</b>	1	+				*		+
Designation	DCBNR/L	DCKNR/L	DCLNR/L	DDJNR/L	DSBNR/L	DSDNN	DSKNR/L	DSSNR/L	DTFNR/L	DTGNR/L
Approach angle	75°	75°	95°	93°	75°	45°	75°	45°	90°	90°
Page	B167	B167	B167	B168	B168	B169	B169	B169	B170	B170
Turning	•		•	•	•	•		•		•
Copying				•						
Facing		•	•				•	•	•	
Chamfering						•				
Back turning			•	•						
Cutting Shape			+							
Designation	DVJNR/L	DVVNN	DWLNR/L							
Approach angle	93°	72.5°	95°							
Page	B170	B171	B171							
Turning	•	•	•							
Copying	•	•								
Facing			•							
Chamfering										
Back turning	•		•							

## Lever Lock System

Cutting Shape	- O					+ 0	+	<b>+</b> 0	60	0
Designation	PCBNR/L	PCKNR/L	PCLNR/L	PDJNR/L	PDNNR/L	PRDCN	PRGCR/L	PSBNR/L	PSDNN	PSKNR/L
Approach angle	75°	75°	95°	93°	62.5°	-	-	75°	45°	75°
Page	B172	B172	B173	B173	B174	B174	B175	B175	B176	B176
Turning	•	•	•	•	•	•	•	•	•	
Copying				•	•	•	•			
Facing			•							•
Chamfering										
Back turning			•	•						
Cutting Shape	1		+ 0		1					
Designation	PSSNR/L	PTFNR/L	PTGNR/L	PTTNR/L	PWLNR/L					
Approach angle	45°	90°	90°	60°	95°					
Page	B177	B177	B178	B178	B178					
Turning	•		•	•	•					
Copying										
Facing	•	•			•					
Chamfering				•						
Back turning					•					

#### Wedge Clamp System

Cutting Shape		+ 0		1			
Designation	WTENN	WTJNR/L	WTXNR/L	WWLNR/L			
Approach angle	60°	93°	105°	95°			
Page	B179	B179	B179	B180			
Turning	•	•	•	•			
Copying	•	•	•				
Facing				•			
Chamfering							
Back turning		•	•	•			

#### **Clamp on System**

Cutting Shape	<b>*</b>		+	<u>†</u>	1			
Designation	CKJNR/L	CKNNR/L	CSDPN	CSKPR/L	CTFPR/L	CTGPR/L		
Approach angle	93°	62.5°	45°	75°	90°	90°		
Page	B181	B181	B181	B182	B182	B182		
Turning	•	•	•			•		
Copying	•	•						
Facing				•	•			
Chamfering								
Back turning	•							

## Multi Lock System

Cutting Shape	a a	<b>1</b>	<b>1</b>				+	•		1
Designation	MCKNR/L	MCLNR/L	MCMNN	MCRNR/L	MDJNR/L	MDNNN	MDQNR/L	MSBNR/L	MSDNN	MSKNR/L
Approach angle	75°	95°	50°	75°	93°	62.5°	107.5°	75°	45°	75°
Page	B183	B183	B183	B184	B184	B184	B185	B185	B185	B186
Turning		•	•	•	•	•	•	•	•	
Copying					•	•	•			
Facing	•	•								•
Chamfering										
Back turning		•			•		•			

Cutting Shape	+		204	1	*		+	+		+
Designation	MSRNR/L	MSSNR/L	MTENN	MTFNR/L	MTGNR/L	MTJNR/L	MVJNR/L	MVQNR/L	MVVNN	MWLNR/L
Approach angle	75°	45°	60°	90°	90°	93°	93°	117.5°	72.5°	95°
Page	B186	B187	B187	B187	B188	B188	B188	B189	B189	B189
Turning	•	•	•		•	•	•	•	•	•
Copying			•			•	•	•	•	
Facing		•		•		•				•
Chamfering										
Back turning						•	•	•		•

#### Screw on System Cutting Shape SCACR/L SRDCN SRGCR/L SSDCN SSKCR/L Designation SCLCR/L SDACR/L SDJCR/L **SDNCN** SSBCR/L 90° 95° 90° 93° 62.5° 75° 45° 75° Approach angle B190 B190 B190 B191 B191 B191 B192 B192 B192 B193 Page • • • • • **Turning** lacktrianglelacktrianglelacktriangle• • • • Copying Facing Chamfering

Cutting Shape			•	4		9	+ 3	+		
Designation	SSSCR/L	STACR/L	STFCR/L	STGCR/L	STTCR/L	SVABR/L	SVHBR/L	SVJBR/L	SVJCR/L	SVVBN
Approach angle	45°	90°	90°	90°	60°	90°	107.5°	93°	93°	72.5°
Page	B193	B193	B194	B194	B194	B195	B195	B195	B196	B196
Turning	•	•		•	•	•	•	•	•	•
Copying						•	•	•	•	•
Facing	•		•							
Chamfering										
Back turning						•	•	•	•	
				· I	I		I		I	·
Cutting Shape	+0 * +									

Cutting Shape						
Designation	SVVCN					
Approach angle	72.5°					
Page	B196					
Turning	•					
Copying	•					
Facing						
Chamfering						
Back turning						


#### **Ceramic Holder**


Back turning


Cutting Shape		+		1	1		+		
Designation	CCNLR/L	CRDNN	CRGNR/L	CSDNN	CSKNR/L	CTFNR/L	CTGNR/L		
Approach angle	95°	-	-	45°	75°	90°	90°		
Page	B197	B197	B197	B197	B198	B198	B198		
Turning	•	•	•	•			•		
Copying			•						
Facing	•				•	•			
Chamfering									
Back turning	•								


## B


#### **Instruction of External Holder**















#### DCBNR/L



CN







75°

• R type insert (mm)


Des	ignation	н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DCBNR/L	2020-K12	20	20	125	17	20	31							
	2525-M12 3225-P12	25	25	150	22	25	31	CN□□1204□□	CVH4	CHX0518	SC44V	FTKA0410	SPR0714	HW30P
	3225-P12	32	25	170	22	32	31							
	2525-P12 2525-M16 3232-P16	25	25	150	22	25	36	CN□□1606□□	CVH5	5 CHX0622	SC54V	FTNA0511	CDD0011	HW40L
		32	32	170	27	32	36	CNTOOO	CVIIS	CHAUUZZ	30341	FINAUSII	SFNUOTI	HW40L
	3232-P19	32	32	170	27	32	40	CN□□1906□□	CVH6	CHX0622	SC63V	FTNA0511	CDD0011	HW40L
	4040-S19	40	40	250	35	40	40	CNDD1900DD	CVIII	CHAUUZZ	30031	FINAUSTI	350011	HW40L

<sup>→</sup> Applicable inserts B36~B42

#### DCKNR/L









75°

• R type insert (mm)


Des	signation	н	w	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DCKNR/L	2020-K12	20	20	125	25	20	21							
	2525-M12	25	25	150	32	25	21	CN1204	CVH4	CHX0518	SC44V	FTKA0410	SPR0714	HW30P
	3225-P12	32	25	170	32	32	21							
	3232-P16	32	32	170	40	32	26	0100100000	CVH5	CHX0622	CCE 4V	FTNA0511	SPR0811	HW40L
4040-S16	40	40	250	50	40	26	CN 1606	СУПЭ	UHAU022	3034V	FINAUSTI	3FN0011	HVV40L	
_														

<sup>→</sup> Applicable inserts B36~B42

#### DCLNR/L



CN





95°

• R type insert (mm)


Des	signation	н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DCLNR/L	2020-K09	20	20	125	25	20	24.5	CN 0903	CVH3	CHX0415	SC32V	ETI/ A 0207	SPR0510	HW25P
	2525-M09	25	25	150	32	25	24.5	CNLLU903LL	CVIIS	CHX0413	30321	FINAUSUI	3500310	HWZJF
	2020-K12	20	20	125	25	20	30							
	2525-M12	25	25	150	32	25	30	CN 1204	CVH4	CHVOE40	00441/	ETI/A0440	CDD074.4	HW30P
	3225-P12	32	25	170	32	32	30		OVII4 O	CHX0518	SC44V	FTKA0410	5PHU/14	HW30P
3	3232-P12	32	32	170	40	32	30							
	2525-M16	25	25	150	32	25	36							
	3225-P16	32	25	170	32	32	36	CN□□1606□□	CVH5	CHX0622	SC54V	FTNA0511	SPR0811	HW40L
	3232-P16	32	32	170	40	32	36							
	2525-M19	25	25	150	32	25	40							
-	3225-P19	32	25	170	32	32	40	CNDD1006DD	CVILIC	CHX0622	SC63V	FTNA0511	CDD0011	HW40L
	3232-P19	32	32	170	40	32	40	0 CN 1906	CVH6	UHAU022	3003V	LICOVALLA	3FN0811	⊓vv40L
	4040-S19	40	40	250	50	40	40							

# B Double Clamp System

#### DDJNR/L



 $\mathsf{DN} \square \square$ 





93°

• R type insert (mm)


Des	signation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DDJNR/L	2020-K11	20	20	125	25	20	30							
	2525-M11	25	25	150	32	25	30	DN 1104	CVH3	CHX0415	SD32V	FTKA0307	SPR0510	HW25P
	3225-P11 3232-P11 2020-K15	32	25	170	32	32	30		CVIIS	UHA0415	3D32V	FTRAU307	3FN0310	ПИУZЭГ
		32	32	170	40	32	30							
		20	20	125	25	20	35							
	2525-M15	25	25	150	32	25	35	DN 1506	CVH4	CHX0518	SD43V	FTKA0410	CDD0714	HW30P
	3225-P15	32	25	170	32	32	35	DINLLIOUGL	CVH4	CHXUS16	3D43V	FINAU410	3FN0/14	HVVSUF
	3232-P15	32	32	170	40	32	35							
	2020-K15-3 2525-M15-3	20	20	125	25	20	35							
		25	25	150	32	25	35	DN□□1504□□	CVH4	CHX0518	SD44V	FTKA0410	SPR0714	HW30P
	3232-P15-3	32	32	170	40	32	35							


<sup>◆</sup> Applicable inserts B43~B48

#### **DSBNR/L**



 $\mathsf{SN} \square \square$ 





• R type insert (mm)


Des	ignation	н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DSBNR/L	2020-K09	20	20	125	17	20	25	SN 0903	CVH3	CHX0415	SS32V	FTKA0307	CDD0E10	HW25P
	2525-M09	25	25	150	22	25	25	3IN0903	CVIIS	CHX0415	3332V	FINAU307	3FN0310	HVV23P
	2020-K12	20	20	125	17	20	32	SN1204						
	2525-M12	25	25	150	22	25	32		CVH4	CHX0518	SS44V	FTKA0410	QDD0714	HW30P
	3225-P12	32	25	170	22	32	32		CVH4	CHAUSTO	3344V	FINAU410	3FN0/14	HWOUP
	3232-P12	32	32	170	27	32	32							
	2525-M15	25	25	150	22	25	38							
	3225-P15	32	25	170	22	32	38	SN□□1506□□	CVH5	CHX0622	SS54V	FTNA0511	SPR0811	HW40L
	3232-P15	32	32	170	27	32	38							
	3232-P19	32	32	170	27	32	43		CVH6	CHX0622	SS64V	ETNIA0E11	SPR0811	HW40L
	4040-S19	40	40	250	35	40	43	3NUL1900	CVHb	UHAU022	3304V	FTNA0511	3FN0811	⊓vv40L

<sup>◆</sup> Applicable inserts B50~B57

#### **DSDNN**



SN





45°

• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DSDNN	2020-K09	20	20	125	10	20	26.5	SN□□0903□□	CVH3	CHX0415	SS32V	FTKA0307	SPR0510	HW25P
	2020-K12	20	20	125	10	20	33							
	2525-M12	25	25	150	12.5	25	33	   SN□□1204□□	CVH4	CHX0518	SS44V	FTKA0410	QDD0714	HW30P
	3225-P12	32	25	170	12.5	32	33	311 1204 1	CVII4	CHAUSTO	3344V	FINAU410	3FN0/14	HWYSOF
	3232-P12	32	32	170	16	32	33							
		25	25	150	12.5	25	39.4	SN□□1506□□	CVH5	CHX0622	SS54V	FTNA0511	SPR0811	HW25P
	3232-P15	32	32	170	16	32	38	311 1300 1	CVIIS	OFIA0022	33341	FIINOUSII	SFNUOTI	HWZSF
	3232-P19	32	32	170	16	32	43	SN□□1906□□	CVH6	CHX0622	SS64V	FTNA0511	SPR0811	HW40L
	4040-S19	40	40	250	20	40	45	3N1900	CVIII	UПЛ0022	3304V	FINAUSII	SFRUOTI	HVV4UL


<sup>◆</sup> Applicable inserts B50~B57

## **DSKNR/L**



SN





• R type insert (mm)


Des	ignation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DSKNR/L	2020-K09	20	20	125	25	20	20	SN□□0903□□	CVH3	CHX0415	SS32V	FTKA0307	SPR0510	HW25P
	2020-K12	20	20	125	25	20	23							
	2525-M12	25	25	150	32	25	23	SN□□1204□□	CVH4	CHX0518	SS44V	FTKA0410	SPR0714	HW30P
	3232-P12	32	32	170	40	32	23							
	3232-P15	32	32	170	40	32	28	SN□□1506□□	CVH5	CHX0622	SS54V	FTNA0511	SPR0811	HW40L
	3232-P19	32	32	170	40	32	35	SN□□1906□□	CVH6	CHX0622	SC64V	FTNA0511	CDD0011	HW40L
	4040-S19	40	40	250	50	40	43	3NUL 1900	CVIIO	UHAU022	30041	FIICUAVII	3FN0011	HVV4UL

<sup>◆</sup> Applicable inserts B50~B57

#### **DSSNR/L**



SN





• R type insert (mm)


Desi	gnation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DSSNR/L	2020-K09	20	20	125	25	20	28.5	SN□□0903□□	CVH3	CHX0415	SS32V	FTKA0307	SPR0510	HW25P
	2020-K12	20	20	125	25	20	35							
	2525-M12	25	25	150	32	25	35	5 SN 1204 SN 1506 SN 1	CVH4	CHX0518	SS44V	FTKA0410	SDD0714	HW30P
	3225-P12	32	25	170	32	32	35		CVH4	CHXU316	3344V	FINAU410	SFN0/14	пиизог
	3232-P12	32	32	170	40	32	35							
	2525-M15	25	25	150	32	25	38.5		CVH5	CHX0622	SS54V	FTNA0511	CDD0011	HW40L
	3232-P15	32	32	170	40	32	38.5		CVHS	UHAU022	3334V	FINAUSII	SPRUOTI	HVV4UL
	3232-P19	32	32	170	40	32	46	SN□□1906□□	CVH6	CHX0622	SS64V	FTNA0511	SPR0811	HW40L
	4040-S19	40	40	250	50	40	46	311 1900 1	CVHO	UHAU022	3304V	FIICUAUIT	3FN0011	HW40L


# **B** Double Clamp System

#### DTFNR/L



 $\mathsf{TN}\square\square$ 





• R type insert

	(111111)	
ing	Wrench	
	09-	


Des	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DTFNR/L	2020-K16	20	20	125	25	20	24.5							
	2525-M16	25	25	150	32	25	24.5	TN□□1604□□	CVH3	CHX0415	ST32V	FTKA0307	SPR0510	HW25P
	3232-P16	32	32	170	40	32	23.5							
	2525-M22	25	25	150	32	25	33							
	3225-P22	32	25	170	32	32	33	TN□□2204□□	CVH4	CHX0518	ST44V	FTKA0410	SPR0714	HW30P
	3232-P22	32	32	170	40	32	33							


Applicable inserts B58∼B65

## DTGNR/L



 $\mathsf{TN}\square\square$ 





• R type insert


														(111111)
Des	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DTGNR/L	2020-K16	20	20	125	25	20	24.5							
	2525-M16	25	25	150	32	25	24.5	TN□□1604□□	CVH3	CHX0415	ST32V	FTKA0307	SPR0510	HW25P
	3232-P16	32	32	170	40	32	24.5							
	2525-M22	25	25	150	32	25	32.6							
	3225-P22	32	25	170	32	32	32.6	TN□□2204□□	CVH4	CHX0518	ST44V	FTKA0410	SPR0714	HW30P
	3232-P22	32	32	170	40	32	32.6							

Applicable inserts B58~B65

#### **DVJNR/L**



VN





93°

• R type insert

														(mm)
Des	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DVJNR/L	2020-K16	20	20	125	25	20	41.5							
	2525-M16	25	25	150	32	25	41.5	VN□□1604□□	CVH3V	CHX0518	SV32V	FTNA03508	SPR0714	HW30P

41.5

3232-P16

32

32

170


40

32

<sup>→</sup> Applicable inserts B66~B67

#### **DVVNN**







72.5°

• R type insert

														(mm)
De	esignation	Н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DVVNN	2020-K16	20	20	125	10	20	40							
	2525-M16	25	25	150	12.5	25	40	VN□□1604□□	CVH3V	CHX0518	SV32V	FTNA03508	SPR0714	HW30P
	3232-P16	32	32	170	16	32	40							


<sup>→</sup> Applicable inserts B66~B67

VN

#### **DWLNR/L**



 $\mathsf{WN} \square \, \square$ 





95°

• R type insert (mm)

Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Wrench
DWLNR/L		20	20	125	25	20	26	WNDD 0604DD	CVH3	CHAUTE	CMOON	FTKA0307	CDD0E10	LIMOED
	2525-M06	25	25	150	32	25	26	WN 0604 0	CVII3	UHX0413	3VV32V	FINAU3U/	3FN0310	HWZ3F
	2020-K08	20	20	125	25	20	32	WN□□ 0804□□	CVH4	CHX0518	CMAAN	ETI/A0410	CDD0714	HWOOD
	2525-M08	25	25	150	32	25	32	WIN 0004	CVH4	CHXUSTO	3VV44V	FINAU410	3FN0/14	HWOUP


<sup>◆</sup> Applicable inserts B68~B72


# **B** Lever Lock System

## PCBNR/L









• R type insert (mm)

Des	ignation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PCBNR/L	2020-K12	20	20	125	17	20	27							
	2525-M12	25	25	150	22	25	27	CN□□ 1204□□	LV4	VHX0821	SC42	SP4	HW30L	LSPS4
	3225-P12	32	25	170	22	32	27							
	2525-M16	25	25	150	22	25	33	CN□□ 1606□□	LV5	VHX0825	SC53	SP5	HW30L	LSPS6
	3232-P16	32	32	170	27	32	33	CN 1000	LVS	VI IA0023	3033	313	TIVVOUL	LOFOU
	3232-P19	32	32	170	27	32	36	CN□□ 1906□□	LV6N	VHX1027N	SC63N	SP6N	HW40L	LSPS6
	4040-S19	40	40	250	35	40	36	CN 1900	LVOIN	VII/ 102/1N	SCOSIN	SFOIN	HVV40L	LOFOU
	4040-S25	40	40	250	35	40	47	CN□□ 2509□□	LV8N	VHX1236N	SC84N	SP8N	HW50L	LSPS8
	4040-S25-5	40	40	250	35	40	47	CN□□ 2507□□	LVOIN	VI IA 1230IN	3004IN	OF OIN	TIVVOUL	LUFUO
	5050-T25	50	50	300	43	50	47	CN□□ 2509□□	LV8N	VHX1236N	SC84N	SP8N	HW50L	LSPS8


<sup>◆</sup> Applicable inserts B36~B42


## **PCKNR/L**



CN







95

• R type insert (mm)


Des	signation	Н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PCKNR/L	2020-K12	20	20	125	25	20	27							
2525-N	2525-M12	25	25	150	32	25	27	CN□□ 1204□□	LV4	VHX0821	SC42	SP4	HW30L	LSPS4
	3225-P12	32	25	170	40	32	30							
	3232-P16	32	32	170	40	32	26	CN 1606	LV5	VHX0825	SC53	SP5	HW30L	HW30L
4	4040-S16	40	40	250	50	40	25	CN 1606	LVS	V II X U 0 2 3	3033	353	HVVSUL	HWOUL


<sup>→</sup> Applicable inserts B36~B42

## PCLNR/L









• R type insert


Des	signation	Н	W	L	S	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PCLNR/L	1616-H09	16	16	100	20	16	20							
	2020-K09	20	20	125	25	20	22	CN□□ 0903□□	LV3	VHX0617	SC32	SP3	HW25L	LSPS3
	2525-M09	25	25	150	32	25	22							
	1616-H12	16	16	100	20	16	28							
	2020-K12	20	20	125	25	20	28							
	2525-M12	25	25	150	32	25	28	CN□□ 1204□□	LV4	VHX0821	SC42	SP4	HW30L	LSPS4
	3225-P12 3232-P12	32	25	170	32	32	28							
	3232-P12	32	32	170	40	32	28							
	2525-M16	25	25	150	32	25	33	- CN 1606	LV5	VHX0825	SC53	SP5	ПМОП	LSPS5
	3232-P16	32	32	170	40	32	33		LVO	VIIAU023	3033	353	HVVSUL	LSFSS
	2525-M19	25	25	150	32	25	36							
	3225-P19	32	25	170	32	32	36							
	3232-P19	32	32	170	40	32	36	CN□□ 1906□□	LV6N	VHX1027N	SC63N	SP6N	HW40L	LSPS6
	4040-P19	40	40	170	50	40	36							
	4040-S19	40	40	250	50	40	36							
	4040-S25	40	40	250	50	40	47	CNDD 2500DD	LV8N	VHX1236N	SC04N	SP8N	HW50L	LSPS8
	5050-T25	50	50	300	60	50	47	— CN□□ 2509□□ □	LVOIN	V I V I Z J D I N	3004IN	SPOIN	TIVVOUL	LOFO
	4040-S25-5	40	40	250	50	40	47	7 CN 2507	LV8N	VHX1236N	SC04N	SP8N	LIMEO	LSPS8
	5050-S25-5	50	50	300	60	50	47		LVSIN	V   1   2   3   1	3084N	SPRIN	⊓vv50L	LSPS8

<sup>◆</sup> Applicable inserts B36~B42

#### PDJNR/L









• R type insert

														()
Des	signation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PDJNR/L	1616-H11	16	16	100	20	16	25							
	2020-K11	20	20	125	25	20	25	DN	LV3	VHX0617	SD317	SP3	HW25L	LSPS3
2525-M11 2020-K15 2525-M15	2525-M11	25	25	150	32	25	30							
	20	20	125	25	20	35								
	25	25	150	32	25	35		LV4B	VHX0821	SD42	SP4	HW30L	LSPS4	
	3225-P15	32	25	170	32	32	35		LV4D	VIIAU021	3D42	3F4	HVVSUL	LOF04
	3232-P15	32	32	170	40	32	35							
2020-K15-3 2525-M15-3 3232-P15-3	20	20	125	25	20	35								
	2525-M15-3	25	25	150	32	25	35	DN	LV4	VHX0821	SD42	SP4	HW30L	LSPS4
	3232-P15-3	32	32	170	40	32	35	1						


<sup>◆</sup> Applicable inserts B43~B48

# **B** Lever Lock System

#### PDNNR/L









62.5°

R type insert	
(mm)	


Des	signation	Н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PDNNR/L	2020-K15	20	20	125	8	20	37							
2525-M15 3232-P15 4025-M15 2525-M15-3 4025-M15-3	2525-M15	25	25	150	12.5	25	37	DN 1506	LV4B	VHX0821	SD42	SP4	HW30L	LSPS4
	3232-P15	32	32	150	16	32	37		LV4D	VIIAU021	3D4Z	SF4	HWOUL	LSF34
	4025-M15	40	25	170	12.5	32	37							
	25	25	150	12.5	25	37	DNDD 4504DD	LV4	VHX0821	SD42	CD4	LIMON	1.0004	
	4025-M15-3	40	25	150	12.5	25	37	, DN□□ 1504□□	LV4	V   1   1   1   1   1   1   1   1   1	3D42	SP4	HW30L	LSPS4

<sup>→</sup> Applicable inserts B43~B48

## **PRDCN**



**RCMX** 





1)	Υ	1	Υ	1


De	signation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PRDCN	2020-M10	20	20	150	10	20	24	RCMX1003M0	LR10	VHX0514	SR10	SP3	HW20L	LSPS3
	2525-M10	25	25	150	12.5	25	24	HOWA TOUSING	LNIU	VIIA0514	SHIU	353	HWZUL	LOFOO
	2525-M12	25	25	150	12.5	25	24							
	2020-K12	20	20	125	10	20	24	RCMX1204M0	LR12	VHX0617	SR12	SP3	HW25L	LSPS3
	3225-Q12	32	25	180	12.5	32	24							
	2525-Q16	25	25	180	12.5	25	30	RCMX1606M0						
	3225-Q16	32	25	180	12.5	32	30		LR16	VHX0621	SR16	SP4	HW25L	LSPS4
	3232-Q16	32	32	180	16	32	35							
	3232-Q20	32	32	180	16	32	40	RCMX2006M0	LR20	VHX0823	SR20	SP20	HW30L	LSPS5
4040-S25 4040-T25	40	40	250	20	40	42	RCMX2507M0	LR25	VHX1030	SR25	SP6N	HW40L	LSPS6	
	4040-T25	40	40	300	20	40	42	HOWAZ307WO	LNZS	VIIXTUSU	SHZS	SFON	HW40L	LOFOU
	5050-U32	50	50	350	25	50	52	RCMX3209M0	LR32	VHX1236	SR32	SP8N	HW50L	LSPS8

Applicable inserts B83, B105

#### PRGCR/L



RCMX





• R type insert (mm)

Des	signation	н	W	L	S	h	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PRGCR/L	2020-K10	20	20	125	25	20	RCMX1003M0	LR10	VHX0514	SR10	SP3	HW20L	LSPS3
	2525-M10	25	25	150	32	25	HCIVIX TUUSIVIU	LNIU	VII/U014	SHIU	SFS	⊓WZUL	LOPOS
	2020-K12	20	20	125	25	20							
	2525-M12	25	25	150	32	25	RCMX1204M0	LR12	VHX0617	SR12	SP3	HW25L	LSPS3
	3225-P12	32	25	170	32	32							
	2525-M16	25	25	150	32	25	RCMX1606M0	LR16	VHX0621	SR16	SP4	HW25L	LSPS4
	3225-P16	32	25	170	32	32	HCIVIX TOUGIVIU	LNIO	VIIAU021	SHIO	354	HWZSL	LOF 34
	3232-P20	32	32	170	40	32	RCMX2006M0	LR20	VHX0823	SR20	SP5-1	HW30L	LSPS5
	4040-S25	40	40	250	50	40	RCMX2507M0	LR25	VHX1030	SR25	SP6N	HW40L	LSPS6


<sup>◆</sup> Applicable inserts B83, B105

#### **PSBNR/L**



 $SN\square\square$ 







75°

• R type insert (mm)

Des	signation	н	W	L	S	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PSBNR/L	1616-H09	16	16	100	13	16	21	SN□□0903□□	LV3	VHX0617	SS32	SP3	HW25L	LSPS3
	2020-K09	20	20	125	17	20	23	0140000000	LVO	V11/X0017	0002	01 0	1111200	E01 00
	2020-K12	20	20	125	17	20	28							
	2525-M12	25	25	150	22	25	28	SN□□1204□□	LV4	VHX0821	SS42	SP4	HW30L	LSPS4
	3225-P12 3232-P12	32	25	170	22	32	28	3NUU 1204UU	LV4	VI1/10021	3342	3F4	HVVOUL	LOF 34
	3232-P12	32	32	170	27	32	28							
	2525-M15	25	25	150	22	25	35	SN□□1506□□	LV5	VHX0825	SS53	SP5	HW30L	LSPS5
	3232-P15	32	32	170	27	32	35	311 1300	LVJ	VIIAUUZJ	3030	01 0	TIVVOUL	LOI 00
	3232-P19	32	32	170	27	32	40	SN□□1906□□	LV6N	VHX1027N	SS63N	SP6N	HW40L	LSPS6
	4040-S19	40	40	250	35	40	40	SIN1900	LVOIN	VIIXIUZ/IN	330311	SFON	HVV40L	LOFOU
	4040-S25	40	40	250	35	40	50	SN 2507 SN 2509 SN 2507						
	4040-S25-6	40	40	250	35	40	50		LV8N	VHX1236N	SS84N	SP8N	HW50L	LSPS8
	5050-T25	50	50	300	43	50	50		LVOIN	VIIVISON	3304IV	OF OIN	HVVOUL	LOPOO
	5050-T25-6	50	50	300	43	50	46							


<sup>◆</sup> Applicable inserts B50~B57

# **B** Lever Lock System

#### **PSDNN**









(m	ır	n)
 _		

De	esignation	Н	W	L	S	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PSDNN	1616-H09	16	16	100	8	16	23	SN0903	LV3	VHX0617	SS32	SP3	HW25L	LSPS3
	2020-K12	20	20	125	10	20	30							
	2525-M12	25	25	150	12.5	25	30	SN□□1204□□	LV4	VHX0821	SS42	SP4	HW30L	LSPS4
	3225-P12	32	25	170	12.5	32	30	SIN1204	LV4	VIIAU021	3342	3F4	HWOOL	LOF 04
	3232-P12 2525-M15	32	32	170	16	32	40							
	2525-M15 3232-P15	25	25	150	12.5	25	40	SN1506	LV5	VHX0825	SS53	SP5	HW30L	LSPS5
		32	32	170	16	32	40		LVS	VIIA0023	3333	353	HWOOL	LOFOO
	3225-P19	32	25	170	12.5	32	40							
	3232-P19	32	32	170	16	32	40	SN□□1906□□	LV6N	VHX1027N	SS63N	SP6N	HW40L	LSPS6
	4040-S19	40	40	250	20	40	40							
	4040-S25 5050-T25	40	40	250	20	40	50	SN 2507	LV8N	VHX1236N	SS84N	SP8N	HW50L	LSPS8
		50	50	300	25	50	50	JIN2507	LVOIN	VIIVISON	3304IN	OFOIN	HWOOL	LOPOO
4040-S	4040-S25-6	40	40	250	20	40	50	CNI DOEOO D	LV8N	VHX1236N	SS84N	SP8N	HW50L	LSPS8
	5050-T25-6	SN   2509	3IN2509	LVOIN	V II A I 230 IN	3304IN	SPRIN	⊓₩SUL	L3738					


<sup>◆</sup> Applicable inserts B50~B57

#### **PSKNR/L**



 $SN \square \square$ 







75°
• R type insert (mm)


Des	signation	н	W	L	S	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PSKNR/L	1616-H09	16	16	100	20	16	17	SN 0903	LV3	VHX0617	SS32	SP3	HW25L	LSPS3
	2020-K09	20	20	125	25	20	20	3NUU 0903UU	LVS	VII/001/	3332	SFS	⊓WZ3L	LOPOS
	2020-K12	20	20	125	25	20	23							
	2525-M12	25	25	150	32	25	23	SN□□1204□□	LV4	VHX0821	SS42	SP4	HW30L	LSPS4
	3232-P12	32	32	170	40	32	23							
	2525-M15	25	25	150	32	25	28	SN□□1506□□	LV5	VHX0825	SS53	SP5	HW30L	LSPS5
	3232-P15	32	32	170	40	32	28		LVS	VII/V023	3333	3F3	HWOOL	LSFSS
	3232-P19	32	32	170	40	32	41.5	SN□□1906□□	LV6N	VHX1027N	SS63N	SP6N	1111/401	LSPS6
40 40 40	4040-S19	40	40	250	50	40	41.5	5NUU1900UU	LVOIN	VHX 102/1N	2203IN	SPON	HW40L	L5P50
	4040-S25	40	40	250	50	40	46	SN□□2507□□						
	4040-S25-6	40	40	250	50	40	46	S SN□□2509□□	LV8N	VHX1236N	SS84N	SP8N	HW50L	LSPS8
	5050-T25-6	50	50	300	60	50	37.5	SN□□2509□□						

<sup>→</sup> Applicable inserts B50~B57

#### **PSSNR/L**



 $SN\square\square$ 





45°

• R type insert (mm)


Des	signation	Н	W	L	S	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PSSNR/L	1616-H09	16	16	100	20	16	25	SN□□0903□□	LV3	VHX0617	SS32	SP3	HW25L	LSPS3
	2020-K12	20	20	125	25	20	30							
	2525-M12	25	25	150	32	25	36	SN□□1204□□		\/I I\/0004	0040	SP4	HW30L	LSPS4
	3225-P12	32	25	170	32	32	36	3NUU1204UU	LV4	VHX0821	SS42	3F4	HVVSUL	LOP34
	3232-P12	32	32	170	40	32	40							
	2525-M15	25	25	150	32	25	36	SN□□1506□□	LV5	VHX0825	SS53	SP5	HW30L	LSPS5
	3232-P15	32	32	170	40	32	45	311 1500	LVS	VUV052	3333	SFS	HWOOL	Loros
	3232-P19	32	32	170	40	32	41.5							
	4040-R19	40	40	200	50	40	41.5	SN□□1906□□	LV6N	VHX1027N	SS63N	SP6N	HW40L	LSPS6
	4040-R19 4040-S19	40	40	250	50	40	41.5							
	4040-S25	40	40	250	50	40	48	SN□□2507□□	LV8N	VHX1236N	SS84N	SP8N	HW50L	LSPS8
	4040-S25-6	40	40	250	50	40	48	SN 2509	LVBIN	V   1   230  N	3364N	SPRIN	UNAOUL	L3738

<sup>◆</sup> Applicable inserts B50~B57

#### PTFNR/L



 $\mathsf{TN} \square \square$ 





W

90°

• R type insert (mm)


De	signation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PTFNR/L	1616-H16	16	16	100	20	16	20							
	2020-K16	20	20	125	25	20	20	TN□□1604□□	LV3	VHX0617	ST317	SP3	HW25L	LSPS3
	2525-M16	25	25	150	32	25	20							
	2525-M22	25	25	150	32	25	25	TN□□2204□□	IV4	VHX0821	ST42	SP4	HW30L	LSPS4
	2525-M22 3232-P22	32	32	170	40	32	25	11NLL2204LL	LV4	V11/0021	3142	3F4	HWOOL	LOF 34
	3232-P27	32	32	170	40	32	34	TN□□2706□□	LV5	VHX0825	ST53	SP5	HW30L	LSPS5
	4040-S27	40	40	250	50	40	34		LVS	VHXU023	3133	3F3	HWOUL	Loroo


<sup>→</sup> Applicable inserts B58~B65

#### PTGNR/L



 $\mathsf{TN} \square \square$ 





• R type insert (mm)


Des	signation	Н	W	L	S	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PTGNR/L	1212-F11	12	12	80	16	12	16							
	1616-H11	16	16	100	20	16	18	TN□□1103□□	LV2	VHX0509B			HW20L	
	2020-K11	20	20	125	25	20	19	INLLIIUSLL	LVZ	VIIVOOOAD	-	-	⊓VVZUL	-
	2525-M11	25	25	150	32	25	20							
	1616-H16 2020-K16	16	16	100	20	16	20							
		20	20	125	25	20	20	TN□□1604□□	LV3	VHX0617	ST317	SP3	HW25L	LSPS3
	2525-M16	25	25	150	32	25	20	11100400	LVS	VII/001/	31317	353	⊓vv∠3L	LOPOS
	3232-P16	32	32	170	40	32	20							
	2525-M22	25	25	150	32	25	28	TN 2204	LV4	VHX0821	ST42	SP4	HW30L	LSPS4
	2525-M22 3232-P22 3232-P27	32	32	170	40	32	28		LV4	VIIAU821	3142	3P4	HW30L	LSPS4
		32	32	170	40	32	33	TN□□2706□□	LV5	VHX0825	ST53	SP5	HW30L	LSPS5
	4040-S27	40	40	250	50	40	33		LV5	VIIAU825	3153	373	HW30L	LOPOD


<sup>◆</sup> Applicable inserts B58~B65

#### PTTNR/L



 $\mathsf{TN} \square \square$ 





• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch
PTTNR/L	1616-H16	16	16	100	13	16	25							
	2020-K16	20	20	125	17	20	25	TN□□1604□□	LV3	VHX0617	ST317	SP3	HW25L	LSPS3
	2525-M16	25	25	150	22	25	32							
	2525-M22	25	25	150	22	25	32	TN□□2204□□	LV4	VHX0821	ST42	SP4	HW30L	LSPS4


<sup>→</sup> Applicable inserts B58~B65

## **PWLNR/L**












Fig. 2

• R type insert (mm)


Des	ignation	Н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Shim Pin	Wrench	Shim Pin Punch	Fig.
PWLNR/L	1616-H06	16	16	100	20	16	20								
	2020-K06	20	20	125	25	20	20	WN□□0604□□	LV3	VHX0617	SW317	SP3	HW25L	LSPS3	1
	2525-M06	25	25	150	32	25	20								
	2020-K08	20	20	125	25	20	26	WN \\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	LV4	VHX0821	014/40	SP4	HW30L	LSPS4	2
	2525-M08	25	25	150	32	25	26	WIN0004	LV4	VI1AU021	SW42	3F4	HWOOL	LOF 04	




<sup>◆</sup> Applicable inserts B68~B72



 $\mathsf{TN} \square \square$ 






7	$TN\Box\Box$										1		• [	R type insert
														(mm)
_		l			_				Wedge Clamp Screw	Stopper Ring		Shim Pin	Nut	Wrench
De	signation	Н	W	L	S	h	Q	Insert	\$ 00°	9		<b>1</b>		
WTENN	2020-K16	20	20	125	10	20	36	TN 1604	CMH6R6 MHX062	6 ER04	ST32M	SP3M-1	N0407	HW30L
	2525-M16	25	25	150	12.5	25	36	11100400	CIVILIONO IVILIAU02	0 EN04	3132101	SP3M	110407	HVVOUL
	2525-M22	25	25	150	12.5	25	42	TN 2204	CMH6R1 MHX062	6 ER04	ST43M	SP4M	N0508	HW30L
	3232-P22	32	32	170	16	32	42	11N2204	CIVII IOI I I IVITIAU02	U L1104	0 1 4 3 IVI	JI 4IVI	140300	TIVVOUL


<sup>→</sup> Applicable inserts B58~B65

#### WTJNR/L



 $\mathsf{TN}\square\square$ 





• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Wedge Clamp	Screw	Stopper Ring		Shim Pin	Nut	Wrench
WTJNR/L	2020-K16	20	20	125	25	20	33						SP3M-1		
	2525-M16	25	25	150	32	25	33	TN□□1604□□	CMH6R6	ЛНX0626	ER04	ST32M	SP3M	N0407	HW30L
	3232-P16	32	32	170	40	32	33						SPSIVI		
	2525-M22	25	25	150	32	25	35	TN□□2204□□	CMH6R1 N	MUVAGAG	ED04	CTAOM	CDAM	NOEGO	HWOOL
	3232-P22	32	32	170	40	32	35	11100220400	CIVINONTI	VIII AU 0 2 0	ENU4	3 I 43IVI	SF4IVI	OUCUN	HVVSUL

<sup>◆</sup> Applicable inserts B58~B65

#### WTXNR/L



 $\mathsf{TN}\square\square$ 





105°

• R type insert (mm)

Des	ignation	Н	W	L	s	h	Q	Insert	Wedge Clamp Screw	Stopper Ring		Shim Pin	Nut	Wrench
WTXNR/L	2020-K16	20	20	125	25	20	30					SP3M-1		
	2525-M16	25	25	150	32	25	33	TN□□1604□□	CMH6R6 MHX0626	ER04	ST32M	SP3M	N0407	HW30L
	3232-P16	32	32	170	40	32	33					SPSIVI		


<sup>→</sup> Applicable inserts B58~B65

# **B** Wedge Clamp System

## WWLNR/L







95°


W	/N□□					n ,					H			• F	R type insert (mm)
Des	ignation	н	W	L	S	h	Q	Insert		Screw	Stopper Ring	Shim	Shim Pin	Nut	Wrench
WWLNR/L	2020-K08	20	20	125	25	20	32		CMH6R/L3				SP2M		HW30L
	2525-M08	25	25	150	32	25	33	WN□□0804□□	CMH6R2 MH	HX0630	CR05	SW43M	SP4M	N0508	HW40L
	3232-P08	32	32	170	40	32	33		CMH6R2				OI HIVI		TIVVTOL


<sup>◆</sup> Applicable inserts B68~B72

## CKJNR/L



 $\mathsf{KN} \square \square$ 





• R type insert (mm)


De	signation	Н	W	L	S	h	Q	Insert	Clamp Clamp Screw	Spring	Shim	Pin + Spring Shim Screw	Wrench
CKJNR	2020-K16	20	20	125	25	20	32						
	2525-M16	25	25	150	32	25	32						
	3225-M16	32	25	150	32	32	32	 	CTUED1 CUVOSOE	SR3	SK33C	PN0515 SHX0310	HW20L
	3225-P16	32	25	170	32	32	32	KINDD 1004DDA	CIRONI CRAU025	ono	SNSSC	SR4	HW40L
	3232-P16	32	32	170	40	32	32						
	4040-R16	40	40	200	50	40	32						
CKJNL	2020-K16	20	20	125	25	20	32						
	XJNL 2020-K16 2525-M16 3232-P16	25	25	150	32	25	32	 	CTH6L1 CHX0625	SR3	SK33CL	PN0515 SHX0310	HW20L
		32	32	170	40	32	32	NINIOU4L	CINOLI CHXU025	SHJ	SNJJUL	SR4 SHX0310	HW40L
	4040-R16	40	40	200	50	40	32						

<sup>◆</sup> Applicable inserts B49

#### **CKNNR/L**



 $\mathsf{KN} \square \square$ 





62.5°

• R type insert (mm)


De	esignation	Н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Spring	Shim	Pin + Spring	Shim Screw	Wrench
CKNNR	2525-M16 3232-P16	25 32	25 32	150 170	14.3 16.8	25 32	37 37	KN□□1604□□R	CTH6R1	CHX0625	SR3	SK33C	PN0515 SR4	SHX0310	HW20L HW40L
CKNNL	2525-M16	25	25	150	14.3	25	37	KN□□1604□□L	CTH6L1	CHAUGUE	CD2		PN0515 SR4		
	3232-P16	32	32	170	16.8	32	37	NINI004L	CIMOLI	CHX0625	SR3	3N33U	SR4	3UV0310	HW40L


Applicable inserts B49

## **CSDPN**



SP□R





• R type insert

														(mm)
									Clamp	Clamp Screw	Shim	Shim Pin	C-Ring	Wrench
Des	ignation	Н	W	L	S	h	Q	Insert		9		7	9	
CSDPN	1616-H09	16	16	100	8	16	30	SP□R0903□□	CH53R1	CH0515C	SS32C	SP3C	CR03C	HW25L
	2525-M12	25	25	150	12.5	25	35	SP□R1203□□	CH6R5	CHX0622C	SS42C	SP3C	CR04C	HW30L

<sup>→</sup> Applicable inserts B85~B86

## Clamp on System

#### CSKPR/L w 75° Н SP□R · R type insert (mm) Shim Pin Clamp Screw C-Ring Shim Wrench 0 W Designation Н L S h Q Insert 7 9

32

SP□R1203□□

CH6R5 CHX0414C

SS42C

SP3C

CR04C

HW30L

2525-M12

25


25

150


32

20

CSKPR/L



<sup>◆</sup> Applicable inserts B90~B93




<sup>→</sup> Applicable inserts B90~B93

<sup>◆</sup> Applicable inserts B85~B86

#### MCKNR/L



CN





75°

• R type insert


													(mm)
Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MCKNR/L	2020-K12	20	20	125	25	20	32						
	2525-M12	25	25	150	32	25	32	CN□□1204□□	CDH6N	DHA1/4-25	SC43D	SP4D	HW31.8L HW23.8L
	3232-P12	32	32	170	40	32	32						111120.0L

<sup>◆</sup> Applicable inserts B36~B42

#### MCLNR/L



 $CN\square\square$ 





95°

• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MCLNR/L	1616-H09	16	16	100	20	16	25			DUIA40.00			
	2020-K09	20	20	125	25	20	25	CN□□0903□□	CDH7N	DHA10-32- 19	SC32D	SP3DS	HW23.8L HW19.8L
	2525-M09	25	25	150	32	25	25			19			111110.02
	2020-K12	20	20	125	25	20	32						
	2525-M12	25	25	150	32	25	32	CN□□1204□□	CDH6N	DHA1/4-25	SC43D	SP4D	HW31.8L
	3225-P12 3232-P12 2525-M16	32	25	170	32	32	32	GN1204	CDHON	DHA 1/4-25	SC43D	5P4D	HW23.8L
		32	32	170	40	32	32						
		25	25	150	32	25	33						
	3232-P16	32	32	170	40	32	33	CN 1606	CDH8N	DHA5/16-32	SC53D	SP5D	HW39.7L HW31.8L
	4040-S16	40	40	250	50	40	33						111101.02
	4040-S16 2525-M19 3232-P19 4040-S19	25	25	150	32	25	38						
		32	32	170	40	32	38	CN 1906	CDH8N	DHA5/16-32	SC63D	SP6D	HW39.7L HW35.7L
		40	40	250	50	40	38						. 11100.7 L
		40	40	250	50	40	38	CN□□2507□□	CDH8N3	DHA3/8-35	SC84D	SP8D	HW39.7L HW47.6L


<sup>◆</sup> Applicable inserts B36~B42

#### **MCMNN**



 $\mathsf{CN} \square \square$ 





• R type insert (mm)

													()
De	esignation	Н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MCMNN	2020-K12	20	20	125	10	20	32						1.114/04.01
	2525-M12 3232-P12	25	25	150	12.5	25	32	CN 1204	CDH6N	DHA1/4-25	SC43D	SP4D	HW31.8L HW23.8L
	3232-P12	32	32	170	16	32	32						111120.02
	2525-M16	25	25	150	12.5	25	40	- CN□□1606□□	CDH8N	DHA5/16-32	SC53D	SP5D	HW39.7L
	3232-P16	32	32	170	16	32	40	CIN1000	CDHON	DHA3/10-32	30330	SF3D	HW31.8L
	3232-P19	32	32	170	16	32	40	CN□□1906□□	CDH8N	DHA5/16-32	SD63D	SP6D	HW39.7L
	4040-519	40	40	250	20	40	32	CINCIDIONO	CDHON	DHA3/10-32	30030	3500	HW35.7L


<sup>◆</sup> Applicable inserts B36~B42


# **B** Multi Lock System

#### MCRNR/L



 $CN\square\square$ 





• R type insert (mm)


Des	signation	н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MCRNR/L	2525-M12	20	20	125	22	20	32	CN□□1204□□	CDH8N1	DHA5/16-32	SC43D	SP4D	HW39.7L
		25	25	150	27	25	32	ON1204	CDITONI	DI IA3/ 10-32	3043D	31 4D	HW23.8L
	2525-M16	25	25	150	27	25	33	CN□□1606□□	CDH8N1	DHA5/16-32	SC53D	SP5D	HW39.7L
	3232-P16	32	32	170	35	32	33	CINLLIBUOLL	CDUONI	DHA3/10-32	30330	3F3D	HW31.8L
	3232-P19 4040-S19	32	32	170	35	32	38	CN□□1906□□	CDH8N1	DHA5/16-32	SC63D	SP6D	HW39.7L
		40	40	250	43	40	38	CINCLE 1900	ואוסרועט	DHA5/10-32	3003D	3700	HW35.7L

<sup>→</sup> Applicable inserts B36~B42

#### MDJNR/L



 $\mathsf{DN} \square \square$ 





93°

• R type insert (mm)


Des	ignation	н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MDJNR/L	2020-K11	20	20	125	25	20	32	DN□□1104□□	CDH6N	DHA1/4-19	SD32D	SP3D	HW31.8L
	2525-M11	25	25	150	32	25	32	DIN1104	CDHON	DHA 1/4-19	30320	SFSD	HW19.8L
	2020-K15-3	20	20	125	25	20	36						1.114/04.01
	2525-M15-3	25	25	150	32	25	36	DN□□1504□□	CDH6N	DHA1/4-25	SD43D	SP4D	HW31.8L HW23.8L
	2525-M15-3 3232-P15-3	32	32	170	40	32	36						11VVZO.0L
	2020-K15	20	20	125	25	20	36						1.11.40.4.01
	2525-M15	25	25	150	32	25	36	DN□□1506□□	CDH6N	DHA1/4-25	SD43D	SP4DL	HW31.8L HW23.8L
	3232-P15	32	32	170	40	32	36						114420.0L

Applicable inserts B43~B48

#### **MDNNN**



 $\mathsf{DN} \square \square$ 





62.5°

Des	ignation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MDNNN	2525-M15-3	25	25	150	12.5	25	41	DN□□1504□□	CDH8N	DHA5/16-32	SD43D	SP4D	HW39.7L HW23.8L
	2525-M15	25	25	150	12.5	25	41	DN 1506	CDH8N	DHA5/16-32	SD43D	SP4DL	HW39.7L HW23.8L


<sup>→</sup> Applicable inserts B43~B48



#### MDQNR/L



DN





107.5°

• R type insert (mm)


Des	ignation	н	w	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MDQNR/L	2525-M15-3 3232-P15-3	25 32	25 32	150 170	32 40	25 32	36 36	DN□□1504□□	CDH6N	DHA1/4-25	SD43D	SP4D	HW31.8L HW23.8L
	2525-M15	25	25	150	32	25	36	DN 1506	CDH6N	DHA1/4-25	SD43D	SP4DL	HW31.8L
	3232-M15	32	32	170	40	32	36	DIVERSION	CDITION	DI IA 1/4-23	30430	OI 4DL	HW23.8L

Applicable inserts B43~B48

#### MSBNR/L



 $SN\square\square$ 





75°

• R type insert (mm)


Des	signation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MSBNR/L	2525-M12 2525-M15 3232-P15 3232-P19	20	20	125	17	20	32	SN□□1204□□	CDH8N1	DHA5/16-32	SS43D	SP4D	HW39.7L
		25	25	150	22	25	32	311 1204	CDITOINT	DI IA3/ 10-32	0040D	JI 4D	HW23.8L
		25	25	150	22	25	35	SN□□1506□□	CDH8N	DHA5/16-32	SS53D	SP5D	HW39.7L
		32	32	170	22	32	35	311 1500	CDHON	DHA3/10-32	33330	3530	HW31.8L
		32	32	170	27	32	40	SN□□1906□□	CDH8N	DHA5/16-32	SS63D	SP6D	HW39.7L
	4040-S19	40	40	250	35	40	40	31111190011	CDHON	DHA3/10-32	3303D	3500	HW35.7L


<sup>→</sup> Applicable inserts B50~B57

#### **MSDNN**



 $SN\square\square$ 





(mm)

De	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MSDNN	1616-H09	16	16	100	8	16	28	SN□□0903□□	CDH7N	DHA10-32-19	SS32D	SP3DS	HW19.8L
	2020-K09	20	20	125	10	20	28	314 0903 0	CDITIN	DIIA10-32-19	3332D	31 303	HW23.8L
	2020-K12	20	20	125	10	20	32						
	2525-M12 3225-P12	25	25	150	12.5	25	32	SN□□1204□□	CDH8N1	DHA5/16-32	SS43D	SP4D	HW39.7L HW23.8L
		32	25	170	12.5	32	32						1100ZO.OL
	2525-M15	25	25	150	12.5	25	35						
	3225-P15	32	25	170	12.5	32	35	SN□□1506□□	CDH8N	DHA5/16-32	SS53D	SP5D	HW39.7L
	3232-P15	32	32	170	16	32	35	311 1300	CDHOIN	DHA5/10-32	3333D	3F3D	HW31.8L
	4040-S15 3232-P19	40	40	250	20	40	35						
		32	32	170	16	32	42	SN□1906□□	CDLION	DUAE/40.00	CCCOD	CDCD	HW39.7L
	4040-S19	40	40	250	20	40	42	SIN1906	CDH8N	DHA5/16-32	SS63D	SP6D	HW35.7L


<sup>●</sup> Applicable inserts B50~B57

# **B** Multi Lock System

#### MSKNR/L









• R type insert


Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MSKNR/L	1616-H09	16	16	100	20	16	28	SN□□0903□□	CDH7N	DHA10-32-19	SS32D	SP3DS	HW19.8L
	2020-K09	20	20	125	22	20	28	311 0903	CDITIN	DI IA 10-32-19	3332D	31 303	HW23.8L
	2020-K12	20	20	125	25	20	32						
	2525-M12 3225-P12 2525-M15	25	25	150	32	25	32	SN□□1204□□	CDH8N1	DHA5/16-32	SS43D	SP4D	HW39.7L HW23.8L
		32	25	170	32	32	32						
		25	25	150	32	25	35	SN□□1506□□	CDH8N	DHA5/16-32	SS53D	SP5D	HW39.7L
	3232-P15	32	32	170	40	32	35	3N1300	CDHON	DHA3/10-32	33330	3530	HW31.8L
	3232-P15 3232-P19 4040-S19	32	32	170	40	32	40	SN□□1906□□	CDH8N	DHA5/16-32	SS63D	SP6D	HW39.7L
		40	40	250	50	40	40	3NUL 1900LL	CDHOIN	DHA3/10-32	3303D	3F0D	HW35.7L
	4040-S25	40	40	250	50	40	40	SN□□2507□□	CDH8N3	DHA3/8-35	SS84D	SP8D	HW47.6L HW39.7L

<sup>◆</sup> Applicable inserts B50~B57

## MSRNR/L









75°

• R type insert (mm)


Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MSRNR/L	1616-H09	16	16	100	17	16	28	SN 0903	CDH7N	DHA10-32-19	SS32D	SP3DS	HW19.8L
	2020-K09	20	20	125	22	20	28	311 0903 0	CDH/N	DHA10-32-19	3332D	SPSDS	HW23.8L
	2020-K12	20	20	125	22	20	32	SN□□1204□□	CDH8N1	DHA5/16-32	SS43D	SP4D	HW39.7L
	2525-M12	25	25	150	27	25	32	3NUL 1204	CDUON	DHA3/10-32	3343D	3F4D	HW23.8L
	2525-M15	25	25	150	27	25	35	SN□□1506□□	CDH8N	DHA5/16-32	SS53D	SP5D	HW39.7L
	3232-P15	32	32	170	35	32	35	311 1306 1	CDHOIN	DHA3/10-32	3333D	3F3D	HW31.8L
	3225-P19	32	25	170	27	32	40						
	3232-P19	32	32	170	35	32	40	SN□□1906□□	CDH8N	DHA5/16-32	SS63D	SP6D	HW39.7L HW35.7L
	4040-S19	40	40	250	43	40	40						11VV00.7 L
	4040-S25	40	40	250	43	40	40	SN□□2507□□	CDH8N3	DHA3/8-35	SS84D	SP8D	HW47.6L HW39.7L


<sup>◆</sup> Applicable inserts B50~B57

#### MSSNR/L



SN





• R type insert


Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MSSNR/L	1616-H09	16	16	100	20	16	28	SN0903	CDH7N	DHA10-32-19	SS32D	SP3DS	HW19.8L
	2020-K09	20	20	125	25	20	28	311 0903	CDITIN	DI IA 10-02-19	3332D	31 303	HW23.8L
	2020-K12	20	20	125	25	20	32	   SN□□1204□□	CDH8N1	DHA5/16-32	SS43D	SP4D	HW39.7L
	2525-M12	25	25	150	32	25	32	311 1204	CDHONT	DHA3/10-32	3343D	3F4D	HW23.8L
	2525-M15	25	25	150	32	25	35	SN□□1506□□	CDH8N1	DHA5/16-32	SS53D	SP5D	HW39.7L
	3232-P15	32	32	170	40	32	35	311 1300	CDHONT	DHA3/10-32	33330	3530	HW31.8L
	3232-P19	32	32	170	40	32	40	SN□□1906□□	CDH8N1	DHA5/16-32	SS63D	SP6D	HW39.7L
	4040-S19	40	40	250	50	40	40	31N1900	CDIJONI	DHA5/10-32	3303D	3700	HW35.7L

<sup>→</sup> Applicable inserts B50~B57

#### **MTENN**



 $\mathsf{TN} \square \square$ 





(mm)


Des	ignation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MTENN	2020-K16 2525-M16	20 25	20 25	125 150	10 12.5	20 25	32 32	TN□□1604□□	CDH7N	DHA10-32-19	ST32D	SP3D	HW23.8L HW19.8L
	2525-M22	25	25	150	12.5	25	35	TN□□2204□□	CDH8N1	DHA5/16-32	ST43D	SP4D	HW39.7L HW23.8L
3	3232-P27	32	32	170	16	32	35	TN2706	CDH8N1	DHA5/16-32	ST53D	SP5D	HW39.7L HW31.8L
	4040-S33	40	40	250	20	40	40	TN□□3307□□	CDH8N	DHA5/16-32	ST63D	SP6DL	HW39.7L HW35.7L

<sup>◆</sup> Applicable inserts B58~B65


#### MTFNR/L



 $\mathsf{TN}\square\square$ 



Clamp



Shim Pin

• R type insert (mm)

Wrench

Des	ignation	Н	W	L	S	h	Q	Insert					
MTFNR/L	1616-H16	16	16	100	20	16	32						1.114/00.01
	2020-K16	20	20	125	25	20	32	TN1604	CDH7N	DHA10-32-19	ST32D	SP3D	HW23.8L HW19.8L
	2525-M16	25	25	150	32	25	32						
	2525-M22	25	25	150	32	25	32						1 114/00 71
	3232-P22	32	32	170	40	32	32	TN□□2204□□	CDH8N1	DHA5/16-32	ST43D	SP4D	HW39.7L HW23.8L
	4040-S22	40	40	250	50	40	32						111120.02
	2222 D27	20	20	170	40	20	25						


HW39.7L HW31.8L 3232-P27 170 40 TN 2706 2 CDH8N1 DHA5/16-32 SP5D 4040-S27 40 40 250 50 40 35 HW39.7L HW35.7L 4040-S33 40 250 TN\_\_3307\_\_ CDH8N DHA5/16-32 SP6DL 40 50 40 40 ST63D


<sup>→</sup> Applicable inserts B58~B65

#### MTGNR/L



 $\mathsf{TN} \square \square$ 





• R type insert (mm)


Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MTGNR/L	1616-H16	16	16	100	20	16	32						
	2020-K16	20	20	125	25	20	32	TN□□1604□□	CDH7N	DHA10-32-19	ST32D	SP3D	HW23.8L HW19.8L
	2525-M16	25	25	150	32	25	32						111110.02
	2525-M22	25	25	150	32	25	32	TN□□2204□□	CDH8N1	DHA5/16-32	ST43D	SP4D	HW39.7L
	3232-P22	32	32	170	40	32	32	111 2204	CDHONT	DHA3/10-32	3143D	3F4D	HW23.8L
	3232-P27	32	32	170	40	32	35	TN□□2706□□	CDH8N1	DHA5/16-32	ST53D	SP5D	HW39.7L
	4040-S27	40	40	250	50	40	35	11100270000	CDITOINT	DI IA3/10-32	31330	31 3D	HW31.8L
	4040-S33	40	40	250	50	40	40	TN□□3307□□	CDH8N	DHA5/16-32	ST63D	SP6DL	HW39.7L HW35.7L


<sup>●</sup> Applicable inserts B58~B65

#### MTJNR/L



 $\mathsf{TN} \square \square$ 





• R type insert


	Desi	gnation	Н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MTJN	NR/L	2020-K16	20	20	125	25	20	32	TN□□1604□□	CDH7N	DHA10-32-19	ST32D	SP3D	HW23.8L
		2525-M16	25	25	150	32	25	32	111001004	ODITIN	DIIA10-02-13	01020	01 00	HW19.8L
		2525-M22	25	25	150	32	25	32	TN□□2204□□	CDH8N1	DHA5/16-32	ST43D	SP4D	HW39.7L
		3232-P22	32	32	170	40	32	32	111 2204	CDITON	DI IA3/10-32	3143D	31 40	HW23.8L
		3232-P27	32	32	170	40	32	35	TN□□2706□□	CDH8N1	DHA5/16-32	ST53D	SP5D	HW39.7L
		4040-S27	40	40	250	50	40	35	111000000	CDHONT	DHA3/10-32	31330	SESD	HW31.8L
		4040-S33	40	40	250	50	40	40	TN□□3307□□	CDH8N	DHA5/16-32	ST63D	SP6DL	HW39.7L HW35.7L

<sup>◆</sup> Applicable inserts B58~B65

## MVJNR/L



VN





• R type insert (mm)

Des	signation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MVJNR/L	2020-K16	20	20	125	25	20	44						
	2525-M16	25	25	150	32	25	45.5	VN□□1604□□	CDH8N2	DHA5/16-32	SV32D	SP3D	HW39.7L HW19.8L
	3232-P16	32	32	170	40	32	55.5						111110.02
	2525-M22	25	25	150	32	25	56						
	3232-P22	32	32	170	40	32	55	VN□□2204□□	CDH8N2	DHA5/16-32	SV43D	SP4D	HW39.7L HW23.8L
	4040-S22	40	40	250	50	40	65						LO.OL




<sup>◆</sup> Applicable inserts B66~B67

#### **MVQNR/L**



VN





117.5°

• R type insert (mm)


Des	ignation	н	W	L	s	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MVQNR/L	MVQNR/L 2020-K16		20	125	25	20	42						
	2525-M16	25	25	150	32	25	42	VN□□1604□□	CDH8N2	DHA5/16-32	SV32D	SP3D	HW39.7L HW19.8L
	3232-P16	32	32	170	40	32	37						1100 13.0L

<sup>→</sup> Applicable inserts B66~B67

#### **MVVNN**



 $\mathsf{VN} \square \square$ 





72.5°


													(mm)
D-		ш	w				0	1	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
De	Designation			L	5	n	Ų	Insert				6000m	
MVVNN	2020-K16	20	20	125	25	20	42	VN□□1604□□	CDH8N2	DHA5/16-32	SV32D	SP3D	HW39.7L
	2525-M16	25	25	150	32	25	42	VIN1004	CDHoinz	DUA2/10-32	37320	3730	HW19.8L

<sup>◆</sup> Applicable inserts B66~B67

#### MWLNR/L



 $WN \square \square$ 





95°

• R type insert (mm)

Des	signation	н	W	L	S	h	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench
MWLNR/L		20	20	125	25	20	32						
	2525-M06	25	25	150	32	25	32	WN□□0604□□	CDH7N	DHA10-32-19	SW32D	SP3D	HW19.8L HW23.8L
	3232-P06	32	32	170	40	32	32						111120.02
2020-K08 2525-M08 3232-P08	2020-K08	20	20	125	25	20	32						
	2525-M08	25	25	150	32	25	32	WN□□0804□□	CDH6N	DHA1/4-21	SW43D	SP4D	HW31.8L HW23.8L
	3232-P08	32	32	170	40	32	32						114420.0L


<sup>◆</sup> Applicable inserts B68~B72


# B Screw on System





 $CC \square T$ 





• R type insert (mm)


Des	ignation	н	W	L	s	h	Insert	Screw	Shim	Shim Screw	Wrench
SCACR/L	1010-E06	10	10	70	10.5	10	CC T0602	FTKA02565	-	-	TW07P
	1212-F09	12	12	80	12.5	12	CC□□T09T3□□	FTKA03508	-	-	TW15P


<sup>◆</sup> Applicable inserts B73~B77, B103

## SCLCR/L



 $CC \square T$ 





• R type insert (mm)


Des	ignation	н	w	L	s	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
SCLCR/L	0808-D06	08	08	60	10	08	10	CC□T0602□□	FTKA02565			TW07P
	1010-E06	10	10	70	16	10	10	CC_10002	FTRA02505	-	-	TVVO/F
	1212-F09	12	12	80	20	12	16					
	1616-H09	16	16	100	20	16	16	CC□T09T3□□	FTGA03508	-	-	TW15P
	2020-K09	20	20	125	25	20	16					
2525-M09 2020-K12	2525-M09	25	25	150	32	25	26	CC□T09T3□□	FTGA0411F	SC42S	SHXN0610F	TW15P, HW40L
	2020-K12	20	20	125	25	20	25	CC□T1204□□	FTGA03508	-	-	TW15P
	2525-M12	25	25	150	32	25	26	CC□T1204□□	FTGA0411F	SC42S	SHXN0610F	TW15P, HW40L


<sup>◆</sup> Applicable inserts B73~B77, B103

## SDACR/L



 $\mathsf{DC} \square \mathsf{T}$ 





(mm)


Des	signation	н	W	L	s	h	Insert	Screw	Shim	Shim Screw	Wrench
SDACR/L	ACR/L 1010-E07		10	70	10.5	10	DC□T0702□□	FTKA02565	-	-	TW07P
_	1212-F11	12	12	80	12.5	12	DC□T11T3□□	FTKA03508	-	-	TW15P
	1616-H11	16	16	100	16.5	16		FTGA03512	SD32S	SHXN0509F	TW15P, HW35L

<sup>◆</sup> Applicable inserts B79~B82, B104

## SDJCR/L



 $DC \square T$ 





w

93°

• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
SDJCR/L	1010-E07	10	10	70	12	10	15					
	1212-F07	12	12	80	16	12	15	DC T0702	FTKA02565			TW07P
	1616-H07 2020-K07	16	16	100	20	16	18		F1KA02303	•	•	TVVO/P
		20	20	125	25	20	15					
	1212-F11	12	12	80	16	12	15					
1616-H11 2020-K11 2525-M11	1616-H11	16	16	100	20	16	24	DC□T11T3□□	FTGA03512	SD32S	SHXN0509F	TW15P, HW35L
	2020-K11	20	20	125	25	20	24		FIGAUSSIZ	3D323	SUVINOSOBL	TWISE, HWSSL
	2525-M11	25	25	150	32	25	29					

<sup>→</sup> Applicable inserts B79~B82, B104

### **SDNCN**



DC□T





62.5°

-						_					(mm)
De	Designation SDNCN 1010-E07		W	L	s	h	Insert	Screw	Shim	Shim Screw	Wrench
SDNCN	1010-E07	10	10	70	5	10	DC□T0702□□	FTKA02565			TW07P
12	1212-F07	12	12	80	6	12	DOL 10702	F1KA02303	-	-	TVVO/F
	1212-H11	12	12	100	6	12	DC□T11T3□□	FTGA03508	-	-	TW15P
	1616-H11	16	16	100	8	16	DC□T11T3□□	FTGA03512	SD32S	SHXN0509F	TW15P. HW35L
	2020-K11	20	20	125	10	20	DOLITIOLL	FIGAUSSIZ	30323	3HXIN0309F	TWISE, HWSSL
	2025-M11	25	25	150	12.5	25	DC T11T3	FTGA03512	SD32S	SHXN0509F	TW25P, HW35L


<sup>→</sup> Applicable inserts B79~B82, B104


## **SRDCN**



 $RC \square T$ 







(mm)


De	signation	Н	W	L	S	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
SRDCN	1010-E06	10	10	70	5	10	10					
	1212-F06	12	12	80	6	12	12	RC□T0602M0	FTKA02565		_	TW07P
	1616-H06	16	16	100	8	16	12	nc∐10002lvl0	FINAUZOOO	-	-	10077
	2525-M06 1616-H08 2020-K08	25	25	150	12.5	25	20					
		16	16	100	8	16	16					
		20	20	125	10	20	20	RC□T0803M0	FTNA0307	-	-	TW09P
	2525-M08	25	25	150	12.5	25	20					
	1616-H10	16	16	100	8	16	25					TIMED
	2020-K10	20	20	125	10	20	25	RC□T1003M0	FTKA03511A	SR10S	SHXN0509F	TW15P HW35L
2525-M1	2525-M10	25	25	150	12.5	25	25					TIVVOOL
	2020-K12	20	20	125	10	20	28	RC□T1204M0	FTGA03512	SR12S	SHXN0509F	TW15P
	2020-K12 2525-M12	25	25	150	12.5	25	28	NG∐11204W0	FIGMUSSIZ	3n123	SHANUSUSE	HW35L


<sup>◆</sup> Applicable inserts B83, B105

### SRGCR/L



 $RC \square T$ 





· R type insert


											(mm)
Doc	ianation	н	W			h	Incort	Screw	Shim	Shim Screw	Wrench
Des	signation	П П	VV		S	h	Insert	9			S/
SRGCR/L	1010-E06	10	10	70	12	10					
	1212-F06	12	12	80	16	12	RC□T0602M0	FTKA02565	-	-	TW07P
	1616-H06	16	16	100	20	16					
	1616-H08	16	16	100	20	16					
	2020-K08	20	20	125	25	20	RC□T0803M0	FTNA0307	-	-	TW09P
	2525-M08	25	25	150	32	25					
	1616-H10	16	16	100	20	16					TMASS
	2020-K10	20	20	125	25	20	RC⊡T1003M0	FTKA03511A	SR10S	SHXN0509F	TW15P HW35L
	2525-M10	25	25	150	32	25					
	2020-K12	20	20	125	25	20	RC□T1204M0	FTGA03512	SR12S	SHXN0509F	TW15P
	2525-M12	25	25	150	32	25	110 <u>11204</u> 1010	1 10403512	011120	OI IVI0009L	HW35L


Applicable inserts B83, B105

## SSBCR/L



SC□T





75°

• R type insert (mm)


Des	signation	н	W	L	s	h	Insert	Screw	Shim	Shim Screw	Wrench
SSBCR/L	1212-F09	12	12	80	11	12	SC□T09T3□□	FTGA03508	-	-	TW15P
	1616-H09	16	16	100	13	16	3001091300	FTGA03512	SS32S	SHXN0509F	TW15P, HW35L
	2020-K12	20	20	125	17	20	SC□T1204□□	FTGA0411F	SS42S	SHXN0610F	TW15P, HW40L


Applicable inserts B84, B106

## **SSDCN**



SC□T






(mm)

Desi	ignation	Н	W	L	S	h	Insert	Screw	Shim	Shim Screw	Wrench
SSDCN	1212-F09	12	12	80	6	12	SC□T09T3□□	FTGA03508	-	-	TW15P
1	1616-H09	16	16	100	8	16	3001091300	FTGA03512	SS32S	SHXN0509F	TW15P, HW35L

<sup>→</sup> Applicable inserts B84, B106



SHXN0509F TW15P, HW35L



13

100

20

16

SC T09T3


FTGA03512

SS32S


1616-H09

16

16



Applicable inserts B84, B106



<sup>→</sup> Applicable inserts B88~B89, B107


Applicable inserts B84, B106


# B Screw on System

### STFCR/L



 $TC \square T$ 





• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
STFCR/L	1010-E09	10	10	70	12	10	10	TC□T0902□□	FTKA02206	-	-	TW06P
	1212-F11	12	12	80	16	12	14	TC□T1102□□	FTKA02565			TW07P
	1616-H11	16	16	100	20	16	14	10_11102	FTRA02303	-	-	TVVO/F
	1616-H16	16	16	100	20	16	19	TC□T16T3□□	FTGA03512	ST32S	SHXN0509F	TW15P. HW35L
	2020-K16	20	20	125	25	20	19	10_11013	FIGAUSSIZ	31323	2UVIN0203L	TWIDE, HWOOL
	2525-M16	25	25	150	32	25	25.2	TC□T16T3□□	FTGA03512	ST32S	SHXN0509F	TW15P, HW35L


<sup>→</sup> Applicable inserts B88~B89, B107

## STGCR/L



TC□T





· R type insert


Des	signation	Н	W	L	S	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
STGCR/L	0808-D09	08	08	60	10	08	11	TC□T0902□□	FTKA02206			TW06P
	1010-E09	10	10	70	12	10	11	1001090200	F1KAU2206	-	•	1 00000
	1212-F11	12	12	80	16	12	14	TC□T1102□□	FTKA02565			TW07P
	1616-H11	16	16	100	20	16	16	ICLITIU2LL	F1KA02505	-	•	10076
	1616-H16	16	16	100	20	16	21					
	2020-K16	20	20	125	25	20	21	TC□T16T3□□	FTGA03512	ST32S	SHXN0509F	TW15P, HW35L
	2525-M16	25	25	150	32	25	21					


<sup>◆</sup> Applicable inserts B88~B89, B107

## STTCR/L



 $TC \square T$ 







• R type insert (mm)

Des	Designation		w	L	s	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
STTCR/L	1616-H11	16	16	100	13	16	14	TC□T1102□□	FTKA02565	-	-	TW07P
	1616-H16	16	16	100	13	16	19	TC□T16T3□□	FTGA03512	ST32S	SHXN0509F	TW15P. HW35L
	2020-K16	20	20	125	17	20	19	10_11613	FIGAUSSIZ	31323	SUVINOSOBL	TWIDE, HWOOL


<sup>→</sup> Applicable inserts B88~B89, B107



<sup>◆</sup> Applicable inserts B94~B96, B108



<sup>→</sup> Applicable inserts B94~B96, B108





<sup>→</sup> Applicable inserts B94~B96, B108

## SVJCR/L









• R type insert (mm)


Des	signation	н	W	L	s	h	Q	Insert	Screw	Shim	Shim Screw	Wrench
SVJCR/L	1212-F11	12	12	80	16	12	25					
	1616-H11	16	16	100	20	16	25	VC□T1103□□	FTKA02565	-	-	TW07P
	2020-K11	20	20	125	25	20	25					
	1212-F13	12	12	80	16	12	32					
	1212-F13 1616-H13	16	16	100	20	16	32	VC□T1303□□	FTKA0307	-	-	TW09P
	2020-K13	20	20	125	25	20	32					
	1616-H16	16	16	100	20	16	40					TWIED
	2020-K16	20	20	125	25	20	40	VC□T1604□□	FTGA03512	SV32S	SHXN0509F	TW15P, HW35L
	2525-M16	25	25	150	32	25	40					TIVVOOL

<sup>◆</sup> Applicable inserts B97~B99, B109

### **SVVBN**



VB□T





72.5°


											(mm)
De	signation	н	W	L	s	h	Insert	Screw	Shim	Shim Screw	Wrench
SVVBN	1212-F11	12	12	80	6	12					
	1616-H11	16	16	100	8	16	VB□T1102□□	FTKA02565	-	-	TW07P
	2020-K11	20	20	125	10	20					
	1616-H16	16	16	100	8	16					
	2020-K16	20	20	125	10	20	   VB□T1604□□	FTGA03512	SV32S	SHXN0509F	TW15P, HW35L
	2525-M16	25	25	150	12.5	25	VB_11004	FIGAUSSIZ	37323	SHAMUSUSE	TWISE, HWSSE
	3225-P16	32	25	170	12.5	32					

<sup>→</sup> Applicable inserts B94~B96, B108

#### **SVVCN**



 $\mathsf{VC} \square \mathsf{T}$ 






(mm)


De	esignation	Н	W	L	s	h	Insert	Screw	Shim	Shim Screw	Wrench
SVVCN	1212-F11	12	12	80	6	12					
	1616-H11	16	16	100	8	16	VC□T1103□□	FTKA02565	-	-	TW07P
	2020-K11	20	20	125	10	20					
	1212-F13	12	12	80	6	12					
	1616-H13	16	16	100	8	16	VC□T1303□□	FTNA0307	-	-	TW09P
	2020-K13	20	20	125	10	20					
1	1616-H16	16	16	100	8	16					
	2020-K16	20	20	125	10	20	VC□T1604□□	FTGA03512	SV32S	SHXN0509F	TW15P, HW35L
	2525-M16	25	25	150	12.5	25					





 $\mathsf{CN} \square \mathsf{N}$ 





• R type insert


	(111111)
ng	Wrench

Designation	Н	W	L	S	h	Q	Insert	Clamp	Screw	Shim	Spring	Wrench
CCLNR/L 2525-M12C	25	25	150	32	25	32	CN□N1204□□ CN□N1207□□	CH6R3	MHX0630 SHX0310	SC42CC	SR3	HW40L HW20L

### **CRDNN**



 $\mathsf{RN} \square \mathsf{N}$ 






	(mm)	
ıg	Wrench	
	HWAN	

D	esignation	Н	W	L	s	h	Q	Insert	Clamp	Screw	Shim	Spring	Wrench
CRDNN 2	2525-M12C	25	25	150	12.5	25	35	RN□N1204□□ RN□N1207□□	CH6R3	MHX0630 SHX0310	SC42CC	SR3	HW40L HW20L

## **CRGNR/L**



 $RN\square N$ 






• R type insert

												(111111)
								Clamp	Screw	Shim	Spring	Wrench
Designation	Н	W	L	S	h	Q	Insert		07			
CRGNR/L 2525-M12C	25	25	150	32	25	32	RN_N1204 RN_N1207	CH6R3	MHX0630 SHX0310	SC42CC	SR3	HW40L HW20L

## **CSDNN**



 $SN\square N$ 








45°

												(mm)
Designation	н	W	L	s	h	Q	Insert	Clamp	Screw	Shim	Spring	Wrench
CSDNN 2525-M12C	25	25	125	12.5	25	35	SN□N1204□□ RN□N1207□□	CH6R3	MHX0630 SHX0310	SS42CC	SR3	HW40L HW20L

## **B** Ceramic Holder










#### KORLOY High Pressure Coolant



#### ISO turning holder

- 300% increased productivity on Inconel machining vs. low pressure coolant system
- · Cooling, tool life, and chip control are improved by the high volume coolant multi-directional injection system



#### Features

- The optimal distance between the insert and the jet orifice and the ideal place of the jet orifice
- Maximized loss pressure of coolant pressure due to streamlined design of internal path
- Easy to clamp an insert for sliding clamp system



The original position of water clamp



The position of placing insert




Optimal position and distance of spraying




Oval direct spray

#### MAX 300 bar

Workpiece	The minimum pressure	The maximum pressure
P	50	
M	70	
K	60	300
N	50	
S	70	







\* Clamp is sold seperately


## B

#### **Technical Information for KHP Coolant**


#### How to use the water clamp



#### Application range





#### Grade Line-up




#### How to clamp the KHP Coolant

- · 3 types of installation systems makes clamping easy
- The banjo type hose provides wider area for machining than other types







<sup>\*</sup> Banjo screws provide easy clamping and clamping a holder to the turning machine with various types of blanks



#### Components of KHP Coolant

- The components of high pressure coolant are sold separately
- Various components are available according to different machining sites and uses machining with high pressure coolant

Designation	Shape	Hose length	High pressure hose	Blank	Adaptor	Banjo screw	Copper washer	Pic.
HPH3/8UNF-200-SET	s s	200 mm			2 EA			4
HPH3/8UNF-250-SET	100 T 100	250 mm			2 EA	-	-	ı
HPH3/8UNF1/8PF-200-SET	S B	200 mm	1.54	1 EA	1 54	1.50	0.54	2
HPH3/8UNF1/8PF-250-SET		250 mm	1 EA	I EA	1 EA	1 EA	3 EA	2
HPH1/8PF-200-SET	ВВВ	200 mm				2 FA	5 EA	3
HPH1/8PF-250-SET	O	250 mm	n		-	2 EA	O EA	3

#### KHP Coolant Parts

Division	Designation		Shape
adaptor	HPA3/8UNF1/8PF		G1/8 (PF1/8) UNF3/8
Blank	HPB1/8PF		G1/8 (PF1/8)
Banjo screw	HPZ1/8PF		G1/8 (PF1/8)
Copper washer	HPW1/8PF	0	Interneral Ø10

#### **⊘** KHP Coolant High pressure hose


	High pressure hose shape	Length	S	В	
Straight to straight	UNF3/8	UNF3/8	200 mm	UNF3/8	
(HPH3/8UNF)	\$ <del> </del>		250 mm	UNF3/6	-
Straight to banjo	UNF3/8	Internal Ø10	200 mm	LINEO/O	Internal Ø10
(HPH3/8UNF1/8PF)	,	=B	250 mm	UNF3/8	Internal Ø10
Banjo to banjo	Internal Ø10	Internal Ø10	200 mm		Internal Oid O
(HPH1/8PF)	В 🍪=	<del></del>	250 mm	<del>-</del>	Internall Ø10

# **B** KHP Coolant

## PCLNR/L









• R type insert


																	(mm)
Designation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Ship pin	Shim Pin Punch		Clamping screw	Oil seal	Plug	Wrench
PCLNR/L 2525-M12-KHP	25	25	150	32	25	34	CN□□1204□□	LV4N	VITAUOUVI	SC42N	SP4N	I CDC4	UD∩D/I U	MUDANIE	⊔D∩79	KHA0404-	HW20L
3232-P12-KHP	32	32	170	40	32	34	CIN 1204	LV4IN	VIIAU02UIN	3042IN	3F4IN	LOP04	nrun/L-n	WINDU413	пголо	NYLOCK	HW30L

<sup>→</sup> Applicable inserts B36~B42

## PDJNR/L



 $\mathsf{DN}\square\square$ 





93°

• R type insert

De	esignation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Ship pin	Shim Pin Punch	Clamp	Clamping screw	Oil seal	Plug	Wrench
PDJNR/L	2525-M11-KHP	25	25	150	32.25	25	42	DN1104	LV3AN	VHX0617N	SD32N	SP3	LSPS3	HPCR/L-ŀ	H MHB0415	HPO7S	KHA0404- NYLOCK	HW20L HW25L HW30L
	2525-M1504-KHP	25	25	150	32.25	25	42	DN□□1504□□	LV4BN	VHX0821N	SD43N	SP4N	LSPS4	HPCR/L-H	H MHB0415	HPO7S	KHA0404- NYLOCK	HW20L HW30L
	2525-M1506-KHP	25	25	150	32.25	25	42	DN 1506	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	HPCR/L-H	H MHB0415	HPO7S	KHA0404- NYLOCK	HW20L HW30L


<sup>→</sup> Applicable inserts B43~B48


## **PSSNR/L**



SN







R type	insert
(1	mm)


	Designation	н	W	L	s	h	Q	Insert	Lever	Screw	Shim	Ship pin	Shim Pin Punch	Clamp	Clamping screw	Oil seal	Plug	Wrench
P	SSNR/L 2525-M12-KHP	25	25	150	34.25	25	35.5	SN□□1204□□	LV4N	VHX0821	SS42N	SP4N	LSPS4	HPCR/L-3H	MHB0415	HPO7S	KHA0404- NYLOCK	HW20L HW30L


<sup>→</sup> Applicable inserts B50~B57













• R type insert (mm)

Designation	Н	W	L S	h	Q	Insert	Lever	Screw	Shim	Ship pin	Shim Pin Punch		Clamping screw	Oil seal	Plug	Wrench
PWLNR/L 2525-M08-KHP	25	25	150 32.25	25	33	WN□□0804□□	LV4N	VILIVOOONI	CMAON	CDAN	I CDC4		MUDOALE	UDO70	KHA0404-	HW20L
3232-P08-KHP	32	32	170 39.25	32	33	WIN0804	LV4IN	VIIAU02UIN	3W4ZIV	SF4IV	LOF04	nrun/L-n	IVINDU413	пголо	NYLOCK	HW30L


<sup>◆</sup> Applicable inserts B68~B72





Applicable inserts B83, B105




Applicable inserts B94~B96, B108


























## **Double Clamp System**

Cutting Shape		3					
Designation	DCLNR/L	DDUNR/L	DSKNR/L	DTFNR/L	DWLNR/L		
Approach angle	95°	93°	75°	90°	95°		
Page	B208	B208	B208	B209	B209		
Copying		•					
Facing	•				•		
Back turning		•					
Turning	•	•	•	•	•		

## Lever Lock System

Cutting Shape			7				
Designation	PCLNR/L	PDSNR/L	PDUNR/L	PSKNR/L	PTFNR/L	PWLNR/L	
Approach angle	95°	62.5°	93°	75°	90°	95°	
Page	B210	B210	B210	B211	B211	B211	
Copying		•	•				
Facing	•					•	
Back turning		•	•			•	
Turning	•	•	•	•	•	•	

### Clamp on System

Cutting Shape						
Designation	CKUNR/L	CSKPR/L	CTFPR/L			
Approach angle	93°	75°	90°			
Page	B212	B212	B212			
Copying						
Facing						
Back turning	•					
Turning	•	•	•			

## Multi Lock System

Cutting Shape		***			7 20		
Designation	MCLNR/L	MDUNR/L	MSKNR/L	MTFNR/L	MVUNR/L	MWLNR/L	
Approach angle	95°	93°	75°	90°	93°	95°	
Page	B213	B213	B213	B214	B214	B214	
Copying		•			•		
Facing	•					•	
Back turning		•			•		
Turning	•	•	•	•	•	•	


# **B** Index for Boring Bar

#### **Screw on System**

Cutting								
Shape		0						
Designation	SCLCR/L	SCLPR/L	SDQCR/L	SDUCR/L	SDZCR/L	SSKCR/L	SSKPR/L	STFCR/L
Approach angle	95°	95°	107.5°	93°	93°	75°	75°	90°
Page	B215	B216	B217	B218	B219	B219	B219	B220
Copying			•	•				
Facing	•	•						
Back turning			•	•	•			
Turning	•	•	•	•	•	•	•	•

Cutting Shape								
Designation	STFPR/L	STWPR/L	SVJCR/L	SVQBR/L	SVQCR/L	SVUBR/L	SVUCR/L	SWLCR/L
Approach angle	90°	60°	142°	108°	108°	93°	93°	95°
Page	B221	B222	B222	B222	B223	B223	B223	B224
Copying			•	•	•	•	•	•
Facing								
Back turning				•	•	•	•	•
Turning	•	•	•	•	•	•	•	•

#### **Compact Mini**



#### Carbide Shank Boring Bar

Designation	SCLCR/L	SCLPR/L	SDQCR/L	SDUCR/L	STFCR/L
Approach angle	95°	95°	107.5°	93°	90°
Page	B215	B216	B217	B218	B220


Designation	STFPR/L	STUBR/L	STUPR/L	SWUBR/L	-
Approach angle	90°	93°	93°	93°	-
Page	B221	B225	B226	B227	-


#### Sleeve


	Shape	
Designation SL	Designation	SL
Page B151	Page	B151





#### **Instructions of Boring Bar assembly**












#### Carbide Shank Boring Bar

- Excellent cutting performance even in internal machining with chattering
- Available for various workpieces such as steel, stainless steel, cast iron, etc.
- Improved tool life and surface roughness

#### Features



Higher strength and durability than steel shank, special surface treatment applied

#### Comparison of chipping


Specifications	Ste	eel boring b	oar	Carl	bide boring	j bar
• SCM440 • vc (m/min) = 200 • ap (mm) = 0.4 • fn (mm/rev) = 0.15 • Cutting depth: 5D		eased chippin				able tool life
	Rmax	Rz	Ra	Rmax	Rz	Ra
	4.67	3.68	0.62	3.07	2.76	0.53

## **B** Double Clamp System

### DCLNR/L








															(mm)
Designation	ØD	Ød	Н	L	s	Q	Insert	Clamp	Clamp Screw		Shim Screw	- 1 - 3	Nozzle	Wrench	Fig.
A25R-DCLNR/L-09	32	25	24	200	17	40	CN 0903	CVH3	CHX0415	SC32V	FTKA0307	SPR0510	CN0605	HW25P	1
A25R-DCLNR/L-12	32	25	24	200	17	40									1
A32S-DCLNR/L-12	40	32	30	250	22	50	CN□□1204□□	CVH4	CHX0518	SC42V	FTKA0410	SPR0714	CN0605	HW30P	2
A40T-DCLNR/L-12	50	40	38	300	27	60									3
A50U-DCLNR/L-16	63	50	48	350	35	70	CN 1606 1	CVH5	CHX0622	SC54V	FTNA0511	SPR0811	CN0605	HW40L	3

<sup>●</sup> Applicable inserts B36~B42

## **DDUNR/L**



 $\mathsf{DN} \square \square$ 



															(mm)
Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw		Nozzle	Wrench	Fig.
A40T-DDUNR/L-15	50	40	38	300	27	60	DN 1506	CVH4	CHX0518	CD40V	FTKA0410	CDD0714	CN0605	HW30P	
A50U-DDUNR/L-15	63	50	47	350	35	70		CVH4	CHV0310	3D43V	FINAU410	3FN0/14	CNUOUS	ПИИЗОР	
A40T-DDUNR/L-15 -3	50	40	37	300	25	60	DN□□1504□□	CVH4	CHX0518	SDAAN	FTKA0410	SDD0714	CN0605	HW30P	2
A50U-DDUNR/L-15 -3	63	50	47	350	35	70	DINLL 1304	CVH4	CHAUSTO	3D44V	FINAU410	3FN0/14	CINUOUS	ПИУЗОГ	٥


<sup>◆</sup> Applicable inserts B43~B48


### **DSKNR/L**



 $SN\square\square$ 

ØD Min. machinii	ng Dia.	7
	75° S	





75°

93°

• R type insert

R	type insert
	(mm)


Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Nozzle	Wrench	Fig.
A25R-DSKNR/L-09	32	25	24	200	17	40	SN□□0903□□	CVH3	CHX0415	SS32V	FTKA0307	SPR0510	CN0605	HW25P	1
A25R-DSKNR/L-12	32	25	24	200	17	40									1
A32S-DSKNR/L-12	40	32	30	250	22	50	SN□□1204□□	CVH4	CHX0518	SS42V	FTKA0410	SPR0714	CN0605	HW30P	
A40T-DSKNR/L-12	50	40	38	300	27	60									3

<sup>◆</sup> Applicable inserts B50~B57

#### DTFNR/L







Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Nozzle	Wrench	Fig.
A25R-DTFNR/L-16	32	25	24	200	17	40	TN□□1604□□	CVH3	CHX0415	ST32V	FTKA0307	CDD0E10	CNIGGOE	HW25P	1
A32S-DTFNR/L-16	40	32	30	250	22	50	111004	CVIIS	UHX0413	31321	FTRAU307	3500310	CINUOUS	ПИУZЭГ	3
A40T-DTFNR/L-22	50	40	38	300	27	60	TNDDOOADD	CVH4	CLIVOE10	ST44V	FTKA0410	CDD0714	CN0605	HW30P	
A50U-DTFNR/L-22	63	50	47	350	35	70	TN2204	UVH4	CHX0518	5144V	F1KA0410	3PHU/14	CINUBUS	HW30P	3

<sup>→</sup> Applicable inserts B58~B65

### **DWLNR/L**



 $WN \square \square$ 

OD Min. machining Dia.	Od Od Od H Fig. 1 Fig. 2 Fig. 3	95°
		• R type insert

															(mm)
Designation	ØD	Ød	Н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Screw	Spring	Nozzle	Wrench	Fig.
A25R-DWLNR/L-06	32	25	24	200	17	40									1
A32S-DWLNR/L-06	40	32	30	250	22	50	WN0604	CVH3	3 CHX0415	15 SW32V	FTKA0307	SPR0510	CN0605	HW25P	3
A40T-DWLNR/L-06	50	40	38	300	27	60									3
A25R-DWLNR/L-08	32	25	24	200	17	40									1
A32S-DWLNR/L-08	40	32	30	250	22	50	WNDD004DD	CVH4 CHX	CHAUETO	CMAON	ETI/ AO 410	CDD0714	CNIGGOE	HW30P	
A40T-DWLNR/L-08	50	40	38	300	27	60	WN 0804 0	CVII4	CHXU310	34424	W42V FTKA0410 SPR0714			ПИУЗОР	3
A50U-DWLNR/L-08	63	50	47	350	35	70									


<sup>◆</sup> Applicable inserts B68~B72



#### PCLNR/L



CN




Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim Pin	Shim Pin Punch	Wrench	Fig.	
S16R-PCLNR/L-09	20	16	14	200	11	25								2	
S20S-PCLNR/L-09	25	20	18	250	13	32	CN□□0903□□	LV3C	VHX0509B	-	-	-	HW20L		
S25R-PCLNR/L-09	32	25	23	200	17	40								3	
S25R-PCLNR/L-12	32	25	23	200	17	40		LV4A	VHX0613A	_			HW25L		
S25T-PCLNR/L-12	32	25	23	300	17	40	CNDD1204DD	LVTA	VIIAUUISA	-	-	-	HWZSL		
S32S-PCLNR/L-12	40	32	30	250	22	50		LV4	VHX0821	SC42B	SP4	LSPS4	HW30L	3	
S32U-PCLNR/L-12	40	32	30	350	22	50	CIN1204	LV4	VHX0821	SC43B	SP4	-	HW30L	3	
S40T-PCLNR/L-12	50	40	38	300	27	60		LV4	VUVOOA	SC42B	SP4	LSPS4	HW30L		
S50U-PCLNR/L-12	63	50	47	350	35	70		LV4	VHX0821	3042B	354	LOF 34	HWOOL		
S50U-PCLNR/L-19	63	50	47	350	35	70	CN□□1906□□	LV6	VHX1027	SC63	SP6	LSPS6	HW40L	3	
A25R-PCLNR/L-12	32	25	24	200	17	40	O CN 1204	LV4A	VHX0613A	-	-	-	HW25L	1	
A32S-PCLNR/L-12	40	32	30	250	22	50		11/4	// \/\!\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	SC42B	SP4	LSPS4	HW30L	3	
A40T-PCLNR/L-12	50	40	38	300	27	60		LV4	LV4	LV4	VHX0821	3042B	3P4	LOP54	HVV3UL

<sup>◆</sup> Applicable inserts B36~B42

#### PDSNR/L








Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim Pin	Shim Pin Punch	Wrench	Fig.
S32S-PDSNR/L-15	40	32	30	250	22	50	DN 1506	I V4B	VHX0821	SD42	SP4	LSPS4	HW30L	
S40T-PDSNR/L-15	50	40	38	300	27	60	DINLLISUOLL	LV4D	VI1/10021	3042	354	LOF 34	HWOOL	
S32S-PDSNR/L-15-3	40	32	30	250	22	50	DN□□1504□□	IV4	VHX0821	SD42	SP4	LSPS4	HW30L	,
S40T-PDSNR/L-15-3	50	40	38	300	27	60	DIN1504	LV4	V	3D42	3F4	LSF34	HWOOL	3
A32S-PDSNR/L-15	40	32	30	250	22	50	DN 1506	LV4B	VHX0821	SD42	SP4	LSPS4	HW30L	
A32S-PDSNR/L-15-3	40	32	30	250	22	50	DN 1504	LV4	VHX0821	SD42	SP4	LSPS4	HW30L	


<sup>◆</sup> Applicable inserts B43~B48


### PDUNR/L



 $\mathsf{DN}\square\square$ 







• R type insert (mm)

Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim Pin	Shim Pin Punch	Wrench	Fig.
S32S-PDUNR/L-11	40	32	30	250	22	50	DN1104	LV3	VHX0617	SD317	SP3	LSPS3	HW25L	3
S32S-PDUNR/L-15	40	32	30	250	22	50								
S40T-PDUNR/L-15	50	40	38	300	27	60	DN 1506 _	LV4B	VHX0821	SD42	SP4	LSPS4	HW30L	3
S50U-PDUNR/L-15	63	50	47	350	35	70								
S32S-PDUNR/L-15-3	40	32	30	250	22	50	DN 1504	LV4	VHX0821	SD42	SP4	LSPS4	HW30L	3
S40T-PDUNR/L-15-3	50	40	38	300	27	60	DIN1504	LV4	V	3D42	3F4	LOF 34	HWSUL	٥
A32S-PDUNR/L-15	40	32	30	250	22	50	DN 1506	LV4B	VHX0821	SD42	SP4	LSPS4	HW30L	3
A32S-PDUNR/L-15-3	40	32	30	250	22	50	DN 1504	LV4	VHX0821	SD42	SP4	LSPS4	HW30L	3




◆ Applicable inserts B43~B48





 $SN \square \square$ 




														٠,
Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim Pin	Shim Pin Punch	Wrench	Fig.
S25R-PSKNR/L-12	32	25	23	200	17	40		LV4A	VHX0613A	-	-	-	HW30L	
S32S-PSKNR/L-12	40	32	30	250	22	50	SN□□1204□□	LV4	VHX0821	SS42B	SP4	LSPS4	HW30L	3
S40T-PSKNR/L-12	50	40	38	300	27	60	OINIZO+	LV4	VIIAU021	33420	354	LOF 34	HWOOL	
A25R-PSKNR/L-12	32	25	24	200	17	40	SN□□1204□□ -	LV4A	VHX0613A	-	-	-	HW25L	1
A32S-PSKNR/L-12	40	32	30	250	22	50	3NUU1204UU	LV4	VHX0821	SS42B	SP4	LSPS4	HW30L	3

<sup>●</sup> Applicable inserts B50~B57

### PTFNR/L



 $\mathsf{TN}\square\square$ 




														(111111)
Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim Pin	Shim Pin Punch	Wrench	Fig.
S16R-PTFNR/L-11	20	16	14	200	11	25								
S20S-PTFNR/L-11	25	20	18	250	13	32	TN	LV2	VHX0509B	-	-	-	HW25L	2
S25R-PTFNR/L-11	32	25	23	200	17	40								3
S25R-PTFNR/L-16	32	25	23	200	17	40		LV3B	VHX0512B	-	-	-	HW20L	
S32S-PTFNR/L-16	40	32	30	250	22	50		LV3	VHX0617	ST317B	SP3	LSPS3	HW25L	3
S40T-PTFNR/L-16	50	40	38	300	27	60	D TN 1604	LVS	VIIAUUI7	313176	353	LOFOO	HWZSL	
A25R-PTFNR/L-16	32	25	24	200	17	40		LV3	VHX0617	-	-	-	HW25L	1
A32S-PTFNR/L-16	40	32	30	250	22	50		LV3	VHX0617	ST317B	SP3	LSPS3	HW25L	3


<sup>→</sup> Applicable inserts B58~B65


### **PWLNR/L**



 $WN \square \square$ 







• R type insert (mm)

														` '
Designation	ØD	Ød	Н	L	s	Q	Insert	Lever	Screw	Shim	Shim Pin	Shim Pin Punch	Wrench	Fig.
S16R-PWLNR/L-06	20	16	14	200	11	25	WNMG060408	LV3B	VHX0512B	-	-	-	HW20L	2
S20S-PWLNR/L-06	25	20	18	250	13	32		LV3B	VHX0512B	_			HW20L	2
S25R-PWLNR/L-06	32	25	23	200	17	40	WN 0604 0	LVSD	VIIVO215D	-	-	-	HVVZUL	2
S32S-PWLNR/L-06	40	32	30	250	22	50		LV3	VHX0617	SW317	SP3	LSPS3	HW25L	3
S25R-PWLNR/L-08	32	25	23	200	17	40	WN 0804	LV4A	VHX0613A	-	-	-	HW25L	
S32S-PWLNR/L-08	40	32	30	250	22	50	VVINU8U4	LV4	VHX0821	SW42	SP4	LSPS3	HW30L	3


<sup>◆</sup> Applicable inserts B68~B72

# B Clamp on System

### **CKUNR/L**



 $\mathsf{KN} \square \square$ 




Designation	ØD	Ød	Н	L	s	Q	Insert	Clamp	Clamp Screw	Spring	Shim	Pin+Spring	Shim Screw	Wrench
S32S-CKUNR-16	40	32	30	250	22	70						DNOC45		
S40T-CKUNR-16	50	40	37	300	27	60	55	CTH6LI	CHX0625	SR3	SK33CL	PN0515 SR4	SHX0310	HW40L HW20L
S50U-CKUNR-16	63	50	43	350	35	55						ON4		TIVVZOL
S32S-CKUNL-16	40	32	30	250	22	70						DNOC4E		
S40T-CKUNL-16	50	40	37	300	27	60		CTH6RI	CHX0625	SR3	SK33C	PN0515 SR4	SHX0310	HW40L HW20L
S50U-CKUNL-16	63	50	43	350	35	55						JN4		111120L


Applicable inserts B49

## CSKPR/L



 $SP \square \square$ 





R type insert (mm)


Designation	ØD	Ød	н		6	0	Insert	Clamp	Clamp Screw	C-ring	Wrench
Designation		χu				*	msert		0	9	
S16R-CSKPR/L-09	20	16	15	200	11	30	SP□□0903□□	CH4R1C	CHX0414C	CR02C	HW25L
S20S-CSKPR/L-09	25	20	18	250	13	36	3F0903	CH5R5C	CHX0519C	CR03C	HW30L
S20S-CSKPR/L-12	25	20	18	250	13	28	SP□□1203□□	CH6R5	CH0616	CR04C	HW30L
S25R-CSKPR/L-12	32	25	23	300	17	40	3FLL1203LL	CHORD	CH0010	UN04U	⊓vv30L


<sup>●</sup> Applicable inserts B85~B86

## CTFPR/L



 $\mathsf{TP} \square \square$ 





• R type insert (mm)

Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	C-ring	Shim	Shim Pin	Wrench
S12M-CTFPR/L-11	16	12	11	150	9	26							
S16R-CTFPR/L-11	20	16	15	200	11	40	TP1103	CH4R1C	CHX0414C	CR02C	-	-	HW25L
S20S-CTFPR/L-11	25	20	18	250	13	40							
S16R-CTFPR/L-16	20	16	15	200	11	40		CHEDEC	CHX0519C	CDOSC			
S20S-CTFPR/L-16	25	20	18	250	13	40		CHOROC	CHX0319C	CHUSC	-	-	
S25R-CTFPR/L-16	32	25	23	200	17	40	TP□□1603□□						HW30L
S32S-CTFPR/L-16	40	32	30	250	22	45		CH6R5	CHX0622C	CR04C	ST32C	SP3C	
S40T-CTFPR/L-16	50	40	37	300	27	60					31320	31 30	
S40T-CTFPR/L-22	50	40	37	300	27	60	TP□□2204□□	CH83R1	CH0823C	CR05C	ST43C	SP4C	HW40L


<sup>•</sup> Use left handed insert for right handed holder

<sup>◆</sup> Applicable inserts B90~B93

## MCLNR/L



CN



Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench	Fig.
S20S-MCLNR/L-09	25	20	18	200	13	32	CN□□0903□	CDH7N	DHA10/32-19		SP3D3	HW19.8L	2
S25R-MCLNR/L-09	32	25	23	250	17	40	CIN0903_	CDH/N	DHA10/32-19	-	35303	HW23.8L	3
S25R-MCLNR/L-12	32	25	23	200	17	40				-	SP4DS	1 114/04 01	
S32S-MCLNR/L-12	40	32	30	250	22	50	CN□□1204□	CDH6N	DHA1/4-21	SC43D	SP4D	HW31.8L HW23.8L	3
S40T-MCLNR/L-12	50	40	38	300	27	60				3043D	3F4D	11VV20.0L	
A25R-MCLNR/L-12	32	25	24	200	17	40	0 CN 1204	CDH6N	DHA1/4-21 -	-	SP4DS	HW31.8L	1
A32S-MCLNR/L-12	40	32	30	250	22	50		CDUOIA	DUN1/4-21	SC43D	SP4D	HW23.8L	3

Applicable inserts B36~B42

## MDUNR/L



 $\mathsf{DN}\square\square$ 

ØD Min. machining Dia.	Ød Ød	H Fig. 2 Fig. 3	93°
			• R type insert (mm)


Designation	ØD	Ød	Н	L	S	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench	Fig.
S32S-MDUNR/L-15-3	40	32	30	250	22	50						1 114/04 01	
S40T-MDUNR/L-15-3	50	40	38	300	27	60	DN□□1504□	CDH6N	DHA1/4-21	SD43D	SP4D	HW31.8L HW23.8L	3
A32S-MDUNR/L-15-3	40	32	30	250	22	50						11W25.0L	

<sup>◆</sup> Applicable inserts B43~B48

## MSKNR/L



 $SN\square\square$ 



													(mm)
Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench	Fig.
S25R-MSKNR/L-12	32	25	23	200	17	40				-	SP4DS		
S32S-MSKNR/L-12	40	32	30	250	22	50	SN□□1204□	CDH8N1	DHA5/16-28	SS43D	SP4D	- HW39.7L HW23.8L	3
S40T-MSKNR/L-12	50	40	38	300	27	60				3343D	3F4D	110020.0L	
A25R-MSKNR/L-12	32	25	23	200	17	40				-	SP4DS	- 1 114/00 71	1
A32S-MSKNR/L-12	40	32	30	250	22	50		CDH8N1	DHA5/16-28	SS43D	SP4D	HW39.7L HW23.8L	3
A40T-MSKNR/L-12	50	40	38	300	27	60				3343D	3F4D	114420.0L	


<sup>◆</sup> Applicable inserts B50~B57

# B Multi Lock System

#### MTFNR/L



 $\mathsf{TN} \square \square$ 



(mm) Clamp Screw Shim Shim Pin Wrench Fig. Designation ØD **M** Ød н L S Q Insert 6000m A S25R-MTFNR/L-16 CDH7N1 DHA10-32-19 SP3D3 32 25 23 200 17 40 HW23.8L S32S-MTFNR/L-16 40 32 30 250 22 50 TN 1604 3 CDH7N1 DHA10-32-19 ST32D SP3D HW19.8L S40T-MTFNR/L-16 50 40 38 300 27 60 A25R-MTFNR/L-16 32 25 24 200 17 40 CDH7N1 DHA10-32-19 SP3D3 HW23.8L TN 1604 A32S-MTFNR/L-16 32 30 250 22 50 CDH7N1 DHA10-32-19 ST32D SP3D HW19.8L 3

#### **MVUNR/L**



VN


OD Min. machining Dia.	Ød H Fig. 1	Ød Fig. 2	Ød H Fig. 3	93°
				• R type insert


(mm) Clamp Clamp Screw Shim Shim Pin Wrench Designation ØD Ød Н L S Q Insert Fig. 0000 S32S-MVUNR/L-16 40 32 30 250 22 50 HW39.7L SP3D VN□□1604□ CDH8N2 DHA5/16-28 SV32D 3 S40T-MVUNR/L-16 HW19.8L 50 38 300 27 60 40 A32S-MVUNR/L-16 40 30 250 32 22 50 HW39.7L SP3D 3 VN□□1604□ CDH8N2 DHA5/16-28 SV32D HW19.8L A40T-MVUNR/L-16 50 38 300 60 40 27


#### MWLNR/L



WN







• R type insert (mm)

													()
Designation	ØD	Ød	н	L	s	Q	Insert	Clamp	Clamp Screw	Shim	Shim Pin	Wrench	Fig.
S25R-MWLNR/L-06	32	25	23	200	17	40				-	SP3D3		
S32S-MWLNR/L-06	40	32	30	250	22	50	WN□□0604□	CDH7N	DHA10/32-19	SW32D	SP3D	HW23.8L HW19.8L	3
S40T-MWLNR/L-06	50	40	38	300	27	60				3W32D	3530	1100 TO.OL	
S25R-MWLNR/L-08	32	25	23	200	17	40				-	SP4DS	- 1 11404 01	
S32S-MWLNR/L-08	40	32	30	250	22	50		CDH6N	DHA1/4-21	SW43D	SP4D	HW31.8L HW23.8L	3
S40T-MWLNR/L-08	50	40	38	300	27	60				30043D	3F4D	114420.0L	
A25R-MWLNR/L-06	32	25	24	200	17	40	WNDD0604D	CDH7N	DHA10/32-19-	-	SP3D3	HW31.8L	1
A32S-MWLNR/L-06	40	32	31	250	22	50	WN 0604	CDH/N	ייות וטואביוט	SW32D	SP3D	HW19.8L	3
A25R-MWLNR/L-08	32	25	24	200	17	40	WN 0804	CDH6N	DHA1/4-21 -	-	SP4DS	HW31.8L	1
A32S-MWLNR/L-08	40	32	31	250	22	50		CDUQIA	DDA1/4-21	SW43D	SP4D	HW23.8L	3

<sup>→</sup> Applicable inserts B68~B72

Applicable inserts B58~B65


Applicable inserts B66~B67


## SCLCR/L



CC□T

# ØD Min. machining Dia.





• R type insert

#### Steel shank type

Designation	ØD	Ød	н	L	s	Q	Insert	Screw	Shim	Shim Screw	Wrench	Fig.
S08K-SCLCR/L-06	11	8	7.2	125	6	12		FTKA02555			TW07	
S10K-SCLCR/L-06	13	10	9	125	6	16						
S10M-SCLCR/L-06	13	10	9	150	6	16	CC□T0602□□	FTKA02565		_	TW07P	2
S12M-SCLCR/L-06	16	12	11	150	9	20		1 1KA02303	-	-	1 4407 F	
S16R-SCLCR/L-06	20	16	14	200	11	25						
S12M-SCLCR/L-09	16	12	11	150	9	20						
S16R-SCLCR/L-09	20	16	14	200	11	25	CC T09T3	FTGA03508	-	-	TW15P	2
S20S-SCLCR/L-09	25	20	18	250	13	32	0001091300					
S25R-SCLCR/L-09	32	25	23	200	17	40		FTGA03510			TW15P	3
S25R-SCLCR/L-12	32	25	23	200	17	40		FTGA0411F	-	-	TW15P	
S32S-SCLCR/L-12	40	32	30	250	22	50	CC□T1204□□	FTGA0411F	SC42S	SHXN0610F	HW40L	3
S40T-SCLCR/L-12	50	40	38	300	27	60		I IGAU4III	30423	SHANOOTOI	TW15P	
A08F-SCLCR/L-06	11	8	7.6	80	6	12		FTKA02555	-	-	TW07P	
A10H-SCLCR/L-06	13	10	9.5	100	7	16	CC□T0602□□	FTKA02565			TW07P	1
A12K-SCLCR/L-06	16	12	11.5	125	9	20		1 1KA02303			1 4407 F	
A12K-SCLCR/L-09	16	12	11.5	125	9	20						
A16M-SCLCR/L-09	20	16	15	150	11	25	CC T09T3	FTGA03508	-	-	TW15P	4
A20Q-SCLCR/L-09	25	20	19	180	13	32	0001091300					'
A25R-SCLCR/L-09	32	25	24	200	17	40		FTGA03510	-	-	TW15P	
A25R-SCLCR/L-12	32	25	24	200	17	40	CC T1204	FTGA0411F	-	-	TW15P	1
A32S-SCLCR/L-12	40	32	31	250	22	50	0001120400	FTGA0411F	SC42S	SHXN0610F	HW40L,TW15P	3

#### Carbide shank type


(mm)

Designation	ØD	Ød	н	L	s	Insert	Screw	Wrench	Fig.
C04G-SCLCR/L-03	5	4	3.8	90	2.5	- CC□T0301□□	FTNA01633	TW06P	
C05H-SCLCR/L-03	6	5	4.4	100	3		FINAUIOSS	1 4400F	_ 1
C06H-SCLCR/L-04	7	6	5.4	100	3.5	CC T0401	FTNA0238	TW06P	'
C07K-SCLCR/L-04	8	7	6.4	125	4	CC_10401	1 11NA0236	TVVOOF	
C08K-SCLCR/L-06	10	8	7	125	5		FTKA02555	TW07P	
C10K-SCLCR/L-06	12	10	9	125	6				
C10M-SCLCR/L-06	12	10	9	150	6	CC□T0602□□	FTKA02565	TW07P	
C12M-SCLCR/L-06	14	12	11	150	9		1 110 02505	1 440/1	
C12Q-SCLCR/L-06	14	12	11	180	9				
C12M-SCLCR/L-09	15	12	11	150	8				2
C12Q-SCLCR/L-09	15	12	11	180	8				
C16R-SCLCR/L-09	20	16	15	200	11	CC T09T3	FTGA03508	TW15P	
C16S-SCLCR/L-09	20	16	15	250	11	0001091300	1 TOA00000	144131	
C20R-SCLCR/L-09	25	20	18	200	13				
C20S-SCLCR/L-09	25	20	18	250	13				
C25T-SCLCR/L-12	32	25	23	300	17	CC□T1204□□	FTGA0411F	TW15P	
E06H-SCLCR/L-04	7	6	5.4	100	3.5		FTNA0238	TW06P	1
E07K-SCLCR/L-04	8	7	6.4	125	4	0001040100	111110200	1 4 4 0 0 1	
E08K-SCLCR/L-06	10	8	7	125	5		FTKA02555	TW07P	
E10K-SCLCR/L-06	12	10	9	125	6				
E10M-SCLCR/L-06	12	10	9	150	6	CC□T0602□□	FTKA02565	TW07P	
E12M-SCLCR/L-06	14	12	11	150	9		1 110 102505	144071	
E12Q-SCLCR/L-06	14	12	11	180	9				
E12M-SCLCR/L-09	15	12	11	150	8				2
E12Q-SCLCR/L-09	15	12	11	180	8				
E16R-SCLCR/L-09	20	16	15	200	11	CC TOOT3	FTGA03508	TW15P	
E16S-SCLCR/L-09	20	16	15	250	11		TTUAUUUU	144131	
E20R-SCLCR/L-09	25	20	18	200	13				
E20S-SCLCR/L-09	25	20	19	250	13				
E25T-SCLCR/L-12	32	25	23	300	17		FTGA0411F	TW15P	

# B Screw on System

## SCLPR/L





#### **ᢒ** Steel shank type

• R type insert (mm)

Designation	ØD	Ød	Н	L	s	Q	Insert	Screw	Wrench	Fig.
S10M-SCLPR/L-08	13	10	9	150	7	16	CP□T0802□□	FTNA0305	TW09P	2
S12M-SCLPR/L-08	16	12	11	150	9	20	CP   10002	FTNA0307	TW09P	7 4
S16N-SCLPR/L-09	20	16	14	160	11	25				
S16R-SCLPR/L-09	20	16	14	200	11	25	CP□T0903□□	FTNA0408	TW15P	2
S20N-SCLPR/L-09	25	20	18	160	13	32	OF 10903	FINAU400	TWISE	
S20S-SCLPR/L-09	25	20	18	250	13	32				3
A10H-SCLPR/L-08	12	10	9.65	100	6	-	CP□T0802□□	FTNA0305	TW09P	1
A12K-SCLPR/L-08	16	12	11.5	125	9	20	CP   10002	FTNA0307	TW09P	7 '
A16M-SCLPR/L-09	20	16	15.5	150	10	25	CP□T0903□□	FTNA0408	TW15P	1
A20Q-SCLPR/L-09	25	20	19	180	13	32	CF□10903□□	FINAU408	IVVIOP	3

#### Carbide shank type

(mm)

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
C10K-SCLPR/L-08	12	10	9	125	6	14.5		FTNA0305	TW09P	
C10M-SCLPR/L-08	12	10	9	150	6	14.5	CP□T0802□□	1 114A0303	1 44031	
C12M-SCLPR/L-08	15	12	11	150	7.5	14.7	01 10002	FTNA0306	TW09P	
C12Q-SCLPR/L-08	15	12	11	180	7.5	14.7		TTNA0300	1 44091	
C12M-SCLPR/L-09	15	12	11	150	8	14.4				2
C12Q-SCLPR/L-09	15	12	11	180	8	14.4				-
C16R-SCLPR/L-09	20	16	15	200	10	22.4	CP□T0903□□	FTNA0408	TW15P	
C16S-SCLPR/L-09	20	16	15	250	10	22.4	OF 10903	FINAU400	IWISE	
C20R-SCLPR/L-09	25	20	18	200	13	22.5				
C20S-SCLPR/L-09	25	20	18	250	13	22.5				
E10K-SCLPR/L-08	12	10	9	125	6	14.5				
E10M-SCLPR/L-08	12	10	9	150	6	14.5		FTNA0305	TW09P	
E12M-SCLPR/L-08	15	12	11	150	7.5	14.7	CP□T0802□□	FINAUSUS	1009F	
E12Q-SCLPR/L-08	15	12	11	180	7.5	14.7	OF 10002			
E12M-SCLPR/L-09	15	12	11	150	8	14.4		FTNA0407	TW09P	2
E12Q-SCLPR/L-09	15	12	11	180	8	14.4		FINAU407	1009P	2
E16R-SCLPR/L-09	20	16	15	200	10	22.4				
E16S-SCLPR/L-09	20	16	15	250	10	22.4	CP□T0903□□	ETNIA 0 4 0 0	TW45D	
E20R-SCLPR/L-09	25	20	18	200	13	22.5	CF_10903	FTNA0408 1	TW15P	
E20S-SCLPR/L-09	25	20	18	250	13	22.5				

<sup>→</sup> Applicable inserts B78

## SDQCR/L





# ØD Min. machining Dia. 107.5° • R type insert

#### **ᢒ** Steel shank type

Steel Shank typ	e					,				(mm)
Designation	ØD	Ød	н	L	S	Q	Insert	Screw	Wrench	Fig.
S10M-SDQCR/L-07	13	10	9	150	7	16		FTKA02555	TW07P	
S12M-SDQCR/L-07	16	12	11	150	9	20	DC□T0702□□	FTKA02565	TW07P	2
S16R-SDQCR/L-07	20	16	14	200	11	25		FTKA02303	TVVO/F	
S16R-SDQCR/L-11	20	16	14	200	11	25		FTGA03508	TW15P	2
S20S-SDQCR/L-11	25	20	18	250	13	32	DC□T11T3□□	FIGAUSSUO	IWISE	4
S25R-SDQCR/L-11	32	25	23	200	17	40		FTGA03510	TW15P	3
A10H-SDQCR/L-07	13	10	9.5	100	7	16	DC T0702	FTKA02555	TW07P	1
A12K-SDQCR/L-07	16	12	11.5	125	9	20	DC_10702	FTKA02565	TW07P	1
A16M-SDQCR/L-11	20	16	15	150	11	25		FTGA03508	TW15P	4
A20Q-SDQCR/L-11	25	20	19	180	13	32	DC□T11T3□□	F1GA03508	1 1 1 1 5 P	'
A25R-SDQCR/L-11	32	25	24	200	17	40		FTGA03510	TW15P	1

#### Carbide shank type

	71-									(mm)
Designation	ØD	Ød	н	L	S	Q	Insert	Screw	Wrench	Fig.
C08K-SDQCR/L-07	10	8	7	125	6	-		FTKA02555	TW07P	
C10K-SDQCR/L-07	13	10	9	125	7	14.0	DC□T0702□□	F1KA02555	TVVU/P	
C12M-SDQCR/L-07	16	12	11	150	9	14.0		FTKA02565	TW07P	
C16R-SDQCR/L-07	20	16	15	200	11	-		F1KA02303	10076	2
C16R-SDQCR/L-11	20	16	15	200	11	21.3				
C20R-SDQCR/L-11	25	20	18	200	13	24.0	DC□T11T3□□	FTGA03508	TW15P	
C20S-SDQCR/L-11	25	20	18	250	13	24.0				
E08K-SDQCR/L-07	10	8	7	125	6	-		FTKA02555	TW07P	
E10K-SDQCR/L-07	13	10	9	125	7	14.0	DC□T0702□□	FTRA02555	10076	
E12M-SDQCR/L-07	16	12	11	150	9	14.0		FTKA02565	TW07P	
E16R-SDQCR/L-07	20	16	15	200	11	-		FTKA02303	10076	2
E16R-SDQCR/L-11	20	16	15	200	11	21.3				
E20R-SDQCR/L-11	25	20	18	200	13	24.0	DC□T11T3□□	FTGA03508	TW15P	
E20S-SDQCR/L-11	25	20	19	250	13	24.0				

<sup>◆</sup> Applicable inserts B79~B82, B103

# B Screw on System

## SDUCR/L





## 

#### **ᢒ** Steel shank type

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
S10M-SDUCR/L-07	13	10	9	150	7	16		FTKA02555	TW07P	2
S12M-SDUCR/L-07	16	12	11	150	9	20	DC□T0702□□	FTKA02565	TW07P	2
S16R-SDUCR/L-07	20	16	14	200	11	25		F1KA02505	TWU/P	
S16R-SDUCR/L-11	20	16	14	200	11	25		FTGA03508	TW15P	2
S20S-SDUCR/L-11	25	20	18	250	13	32		FIGAUSSUO	100156	2
S25R-SDUCR/L-11	32	25	23	200	17	40		FTGA03510	TW15P	3
S32S-SDUCR/L-11	40	32	30	250	22	50		FIGAUSSIU	100156	3
A10H-SDUCR/L-07	13	10	9.5	100	7	16		FTKA02555	TW07P	1
A12K-SDUCR/L-07	16	12	11.5	125	9	20	DC□T0702□□	ETI/A00FCF	TW07P	1
A16M-SDUCR/L-07	20	16	15	150	11	25		FTKA02565	1 VVU/P	'
A20Q-SDUCR/L-11	25	20	19	180	13	32	DC T11T3	FTGA03508	TW15P	1
A25R-SDUCR/L-11	32	25	24	200	17	40		FTGA03510	TW15P	

#### • Carbide shank type


• Garbias Grianii	1)   0									(mm)
Designation	ØD	Ød	Н	L	s	Q	Insert	Screw	Wrench	Fig.
C10K-SDUCR/L-07	13	10	9	125	7	9.8		FTKA02555	TW07P	
C10M-SDUCR/L-07	13	10	9	150	7	9.8		FTRA02555	10076	
C12M-SDUCR/L-07	16	12	11	150	9	11.0	DC T0702			
C12Q-SDUCR/L-07	16	12	11	180	9	11.0	DOL10702	FTKA02565	TW07P	
C16R-SDUCR/L-07	20	16	15	200	11	-		F1KA02505	10076	
C16S-SDUCR/L-07	20	16	15	250	11	-				2
C16R-SDUCR/L-11	20	16	15	200	11	-				
C16S-SDUCR/L-11	20	16	15	250	11	-		FTGA03508	TW15P	
C20R-SDUCR/L-11	25	20	18	200	13	-	DC□T11T3□□	F1GA03508	IWISE	
C20S-SDUCR/L-11	25	20	18	250	13	-				
C25T-SDUCR/L-11	32	25	23	300	17	-		FTGA03510	TW15P	
E10K-SDUCR/L-07	13	10	9	125	7	9.8		FTKA02555	TW07P	
E10M-SDUCR/L-07	13	10	9	150	7	9.8		FTKA02555	10076	
E12M-SDUCR/L-07	16	12	11	150	9	11.0	DC T0702			
E12Q-SDUCR/L-07	16	12	11	180	9	11.0	DC_10702	FTKA02565	TW07P	
E16R-SDUCR/L-07	20	16	15	200	11	-		FTRA02303	10076	
E16S-SDUCR/L-07	20	16	15	250	11	-				2
E16R-SDUCR/L-11	20	16	15	200	11	-				
E16S-SDUCR/L-11	20	16	15	250	11	-		ETC A03500	TW15P	
E20R-SDUCR/L-11	25	20	18	200	13	-	DC□T11T3□□	FTGA03508	IVVIOP	
E20S-SDUCR/L-11	25	20	18	250	13	-				
E25T-SDUCR/L-11	32	25	23	300	17	-		FTGA03510	TW15P	


<sup>◆</sup> Applicable inserts B79~B82, B104


### SDZCR/L



 $DC \square T$ 







• R type insert (mm)


Designation	ØD	Ød	н	L	s	Q	f	Insert	Screw	Shim	Shim Screw	Wrench	Fig.
S16R-SDZCR/L-07	20	16	14	200	11	25	6.5	DC□T0702□□	FTKA02565	_		TW07P	2
S20S-SDZCR/L-07	25	20	18	250	13	32	7.5	DC_10/02	F1KA02303	-	-	10077	2
S25R-SDZCR/L-11	32	25	23	200	17	40	9		FTGA03510	-	-	TW15P	
S32S-SDZCR/L-11	40	32	30	250	22	50	11		FTGA03512	SD32S	SHXN0509F	TW15P,	3
S40T-SDZCR/L-11	50	40	38	300	27	60	11	DC T11T3 D	FIGAUSSIZ	30323	SHANUSUSE	HW35L	
A25R-SDZCR/L-11	32	25	24	200	17	40	9		FTGA03510	-	-	TW15P	1
A32S-SDZCR/L-11	40	32	30	250	22	50	11		FTGA03512	SD32S	SHXN0509F	TW15P, HW35L	3


<sup>→</sup> Applicable inserts B79~B82, B104


#### SSKCR/L



 $SC \square T$ 







• R type insert (mm)


Designation	ØD	Ød	н	L	S	Q	Insert	Screw	Shim	Shim Screw	Wrench	Fig.
S12M-SSKCR/L-09	16	12	11	150	9	20		FTGA03507	-	-	TW15P	
S16R-SSKCR/L-09	20	16	14	200	11	25	SC□T09T3□□	FTGA03508		_	TW15P	2
S20S-SSKCR/L-09	25	20	18	250	13	32		FIGAUSSUS	-	-	TWIDE	
S25R-SSKCR/L-12	32	25	23	200	17	40	SC□T1204□□	FTGA0411F	-	-	TW15P	3
S32S-SSKCR/L-12	40	32	30	250	22	50	30_11204	FTGA0411F	SS42S	SHXN0610F	TW15P, HW40L	<u> </u>
A12K-SSKCR/L-09	16	12	11.5	125	9	20		FTGA03507	-	-	TW15P	
A16M-SSKCR/L-09	20	16	15	150	11	25	SC□T09T3□□	FTGA03508	_	_	TW15P	4
A20Q-SSKCR/L-09	25	20	19	180	13	32		FIGAUSSUO	-	-	TWISE	'
A25R-SSKCR/L-12	32	25	24	200	17	40	SC□T1204□□	FTGA0411F	-	-	TW15P	
A32S-SSKCR/L-12	40	32	30	250	22	50	30_11204	FTGA0411F	SS42S	SFXN0610F	TW15P, HW40L	3


<sup>◆</sup> Applicable inserts B84, B106


#### SSKPR/L



SP□T







• R type insert

J	٣٠			
	(	'n	ηn	n)
	т			

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
S12M-SSKPR/L-09	16	12	11	150	9	20				
S16N-SSKPR/L-09	20	16	14	160	11	25				
S16R-SSKPR/L-09	20	16	14	200	11	25	SP□T09T3□□	FTNA0307	TW09P	2
S20N-SSKPR/L-09	25	20	18	160	13	32				
S20S-SSKPR/L-09	25	20	18	250	13	32				
A12K-SSKPR/L-09	16	12	11.5	125	9	20				
A16M-SSKPR/L-09	20	16	15	150	11	25	SP□T09T3□□	FTNA0307	TW09P	1
A20Q-SSKPR/L-09	25	20	19	180	13	32				

<sup>→</sup> Applicable inserts B85~B86


<sup>·</sup> Use left handed insert for right handed holder

# B Screw on System

## STFCR/L







#### **ᢒ** Steel shank type

Designation	ØD	Ød	н	L	s	Q	Insert	Screw	Shim	Shim Screw	Wrench	Fig.
S10M-STFCR/L-09	13	10	9	150	7	16	TC T0902	FTKA02206			TW06P	2
S12M-STFCR/L-09	16	12	11	150	9	20	1001090200	FINAUZZUU	-	-	TVVOOF	_
S12M-STFCR/L-11	16	12	11	150	9	20						
S16R-STFCR/L-11	20	16	14	200	11	25	TC□T1102□□	FTKA02565	-	-	TW07P	2
S20S-STFCR/L-11	25	20	18	250	13	32						
S20S-STFCR/L-16	25	20	18	250	13	32	TO TACTO D	ETC 400E40			TWACD	2
S25R-STFCR/L-16	32	25	23	200	17	40	TC□T16T3□□	FTGA03510	-	-	TW15P	3
S32S-STFCR/L-16	40	32	30	250	22	50	TO TACTO D	ETC 400E40	CTOOC	CLIVNIOCOOF	TM4CD LIMOCI	
S40T-STFCR/L-16	50	40	38	300	27	60	TC□T16T3□□	FTGA03512	ST32S	2HXIN0309F	TW15P, HW35L	3
A10H-STFCR/L-09	13	10	9.5	100	7	16	TOTTOOOOTT	ETI/ 400000			TWOCD	4
A12K-STFCR/L-09	16	12	11.5	125	9	20	TC□T0902□□	FTKA02206	-	-	TW06P	'
A12K-STFCR/L-11	16	12	11.5	125	9	20						
A16M-STFCR/L-11	20	16	15	150	11	25	TC□T1102□□	FTKA02565	-	-	TW07P	1
A20Q-STFCR/L-11	25	20	19	180	13	32						
A25R-STFCR/L-16	32	25	24	200	17	40	TO TACTO O	FTKA03510	-	-	TW15P	1
A32S-STFCR/L-16	40	32	30	250	22	50	TC□T16T3□□	FTGA03512	ST32S	SHXN0509F	TW15P, HW35L	3

#### Carbide shank type

										(mm)
Designation	ØD	Ød	н	L	s	Q	Insert	Screw	Wrench	Fig.
C08K-STFCR/L-09	10	8	7	125	5	-	TC T0902	FTKA02206	TW06P	
C10K-STFCR/L-09	12	10	9	125	6	14.0	1001090200	FINAU2200	IVVOOP	
C10K-STFCR/L-11	12	10	9	125	6	12.5				
C12M-STFCR/L-11	15	12	11	150	8	-				
C16R-STFCR/L-11	20	16	15	200	10	-	TC□T1102□□	FTKA02565	TW07P	
C20R-STFCR/L-11	25	20	18	200	13	23.0				2
C20S-STFCR/L-11	25	20	18	250	13	23.0				
C20R-STFCR/L-16	25	20	18	200	13	-	TC□T16T3□□	FTGA03510	TW15P	
C20S-STFCR/L-16	25	20	18	250	13	-	10_11013	FIGAUSSIU	TWISE	
E08K-STFCR/L-09	10	8	7	125	5	-	TC□T0902□□	FTKA02206	TW06P	
E10K-STFCR/L-09	12	10	9	125	6	14.0	1001090200	FINAUZZUU	TWOOF	
E10K-STFCR/L-11	12	10	9	125	6	12.5				
E12M-STFCR/L-11	15	12	11	150	8	-				
E16R-STFCR/L-11	20	16	15	200	11	-	TC□T1102□□	FTKA02565	TW07P	
E20R-STFCR/L-11	25	20	18	200	13	23.0				2
E20S-STFCR/L-11	25	20	18	250	13	23.0				
E20R-STFCR/L-16	25	20	18	200	13	-	TC T16T3	FTGA03510	TW15P	
E20S-STFCR/L-16	25	20	19	250	13	-	1001101300	FIGAUSSIU	IVVIOR	

<sup>◆</sup> Applicable inserts B88~B89, B107

## STFPR/L





# OD Min. machining Dia. Od Od Od Od Od PFig. 1 Fig. 2 Fig. 3 90° - R type insert (mm)

#### Steel shank type

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.	
S10M-STFPR/L-11	13	10	9	150	7	16		FTNA0306	TW09P	2	
S12M-STFPR/L-11	16	12	11	150	9	20	   TP□T1103□□				
S16N-STFPR/L-11	20	16	14	160	11	25		FTNA0307	TW09P	2	
S16R-STFPR/L-11	20	16	14	200	11	25					
S20N-STFPR/L-16	25	20	18	160	13	32	TP□T1604□□	FTNA0408	TW15P	2	
S20S-STFPR/L-16	25	20	18	250	13	32	IFL  1004L L	FTNAU400	IWISE	2	
A10H-STFPR/L-11	13	10	9.5	100	7	16		FTNA0306	TW09P	1	
A12K-STFPR/L-11	16	12	11	125	9	20	TP□T1103□□	FTNA0307	TW09P	1	
A16M-STFPR/L-11	20	16	15	150	11	25		FTINAU307	1 4409F	1	
A20Q-STFPR/L-16	25	20	19	180	13	32	TP□T1604□□	FTNA0408	TW15P	1	

#### Carbide shank type

	- 7   0									(mm)
Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
C08K-STFPR/L-08	10	8	7	125	5	13.7	TP□T0802□□	FTNA02205	TW06P	
C10K-STFPR/L-11	12	10	9	125	6	14.0		FTNA0305	TW09P	
C10M-STFPR/L-11	12	10	9	150	6	14.0		FINAUSUS	1 00091	
C12M-STFPR/L-11	15	12	11	150	8	-				
C12Q-STFPR/L-11	15	12	11	180	8	-	TP□T1103□□			
C16R-STFPR/L-11	20	16	15	200	10	-		FTNA0307	TW09P	2
C16S-STFPR/L-11	20	16	15	250	10	-		FINAUSU7	1 00091	2
C20R-STFPR/L-11	25	20	18	200	13	-				
C20S-STFPR/L-11	25	20	18	250	13	-				
C20R-STFPR/L-16	25	20	18	200	13	-				
C20S-STFPR/L-16	25	20	18	250	13	-	TP□T1604□□	FTNA0408	TW15P	
C25T-STFPR/L-16	32	25	23	300	17	23.5				
E08K-STFPR/L-08	10	8	7	125	5	13.7	TP□T0802□□	FTNA02205	TW06P	
E10K-STFPR/L-11	12	10	9	125	6	14.0		FTNA0305	TW09P	
E10M-STFPR/L-11	12	10	9	150	6	14.0		FINAUSUS	10095	
E12M-STFPR/L-11	15	12	11	150	8	-				
E12Q-STFPR/L-11	15	12	11	180	8	-	TP□T1103□□			
E16R-STFPR/L-11	20	16	15	200	10	-		FTNA0307	TW09P	2
E16S-STFPR/L-11	20	16	15	250	10	-		FINAUSU7	10095	2
E20R-STFPR/L-11	25	20	18	200	13	-				
E20S-STFPR/L-11	25	20	18	250	13	-				
E20R-STFPR/L-16	25	20	18	200	13	-				
E20S-STFPR/L-16	25	20	18	250	13	-	TP□T1604□□	FTNA0408	TW15P	
E25T-STFPR/L-16	32	25	23	300	17	23.5				

<sup>◆</sup> Applicable inserts B90~B93


<sup>•</sup> Use left handed insert for right handed holder

# B Screw on System

#### STWPR/L







										(mm)
Designation	ØD	Ød	н	L	s	Q	Insert	Screw	Wrench	Fig.
S10M-STWPR/L-11	13	10	7	150	7	16	TPGH1102□□	FTNA0305	TW09P	
S12M-STWPR/L-11	16	12	9	150	9	20	TD014400			
S16Q-STWPR/L-11	20	16	14	180	11	25	TPGH1103□□ TPMT1103□□	FTNA0306	TW09P	2
S20R-STWPR/L-11	25	20	18	200	13	32	1110111100			

<sup>◆</sup> Applicable inserts B90~B93





 $VC \square \square$ 

OD Min. machining Dia.	Ød	Ød	Ød
	H	H	H
	Fig. 1	Fig. 2	Fig. 3



• R type insert

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
S12M-SVJCR/L-08	16	12	11	150	2	26	VCMT0802□□	FTNA0204	TW06P	
S16Q-SVJCR/L-08	20	16	15	180	2	36	V CIVI I UOUZ	FTINAU2U4	1 44005	


<sup>◆</sup> Applicable inserts B97~B99, B109


## SVQBR/L



VB□T

OD Min. machining Dia.
108'





• R type insert (mm)


Designation	ØD	Ød	н	L	s	Q	Insert	Screw	Shim	Shim Screw	Wrench	Fig.
S32S-SVQBR/L-16	40	32	30	250	22	50					TWATER	
S40T-SVQBR/L-16	50	40	38	300	27	60	VB□T1604□□	FTGA03512	SV32S	SHXN0509F	TW15P HW35L	3
A32S-SVQBR/L-16	40	32	30	250	22	50					TIVVOOL	

<sup>→</sup> Applicable inserts B94~B96, B108

#### SVQCR/L




 $VC \square T$ 




Designation	ØD	Ød	н	L	s	Q	Insert	Screw	Shim	Shim Screw	Wrench	Fig.
S16R-SVQCR/L-11	20	16	14	200	11	25						2
S20S-SVQCR/L-11	25	20	18	250	13	32	VC□T1103□□	FTKA02565	-	-	TW07P	
S25R-SVQCR/L-11	32	25	23	200	17	40						3
S20S-SVQCR/L-13	25	20	18	250	13	32	VC□T1303□□	FTKA0307			TW07P	2
S25R-SVQCR/L-13	32	25	23	200	17	40	VC_11303	FINAUSUI	-	-	TVVO/F	3
S25R-SVQCR/L-16	32	25	23	200	17	40		FTGA03510	-	-	TW15P	
S32S-SVQCR/L-16	40	32	30	250	22	50	VC□T1604□□	FTGA03512	SV32S	SHXN0509F	TW15P	3
S40T-SVQCR/L-16	50	40	38	300	27	60		FIGAUSSIZ	3 7 3 2 3	SHANUSUSE	HW35L	

Applicable inserts B97~B99, B109



<sup>→</sup> Applicable inserts B94~B96, B108




Applicable inserts B97~B99, B109

# **B** Screw on System

## SWLCR/L








• R type insert (mm)


Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
S25R-SWLCR/L-08	32	25	23	200	17	40	WC□T0804□□	FTGA0411F	TW15P	3
S32S-SWLCR/L-08	40	32	30	250	22	50	WC_10004	FIGAU411F	IWISE	3
A25R-SWLCR/L-08	32	25	24	200	17	40	WC□T0804□□	FTGA0411F	TW15P	1
A32S-SWLCR/L-08	40	32	30	250	22	50	WC_10004	FIGAU411F	IWISE	3





**CCET** 





• R type insert (mm)

93°

• R type insert (mm)


Designation	ØD	Ød	Н	L	s	Q	Insert	Screw	Wrench
S10H-SCLCR/L-0305	5	10	9	100	2.5	25	CCET0301□□	FTNA01633	TW06P
S10H-SCLCR/L-0306	6	10	9	100	3.0	25	COETUSUILL	FINAUIOSS	IWUOF
S10J-SCLCR/L-0407	7	10	9	110	3.5	30	CCET0401□□	FTNA0238	TW06P
S10J-SCLCR/L-0408	8	10	9	110	4.0	30	CCE10401	FINAU238	1 00000

<sup>◆</sup> Applicable inserts B73 ~B77, B103

### STUBR/L



 $\mathsf{TB} \square \square$ 



#### Steel shank type

Designation	ØD	Ød	Н	L	s	Q	Insert	Screw	Wrench
S08K-STUBR/L-06	8	8	7	125	4	30	TB□□0601□□R/L	ETNIA0204	TWOCD
A08F-STUBR/L-06	8	8	7.5	80	4	30	TB□□0601□□R/L	FTNA0204	TW06P

#### Carbide shank type


• • • • • • • • • • • • • • • • • • •									(mm)
Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench
C08K-STUBR/L-06	10	8	7	125	5		TB□T0601□□	FTNA0204	TW06P
C10K-STUBR/L-06	12	10	9	125	6		16_10001	FTNA0204	I WOOF
E08K-STUBR/L-06	10	8	7	125	5		TB□T0601□□	FTNA0204	TW06P
E10K-STUBR/L-06	12	10	9	125	6		1001100	F1NA0204	I WOOF


Applicable inserts B87

### STLBR/L



ТВ□□





#### Steel shank type

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench
S06H-STLBR/L-06-SP	8	6	5	100	3.8	12	TB 0601 R/L	FTNA0204	TW06P

Applicable inserts B87

• R type insert (mm)

<sup>•</sup> Use left handed insert for right handed holder

<sup>•</sup> Use left handed insert for right handed holder


<sup>•</sup> Use left handed insert for right handed holder

# **B** Compact Mini

### STUPR/L







#### Steel shank type

• R type insert (mm)

Designation	ØD	Ød	Н	L	s	Q	Insert	Screw	Wrench	Fig.
S08K-STUPR/L-08	10	8	7	125	4	18	TP□□0802□□R/L	ETNIAGOOGE	TW06P	
A08F-STUPR/L-08	10	8	7.5	80	5	18	IPUU0802UUR/L	FTNA02205 T	TVVOOP	

#### Carbide shank type

\ /
-----

Designation	ØD	Ød	н	L	S	Q	Insert	Screw	Wrench	Fig.
C08K-STUPR/L-08	10	8	7	125	5		TP□T0802□□	FTNA02205	TW06P	
C10K-STUPR/L-11	12	10	9	125	6			FTNA0305	TW09P	
C10M-STUPR/L-11	12	10	9	150	6		TP□T1103□□	FINAUSUS	1 4409P	
C12M-STUPR/L-11	15	12	11	150	8					
C12Q-STUPR/L-11	15	12	11	180	8					
C16R-STUPR/L-11	20	16	15	200	10			FTNA0307	TW09P	,
C16S-STUPR/L-11	20	16	15	250	10			1 11VA0307	10099	2
C20R-STUPR/L-11	25	20	18	200	13					
C20S-STUPR/L-11	25	20	18	250	13					
C20R-STUPR/L-16	25	20	18	200	13		TP□T1604□□  TP□T0802□□	FTNA0408	TW15P	
C20S-STUPR/L-16	25	20	18	250	13					
C25T-STUPR/L-16	32	25	23	300	17					
E08K-STUPR/L-08	10	8	7	125	5			FTNA02205	TW06P	
E10K-STUPR/L-11	12	10	9	125	6		- TP□T1103□□	FTNA0305 TW09P	TWOOD	2
E10M-STUPR/L-11	12	10	9	150	6				1009P	
E12M-STUPR/L-11	15	12	11	150	8				TWOOD	
E12Q-STUPR/L-11	15	12	11	180	8					
E16R-STUPR/L-11	20	16	15	200	10					
E16S-STUPR/L-11	20	16	15	250	10				1 44091	
E20R-STUPR/L-11	25	20	18	200	13					
E20S-STUPR/L-11	25	20	18	250	13					
E20R-STUPR/L-16	25	20	18	200	13					
E20S-STUPR/L-16	25	20	18	250	13		TP□T1604□□	FTNA0408	TW15P	
E25T-STUPR/L-16	32	25	23	300	17					


<sup>◆</sup> Applicable inserts B90~B93

 $<sup>\</sup>bullet$  Use left handed insert for right handed holder

### SWUBR/L



 $WB \square T$ 



#### Steel shank type

• R type insert (mm)

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
S05H-SWUBR/L-02	5.5	5	4.5	100	2.75	-	WBGT0201□□R/L	FTNA0203	TW06P	
S08K-SWUBR/L-02	8	8	7	125	4	30	WDG10201H/L	FTNA02033	TVVOOF	
S08K-SWUBR/L-S3	10	8	7	125	5	18	WBGTS302□□R/L	FTNA02205	TW06P	2
A08F-SWUBR/L-02	8	8	7.5	80	4	30	WBGT0201□□R/L	FTNA0203	TW06P	
A08F-SWUBR/L-S3	10	8	7.5	80	5	16	WBGTS302□□R/L	FTNA02205	TW06P	

#### Carbide shank type

(mm)

Designation	ØD	Ød	Н	L	S	Q	Insert	Screw	Wrench	Fig.
C05H-SWUBR/L-02	6	5	4.4	100	3	-		FTNA0203	TW06P	
C06H-SWUBR/L-02	7	6	5.4	100	3.5	-	WB□T0201□□	FTNAU203	1 0000	'
C08K-SWUBR/L-02	9	8	7	125	4.5	-		FTNA02033	TW06P	
C08K-SWUBR/L-S3	10	8	7	125	4.5	-	WB□TS301□□	FTNA02205	TW06P	2
E06H-SWUBR/L-02	7	6	5.4	100	3.5	-	WB□T0201□□	FTNA0203	TW06P	1
E08K-SWUBR/L-02	9	8	7	125	4.5	-	WDL10201LL	FTNA02033	TW06P	
E08K-SWUBR/L-S3	10	8	7	125	5	-	WB□TS301□□	FTNA02205	TW06P	2

<sup>◆</sup> Applicable inserts B101




\* See page B151 for applicable sleeves

<sup>•</sup> Use left handed insert for right handed holder


2 sides restraint - side and taper part

### HSK Tooling System [For Multi-task Machines]

- 2 sides restraint side and taper part
- Toughness guaranteed for static and dynamic movements
- Precision guaranteed on shaft and repeat directions
- Suitable at high speeds
- Suitable for small work pieces
- Coolant Nozzle is easily adjustable








#### ICTM (Interface committee for turning mill)

· Interface for Multi-task machines turning tool, which is tooling system based on ICTM standard from 17 major japanese companies cooperation and is compatible with conventional HSK-A type and common to Multi-task machines and machining centers

#### **○** Tolerance of keyway has been improved: HSK-T63




#### Tolerance comparison (Example)

		(11111)
Remarks	Maximum Tolerance	Minimum Tolerance
ICTM STANDARD HSK-T63	0.075	0.035
ISO STANDARD HSK-A63	0.33	0.08

#### 3 Face Binding - Superior precision

## KM Tooling System [For Multi-task Machines]

- 3 Face binding/Superior precision
- Flexible clamping system/Superior rigidity
- Various size & style
- Appropriate for turning & milling
- Adjustable coolant direction with coolant nozzle



#### Code system

C: 80° Diamond D: 55° Diamond S: 90° Square T: 60° Triangle V: 35° Diamond W: 80° Hexagon

 $N = 0^{\circ}$  $B = 5^{\circ}$ 

DX: 65 H: 100 L: 140

Clearance angle **Insert Shape** of insert

Length of tool holder



#### Taper design & size


50, 63UT 80ATC, 100

#### **Clamping Type**

D: Double Clamp M: Multi Clamp

P: Lever Lock


S: Screw On W: Wedge Clamp



#### Hand

R: Right L: Left

N: No Hand










#### Multi-tasking machine



### KM Tooling system is superior for wide application.

**External Process Internal Process**  **Grooving Process** 

**Drill Process** 

**Parting-off Process** 

KM50, KM63UT, KM80, KM100 Standard and Special type can be produced.



# B Index for HSK/KM Tooling System

### **Index for HSK Tooling System**

Designation         H63T-DCLNR/L-DX12         H63T-DCMNN-H/L12         H63T-DDJNR/L-DX12           Approach angle         95°         95°         93°           Page         B231         B231         B231           Turning         ●         ●         ●		4			
Page         B231         B231         B231	-DX15 H63T-DDNNN-H/L15	H63T-PCLNR/L-DX12	H63T-PCMNN-H/L12	H63T-PDJNR/L-DX15	H63T-PDNNN-H/L15
	107.5°	95°	95°	93°	107.5°
Turning • •	B231	B232	B232	B232	B232
	•	•	•	•	•
Copying	•			•	•
Facing • •	•	•	•	•	•
Back turning	•	•	•	•	•
Internal turning					

Cutting Shape						1		
Designation	H63T-PRGCR-DX12	H63T-PRDCN-H/L12	H63T-SVPBR/L-DX16	H63T-SVVBN-H/L16	H63T-A25K/A32L-DCLNR/L-12	H63T-MCFR/L	H63T-MCHR/L	
Approach angle	-	-	117.5°	117.5°	95°	-	-	
Page	B233	B233	B233	B233	B235	B235	B234	
Turning	•	•	•	•	•	•		
Copying	•	•	•	•		•		
Facing	•	•	•	•	•	•	•	
Back turning	•	•	•	•	•			
Internal turning					•			

## Index for KM Tooling System


Cutting Shape	1	+			47	***
Designation	KM50-DCLNR/L-C12 KM63UT-DCLNR/L-D12	KM50-DCMNN-C12 KM63UT-DCMNN-D12	KM50-DDJNR/L-C15(-3) KM63UT-DCJNR/L-D15(-3)	KM50-DDNNN-C15(-3) KM63UT-DDNNN-D15(-3)	KM50-A25K-DCLNR/L-12 KM50-A32K-DCLNR/L-12 KM63UT-A25K-DCLNR/L-12 KM63UT-A32L-DCLNR/L-12	KM50-PCLNR/L-C12 KM63UT-PCLNR/L-D12
Approach angle	95°	95°	93°	107.5°	95°	95°
Page	B237	B237	B237	B238	B240	B238
Turning	•	•	•	•	•	•
Copying			•	•		
Facing	•	•	•	•	•	•
Back turning	•	•	•	•	•	•
Internal turning					•	
Cutting Shape	<b>*</b>					
Designation	KM50-PCMNN-C12 KM63UT-PCMNN-D12	KM50-PDJNR/L-C15(-3) KM63UT-PDJNR/L-D15(-3)	KM50-PDNNN-C15(-3) KM63UT-PDNNN-D15(-3)	KM50-MCHR/L KM63UT-MCHR/L		
Approach angle	95°	93°	107.5°	-		
Page	B238	B239	B239	B239		
Turning	•	•	•	•		
Copying		•	•	•		
Facing	•	•	•			

Back turning Internal turning

### DCLNR/L



CN





95°

• R type insert


	Designation	L	s	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench	Coolant Pipe
Н	63T-DCLNR/L-DX12	65	45	CN1204	CVH4	CHX0518	SC44V	FTKA0410	SPR0714	CN0605	-	HW30P	CP63T


<sup>◆</sup> Applicable inserts B36~B42

### **DCMNN**



CN





(mm)
Coolant Pipe


Designation	L	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench	Coolant Pipe
H63T-DCMNN-H12	100	CN□□1204□□	CVH4	CHX0518	SC44V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P	CP63T
H63T-DCMNN-L12	140	CN□□1204□□	CVH4	CUV0210	3044V	FINAU410	3FN0/14	CNUOUS	NHAU0U0	HWOUP	CPOST


<sup>→</sup> Applicable inserts B36~B42

### DDJNR/L



 $\mathsf{DN}\square\square$ 







93°

· R type insert

Designation	L	s	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench	Coolant Pipe
H63T-DDJNR/L-DX15	65	45	DN 1506	CVH4	CHX0518	SD43V	- FTKA0410	SPR0714	CN0605		HW30P	CP63T
H63T-DDJNR/L-DX15-3	65	45	DN 1504	UV114	CHV0010	SD44V	- F1NA0410	3FN0/14	CINODOS	-	HVVOUP	UF 03 I


Applicable inserts B43~B48

### **DDNNN**



 $\mathsf{DN} \square \square$ 







107.5°


											(mm)
Designation	L	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench	Coolant Pipe
H63T-DDNNN-H15	100	DN 1506	CVH4	CHX0518	SD43V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P	CP63T
H63T-DDNNN-L15	140	DN1500	CVII4	CHAUSTO	3D43V	FINAU410	3FN0/14	CINUOUS	KHAUOUO	ПИУЗОГ	CF031
H63T-DDNNN-H15-3	100	DN□□1504□□	CVH4	CHX0518	SD44V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P	CP63T
H63T-DDNNN-L15-3	140		UVN4	OHV0310	3D44V	FINAU410	3FN0/14	CINODOS	NHAU0U0	HWOOF	UF031

<sup>◆</sup> Applicable inserts B43~B48

### PCLNR/L



CN





95°

٠R	type	insert
	- 1	mm)


Designation	L	s	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench	Coolant Pipe
H63T-PCLNR/L-DX12	65	45	CN□□1204□□	LV4N	VHX0820N	SC42N	SP4N	LSPS4	CN0605	-	HW30L	CP63T

<sup>→</sup> Applicable inserts B36~B42

### **PCMNN**



CN





95°


											(mm)
Designation	L	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench	Coolant Pipe
H63T-PCMNN-H12	100	CN 1204	LV4N	VHX0820N	SC42N	SP4N	LSPS4	CN0605	KHA0808	HW30L	CP63T
H63T-PCMNN-L12	140	CIN1204	LV4IN	VIIAU0ZUIN	3042N	OF4IN	LOF04	CINODOS	NHAU0U0	HWYSUL	OF031

<sup>→</sup> Applicable inserts B36~B42

### PDJNR/L



 $\mathsf{DN} \square \square$ 





95°

· R type insert (mm)


Designation	L	s	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench	Coolant Pipe
H63T-PDJNR/L-DX15	65	45	DN 1506	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	CN0605		HW30L	CP63T
H63T-PDJNR/L-DX15-3	65	45	DN□□1504□□	LV4DIN	VIIAU021IV	SD43N	SF4IN	LOPO4	CINODOS	-	HVVSUL	CF031

Applicable inserts B43~B48

### **PDNNN**



 $\mathsf{DN} \square \square$ 






107.5°

(mm)

Designation	L	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench	Coolant Pipe
H63T-PDNNN-H15	100	DN 1506	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	CN0605	KHA0808	HW30L	CP63T
H63T-PDNNN-L15	140	DINLLISUOLL	LV4DIN	VIIAU02 IIV	SD4ZIV	SF4IN	LSF34	CINODOS	NHAU0U0	HVVSUL	CF031
H63T-PDNNN-H15-3	100	DN□□1504□□	LV4BN	VHX0821N	SD43N	SP4N	LSPS4	CN0605	KHA0808	HW30L	CP63T
LICOT DONNIN LAF O	140		LV4DIV	VIIVOS IIV	3D43N	3F4N	L3F34	CINODOS	NHAU0U0	HVVJUL	OF 03 I

140




H63T-PDNNN-L15-3



### PRGCR/L



RCMX1204M0





• R type insert (mm)


Designation	L	s	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench	Coolant Pipe
H63T-PRGCR/L-DX12	65	45	RCMX1204M0	LR12	VHX0617	SR12	SP3	LSPS3	CN0605	-	HW25L	CP63T


Applicable inserts B83, B105

### **PRDCN**



RCMX1204M0








							' '					(mm)
Designation	L	α°	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench	Coolant Pipe
H63T-PRDCN-H12	100	69	RCMX1204M0	LR12	VHX0617	SR12	SP3	LSPS3	CN0605		HW25L	CP63T
H63T-PRDCN-L12	140	75	HOIVIA 1204IVIU	LNIZ	VIIVOOI	SHIZ	353	LOFOO	CNUOUS	-	HWZJL	CFOST


→ Applicable inserts B83, B105

### SVPBR/L



 $\mathsf{VB} \square \mathsf{T}$ 







117.5°

• R type insert (mm)


Designation	L	s	Insert	Screw	Shim Screw	Shim	Nozzle	Plug	Wrench	Wrench	Coolant Pipe
H63T-SVPBR/L-DX16	65	45	VB□T1604□□	FTGA03512	SHXN0509F	SV32S	CN0605	-	TW15P	HW32L	CP63T

◆ Applicable inserts B94~B96, B108

### **SVVBN**



 $\mathsf{VB} \square \mathsf{T}$ 





117.5°


											(mm)
Designation	L	α°	Insert	Screw	Shim Screw	Shim	Nozzle	Plug	Wrench	Wrench	Coolant Pipe
H63T-SVVBN-H16	100	66.5	VB□T1604□□	FTGA03512	SHXN0509F	SV32S	CN0605	KHA0808	TW15P	HW32L	CP63T
H63T-SVVBN-L16	140	72.5	VB_11004	FIGAUSSIZ	SHAMOOUSE	37323	CINUOUS	KIIAUOUO	IWISE	HWVJZL	CFOST

◆ Applicable inserts B94~B96, B108

# **B** HSK Tooling System

### MCHR/L












Designation	L	t	W	Т-мах	Insert	Cartridge	Clamp	Clamp Screw	Hinge Screw	Screw	Nozzle	Plug	Wrench	Coolant Pipe
H63T-MCHR/L	85	18	3	16	MGMN	MCER/L3-T16								
	85	18	4	16	MGMR/L	MCER/L4-T16	- CHX8N	N DHA0818F RHA	DIIAOC10	0613 EHGA0619	CNOGOE		1114/401	CDCOT
	89	22	5	20	MGGN	MCER/L5-T20			F RHA0613	FHGAU618	CN0605	-	HW40L	CP63T
	89	22	6	20	MRMN	MCER/L6-T20								

## MCER/L (Cartridge)



MGMN / MGMR/L MGGN / MRMN



• R type insert (mm)


	Decimation		1.	S <sub>1</sub>	T-MAX	ı	nsert	Tool holders
	Designation	L	L1	51	I-WAX	W	Designation	1001 Holders
MCER/L	3-T16	6.00	44.5	6.35	16	3	MGMN	
	4-T16	5.97	44.5	6.35	16	4	MGMR/L	H63T-MCHR/L
	5-T20	5.87	48.5	6.35	20	5	MGGN	HO3 I-MCHR/L
	6-T20	5.82	48.5	6.35	20	6	MGMN	

<sup>→</sup> Applicable inserts C28~C30

### MCHR/L



MFMN300 MGMN400






• R type insert (mm)

							(1111
Designation	L	t	W	T-MAX	Insert	Cartridge	Clamp Clamp Screw Hinge Screw Screw Nozzle Plug Wrench Coolant P
H63T-MCHR/L	85	18	3	16		MCFR/L3-24/35-T16	
	85	18	3	16		MCFR/L3-29/40-T16	
	85	18	3	16	MFMN300	MCFR/L3-34/50-T16	
	85	18	3	16		MCFR/L3-44/70-T16	   CHX8N DHA0818F RHA0613 FHGA0618 CN0605 - HW40L
	85	18	3	16		MCFR/L3-64/99-T16	CHAON DHAU010F NHAU013 FHIGAU010 CHOOUS - HW40L
	85	18	3	16		MCFR/L4-44/60-T16	
	85	18	3	16	MGMN400	MCFR/L4-60/120-T16	
	85	18	3	16		MCFR/L4-112/200-T16	

## MCFR/L (Cartridge)





• R type insert (mm)

	leeismetien	_	1.	S <sub>1</sub>	T-MAX	I	nsert	Tool holders
U	esignation	'	L <sub>1</sub>	31	I-WAX	W	Designation	1001 flolders
MCFR/L3-	24/35-T16	8.00	44.5	6.35	16	3		
	29/40-T16	8.00	44.5	6.35	16	3		
	34/50-T16	8.00	44.5	6.35	16	3	MFMN300	
	44/70-T16	8.00	44.5	6.35	16	3		LICOT MOUD/I
	64/99-T16	8.00	44.5	6.35	16	3		H63T-MCHR/L
MCFR/L4-	44/60-T16	7.97	44.5	6.35	16	4		
	60/120-T16	7.97	44.5	6.35	16	4	MGMN400	
	112/200-T16	7.97	44.5	6.35	16	4		


<sup>→</sup> Applicable inserts C28~C30

### DCLNR/L












95°


• R type insert (mm)

Designation	ØD	Ød	L	L <sub>1</sub>	s	Insert	Clamp	Screw	Shim		Spring	Nozzle	Plug	Wrench	Coolant Pipe
H63T-A25K-DCLNR/L-12	32	25	125	80	17	CN□□1204□□	CVH4	CHX0518	00401/	FTKA0410	0000744	CNIOCOE		LIMOOD	CDCOT
H63T-A32L-DCLNR/L-12	40	32	140	98	22	CN1204	CVH4	CHXU318	3042V	FINAU410	5PHU/14	CINUOUS	-	HW30P	CP63T

<sup>→</sup> Applicable inserts B36~B42

### **Blank Tool**






(	r	ľ	١	ľ	Υ	

				(11111)
Designation	ØD	L	Fig.	Coolant Pipe
HSK-T63-BL62-102	62	102	1	
HSK-T63-BL62-142	62	142	2	CP63T
HSK-T63-BL100-67	100	67	1	05031
HSK-T63-BL120-70	120	70	2	




### EV2525R/L-112



Designation	L	L <sub>1</sub>	L <sub>2</sub>	Н	h <sub>1</sub>	h <sub>2</sub>	s	S <sub>1</sub>	<b>b</b> 1	b <sub>2</sub>	Screw	Plug	Nozzle	Wrench	Coolant Pipe
EV2525R/L-112	150	112	77	25	32	53	45	12.75	37.75	32	KHA1231	KHA0808	CN0605	HW50L	CP63T

### EV2525R/L-115



#### · Holder information

- Holder size: 25 x 25
- Holder Size. 25 x 25
   Before setting the holder,
  please cut the holder length to 110 mm.




R	type	inse

(mm)

Designation	L	L <sub>1</sub>	L <sub>2</sub>	Н	h <sub>1</sub>	h <sub>2</sub>	<b>b</b> 1	<b>b</b> 2	Screw	Plug	Nozzle	Wrench	Coolant Pipe
EV2525R/L-115	115	40	110	25	32	53	45	45	KHA1231	KHA0808	CN0605	HW50L	CP63T

### EV2020R/L-105-3






- Before setting the holder, please cut the holder length to 105 mm.



 R type insert (mm)

	Designation	L	L <sub>1</sub>	L <sub>2</sub>	н	ØD	s	<b>S</b> 1	B <sub>1</sub>	Screw	Plug	Nozzle	Wrench	Coolant Pipe
E	EV2020R/L-105-3	140	105	70	20	90	40	15	35	KHA1231	KHA0808	CN0605	HW50L	CP63T






· R type insert

Designation	ØD	D1	L	L <sub>1</sub>	М	Screw	Wrench	Coolant Pipe
B08-65	28	8	65	40	M8			
B10-70	35	10	70	45	M8			
B12-70	42	12	70	45	M8			
B16-75	48	16	75	50	M10	KHA1218	HW50L	CP63T
B20-75	52	20	75	50	M10	KHAIZIO	HWOOL	CF631
B25-83	62	25	83	58	M12			
B32-87	62	32	87	62	M12			
B40-97	65	40	97	72	M16			

## DCLNR/L



CN





95°

• R type insert

Designation	L	s	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench
KM50-DCLNR/L-C12	50	35	CN□□1204□□	CVH4	CHX0518	SC44V	FTKA0410	SPR0714	CN0605		HW30P
KM63UT-DCLNR/L-D12	60	43		CVH4	CUV0219	3044V	FINAU410	3FN0/14	CINUOUS	-	пилоп

<sup>◆</sup> Applicable inserts B36~B42

## **DCMNN**



CN□□







95


										(mm)
Designation	L	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench
KM50-DCMNN-C12	50	CN□□1204□□	CVH4	CHX0518	SC44V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P
KM63UT-DCMNN-D12	60		UV114	OUVOOLO	3044V	FINAU410	3FN0/14	CINODOS	NHAU0U0	HWYSUF

<sup>◆</sup> Applicable inserts B36~B42

### DDJNR/L



 $\mathsf{DN} \square \square$ 







93°

• R type insert

Designation	L	s	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench
KM50-DDJNR/L-C15	50	35	DN□□1506□□	CVH4	CHX0518	SD43V	FTKA0410	SPR0714	CN0605	-	HW30P
KM50-DDJNR/L-C15-3	50	35	DN□□1504□□	CVH4	CHX0518	SD44V	FTKA0410	SPR0714	CN0605	-	HW30P
KM63UT-DDJNR/L-D15	60	43	DN□□1506□□	CVH4	CHX0518	SD43V	FTKA0410	SPR0714	CN0605	-	HW30P
KM63UT-DDJNR/L-D15-3	60	43	DN□□1504□□	CVH4	CHX0518	SD44V	FTKA0410	SPR0714	CN0605	-	HW30P

Applicable inserts B43~B48

# **B** KM Tooling System

### **DDNNN**













117.5°

(mm)


Designation	L	Insert	Clamp	Screw	Shim	Shim Screw	Spring	Nozzle	Plug	Wrench
KM50-DDNNN-C15	50	DN□□1506□□	CVH4	CHX0518	SD43V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P
KM50-DDNNN-C15-3	50	DN□□1504□□	CVH4	CHX0518	SD44V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P
KM63UT-DDNNN-D15	60	DN□□1506□□	CVH4	CHX0518	SD43V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P
KM63UT-DDNNN-D15-3	60	DN□□1504□□	CVH4	CHX0518	SD44V	FTKA0410	SPR0714	CN0605	KHA0808	HW30P

<sup>◆</sup> Applicable inserts B43~B48

## PCLNR/L



CN





95°

• R type insert (mm)

Designation	L	s	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench
KM50-PCLNR/L-C12	50	35	CN□□1204□□	LV4N	VHX0820N	SC42N	SP4N	LSPS4	CN0605		HW30L
KM63UT-PCLNR/L-D12	60	43	CN1204	LV4IN	VIIAU0ZUIN	3042N	SF4N	LSF34	CINUOUS		HVVSUL


<sup>●</sup> Applicable inserts B36~B42

### **PCMNN**



CN







95°


Designation	L	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench
KM50-PCMNN-C12	50	CN□□1204□□	LV4N	VHX0820N	SC42N	SP4N	LSPS4	CN0605	KHA0808	HW30L
KM63UT-PCMNN-D12	60		LV4IN	VIIAU0ZUIN	3042N	SF4IN	LOF 34	CINUOUS	NHAU0U0	HVVSUL

<sup>●</sup> Applicable inserts B36~B42

### PDJNR/L









93°

• R type insert (mm)


Designation	L	s	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench
KM50-PDJNR/L-C15	50	35	DN□□1506□□	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	CN0605	-	HW30L
KM50-PDJNR/L-C15-3	50	35	DN□□1504□□	LV4BN	VHX0821N	SD43N	SP4N	LSPS4	CN0605	-	HW30L
KM63UT-PDJNR/L-D15	60	43	DN□□1506□□	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	CN0605	-	HW30L
KM63UT-PDJNR/L-D15-3	60	43	DN 1504	LV4BN	VHX0821N	SD43N	SP4N	LSPS4	CN0605	-	HW30L

<sup>→</sup> Applicable inserts B43~B48

### **PDNNN**



 $\mathsf{DN}\square\square$ 





107.5°

(mm)


Designation	L	Insert	Lever	Screw	Shim	Shim Pin	Punching	Nozzle	Plug	Wrench
KM50-PDNNN-C15	50	DN□□1506□□	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	CN0605	KHA0808	HW30L
KM50-PDNNN-C15-3	50	DN 1504	LV4BN	VHX0821N	SD43N	SP4N	LSPS4	CN0605	KHA0808	HW30L
KM63UT-PDNNN-D15	60	DN□□1506□□	LV4BN	VHX0821N	SD42N	SP4N	LSPS4	CN0605	KHA0808	HW30L
KM63UT-PDNNN-D15-3	60	DN 1504	LV4BN	VHX0821N	SD43N	SP4N	LSPS4	CN0605	KHA0808	HW30L

<sup>→</sup> Applicable inserts B43~B48

### MCHR/L



MGMN / MGMR/L MGGN / MRMN





• R type insert (mm)


	Designation	s	L	t	W	T-MAX	Insert	Cartridge	Clamp	Clamp Screw	Hinge Screw	Screw	Nozzle	Plug	Wrench
		35	72.5	18	3	16		MCER/L3-T16							
	KM50-MCHR/L	35	72.5	18	4	16		MCER/L4-T16	CHX8N	DHA0818F	RHA0613	FHGA0618	CN0605	-	HW40L
	KIVIOU-IVICHIA/L	35	76.5	22	5	20	MGMN	MCER/L5-T20	CHAON	DUANOIOL	HHAU013	FNGA0010	CNUOUS	-	⊓W4UL
		35	76.5	22	6	20	MGMR/L	MCER/L6-T20							
		43	81.5	18	3	16	MGGN	MCER/L3-T16							
	MESTIT MCHD/I	43	81.5	18	4	16	MRMN	MCER/L4-T16	CHX8N	DHA0818F	RHA0613	FHGA0618	CN0605	-	HW40L
		43	85.5	22	5	20		MCER/L5-T20	CHAON	DHAUGIGE	HIAUUIS	FIIGAUUTO	CINUOUS	-	HW4UL
		43	85.5	22	6	20		MCER/L6-T20							

<sup>◆</sup> Applicable inserts C28~C30

# **B** KM Tooling System

### MCER/L (Cartridge)





• R type insert (mm)


	Decimation	-	L	S <sub>1</sub>	T-MAX	I	nsert	Tool holders
	Designation	'	L1	31	I-WAX	W	Designation	1001 noiders
MCER/L	3-T16	6.00	44.5	6.35	16	3	MGMN	
	4-T16	5.97	44.5	6.35	16	4	MGMR/L	H-63T-MCHR/L
	5-T20	5.87	48.5	6.35	20	5	MGGN	H-03 I-WCHH/L
	6-T20	5.82	48.5	6.35	20	6	MRMN	

<sup>→</sup> Applicable inserts C28~ C30





CN







• R type insert

														, (mm)
Designation	ØD	Ød	L	L <sub>1</sub>	s	Insert	Clamp	Screw		Shim Screw	Spring	Nozzle	Plug	Wrench
KM50-A25K-DCLNR/L-12	32	25	125	80	17									
KM50-A32L-DCLNR/L-12	40	32	140	98	22	CN□□1204□□	CVH4	CLIVOE40	004014	FTKA0410	SPR0714	CN0605		HW30P
KM63UT-A25K-DCLNR/L-12	32	25	125	80	17	CINLL 1204LL	CVH4	CHXU318	3042V	FINAU410	5PH0/14	CINODOS	-	HW30P
KM63UT-A32L-DCLNR/L-12	40	32	140	98	22									

<sup>◆</sup> Applicable inserts B36~B42


### **Blank Tool**








(mm)


Designation	ØD	L	Ød	Fig.
KM50-BL7562	45	62	50	1
KM50-BL10562	105	62	50	2
KM63UT-BL65200	65	200	50	1
KM63UT-BL115150	115	150	50	2

























# **B** Index for Cartridge


		Cutting Shape		Turning	Copying	Facing	Chamfering	Applicable inserts	Page
	CSKPR/L		10CA-09 12CA-12	•				SP□R0903□□ SP□R1203□□	B243
Ľ	CTTPR/L		10CA-11 12CA-16	•				TP□R1103□□ TP□R1603□□	B244
Clamp on System	CTWPR/L		10CA-11 12CA-16	•				TP□R1103□□ TP□R1603□□	B245
S	CTFPR/L		10CA-11 12CA-16	•		•		TP□R1103□□ TP□R1603□□	B243
	CTSPR/L		10CA-11 12CA-16	•				TP□R1103□□ TP□R1603□□	B244
	SSKCR/L		10CA-09 12CA-12	•				SC   T09T3	B245
_	SSSCR/L		10CA-09 12CA-12	•			•	SC_T09T3 SC_T1204	B246
Screw on System	STFCR/L		10CA-11 12CA-16	•		•		TC T1102 TC T16T3	B246
W)	STTCR/L		10CA-11 12CA-16	•		•		TC T1102 TC T16T3	B247
	STWCR/L		10CA-11 12CA-16	•				TC□T1102□□ TC□T16T3□□	B247

### CSKPR/L



SP□R





• R type insert (mm)

De	Designation		Н	W	L*	S*	h	K	$\alpha^{\circ}$	β°	а	t	v°	Insert
CSKPR/L	10CA-09	40	15	11	50	14	10	8	6	0	20	5	20	SP□R0903□□
	12CA-12	50	20	15	55	20	12	8	6	0	20	6	20	SP□R1203□□

→ Applicable inserts B76~B77


· a base Insert : r = 0.8 D = ØD Min. machining Dia.

	Parts		Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
CSKPR/L	10CA-09	CA05R	AZ0508F	KHA0408	RHA0620	WA0602	TW 15P	HW20L
	12CA-12	CA06R	AZ0508F	KHA0412	RHA0625	WA0602	TW 15P	HW20L

### CTFPR/L



 $\mathsf{TP} \square \mathsf{R}$ 



• R type insert

(mm)

De	signation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	v°	Insert
CTFPR/L	10CA-11	40	15	11	50	14	10	8	6	0	20	5	20	TP□R1103□□
	12CA-16	50	20	15	55	20	12	8	6	0	20	6	20	TP□R1603□□

→ Applicable inserts B81~B83

· a base Insert : r = 0.4 ( I = 11) r = 0.8 ( I = 16) D = ØD Min. machining Dia.


	Parts	Clamp	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
CTFPR/L	10CA-11	CA05R	AZ0508F	KHA0408	RHA0620	WA0602	TW25L	HW20L
	12CA-16	CA06R	AZ0508F	KHA0412	RHA0625	WA0602	TW30L	HW20L


# B Clamp on System

### CTSPR/L



TP□R





• R type insert (mm)

De	esignation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
CTSPR/L	10CA-11	40	15	11	44	14	10	8	4	0	20	5	20	TP□R1103□□
	12CA-16	50	20	15	47	20	12	8	5	0	20	6	20	TP□R1603□□

→ Applicable inserts B81~B83


· a base Insert : r = 0.4 ( I =11) r = 0.8 ( I = 16)  $D = \emptyset D$  Min. machining Dia.


	Parts	Clamp	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
CTSPR/L	10CA-11	CA05R	AZ0508F	KHA0408	RHA0620	WA0602	TW25L	HW20L
	12CA-16	CA06R	AZ0508F	KHA0412	RHA0625	WA0602	TW30L	HW20L

### CTTPR/L



 $\mathsf{TP} \square \mathsf{R}$ 





• R type insert

(mm) Designation ØD н W L\* S\* h K  $\alpha^{\circ}$ β° ٧° Insert а CTTPR/L 10CA-11 40 9 10 20 15 11 50 8 5 0 20 5 TP□R1103□□ 12CA-16 50 20 55 20 8 5 0 20 6 20 TP□R1603□□ 15 12


→ Applicable inserts B81~B83


· a base Insert : r = 0.8 D = ØD Min. machining Dia.

	Parts	Clamp	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
CTTPR/L	10CA-11	CA05R	AZ0508F	KHA0408	RHA0620	WA0602	TW25L	HW20L
	12CA-16	CA06R	AZ0508F	KHA0412	RHA0625	WA0602	TW30L	HW20L

### CTWPR/L







• R type insert

De	signation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
CTWPR/L	10CA-11	40	15	11	44	14	10	8	5	0	20	5	20	TP□R1103□□
	12CA-16	50	20	15	47	20	12	8	5	0	20	6	20	TP□R1603□□

→ Applicable inserts B81~B83


 $\cdot$  a base Insert : r = 0.8D = ØD Min. machining Dia.


	Parts	Clamp	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
CTWPR/L	10CA-11	CA05R	AZ0508F	KHA0408	RHA0620	WA0602	TW25L	HW20L
	12CA-16	CA06R	AZ0508F	KHA0412	RHA0625	WA0602	TW30L	HW20L

### SSKCR/L









• R type insert (mm)

De	signation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
SSKCR/L	10CA-09	40	15	11	50	14	10	8	0	-4	20	5	20	SC□□09T3□□
	12CA-12	50	20	15	55	20	12	8	0	-4	20	6	20	SC□□1204□□

◆ Applicable inserts B74~B75, B94

D = ØD Min. machining Dia.  $\cdot$  a base Insert : r = 0.8


	Parts	Screw	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
SSKCR/L	10CA-09	FTGA03508	AZ0508F	KHA0408	RHA0620	WA0602	TW 15P	HW20L
	12CA-12	FTGA0411F	AZ0508F	KHA0412	RHA0625	WA0602	TW 15P	HW20L


# B Screw on System

### SSSCR/L



SC□□





• R type insert (mm)

De	esignation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
SSSCR/L	10CA-09	40	15	11	44	14	10	8	-5	0	20	5	20	SC□□09T3□□
	12CA-12	50	20	15	47	20	12	8	-5	0	20	6	20	SC□□1204□□

◆ Applicable inserts B74~B75, B94


· a base Insert : r = 0.8 D = ØD Min. machining Dia.


	Parts	Screw	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
SSSCR/L	10CA-09	FTGA03508	AZ0508F	KHA0408	RHA0620	WA0602	TW 15P	HW20L
	12CA-12	FTGA0411F	AZ0508F	KHA0412	RHA0625	WA0602	TW 15P	HW20L

### STFCR/L



 $TC \square \square$ 





• R type insert (mm)

De	esignation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
STFCR/L	10CA-11	40	15	11	50	14	10	8	0	-3	20	5	20	TC□□1102□□
	12CA-16	50	20	15	55	20	12	8	0	-3	20	6	20	TC□□16T3□□

→ Applicable inserts B79~B80, B95


 $\cdot$  a base Insert : r = 0.4 ( I =11) r = 0.8 ( I = 16) D = Min. machining Dia.


	Parts	Screw	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
STFCR/L	10CA-11	FTKA02565	AZ0508F	KHA0408	RHA0620	WA0602	TW 15P	HW20L
	12CA-16	FTKA03508	AZ0508F	KHA0412	RHA0625	WA0602	TW 15P	HW20L

### STTCR/L



TC□□





• R type insert

	(111111)
L	

De	Designation		Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
STTCR/L	10CA-11	40	15	11	50	9	10	8	-5	0	20	5	20	TC□□1102□□
	12CA-16	50	20	15	47	20	12	8	-3	0	20	6	20	TC□□16T3□□

◆ Applicable inserts B79~B80, B95


 $\cdot$  a base Insert : r = 0.4 ( I =11) r = 0.8 ( I = 16) D = Min. machining Dia.


	Parts	Screw	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
STTCR/L	10CA-11	FTKA02565	AZ0508F	KHA0408	RHA0620	WA0602	TW 07P	HW20L
	12CA-16	FTKA03508	AZ0508F	KHA0412	RHA0625	WA0602	TW 15P	HW20L

### STWCR/L



 $\mathsf{TC} \square \square$ 





• R type insert

(mm)

De	signation	ØD	Н	W	L*	S*	h	K	α°	β°	а	t	٧°	Insert
STWCR/L	10CA-11	40	15	11	44	14	10	8	0	-4	20	5	20	TC□□1102□□
	12CA-16	50	20	15	47	20	12	8	-5	0	20	6	20	TC□□16T3□□

→ Applicable inserts B79~B80, B95

· a base Insert : r = 0.4 ( I = 11) r = 0.8 ( I = 16) D = Min. machining Dia.

	Parts	Screw	Axial Adjust Screw	Radial Adjust Screw	MountingScrew	Washer	Wrench	Wrench
STWCR/L	10CA-11	FTKA02565	5 AZ0508F KHA040		RHA0620	WA0602	TW 15P	HW20L
	12CA-16	FTKA03508	AZ0508F	KHA0412	RHA0625	WA0602	TW 15P	HW20L

# **MULTI FUNCTIONAL TOOLS**

Korloy Multi-functional tools can be used for machining in grooving, parting-off, facing and forming applications. Its design ensures superior machinability and productivity.



**Application Example** 

C02 Application Example

C04 Technical Information for Multi

Functional tools

**K Notch** 

C55 Technical Information for

K Notch

C57 K Notch

**KGT** 

C07 Technical Information for KGT

C12 KG7

C25 KGT Blade for Parting off

**Saw Man** 

C60 Technical Information for

Saw Man

C61 Saw Man

**MGT** 

C26 Technical Information for MGT

C28 MGT

C36 MGT (Face grooving)

Saw Man-X

C63 Technical Information for

Saw Man-X

C65 Saw Man-X

**KGT/MGT Cartridge** 

C39 Technical Information for KGT/MGT Cartridge

C40 KGT/MGT Cartridge Holder

C41 KGT CartridgeC42 MGT Cartridge

**Fine Tools** 

C67 Technical Information for

Fine Tools

C68 Fine Tools

**MGT Aluminum Wheel Series** 

C43 Technical Information for MGT

Aluminum Wheel

C44 MGT Aluminum Wheel

**Grooving/Parting off** 

C70 IGH

C70 DBH

C71 GFIP

TB/TB-M

C47 Technical Information for

TB/TB-M

C51 TB/TB-M

**Special Order Form** 


C72 Special Order Form for MGT

C73 Special Order Form for


V-Pulley Insert

# C Application Example


#### For external machining




#### For internal machining



#### For face grooving



#### For parting off





### **Technical Information for Multi Functinal Tools Series**

#### **Turning and Grooving**

#### Selection of insert

- Feed rate
- Decide maximum feed rate after considering the insert's characteristics and machine capabilities (Fmax = W x 0.075)
- Max feed rate should not be larger than the corner radius of the insert
- In grooving applications, chip evacuation problems can be remedied by using step feed methods at small intervals
- Depth of cut The minimum depth of cut should be bigger than corner radius of insert
  - When deciding on the max depth of cut please consider the machine's cutting load
  - Depending on the shape of the insert, deflection of work piece and clearance angle can be changed







#### Notice for turning

- KGT/MGT tools are designed to incur side cutting force from its clearance angle; this feature gives you advantage over a standard ISO insert
- The standard MGT insert also provides a "wiper" effect to improve surface roughness

#### Notice for finishing (offset need final quality)


- · After desired diameter is grooved, continuous turning operation might cause some deflection of the workpiece. In these cases follow the given formula, offsetting these factors enables the desired diameter that you want
- To eliminate the difference in the machined diameter by utilizing the clearance angle (which is commonly generated during the final turning operation) follow the directions above when machining To obtain a good surface roughness without offsetting in an application follows the directions below
  - 1) Groove to the desired diameter
- 2) Pull the tool backs a total distance of  $\theta/2$
- 3) Continue the external turning operation to desired diameter






#### Notice for MGT turning applications


· KGT/MGT tools are available for grooving and turning as a multifunctional tool. When using a M.G.T tool keep in mind that the tool imitates a standard ISO turning application. The application uses a positive clearance angle where a tool's cutting force and depth of cut are all applied in an application. This might create normal wear on the insert, after turning, a grooving process might not meet the desired diameter on the work piece. To off set this, adjust the tool 0.1 mm and return to the original position of the grooving application





#### Machining workpiece with a radius bigger than the insert's corner radius




Stabilize your tool pressure. KGT/MGT tools create a cutting load when machining a workpiece with a radius larger than the corner radius of insert (shown in the picture). The unequal cutting force might initially break the insert or holder












### Parting off & Grooving

#### Insert



- 4°- Pipe (Tubing and hollow bar)
- 6°- Pipe and solid bar
- · 8°- Solid bar
- · 15°- Small diameter Solid bar



Lead angle 0° (Neutral)

- · Parting off on solid bar type
- Occurring the center stub when parting off
- Prevent to be deflected workpiece by cutting direction during parting off
- · Available for use deep parting depth



Lead angle 4°~8°

 Reduce the center stub wher parting off on solid bar type

4~8

(Lead angle)

 Reduce the burr when parting off on tubing or hollow bar type



Lead angle 8°~15°

· Parting off on small diameter and

· Reduce the burr and center stub

when parting off on small

diameter solid bar type

hollow bar type

#### 

#### Selection of Insert


 $\bullet$  To properly match the insert and cutting condition, the following factors should be considered

(Lead angle)

- · Width of insert · Chip breaker · Grade and nose R
- The relationship between the cutting width and cutting depth
  - Neutral type, inserts with a 0-degree lead angle are best when used an applications maximum depth of cut
  - In general alloy steel, the maximum depth of cut = W x 0.8
- · Insert with lead angle
  - To reduce burrs, we recommend using insert with a lead angle.
  - · Insert that have larger lead angles reduce burrs but will also decreases tool life
  - In the case where burrs are acceptable, we recommend using a neutral type insert


#### Setting of holders

 The cutting position should be exactly mounted on machined axis in order to create a perpendicular direction or 90 to minimize vibration



#### Setting of parting off

- The edge height of an insert should be set within ±0.1mm based on the center line
  - · Parting off should be done as close to the chuck as possible to minimize vibration



#### Notice

- · Keep a consistent cutting speed and feed
- Use proper amounts of coolant for better performance
- · Properly clean the insert pocket before mounting insert

#### Usage

- If insert is worn, immediately replace with a new insert. This is to prevent the damage on the workpiece
- If the holder seat is worn or damaged replace with a new one immediately for stable clamping
- Do not grind or regrind the holder seat

#### Selection of chip breaker


- Our chip breakers are designed to narrow chips during grooving operations. Narrow chips usually offer the following advantages
- Decreases friction between chips and the workpiece. This usually gives a better surface roughness finish
- With better chip flow, a machinist is able to increase feed rates due to a reduced cutting load

## C Technical Information for Multi-Functinal Tools Series

#### Face grooving tools


#### For shallow grooving

- · Economical tools utilizing a double ended cutting edge system
- · Newly designed chip breakers that help ensure chip control for various face grooving applications
- · KORLOY face grooving tools provide various holder line-ups to give you more options and benefits




#### For deep grooving

- These tools are suitable for deep grooving with a single cutting edge (Tmax 25 mm)
- · A variety of chip breakers enable a machinist to apply a wide range of functions in machining
- · A variety of holders ensures multiple application ranges




#### Selection system of holder

• Follow these 3 simple directions to choose the right insert and holder for your application




#### Insert and holder

Choose an insert and holder that best applies to your application according to the cutting width and part of workpiece to be machined



#### **Holder Tmax**

Choose the holder with the shortest overhang that will still meet the cutting depth required



#### Machining Dia.

Choose the largest size of shank depending on the initial grooving diameter required in the application

Notice: To minimize chattering, use the shortest holder according to Tmax.

#### Optimization of face grooving

Roughing: When face grooving decreases the cutting speed 40% below a normal face turning operation



· Grooving at the initial diameter



 Face turning away from center



Face turning to center

#### Finishing: When face grooving decreases the cutting speed 40% below a normal face turning operation



· Grooving at the initial diameter to the final cutting depth and face turning away from center



· Radius operation toward final dimension at the




· Face turning to center




· Grooving for the right dimension you want

#### Notice for face grooving

· Before machining, check and adjust the following holder position



- · Check the cutting edge height at the center of the workpiece
- · Machine towards the center and check for burrs



· For better surface roughness, set up the insert in order to perpendicular at center line


#### Multi-functional machining with strong clamping system and new technology

### **KGT**


- Double-sided inserts of KGT reduces machining cost
- Strong clamping system ensures stable and accurate machining
- New grade and new technology provide superior tool life
- Various tooling solutions of the KGT improve productivity
- The foreside and clearance face of the KGT insert having cutting edges are optimal for grooving, parting-off, turning and facing with reducing processing time
- Three-dimensional chip breaker ensures excellent chip control in various applications
- The KGT inserts with various chip breakers are available for wide application range
- Special cutting edges are available for quotation


#### Code system

Insert



Holder








# C Technical Information for KGT Series

#### Recommended insert

							Appli	cation				
			For ex	ternal mac	hining	For groo		For In		Copying	For relief	Special machining
Designation	Geometry	Picture	Parting	Grooving	Turning	Grooving	Turning	Grooving	Turning	Copying	Reliefing	Special
				+	-1-			+				
	L Light Grooving	The same of the sa	0	0		0						
KGMN	<b>R</b> Rough Grooving		0	0		0						
	<b>T</b> Turning-Multi Grooving		0	0	0	0	0					
КСМІ	<b>T</b> Internal Grooving							0	0			
KRMN	<b>C</b> Copying	To all the same of								0	0	
KGMR/L	<b>LP</b> Light Parting	1	0									
KGINIH/L	RP Rough Parting	1	0									
KGGN	<b>B</b> Precision Grooving	S. S. S. S. S. S. S. S. S. S. S. S. S. S		0								0
NGGN	A Aluminum Grooving	1	0	0	0							
KRGN	<b>A</b> Aluminum Profiling	W. Carlot								0	0	
KRMI	<b>C</b> Copying	-								0	0	


#### Features




#### C/B guide


#### For Light Grooving







- · Low carbon steel
- · Alloy steel
- Small diameter component
- Stainless



#### For Rough Grooving










- · Strong cutting edge
- · High feed machining
- · Interrupted cutting
- · Carbon steel
- · Alloy steel
- Stainless
- · Cast iron




#### For Turning and Multi Grooving







- · Sharp cutting edge
- · Improved chip control
- Turning & grooving machining
- Carbon steel
- · Alloy steel
- Stainless
- · Cast iron



### For Copying and Relief










- · Improved chip control
- Copying
- Relief
- · Carbon steel
- · Alloy steel
- Stainless
- · Cast iron



### For Light Parting










- · Sharp cutting edge
- · Low feed machining
- Small diameter component
- · Right/left handed
- · Low carbon steel
- · Carbon steel
- · Alloy steel
- Stainless



### **Technical Information for KGT Series**

#### RP For Rought Parting










- · Strong cutting edge
- · High feed machining
- Interrupted cutting
- · Right/left handed
- · Carbon steel
- · Alloy steel
- Cast iron




#### **For Precision Grooving**







- · Ground insert
- · Precise tolerance
- · Various cutting edge length, Nose R
- · Carbon steel
- · Alloy steel
- Stainless
- · Cast iron



#### For Aluminium Grooving












- Sharp cutting edge
- Precise tolerance
- Aluminum alloy
- Copper alloy



#### Grades for recommended application range

	Workpiece	Grade	Order of recommended			Reco	mmended	d cutting speed (	m/min)		
	workpiece	Grade	grade		50	10	0	150	20	0	800
		PC5300	1		7	70	120				
	Chaol	PC3035	2		[7	70	130				
	Steel	NC3225	3					130		220	
P		NC5330	4				1	20	200		
-		PC5300	1		60	105					
	Alloy	PC3035	2		60	1	10				
	Steel	NC3225	3					130	200		
		NC5330	4			90			180		
		PC5300	1		G	70	120				
M	Stainless steel	PC9030	2		[7	70 	115				
		NC5330	3			75	125				
K	Cast iron	PC5300	1		55	90					
K	Cast IION	NC5330	2			9:	5	160			
N	Non-ferrous metal	H01	1							200 790	
s	HRSA	PC5300	1	20 35							

#### Performance evaluation

#### **Multi-function machining**

#### Turning + Grooving repetition


#### Optimized geometry for turning + grooving - High efficiency.


■ Workpiece SM45C

■ Cutting vc = 170 (m/min)condition fn = 0.15 (mm/rev)

> ap = 2 mmW = 3 mmwet

■ Designation KGMN300-04-T (PC5300)





Grooving **Shoulder Grooving** 

#### Tough geometry for interrupted and deep grooving.


■ Workpiece SUS304

■ Cutting vc = 120 (m/min) condition fn = 0.12 (mm/rev)

ap = 5 mmW = 4 mmwet

■ Designation KGMN400-03-R (PC5300)





#### **Shaft machining**

#### **Grooving (Roughing) & Turning (Finishing)**

#### Excellent chip control for higher efficiency.

■ Workpiece SCM440


**■** Cutting vc = 150 (m/min) condition fn = 0.15 (mm/rev)

> ap = 5 mmW = 3 mm x 3

wet

■ Designation KGMN300-04-T (PC5300)





Parting off **Pipe Parting-off** 

#### Exclusive parting-off chip breaker for longer tool life. / Sharp geometry for less burr.


■ Workpiece SUS304

■ Cutting vc = 140 (m/min)condition fn = 0.15 (mm/rev)

ap = 2 mmW = 3 mmwet

■ Designation KGMR300-6D-LP (PC5300)





# C KGT Series

#### Insert

ion							ated				Dimer	sions	s (mm	)		
Application	Picture	De	signation	NC3225	NC5330	NC6315	PC3035	PC5300	PC9030	b	r	ı	d	α°	Configuration	Page
		KGMN	200-02-L	•	•		•	•	•	2.0	0.2	20	1.7	-		C14~2
			300-02-L	•	•		•	•	•	3.0	0.2	20	2.3	-		C23
			400-02-L	•	•		•	•	•	4.0	0.2	20	3.3	-		020
	KGMN-L		500-03-L	•	•		•	•		5.0	0.3	25	4.1	-	d	
<u> </u>	<b>***</b>		600-03-L	•	•			•		6.0	0.3	25	5.1	-	b	
Grooving	2														7	
		KGMN	150-015-R	•	•			•		1.5	0.15	16	1.2	-		C14~2
			200-02-R	•	•		•	•	•	2.0	0.2	20	1.7	-		C23
E			300-02-R	•	•		•	•	•	3.0	0.2	20	2.3	-		
<u>ල</u>			400-03-R	•	•		•	•	•	4.0	0.3	20	3.3	-	d	
Ē	KGMN-R		500-03-R		•			•		5.0	0.3	25	4.1	-	b	
J.			600-03-R		•			•		6.0	0.3	25	5.1	-	1	
Grooving · Parting off			800-04-R		•			•		8.0	0.4	30	6.1	-		
		KGMN	150-015-T	•	•	•		•		1.5	0.15	16	1.2			C14~2
			200-02-T	•	•	•	•	•	•	2.0	0.2	20	1.7	-		C23
5			250-02-T	•	•			•		2.5	0.2	20	2.0			
			300-02-T	•	•	•	•	•	•	3.0	0.2	20	2.3	-	d	
	KGMN-T		04-T	•	•	•	•	•	•	3.0	0.4	20	2.3	-	b b	
	A STATE OF THE STA		400- <u>04-</u> T	•	•	•	•	•	•	4.0	0.4	20	3.3	-	- \r	
<u> </u>			08-T	•	•	•	•	•	•	4.0	0.8	20	3.3	-		
Grooving · Iurning			500-04-T	•	•	•	•	•	•	5.0	0.4	25	4.1	-		
5			T-80	•	•	•	•	•	•	5.0	8.0	25	4.1	-	7°	
			600- <u>04-</u> T	•	•	•	•	•	•	6.0	0.4	25	5.1	-		
			T-80	•	•	•	•	•		6.0	8.0	25	5.1	-		
			800-08-T	•		•	•	•		8.0	0.8	30	6.1	-		
		KRMN	200-C	•	•	•	•	•		2.0	1.0	20	1.7	-		C14~2
			300-C	•	•	•	•	•		3.0	1.5	20	2.2	-		
			400-C	•	•	•	•	•		4.0	2.0	20	3.2	-		
<u></u>	KRMN-C		500-C	•	•	•	•	•		5.0	2.5	25	4.0	-	d	
┋	retenine-o		600-C	•	•	•	•	•		6.0	3.0	25	5.0	-	b t	
Relief Profiling	-		800-C	•	•	•		•		8.0	4.0	30	6.0	-		
		KRMI	200-C							2.0	1.0	20	1.7	-		C23
			300-C 400-C							3.0 4.0	1.5 2.0	20	2.2	-		
Profiling	KRMI-C		400-0							4.0	2.0	20	3.2	-	d b	

<sup>•</sup> You can grind the chip breaker, 'B' as any shape you want. If you want any special shape of chip breaker, please contact your distributor.

#### Insert

Coat Picture Designation C3272  NC3225  NC3225  NC3225	ted Uncoated	Dimensions (mm)	
732 732 753	3 00 1		Configuration Page
▼ Z Z Z	NC6315 PC5300 PC9030 H01 H05	b r l d a°	- ago
KGMI 200-02-T	•	2.0 0.2 20 1.7 -	C23
300-04-T	•	3.0 0.4 20 2.3 -	
<b>KGMI-T</b> 400-04-T	•	4.0 0.4 20 3.3 -	d b
KGMI-T 400-04-T 300-04-T			
gri			7°
70			
5			14°
KGMR 200-6D-LP		2.0 0.2 20 1.7 6	
8D-LP		2.0 0.2 20 1.7 8	C14
15D-LP	•	2.0 0.2 20 1.7 15	d C16
KGMR-LP 300-6D-LP	•	3.0 0.2 20 2.3 6	a° r
15D-LP ●	•	3.0 0.2 20 2.3 15	<u>u-  -</u>   <u>U</u>
400-4D-LP ●	•	4.0 0.3 20 3.3 4	
15D-LP ●	•	4.0 0.3 20 3.3 15	
KGMR-LP   S00-6D-LP   SD-LP   S00-6D-LP	5.0 0.3 25 4.1 4	7°	
KGMR 200-6D-RP ●	•	2.0 0.2 20 1.7 6	C14
8D-RP		2.0 0.2 20 1.7 8	C16
RGIWIR   200-6D-RP   8D-RP   15D-RP   0	•	2.0 0.2 20 1.7 15	d b
300-6D-RP ●	•	3.0 0.2 20 2.3 6	<u>a°</u> 1 r
15D-RP •	•	3.0 0.2 20 2.3 15	
400-4D-RP • 15D-RP •		4.0     0.3     20     3.3     4       4.0     0.3     20     3.3     15	
500-4D-RP		5.0 0.3 25 4.1 4	7°
<u>500-4D-HF</u>		3.0 0.3 23 4.1 4	
KGML 200-6D-LP		2.0 0.2 20 1.7 6	C14
15D-LP		2.0 0.2 20 1.7 15	C16
KGML-LP 300-6D-LP		3.0 0.2 20 2.3 6	d bi
15D-LP		3.0 0.2 20 2.3 15	a° r
400-4D-LP		4.0 0.2 20 3.3 4	
15D-LP		4.0 0.2 20 3.3 15	
15D-LP 300-6D-LP 15D-LP 400-4D-LP 15D-LP 15D-LP			7°
Pa			
KGML 200-6D-RP		2.0 0.2 20 1.7 6	
15D-RP		2.0 0.2 20 1.7 6	C14 C16
300-6D-RP		3.0 0.2 20 2.3 6	a
KGML-RP 15D-RP		3.0 0.2 20 2.3 15	
400-4D-RP		4.0 0.2 20 3.3 4	
15D-RP		4.0 0.2 20 3.3 15	
15D-RP 300-6D-RP 15D-RP 400-4D-RP 15D-RP			7°
Par			,
KGGN 265-015-B		2.65 0.15 20 2.3 -	C14
300-020-B		3.0 0.20 20 2.3 -	
040-B		3.0 0.40 20 2.3 - 3.15 0.15 20 2.3 -	
315-015-B 400-040-B 080-B 415-015-B 478-055-B 500-080-B 515-015-B 600-080-B		3.15 0.15 20 2.3 - 4.0 0.40 20 3.3 -	d
KGGN-B 080-B		4.0 0.40 20 3.3 -	of the p
415-015-B		4.15 0.15 20 3.3 -	1 1
478-055-B		4.78 0.55 25 4.1 -	
500-080-B		5.0 0.80 25 4.1 -	
515-015-B		5.15 0.15 25 4.1 -	7°
€ 600-080-B		6.0 0.80 25 5.1 -	
120-B		6.0 1.20 25 5.1 -	
800-080-B		8.0 0.80 30 6.1 -	
120-B		8.0 1.20 30 6.1 -	

<sup>•</sup> You can grind the chip breaker, 'B' as any shape you want. If you want any special shape of chip breaker, please contact your distributor.

# C KGT Series

#### Insert

Application						Coa				Unce	oated	L	Dimer	ISIONS	s (mm	)		
¥	Picture	Des	signation	NC3215	NC3225	NC5330	NC6315	PC5300	PC9030	된	H05	b	r	1	d	α°	Configuration	Page
Ê		KGGN	200-02-R									2.0	0.2	20	1.7	-		C14~21
inse			300-02-R									3.0	0.2	20	2.3	-		
pun	new		400-03-R									4.0	0.3	20	3.3	-	d b	
9	KGGN-R		500-03-R									5.0	0.3	25	4.1	-		
#0			600-03-R									6.0	0.3	25	5.1	-		
Grooving · Parting off (Ground insert)	1		800-04-R									8.0	0.4	30	6.1	-		
		KGGN	200S-02-R									2.0	0.2	19.9	1.7	-		C24
ser			300S-02-R					•				3.0		19.9	2.3	-		024
흗	new		400S-03-R					•				4.0	0.3	19.9	3.3	-	d  +	
Sing	KGGN-R		500S-03-R					•				5.0	0.3	24.9	4.1	-	Б	
#0	NOO!! I		600S-03-R					•				6.0	0.3	24.9	5.1	-	\ <u>\</u> \ <u></u>	
Grooving · Parting off (Single insert)			800S-04-R					•				8.0	0.4	24.9	6.1	-	7	
		KGGN	200-02-A							•		2.0	0.2	20	1.7	-		C24
ng			300-02-A							•		3.0	0.2	20	2.3	-		02.
٥٧i	new		400-04-A							•		4.0	0.4	20	3.3	-	d   b	
210	KGGN-A		500-04-A							•		5.0	0.4	25	4.1	-	r	
Aluminum Grooving			600-04-A							•		6.0	0.4	25	5.1	-	7'	
æ		KGGN	200S-02-A									2.0	0.2	20	1.7	-		C24
nse	_		300S-02-A									3.0	0.2	20	2.3	-		024
gle	KGGN-A		400S-04-A									4.0	0.4	20	3.3	-	d	
Sir	NOOH-A		500S-04-A									5.0	0.4	25	4.1	-	b	
Aluminum Grooving (Single insert)			600S-04-A									6.0	0.4	25	5.1	-		
		KRGN	300-A							•		3.0	1.5	20	2.3	-		C14~21
DG.			400-A							•		4.0	2.0	20	3.3	-		014~21
ovii	new	w	500-A							•		5.0	2.5	25	4.1	-	d  b	
Jro.	KKGN-A		600-A							•		6.0	3.0	25	5.1	-		
<b>Aluminum Grooving</b>	KRGN-A		800-A							•		8.0	4.0	30	6.1	-	7	

 $<sup>\</sup>bullet \ \, \text{You can grind the chip breaker, 'B' as any shape you want. If you want any special shape of chip breaker, please contact your distributor. }$ 

<sup>• :</sup> Stock item


# KGEHR/L


For grooving, turning, parting off, and relief machining











• R type insert (mm)

MAGN										(mm)
D	esignation	H = (h)	W	L	S	h1	Т-мах	Inserts	Screw	Wrench
KGEHR/L	1616-1.5-T14	16	16	100	16.2	-	14			
	2020-1.5-T14	20	20	125	20.2	-	14	KGMN150-□-□	MHA0512	HW40L
	2525-1.5-T14	25	25	150	25.2	-	14			
	1212-2-T08	12	12	100	12.2	-	8			
	1616-2-T08	16	16	100	16.2	-	8			
	2020-2-T08	20	20	125	20.2	-	8			
	2525-2-T08	25	25	150	25.2	-	8	KGMN200-□-□		
	1616-2-T12	16	16	100	16.2	-	12	KGMR/L200-□-□	MHA0512	HW40L
	2020-2-T12	20	20	125	20.2	-	12	KRMN200-C		
	2525-2-T12	25	25	150	25.2	-	12	KGGN200-□-□		
	1616-2-T17	16	16	100	16.2	-	17			
	2020-2-T17	20	20	125	20.2	-	17	1		
	2525-2-T17	25	25	150	25.2	-	17			
	1616-2.5-T17	16	16	100	16.3	-	17	1		
	2020-2.5-T17	20	20	125	20.3	-	17	KGMN250-□-□	MHA0512	HW40L
	2525-2.5-T17	25	25	150	25.3	-	17			
	1616-3-T10	16	16	100	16.4	-	10			
	2020-3-T10		_							
	2525-3-T10	25	25	150	25.4	-	10			
	3232-3-T10	32	32	170	32.4	-	10	KCMNIGOO 🗆 🗆		
	1616-3-T13	16	16	100	16.4	-	13	KGMN300-□-□ KGMR/L300-□-□	MHA0512	
	2020-3-T13	20	20	125	20.4	-	13	KRMN300-C		HW40L
	2525-3-T13	25	25	150	25.4	-	13	KGGN300-□-□		
	1616-3-T20	16	16	100	16.4	-	20	KRGN300-□		
	2020-3-T20	20	20	125	20.4	-	20			
	2525-3-T20	25	25	150	25.4	-	20	_		
	3232-3-T20	32	32	170	32.4	-	20			
	2525-3-T25	25	25	150	25.4	-	25			
	1616-4-T10	16	16	100	16.4	-	10			
	2020-4-T10	20	20	125	20.4	-	10	_		
	2525-4-T10	25	25	150	25.4	-	10			
	3232-4-T10	32	32	150	32.4	-	10	4		
	1616-4-T15	16	16	100	16.4	-	15	   KGMN400-□-□		
	2020-4-T15	20	20	125	20.4	-	15	KGMR/L400		
	2525-4-T15	25	25	150	25.4	-	15	KRMN400-C	BHA0616	HW50L
	1616-4-T20	16	16	100	16.4	-	20	KGGN400-□-□		
	2020-4-T20	20	20	125	20.4	-	20	KRGN400-□		
	2525-4-T20	25	25	150	25.4	-	20	-		
	3232-4-T20	32	32	170	32.4	-	20	-		
	1616-4-T25	16	16	100	16.4	-	25	-		
	2020-4-T25	20	20	125	20.4	-	25	-		
	2525-4-T25	25	25	150	25.4	-	25			

# C KGT Series


# KGEHR/L

For grooving, turning, parting off, and relief machining











• R type insert (mm)


	Designation	H = (h)	W	L	s	h1	Т-мах	Inserts	Screw	Wrench
GEHR/L	2020-5-T12	20	20	125	20.5	-	12			
	2525-5-T12	25	25	150	25.5	-	12			
	2020-5-T15	20	20	125	20.55	-	15			
	2525-5-T15	25	25	150	25.55	-	15	KGMN500	BHA0616	HW50L
	3232-5-T15	32	32	170	32.55	-	15	KRMN500-C KGGN500-□-□		
	2020-5-T20	20	20	125	20.5	-	20	KRGN500-□-□		
	2525-5-T20	25	25	150	25.5	-	20			
	3232-5-T20	32	32	170	32.5	-	20		BHA0620	HW50L
	2525-5-T32	25	25	150	25.5	7	32		BHAU020	HWOOL
	2020-6-T12	20	20	125	20.5	-	12			
	2525-6-T12	25	25	150	25.5	-	12			
	2525-6-T15	25	25	150	25.55	-	15	KGMN600-□-□	BHA0616	HW50L
	3232-6-T15	32	32	170	32.55	-	15	KRMN600-C	DHAU010	HWOUL
	2020-6-T20	20	20	125	20.5	-	20	KGGN600-□-□		
	2525-6-T20	25	25	150	25.5	-	20	KRGN600-□		
	3232-6-T20	32	32	170	32.5	-	20		BHA0620	LIMEOL
	2525-6-T32	25	25	150	25.5	7	32		BHA0020	HW50L
	2525-8-T16	25	25	150	26	-	16			
	3232-8-T16	32	32	170	33.05	-	16	KGMN800-□-□	BHA0616	HW50L
	2525-8-T25	25	25	150	26	-	25	KRMN800-C		
	3232-8-T25	32	32	170	33	-	25	KGGN800-□-□		
	2525-8-T36	25	25	150	26	7	36	KRGN800-□	BHA0620	HW50L
	3232-8-T36	32	32	170	33	-	36	1		

Applicable inserts C12~C14

# KGEHR/L-D00A (Auto Tool)

For grooving, turning, parting off machining







• R type insert


D	Designation	H = (h)	w	L	S	h1	ØD Max	Inserts	Screw	Wrench
KGEHR/L	1010-2-D20A	10	10	125	10.2	2	20	KGMN200-□-□		
	1212-2-D25A	12	12	125	12.2	2	25	KGMR/L200-□-□		
	1414-2-D25A	14	14	125	14.2	-	25	KRMN200-C		
	1616-2-D32A	16	16	125	16.2	-	32	KGGN200-□-□	ETNA0412	TW15L
	1212-3-D25A	12	12	125	12.4	2	25	KGMN300-□-□ KGMR/L300-□-□	2110/10/12	111102
	1616-3-D32A	16	16	125	16.4	-	32	KRMN300-C KGGN300-□-□		

<sup>→</sup> Applicable inserts C12~C14

# KGEHR/L-D00B (Auto Tool)

For grooving, turning, parting off machining







• R type insert

(mm)

										(mm)
D	esignation	H = (h)	W	L	S	h1	ØD Max	Inserts	Screw	Wrench
KGEHR/L	1010-2-D30B	10	10	140	10.2	6.6	30			
	1212-2-D25B	12	12	140	12.5	3.5	25	KGMN200-□-□		
	1212-2-D30B	12	12	140	12.2	3.5	30	KGMR/L200-□-□ KRMN200-C		
	1616-2-D25B	16	16	140	16.2	-	25	KGGN200-□-□		
	1616-2-D32B	16	16	140	16.2	-	32		MHA0512	HW40L
	1212-3-D25B	12	12	140	12.4	3.5	25	  - KGMN300-□-□		
	1212-3-D32B	12	12	140	12.4	3.5	32	KGMR/L300-□-□		
	1616-3-D25B	16	16	140	16.4	-	25	KRMN300-C		
	1616-3-D32B	16	16	140	16.4	-	32	KGGN300-□-□		


<sup>●</sup> Applicable inserts C12~C14




# KGEHR/L-T00

## For grooving, turning, face grooving machining







• R type insert

(n	nr	n)

D	esignation	H = (h)	W	L	S	ØD Min	Т-мах	Inserts	Screw	Wrench
KGEHR/L	1616-3-T00	16	16	100	16.4	80	4.8	KGMN300-□-□		
	2020-3-T00	20	20	125	20.4	80	4.8	KRMN300-C KGGN300-□-□	MHA0512	HW40L
	2525-3-T00	25	25	150	25.4	80	4.8	KRGN300-□		
	1616-4-T00	16	16	100	16.4	80	4.8	KGMN400-□-□		
	2020-4-T00	20	20	125	20.4	80	4.8	KRMN400-C KGGN400-□-□	BHA0616	HW50L
	2525-4-T00	25	25	150	25.4	80	4.8	KRGN400-□		
	2020-6-T00	20	20	125	20.5	80	6.0	KGMN600-□-□ KRMN600-C	BHA0616	HW50L
	2525-6-T00	25	25	150	25.5	80	6.0	KGGN600-□-□ KRGN600-□	DHAU010	HVV50L

<sup>→</sup> Applicable inserts C12~C14


## KGEVR/L-T00

KGGN

For grooving, turning, face grooving machining



**KRGN** 





R type insert

(mm)

Screw Wrench ØD s Designation H = (h)W L Т-мах Inserts Min 0 KGEVR/L 2020-1.5 -T00 20 20 125 23.5 120 3 2525-1.5 -T00 25 25 150 28.5 120 3 KGMN150-□-□ MHA0512 HW40L 3232-1.5 -T00 32 32 170 35.5 120 3 23.5 2020-2 -T00 20 20 125 120 3 KGMN200-□-□ 2525-2 -T00 25 25 150 28.5 120 3 KRMN200-C MHA0512 HW40L KGGN200-□-□-□ 3232-2 -T00 35.5 3 32 32 170 120 2020-2.5 -T00 20 20 125 24.5 4 2525-2.5 -T00 25 25 150 29.5 80 4 KGMN250-□□ MHA0512 HW40L 3232-2.5 -T00 32 32 170 36.5 4 80 KGMN300-□-□ 2020-3-T00 20 20 125 25 80 4.8 KRMN300-C 2525-3-T00 25 25 150 30 80 4.8 MHA0512 HW40L KGGN300-□-□ 3232-3 -T00 32 32 170 37 80 4.8 KRGN300-□ KGMN400-□-□ 2020-4-T00 20 125 4.8 20 25 80 KRMN400-C 2525-4-T00 25 150 30 80 4.8 BHA0616 HW50L KGGN400-□-□ 3232-4 -T00 32 32 170 37 4.8 80 KRGN400-KGMN500- 🗆 -2020-5 -T00 20 20 125 29.5 60 6 KRMN500-C 2525-5 -T00 25 25 150 31.5 60 6 BHA0616 HW50L KGGN500-□-□ 3232-5 -T00 32 32 170 38.5 60 6 KRGN500-□ KGMN600- 🗆 -2020-6 -T00 20 20 125 26.5 60 6 KRMN600-C 2525-6-T00 25 25 150 31.5 6 BHA0616 HW50L 80 KGGN600-□-□ 3232-6 -T00

38.5

33.5

38.5

60

50

6

8

8

KRGN600-□ KGMN800-□-□

KRMN800-C

KRGN800-□

KGGN800-□-□

2525-8 -T00

3232-8 -T00

32

25

32

32

25

32

170

150

170

BHA0616


HW50L

<sup>→</sup> Applicable inserts C12~C14


# C KGT Series

# KGEUR/L





## For relief machining



• R type insert (mm)


D	esignation	H = (h)	W	L	S	ØD Min	Т-мах	Inserts	Screw	Wrench
KGEUR/L	1616-3	16	16	100	19	40	2.8			
	2020-3	20	20	125	23	40	2.8	KRMN300-C	MHA0512	HW40L
	2525-3	25	25	150	28	40	2.8	KRGN300-□	IVIHAU512	HVV40L
	3232-3	32	32	170	35	40	2.8			
	1616-4	16	16	100	19	40	2.8			HW50L
	2020-4	20	20	125	23	40	2.8	KRMN400-C	BHA0616	
	2525-4	25	25	150	28	40	2.8	KRGN400-□		
	3232-4	32	32	170	35	40	2.8			
	2020-5	20	20	125	23.5	50	3.3	L/DAMESON O		
	2525-5	25	25	150	28.5	50	3.3	KRMN500-C KRGN500-□	BHA0616	HW50L
	3232-5	32	32	170	35.5	50	3.3	KHGN500-		
	2020-6	20	20	125	23.5	50	3.3	L/DMMH000 O		
	2525-6	25	25	150	28.5	50	3.3	KRMN600-C KRGN600-□	BHA0616	HW50L
	3232-6 2525-8	32	32	170	35.5	50	3.3	Khanooo-		
		25	25	150	28.5	65	3.3	KRMN800-C	DLIAGGAG	LIMEOL
	3232-8	32	32	170	35.5	65	3.3	KRGN800-□	BHA0616	HW50L

<sup>→</sup> Applicable inserts C12~C14

# KGFVR/L



KGMN KRMN KGGN KRGN



	) a ciamatian	LI _ /b)	W		s	T-MAX	Ø	D	Incorto	Screw	Wrench
L	Designation	H = (h)	vv	L	5	I-MAX	Min	Max	Inserts	9	
KGFVR/L	325-34/50-T10	25	25	150	36	10	34	50	KGMN300- 🗆 -		
	44/60-T15	25	25	150	41	15	44	60	KRMN300-C KGGN300-□-□	MHA0512	HW40L
	54/85-T15	25	25	150	41	15	54	85	KRGN300-□-□		
	425-32/50-T15	25	25	150	41	15	32	50			
	42/60-T15	25	25	150	41	15	42	60	KGMN400-□-□		
	44/70-T20	25	25	150	45.5	20	44	70	KRMN400-C	BHA0616	HW50L
	52/85-T15 60/120-T20	25	25	150	41	15	52	85	KGGN400-□-□		
	60/120-T20	25	25	150	45.5	20	60	120	KRGN400-□		
	112/200-T20	25	25	150	45.5	20	112	200	00		
	525-50/80-T20	25	25	150	46	20	50	80			
	70/110-T20	25	25	150	46	20	70	110	KGMN500-□-□		
	100/150-T20	25	25	150	46	20	100	150	KRMN500-C KGGN500-□-□	BHA0616	HW50L
	140/200-T20	25	25	150	46	20	140	200	KRGN500-□-□		
	200-T20 625-48/85-T20 73/150-T20 138/250-T20	25	25	150	46	20	200	∞			
		25	25	150	46	20	48	85	KGMN600-□-□		
		25	25	150	46	20	73	150	KRMN600-C	DUADCAC	LIMEO
		25	25	150	46	20	138	250	KGGN600-□-□	BHA0616	HW50L
	250-T20	25	25	150	46	20	250	∞	KRGN600-□		


<sup>◆</sup> Applicable inserts C12~C14




# KGFHR/L

### For face grooving machining








• R type insert


	Darden etten	11 (1-)	147		•	<b></b>	Q	D	L	Screw	Wrench
	Designation	H = (h)	W	L	S	Т-мах	Min	Max	Inserts	<b>O</b>	
GFHR/L	320-34/50-T10	20	20	150	20.5	10	34	50			
	44/70-T15	20	20	150	20.5	15	44	70	KGMN300-□-□		
	64/100-T15	20	20	150	20.5	15	64	100	KRMN300-LI-LI	MHA0512	HW40
	325-34/50-T10	25	25	150	25.5	10	34	50	KGGN300-□-□	IVITAUS12	ПVV40
	44/70-T15	25	25	150	25.5	15	44	70	KRGN300-□		
	64/100-T15	25	25	150	25.5	15	64	100			
	420-34/50-T16	20	20	150	20.5	16	34	50			
	42/70-T16	20	20	150	20.5	16	42	70			HW50L
	62/120-T16	20	20	150	20.5	16	62	120			
	112/200-T16	20	20	150	20.5	16	112	200			
	425-34/50-T20	25	25	150	25.6	20	34	50	KGMN400-□-□		
	40/60-T10	25	25	150	25.6	10	40	60	KRMN400-C KGGN400-□-□	BHA0616	
	44/70-T20	25	25	150	25.6	20	44	70	KRGN400-□		
	84/92-T20	25	25	150	25.6	20	84	92			
	60/120-T20	25	25	150	25.6	20	60	120			
	112/200-T20	25	25	150	25.6	20	112	200			
	200-T20	25	25	150	25.6	20	200	∞			
	525-50/80-T15	25	25	150	25.6	15	50	80			
	50/80-T25	25	25	150	25.6	25	50	80			
	70/110-T15	25	25	150	25.6	15	70	110	KGMN500-□-□		
	70/110-T25	25	25	150	25.6	25	70	110	KRMN500-C	BHA0616	HW50
	100/150-T25	25	25	150	25.6	25	100	150	KGGN500-□-□	DUANDID	СМА
	140/200-T25	25	25	150	25.6	25	140	200	KRGN500-□		
	190/220-T10	25	25	150	25.6	10	190	200			
	200-T25	25	25	150	25.6	25	200	∞			
	625-170/190-T10 190/220-T10	25	25	150	25.6	10	170	190	KGMN600-□-□ KRMN600-C	PUAGES	LI\\/E/
		190/220-T10 25 25	25 25 150	) 25.6	10	190	200	KGGN600-□-□ KRGN600-□	BHA0616	HW50	

<sup>◆</sup> Applicable inserts C12~C14

# KGIUR/L









• R type insert

(mm)

ſ	Designation	ØD	Ød	L	Q	Т-мах	н	s	Inserts	Screw	Wrench
KGIUR/L	3520-3	35	20	150	45	3.5	18	13	.,		
	4025-3	40	25	200	50	3.5	23	15.5	KRMN300-C KRGN300-□	MHA0512	HW40L
	5032-3	50	32	250	65	3.5	30	19	- KHGNOOO-		
	3520-4	35	20	150	45	3.5	18	13			
	4025-4	40	25	200	50	3.5	23	15.5	KRMN400-C KRGN400-□	MHA0512	HW40L
	5032-4	50	32	250	65	3.5	30	19			
	4025-5	40	25	200	50	3.5	23	15.5	KRMN500-C		1,11,4,01
	5032-5	50	32	250	65	3.5	30	19	KRGN500-□	MHA0512	HW40L
	4025-6	40	25	200	50	3.5	23	15.5	KRMN600-C	MULAOFAO	1.04/401
	5032-6	50	32	250	65	3.5	30	19	KRGN600-□	MHA0512	HW40L
	4025-8	40	25	200	50	3.5	23	18.5	KRMN800-C	141140540	1.04/401
	5032-8	50	32	250	65	3.5	30	22	KRGN800-□	MHA0512	HW40L

<sup>→</sup> Applicable inserts C12~C14

# C KGT Series


## KGIVR/L


### For grooving, turning and profil machining



KGMI KGGN KRMN

KGMN KRMI





• R type insert

											(mn
[	Designation	ØD	Ød	L	Q	Т-мах	н	s	Inserts	Screw	Wrench
KGIVR/L	2016-1.5	20	16	125	35	4	15	12		MHB0410	HW30L
	2520-1.5	25	20	150	45	6	18	15.5	KGMN150-□-□	MHB0410	HW30L
	3225-1.5	32	25	200	45	7	23	19		MHA0512	HW40L
	2516-2	25	16	125	35	6.5	15	14	KCM1000 🗆 T	MHB0410	HW30L
	2520-2	25	20	150	45	6.5	18	15.5	KGMI200-□-T KRMI200-C	WITIDU410	HWOOL
	3225-2	32	25	200	45	7	23	19	141 IIVII200-0	MHB0512	HW40L
	2516-2.5	25	16	125	35	6.5	15	14		MHB0410	HW30L
	2520-2.5	25	20	150	45	6.5	18	15.5	KGMN250-□-□	WII IDO4 TO	TIVVOOL
	3225-2.5	32	25	200	45	7	23	19		MHA0512	HW40L
	2520-3	25	20	150	45	6.5	18	15.5	KGMI300-□-T	MHB0410	HW30L
	3225-3	32	25	200	45	7	23	19	KGMI300-∐-1	MHA0512	HW40L
	4032-3	40	32	250	55	7.5	30	22.5	TO INFO C	BHA0616	HW50L
	2520-4	25	20	150	45	6.5	18	15.5	   KGMI400-□-T	MHB0410	HW30L
	3225-4	32	25	200	45	7	23	19	KGMI400-∐-1	MHA0512	HW40L
	4032-4	40	32	250	55	7.5	30	22.5	TO TOTAL	BHA0616	HW50L
	3225-5	32	25	200	45	7.5	23	19.5	KGMN500-□-□ KRMN500-C	MHA0512	HW40L
	4032-5	40	32	250	55	8.5	30	23.5	KGGN500-□-R KGGN500-□-A	BHA0616	HW50L
	3225-6	32	25	200	45	7.5	23	19.5	KGMN600-□-□ KRMN600-C	MHA0512	HW40L
	4032-6	40	32	250	55	8.5	30	23.5	KGGN600-□-R KGGN600-□-A	BHA0616	HW50L
	4032-8	40	32	250	55	8.5	30	23.5	KGMN800-[]-[]	BHA0616	HW50L
	4540-8	45	40	300	70	8.5	37	26.5	KRMN800-C KGGN800-□-R	BHA0616	HW50L


<sup>→</sup> Applicable inserts C12~C14

<sup>• 200, 300, 400</sup> inserts : Internal inserts, KGMI or KRMI

# **KGT Blade for Parting off**

## Features

- Parting application with the use of existing KGT inserts
- Economical machining with a double sided insert
- Specially designed slot for strong and stable clamping
- Easy change of insert with the use of exclusive wrench



## Code system




## How to clamp insert




1) Insert the pin of wrench into the hole of blade.




2 Clamp the insert on its seat after turning the handle to  $45^{\circ} \sim 160^{\circ}$  for loosening the seat.



3 Finish clamp by removing the wrench after moving it back to its original state.



D	esignation	н	W	W'	L	h	ØD Max <sup>(2)</sup>	ØD Max <sup>(3)</sup>	Inserts	Wrench	Fig
KGTB	1526S	26	2.4	1.0	150	21	-	26	KG□□150-□-□		4
	1532	32	2.4	1	150	25	-	26	KG□□150-□-□		1
	2026S	26	2.4	1.8	150	21	50	39	KG□□200-□-□ KG□□200S-□-R <sup>(4)</sup>		4
	2032	32	2.4	1.8	150	25	50	39	KG□□200-□-□ KG□□200S-□-R <sup>(4)</sup>		1
	3026S	26	2.4	-	150	21	100	39	KG□□300-□-□ KG□□300S-□-R <sup>(4)</sup>	5.44000	4
	3032	32	2.4	-	150	25	100	39	KG□□300-□-□ KG□□300S-□-R <sup>(4)</sup>	EW1203 (Separately	2
	4026S	26	3.2	-	150	21	100	39	KG□□400-□-□ KG□□400S-□-R <sup>(4)</sup>	ordered)	4
	4032	32	3.2	-	150	25	100	39	KG□□400-□-□ KG□□400S-□-R <sup>(4)</sup>		2
	5032	32	4	-	150	25	120	49	KG□□500-□-□ KG□□500S-□-R <sup>(4)</sup>		2
	6032	32	5.2	-	150	25	120	49	KG□□600-□-□ KG□□600S-□-R <sup>(4)</sup>		2
	<b>8032S</b> (1)	32	6.2	-	150	25	80	59	KG□□800-□-□ KG□□800S-□-R <sup>(4)</sup>	HW30L	3




## Inserts are offered with two edges, for better economical machining

## **MGT Series**

- Inserts are offered with two edges, for better economical machining
- Multi-function operations Reduce cycle time & increase productivity with the ability to groove, turn, face or copy in an application
- Shorten time & save on tool cost Korloy's MGT system allows a machinist to apply one tool against many applications, reducing the number of tools
- Flat Cutting Edge MGT tools have a flat geometry on its cutting edge to ensure excellent surface finishes. Even in high Feed applications by using a wiper function, Korloy ensures excellent surface finishes in roughing operations

## Code system

· Insert





## Geometry of chip breaker



- Specially designed chip breaker allows a smoother chip flow versus conventional flat-top geometries through the use of a central chip breaker
- Specially placed convex dots assists with chip control in external machining, for a smoother chip flow
- Chip breaker designed for turning & grooving applications
- Specially designed high positive geometry, ideal for machining aluminum
- The chip breaker's super buffed, high rake angle allows optimal chip flow of aluminum

## MGMN-G

- Specially designed chip breaker allows narrower chips to promote better chip flow
  - Specifically designed for grooving applications

### MRMN-M




- Full radius geometry for applications that require profiling
- Available for relief machining

### **MFMN300**



- · Specially designed chip breaker allows narrower chips to promote better chip flow
- Chip breaker specially designed for facegrooving

- Sharply designed cutting edge.
- Recommended in machining low carbon steel and stainless steel
- Specially designed chip breaker allows narrower chips to promote better
- Able to machine Feed rates and small diameter cutting



- · Able to machine at Feed rates as high and bar stock
- Chip breaker design helps narrows chips for better

### MGGN-A



- · Sharp cutting edge
- Low cutting resistance
- For auto CNC machine
- For small Dia. processing

## MGMN-R

- · Strong cutting edge
- For high feed rate processing

### **MGMN-T**

- $\cdot$  For turning & grooving
- Reduced chip width & smooth chip control by dot designed on the top

### · Smooth chip flow

· Reduced build up on cutting edge

## **○** Parting off (MGMN/MGMR/L)

			Cut	ting Speed	d (vc = m/r	nin)				Feed	d (fn = mm.	/rev)	
Workpiece		C	<b>V</b> D			PVD		Uncoated		Cut	ting width (ı	nm)	
	NC3120	NC3030	NCM325	NC5330	PC8110	PC5300	PC6510	ST30A	2	3	4	5	6
SM□□C	80~180			80~180		80~180			0.02~0.15	0.03~0.20	0.08~0.30	0.10~0.40	0.12~0.50
SCM	70~150	70~150	70~150	70~150		70~150			0.02~0.15	0.03~0.20	0.08~0.30	0.10~0.40	0.12~0.50
GC/GCD				50~100			50~100	50~100	0.05~0.12	0.10~0.25	0.10~0.30	0.10~0.35	0.10~0.40
STS			50~120	50~120	50~120	60~140			0.02~0.10	0.03~0.15	0.08~0.25	0.10~0.35	0.12~0.40
Non-ferrous metal (Al, Copper)								200~450	0.05~0.10	0.05~0.20	0.05~0.25	0.05~0.30	0.05~0.35

## **○** Facing (FGD/FGM/FMM/MFMN/MGMN)

			Cu	tting Speed	(vc = m/min)			Fe	ed (fn = mm/r	ev)
Workpiece		C	VD			PVD	Uncoated	Cı	utting width (m	m)
	NC6110	NC3030	NC5330	NC3120	PC215K	PC8110 / PC5300	H01	3	4	5
SM□□C			100~160	100~160				0.05~0.10	0.05~0.12	0.05~0.15
SCM		50~130	50~130	50~130			200~800	0.05~0.10	0.05~0.12	0.05~0.15
GC/GCD	120~150		120~150		120~150			0.05~0.10	0.05~0.12	0.05~0.15
STS			60~150			60~150		0.05~0.10	0.05~0.12	0.05~0.15
Non-ferrous metal (Al, Copper)								0.05~0.15	0.08~0.15	0.08~0.15

## **②** Grooving, Turning (MGMN/MRMN)

			Cutt	ing Speed	I (vc = m/	min)					Feed (fn :	= mm/rev)		
Workpiece		CVD		P۱	/D	Cermet	Unco	ated			Cutting w	idth (mm)		
	NC3120	NC3030	NC5330	PC215K	PC5300	CN20	ST30A	ST20	0.5~1.0	1.0~2.0	2~3	3~4	4~5	6~8
SM□□C	80~200		80~200		80~180	80~120		80~120	0.03~0.08	0.04~0.09	0.05~0.1	0.05~0.12	0.05~0.15	0.05~0.2
SCM	80~180	80~180	80~180		80~160	80~120	80~120	80~120	0.03~0.07	0.04~0.08	0.05~0.08	0.05~0.1	0.05~0.12	0.05~0.15
GC/GCD			60~130		60~130				0.03~0.07	0.04~0.08	0.05~0.08	0.05~0.1	0.05~0.10	0.05~0.12
STS			60~100	60~100			60~100		0.03~0.08	0.04~0.09	0.05~0.10	0.05~0.12	0.05~0.12	0.05~0.15
Non-ferrous metal (Al, Copper)				150~300			150~400		0.05~0.12	0.05~0.15	0.05~0.15	0.08~0.15	0.08~0.15	0.10~0.20

# C MGT Series

E .							Coa	ated	1			Uncoated		Dimer	nsions	(mm	)		
Application	Picture	De	signation	NC3120	NC3225	NC3030	NC5330	NC6315	PC5300	PC8110	PC9030	H01	b	r	ı	d	t	Configuration	Page
_		FGD	300R-03		_	•	_	_	-		ш.	_	3.0	0.3	15.0	2.0	4.0		C36
	FGD		400R-04			•							4.0	0.4	15.0	3.0	4.5	d	C37
			500R-04			•							5.0	0.4	15.0	4.0	5.0		007
																		7*	
ρ		FGM	300R-03										3.0	0.3	15.0	2.0	4.0	d <b>*</b>	C36
Š	FGM		400R-04			•							4.0	0.4	15.0	3.0	4.5	b	C37
) Siro			500R-04										5.0	0.4	15.0	4.0	5.0		
Face Grooving																		7°	
		FMM	300R-03			•				•			3.0	0.3	15.0	2.0	3.91		C36
	FMM		400R-04			•							4.0	0.4	15.0	3.0	3.96	d b	C37
			500R-04							•			5.0	0.4	15.0	4.0	4.42		
	4																	77	
ō		MFMN	300				•						3.0	0.2	18.0	2.0	3.0		C35
ě	MFMN																	b d	C41
5	B																		
Face Grooving	9																	12°	
			300-02-M										3.0	0.2	21.0	2 35	4.83		020
			04-M		Н								3.0	0.4	21.0		4.83		C30 C32
			08-M		Н								3.0	0.8	21.0		4.83		C34
			400-02-M		П								4.0	0.2	21.0	3.3	4.83		C41
Grooving · Turning			04-M										4.0	0.4	21.0	3.3	4.83		
	MGGN-M		08-M										4.0	8.0	21.0	3.3	4.83	Signature of the state of the s	
[. 6			500-02-M										5.0	0.2	26.0	4.1	5.82		
Ä	13		04-M 08-M										5.0	0.4	26.0 26.0	4.1	5.82 5.82		
00			600-02-M										6.0	0.0	26.0	5.0	5.81	7°	
G			04-M										6.0	0.4	26.0	5.0	5.81	,	
			08-M										6.0	0.8	26.0	5.0	5.81		
		MGMN	150-G		•	•			•		•	•	1.5	0.15	16.0	1.2	3.5		C30
			200-G	•	•	•					•	•	2.0	0.2	16.0	1.6	3.5		C32
ng	MGMN-G		250-G		•	•			•		•		2.5	0.2	18.5	2.0	3.85		C34
Grooving	1		300-G	•	•	•	•		•		•		3.0	0.3	21.0				C41
Gro			400-G	•					•		•		4.0	0.3	21.0	3.3	4.83		
			500-G 600-G		Н								5.0 6.0	0.5	26.0	4.1 5.0	5.82 5.81	70	
			000-G										0.0	0.0	20.0	3.0	3.01	ı	
		MGMN	200-M	•	•	•	•		•		•	•	2.0	0.2	16.0	1.6	3.5		C30
			250-M	•	•	•			•		•		2.5	0.2	18.5	2.0	3.85		C32
			300-02-M				•						3.0	0.2	21.0	2.35	4.83		C34
Grooving · Turning			300-M	•	•	•	•	•	•	•	•	•	3.0	0.4	21.0		4.83		C41
Inr	MGMN-M		350-03-M										3.5	0.3	21.0	2.9	4.83	S b	
G	1		400-02-M		_			_	_				4.0	0.2	21.0	3.3	4.83		
ving	1		400-M	•	•	•	•	•	•	•	•	•	4.0	0.4	21.0	3.3	4.83		
00			500-04-M 500-M			-		•			•		5.0	0.4	26.0	4.1	5.82	7°	
Ō			600-M		•			•			•		5.0 6.0	0.8	26.0 26.0	4.1 5.0	5.82 5.81	r	
			800-IVI			_	•	_					8.0	0.8	31.0	6.0	6.52		
													5.0	5.0	51.0	5.0	0.02		

tion								atec				oated		Dim	ensi	ons (	(mm)			
Application	Picture	D	esignation	NC3120	NC3225	NC3030	NC5330	NC6315	PC5300	PC8100 PC9030	된	H05	b	r	ı	d	t	α°	Configuration	Pag
		MGMN	200-02-L										2.0	0.2	16	1.6	3.5	-		C3
			04-L										2.0	0.4	20	1.7	3.5	-		C3
			250-02-L	+		_			_		-		2.5				3.85	-		C3
			300- <u>02-L</u>			_			•				3.0	0.2	21		4.83	-		C3
	MGMN-L		04-L 400-02-L	-							-		3.0	0.4	20	2.3	4.83 4.83	-	d b	
ing	WIGWIN-L		04-L	+					•				4.0	0.2	21		4.83	-		
Grooving			500-03-L	+		Н							5.0	0.4	26	4.1		_	l la market	
בַּ			04-L						•				5.0	0.4	26		5.82	-		
		MGMN	150-015-R										1.5	0.15	16	1.2	3.5	-		C30
			200-02-R										2.0	0.2	16	1.6	3.5	-		C3
			04-R										2.0	0.4	20	1.7	3.5	-		C3
			250-02-R										2.5	0.2		2.0		-		СЗ
			300-02-R	-		•			•				3.0	0.2	21		4.83	-		
off			04-R										3.0	0.4	20	2.3		-		
ing	MOMNIB		400- <u>02-R</u>	-		•			•		-		4.0	0.2	21		4.83	-	d b	
Grooving · Parting off	MGMN-R		04-R 500-04-R			•			•				4.0	0.4	20	4.1	4.83 5.82	-		
<u>.</u>	1		08-R			•							5.0	0.4	26		5.82			
ing	1.80		600-04-R	+									6.0	0.4	26		5.81			
90	1		08-R										6.0	0.4	26		5.81		7°	
		MGMN	150-015-T										1.5	0.15	16	1.2	3.5			000
		IVICIIVIIA	200-T										2.0	0.13	16	1.6	3.5	-		C30
			300-T			•			•				3.0	0.4			4.83			C3
6			400-T			•			•				4.0	0.4	21		4.83	-		C3
in	MCMN T		500-04-T										5.0	0.4	26		5.82	-	d	00.
֡֞֝֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֞֡֞֞֞֞֡֞֡֞	MGMN-T		500-T			П			•				5.0	0.8	26	4.1	5.82	-		
CD	1		600-08-T										6.0	0.8	26	5.0	5.81	-		
Grooving · Turning																			7'	
		MGGN	300- <u>02-A</u> 04-A										3.0	0.2			4.83			C28
			04-A 08-A	+									3.0	0.4	21		4.83			C3
			400-02-A	+		-		-					4.0	0.0	21		4.83			C3
			04-A	+									4.0	0.2	21		4.83			C4
<u>ත</u>	MGGN-A		08-A										4.0	0.4	21		4.83		d b	
Ϋ́			500-02-A	$\top$									5.0	0.2	26		5.82			
Grooving			04-A	+									5.0	0.4	26		5.82			
Ğ	2		08-A											0.8	26		5.82			
																			7°	

# C MGT Series

ion							Coa					Incoated		Dim	ensi	ons (	(mm)			
Application	Picture	D	esignation	NC3120	NC3225	NC3030	NC5330	NC6315	PC5300	PC8100	00000	H01	b	r	ı	d	t	α°	Configuration	Page
		MGMR	300-6D-PS										3.0	0.2	21		4.83	6		C30
			8D-PS										3.0	0.2	21		4.83	5	d	C32
	MGMR-PS		15D-PS	_							4		3.0	0.2	21		4.83	15	b	
			400-4D-PS	-						_	+		4.0	0.3	21	3.3		4		
Parting off			500-4D-PS										5.0	0.3	26	4.1	5.82	4	7"	
iţ		MGML	300-6D-PS								+		3.0	0.2	21.0	2.35	4.83	6		
Pal			8D-PS										3.0				4.83	5	α°	
	MGML-PS		15D-PS										3.0	0.2	21.0	2.35	4.83	15	d	
	M		400-4D-PS										4.0	0.3	21	3.3	4.83	4		
			500-4D-PS										5.0	0.3	26	4.1	5.82	4		
		MGMR	200-6D-PT						•		Ť		2.0	0.2	16	1.6	3.5	6		C30
			300-6D-PT										3.0	0.2	21	2.35	4.83	6	<u> </u>	C32
	MGMR-PT		8D-PT		•								3.0	0.2	21		4.83	8	<b>→</b> 8 • • • • •	
			15D-PT								1		3.0	0.2	21		4.83	15	a	
			400-4D-PT	-							+		4.0	0.3	21		4.83	4		
Parting off			500-4D-PT										5.0	0.3	26	4.1	5.82	4	7'	
rii		MGML	200-6D-PT								Ť		2.0	0.2	16	1.6	3.50	6		
Ра			300-6D-PT				•						3.0	0.2	21	2.35	4.83	6	<u>a°</u>	
	MGML-PT		8D-PT										3.0	0.2	21		4.83	8	- 38k	
			15D-PT										3.0	0.2	21		4.83	15	<del>                                 </del>	
	M		400-4D-PT	-							_		4.0	0.3	21		4.83	4		
			500-4D-PT										5.0	0.3	26	4.1	5.82	4	7'	
		MRGN	300-A								+		3.0	1.5	21.0	2.35	4.83	_		C30
			400-A								-	•	4.0				4.83	-		C31
			500-A								T		5.0	2.5	26.0	4.1	5.82	-		C33
_			600-A								•	•	6.0	3.0	26.0	5.0	5.81	-		C34
튈	MRGN-A		800-A								•	•	8.0	4.0	31.0	6.0	6.52	-		
Aluminum																			77	
		MRMN	200-M	•	•	•							2.0	1.0	16 0	1.5	3.5	_		C30
			300-M	•	•	•	•		•				3.0				4.83	-		~34
			400-M	•	•	•	•			•			4.0				4.83	-		C41
6			500-M			•			•				5.0				5.82	-		371
iii			600-M		•	•	•						6.0				5.81		A STATE BY	
Pro	MRMN-M		800-M			•	•						8.0	4.0	31.0	6.0	6.52	-		
Reliefing Profiling	3																			


# MGEHR/L

For grooving, turning, parting off, relief, profil machining











MGMN	I MGMR		h				H		
MGGN	I MRMN		_	,					R type insert
MRGN	I								(mm)
								Screw	Wrench
D	esignation	H = (h)	W	L	S	Т-мах	Inserts	a) Marie	
MGEHR/L	1616-1.5	16	16	100	16.2	14			
	2020-1.5	20	20	125	20.2	14	MGMN150-G	LTX0514	TW20L
	2525-1.5	25	25	150	25.2	14			
	1212-2	12	12	100	14.25	14	MGMN200-G		
	1616-2	16	16	100	16.25	14	MGMN200-M	MHA0512	HW40L
	2020-2	20	20	125	20.25	14	MGMR200-□□-□□	111111110012	1111102
	2525-2	25	25	150	25.25	14			
	1616-2.5	16	16	100	16.30	16	MGMN250-G		
	2020-2.5	20	20	125	20.30	16	MGMN250-M	MHA0512	HW40L
	2525-2.5	25	25	150	25.30	16			
	1616-3	16	16	100	16.35	18			
	2020-3-T10	20	20	125	20.4	10	MGMN300-M/T		
	2020-3	20	20	125	20.4	18	MGGN300-□□-M		
	2525-3-T10	25	25	150	25.4	10	MRMN300-M		
	2525-3 3232-3-T10	25 32	25 32	150 170	25.4 32.4	18	MGMR300-□□-□□ MGMN300-□□-L/R		
	3232-3-110	32	32	170	32.4	18	Walvii 4300E/11		
	2020-4-T10	20	20	125	20.4	10			
	2020-4-110	20	20	125	20.4	18	MGMN400-M/T	Screw  LTX0514  MHA0512  MHA0516	
	2525-4-T10	25	25	150	25.4	10	MGGN400-□□-M		
	2525-4	25	25	150	25.4	18	MRMN400-M		
	3232-4-T10	32	32	170	32.4	10	MGMR400-□□-□□		
	3232-4	32	32	170	32.4	18	MGMN400-□□-L/R		
	2020-5-T15	20	20	150	20.5	15			
	2020-5	20	20	150	20.5	23	MGMN500-M/T		
	2525-5-T15	25	25	150	25.5	15	MGGN500- M		
	2525-5	25	25	150	25.5	23	MRMN500-M MGMR500-□□-□□		
	3232-5-T15	32	32	170	32.5	15	MGMN500-□□-L/R		
	3232-5	32	32	170	32.5	23	Walkingsoo Erri	BHA0616	HW50L
	2020-6-T15	20	20	125	20.6	15			
	2020-6	20	20	125	20.6	23	MGMN600-M		
	2525-6-T15	25	25	150	25.6	15	MGGN600-□□-M		
	2525-6	25	25	150	25.6	23	MRMN600-M		
	3232-6-T15	32	32	170	32.6	15			
	3232-6	32	32	170	32.6	23			
	2525-8-T15	25	25	150	26.1	15	MDMNIOOO M		
	2525-8 3232-8-T15	25	25 32	150	26.1	28	MRMN800-M MGMN800-M		
	3232-8	32	32	170 170	33.1	16 28	IVIGIVINOUU-IVI		
	2525-6A-T15	25	25	150	25.6	15			
	2525-6A 2525-6A	25	25	150	25.6	23			
	3232-6A-T15	32	32	170	32.6	15	MRGN600-A		
	3232-6A	32	32	170	32.6	23			
	2525-8A-T15	25	25	150	26.1	16			
	2525-8A	25	25	150	26.1	28			
	3232-8A-T15	32	32	170	33.1	15	MRGN800-A		
	3232-8A	32	32	170	33.1	28			




# MGEUR/L

For relief, profil machining



MRMN MRGN







• R type insert

(mm)

D	esignation	H = (h)	W	L	s	Т-мах	Inserts	Screw	Wrench
MGEUR/L	2020-3	20	20	125	23	3			
	2525-3	25	25	150	28	3	MRMN300-M		
	3232-3	32	32	170	35	3			
	2020-4	20	20	125	23	3			
	2525-4	25	25	150	28	3	MRMN400-M		
	3232-4	32	32	170	35	3			
	2020-5	20	20	125	24	4			
	2525-5	25	25	150	29	4	MRMN500-M		
	3232-5	32	32	170	36	4		BHA0616	HW50L
	2020-6	20	20	125	24	4		DHAU010	HWOOL
	2525-6	25	25	150	29	4	MRMN600-M		
	3232-6	32	32	170	36	4			
	2525-8	25	25	150	30	5	MRMN800-M		
	3232-8	32	32	170	37	5	IVIMIVINOU-IVI		
	2525-6A	25	25	150	29	4	MRGN600-A		
	3232-6A	32	32	170	36	4	IVINGINOUU-A		
	2525-8A	25	25	150	30	5	MRGN800-A		
	3232-8A	32	32	170	37	5	IVINGIN800-A		


<sup>◆</sup> Applicable inserts C28~C30

# MGEVR/L

For grooving, turning, profil machining



MGMN MGGN MRMN MRGN





• R type insert

(mm)

Des	signation	H = (h)	w	L	s	Т-мах	Min. machining Dia. (ØD)	Inserts	Screw	Wrench
/IGEVR/L	2020-1.5	20	20	125	23	3	85			
	2525-1.5	25	25	150	28	3	85	MGMN150-G	LTX0514	TW20L
	3232-1.5	32	32	170	35	3	85			
	2020-2	20	20	125	23.5	3.5	65	140141000 14		
	2525-2	25	25	150	28.5	3.5	65	MGMN200-M MGMN200-G		
	3232-2	32	32	170	35.5	3.5	65	Wawn200-a		
	2020-2.5	20	20	125	24	4	65	140141050 14		
	2525-2.5 3232-2.5 2020-3 2525-3	25	25	150	29	4	65	MGMN250-M MGMN250-G		
		32	32	170	36	4	65	WGWIN230-G		
	2020-3	20	20	125	25.5	5	75	MGMN300-M/T		
		25	25	150	30.5	5	75	MGGN300-□-M MRMN300-M		
	3232-3	32	32	170	37.5	5	75	MGMN300-□□-L/R		
	2020-4	20	20	125	25.5	5	70	MGMN400-M/T		
	2525-4	25	25	150	30.5	5	70	MGGN400-□□-M MRMN400-M		
	3232-4	32	32	170	37.5	5	70	MGMN400-□□-L/R	BHA0616	HW50L
	2020-5	20	20	125	27	7	75	MGMN500-M/T	DUANOIO	HVVSUL
	2525-5	25	25	150	32	7	75	MGGN500-□□-M MRMN500-M		
	3232-5	32	32	170	39	7	75	MGMN500-□□-L/R		
	2020-6	20	20	125	27	7	70	MGMN600-M		
	2525-6	25	25	150	32	7	70	MGGN600-□□-M		
	3232-6	32	32	170	39	7	70	MRMN600-M		
	2525-8	25	25	150	34	9	50	MRMN800-M		
	3232-8	32	32	170	41	9	50	MGMN800-M		
	2525-6A	25	25	150	32	7	70	MDCN600 A		
	3232-6A	32	32	170	39	7	70	MRGN600-A		
	2525-8A	25	25	150	34	9	45	MDCN000 A		
	3232-8A	32	32	170	41	9	45	MRGN800-A		


<sup>→</sup> Applicable inserts C28~C30

# C MGT Series

# MGIUR/L

## For relief, profil machining







MRMN MRGN

• R type insert

											(mr
Desi	ignation	ØD	Ød	L	Q	Т-мах	н	S	Inserts	Screw	Wrench
MGIUR/L	3520-3	35	20	150	45	3.5	18	13			
	4025-3	40	25	200	45	3.5	23	15.5	MRMN300-M		
	5032-3	50	32	250	65	3.5	30	19		MHA0512	HW40L
	3520-4	35	20	150	45	3.5	18	13		IVITAU512	HVV4UL
	4025-4	40	25	200	45	3.5	23	15.5	MRMN400-M		
	5032-4	50	32	250	65	3.5	30	19			
	4025-5	40	25	200	45	3.5	23	15.5	MRMN500-M	BHA0616	
	5032-5	50	32	250	65	3.5	30	19	INI-NOCULINIMIN	BHA0620	
	4025-6	40	25	200	45	3.5	23	19	MRMN600-M	BHA0616	
	5032-6	50	32	250	65	3.5	30	19	IVIMIVINOUU-IVI	BHA0620	
	4025-8	40	25	200	45	6.5	23	15.5	MRMN800-M	BHA0616	HW50L
	5032-8	50	32	250	65	6.5	30	19	IVIMIVINOUU-IVI	BHA0620	HVVOUL
	4025-6A	40	25	200	45	3.5	23	15.5	MDONGOO A	BHA0616	
	5032-6A	50	32	250	65	3.5	30	19	MRGN600-A	BHA0620	
	4025-8A	40	25	200	45	5.0	23	18.5	MDONIOO A	BHA0616	
	5032-8A	50	32	250	65	6.5	30	22	MRGN800-A	BHA0620	

<sup>→</sup> Applicable inserts C28~C30

# MGIVR/L

## For grooving, turning, profil machining






MRMN MRGN

MGMN MGGN

ØD Min. machining Dia.





• R type insert

		1									(mm
De	esignation	ØD	Ød	L	Q	Т-мах	Н	S	Inserts	Screw	Wrench
MGIVR/L	2016-1.5	20	16	125	35	3.5	15	11.3		MHB0310	HW25L
	2520-1.5	25	20	150	45	3.5	18	13.1	MGMN150-G	MULAOFIO	1111/401
	2925-1.5	29	25	200	45	3.5	23	16.2		MHA0512	HW40L
	2016-2	20	16	125	35	4.5	15	12.4	MGMN200-G	MHB0310	HW25L
	2520-2	25	20	150	45	4.5	18	14.0	MGMN200-M	MUADE10	LIMAGI
	2925-2	29	25	200	45	4.5	23	17.2	MRMN200-M	MHA0512	HW40L
	2016-2.5	20	16	125	35	4.5	15	12.5	MOMNOFO	MHB0310	HW25L
	2520-2.5	25	20	150	45	4.5	18	15.1	MGMN250-G MGMN250-M	MHA0512	HW40L
	2925-2.5	29	25	200	45	4.5	23	18.2	WIGHNINZSO-IVI	IVITAUS12	HVV4UL
	2520-3	25	20	150	45	5	18	15.6			
	2520-3-T7	25	20	150	49.3	7	18	19.92	MOMNIOGO MA/O/T		
	3125-3	31	25	200	45	6	23	18.9			
	3125-3-T10	31	25	200	45	10	23	18.9	MRMN300-M MGMN300-∏∏-L/R		
	3732-3	37	32	250	65	6	30	21.5	WIGHNINGOO-		
		37	32	250	65	12	30	21.5		MUADE10	LIMAGI
	2520-4	25	20	150	45	6	18	15.6		MHA0512	HW40L
	2520-4-T7	25	20	150	45	7	18	15.6	MOMNIAGO NA/O/T		
	3125-4	31	25	200	45	6	23	18.9	MGMN400-M/G/T MGGN400-□□-M		
	3125-4-T10	31	25	200	45	10	23	19	MRMN400-M MGMN400-∏∏-L/R		
	3732-4	37	32	250	65	6	30	21.5	WIGIVIN400-LILI-L/H		
	3732-4-T12	37	32	250	65	12	30	21.5			
	3125-5	31	25	200	45	8	23	19.4	MGMN500-M/G/T MGGN500-□□-M	BHA0616	
	3732-5	37	32	250	65	8	30	21.5	MRMN500-M MGMN500-□□-L/R	BHA0620	
	3125-6	31	25	200	45	8	23	19.4	MGMN600-MG	BHA0616	
	3732-6	37	32	250	65	8	30	21.5	MGGN600-□□-M MRMN600-M		
	3732-8	37	32	250	65	10	30	23.4	MRMN800-M	BHA0620	HW50L
	4540-8	45	40	300	70	10	37	27.2	MGMN800-M		
		31	25	200	45	8	23	19.4		BHA0616	
	3732-6A	37	32	250	65	8	30	21.5	MRGN600-A		
	3732-8A	37	32	250	65	10	30	23.4		BHA0620	
	4540-8A	45	40	300	70	10	37	27.2	MRGN800-A		


<sup>→</sup> Applicable inserts C28~C30


# C MGT Series (Face Grooving)

## MGFHR/L

## For face grooving machining







• R type insert

	(r	n	m


		11 (6)	14/			T	Q	D	Income	Screw	Wrench
D	esignation	H = (h)	W	L	S	Т-мах	Min	Max	Inserts	97	
MGFHR/L	325-24/35-T10	25	25	150	25.6	10	24	35			
	29/40-T10	25	25	150	25.6	10	29	40			
	34/50-T10	25	25	150	25.6	10	34 50	MFMN300			
	44/70-T10	25	25	150	25.6	10	44	70	IVIFIVINGUU	BHA0616	HW50L
	64/99-T10	25	25	150	25.6	10	64	99		DHAU010	HWOOL
	425-42/63-T15	25	25	150	25.6	15	42	63			
	62/120-T15	25	25	150	25.6	15	62	120	MGMN400-M/T		
	112/200-T15	25	25	150	25.6	15	112	200	MGMN400-□□-L/R		


<sup>→</sup> Applicable inserts C28~C30

## MGFVR/L

### For face grooving machining







• R type insert

(mm)

	esignation	U _ /b)	W		S	Т-мах	Ø	ID D	Inserts	Screw	Wrench
L	esignation	H = (h)	VV	L	3	I-WAX	Min	Max	lliserts	0	
MGFVR/L	325-24/35-T10	25	25	150	36	10	24	35			
	29/40-T10	25	25	150	36	10	29	40			
	34/50-T10	25	25	150	36	10	34	50	MFMN300	MHA0512	HW40L
	44/70-T10	25	25	150	36	10	44	70			
	64/99-T10	25	25	150	36	10	64	99			
	425-44/60-T15	25	25	150	41	15	44	60	MONINGO MET		
	60/120-T15	25	25	150	41	15	60	120	MGMN400-M/T MGMN400-□□-L/R	BHA0616	HW50L
	112/200-T15	25	25	150	41	15	112	200	WIGHNIN-00-		

<sup>◆</sup> Applicable inserts C28~C30

# MGT Series (Face Grooving)


# **FGHH**


FGD

## For face grooving, turning machining



FGM FMM








• R type insert

							_	Q	)D		Screw	Wrench
	Designation		H = (h)	W	L	S	Т-мах	Min	Max	Inserts	9	
FGHH	320R - 25/	/30	20	20	125	20.6	12	25	30			
	30/	/35	20	20	125	20.6	12	30	35	FMM300R-03		
	35/	/48	20	20	125	20.6	12	35	48			
	48/	<b>/60</b>	20	20	125	20.6	22	48	60			
	60/	75	20	20	125	20.6	22	60	75	FGD300R-03		
	75/	/100	20	20	125	20.6	22	75	100	FGM300R-03		
		0/140	20	20	125	20.6	22	100	140		_	
	325R - 25/		25	25	150	25.6	12	25	30			
	30/		25	25	150	25.6	12	30	35	FMM300R-03		
	35/		25	25	150	25.6	12	35	48			
	48/		25	25	150	25.6	22	48	60			
	60/		25	25	150	25.6	22	60	75	FGD300R-03		
		/100	25	25	150	25.6	22	75	100	FGM300R-03		
		0/140	25	25	150	25.6	22	100	140			
	420R - 25/	/30	20	20	125	20.6	12	25	30			
	30/		20	20	125	20.6	12	30	35	FMM400R-04		
	35/	/48	20	20	125	20.6	12	35	48			
	48/	<b>/60</b>	20	20	125	20.6	25	48	60			HW50L
	60/	75	20	20	125	20.6	25	60	75	FGD400R-04		
	75/	/100	20	20	125	20.6	25	75	100	FGM400R-04		
	100	0/140	20	20	125	20.6	25	100	140			
	425R - 25/	/30	25	25	150	25.6	12	25	30		BHA0616	
	30/		25	25	150	25.6	12	30	35			
	35/		25	25	150	25.6	12	35	48			
	48/		25	25	150	25.6	25	48	60			
	60/		25	25	150	25.6	25	60	75	FGD400R-04		
		/100	25	25	150	25.6	25	75	100	FGM400R-04		
		0/140	25	25	150	25.6	25	100	140		_	
	520R - 25/		20	20	125	20.6	12	25	30			
	30/		20	20	125	20.6	12	30	35	FMM500R-04		
	35/		20	20	125	20.6	20	35	40			
	40/		20	20	125	20.6	20	40	48		-	
	48/		20	20	125	20.6	25	48	60			
	60/		20	20	125	20.6	25	60	75	FGD500R-04		
	_	/100	20	20	125	20.6	25	75	100	FGM500R-04		
		0/140	20	20	125	20.6	25	100	140		-	
	525R - 25/		25	25	150	25.6	12	25	30			
	30/		25	25	150	25.6	12	30	35	FMM500R-04		
	35/		25	25	150	25.6	20	35	40			
	40/		25	25	150	25.6	20	40	48		-	
	48/		25	25	150	25.6	25	48	60			
	60/		25	25	150	25.6	25	60	75	FGD500R-04		
		/100	25	25	150	25.6	25	75	100	FGM500R-04		
	100	0/140	25	25	150	25.6	25	100	140			

# **FGVH**









n	гуре	insert
		(mm)

FGI	D FGM	LIVIIVI					ØDMIN			(mm)		
						•	_	Q	ØD		Screw	Wrench
	Designation	on	H = (h)	W	L	S	Т-мах	Min	Max	Inserts	9 Mar	
GVH	320R	- 25/30	20	20	125	20.6	12	25	30			
		30/35	20	20	125	20.6	12	30	35	FMM300R-03		
		35/48	20	20	125	20.6	12	35	48			
		48/60	20	20	125	20.6	22	48	60			
		60/75	20	20	125	20.6	22	60	75	FGD300R-03		
		75/100	20	20	125	20.6	22	75	100	FGM300R-03		
		100/140	20	20	125	20.6	22	100	140			
	325R	- 25/30	25	25	150	25.6	12	25	30		1	
		30/35	25	25	150	25.6	12	30	35	FMM300R-03		
		35/48	25	25	150	25.6	12	35	48			
		48/60	25	25	150	25.6	22	48	60			
		60/75	25	25	150	25.6	22	60	75	FGD300R-03		
		75/100	25	25	150	25.6	22	75	100	FGM300R-03		
		100/140	25	25	150	25.6	22	100	140			
	420R	- 25/30	20	20	125	20.6	12	25	30			
		30/35	20	20	125	20.6	12	30	35	FMM400R-04	BHA0616	
		35/48	20	20	125	20.6	12	35	48			HW50L
		48/60	20	20	125	20.6	25	48	60			
		60/75	20	20	125	20.6	25	60	75	FGD400R-04		
		75/100	20	20	125	20.6	25	75	100	FGM400R-04		
		100/140	20	20	125	20.6	25	100	140			
	/25R	- 25/30	25	25	150	25.6	12	25	30	)		
	72311	30/35	25	25	150	25.6	12	30	35			
		35/48	25	25	150	25.6	12	35	48	1 10110140011-04		
		48/60	25	25	150	25.6	25	48	60			
										FCD400D 04		
		60/75	25	25	150	25.6	25	60	75	FGD400R-04		
		75/100	25	25	150	25.6	25	75	100	FGM400R-04		
		100/140	25	25	150	25.6	25	100	140		-	
	520H	- 25/30	20	20	125	20.6	12	25	30			
		30/35	20	20	125	20.6	12	30	35	FMM500R-04		
		35/40	20	20	125	20.6	20	35	40			
		40/48	20	20	125	20.6	20	40	48		-	
		48/60	20	20	125	20.6	25	48	60			
		60/75	20	20	125	20.6	25	60	75	FGD500R-04		
52		75/100	20	20	125	20.6	25	75	100	FGM500R-04		
		100/140	20	20	125	20.6	25	100	140			
	525R	- 25/30	25	25	150	25.6	12	25	30			
		30/35	25	25	150	25.6	12	30	35	FMM500R-04		
		35/40	25	25	150	25.6	20	35	40			
		40/48	25	25	150	25.6	20	40	48			
		48/60	25	25	150	25.6	25	48	60			
		60/75	25	25	150	25.6	25	60	75	FGD500R-04		
		75/100	25	25	150	25.6	25	75	100	FGM500R-04		
		100/140	25	25	150	25.6	25	100	140			

## KGT/MGT cartridge


### Features

- Compatible and Economical due to divided cartridge & exclusive holder system from existing single body system
- Interchangeable cartridge
  - Various assembly depends on working style
  - Reduce cutting tool costs by over 30%
  - Setting with upper clamp & side screw
- Strong & Stable setting force
  - Simultaneous assembly of insert & cartridge
  - Easy assembly & tool exchange
- Stable assembly system
  - Simple & Superior setting force


# Stable Assembly thanks to double screw & clamp Simple & Strong Setting

## Code system

### Holder



## Cartridge





# C KGT/MGT Cartridge Holder

# MCHR/L (Holder)

For grooving, turning, parting off, relief, profil machining







h h

• R type insert

(mm)

MCER/L MCFR/L

Desig	nation	H = (h)	W	L	s	Q	h1	Cartridge	Clamp	Clamp Screw	Hinge Screw	Clamping Screw	Wrench
MCHR/L	2020	20	20	133	20.7	30	12	KCER/L,					
	2525	25	25	133	25.7	30	7	KCFR/L MCER/L,	CXH8N	DHA0818F	RHA0613	FHGA0618	HW40L
	3232	32	32	153	32.7	-	-	MCFR/L					


<sup>◆</sup> Applicable cartridge C41~C42


## MCVR/L (Holder)


For face grooving, turning machining











• R type insert

MCER/L	
MCFR/L	

Desig	nation	H = (h)	W	L	S	Q	h1	Cartridge	Clamp	Clamp Screw	Hinge Screw	Clamping Screw	Wrench
MCVR/L	2020	20	20	150	38	30	12	KCER/L,					
	2525	25	25	150	43	30	7	KCFR/L MCER/L,	CXH8N	DHA0818F	RHA0613	FHGA0618	HW40L
	3232	32	32	170	50	-	-	MCFR/L					

<sup>→</sup> Applicable cartridge C41~C42

# KCER/L (Cartridge)


KRMN

For grooving, turning, parting off, relief, profil machining



KGGN







• R type insert

(mm)


	Designation	т	L <sub>1</sub>	S <sub>1</sub>	T-MAX		Inserts	Holder
	Designation	'	LI	31	I-WAX	Width	Designation	noidei
KCER/L	3-T16	5.97	44.5	6.35	16	3	KGMN	
	4-T16	5.97	44.5	6.35	16	4	KGMR/L	MCVR/L
	5-T20	5.87	48.5	6.35	20	5	KGGN	MCHR/L
	6-T20	5.82	48.5	6.35	20	6	KRMN	


Applicable inserts C12~C14

# KCFR/L (Cartridge)



KGMN KGMI







• R type insert

(mm

	Designation	_	1.	6.	T	Ø	íD		Inserts	Haldan
	Designation		L <sub>1</sub>	S <sub>1</sub>	Т-мах	Min	Max	Width	Designation	Holder
KCFR/L	3-34/50-T16	8.35	44.5	6.35	16	34	50	3		
	44/70-T16	8.35	44.5	6.35	16	44	70	3		
	64/99-T16	8.35	44.5	6.35	16	64	99	3	KGMN	MCVR/L
	4-44/60-T16	8.35	44.5	6.35	16	44	60	4	KRMN KGGN	MCHR/L
	60/120-T16	8.35	44.5	6.35	16	60	120	4	Radiv	
	112/200-T16	8.35	44.5	6.35	16	112	200	4	1	

<sup>→</sup> Applicable inserts C12~C14

# C MGT Cartridge


# MCER/L (Cartridge)


For grooving, turning, parting off, relief, profil machining



MGMN MGMR MGGN MRMN







• R type insert


(mm)

	Designation		l.	S <sub>1</sub>	T-MAX		Inserts	Holder
Designation		•	L1	31	I-MAX	Width	Designation	noidei
MCER/L	3-T16	6.00	44.5	6.35	16	3	MGMN	
	4-T16	5.97	44.5	6.35	16	4	MGMR/L	MCVR/L
	5-T20	5.87	48.5	6.35	20	5	MGGN	MCHR/L
	6-T20	5.82	48.5	6.35	20	6	MRMN	

<sup>→</sup> Applicable inserts C28~C30

## MCFR/L (Cartridge)





For face grooving, turning machining



• R type insert

(mm)

	D	_		•	<b>T</b>	ØD			Inserts	Halde
	Designation	Т	Lı	S <sub>1</sub>	Т-мах	Min	Min Max Width Designation		Holder	
MCFR/L	3-24/35-T16	8.00	44.5	6.35	16	24	35	3		
	29/40-T16	8.00	44.5	6.35	16	29	40	3		
	34/50-T16	8.00	44.5	6.35	16	34	50	3	MFMN300	MCVR/L MCHR/L
	44/70-T16	8.00	44.5	6.35	16	44	70	3		
	64/99-T16	8.00	44.5	6.35	16	64	99	3		
	4-44/60-T16	7.97	44.5	6.35	16	44	60	4		
	60/120-T16	7.97	44.5	6.35	16	60	120	4	MGMN400	
	112/200-T16	7.97	44.5	6.35	16	112	200	4		

<sup>◆</sup> Applicable inserts C28~C30


## MGT - Machining aluminum wheels

### Features

- Optimally designed inserts for aluminum wheel machining
- Longer tool life when matched with the best grade for application
- Unique clamping mechanism places a strong clamp over the insert
- A variety of insert types for multi application functions

## Code system

### Insert




### Holder



## Various insert types


MRGN type : Full "Round" geometry MRGN-A (For general) MRGN-A5 (For copying) MRGN-AM (Medium finishing) **MRGN-AP (PCD)** MVGN-A (For fine finishing) Reinforced clamping force High rake angle, Sharp cutting edge For ductile cast iron Improved chip control High rake and relief angle

## New clamping system



# C Available Insert for MGT Aluminum Wheel

## Application of aluminum wheels



## Recommended cutting condition


Workpiece	•	Hardness Brinell (HB)	kc (MPa)	vc (m/min)	fn (mm/rev)
Aluminum alloy (Forgod)	Unhardened	50~70	500~600	1,000~2,500	0.1~0.6
Aluminum alloy (Forged)	Hardened	90~110	700~900	300~1,000	0.1~0.5
Aluminum alloy (Cast)	Unhardened	70~80	700~800	300~1,000	0.1~0.5
Aluminum anoy (Cast)	Hardened	80~110	800~950	200~600	0.1~0.4
Copper allo	у	90~110	700~900	300~800	0.1~0.5
Magnesium al	loy	70~80	700~800	300~1,000	0.1~0.5


o				Coated	Uncoated		Dime	nsions	(mm)			
Application	Picture	De	esignation	DP150	G10	b	r	ı	d	t	Configuration	Page
		MVGN	8N-A-R1.2			-	1.2	30.0	6.0	6.9		C46
			8N-A-R1.6			-	1.6	30.0	6.0	6.9		
For Aluminum Wheel	MVGN										35'	
ië		MRGN	6N-A		•	6.0	3.0	26.0	5.0	5.9		C45
Į,			6N-AM			6.0	3.0	26.0	5.0	5.9		C46
or /	MRGN-A		6N-AP			6.0	3.0	26.0	5.0	5.9	d∳	
ŭ.			6N-A5		•	6.0	3.0	26.0	5.0	5.9	b l	
	115		8N-A			8.0	4.0	30.0	6.0	6.5		
			8N-AM			8.0	4.0	30.0	6.0	6.5		
			8N-AP			8.0	4.0	30.0	6.0	6.5	t	
			8N-A5		•	8.0	4.0	30.0	6.0	6.5		

## MGEHR/L









• R type insert (mm)


Designation		H = (h)	h1	W	L	S	Т-мах	Inserts	Screw	Wrench
MGEHR/L	25N-6A	25	7	25	150	25.55	23.5	MRGN6N-A/AP/AM		
	32N-6A	32	8	32	150	32.55	27	WINGINGIN-A/AP/AIVI		
	25N-8A	25	7	25	150	25.55	23.5	MRGN8N-A/AP/AM		
	32N-8A	32	8	32	150	32.55	27	WINGINON-A/AP/AWI		LIMEOL
	25N-6A5	25	7	25	150	25.55	23.5	MDONON AS		HW50L
	32N-6A5	32	8	32	150	32.55	27	MRGN6N-A5		
	25N-8A5	25	7	25	150	25.55	23.5	MDCNON AF		
	32N-8A5	32	8	32	150	32.55	27	MRGN8N-A5		


Applicable inserts C44

## MGEHR/L-15



MRGN





• R type insert (mm)


Designation		H = (h)	h1	W	L	S	Т-мах	Inserts	Screw	Wrench
MGEHR/L	25N-6A-15	25	7	25	150	32.2	20	MRGN6N-A/AP/AM		
	32N-6A-15	32	8	32	150	39.2	25	WINGINGIN-A/AP/AWI		
	25N-8A-15	25	7	25	150	32.2	20	MRGN8N-A/AP/AM		
	32N-8A-15	32	8	32	150	39.2	25	WINGINON-A/AP/AWI		HW50L
	25N-6A5-15	25	7	25	150	32.2	20	MDCNON AF		HVVOUL
	32N-6A5-15	32	8	32	150	39.2	25	MRGN6N-A5		
	25N-8A5-15	25	7	25	150	32.2	20	MDCNON AF		
	32N-8A5-15	32	8	32	150	39.2	25	MRGN8N-A5		


Applicable inserts C44

# MGIUR/L-MR



**MRGN** 





• R type insert (mm)


Designation		ØD	Ød	L	Q	Т-мах	н	s	Inserts	Screw	Wrench
MGIUR/L	6832-8A-MR	68	32	170	65	7	30	26	MRGN8N-A/AM/AP	BULACCOO	LIMEOL
	6832-8A5-MR	68	32	170	65	7	30	26	MRGN8N-A5	BHA0620	HW50L

Applicable inserts C44


# C MGT Aluminum Wheel

## MGIXR/L-MR





ØD Min. machining Dia.




• R type insert

(mm)


D	esignation	ØD	Ød	L	Q	Т-мах	н	s	Inserts	Screw	Wrench
MGIXR/L	7050-8A-MR	70	50	350	80	5.5	46	30.2	MRGN8N-A/AM/AP	BHA0620	HW50L
	7050-8A5-MR	70	50	350	80	5.5	46	30.2	MRGN8N-A5	DHAU020	HWOOL

Applicable inserts C44



De	esignation	H = (h)	W	L	S	Т-мах	α°	Inserts	Screw	Wrench
MGEXR/L	25N-8A-5V	25	25	150	29	23.5	5	MVGN8N-A-R1.2	BHA0620	HW50L
	25N-8A-22.5V	25	25	150	35	27	22.5	MVGN8N-A-R1.6	DHAU02U	HWOOL

Applicable inserts C44



Applicable inserts C44

## **Economical 3-corner insert for high precision grooving**

## TB/TB-M


- Economical 3-corner insert for grooving
- Various cutting edge size ranging from 1.25~4.5 mm
- High accuracy ground insert ensures high precision machining
- Stable chip control optimized for automated grooving process



## Code system

Insert





## TB/TB-M


5	Specification	TB3000R/L, TB4000R/L	TB4000R-M	TB5000N-000-M		
ı	Designation	TB3125R/L~TB3430R/L (Inscribed circle of 9.525 mm) TB4125R/L~TB4430R/L (Inscribed circle of 12.7 mm)	TB4150R-M~TB4450R-M (Inscribed circle of 12.7 mm)	TB5050N-000-M~TB5318-020-M (Inscribed circle of 15.875 mm)		
ı	nsert shape	50		10		
	Chip breaker	Ground chip breaker	Pressed chip breaker	Pressed chip breaker		
	Hand	Right/Left-handed	Right-handed	Neutral		
ıres	Cutting edge width (b)	TB3000: 1.25~4.3 mm TB4000: 1.25~4.5 mm	1.5~4.5 mm	0.5~3.18 mm		
Features	Depth of cut (T-MAX)	TB3000: ~3.5 mm TB4000: ~5.0 mm	~5.0 mm	~6.5 mm		
	Shape	0	X	X		
	Cutting edge width	0	0	0		
(	Chip breaker shape	T.Hat b		A. A. A. A. A. A. A. A. A. A. A. A. A. A		
Apı	plication range	Р	P, M, K	P, M, K		
	Grade	CN2500, PC5300	CN2500, PC5300	PC5300		

# C

## **Technical Information for TB/TB-M**

## TB-M chip breaker


- ullet Minimized cutting force at high speed and high feed ullet Smooth chip evacuation outside each groove
- High precision cutting performance → Exceptional surface finish and accurate dimensions
- ullet Excellent chip flow and cutting results ullet Ideal for automated and unmanned productionw



### TB5-M Chip breaker

- Lowered back area: reduced load of chip evacuation due to minimizing chip friction
- Beveled protruding dot: made regular sized chip curls good chip flow out of the groove by reducing the chip width minimized load for chip evacuation in high depth of cut
- Land: prevented chipping and increased stability in interrupted machining
- Use: for grooving with T-MAX 6.5 mm below, parting and interrupted machining

Designation	TB5050N-M ~TB5120N-M	TB5140N-M ~TB5178N-M	TB5196N-M ~TB5239N-M	TB5247N-M ~TB5287N-M	TB5300N-M ~TB5318N-M
Shape	b			20	20
Cutting edge width (b)	0.5~1.2 mm	1.40~1.78 mm	1.96~2.39 mm	2.47~2.87 mm	3.0~3.18 mm



Designation	TB4150R-M~TB4185R-M	TB4200R-M~TB4228R-M	TB4300R-M~TB4350R-M	TB4400R-M~TB4450R-M
Shape				A 1
Cutting edge width (b)	1.5~1.85 mm	2.0~2.8 mm	3.0~3.5 mm	4.0~4.5 mm

# Technical Information for TB/TB-M C

## Guide for TB

- 1	n	10	m


		ТВ			TB3 / TB4	TB4-M	TB5-M		
Recommended machining method					1	1 -1-	1 -1-		
Cutting edge width W	Dept	h of cut T-	MAX	Recommended feed rate	50		10		
	TB3/TB4	TB4-M	TB5-M	(mm/rev)					
0.50	-	-	2.5		-	-	•		
0.80	-	-	1.6		-	-	•		
1.00	-	-	3.5	0.05 (0.03, 0.1)	-	-	•		
1.04	-	-	2.0	0.05 (0.03~0.1)	-	-	•		
1.20	-	-	2.0		-	-	•		
1.25	2.0	-	2.0		•	-	-		
1.40	2.0	-	6.5		•	-	•		
1.45	2.0	-	-	1	•	-	-		
1.47	-	-	6.5		-	-	•		
1.50	3.5	3.5	6.5		•	•	•		
1.57	-	-	6.5		-	-	•		
1.70	-	-	6.5	0.10 (0.03~0.15)	-	-	•		
1.75	3.5	3.5	-	1	•	•	-		
1.78	-	-	6.5	]	-	-	•		
1.85	3.5	3.5	-	]	•	•	-		
1.96	-	-	6.5	1	-	-	•		
2.00	3.5	3.5	6.5	1	•	•	•		
2.15	3.5	3.5	-		•	•	-		
2.22	6.5	-	6.5		-	-	•		
2.30	3.5	3.5	6.5	1	•	•	•		
2.39	-	-	6.5	1	-	-	•		
2.47	-	-	6.5	]	-	-	•		
2.50	4.0	4.0	6.5	0.12 (0.03~0.2)	•	•	•		
2.65	4.0	4.0	6.5		•	•	-		
2.70	-	-	6.5	1	-	-	•		
2.80	4.0	4.0	-	1	•	•	-		
2.87	-	-	6.5	]	-	-	•		
3.00	4.0	4.0	6.5	1	•	•	•		
3.15	-	-	6.5		-	-	•		
3.18	-	-	6.5	1	-	-	•		
3.30	4.0	-	-	1	•	-	-		
3.50	5.0	5.0	-	0.15 (0.05~0.2)	•	•	-		
4.00	5.0	5.0	-	1	•	•	-		
4.30	5.0	5.0	-	1	•	•	-		
4.50	5.0	5.0	-	1	•	•	-		

## Recommended cutting conditions

Markeiga	Cuada	CN2	2500 (Ceri	met)	PC5300 (Coated)			
Workpiece	Grade	Min	Recommended	Max.	Min	Recommended	Max.	
P	SM□□C type	100	160	220	80	140	200	
P	SCM type	100	150	200	80	130	180	
М	STS type	-	-	-	40	80	150	
K	GC, GCD type	-	-	-	80	130	180	

Recommended cutting speed, vc (m/min)


## Recommended cutting range





# C Technical Information for TB/TB-M

## **○** TB5-M machining range

- $\bullet$  There is a limit to cutting diameters of TB5-M when depth of cuts are over 5  $\mbox{mm}$ (e.g. When cutting with a TB5200N-020-M insert at the depth of 6.2 mm, Ø60 D-MAX is available)
- N.L = No limit







(mm)

	Desimation	b		g	ØD-MAX								
	Designation		r	(T-MAX)	T ≤ 3.0	T ≤ 3.5	T ≤ 4.0	T ≤ 4.5	T ≤ 5.0	T ≤ 5.5	T ≤ 6.0	T ≤ 6.4	T ≤ 6.5
ТВ	5050N- 000-M	0.50	0.00	1.0	-	-	-	-	-	-	-	-	-
	004-M	0.50	0.04	2.5	-	-	-	-	-	-	-	-	-
	5080N- 000-M	0.80	0.00	1.6	-	-	-	-	-	-	-	-	-
	5100N- 006-M	1.00	0.06	3.5	-	-	-	-	-	-	-	-	-
	5104N- 000-M	1.04	0.00	2.0	-	-	-	-	-	-	-	-	-
	5120N- 000-M	1.20	0.00	2.0	-	-	-	-	-	-	-	-	-
	5140N- 000-M	1.40	0.00	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5147N- 000-M	1.47	0.00	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5150N- 010-M	1.50	0.10	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	015-M	1.50	0.15	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5157N- 015-M	1.57	0.15	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5170N- 010-M	1.70	0.10	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5178N- 018-M	1.78	0.18	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5196N- 015-M	1.96	0.15	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5200N- 020-M	2.00	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5222N- 015-M	2.22	0.15	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5230N- 020-M	2.30	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5239N- 015-M	2.39	0.15	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5247N- 020-M	2.47	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5250N- 020-M	2.50	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5270N- 010-M	2.70	0.10	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5287N- 020-M	2.87	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5300N- 000-M	3.00	0.00	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5300N- 020-M	3.00	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	040-M	3.00	0.40	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5315N- 015-M	3.15	0.15	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40
	5318N- 020-M	3.18	0.20	6.5	N.L	N.L	N.L	N.L	N.L	Ø300	Ø170	Ø60	Ø40

### Insert

			Cer	met	Coated		Dime	ensions	(mm)		
Picture	С	Designation	CN2000	CN2500	PC5300	b	g (T-max)	r	w	d	Configuration
	тв	3125R				1.25	1.5	0.2	4.76	9.525	
	(Right- handed)	3145R				1.45	1.5	0.2	4.76	9.525	
	nanaea)	3175R				1.75	2.5	0.2	4.76	9.525	
		3185R				1.85	2.5	0.2	4.76	9.525	
		3200R				2.00	2.5	0.2	4.76	9.525	
		3230R				2.30	3.5	0.3	4.76	9.525	
		3280R				2.80	3.5	0.3	4.76	9.525	
		3330R				3.30	3.5	0.3	4.76	9.525	
		3430R				4.30	3.5	0.4	4.76	9.525	
		4125R	•		•	1.25	2.0	0.2	4.76	12.7	
		4145R	•		•	1.45	2.0	0.2	4.76	12.7	r = b
50		4150R	•		•	1.50	3.5	0.2	4.76	12.7	g
0		4175R	•		•	1.75	3.5	0.2	4.76	12.7	
		4185R	•		•	1.85	3.5	0.2	4.76	12.7	
-		4200R	•		•	2.00	3.5	0.2	4.76	12.7	
		4215R	•		•	2.15	3.5	0.2	4.76	12.7	<del></del>
		4230R	•		•	2.30	3.5	0.2	4.76	12.7	
		4250R	•		•	2.50	4.0	0.3	4.76	12.7	
		4265R	•		•	2.65	4.0	0.3	4.76	12.7	
		4280R	•		•	2.80	4.0	0.3	4.76	12.7	
		4300R	•		•	3.00	4.0	0.3	4.76	12.7	
		4330R	•			3.30	4.0	0.3	4.76	12.7	
		4350R	•			3.50	5.0	0.3	4.76	12.7	
		4400R	•		•	4.00	5.0	0.4	4.76	12.7	
		4430R	•		•	4.30	5.0	0.4	4.76	12.7	
		4450R	•		•	4.50	5.0	0.4	4.76	12.7	
	TB // off	3125L				1.25	1.5	0.2	4.76	9.525	
	(Left- handed)	3145L				1.45	1.5	0.2	4.76	9.525	
		3175L				1.75	2.5	0.2	4.76	9.525	
		3185L				1.85	2.5	0.2	4.76	9.525	
		3200L				2.00	2.5	0.2	4.76	9.525	
		3230L				2.30	3.5	0.3	4.76	9.525	
		3280L				2.80	3.5	0.3	4.76	9.525	
		3330L				3.30	3.5	0.3	4.76	9.525	
		3430L				4.30	3.5	0.4	4.76	9.525	
		4125L				1.25	2.0	0.2	4.76	12.7	
		4145L				1.45	2.0	0.2	4.76	12.7	
-		4150L				1.50	3.5	0.2	4.76	12.7 12.7	
0		4175L				1.75	3.5	0.2	4.76	12.7	
1		4185L 4200L				2.00	3.5	0.2	4.76	12.7	1
~		4200L 4215L				2.15	3.5	0.2	4.76	12.7	
		4215L 4230L				2.13	3.5	0.2	4.76	12.7	
		4250L 4250L				2.50	4.0	0.2	4.76	12.7	
		4265L				2.65	4.0	0.3	4.76	12.7	
		4280L				2.80	4.0	0.3	4.76	12.7	
		4300L				3.00	4.0	0.3	4.76	12.7	
		4300L 4330L				3.30	4.0	0.3	4.76	12.7	
		4350L 4350L				3.50	5.0	0.3	4.76	12.7	
		4400L				4.00	5.0	0.3	4.76	12.7	
		4430L				4.30	5.0	0.4	4.76	12.7	
		4450L				4.50	5.0	0.4	4.76	12.7	
		THUUL				+.50	J.U	0.4	7.70	14.1	

## С тв/тв-м

#### Insert

			Cer	met	Coated		Dime	nsions (	(mm)		
Picture	C	Designation	CN2000	CN2500	PC5300	b	g (T-max)	r	w	d	Configuration
	ТВ	4150R-M	•		•	1.50	3.5	0.20	4.76	12.7	
	(Right- handed)	4175R-M	•		•	1.75	3.5	0.20	4.76	12.7	
	,	4185R-M	•		•	1.85	3.5	0.20	4.76	12.7	
		4200R-M	•		•	2.00	3.5	0.20	4.76	12.7	
		4215R-M	•		•	2.15	3.5	0.20	4.76	12.7	
-		4230R-M	•		•	2.30	3.5	0.20	4.76	12.7	r b
-		4250R-M	•		•	2.50	4.0	0.30	4.76	12.7	
9		4265R-M	•		•	2.65	4.0	0.30	4.76	12.7	
		4280R-M	•		•	2.80	4.0	0.30	4.76	12.7	
		4300R-M	•		•	3.00	4.0	0.30	4.76	12.7	<u> </u>
		4330R-M			•	3.30	4.0	0.30	4.76	12.7	
		4350R-M	•		•	3.50	5.0	0.30	4.76	12.7	
		4400R-M	•		•	4.00	5.0	0.40	4.76	12.7	
		4430R-M	•		•	4.30	5.0	0.40	4.76	12.7	
		4450R-M	•		•	4.50	5.0	0.40	4.76	12.7	
	TB	5050N-000-M			•	0.50	1.0	0.00	4.50	15.875	
	(Neutral)	5050N-004-M			•	0.50	2.5	0.04	4.50	15.875	
		5080N-000-M			•	0.80	1.6	0.00	4.50	15.875	
		5100N-006-M			•	1.00	3.5	0.06	4.50	15.875	
		5104N-000-M			•	1.04	2.0	0.00	4.50	15.875	
		5120N-000-M			•	1.20	2.0	0.00	4.50	15.875	
		5140N-000-M			•	1.40	6.5	0.00	4.50	15.875	
		5147N-000-M			•	1.47	6.5	0.00	4.50	15.875	
		5150N-010-M			•	1.50	6.5	0.10	4.50	15.875	
		5150N-015-M			•	1.50	6.5	0.15	4.50	15.875	
		5157N-015-M			•	1.57	6.5	0.15	4.50	15.875	r b
new		5170N-010-M			•	1.70	6.5	0.10	4.50	15.875	9
10		5178N-018-M			•	1.78	6.5	0.18	4.50	15.875	
18		5196N-015-M			•	1.96	6.5	0.15	4.50	15.875	
		5200N-020-M			•	2.00	6.5	0.20	4.50	15.875	
		5222N-015-M			•	2.22	6.5	0.15	4.50	15.875	<u> </u>
		5230N-020-M			•	2.30	6.5	0.20	4.50	15.875	
		5239N-015-M			•	2.39	6.5	0.15	4.50	15.875	
		5247N-020-M			•	2.47	6.5	0.20	4.50	15.875	
		5250N-020-M			•	2.50	6.5	0.20	4.50	15.875	
		5270N-010-M			•	2.70	6.5	0.10	4.50	15.875	
		5287N-020-M			•	2.87	6.5	0.20	4.50	15.875	
		5300N-000-M			•	3.00	6.5	0.00	4.50	15.875	
		5300N-020-M			•	3.00	6.5	0.20	4.50	15.875	
		5300N-040-M			•	3.00	6.5	0.40	4.50	15.875	
		5315N-015-M			•	3.15	6.5	0.15	4.50	15.875	
		5318N-020-M			•	3.18	6.5	0.20	4.50	15.875	

#### Insert

	Cer	met	Coated		Di	mensio	ons (mr	n)		
	CN2000	CN2500	PC5300	b	g (T-MAX)	r	a°	w	d	Configuration
Р				0.50	1.0	0.04	-	4.50	15.875	
Р				1.00	3.5	0.10	-	4.50	15.875	
Р				1.50	6.5	0.10	-	4.50	15.875	
P				1.50	6.5	0.20	-	4.50	15.875	
P				2.00	6.5	0.10	-	4.50	15.875	<u>r</u> • b
P				2.00	6.5	0.20	-	4.50	15.875	
Р				2.39	6.5	0.15	-	4.50	15.875	
P				2.50	6.5	0.20	-	4.50	15.875	
Р				3.00	6.5	0.20	-	4.50	15.875	- W
.P				1.00	3.5	0.05	6	4.50	15.875	
R-P				1.00	3.5	0.05	15	4.50	15.875	la.
.P				1.50	6.5	0.05	6	4.50	15.875	
R-P				1.50	6.5	0.05	15	4.50	15.875	9
-P R-P				2.00	6.5	0.10	6 15	4.50	15.875 15.875	
										- W -
Р				1.00	3.5	0.05	6	4.50	15.875	
P				1.00	3.5	0.05	15	4.50	15.875	
.P				1.50	6.5	0.05	6	4.50	15.875	
P				1.50	6.5	0.05	15	4.50	15.875	
.P				2.00	6.5	0.10	6	4.50	15.875	
P				2.00	6.5	0.10	15	4.50	15.875	w
Р				1.57	6.5	0.79	-	4.50	15.875	
P				2.00	6.5	1.00	-	4.50	15.875	
P				2.39	6.5	1.20	-	4.50	15.875	
P				3.00	6.5	1.50	-	4.50	15.875	G G G G G G G G G G G G G G G G G G G
P					2.39	2.39 6.5	2.39 6.5 1.20	2.39 6.5 1.20 -	2.39 6.5 1.20 - 4.50	2.39 6.5 1.20 - 4.50 15.875


• : Stock item

## С тв/тв-м

## **TBH**













R type insert





D	almostic n			Dimer	nsions			Income	Clamp	Clamp Screw	Screw	Wrench	Fi.e.
De	esignation	H = (h)	W	L	Q	h <sub>1</sub>	S	Inserts	2		O TIME		Fig.
ТВН	320R/L-23	20	20	125	25.5	-	25	TB3125~3230R/L					
	320R/L-33	20	20	125	25.5	-	25	TB3280~3330R/L					
	320R/L-43	20	20	125	25.5	-	25	TB3430R/L					
	325R/L-23	25	25	150	25.5	-	30	TB3125~3230R/L					
	325R/L-33	25	25	150	25.5	-	30	TB3280~3330R/L					
	325R/L-43	25	25	150	25.5	-	30	TB3430R/L	CS6R1	DHA0617		HW30L	1
	420R/L-23	20	20	125	25.5	-	25	TB4125~4230R/L	CSONI	DHAUGI7	-	HVVSUL	'
	420R/L-33	20	20	125	25.5	-	25	TB4250~4330R/L					
	420R/L-45	20	20	125	25.5	-	25	TB4350~4450R/L					
	425R/L-23	25	25	150	25.5	-	30	TB4125~4230R/L					
	425R/L-33	25	25	150	25.5	-	30	TB4250~4330R/L					
	425R/L-45	25	25	150	25.5	-	30	TB4350~4450R/L					
ТВН	510R/L	10	10	125	25	15	7.8				FTNA0512	TW20L	3
	512R/L	12	12	125	25	13	9.8		_	-	FINAUSIZ	I WZUL	3
	516R/L	16	16	125	26	9	13.8	TB5050~5318N				LIMON	
	520R/L	20	20	125	26	5	17.8		CS6R1	DHA0617	FTNA0516	HW30L, TW20L	2
	525R/L	25	25	150	-	-	22.8					1 VVZUL	

#### The Solution for High-Precision Grooving


## **K Notch**

#### **KORLOY Grooving Tool**

- KORLOY clamping system offers high rigidity for high precision machining
- High-quality cutting edge ensuring long tool life and excellent machinability
- Provides various cutting edge widths for a wide range of selection

#### Code system


Insert



Holder




#### Features of holder



# C Technical Information for K Notch


#### Features of insert



High-quality edge preparation

- Cutting edges in uniform quality
- · Long tool life





[Competitor]

#### Mirror-like rake surface

- Improved resistance to welding and chipping
- Improved surface finish of workpieces



[K Notch]

#### Recommended feed per insert type

Туре		KNG	KNGP	KNR	KNRP	KNB
Insert shape						
Cutting-ed	dge	10'	57	10'	5'4	10
Applicati	on	General grooving	General grooving	Turning profiling	Turning profiling	Blank
Recom-	1st	P, K	M, N, S	P, K	M, N, S	-
mended workpiece	2nd	M, N, S	P, K	M, N, S	P, K	-
	P	0.10 - 0.28	0.08 - 0.25	0.10 - 0.28	0.08 - 0.25	-
Recom- mended	M	0.10 - 0.25	0.08 - 0.25	0.10 - 0.25	0.08 - 0.25	-
feed,	K	0.10 - 0.28	0.08 - 0.25	0.10 - 0.28	0.08 - 0.25	-
fn (mm/ rev)	N	0.01 - 0.30	0.01 - 0.30	0.01 - 0.30	0.01 - 0.30	-
	S	0.05 - 0.15	0.05 - 0.15	0.05 - 0.15	0.05 - 0.15	-

#### Recommended cutting speed per grade

	Modernio	Overde		Recon	nmended cutting speed	l, vc (m/min)	
	Workpiece	Grade	50	100	200	300	600
P	Steel	PC5300		80	200		
	Alloy steel	PC5300	60		160		
М	Stainless steel	PC5300		80 130			
IVI	Stainless steel	PC8110		80	160		
K	Cast iron	PC5300		90	200		
N	Non-ferrous metal	PC5300			150		600
S	Heat-resistant alloy	PC8110	35 65				3

### **○** Insert (Metric)

o					Coa	ated	Uncoated					Dimen	sions					
Eati	Picture	Des	igna	ition	8	9				mm					inch			Configuration
Application			<b>J</b>		PC5300	PC8110	H05	s	W1	r	t	Q	s	W1	r	t	Q	3
		KNG	2M	150R				5.56	1.50	0.19	2.79	13.030	0.219	0.059	0.0075	0.11	0.513	
				200R				5.56	2.00	0.19	2.79	13.030	0.219	0.079	0.0075	0.11	0.513	
				250R				5.56	2.50	0.19	2.79	13.030	0.219	0.098	0.0075	0.11	0.513	55°
				300R				5.56	3.00	0.19	2.79	13.030	0.219	0.118	0.0075	0.11	0.513	
do			3M	150R	•	•		8.74	1.50	0.19	2.79	22.709	0.344	0.059	0.0075	0.075	0.894	s s
Flat Top				200R	•	•		8.74	2.00	0.19	2.79	22.709	0.344	0.079	0.0075	0.11	0.894	r
Ë				250R	•	•		8.74	2.50	0.19	3.81	22.709	0.344	0.098	0.0075	0.15	0.894	w <sub>1</sub>
				300R	•	•		8.74	3.00	0.19	3.81	22.709	0.344	0.118	0.0075	0.15	0.894	
				400R	•	•		8.74	4.00	0.19	3.81	22.709	0.344	0.157	0.0075	0.15	0.894	3° 0
			4M	500R				11.51	5.00	0.20	6.35	28.663	0.453	0.197	0.0079	0.25	1.128	
				600R				11.51	6.00	0.20	6.35	28.663	0.453	0.236	0.0079	0.25	1.128	
		KNGP	2M	150R				5.56	1.50	0.19	2.79	13.030	0.219	0.059	0.0075	0.11	0.513	
				200R				5.56	2.00	0.19	2.79	13.030	0.219	0.079	0.0075	0.11	0.513	_
				250R				5.56	2.50	0.19	2.79	13.030	0.219	0.098	0.0075	0.11	0.513	55°
٥				300R				5.56	3.00	0.19	2.79	13.030			0.0075	0.11	0.513	
C/B Ground			3M	150R	•	•		8.74	1.50	0.19	2.79	22.709	0.344		0.0075	0.075	0.894	
چَ				200R	•	•		8.74	2.00	0.19	2.79	22.709	0.344		0.0075	0.11	0.894	<u></u>
S/B				250R	•	•		8.74	2.50	0.19	3.81	22.709	0.344		0.0075	0.15	0.894	W1
				300R	•	•		8.74	3.00	0.19	3.81	22.709	0.344		0.0075	0.15	0.894	3°
				400R	•	•		8.74	4.00	0.19	3.81	22.709	0.344		0.0075	0.15	0.894	
			4M	500R				11.51	5.00	0.20	6.35	28.663	0.453		0.0079	0.25	1.128	
				600R				11.51	6.00	0.20	6.35	28.663		0.236	0.0079	0.25	1.128	
		KNB	2R					5.56	3.81	-	-	13.030		0.150	-	-	0.513	
			3R					8.74	4.95	-	-	22.709		0.195	-	-	0.894	55°
			4R					11.51	6.48	-	-	28.663	0.453	0.255	-	-	1.128	
Blank																		w <sub>1</sub>

• : Stock item

### **○** Insert (Threading)

ion				Coa	ated				Dim	ensions	6			
Application	Picture	Des	ignation	300	110		mm			inch		Pitch (Ex	cternal)	Configuration
Арр				PC5300	PC8110	s	W1	r	s	W1	r	mm	tpi	
		KNT	2R			5.56	3.81	0.10	0.219	0.150	0.004	0.70-3.00	8-36	
			3R			8.74	4.95	0.17	0.344	0.195	0.007	1.25-4.00	6-20	55°
			4R			11.51	6.48	0.17	0.453	0.255	0.007	1.25-6.25	4-20	s
iling 60°			<u>4R</u>											f 60° W1
Partial Protiling 60°														Internal 60° External
														Partial Profiling 60°

•: Stock item

# C K Notch

### Insert (Inch)


uo				Coa	ated					Dimer	nsions					
Application	Picture	Des	ignation					mm					inch			Configuration
Appli			.9	PC5300	PC8110	s	W1	r	t	Q	s	W1	r	t	Q	
1		KNG	2031R	1	а.	5.56	0.79	0.09	1.27	13.030	0.219	0.031	0.0035	0.05	0.513	
		I	2041R			5.56	1.04	0.09	1.27	13.030	0.219	0.041	0.0035	0.05	0.513	
			2047R			5.56	1.19	0.09	1.27	13.030	0.219		0.0035	0.05	0.513	
			2058R			5.56	1.47	0.19	1.27	13.030	0.219		0.0075	0.05	0.513	
			2062R			5.56	1.57	0.19	2.79	13.030	0.219		0.0075	0.11	0.513	
			2094R			5.56	2.39	0.19	2.79	13.030	0.219		0.0075	0.11	0.513	
			2125R			5.56	3.18	0.19	2.79	13.030	0.219		0.0075	0.11	0.513	
			3047R			8.74	1.19	0.19	1.91	22.709	0.344	0.047	0.0075	0.075	0.894	
			3062R	•	•	8.74	1.57	0.19	2.39	22.709	0.344	0.062	0.0075	0.094	0.894	
			3072R			8.74	1.83	0.19	2.39	22.709	0.344	0.072	0.0075	0.094	0.894	
			3078R	•	•	8.74	1.98	0.19	2.39	22.709	0.344	0.078	0.0075	0.094	0.894	
			3088R			8.74	2.24	0.19	2.39	22.709	0.344	0.088	0.0075	0.094	0.894	55°
			3094R			8.74	2.39	0.19	3.81	22.709	0.344	0.094	0.0075	0.15	0.894	s
Top	A ~		3097R	•	•	8.74	2.46	0.32	3.81	22.709	0.344	0.097	0.0125	0.15	0.894	
Flat Top			3105R			8.74	2.67	0.19	3.81	22.709	0.344	0.105	0.0075	0.15	0.894	
أتر			3110R			8.74	2.79	0.32	3.81	22.709	0.344	0.110	0.0125	0.15	0.894	W1
			3122R			8.74	3.10	0.19	3.81	22.709	0.344	0.122	0.0075	0.15	0.894	3° Q
			3125R	•	•	8.74	3.18	0.19	3.81	22.709	0.344	0.125	0.0075	0.15	0.894	
			3142R			8.74	3.61	0.32	3.81	22.709	0.344	0.142	0.0125	0.15	0.894	
			3156R	•	•	8.74	3.96	0.19	3.81	22.709	0.344	0.156	0.0075	0.15	0.894	
			3178R			8.74	4.52	0.19	3.81	22.709	0.344	0.178	0.0075	0.15	0.894	
			3185R			8.74	4.70	0.57	3.81	22.709	0.344	0.185	0.0225	0.15	0.894	
			3189R	•	•	8.74	4.80	0.57	3.81	22.709	0.344	0.189	0.0225	0.15	0.894	
			4125R	•	•	11.51	3.18	0.19	3.81	28.663	0.453	0.125	0.0075	0.15	1.128	
			4189R			11.51	4.80	0.57	6.35	28.663	0.453		0.0225	0.25	1.128	
			4213R			11.51	5.41	0.19	6.35	28.663	0.453		0.0075	0.25	1.128	
			4219R	-		11.51	5.56	0.57	6.35	28.663	0.453		0.0225	0.25	1.128	
			4250R	-		11.51	6.35	0.57	6.35	28.663	0.453	0.250	0.0225	0.25	1.128	
		KNGP	2031R			5.56	0.79	0.09	1.27	13.030	0.219	0.031	0.0035	0.05	0.513	
			2062R	-		5.56	1.57	0.19	2.79	13.030	0.219	0.062	0.0075	0.11	0.513	55°
pu			2125R			5.56	3.18	0.19	2.79	13.030	0.219	0.125	0.0075	0.11	0.513	s
round			3088R	-		8.74	2.24	0.19	2.39	22.709		0.088	0.0075		0.894	r t
C/B G			3125R 3156R	•	_	8.74 8.74	3.18	0.19	3.81	22.709		0.125	0.0075	0.15	0.894	
ວັ			3189R	•	•	8.74	4.80	0.19	3.81	22.709		0.130	0.0075	0.15	0.894	W1
			4189R			11.51	4.80	0.57	6.35	28.663		0.189	0.0225	0.15	1.128	3° Q
			4250R			11.51	6.35	0.57	6.35	28.663		0.103	0.0225	0.25	1.128	
		KNR	2031R			5.56	1.57	0.79	2.79	13.030	0.219	0.062	0.031	0.11	0.513	
			2047R			5.56	2.39	1.19	2.79	13.030	0.219	0.094	0.047	0.11	0.513	55°
Тор	A ~		3031R	•	•	8.74	1.57	0.79	2.39	22.709	0.344	0.062	0.031	0.094	0.894	s
Round Flat Top			3047R	•	•	8.74	2.39	1.19	3.81	22.709	0.344	0.094	0.047	0.15	0.894	
P			3062R	•	•	8.74	3.18	1.59	3.81	22.709	0.344		0.0625	0.15	0.894	r   -t -
uno			3078R	•	•	8.74	3.96	1.98	3.81	22.709	0.344	0.156	0.078	0.15	0.894	W1
Œ			3094R	•	•	8.74	4.78	2.39	3.81	22.709	0.344	0.188	0.094	0.15	0.894	3° 0
			4125R			11.51	6.35	3.18	6.35	28.663	0.453	0.250	0.125	0.25	1.128	* -
		KNRP	2031R			5.56	1.57	0.79	2.79	13.030	0.219	0.062	0.031	0.11	0.513	\psi^-
pul			2047R			5.56	2.39	1.19	2.79	13.030	0.219	0.094	0.047	0.11	0.513	55°
rou	_		3031R	•	•	8.74	1.57	0.79	2.39	22.709	0.344	0.062	0.031	0.094	0.894	s
B			3047R	•	•	8.74	2.39	1.19	3.81	22.709	0.344	0.094	0.047	0.15	0.894	
Round C/B Ground			3062R	•	•	8.74	3.18	1.59	3.81	22.709	0.344	0.125	0.0625	0.15	0.894	
muc			3078R	•	•	8.74	3.96	1.98	3.81	22.709	0.344	0.156	0.078	0.15	0.894	w1 ///\D
Ro			3094R	•	•	8.74	4.78	2.39	3.81	22.709	0.344	0.188	0.094	0.15	0.894	3° 0
			4125R			11.51	6.35	3.18	6.35	28.663	0.453	0.250	0.125	0.25	1.128	<del>,</del>



## KNSR For grooving, profil machining









KNG KNGP KNT KNR KNRP KNB

				mm					inch				Clamp	Screw	Wrench
Desi	ignation	н	В	F	L1	L2	н	В	F	L1	L2	Insert		9	
KNSR	1010E2	10	10	14	19	70	0.394	0.394	0.551	0.748	2.756				
	1212F2	12	12	16	19	80	0.472	0.472	0.630	0.748	3.150	KNG2□ KNGP2□			
	1616H2	16	16	20	19	100	0.630	0.630	0.787	0.748	3.937	KNR2□	CM74	MHB3010	HW25L
	2020K2	20	20	25	19	125	0.787	0.787	0.984	0.748	4.921	KNB2R KNT2R			
	2525M2	25	25	32	19	150	0.984	0.984	1.260	0.748	5.906				
	2020K3	20	20	25	32	125	0.787	0.787	0.984	1.260	4.921	KNG3			
	2525M3	25	25	32	32	150	0.984	0.984	1.260	1.260	5.906	KNGP3□ KNR3□	CM72LP	MHA0512	HW40L
	3225P3	32	32	32	32	170	1.260	1.260	1.260	1.260	6.693	KNRP3□ KNB3R	GWI72LP	MIHAU512	HVV40L
	3232P3	32	32	40	32	170	1.260	1.260	1.575	1.260	6.693	KNT3R			
	2525M4	25	25	32	35	150	0.984	0.984	1.260	1.378	5.906	KNG4□ KNGP4□			
	3225P4	32	32	32	35	170	1.260	1.260	1.260	1.378	6.693	KNR4□	CM72LP	MHA0512	HW40L
	3232P4	32	32	40	35	170	1.260	1.260	1.575	1.378	6.693	KNB4R KNT4R			



# C Technical Information for Saw Man Saw Man



#### For deep hole grooving/parting off

## **Saw Man**

#### Features of parting insert

- Possible to machine a wide range of workpieces such as steel, cast iron, stainless steel, etc.
- Extended tool life due to low resistance rake angle
- Minimized burr due to minimal Nose R
- Various lead angle available
- Narrow chip curl due to dots on rake surface of insert

			Cutt	ing Speed	d (vc = m/	/min)				Feed	d (fn = mm	/rev)	
Workpiece		C	/D			PVD		Uncoated		Cutt	ing width (	mm)	
	NC3120	NC3030	NCM325	NC5330	PC8110	PC5300	PC6510	ST30A	2	3	4	5	6
SM□□C	80~180			80~180		80~180			0.02~0.15	0.03~0.20	0.08~0.30	0.10~0.4	0.12~0.50
SCM	70~150	70~150	70~150	70~150		70~150			0.02~0.15	0.03~0.20	0.08~0.30	0.10~0.4	0.12~0.50
GC/GCD				50~100			50~100	50~100	0.05~0.12	0.10~0.25	0.10~0.30	0.10~0.35	0.10~0.40
STS			50~120	50~120	50~120	60~140			0.02~0.10	0.03~0.15	0.08~0.25	0.10~0.35	0.12~0.40
Non-ferrous metal (Al, Copper)								200~450	0.05~0.10	0.05~0.20	0.05~0.25	0.05~0.30	0.05~0.35

#### Insert


u								Coa	ated					Uncoated	Dim	ensions (	mm)		
Application	Picture	De	esignation	NC3120	NC3225	NC3030	NCM325	NC5330	PC3035	PC8105	PC8110	PC5300	PC9030	ST30A	W	ı	r	Configur	ation
		SP	160												1.6	7.8	0.16		
			180												1.8	9.3	0.16		
			200		•	•	•	•			•	•	•		2.2	9.3	0.2	R type	Standard
			200R			•							•		2.2	9.3	0.2		
			200L										•		2.2	9.3	0.2		
			300	•	•	•	•	•			•	•	•		3.1	11.3	0.2	<b>M</b>	1000
			300R		•	•	•				•				3.1	11.3	0.2	8*	
<u>0</u>			300L			•									3.1	11.3	0.2	r / w   w	W
100			400	•	•	•	•	•			•	•	•		4.1	11.3	0.25		
ıg			400R			•					•				4.1	11.3	0.25	L type	
Parting tools			400L			•									4.1	11.3	0.25		1
٣			500			•	•	•			•	•			5.1	11.4	0.3		
			500R												5.1	11.4	0.3	4 (100)	
			500L												5.1	11.4	0.3	8°	7.
			600			•		•				•			6.4	11.4	0.35	W r	$W = \pm 0.1$
			600R												6.4	11.4	0.35		
			600L												6.4	11.4	0.35		
			800												8.0	14.06	0.4		
			900												9.6	14.06	0.45		


• : Stock item




# SPB/SPB-S (Blades)









$^{\circ}$	П
J	Г


								(mm)	
Des	signation	н	W	L	h	Inserts	Wre	ench	Fig.
SPB	226	26	1.6	110	21	SP200, 200R/L			
	232	32	1.6	150	25	SP200, 200R/L			
	326	26	2.4	110	21	SP300, 300R/L			
	332	32	2.4	150	25	SP300, 300R/L			
	426	26	3.2	110	21	SP400, 400R/L	014/501		
	432	32	3.2	150	25	SP400, 400R/L	SW50L	-	1
	526	26	4.0	110	21	SP500, 500R/L			
	532	32	4.0	150	25	SP500, 500R/L			
	626	26	5.2	110	21	SP600, 600R/L			
	632	32	5.2	150	25	SP600, 600R/L			
SPB-S	226-S	26	1.6	110	21	SP200, 200R/L			
	232-S	32	1.6	150	25	SP200, 200R/L			
	326-S	26	2.4	110	21	SP300, 300R/L			
	332-S	32	2.4	150	25	SP300, 300R/L			
	426-S	26	3.2	110	21	SP400, 400R/L			
	432-S	32	3.2	150	25	SP400, 400R/L		0)4450	
	526-S	26	4.0	110	21	SP500, 500R/L		SW15S	2
	532-S	32	4.0	150	25	SP500, 500R/L	_	(Separately ordered)	2
	626-S	26	5.2	110	21	SP600, 600R/L		ordered)	
	632-S	32	5.2	150	25	SP600, 600R/L			
	832-S	32	6.8	150	25	SP800			
	932-S	32	8	150	25	SP900			
	8526-S	52.6 6.8 150 45 SP800		SP800					
	9526-S	52.6	8	150	45	SP900			

Applicable inserts C60

## SMBB (Block)








												(mm)
De	esignation	н	W	<b>H</b> 3	L	H1	<b>H</b> 2	W1	В	M	Blades	Wrench
SMBB	1626	16	12	26	86	43	13	30	5.3	3-M6	SPB□26(-S)	
	2026	20	19	26	86	43	9	38	5.3	3-M6	3FD∐20(-3)	
	2032	20	19	32	100	50	13	38	5.3	4-M6	SPB <u></u> 32(-S) KGTB <u></u> 32	HW50L
	2526	25	23	26	86	43	4	42	5.3	4-M6	SPB□26(-S)	
	2532	25	23	32	110	50	8	42	5.3	4-M6	SPB□32(-S)	
	3232	32	30	32	110	54	5	48	5.3	4-M6	KGTB□□32	
	40526	40	41	52.6	130	81.73	22	66	8	4-M8	SPB□526(-S)	HW60L


<sup>→</sup> Applicable inserts C60




## SPH/SPH-S (Holder)









· R type insert

								Wro	ench	(m
De	signation	H = (h)	W	L	Ød	S	Inserts			Fig.
SPH	316R/L	16	16	100	32	16.3	SP300, 300R/L			
	320R/L	20	20	120	40	20.3	SP300, 300R/L			
	325R/L	25	25	150	50	25.3	SP300, 300R/L			
	420R/L	20	20	120	50	20.4	SP400, 400R/L	SW50L	-	1
	425R/L	25	25	150	60	25.4	SP400, 400R/L			
	520R/L	20	20	120	60	20.5	SP500, 500R/L			
	525R/L	25	25	150	70	25.5	SP500, 500R/L			
SPH-S	316R/L-S	16	16	100	32	16.3	SP300, 300R/L			
	320R/L-S	20	20	120	40	20.3	SP300, 300R/L			
	325R/L-S	25	25	150	50	25.3	SP300, 300R/L		SW15S	
	420R/L-S	20	20	120	50	20.4	SP400, 400R/L	-	(Separately	2
	425R/L-S	25	25	150	60	25.4	SP400, 400R/L	1	ordered)	
	520R/L-S	20	20	120	60	20.5	SP500, 500R/L	1		
	525R/L-S	25	25	150	70	25.5	SP500, 500R/L	1		

Applicable inserts C60


#### A solution for parting and deep grooving

## Saw Man-X

- Stable machining in deep grooving applying clamping system with strong three-way V-Rail
- Improved clamping precision and convenient replacing of inserts with using the exclusive wrench

#### Code system

#### Insert




30: 3 mm

40: 4 mm

#### Features

- Three-way V-Rail More stable clamping system
- New treatment on cutting edge Better quality of machining and longer tool life
- · Superior chip breaker Better chip control
- · Exclusive wrench More convenient clamping system



32: 32 mm

## C Technical Information for Saw Man-X

#### Features of chip breaker


- The design of chip breaker and its bump in the back area realize better chip evacuation
- The chip breaker with negaland is used universally

#### Coolant path and guide for chip evacuation

- Inner coolant holder is available
- Guide for chip evacuation

#### Negaland

- Applying for various workpieces
- Stable in interrupted cutting and machining with high depth of cut



#### The second chip breaker in the back area

- Better chip control in machining of workpiece with a bigger diameter
- Preventing damage to holder from chip evacuation

#### Strong land on flank


- Smaller diameter of chip curl makes better chip control
- Higher rigidity of insert

#### Recommended cutting conditions

		Workpie	ece			Cutting of	onditions
ISO	Workpiece	KS	AISI	ISO (DIN)	Grade	vc (m/min)	fn (mm/rev)
	Carbon steel	SM45C	1045	C45	PC5300	80-200	0.08-0.28
Р	Carbon Steet	SIVI45C	1045	C45	PC3035	80-220	0.08-0.28
Р	Alloy steel	steel SCM440		42CrMo4	PC5300	80-160	0.08-0.25
	Alloy Steel	SCIVI440	4140	(42CrMo4)	PC3035	80-180	0.08-0.25
М	Stainless steel	sinless steel STS304 304			PC5300	80-190	0.06-0.20
		STS316	316	X5CrNiMo17-12-2	PC5300	80-190	0.06-0.20
	Cuay aget iven	00050	NeOCD	250	PC8110	100-220	0.10-0.28
v	Gray cast iron	GC250	No35B	(GG25)	PC5300	100-200	0.10-0.28
K	Nodular graphite	000500	00 55 00	450.40	PC8110	80-200	0.10-0.25
	cast iron	GCD500	80-55-06	450-10	PC5300	80-180	0.10-0.25
_	LIDOA	l 1 740	7740	45450.0	PC8110	35-65	0.05-0.15
S	HHSA	HRSA Inconel 718 7718	15156-3	PC5300	25-55	0.05-0.15	

#### Cutting edge width and T-MAX by items

⊚: First recommendation ⊝: Second recommendation




#### Insert

Application	Figure Picture	Designation			Coated					Configuration
Applic	Picture	۱ ۱	Designation	PC3035	PC5300	PC8110	W	r	L	Configuration
		KSP	200-020-N	•	•	•	2.0	0.20	11.0	
g			300-020-N	•	•	•	3.0	0.20	12.0	
Parting			400-025-N	•	•	•	4.0	0.25	12.5	
g.			500-025-N	•	•		5.0	0.25	13.5	
			600-035-N	•	•		6.0	0.35	14.5	r / +   W   -









(mm)


	Designation	Cutting edge width	н	W	L	h	Т-мах	Wrench
KSPB	2026	2	26	1.6	110	21	25	
	2032	2	32	1.6	150	25	26	
	3026	3	26	2.4	110	21	36	CW08
	3032	3	32	2.4	150	25	60	CVVU8
	4026	4	26	3.2	110	21	36	
	4032	4	32	3.2	150	25	60	
	5026	5	26	4.0	110	21	40	
	5032	5	32	4.0	150	25	60	CW10
	6026	6	26	5.2	110	21	60	CW10
	6032	6	32	5.2	150	25	60	

Applicable inserts C64

## SMBB (Block)








											(11111)
De	signation	н	w	Нз	L	<b>H</b> 1	<b>H</b> 2	<b>W</b> 1	В	М	Wrench
SMBB	1626	16	12	26	86	43	13	30	5.3	3-M6	
	2026	20	19	26	86	43	9	38	5.3	3-M6	
	2032	20	19	32	100	50	13	38	5.3	4-M6	HW50L
	2526	25	23	26	86	43	4	42	5.3	4-M6	
	2532	25	23	32	110	50	8	42	5.3	4-M6	
	3232	32	30	32	110	54	5	48	5.3	4-M6	

Applicable inserts C64



## KSPH (Shank)







С	Designation	Cutting edge width	н	W	L	Ød	S	Wrench
KSPH	216R/L	2	16	16	100	46	16.2	
	220R/L	2	20	20	120	48	20.2	
	225R/L	2	25	25	150	50	25.2	
	316R/L	3	16	16	100	52	16.2	CW08
	320R/L	3	20	20	120	54	20.2	CVVU8
	325R/L	3	25	25	150	56	25.2	
	420R/L	4	20	20	120	64	20.4	
	425R/L	4	25	25	150	66	25.4	
	520R/L	5	20	20	120	74	20.4	
	525R/L	5	25	25	150	76	25.4	CW10
	625R/L	6	25	25	150	76	25.4	


Applicable inserts C64

#### Six kinds of inserts can be used in one holder for various operations

## **Fine Tools**

- Strong clamping system and specially designed insert are suitable for small diameter machining
- Six kinds of inserts can be clamped in one holder for various operations
- Guaranteed long tool life due to good toughness substrate with new TiAIN
- High accuracy ground insert ensures high precision machining
- ◆ Application range · Internal grooving, Profiling, Threading and Boring at Ø8 mm~Ø16 mm












#### Recommended cutting condition

	Cuada			Cutting Condition	n	
Workpiece	Grade (PC130)			Min. machining Dia. (Ø	Dmin)	
	(FC130)		Ø8	Ø11	Ø14	Ø16
On who are ado al		vc (m/min)	70~120	70~120	70~120	70~120
Carbon steel	0	fn (mm/rev)	0.01~0.04	0.01~0.05	0.02~0.05	0.02~0.06
Allowated	0	vc (m/min)	70~120	70~120	70~120	70~120
Alloy steel		fn (mm/rev)	0.01~0.02	0.01~0.04	0.02~0.04	0.02~0.05
Cast iron	0	vc (m/min)	60~100	60~100	60~100	60~100
Cast Iron		fn (mm/rev)	0.01~0.05	0.01~0.05	0.02~0.05	0.02~0.05
Non formano allan		vc (m/min)	100~180	100~180	100~180	100~180
on-ferrous alloy	0	fn (mm/rev)	0.02~0.06	0.02~0.06	0.02~0.06	0.02~0.06

- In case of chattering, reduce the cutting speed and feed
   To find the optimal cutting conditions, advise to gradually increase from the lowest cutting condition of the above recommendation
   In case of the unilateral grooving depth over 1 mm, work to the step feed rate

#### Clamping system



# C Fine Tools

#### Insert

Picture   Pict	ion		Coated Dimensions (mm)												
NFIG   G80/SFR/L	licati	Picture	De	signation	PC5300									_	Configuration
NFIG   G80/SFR/L	App				R L	ØD	b	r	S	g	Ød <sub>2</sub>	t	Pitch	f	
BOORSERIL			NFTG	08075R/L	•	8	0.75	-	7.75	1.3	5.9	3.85	-	-	
					•	8	0.85	-	7.75	1.3	5.9	3.85	-	-	1
Bell File				08095R/L	•	8	0.95	-	7.75	1.3	5.9	3.85	-	-	
					•	8	1.21	-	7.75	1.3		3.85	-	-	
BORTIFIAL								-					-	-	
B08202PNL														-	_
11075RJL															-
11085RAL						_									-
11095FPL						_									-
															-
Page														-	-
11171RJL					•	_		-					-	-	1
11202RJ_       11   2.02   1.07   2.6   8.0   4.9				11152 R/L	•	11	1.52	-	10.7	2.6	8.0	4.9	-	-	1
Page   Page				11171R/L	•	11	1.71	-	10.7	2.6	8.0	4.9	-	-	
11252PL						11		-	10.7	2.6	8.0	4.9	-	-	
14141R/L   0						_							-	-	,
14141R/L   0	ing														Ød2
14141R/L   0	00					-									
14141R/L   0	g					_									s
14141R/L   0	rna					_									
14141R/L   0	nte				_										ØD Min. machining Dia
14171R/L					•			-					-	-	t
14202R/L				14152R/L	•	14	1.52	-	13.5	4.3	9.0	5.85	-	-	1 11
14252R/L				14171R/L	•	14	1.71	-	13.5	4.3	9.0	5.85	-	-	
14302R/L					•	14	2.02	-	13.5	4.3	9.0	5.85	-	-	
16075R/L						_							-	-	
16085R/L						_									_
16095R/L								-							_
16121R/L					_	_									-
16141R/L					_	_									-
16171R/L     16   1.71   - 15.7   4.6   11.0   5.8   -   -						-								-	-
16252R/L     16   2.52   - 15.7   4.6   11.0   5.8   -   -				16171R/L	•	16	1.71	-	15.7	4.6	11.0	5.8	-	-	1
16302R/L   16   3.02   15.7   4.6   11.0   5.8   -   -				16202R/L	•	16	2.02	-	15.7	4.6	11.0	5.8	-	-	
16352R/L     16   3.52   - 15.7   4.6   11.0   5.8   -   -					•	16	2.52	-	15.7	4.6	11.0	5.8	-	-	
NFTT   0805MR/L					•	16		-					-	-	_
NFTT   0805MR/L						-									
D810MR/L   ■   8			NICTT		_	-									
D815MR/L			INCII		_										-
1110MR/L   111   -   10.7   -   8.0   4.9   1.0   1.2															_
1115MR/L   111   -   10.7   -   8.0   4.9   1.5   1.2     1120MR/L   111   -   10.7   -   8.0   4.9   2.0   1.2     1125MR/L   111   -   10.7   -   8.0   4.9   2.5   1.2     1410MR/L   14   -   13.5   -   9.0   5.85   1.0   1.2     1415MR/L   14   -   13.5   -   9.0   5.85   1.5   1.2     1420MR/L   14   -   13.5   -   9.0   5.85   2.0   1.2     1425MR/L   14   -   13.5   -   9.0   5.85   2.5   1.2     1425MR/L   16   -   15.7   -   11.0   5.8   1.5   1.2     1610MR/L   16   -   15.7   -   11.0   5.8   2.0   1.2     1625MR/L   16   -   15.7   -   11.0   5.8   2.5   1.2     1630MR/L   16   -   15.7   -   11.0   5.8   3.0   1.5     1635MR/L   16   -   15.7   -   11.0   5.8   3.5   1.6     1635MR/L   16   -   15.7   -   11.0   5.8   3.5   1.6     1.5     1.					_	-									
1125MR/L   11					•	11	-	-		-					
1410MR/L       ●       14       -       -       13.5       -       9.0       5.85       1.0       1.2         1415MR/L       ●       14       -       -       13.5       -       9.0       5.85       1.5       1.2         1425MR/L       ●       14       -       -       13.5       -       9.0       5.85       2.0       1.2         1610MR/L       ●       16       -       -       15.7       -       11.0       5.8       1.0       1.2         1615MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.5       1.2         1625MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.5       1.2         1630MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.5       1.2         1635MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.5       1.2         1635MR/L       ●       16       -       -       15.7       -       11.0       5.8       3.5       1.6 </th <th></th> <th></th> <th></th> <th>1120MR/L</th> <th>•</th> <th>11</th> <th>-</th> <th>-</th> <th>10.7</th> <th>-</th> <th>8.0</th> <th>4.9</th> <th colspan="2">2.0 1.2</th> <th>Ød2</th>				1120MR/L	•	11	-	-	10.7	-	8.0	4.9	2.0 1.2		Ød2
1415MR/L				1125MR/L	•	11	-	-	10.7	-	8.0	4.9	2.5	1.2	
1610MR/L	ng				_		-	-		-					
1610MR/L	adi														
1610MR/L	hre				_										
1615MR/L						-									∫ Min. machining Dia
1620MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.0       1.2         1625MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.5       1.2         1630MR/L       ●       16       -       -       15.7       -       11.0       5.8       3.0       1.5         1635MR/L       ●       16       -       -       15.7       -       11.0       5.8       3.5       1.6						_									- t
1625MR/L       ●       16       -       -       15.7       -       11.0       5.8       2.5       1.2         1630MR/L       ●       16       -       -       15.7       -       11.0       5.8       3.0       1.5         1635MR/L       ●       16       -       -       15.7       -       11.0       5.8       3.5       1.6						-									
1630MR/L															-
<b>1635MR/L</b> ● 16 15.7 - 11.0 5.8 3.5 1.6						-	-								-
<b>1640MR/L</b> ● 16 15.7 - 11.0 5.8 4.0 1.8				1635MR/L	•	16		-	15.7		11.0	5.8	3.5	1.6	
				1640MR/L	•	16	-	-	15.7	-	11.0	5.8	4.0	1.8	

#### Insert


ion				ated			Dime	ensions (	(mm)					
Application	Picture	De	signation	PC5	300	D	b	r	s	g	Ød <sub>2</sub>	t	Configuration	
Ap				R	L		b	'	3	9	Øu2	•		
		NFTF	08082R/L	•		8	0.82	0.41	7.75	1.3	5.9	3.85		
			08122R/L	•		8	1.22	0.61	7.75	1.3	5.9	3.85		
			00102102	•		8	1.82	0.91	7.75	1.3	5.9	3.85		
		11082R/L			•		11	0.82	0.41	10.7	2.6	8	4.9	
			11122R/L	•		11	1.22	0.61	10.7	2.6	8	4.9		
		11182	11182R/L	•		11	1.82	0.91	10.7	2.6	8	4.9	Ød2	
			11202R/L	•		11	2.02	1.01	10.7	2.6	8	4.9		
ng			11302R/L	•		11	3.02	1.51	10.7	2.6	8	4.9		
Profiling			14122R/L	•		14	1.22	0.61	13.5	4.3	9	5.85		
౼			14182R/L	•		14	1.82	0.91	13.5	4.3	9	5.85		
			14202R/L	•		14	2.02	1.01	13.5	4.3	9	5.85	ØD Min. machining Dia.	
			14222R/L	•		14	2.22	1.11	13.5	4.3	9	5.85	t	
		143		•		14	3.02	1.51	13.5	4.3	9	5.85		
	16182R/L 16222R/L 16302R/L		16182R/L	•		16	1.82	0.91	15.7					
		16222R/L	•		16	2.22	1.11	15.7	4.6	11	5.8			
		16302R/L	•		16	3.02	1.51	15.7	4.6	11	5.8			
			16402R/L	•		16	4.02	2.01	15.7	4.6	11	5.8		

• : Stock item

## **NFTIH**









					•		<u>' L</u>			Fig. 2	•  -	type insert (mm)
Des	signation	ØD	Ød	L	Q	Т-мах	н	s	Inserts  NFTG: Grooving NFTT: Threading NFTF: Forming	Screw	Wrench	Fig.
NFTIH	08206C	8	6	65	-	1.0	4	4.8				
	08212C	8	12	70	16	1.0	10	4.8	NFTG08□□□R/L			
	08312C	8	12	80	24	1.0	10	4.8	NFTT08	PTKA02508	TW08P	1
	08312S	8	12	80	24	1.0	10	4.8	NFTF08	1 110402500	1 44001	'
	08412C	8	12	90	32	1.0	10	4.8				
	08512C 11208C 11212C	8	12	100	40	1.0	10	4.8				
		11	8	80	-	2.3	7	6.7				
		11	12	75	22	2.3	11	6.7	NFTG11□□□R/L			
	11312C		12	95	33	2.3	11	6.7	NFTT11 R/L	PTKA03510	TW15P	2
	11312S	11	12	95	33	2.3	11	6.7	NFTF11 \B\B\B\B\B\B\B\B\B\B\B\B\B\B\B\B\B\B\	1 11XA03310	1 44 131	
	11412C	11	12	110	44	2.3	11	6.7				
	11512C	11	12	120	55	2.3	11	6.7				
	14012C	14	12	75	20	4.0	11	9.0				
	14016C	14	16	75	20	4.0	15	9.0				
	14112C	14	12	100	34	4.0	11	9.0	NFTG14□□□R/L			
	14116C	14	16	100	34	4.0	15	9.0	NFTT14 \B\B\R/L	PTKA0412	TW15P	2
	14212C	14	12	110	45	4.0	11	9.0	NFTF14 \B\B\C\L	FIRAU412	IWISE	-
	14216C	14	16	110	45	4.0	15	9.0				
	14312C	14	12	130	64	4.0	11	9.0				
	14316C	14	16	130	64	4.0	15	9.0				
	16312C	16	12	130	48	4.3	11	10.2				
	16312S 16412C 16512C 16316C	16	12	130	48	4.3	11	10.2				
		16	12	130	64	4.3	11	10.2	NFTG16□□□R/L			
		16	12	150	80	4.3	11	10.2	NFTT16□□□R/L	PTKA0512	TW20P	2
		16	16	130	48	4.3	15	10.2	NFTF16□□□R/L		. ***	
	16416C	16	16	130	64	4.3	15	10.2				
	16516C	16	16	150	80	4.3	15	10.2				


# C Grooving Tools





IG





· R type insert

	IG				_		7			(mm)
	Designation	ØD	Ød	н	L	Q	s	Inserts	Screw	Wrench
IGH	214R	14	16	15	150	25	6.6			
	216R	16	16	15	150	30	7.6	IG125~280	FTKA02565	TW07P
	220R	20	20	18	200	40	9.6			

Applicable inserts C70

#### Insert


e e				Coated			U	Uncoated			Dime	nsions	(mm)		
Application	Picture		Designation		NC3120	NC3225	H01	G10	ST30A	b	g	t	d	d1	Configuration
<u>D</u> E		IG	125R						•	1.25	1.5	3.18	6.35	2.8	+ - b - t -
S.			145R						•	1.45	1.5	3.18	6.35	2.8	
grooving	(6)		175R						•	1.75	1.5	3.18	6.35	2.8	
<u>a</u>			200R						•	2.0	2.3	3.18	6.35	2.8	d1
Internal			230R						•	2.3	2.3	3.18	6.35	2.8	
≟			280R						•	2.8	2.3	3.18	6.35	2.8	d =

• : Stock item











• R type insert


(mm)

	Dani:		11 (6)	347		٥	,	5	ins	erts	Clamp	Clamp Screw	Screw	Locator	Wrench
	Desi	gnation	H = (h)	W	-	¥	*	**	*	**		<b>6</b>			
Ì	DBH	320R	20	20	150	40	22.3	22.8	DB300	DB400	CGH5R1	MHA0512	MUDO410	LD34	HW30L HW40L
		325R	25	25	150	40	27.3	27.8	DC300	DC400	CGHShT	MINAUSTZ	WINDU410	LD34	HWOOL HWAOL
		520R	20	20	150	40	23.8	24.3	DB500	DB600	CGH5R2	MHA0512	MUDO410	LD56	HW30L HW40L
		525R	25	25	150	40	28.8	29.3	DC500	DD000	CGHShZ	IVITAU512	IVINDU410	LD56	HVV3UL HVV4UL
		720R	20	20	150	40	25.8	26.3	DB700	DROOD	CCHEDS	MUAGE12	MUDO410	I D70	U/V/201 U/V/401
		725R	25	25	150	40	30.8	31.3	DB/00	DB600	Cariona	WITHUSTZ	WIND0410	LD/0	HVV30L HVV40L
		720R	20	20	150	40	25.8	26.3	DB700	DB800	CGH5R3	MHA0512	MHB0410	LD78	HW30L F

→ Applicable inserts C70

#### Insert

on				Cermet		Coated	l	Unco	oated		Dimensi	ons (mm	1)	
Application	Picture	С	Designation	CN2000	NC3215	NC3120	NC3225	HOH	G10	b	ı	t	r	Configuration
		DB	300							3.0	20	7.5	0.2	
			400							4.0	20	7.5	0.2	b
			500							5.0	20	7.5	0.2	
			600							6.0	20	7.5	0.2	t
g			700							7.0	20	7.5	0.2	
Grooving			800							8.0	20	7.5	0.2	5°
9		DC	300							3.0	20	7.5	0.2	
<u>ত</u>	- Alle		400							4.0	20	7.5	0.25	b
			500							5.0	20	7.5	0.3	
														5°



Des	ignation	ØD	Ød	н	L	Q	s	Inserts	Clamp	C-ring	Screw	Pin	Wrench
GFIP	316R/L	20	16	15	150	17	11		CH5R2	CR04	CHX0513	PN0310	HW25L
	320R/L	26	20	18	150	22	13	GW110~300R/L,BF3	CHORZ	Ch04	CHXUSIS	FINUSTU	⊓vv23L
	325R/L	32	25	23	200	22	17	GWIIU~300H/L,DF3		R2 CR05	CHX0616	DNOOTO	HW30L
	340R/L	50	40	37	300	32	27		CH6R2				
	525R/L	32	25	23	200	22	17	GW315~500R/L.BF5	CHORZ	Chub	CHXU010	FINUSTU	HWOUL
	540R/L	50	40	37	300	32	27	GVV313~300H/L,DF3					
	840R/L	50	40	37	300	32	27	GW600~800R/L,BF8	CS8R1	-	DHA0820	PN0314	HW40L

Applicable inserts C71

#### Insert

uo				Unc	oated		[	Dimensi	ons (mn	1)		
Application	Picture	De	esignation	S1	730A	b	g	W	I	t	r	Configuration
		BF	-3		•			3.1	16.4	5.26	-	
포			-5					5.1	22.4	6.26	-	
Blank			-8					8.1	27.4	7.26	-	
<u> </u>												11°
				R	L							
		GW	110R/L	•	•	1.1	2.1	3.1	16	5.0	0.2	
			130R/L	•	•	1.3	2.3	3.1	16	5.0	0.2	
			160R/L	•	•	1.6	2.6	3.1	16	5.0	0.2	
			185R/L	•	•	1.85	2.9	3.1	16	5.0	0.2	
<u>p</u>			215R/L	•	•	2.15	3.2	3.1	16	5.0	0.2	b w
Grooving	1		265R/L	•	•	2.65	3.7	3.1	16	5.0	0.2	9
5			300R/L	•	•	3.0	4.0	3.1	16	5.0	0.2	
ര			315R/L	•	•	3.15	4.2	5.1	22	6.0	0.3	
			415R/L		•	4.15	5.2	5.1	22	6.0	0.3	110
			500R/L			5.0	6.0	5.1	22	6.0	0.3	
			600R/L			6.0	7.0	8.1	27	7.0	0.3	
			800R/L			8.0	9.0	8.1	27	7.0	0.3	


<sup>• :</sup> Stock item

<sup>•</sup> Use right-hand insert for left-hand holder


Code system	Configuration
M F G N 4 - 0.5R - 30D  ① Wulti ② Forming ③ Feed Direction ② Degree: 30°  ③ Grinding ⑤ Nose Radius: 0.5	Ex) MFGN4-0.5R-30D
MFGN4 - 0.5R - L 50 D - R 30D  ① Refer to No. 1 ② Nose Radius: 0.5 ③ Left ⑤ Right ⑥ Degree > 30°	Ex) MFGN4-0.5R-L50D-R30D
MFGN4 - 2.0 - R 020 250 - L 105 335 ① ② ② ④ ⑤ ⑥ ⑦ ⑧ ① Refer to No. 1 ② Width of cutting edge: 2.0mm ③ Right ③ Nose Radius: 0.20 ⑦ Nose Radius: 1.05 ⑧ Degree: 25.0° ⑥ Left	25.0° 25.0° 25.0° 35.5° Ex) MFGN4-2.0-R020250-L105338
MFGN5 - 4.0R F 3 S Refer to No. 1	Ex) MFGN5-4.0RF
MFGN5 - 4.0R B 3  ① Refer to No. 1 ② Radius: 4.0 ③ Back(Concave)	Ex) MFGN5-4.0RB
MFGN5 - 4.0 - R 005 - L 030 ① ③ ④ ⑤ ⑥  ① Refer to No. 1 ② Width of cutting edge: 4.0 mm ③ Right ⑥ Nose Radius: 0.05 ⑤ Left ⑥ Nose Radius: 0.30	Ex) MFGN5-4.0-R005-L030
MFGN5 - 4.0 - 0.05 R  ① Refer to No. 1 ② Width of cutting edge: 4.0 mm ③ Nose Radius: 0.05	4.0 R0.05 TYP Ex) MFGN5-4.0-0.05R
MFG R 5 - 4.0 - 5D - R 002 - L 115  ① ② ③ ④ ④ ⑤ ⑥ ⑦ ⑧ ⑨  ① Refer to No. 1 ② Right ③ Clamp part: 5mm ④ Width of cutting edge: 4.0mm ⑤ Lead angle: 5° ⑥ Right ⑦ Nose Radius: 0.02 ⑧ Left ⑨ Nose Radius: 1.15	4.0 Ex) MFGR5-4.0-5D-R002-L115
MFG L 5 - 4.0 - 15D - 1.5R  ① ② ③ ④ ④ ⑤ ⑥  ① Refer to No. 1 ② Left ③ Clamp part: 5 mm ④ Width of cutting edge: 4.0 mm ⑤ Lead angle: 15° ⑥ Right Nose Radius: 1.5	4.0 Ex) MFGL5-4.0-15D-1.5R
MFG R 5 - 4.10 - 25D - R012 - L000  ① ② ③ ④ ⑤ ⑥ ⑦  ① Refer to No. 1 ② Right ③ Clamp part: 5mm ⑥ Right Nose Radius: 0.0	Ex) MFGR5-4.10-25D-R012-L000


## Special Order Form for V-Pulley Insert C


#### Code system




#### Insert for machining of pulley












KP27064-R0.35-N4 (Former: DF356-4B)








KP27064-R0.375-N5 (Former: DF356-5B)




**UF320** 



## **THREADING**

Korloy threading tools are available for machining various shapes of thread at various pitches while ensuring high quality performances



#### **Threading Code System**

D02 Threading Holder Code SystemD02 Threading Insert Code System

## **Technical Information for Threading**

D03 Technical Information for ThreadingD09 Threading Insert with Chip Breaker

#### **Thread Inserts**

D24

D30

**D24** American ACME (ACME) **D25** Stub ACME (STACME) **D26** UNJ (Unified Constant Thread) **D28** American Buttress (ABUT) **D28** British Buttress (BBUT) **D29** Metric Buttress (SAGE)/API **D30** API Buttress Casing (BUT) D30 API Round Casing & Tubing (APIRD)

Extreme Line Casing (EL)

Trapez DIN103 (TR)

#### **Thread Inserts**

**D23** 

D10 Partial profile 60° D11 Partial profile 55° D12 ISO Metric **D16** American UN (UN, UNC, UNF, UNEF, UNS) D18 Whitworth (BSW, BSF, BSP, BSB) British Standard Pipe Thread **D22** (BSPT) **D22** National Pipe Thread (NPT) **D23** National Pipe Threads-Dryseal (NPTF)

Round DIN405 (RD)

#### **Thread Holders**

D31 External HolderD32 Internal HolderD33 Vertical Type Holder

#### **Thread Milling**

D34 Technical Information for Thread Milling
 D44 Thread Milling Insert
 D49 Thread Milling Holder

### Threading holder code system






E: For External I: For Internal



R: Right handed L: Left handed



8, 10, 12, 16, 20, 25, 32, 40, 50



N: No shim required

10, 12, 13, 16, 20, 25, 32, 49, 50, 60

\*Refer to the specification for shank diameter information



11: d = 6.35

16: d = 9.525

22: d = 12.7

27: d = 15.875



H: Holder







C: Clamp on system

Insert

shape

### Threading insert code system







E: External thread I: Internal thread




R: Right handed L: Left handed











Partial profile 60° Partial Profile 55° ISO Metric (Full Profile) American UN (Full Profile) UN, UNC, UNF, UNEF Whitworth (Full Profile) BSW, BSF, BSP British Standard Pipe thread (Full Profile) BSPT National Pipe Thread (Full Profile) NPT National Pipe Threads-Dryseal (Full Profile) NPTF Round DIN 405 Trapez DIN 103

American ACME

Stub ACME

UNJ


American Buttress **British Buttress** 

Metric Buttress-Sagengewinde

**API Buttress Casing** API Round Casing & Tubing **EL-Extreme Line Casing** 

## g D

#### Special features






A thread which, when viewed axially, winds in a counter clockwise and receding direction. All left handed threads are designated LH




A thread which, when viewed axially, winds in a clockwise and receding direction. Threads are always right handed unless they are specified





For a straight thread, where the lead of the thread and the pitch diameter circle circumference form a right angled triangle, the helix angle is the angle opposite of the lead

#### Machining a multi-start thread


A thread in which the lead is an integral multiple, greater than one, of the pitch. A multi-start thread permits a
more rapid advance without a coarser (larger) thread form









#### Insert profile style




The V partial profile insert cuts without topping the outer diameter of the thread. The same insert can be used for a range of different thread pitches which have a common thread angle



The full profile insert will form a complete thread profile including the crest. For every thread pitch and standard, a separate insert is required



The full profile for Fine Pitches will form a complete thread The topping of the outer diameter is generated by second tooth




The Semi profile insert will form a complete thread including crest radius but without topping the outer diameter Mainly used for trapezoidal profiles


### **Technical Information for Threading**

#### Thread turning method


Thread	Inserts & Tool holder	Rotation	Feed direction	Helix method	Drawing no.
Dight Hand Externa	EX RH	Counter clockwise	Towards chuck	Regular	1
Right Hand Externa	EX LH	Clockwise	From chuck	Reversed	2
Dight Hand Internal	IN RH	Counter clockwise	Towards chuck	Regular	3
Right Hand Internal	IN LH	Clockwise	From chuck	Reversed	4
Left Lloyd External	EX LH	Clockwise	Towards chuck	Regular	5
Left Hand External	EX RH	Counter clockwise	From chuck	Reversed	6
Laft Hand Internal	IN LH	Clockwise	Towards chuck	Regular	7
Left Hand Internal	IN RH	Counter clockwise	From chuck	Reversed	8

#### **External RH thread**







**External LH thread** 




Internal RH thread







Internal LH thread



#### Calculating the helix angle (β)





$$\beta = tan^{-1} \quad \frac{P \times N}{\pi \times D}$$

 $\beta$ : Helix angle (°)


P: Pitch (mm)

N: No. of starts

D: Pitch diameter (mm)

Lead =  $P \times N$ 

• The helix angle can also be found from the diagram below



#### Thread infeed method

In	feed	Application									
	Radial infeed	When the pitch is smaller than 16 tpi For material with short chips For work with hardened material	<b>→</b>	Radial infeed is the simplest and quickest method The feed is perpendicular to the turning axis, and both flanks of the insert perform the cutting operation Radial infeed is recommended in 3 cases							
1-3°	Flank infeed (modified)	When the thread pitch is greater than 16 tpi. Using the radial method, the effective cutting edge length is too large, resulting in chatter. for TRAPEZ and ACME. The radial method results in three cutting edges, making chip flow very difficult	<b>→</b>	Flank infeed is recommended in the following cases							
	Alternate flank infeed	This method divides the load equally on both flanks, resulting in equal wear along the cutting edges Alternate flank infeed requires more complicated programming, and is not available on all lathes	<b>→</b>	Use of the alternate flank method is recommended especially in large pitches and for materials with long chips							

#### Shim


Ε	ATE (5. t	ATI (Thursday)	.5°	Insert	d	9.5	25	12	2.7	15.8	875
rd shim	ATE (External)	ATI (Through)	gle 1	size	L	1	6	2	2	2	7
Standard	1		Helix an	Hol	der	ER(L)H	IR(L)H	ER(L)H	IR(L)H	ER(L)H	IR(L)H
Ó			Ť	Orderin	ng code	ATE16	ATI16	ATE22	ATI22	ATE27	ATI27

 $\,$  % Standard shim has lead angle 1.5°

### Application grade

Grade		Features	Available insert type
PC5300	Universal grade	<ul> <li>For chip breaker type only</li> <li>Stable machining on a wide application due to fine-grained carbide substrate with balanced heat resistance and toughness</li> <li>Excellent wear resistance and oxidation resistance due to AiTN coating film Outstanding performance on high speed machining</li> </ul>	ERM/IRM (Insert with Chip breaker)
PC3030T	Specialized grade for threading inserts	A tough sub-micron substrate with TiAIN coating provides good fracture toughness and excellent wear resistance     Outstanding performance on STS and hard to cut materials	ER/IR (Ground insert)
PC9070T	Specialized grade for threading inserts	Strong wear resistance in stainless machining thanks to multilayer PVD coatings	E/IR (Ground insert)

#### Application range



## D


## **Technical Information for Threading**

#### Recommended cutting speed as per workpiece (vc)

Workpiece		Hardness		vc (m/min)			
		brinell (HB)	PC3030T	PC9070T	PC5300		
		Low carbon (C=0.1-0.25 %)	125	115~190		110~190	
	Carbon steel	Medium carbon (C=0.25-0.55 %)	150	100~175		100~165	
		High carbon (C=0.55-0.85 %)	170	90~155		90~155	
		Non-hardened	180	100~180		100~180	
Р	Low alloy steel	Hardened	275	75~140		75~140	
		Hardened	350	70~135		70~135	
	High alloy steel	Annealed	200	80~120		80~120	
	nigh alloy steel	Hardened	325	50~100		50~100	
	Cast steel	Low alloy	200	70~130		70~130	
	Cast steel	High alloy	225	60~120		60~120	
	Stainless steel	Non-hardened	200	70~130	70~150	70~130	
	ferritic	Hardened	330	50~95	60~125	50~95	
	Stainless steel	Austenitic	180	80~120	90~160	80~120	
	austenitic	Super austenitic	200	30~100	40~120	30~100	
	Stainless steel cast ferritic	Non-hardened	200	90~120	90~150	90~120	
	cast ferritic	Hardened	330	65~110	65~120	65~110	
D./I	Stainless steel	Austenitic	200	85~110	85~120	85~110	
IVI	cast austenitic	Hardened	330	60~100	60~110	60~100	
	High	Annealed (Iron based)	200	45~60		45~60	
		Aged (Iron based)	280	30~50		30~50	
	temperature allov	Annealed (Nickel or Cobalt based)	250	20~30		20~30	
	alloy	Aged (Nickel or Cobalt based)	350	15~25		15~25	
	Titanium alloy	99.5% pure Titanium	400Rm	140~170		140~170	
	Titaliiuiii alioy	Titanium alloy	1050Rm	50~70		50~70	
	Extra hard steel	Hardened & tempered	55HRC	45~60		45~60	
	Malleable	Ferritic (short chips)	130	70~120		70~120	
	cast iron	Pearlitic (long chips)	230	70~120		70~120	
K	Grov cost iron	Low tensile strength	180	70~130		70~130	
	Gray cast iron	High tensile strength	260	60~100		60~100	
	Nodular SG iron	Ferritic	160	125~160		125~160	
	Nodulai 5G iron	Pearlitic	260	90~120		90~120	
	Aluminum alloy	Non-aging	60	100~250		100~250	
	wrought	Aged	100	80~180		80~180	
		Cast	75	200~400		200~400	
N	Aluminum alloy	Cast & aged	90	200~280		200~280	
		Cast Si 13-22%	130	60~150		60~180	
	Copper and	Brass	90	80~120		80~210	
	copper alloy	Bronze and non-leaded copper	100	80~120		80~210	

### Calculation of n [RPM]

$$n = \frac{vc \times 1000}{\pi \times D} \qquad vc = \frac{\pi \times D \times n}{1000}$$



n: Revolution Per Minute [min<sup>-1</sup>] vc: Cutting Speed [m/min]

D: Workpiece Diameter [mm]


#### Number of passes

Pitch	mm	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.50	3.00	3.50	4.00	4.50	5.00	5.50	6.00	8.00
	tpi	48	32	24	20	16	14	12	10	8	7	6	5.5	5	4.5	4	3
No. of	passes	4~6	4~7	4~8	5~9	6~10	7~12	7~12	8~14	9~16	10~18	11~18	11~19	12~20	12~20	12~20	15~24

<sup>\*\*</sup> One cutting depth is calculated by total cutting depth divided into machining times ex) ER16-1.5ISO, hmin 0.92: If 10 times machining, one cutting depth is 0.092 (0.92/10)




#### Step by step thread turning



#### **Application**

- Thread: External right hand ISO metric M40x2.5
- Material: 4140 (25 HRC)

#### 1 Choose the thread turning method



Feed direction towards the chuck was chosen Therefore an external right hand insert and an external right hand holder will be used

#### 3 Choose the tool holder



Chosen tool holder: ERH 25-16

Insert size	Ordering code	Dimensions (mm)				
d RH (Right Hand)		H=h	W	S	L	Q
9.525	ERH25-16	25	25	25	153.6	30


#### 2 Choose the insert size



Chosen insert: ER16-2.5 ISO

Insert size	Pitch	Ordering code	Shim	Tool holder	
d mm		RH (Right Hand) RH (Right Hand		Tool Holder	
9.525	2.5	ER16-2.5ISO	ATE16	ERH□□-16	

#### 4 Determine the helix angle



From the table, using a pitch of 2.5 mm (10 tpi) and a workpiece diameter of 40 mm (1.57"), we find the helix angle to be 1.5°

#### 5 Choose the correct shim

Resultant H	1.5°	
lucant ains	d	9.525
Insert size	L	16
Orderin	ATE16	

#### 7 Determine the number of passes

Pitch	mm	1.50	1.75	2.00	2.50	3.00	3.50	4.00
	tpi	16	14	12	10	8	7	6
No.of passes		6~10	7~12	7~12	8~14	9~16	10~18	11~18

- · Carbide grade chosen: PC3030T
- Cutting speed: 140 m/min

#### 6 Choose the carbide grade and cutting speed

	Worl	кріесе	НВ	vc (m/min) PC3030T
		Non-hardened	180	85~145
Р	Low alloy steel (alloying elements ≤ 5%)	Hardened	275	75~140
	(alloying elements \$ 5%)	Hardened	350	70~135

- Carbide grade chosen: PC3030T
- Cutting speed: 140 m/min

#### 8 Summary

Thread type	ISO M40 x 2.5 External right hand
Feed direction	Towards the chuck
2. Insert and grade	ER16-2.5ISO, PC3030T
3. Tool holder	ERH25-16
4. Helix angle	1.5°
5. Shim	ATE16
6. Cutting speed	140 m/min
7. Number of passes	10



## **Technical Information for Threading**

### Cutting condition depending on

	Material type	
Workpiece	Material dimension	₽ D
workpiece	Diameter and length chipflow character	the Con
	Material hardness	HRC HB
	External or internal	
Thread application	Profile shape	
	Surface finish	$\sqrt{}$
	Machine stability	mane DEV
Machine	Max. RPM	(RPM) n
	Clamping system stability	

Coolant	Coolant type	*
	Holder cross section area	
Holders	Holder overhang	Overhang
riolueis	Through coolant option	(a) / =   = = = = = = = = = = = = = = = = =
	Shank type: Carbide, alloy	
	Carbide implant grade	P M K
Insert	Profile shape: Pitch and depth	
ilisert	Nose radius	R
	Chip breaker style	

## **○** Trouble shooting

Problem		Possible cause	Solution
	Increased flank wear	Cutting speed too high  Depth of cut too low/too many passes  Unsuitable carbide grade  Insufficient cooling	<ul><li>Increase the depth of cut per pass</li><li>Use a coated carbide grade</li></ul>
	Uneven cutting edge wear	Incorrect helix angle Wrong infeed method	
	Extreme plastic deformation	Depth of cut too large Insufficient cooling Cutting speed too high Unsuitable carbide grade Nose radius too small	Reduce cutting speed  Use a tougher carbide
	Cutting edge breakage	Depth of cut too large Extreme plastic deformation Insufficient cooling Unsuitable ca rbide grade Instability	Use a tougher carbide Increase flow rate and/ or correct flow direction Use a tougher carbide
	Built-up edge	Incorrect cutting speed Unsuitable carbide grade	
	Thread profile is too shallow	The tool is not at the workpiece axis height Insert is not machining the thread crest Worn insert	Measure the workpiece diameter
	Poor surface quality	Too low cutting speed Wrong shim Flank infeed method is not appropriate	> Choose correct shim

## Threading insert with chip breaker

#### **▶ Features** • Economical insert

- Good toughness and high accuracy as ground type inserts
- Exclusive insert design improves chip control
- New grade for general application of various kinds of workpieces

Туре	Ground	d insert		Insert with a	chip breaker		
C/B Code	No	ne	No	ne	U		
Designation	ER16-1.5ISO		ERM16	-1.5ISO	ERM16-1.5ISO-U		
Machining	External Internal		External Internal		External	Internal	
Insert Shape				6	10	a)	
Chip Shape		nns		Em (	Tw.	ne	
Class	P, M, F	K, N, S	P, M, K		P, M, K		
Application	G-Class		M-C	lass	M-Class		
Features	Groove-shaped chip breaker with superior chip evacuation lowers cutting load Enables high precision machining Applicable for machining of various shapes of threads Applicable for machining of various workpieces		M-Class  • Unique 3 dimensional chip breaker improves machinability with good chip control  • Excellent cutting edge treatment technology ensures high precision sharp cutting edge		Groove-shaped chip breaker with superior chip evacuation lowers cutting load     Reduces machining pass by 10~30%     Excellent cutting edge treatment achieves high precision sharp cutting edge		

### Application examples

	KORLOY	ERM16-1.5ISO [PC3030T]	IRM16-2.0ISO [PC3030T]						
Com	petitor tools	ER16-1.5ISO [A-Maker]	IR16-2.0ISO [B-Maker]						
	Material	SCM440	STS304						
Workpiece	Figure								
	Cutting speed (m/min)	63	120						
Cutting	Pass	8	9						
condition	Machining	Radial infeed	Radial infeed						
	Pitch	1.5	2.0						
	Coolant	Wet	Wet						
	Result	Increased tool life with good chip breaking  PC3030T Competitor A	Prevention outbreak damage of insert due to smooth chip control  PC3030T Competitor B						

## Partial profile 60°

Applicable holders D31, D32

Applicable holders D31, D32

-	_		-	_			_	_	Pito	ch		Dime	nsions	(mm)		
Туре	Designation (Right)		PC3030T	PC9070T	De	signation (Left)	PC3030T	PC9070T	(mm)	(tpi)	d	L	r	x	f	Picture
	ER 11-A60		•	• E		11-A60	•		0.5~1.5	48~16	6.35	11	0.05	0.8	0.9	f
		16-A60	•	•		16-A60	•		0.5~1.5	48~16	9.525	16	0.05	8.0	0.9	× ¬ +   +   -
la l		16-G60	•			16-G60	•		1.75~3.0	14~8	9.525	16	0.27	1.2	1.7	60° Internal
External		16-AG60	•	•		16-AG60	•		0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	
Ä		22-N60	•	•		22-N60	•		3.5~5.0	7~5	12.7	22	0.53	1.7	2.5	
		27-Q60	•	•		27-Q60	•		5.5~6.0	4.5~4	15.875	27	0.64	2.1	3.1	External
	IR	11-A60	•	•	IL	11-A60	•	•	0.5~1.5	48~16	6.35	11	0.05	0.8	0.9	.f.
		16-A60	•			16-A60	•		0.5~1.5	48~16	9.525	16	0.05	0.8	0.9	Internal
اهر		16-G60	•			16-G60	•		1.75~3.0	14~8	9.525	16	0.16	1.2	1.7	60° Internal
Internal		16-AG60	•	•		16-AG60	•		0.5~3.0	48~8	9.525	16	0.05	1.2	1.7	
르		22-N60	•	•		22-N60	•		3.5~5.0	7~5	12.7	22	0.30	1.7	2.5	
		27-Q60	•	•		27-Q60			5.5~6.0	4.5~4	15.875	27	0.30	1.8	2.7	External
															~	

Partial profile 60° (M chip breaker)

		•			•		•			,				
			_			_	Pit	ch		Dime	nsions	(mm)		
Type	Designation (Right)		PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	(tpi)	d	L	r	x	f	Picture
	<b>ERM</b>	16-A60	•				0.5~1.5	48~16	9.525	16	0.08	8.0	0.9	_f_
		16-G60	•				1.75~3.0	14~8	9.525	16	0.27	1.2	1.7	x-j r Internal
External		16-AG60	•				0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	60°
ien		22-N60	•				3.5~5.0	7~5	12.7	22	0.53	1.7	2.5	
Û														External
	IRM	11-A60	•				0.5~1.5	48~16	6.35	11	0.08	0.8	0.9	.f.
		16-A60	•				0.5~1.5	48~16	9.525	16	0.08	0.8	0.9	Internal
a		16-G60	•				1.75~3.0	14~8	9.525	16	0.12	1.2	1.7	60° Internal
Internal		16-AG60	•				0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	
直		22-N60	•				3.5~5.0	7~5	12.7	22	0.30	1.7	2.5	
														External

## Partial profile 60° (U chip breaker)

	•			•		•			,				
4		_			_	Pit	ch		Dime	nsions	(mm)		
Туре	Designation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	(tpi)	d	L	r	x	f	Picture
	ERM 16-AG60-U					0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	, <del>-     -</del> ,
External													60° Internal External
	IRM 16-AG60-U					0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	f
Internal													60° Internal

•: Stock item

• : Stock item

•: Stock item

• : Stock item

## Partial profile 55°

Applicable holders D31, D32

Applicable holders D31, D32

-	_		-	<b>—</b>			_	_	Pito	ch		Dime	nsions	(mm)			
Type	Designation (Right)		PC3030T	PC9070T	De	signation (Left)	PC3030T	PC9070T	(mm)	(tpi)	d	L	r	x	f	Picture	
	ER	11-A55	•		EL	11-A55			0.5~1.5	48~16	6.35	11	0.05	0.8	0.9	f	
		16-A55				16-A55	•		0.5~1.5	48~16	9.525	16	0.05	0.8	0.9	×	
اهر		16-G55	•			16-G55			1.75~3.0	14~8	9.525	16	0.21	1.2	1.7	55° Internal	
External		16-AG55				16-AG55	•		0.5~3.0	48~8	9.525	16	0.07	1.2	1.7		
X		22-N55	•			22-N55			3.5~5.0	7~5	12.7	22	0.43	1.7	2.5		
_		27-Q55				27-Q55			5.5~6.0	4.5~4	15.875	27	0.60	2.0	2.9	External	
	IR	11-A55	•		IL	11-A55	•		0.5~1.5	48~16	6.35	11	0.05	0.8	0.9	f	
		16-A55	•			16-A55			0.5~1.5	48~16	9.525	16	0.05	0.8	0.9	Internal	
<u>a</u>		16-G55	•			16-G55			1.75~3.0	14~8	9.525	16	0.21	1.2	1.7	55°	
Internal		16-AG55	•			16-AG55	•		0.5~3.0	48~8	9.525	16	0.07	1.2	1.7		
할		22-N55	•			22-N55			3.5~5.0	7~5	12.7	22	0.43	1.7	2.5		
		27-Q55				27-Q55			5.5~6.0	4.5~4	15.875	27	0.60	2.0	2.9	External	
															· •		

## Partial profile 55° (M chip breaker)

-	B i ii		_			_	Pit	ch		Dime	nsions	(mm)		
Туре		ignation Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	(tpi)	d	L	r	x	f	Picture
	ERM	16-A55	•				0.5~1.5	48~16	9.525	16	0.08	0.8	0.9	+1+
		16-G55	•				1.75~3.0	14~8	9.525	16	0.21	1.2	1.7	Internal
nal		16-AG55	•				0.5~3.0	48~8	9.525	16	0.07	1.2	1.7	555*
External		22-N55	•				3.5~5.0	7~5	12.7	22	0.43	1.7	2.5	
Ш														External
	IRM	11-A55	•				0.5~1.5	48~16	6.35	11	0.08	0.8	0.9	
		16-A55	•				0.5~1.5	48~16	9.525	16	0.05	0.8	0.9	x Internal
a		16-G55					1.75~3.0	14~8	9.525	16	0.08	1.2	1.7	55° Mellal
Internal		16-AG55	•				0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	
<u> </u>		22-N55	•				3.5~5.0	7~5	12.7	22	0.43	1.7	2.5	
														External

## Partial profile 55° (U chip breaker)

40		-			_	Pite	ch		Dime	nsions	(mm)		
Туре	Designation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	(tpi)	d	L	r	x	f	Picture
	ERM 16-AG55-U					0.5~3.0	48~8	9.525	16	0.07	1.2	1.7	x—————————————————————————————————————
External													55° Internal
	IRM 16-AG55-U					0.5~3.0	48~8	9.525	16	0.08	1.2	1.7	, <del>-1</del> 1+v
Internal													55° Internal External

## **ISO Metric**

		_	_			_	L	Pitch		Dime	nsions	(mm)		
Туре	Designation (Right)	PC3030T	PC9070T		signation (Left)	PC3030T	PC9070T	(mm)	d	L	hmin	Х	f	Picture
	ER 11-0.35ISO	•			11-0.35ISO			0.35	6.35	11	0.21	0.8	0.4	
	11-0.4ISO	•		_	11-0.4ISO			0.4	6.35	11	0.25	0.7	0.4	
	11-0.45ISO	•		_	11-0.45ISO			0.45	6.35	11	0.28	0.7	0.4	
	11-0.5ISO	•		_	11-0.5ISO			0.5	6.35	11	0.31	0.6	0.4	
	11-0.6ISO	•		_	11-0.6ISO			0.6	6.35	11	0.37	0.6	0.6	
	11-0.7ISO	•		_	11-0.7ISO			0.7	6.35	11	0.43	0.6	0.6	
	11-0.75ISO			_	11-0.75ISO			0.75	6.35	11	0.46	0.6	0.6	
	11-0.8ISO	•		_	11-0.8ISO			0.8	6.35	11	0.49	0.6	0.6	
	11-1.0ISO	•		_	11-1.0ISO			1.0	6.35	11	0.61	0.7	0.7	
	11-1.25ISO	•	•	_	11-1.25ISO			1.25	6.35	11	0.77	0.8	0.9	
	11-1.5ISO	•		_	11-1.5ISO	•		1.5	6.35	11	0.92	0.8	1.0	
	11-1.75ISO	•		_	11-1.75ISO			1.75	6.35	11	1.07	0.8	1.1	f.
	16-0.35ISO			_	16-0.35ISO			0.35	9.525	16	0.21	0.8	0.4	x ¬
	16-0.4ISO				16-0.4ISO			0.4	9.525	16	0.25	0.7	0.4	1/4P Internal
	16-0.45ISO	•		_	16-0.45ISO			0.45	9.525	16	0.28	0.7	0.4	60°
na	16-0.5ISO	•		_	16-0.5ISO	•		0.5	9.525	16	0.31	0.6	0.4	
External	16-0.6ISO	•		_	16-0.6ISO			0.6	9.525	16	0.37	0.6	0.6	
ũ	16-0.7ISO	•		_	16-0.7ISO			0.7	9.525	16	0.43	0.6	0.6	d 1/8P External
	16-0.75ISO	•		_	16-0.75ISO			0.75	9.525	16	0.46	0.6	0.6	
	16-0.8ISO	•	•	_	16-0.8ISO			0.8	9.525	16	0.49	0.6	0.6	
	16-1.0ISO	•	•	_	16-1.0ISO	•		1.0	9.525	16	0.61	0.7	0.7	
	16-1.25ISO	•	•	_	16-1.25ISO	•		1.25	9.525	16	0.77	0.8	0.9	
	16-1.5ISO	•	•	_	16-1.5ISO	•		1.5	9.525	16	0.92	0.8	1.0	
	16-1.75ISO	•	•		16-1.75ISO			1.75	9.525	16	1.07	0.9	1.2	
	16-2.0ISO	•	•	_	16-2.0ISO	•		2.0	9.525	16	1.23	1.0	1.3	
	16-2.5ISO	•	•	_	16-2.5ISO			2.5	9.525	16	1.53	1.1	1.5	
	16-3.0ISO	•	•	_	16-3.0ISO	•		3.0	9.525	16	1.84	1.2	1.6	
	22-3.5ISO	•	•		22-3.5ISO			3.5	12.7	22	2.15	1.6	2.3	
	22-4.0ISO	•	•	_	22-4.0ISO	•		4.0	12.7	22	2.45	1.6	2.3	
	22-4.5ISO	•	•	22-4.5ISO			4.5	12.7	22	2.78	1.7	2.4		
	22-5.0ISO	•	•	_	22-5.0ISO	•		5.0	12.7	22	3.07	1.7	2.5	
	27-5.5ISO				27-5.5ISO		5.5	15.875	27	3.37	1.9	2.7		
	27-6.0ISO	•	•		27-6.0ISO			6.0	15.875	27	3.68	2.0	2.9	

● : Stock item

## **ISO Metric (M chip breaker)**

4	_		-			H	Pitch		Dime	nsions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	d	L	hmin	X	f	Picture
	ERM	16-1.0ISO	•				1.0	9.525	16	0.61	0.7	0.7	f
		16-1.25ISO					1.25	9.525	16	0.77	8.0	0.9	1/4P Internal
ы		16-1.5ISO	•				1.5	9.525	16	0.93	8.0	1.0	60°
External		16-1.75ISO	•				1.75	9.525	16	1.09	0.9	1.2	
Ж		16-2.0ISO	•				2.0	9.525	16	1.25	1.0	1.3	
		16-2.5ISO	•				2.5	9.525	16	1.55	1.1	1.5	1/8P External
		16-3.0ISO	•				3.0	9.525	16	1.87	1.2	1.6	· ·

● Applicable holders D31 •: Stock item

## **ISO Metric (U chip breaker)**

	_		-			H	Pitch		Dime	nsions	(mm)		
Type		esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	d	L	hmin	X	f	Picture
	ERM	16-1.5ISO-U					1.5	9.525	16	0.93	0.8	1.0	
		16-2.0ISO-U					2.0	9.525	16	1.25	1.0	1.3	1/4P Internal
External													1/8P External

● Applicable holders D31 •: Stock item

### **D** Thread Insert

### **ISO Metric**

			_	<b>—</b>			_	L	Pitch		Dime	ensions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC9070T		signation (Left)	PC3030T	PC9070T	(mm)	d	L	hmin	Х	f	Picture
	IR	11-0.35ISO	•		IL 1	1-0.35ISO			0.35	6.35	11	0.20	0.8	0.3	
		11-0.4ISO	•		1	1-0.4ISO			0.4	6.35	11	0.23	8.0	0.4	
		11-0.45ISO	•		_1	1-0.45ISO			0.45	6.35	11	0.26	8.0	0.4	
		11-0.5ISO	•		1	1-0.5ISO	•		0.5	6.35	11	0.29	0.6	0.4	
		11-0.6ISO	•		1	1-0.6ISO			0.6	6.35	11	0.35	0.6	0.6	
		11-0.7ISO	•		1	1-0.7ISO			0.7	6.35	11	0.40	0.6	0.6	
		11-0.75ISO	•		1	1-0.75ISO	•		0.75	6.35	11	0.43	0.6	0.6	
		11-0.8ISO			_	1-0.8ISO			0.8	6.35	11	0.46	0.6	0.6	
		11-1.0ISO	•	•	_	1-1.0ISO			1.0	6.35	11	0.58	0.6	0.7	
		11-1.25ISO	•	•	1	1-1.25ISO	•		1.25	6.35	11	0.72	8.0	0.9	
		11-1.5ISO	•	•	1	1-1.5ISO	•	•	1.5	6.35	11	0.87	8.0	1.0	
		11-1.75ISO		•	1	1-1.75ISO			1.75	6.35	11	1.01	0.9	1.1	
		11-2.0ISO	•	•	_	1-2.0ISO	•		2.0	6.35	11	1.15	0.9	1.1	f
		11-2.5ISO	•		1	1-2.5ISO	•		2.5	6.35	11	1.44	8.0	1.1	x
		16-0.35ISO	•		_	6-0.35ISO			0.35	9.525	16	0.20	8.0	0.3	1/4P Internal
		16-0.4ISO	•			6-0.4ISO			0.4	9.525	16	0.23	8.0	0.4	60°
nal		16-0.45ISO	•		1	6-0.45ISO			0.45	9.525	16	0.26	8.0	0.4	
Internal		16-0.5ISO	•		_	6-0.5ISO			0.5	9.525	16	0.29	0.6	0.4	1/8P External
드		16-0.6ISO			_	6-0.6ISO			0.6	9.525	16	0.35	0.6	0.6	1701 2.10112
		16-0.7ISO				6-0.7ISO			0.7	9.525	16	0.40	0.6	0.6	
		16-0.75ISO	•		_	6-0.75ISO			0.75	9.525	16	0.43	0.6	0.6	
		16-0.8ISO	•			6-0.8ISO			0.8	9.525	16	0.46	0.6	0.6	
		16-1.0ISO	•	•	_	6-1.0ISO			1.0	9.525	16	0.58	0.6	0.7	
		16-1.25ISO	•	•	_	6-1.25ISO			1.25	9.525	16	0.72	0.8	0.9	
		16-1.5ISO	•	•	_	6-1.5ISO	•		1.5	9.525	16	0.87	0.8	1.0	
		16-1.75ISO	•	•	_	6-1.75ISO			1.75	9.525	16	1.01	0.9	1.2	
		16-2.0ISO	•	•	_	6-2.0ISO	•		2.0	9.525	16	1.15	1.0	1.3	
		16-2.5ISO	•	•		6-2.5ISO	•		2.5	9.525	16	1.44	1.1	1.5	
		16-3.0ISO	•	•	_	6-3.0ISO	•		3.0	9.525	16	1.73	1.1	1.5	
		22-3.5ISO	•	•		22-3.5ISO			3.5	12.7	22	2.02	1.6	2.3	
		22-4.0ISO	•	•	_	22-4.0ISO	•		4.0	12.7	22	2.31	1.6	2.3	
		22-4.5ISO	•	•	_	22-4.5ISO			4.5	12.7	22	2.60	1.6	2.4	
		22-5.0ISO	•	•	_	22-5.0ISO			5.0	12.7	22	2.89	1.6	2.3	
		27-5.5ISO	•		_	27-5.5ISO			5.5	15.875	27	3.17	1.6	2.3	
		27-6.0ISO	•		2	27-6.0ISO			6.0	15.875	27	3.46	1.8	2.5	

→ Applicable holders D32
• : Stock item

## **ISO Metric (M chip breaker)**

-	_		-			<b>—</b>	Pitch		Dime	nsions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	d	L	hmin	X	f	Picture
	IRM	11-1.5ISO	•				1.5	6.35	11	0.85	8.0	1.0	
		16-1.0ISO	•				1.0	9.525	16	0.58	0.6	0.7	+  x
_		16-1.25ISO					1.25	9.525	16	0.72	8.0	0.9	1/4P Internal 60°
Internal		16-1.5ISO	•				1.5	9.525	16	0.85	8.0	1.0	
nte		16-1.75ISO					1.75	9.525	16	1.01	0.9	1.2	
_		16-2.0ISO	•				2.0	9.525	16	1.12	1.0	1.3	1/8P External
		16-2.5ISO	•				2.5	9.525	16	1.44	1.1	1.5	
		16-3.0ISO	•				3.0	9.525	16	1.69	1.1	1.5	

→ Applicable holders D32 •: Stock item

# **ISO Metric (U chip breaker)**

	_		-			-	Pitch		Dime	nsions	(mm)		
Type	D	esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(mm)	d	L	hmin	Х	f	Picture
	IRM	16-1.5ISO-U					1.5	9.525	16	0.85	8.0	1.0	
		16-2.0ISO-U					2.0	9.525	16	1.12	1.0	1.3	<del>+ <sup>†</sup> -</del> ,,
Internal													1/4P Internal 60°

→ Applicable holders D32
• : Stock item



## American UN (UN, UNC, UNF, UNEF, UNS)

4.			_	<b>—</b>		  -	_	Pitch		Dime	nsions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC9070T	Designation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	х	f	Picture
	ER	11-72UN	•		EL 11-72UN			72	6.35	11	0.22	8.0	0.4	
		11-64UN	•		11-64UN			64	6.35	11	0.24	8.0	0.4	
		11-56UN	•		11-56UN			56	6.35	11	0.28	0.7	0.4	
		11-48UN	•		11-48UN			48	6.35	11	0.32	0.6	0.6	
		11-44UN	•		11-44UN			44	6.35	11	0.35	0.6	0.6	
		11-40UN	•		11-40UN			40	6.35	11	0.39	0.6	0.6	
		11-36UN	•		11-36UN			36	6.35	11	0.43	0.6	0.6	
		11-32UN	•		11-32UN			32	6.35	11	0.49	0.6	0.6	
		11-28UN	•		11-28UN			28	6.35	11	0.56	0.6	0.7	
		11-27UN	•		11-27UN			27	6.35	11	0.58	0.7	0.8	
		11-24UN	•		11-24UN			24	6.35	11	0.65	0.7	0.8	
		11-20UN	•		11-20UN			20	6.35	11	0.78	8.0	0.9	
		11-18UN	•		11-18UN			18	6.35	11	0.87	8.0	1.0	
		11-16UN	•		11-16UN			16	6.35	11	0.97	0.9	1.1	
		11-14UN	•		11-14UN			14	6.35	11	1.11	0.9	1.1	
		16-72UN			16-72UN			72	9.525	16	0.22	8.0	0.4	.f.
		16-64UN			16-64UN			64	9.525	16	0.24	8.0	0.4	× ¬
		16-56UN			16-56UN			56	9.525	16	0.28	0.7	0.4	1/4P Internal
		16-48UN			16-48UN			48	9.525	16	0.32	0.6	0.6	60°
<del>-</del>		16-44UN			16-44UN			44	9.525	16	0.35	0.6	0.6	
Ĭ		16-40UN			16-40UN			40	9.525	16	0.39	0.6	0.6	
External		16-36UN			16-36UN			36	9.525	16	0.43	0.6	0.6	d 1/8p External
		16-32UN	•		16-32UN			32	9.525	16	0.49	0.6	0.6	
		16-28UN	•		16-28UN			28	9.525	16	0.56	0.6	0.7	
		16-27UN	•		16-27UN			27	9.525	16	0.58	0.7	0.8	
		16-24UN	•	•	16-24UN			24	9.525	16	0.65	0.7	0.8	
		16-20UN	•	•	16-20UN			20	9.525	16	0.78	8.0	0.9	
		16-18UN	•	•	16-18UN	•		18	9.525	16	0.87	8.0	1.0	
		16-16UN	•	•	16-16UN	•		16	9.525	16	0.97	0.9	1.1	
		16-14UN	•	•	16-14UN			14	9.525	16	1.11	1.0	1.2	
		16-13UN			16-13UN			13	9.525	16	1.20	1.0	1.3	
		16-12UN	•	•	16-12UN			12	9.525	16	1.30	1.1	1.4	
		16-11.5UN			16-11.5UN			11.5	9.525	16	1.35	1.1	1.5	
		16-11UN	•	•	16-11UN			11	9.525	16	1.42	1.1	1.5	
		16-10UN	•	•	16-10UN			10	9.525	16	1.56	1.1	1.5	
		16-9UN	•		16-9UN			9	9.525	16	1.73	1.2	1.7	
		16-8UN	•	•	16-8UN			8	9.525	16	1.95	1.2	1.6	
		22-7UN			22-7UN			7	12.7	22	2.22	1.6	2.3	
		22-6UN			22-6UN			6	12.7	22	2.60	1.6	2.3	
		22-5UN	•		22-5UN			5	12.7	22	3.12	1.7	2.5	
		27-4.5UN			27-4.5UN			4.5	15.875	27	3.46	1.9	2.7	
		27-4UN			27-4UN			4	15.875	27	3.89	2.1	3.0	

## American UN (UN, UNC, UNF, UNEF, UNS)

-			_	_			_	_	Pitch		Dime	nsions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	IR	11-72UN			IL	11-72UN			72	6.35	11	0.20	8.0	0.3	
		11-64UN				11-64UN			64	6.35	11	0.23	8.0	0.4	
		11-56UN				11-56UN			56	6.35	11	0.26	0.7	0.4	
		11-48UN				11-48UN			48	6.35	11	0.31	0.6	0.6	
		11-44UN				11-44UN			44	6.35	11	0.33	0.6	0.6	
		11-40UN				11-40UN			40	6.35	11	0.37	0.6	0.6	
		11-36UN				11-36UN			36	6.35	11	0.41	0.6	0.6	
		11-32UN				11-32UN			32	6.35	11	0.46	0.6	0.6	
		11-28UN				11-28UN			28	6.35	11	0.52	0.6	0.7	
		11-27UN				11-27UN			27	6.35	11	0.54	0.7	0.8	
		11-24UN				11-24UN			24	6.35	11	0.61	0.7	0.8	
		11-20UN		•		11-20UN			20	6.35	11	0.73	8.0	0.9	
		11-18UN	•			11-18UN			18	6.35	11	0.81	8.0	1.0	
		11-16UN				11-16UN			16	6.35	11	0.92	0.9	1.1	
		11-14UN	•			11-14UN			14	6.35	11	1.05	0.9	1.1	
		11-12UN		•		11-12UN			12	6.35	11	1.22	0.8	1.1	
		11-11UN	•			11-11UN	•		11	6.35	11	1.33	0.8	1.1	f
		16-72UN				16-72UN			72	9.525	16	0.20	0.8	0.3	x
		16-64UN				16-64UN			64	9.525	16	0.23	0.8	0.4	1/4P Internal
		16-56UN				16-56UN			56	9.525	16	0.26	0.7	0.4	60°
_		16-48UN				16-48UN			48	9.525	16	0.31	0.6	0.6	
ınal		16-44UN				16-44UN			44	9.525	16	0.33	0.6	0.6	
Internal		16-40UN				16-40UN			40	9.525	16	0.37	0.6	0.6	d 1/8P External
-		16-36UN				16-36UN			36	9.525	16	0.41	0.6	0.6	
		16-32UN				16-32UN			32	9.525	16	0.51	0.6	0.6	
		16-28UN	•			16-28UN			28	9.525	16	0.52	0.6	0.7	
		16-27UN				16-27UN			27	9.525	16	0.54	0.7	0.8	
		16-24UN				16-24UN			24	9.525	16	0.61	0.7	0.8	
		16-20UN	•			16-20UN			20	9.525	16	0.73	0.8	0.9	
		16-18UN	•	•		16-18UN			18	9.525	16	0.81	0.8	1.0	
		16-16UN	•	•		16-16UN			16	9.525	16	0.92	0.9	1.1	
		16-14UN	•			16-14UN			14	9.525	16	1.05	0.9	1.2	
		16-13UN				16-13UN			13	9.525	16	1.13	1.0	1.3	
		16-12UN	•	•		16-12UN			12	9.525	16	1.22	1.1	1.4	
		16-11.5UN	•			16-11.5UN			11.5	9.525	16	1.28	1.1	1.5	
		16-11UN	•	•		16-11UN			11	9.525	16	1.33	1.1	1.5	
		16-10UN	•			16-10UN	•		10	9.525	16	1.47	1.1	1.5	
		16-9UN		•		16-9UN			9	9.525	16	1.63	1.2	1.7	
		16-8UN	•	•		16-8UN	•		8	9.525	16	1.83	1.2	1.5	
		22-7UN				22-7UN			7	12.7	22	2.09	1.6	2.3	
		22-6UN				22-6UN			6	12.7	22	2.44	1.6	2.3	
		22-5UN				22-5UN			5	12.7	22	2.93	1.7	2.3	
		27-4.5UN				27-4.5UN			4.5	15.875	27	3.26	1.9	2.4	
		27-4UN				27-4UN			4	15.875	27	3.67	2.1	2.7	

→ Applicable holders D32 • : Stock item

## Whitworth (BSW, BSF, BSP, BSB)

4)	_		Ŀ	Ŀ	_		Ŀ	Ŀ	Pitch		Dime	ensions	(mm)		
Type		esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	х	f	Picture
	ER	11-72W	•		EL	11-72W			72	6.35	11	0.23	0.7	0.4	
		11-60W	•			11-60W			60	6.35	11	0.27	0.7	0.4	
		11-56W	•			11-56W			56	6.35	11	0.29	0.7	0.4	
		11-48W	•			11-48W			48	6.35	11	0.34	0.6	0.6	
		11-40W	•			11-40W			40	6.35	11	0.41	0.6	0.6	
		11-36W	•			11-36W			36	6.35	11	0.45	0.6	0.6	
		11-32W	•			11-32W			32	6.35	11	0.51	0.6	0.6	
		11-28W	•			11-28W			28	6.35	11	0.58	0.6	0.7	
		11-26W	•			11-26W			26	6.35	11	0.63	0.7	8.0	
		11-24W	•			11-24W			24	6.35	11	0.68	0.7	0.8	
		11-22W	•			11-22W			22	6.35	11	0.74	8.0	0.9	
		11-20W	•			11-20W			20	6.35	11	0.81	8.0	0.9	
		11-19W	•			11-19W			19	6.35	11	0.86	8.0	1.0	
		11-18W	•			11-18W			18	6.35	11	0.90	8.0	1.0	
		11-16W	•			11-16W			16	6.35	11	1.02	0.9	1.1	
		11-14W	•			11-14W	•		14	6.35	11	1.16	1.0	1.2	
		16-72W	•			16-72W			72	9.525	16	0.23	0.7	0.4	
		16-60W	•			16-60W			60	9.525	16	0.27	0.7	0.4	
		16-56W	•			16-56W			56	9.525	16	0.29	0.7	0.4	
		16-48W	•			16-48W			48	9.525	16	0.34	0.6	0.6	l × l
nal		16-40W	•			16-40W			40	9.525	16	0.41	0.6	0.6	<u>R0.137P</u> Internal <u>55</u> °
External		16-36W	•			16-36W			36	9.525	16	0.45	0.6	0.6	
ũ		16-32W	•			16-32W			32	9.525	16	0.51	0.6	0.6	
		16-30W	•			16-30W			30	9.525	16	0.55	0.6	0.7	R0.137P External
		16-28W	•	•		16-28W			28	9.525	16	0.58	0.6	0.7	
		16-26W				16-26W			26	9.525	16	0.63	0.7	0.8	
		16-24W	•			16-24W			24	9.525	16	0.68	0.7	0.8	
		16-22W	•			16-22W			22	9.525	16	0.74	0.8	0.9	
		16-20W	•			16-20W			20	9.525	16	0.81	8.0	0.9	
		16-19W	•	•		16-19W			19	9.525	16	0.86	8.0	1.0	
		16-18W	•			16-18W			18	9.525	16	0.90	8.0	1.0	
		16-16W	•			16-16W			16	9.525	16	1.02	0.9	1.1	
		16-14W	•	•		16-14W			14	9.525	16	1.16	1.0	1.2	
		16-12W	•			16-12W			12	9.525	16	1.36	1.1	1.4	
		16-11W	•	•		16-11W			11	9.525	16	1.48	1.1	1.5	
		16-10W	•			16-10W			10	9.525	16	1.63	1.1	1.5	
		16-9W	•			16-9W			9	9.525	16	1.81	1.2	1.7	
		16-8W	•			16-8W			8	9.525	16	2.03	1.2	1.5	
		22-7W	•			22-7W	-		7	12.7	22	3.32	1.6	2.3	
		22-6W	•			22-6W	•		6	12.7	22	2.71	1.6	2.3	
		22-5W	•			22-5W			5	12.7	22	3.25	1.7	2.4	
		27-4.5W	•			27-4.5W			4.5	15.875	27	3.61	1.8	2.6	
		27-4W				27-4W			4	15.875	27	4.07	2.0	2.9	

→ Applicable holders D31

 Stock item

## Whitworth (M chip breaker)

4	_		-			<b>—</b>	Pitch		Dime	nsions	(mm)		
Type		esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(tpi)	d	L	hmin	X	f	Picture
	<b>ERM</b>	16-11W	•				14	9.525	16	1.16	1.0	1.2	f
		16-14W	•				11	9.525	16	1.48	1.1	1.5	R0.137P Internal
nal		16-19W	•				19	9.525	16	0.86	8.0	1.0	555
External													R0.137P External

◆ Applicable holders D31

## Whitworth (U chip breaker)

	_		-			-	Pitch		Dime	nsions	(mm)		
Type	De	esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(tpi)	d	L	hmin	X	f	Picture
	ERM	16-14W-U					14	9.525	16	1.16	1.0	1.2	,
		16-11W-U					11	9.525	16	1.48	1.1	1.5	R0.137P Internal
External													R0.137PExternal

● Applicable holders D31 • : Stock item



## Whitworth (BSW, BSF, BSP, BSB)

4	_		ı.	H	_		-	F.	Pitch		Dime	ensions (	(mm)		
Туре		esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	IR	11-72W	•		IL	11-72W			72	6.35	11	0.23	0.7	0.4	
		11-60W	•			11-60W			60	6.35	11	0.27	0.7	0.4	
		11-56W	•			11-56W			56	6.35	11	0.29	0.7	0.4	
		11-48W	•			11-48W			48	6.35	11	0.34	0.6	0.6	
		11-40W	•			11-40W			40	6.35	11	0.41	0.6	0.6	
		11-36W	•			11-36W			36	6.35	11	0.45	0.6	0.6	
		11-32W	•			11-32W			32	6.35	11	0.51	0.6	0.6	
		11-28W	•			11-28W			28	6.35	11	0.58	0.6	0.7	
		11-26W	•			11-26W			26	6.35	11	0.63	0.7	0.8	
		11-24W	•			11-24W			24	6.35	11	0.68	0.7	0.8	
		11-22W	•			11-22W			22	6.35	11	0.74	0.8	0.9	
		11-20W				11-20W			20	6.35	11	0.81	0.8	0.9	
		11-19W	•	•		11-19W	•		19	6.35	11	0.86	0.8	1.0	
		11-18W	•			11-18W	•		18	6.35	11	0.90	0.8	1.0	
		11-16W	•			11-16W	•		16	6.35	11	1.02	0.9	1.1	
		11-14W	•			11-14W	•		14	6.35	11	1.16	0.9	1.1	
		11-12W	•			11-12W	•		12	6.35	11	1.32	0.9	1.2	
		16-72W	•			16-72W			72	9.525	16	0.23	0.7	0.4	
		16-60W	•			16-60W			60	9.525	16	0.27	0.7	0.4	
		16-56W	•			16-56W			56	9.525	16	0.29	0.7	0.4	- T
_		16-48W	•			16-48W			48	9.525	16	0.34	0.6	0.6	R0.137P Internal
rna		16-40W	•			16-40W			40	9.525	16	0.41	0.6	0.6	55°
Internal		16-36W	•			16-36W			36	9.525	16	0.45	0.6	0.6	
_		16-32W	•			16-32W			32	9.525	16	0.51	0.6	0.6	R0.137P
		16-30W	•			16-30W			30	9.525	16	0.55	0.6	0.7	External
		16-28W	•			16-28W			28	9.525	16	0.58	0.6	0.7	
		16-26W	•			16-26W			26	9.525	16	0.63	0.7	0.8	
		16-24W	•			16-24W			24	9.525	16	0.68	0.7	0.8	
		16-22W	•			16-22W			22	9.525	16	0.74	0.8	0.9	
		16-20W	•			16-20W			20	9.525	16	0.81	0.8	0.9	
		16-19W	•			16-19W			19	9.525	16	0.86	0.8	1.0	
		16-18W	•			16-18W			18	9.525	16	0.90	0.8	1.0	
		16-16W	•			16-16W			16	9.525	16	1.02	0.9	1.1	
		16-14W	•	•		16-14W			14	9.525	16	1.16	1.0	1.2	
		16-12W	•			16-12W			12	9.525	16	1.36	1.1	1.4	
		16-11W	•	•		16-11W			11	9.525	16	1.48	1.1	1.5	
		16-10W	•			16-10W			10	9.525	16	1.63	1.1	1.5	
		16-9W	•			16-9W			9	9.525	16	1.81	1.2	1.7	
		16-8W	•			16-8W			8	9.525	16	2.03	1.2	1.5	
		22-7W				22-7W			7	12.7	22	3.32	1.6	2.3	
		22-6W	•			22-6W			6	12.7	22	2.71	1.6	2.3	
		22-5W	•			22-5W			5	12.7	22	3.25	1.7	2.4	
		27-4.5W	•			27-4.5W			4.5	15.875	27	3.61	1.8	2.6	
		27-4W	•			27-4W			4	15.875	27	4.07	2.0	2.9	

● Applicable holders D32 • : Stock item

•: Stock item

## Whitworth (M chip breaker)

			-			ь	Pitch		Dime	ensions	(mm)		
Type	De	esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(tpi)	d	L	hmin	Х	f	Picture
	IRM	16-14W					14	9.525	16	1.16	1.0	1.2	
		16-11W	•				11	9.525	16	1.48	1.1	1.5	<del>-1-</del>
Internal													R0.137P Internal 55°

## Whitworth (U chip breaker)

Applicable holders D32

_	_		F			-	Pitch		Dime	nsions	(mm)		
Type	De	esignation (Right)	PC3030T	PC5300	Designation (Left)	PC3030T	(tpi)	d	L	hmin	X	f	Picture
	IRM	16-14W-U					14	9.525	16	1.16	1.0	1.2	
		16-11W-U					11	9.525	16	1.48	1.1	1.5	+ <del>11+</del> ,,
Internal													R0.137P Internal 55°

● : Stock item

### **British Standard Pipe Thread (BSPT)**

	Designation	_	_			_	_	Pitch		Dime	ensions	(mm)			
Type	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	х	f	Picture
	ER	11-28BSPT			EL	11-28BSPT			28	6.35	11	0.58	0.6	0.6	
		11-19BSPT				11-19BSPT			19	6.35	11	0.86	8.0	0.9	f
		11-14BSPT				11-14BSPT			14	6.35	11	1.16	0.9	1.0	x ————————————————————————————————————
<u>_</u>		16-28BSPT				16-28BSPT			28	9.525	16	0.58	0.6	0.6	R0.137P Internal 27.5°   27.5°
External		16-19BSPT	•	•		16-19BSPT			19	9.525	16	0.86	0.8	0.9	
X		16-14BSPT		•		16-14BSPT			14	9.525	16	1.16	1.0	1.2	
_	-	16-11BSPT	•	•		16-11BSPT			11	9.525	16	1.48	1.1	1.5	90° 1°47 R0.137P External
	IR	11-28BSPT			IL	11-28BSPT			28	6.35	11	0.58	0.6	0.6	
		11-19BSPT		•		11-19BSPT			19	6.35	11	0.86	0.8	0.9	, f
		11-14BSPT		•		11-14BSPT			14	6.35	11	1.16	0.9	1.0	×
<del>-</del>		16-28BSPT				16-28BSPT			28	9.525	16	0.58	0.6	0.6	R0.137P Internal 27.5°   27.5°
Internal		16-19BSPT	•	•		16-19BSPT			19	9.525	16	0.86	8.0	0.9	
Ĭ		16-14BSPT	•	•		16-14BSPT			14	9.525	16	1.16	1.0	1.2	
		16-11BSPT	•	•		16-11BSPT			11	9.525	16	1.48	1.1	1.5	90° 1°47° R0.137P External

Applicable holders D31, D32

•: Stock item

## **National Pipe Thread (NPT)**

			_	_			_	_	Pitch		Dime	nsions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	X	f	Picture
	ER	11-27NPT	•		EL	11-27NPT			27	6.35	11	0.66	0.7	0.8	
		11-18NPT	•			11-18NPT			18	6.35	11	1.01	8.0	1.0	
		11-14NPT	•			11-14NPT			14	6.35	11	1.33	8.0	1.0	x
=		16-27NPT	•			16-27NPT			27	9.525	16	0.66	0.7	0.8	30° 30° Internal
External		16-18NPT	•	•		16-18NPT			18	9.525	16	1.01	8.0	1.0	
X		16-14NPT	•	•		16-14NPT			14	9.525	16	1.33	0.9	1.2	
		16-11.5NPT	•			16-11.5NPT			11.5	9.525	16	1.64	1.1	1.5	90° 1°47 External
		16-8NPT	•			16-8NPT			8	9.525	16	2.42	1.3	1.8	
	IR	11-27NPT	•		IL	11-27NPT			27	6.35	11	0.66	0.7	0.8	
		11-18NPT	•			11-18NPT			18	6.35	11	1.01	8.0	1.0	
		11-14NPT	•	•		11-14NPT	•		14	6.35	11	1.33	8.0	1.0	f - X
=		16-27NPT	•			16-27NPT			27	9.525	16	0.66	0.7	0.8	30° 30° Internal
Internal		16-18NPT				16-18NPT			18	9.525	16	1.01	8.0	1.0	
nte		16-14NPT	•	•		16-14NPT			14	9.525	16	1.33	0.9	1.2	
_		16-11.5NPT	•	•		16-11.5NPT	•		11.5	9.525	16	1.64	1.1	1.5	90° 1°47 External
		16-8NPT	•			16-8NPT	•		8	9.525	16	2.42	1.3	1.8	d

● : Stock item

## **National Pipe Threads-Dryseal (NPTF)**

-			_	_			_	_	Pitch		Dime	nsions	(mm)		
Туре	D	esignation (Right)	PC3030T	PC9070T	De	signation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	11-27NPTF			EL	11-27NPTF			27	6.35	11	0.64	0.7	0.8	
		11-18NPTF				11-18NPTF			18	6.35	11	1.00	8.0	1.0	, if ,
		11-14NPTF				11-14NPTF			14	6.35	11	1.35	8.0	1.0	x —
<del>-</del>		16-27NPTF				16-27NPTF			27	9.525	16	0.64	0.7	0.8	30° 30° Internal
, L		16-18NPTF	•			16-18NPTF			18	9.525	16	1.00	8.0	1.0	
External		16-14NPTF				16-14NPTF			14	9.525	16	1.35	0.9	1.2	
	•	16-11.5NPTF				16-11.5NPTF			11.5	9.525	16	1.63	1.1	1.5	90° 1°47' External
		16-8NPTF				16-8NPTF	•		8	9.525	16	2.38	1.3	1.8	
	IR	11-27NPTF			IL	11-27NPTF			27	6.35	11	0.64	0.7	8.0	
		11-18NPTF				11-18NPTF			18	6.35	11	1.00	8.0	1.0	
		11-14NPTF				11-14NPTF			14	6.35	11	1.35	8.0	1.0	×
=		16-27NPTF				16-27NPTF			27	9.525	16	0.64	0.7	8.0	30° 30° Internal
rus	Eu a	16-18NPTF				16-18NPTF			18	9.525	16	1.00	8.0	1.0	
Internal		16-14NPTF				16-14NPTF			14	9.525	16	1.35	0.9	1.2	
_		16-11.5NPTF				16-11.5NPTF			11.5	9.525	16	1.63	1.1	1.5	90° 1°47 External
		16-8NPTF				16-8NPTF			8	9.525	16	2.38	1.3	1.8	

Applicable holders D31, D32

#### • : Stock item

### **Round DIN 405**

			<b>—</b>	_			-	_	Pitch		Dime	ensions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	16-10RD			EL	16-10RD			10	9.525	16	1.27	1.1	1.2	
		16-8RD	•			16-8RD			8	9.525	16	1.59	1.4	1.3	
		16-6RD	•			16-6RD			6	9.525	16	2.12	1.5	1.7	<u>×</u>
<u>च</u>		22-6RD				22-6RD			6	12.7	22	2.12	1.5	1.7	R0.22104P Internal 30°
External		22-4RD	•			22-4RD			4	12.7	22	3.18	2.2	2.3	
Ä		27-4RD				27-4RD			4	15.875	27	3.18	2.2	2.3	
															d R0.22104P External
	IR	16-10RD			IL	16-10RD			10	9.525	16	1.27	1.1	1.2	
		16-8RD				16-8RD			8	9.525	16	1.59	1.4	1.4	,
		16-6RD	•			16-6RD			6	9.525	16	2.12	1.4	1.5	
<del></del>		22-6RD				22-6RD			6	12.7	22	2.12	1.5	1.7	R0.22104P Internal 30°
Internal		22-4RD	•			22-4RD			4	12.7	22	3.18	2.2	2.3	
<u>n</u>		27-4RD				27-4RD			4	15.875	27	3.18	2.2	2.3	
															R0.22104P External

● Applicable holders D31, D32 • : Stock item

## Trapez DIN 103 (TR)

	_		<b>—</b>	-			ı_	-	Pitch		Dime	ensions	(mm)		
Type	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(mm)	d	L	hmin	Х	f	Picture
	ER	11-1.5TR	•		EL	11-1.5TR	•		1.5	6.35	11	0.90	8.0	0.9	
		16-1.5TR				16-1.5TR			1.5	9.525	16	0.90	1.0	1.1	f
		16-2.0TR	•			16-2.0TR	•		2.0	9.525	16	1.25	1.1	1.3	×
<u>=</u>		16-3.0TR	•	•		16-3.0TR	•		3.0	9.525	16	1.75	1.3	1.5	30° Internal
External		22-4.0TR	•	•		22-4.0TR	•		4.0	12.7	22	2.25	1.7	1.9	
X		22-5.0TR	•	•		22-5.0TR	•		5.0	12.7	22	2.75	2.1	2.5	
		27-6.0TR	•	•		27-6.0TR	•		6.0	15.875	27	3.50	2.3	2.7	External
	IR	11-1.5TR			IL	11-1.5TR	•		1.5	6.35	11	0.90	8.0	0.9	
		16-1.5TR	•			16-1.5TR	•		1.5	9.525	16	0.90	1.0	1.1	fr .
		16-2.0TR	•			16-2.0TR	•		2.0	9.525	16	1.25	1.1	1.3	
<del>-</del>		16-2.5TR	•			16-2.5TR	•		2.5	9.525	16	1.53	1.2	1.4	30° Internal
Internal		16-3.0TR	•			16-3.0TR	•		3.0	9.525	16	1.75	1.3	1.5	
Inte		22-4.0TR	•	•		22-4.0TR	•		4.0	12.7	22	2.25	1.7	1.9	
		22-5.0TR	•	•		22-5.0TR			5.0	12.7	22	2.75	2.1	2.5	External
		27-6.0TR	•	•		27-6.0TR	•		6.0	15.875	27	3.50	2.3	2.7	

Applicable holders D31, D32

•: Stock item

## American ACME (ACME)

-			-	_			_	_	Pitch		Dime	ensions	(mm)		
Type	D	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	11-16ACME			EL	11-16ACME			16	6.35	11	0.92	1.0	1.1	
		16-16ACME				16-16ACME			16	9.525	16	0.92	1.0	1.1	
		16-14ACME				16-14ACME			14	9.525	16	1.03	1.0	1.2	
		16-12ACME				16-12ACME			12	9.525	16	1.19	1.1	1.2	x   x
=		16-10ACME				16-10ACME			10	9.525	16	1.52	1.3	1.4	29° Internal
ir në		16-8ACME				16-8ACME			8	9.525	16	1.84	1.4	1.5	
X.	16-8ACME 16-8ACME 16-6ACME 16-6ACME 22-6ACME 22-6ACME		6	9.525	16	2.37	1.7	1.9							
ш		22-6ACME	•			22-6ACME	•		6	12.7	22	2.37	1.8	2.1	External
		22-5ACME	•			22-5ACME	•		5	12.7	22	2.79	2.0	2.3	
		27-4ACME				27-4ACME			4	15.875	27	3.43	2.4	2.7	
	IR	11-16ACME			IL	11-16ACME			16	6.35	11	0.92	0.9	0.9	
		16-16ACME				16-16ACME			16	9.525	16	0.92	1.0	1.1	,f,
		16-14ACME				16-14ACME			14	9.525	16	1.03	1.1	1.2	x
_		16-12ACME				16-12ACME			12	9.525	16	1.19	1.2	1.3	29° Internal
rna		16-10ACME	•			16-10ACME			10	9.525	16	1.52	1.2	1.3	
Internal		16-8ACME	•			16-8ACME			8	9.525	16	1.84	1.4	1.5	
_		16-6ACME				16-6ACME			6	9.525	16	2.37	1.7	1.9	External
		22-6ACME	•			22-6ACME			6	12.7	22	2.37	1.8	2.1	The state of the s
		22-5ACME	•			22-5ACME			5	12.7	22	2.79	2.0	2.3	
		27-4ACME	•			27-4ACME			4	15.875	27	3.43	2.3	2.6	

## Stub ACME (STACME)

			_	L					Pitch		Dime	nsions	(mm)		
Type	D	esignation (Right)	PC3030T	PC9070T		esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	11-16STACME			EL	11-16STACME			16	6.35	11	0.60	1.0	1.0	
		16-16STACME				16-16STACME			16	9.525	16	0.60	1.0	1.0	
		16-14STACME				16-14STACME			14	9.525	16	0.67	1.1	1.1	
		16-12STACME				16-12STACME			12	9.525	16	0.76	1.2	1.2	<u>→</u>
		16-10STACME				16-10STACME			10	9.525	16	1.02	1.2	1.3	×
nal		16-8STACME				16-8STACME			8	9.525	16	1.21	1.4	1.5	29° Internal
External		16-6STACME				16-6STACME			6	9.525		l l			
ш		22-6STACME				22-6STACME			6	12.7	22	1.52	1.7		
		22-5STACME				22-5STACME		External							
	27-4STACME	27-4STACME				27-4STACME			4	15.875	27	2.16	2.3	2.4	
		27-3STACME				27-3STACME			3	15.875	27	2.79	2.9	2.9	
	IR	11-16STACME			IL	11-16STACME			16	6.35	11	0.60	1.0	1.0	
		16-16STACME				16-16STACME			16	9.525	16	0.60	1.0	1.0	
		16-14STACME				16-14STACME			14	9.525	16	0.67	1.1	1.1	<del> - </del>
		16-12STACME				16-12STACME			12	9.525	16	0.76	1.1	1.2	×
a		16-10STACME				16-10STACME			10	9.525	16	1.02			29° Internal
Internal	16-8STACME	16-8STACME				16-8STACME			8	9.525	16	1.21	1.4	1.5	
<u>=</u>		16-6STACME				16-6STACME			6	9.525	16	1.52	1.7	1.8	
		22-6STACME				22-6STACME			6	12.7	22	1.52	1.7	1.8	d
		22-5STACME				22-5STACME			5	12.7	22	1.78	2.1	2.3	
		27-4STACME				27-4STACME			4	15.875	27	2.16	2.3	2.4	
		27-3STACME				27-3STACME			3	15.875	27	2.79	2.9	2.9	

Applicable holders D31, D32

# **UNJ (Unified Constant Thread)**

							١.		Pitch		Dime	ensions	(mm)		
Type	De	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	X	f	Picture
	ER	11-48UNJ			EL	11-48UNJ			48	6.35	11	0.31	0.6	0.5	
		11-44UNJ				11-44UNJ			44	6.35	11	0.33	0.6	0.6	
		11-40UNJ				11-40UNJ			40	6.35	11	0.37	0.6	0.6	
		11-36UNJ				11-36UNJ			36	6.35	11	0.41	0.6	0.6	
		11-32UNJ				11-32UNJ			32	6.35	11	0.46	0.6	0.7	
		11-28UNJ				11-28UNJ			28	6.35	11	0.52	0.7	0.7	
		11-24UNJ	•			11-24UNJ			24	6.35	11	0.61	0.7	8.0	
		11-20UNJ				11-20UNJ			20	6.35	11	0.73	0.8	0.9	
		11-18UNJ				11-18UNJ			18	6.35	11	0.81	8.0	1.0	
		11-16UNJ				11-16UNJ			16	6.35	11	0.92	0.9	1.1	
		11-14UNJ				11-14UNJ			14	6.35	11	1.05	1.0	1.2	
		16-48UNJ				16-48UNJ			48	9.525	16	0.31	0.6	0.5	,f.
		16-44UNJ				16-44UNJ			44	9.525	16	0.33	0.6	0.6	x
		16-40UNJ				16-40UNJ			40	9.525	16	0.37	0.6	0.6	5/16P Internal
		16-36UNJ				16-36UNJ			36	9.525	16	0.41	0.6	0.6	
nal		16-32UNJ	•			16-32UNJ			32	9.525	16	0.46	0.6	0.7	
External		16-28UNJ	•			16-28UNJ			28	9.525	16	0.52	0.7	0.7	Rmax0.18042P
ũ		16-24UNJ	•			16-24UNJ			24	9.525	16	0.61	0.7	8.0	d Rmax0.15011P External
		16-20UNJ	•			16-20UNJ			20	9.525	16	0.73	8.0	0.9	
		16-18UNJ				16-18UNJ			18	9.525	16	0.81	8.0	1.0	
		16-16UNJ	•			16-16UNJ			16	9.525	16	0.92	0.9	1.1	
		16-14UNJ				16-14UNJ			14	9.525	16	1.05	1.0	1.2	
		16-13UNJ				16-13UNJ			13	9.525	16	1.13	1.0	1.3	
		16-12UNJ	•			16-12UNJ			12	9.525	16	1.22	1.1	1.3	
		16-11UNJ				16-11UNJ			11	9.525	16	1.33	1.2	1.5	
		16-10UNJ				16-10UNJ	•		10	9.525	16	1.47	1.2	1.5	
		16-9UNJ				16-9UNJ			9	9.525	16	1.63	1.3	1.7	
		16-8UNJ				16-8UNJ			8	9.525	16	1.83	1.2	1.6	
		22-7UNJ				22-7UNJ			7	12.7	22	2.09	1.7	2.3	
		22-6UNJ				22-6UNJ			6	12.7	22	2.44	1.7	2.3	
		22-5UNJ				22-5UNJ			5	12.7	22	2.93	1.8	2.5	
		27-4.5UNJ				27-4.5UNJ			4.5	15.875	27	3.26	2.0	2.7	
		27-4UNJ				27-4UNJ			4	15.875	27	3.67	2.2	3.0	

● Applicable holders D31 • : Stock item

# **UNJ (Unified Constant Thread)**

			L	_			L	L	Pitch		Dime	ensions	(mm)		
Туре	D	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	х	f	Picture
	IR	11-48UNJ			IL	11-48UNJ			48	6.35	11	0.28	0.6	0.5	
		11-44UNJ				11-44UNJ			44	6.35	11	0.30	0.6	0.6	
		11-40UNJ				11-40UNJ			40	6.35	11	0.33	0.6	0.6	
		11-36UNJ				11-36UNJ			36	6.35	11	0.37	0.6	0.6	
		11-32UNJ				11-32UNJ			32	6.35	11	0.42	0.6	0.7	
		11-28UNJ				11-28UNJ			28	6.35	11	0.47	0.7	0.7	
		11-24UNJ				11-24UNJ			24	6.35	11	0.55	0.7	8.0	
		11-20UNJ				11-20UNJ			20	6.35	11	0.66	8.0	0.9	
		11-18UNJ				11-18UNJ			18	6.35	11	0.74	8.0	1.0	
		11-16UNJ				11-16UNJ			16	6.35	11	0.83	0.9	1.1	
		11-14UNJ				11-14UNJ			14	9.525	11	0.95	1.0	1.2	
		16-48UNJ				16-48UNJ			48	9.525	16	0.28	0.6	0.5	f
		16-44UNJ				16-44UNJ			44	9.525	16	0.30	0.6	0.6	
	1	16-40UNJ				16-40UNJ			40	9.525	16	0.33	0.6	0.6	5/16P Internal
		16-36UNJ				16-36UNJ			36	9.525	16	0.37	0.6	0.6	600
Jal		16-32UNJ				16-32UNJ			32	9.525	16	0.42	0.6	0.7	
Internal		16-28UNJ				16-28UNJ			28	9.525	16	0.47	0.7	0.7	Rmax0.18042P
2		16-24UNJ				16-24UNJ			24	9.525	16	0.55	0.7	8.0	d Rmax0.15011P External
		16-20UNJ				16-20UNJ			20	9.525	16	0.66	8.0	0.9	
		16-18UNJ				16-18UNJ			18	9.555	16	0.74	8.0	1.0	
		16-16UNJ				16-16UNJ			16	9.525	16	0.83	0.9	1.1	
		16-14UNJ				16-14UNJ			14	9.525	16	0.95	1.0	1.2	
		16-13UNJ				16-13UNJ			13	9.525	16	1.02	1.0	1.3	
		16-12UNJ				16-12UNJ	•		12	9.525	16	1.11	1.1	1.3	
		16-11UNJ				16-11UNJ			11	9.525	16	1.21	1.2	1.5	
		16-10UNJ				16-10UNJ			10	9.525	16	1.33	1.2	1.5	
		16-9UNJ				16-9UNJ			9	9.525	16	1.48	1.3	1.7	
		16-8UNJ				16-8UNJ			8	9.525	16	1.66	1.2	1.6	
		22-7UNJ				22-7UNJ			7	12.7	22	1.90	1.7	2.3	
		22-6UNJ				22-6UNJ			6	12.7	22	2.21	1.7	2.3	
		22-5UNJ				22-5UNJ			5	12.7	22	2.66	1.8	2.5	
		27-4.5UNJ				27-4.5UNJ			4.5	15.875	27	2.95	2.0	2.7	
		27-4UNJ				27-4UNJ			4	15.875	27	3.32	2.2	3.0	

● : Stock item

## **American Buttress (ABUT)**

			_	_			_	_	Pitch		Dime	nsions	(mm)		
Type	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	11-20ABUT			EL	11-20ABUT			20	6.35	11	0.84	1.0	1.4	
		11-16ABUT				11-16ABUT			16	6.35	11	1.05	1.3	1.9	
		16-20ABUT	•			16-20ABUT			20	9.525	16	0.84	1.0	1.4	x_ <del>-   -</del>
=		16-16ABUT				16-16ABUT			16	9.525	16	1.05	1.3	1.9	0.16316P 7° Internal
External		16-12ABUT				16-12ABUT			12	9.525	16	1.40			
xte		16-10ABUT				16-10ABUT			10	9.525	16	1.68	1.5	2.3	
	3.2	0.16316P - External													
	22-8ABUT 22-6ABUT	22-6ABUT				22-6ABUT			6	12.7	22	2.80	2.2	3.5	- I - Literia
	IR	11-20ABUT	•		IL	11-20ABUT			20	6.35	11	0.84	1.0	1.4	
		11-16ABUT				11-16ABUT			16	6.35	11	1.05	1.3	1.9	
_		16-20ABUT	•			16-20ABUT			20	9.525 16 0.84 1.0 1.4	0.16316P 7° Internal				
Internal	16- 16-	16-16ABUT				16-16ABUT			16	9.525	16	1.05	1.3	1.9	
nte		16-12ABUT	•			16-12ABUT			12	9.525	16	1.40	1.4	2.0	
_		16-10ABUT	•			16-10ABUT			10	9.525	16	1.68	1.5	2.3	0.16316P External
		22-8ABUT				22-8ABUT			8	12.7	22	2.10	2.0	3.2	
		22-6ABUT				22-6ABUT			6	12.7	22	2.80	2.2	3.5	

Applicable holders D31, D32

#### •: Stock item

## **British Buttress (BBUT)**

			_	-			_	_	Pitch		Dime	ensions	(mm)		
Туре	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	16-16BBUT	•		EL	16-16BBUT			16	9.525	16	0.80	1.1	1.6	
		16-12BBUT				16-12BBUT			12	9.525	16	1.07	1.4	2.1	X¬ f
=		16-10BBUT				16-10BBUT			10	9.525	16	1.28	1.4	2.2	0.2754P 7° Internal
rna		16-8BBUT	•			16-8BBUT			8	9.525	16	1.61	1.6	2.5	
External	-	22-8BBUT				22-8BBUT			8	12.7	22	1.61	1.6	2.5	
															<u>0.2754P</u> →External
	IR	16-16BBUT	•		IL	16-16BBUT			16	9.525	16	0.80	1.1	1.6	
		16-12BBUT				16-12BBUT			12	9.525	16	1.07	1.4	2.1	, f , <b>←</b> X
_		16-10BBUT				16-10BBUT			10	9.525	16	1.28	1.4	2.2	0.2754P 7° Internal
rna		16-8BBUT				16-8BBUT			8	9.525	16	1.61	1.6	2.5	
Internal		22-8BBUT				22-8BBUT			8	12.7	22	1.61	1.6	2.5	
_															d 0.2754P External

Applicable holders D31, D32



## **Metric Buttress (SAGE)**

-	_		_	_	_		ь	<b>–</b>	Pitch		Dime	nsions	(mm)				
Туре	D	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(mm)	d	L	hmin	х	f	Picture		
	ER	16-2.0SAGE			EL	16-2.0SAGE			2.0	9.525	16	1.74	1.47	2.08			
		22-2.0SAGE				22-2.0SAGE			2.0	12.7	22	1.74	1.47	2.08	0.26384P 3° Internal		
nal		22-3.0SAGE	•			22-3.0SAGE			3.0	12.7	22	2.60	1.79	2.60	0 0		
External		27-4.0SAGE	•			27-4.0SAGE			4.0	15.875	27	3.55	1.93	3.20			
Û														0.26384P Externa			
	IR	16-2.0SAGE	•		IL	16-2.0SAGE			2.0	9.525	16	1.50	1.52	2.2			
		22-3.0SAGE				22-3.0SAGE			3.0	12.7	22	2.25	1.66	2.9	0.26384P 3° Internal		
व्य		27-4.0SAGE	•			27-4.0SAGE			4.0	5/8	27	3.09	2.12	3.2	30°		
Internal															0.26384P External		

● : Stock item

### **API**

			_	_			L	_	Pitch		Dime	nsions	(mm)		
Туре	D	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	Х	f	Picture
	ER	22-4API382	•		EL	22-4API382			4	12.7	22	3.09	2.1	2.8	
		22-4API383				22-4API383			4	12.7	22	3.08	2.1	2.8	
		22-4API502	•			22-4API502			4	12.7	22	3.75	2.0	2.9	
		22-4API503	•			22-4API503			4	12.7	22	3.74	2.0	2.9	
		22-5API403				22-5API403			5	12.7	22	2.99	1.8	2.6	×
nal		22-6API551				22-6API551			6	12.7	22	1.41	2.6	2.0	30° 30° Internal
External		27-4API382	•			27-4API382			4	15.875	27	3.09	2.1	2.8	
ŭ		27-4API383				27-4API383			4	15.875	27	3.08	2.1	2.8	900
		27-4API502				27-4API502			4	15.875	27	3.75	2.1	3.1	d External
		27-4API503	•			27-4API503			4	15.875	27	3.74	2.1	3.1	
		27-5API403	•			27-5API403			5	15.875	27	2.99	1.9	2.7	
	IR	22-4API382			IL	22-4API382			4	12.7	22	3.09	2.1	2.8	
		22-4API383				22-4API383			4	12.7	22	3.08	2.1	2.8	4
		22-4API502	•			22-4API502			4	12.7	22	3.75	2.1	3.1	
		22-4API503				22-4API503			4	12.7	22	3.74	2.0	2.9	Internal
a		22-5API403	•			22-5API403			5	12.7	22	2.99	1.8	2.6	30° 30°
Internal		22-6API551	•			22-6API551			6	12.7	22	1.41	2.6	2.0	
Ξ		27-4API382 27-4API383				27-4API382			4	15.875	27	3.09	2.1	2.8	90° a
						27-4API383			4	15.875	27	3.08	2.1	2.8	d External
		27-4API502	•			27-4API502			4	15.875	27	3.75	2.1	3.1	
		27-4API503	•			27-4API503			4	15.875	27	3.74	2.1	3.1	
		27-5API403	•			27-5API403			5	15.875	27	2.99	1.9	2.7	

● : Stock item

Applicable holders D31, D32

### **API Buttress Casing (BUT)**

4.	_		-	_	_		-	_	Pitch		Dim	nensi	ons (m	ım)		
Туре	De	esignation (Right)	PC3030T	PC9070T	De	esignation (Left)	PC3030T	PC9070T	(tpi)	IPF	d	L	hmin	Х	f	Picture
	ER	22-5BUT75	•		EL	22-5BUT75			5	0.75	12.7	22	1.55	3.1	1.9	f
		22-5BUT1				22-5BUT1			5	1	12.7	22	1.55	3.1	1.9	X Internal
External																d h a a External
	IR	22-5BUT75	•		IL	22-5BUT75			5	0.75	12.7	22	1.55	2.8	1.9	$\alpha = \arctan(IPF/24)$
		22-5BUT1	•			22-5BUT1			5	1	12.7	22	1.55	2.8	1.9	x (L-arcig(II 1724)
Internal																n en a la company de la compan

## **API Round Casing & Tubing (APIRD)**

4)	_		-	F	_		-	-	Pitch		Dime	nsions	(mm)		
Type	D	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(tpi)	d	L	hmin	х	f	Picture
	ER	16-10APIRD	•		EL	16-10APIRD			10	9.525	16	1.41	1.2	1.4	, f.
		16-8APIRD	•			16-8APIRD			8	9.525	16	1.81	1.3	1.5	X
External															30° 30° members
	IR	16-10APIRD	•		IL	16-10APIRD			10	9.525	16	1.41	1.2	1.4	f
		16-8APIRD	•			16-8APIRD			8	9.525	16	1.81	1.3	1.5	X X
Internal															30° 30° Internal
<b>→</b> A	pplica	able holders D	31, I	032											• : Stock item

### **Extreme Line Casing (EL)**

			_	_			_	_	Pitch		Dim	nensi	ons (m	ım)		
Type	De	esignation (Right)	PC3030T	PC9070T	D	esignation (Left)	PC3030T	PC9070T	(tpi)	IPF	d	L	hmin	х	f	Picture
	ER	22-6EL15			EL	22-6EL15			6	1.5	12.7	22	1.21	1.9	1.9	.f.
		22-5EL125				22-5EL125			5	1.25	12.7	22	1.71	2.3	2.4	x Internal
External																h 90 a External
	IR	22-6EL15			IL	22-6EL15			6	1.5	12.7	22	1.39	1.8	1.9	f
		22-5EL125				22-5EL125			5	1.25	12.7	22	1.91	2.2	2.4	α=arctg (IPF/24)
Internal																d d external


• : Stock item

# ER(L)H

### (Screw on system)









Righthand drawing

(mm)

	Designation	Inscribed circle	н	w	L	S	н	Q	Insert screw	Shim screw	Screw RH	Screw LH	Wrench
ER(L)H	08N-11	6.35	8	8	136.4	11	8	17.5					
	10N-11	6.35	10	10	70.0	11	10	17.5	ST11N	-	-	-	TW08P
	12N-11	6.35	12	12	80.0	12	12	17.5					
	12N-16	9.525	12	12	83.2	16	12	22	ST16N	-	-	-	TW10P
	09-16	9.525	9.52	9.52	63.6	16	9.52	20.5					
	12-16	9.525	12	12	83.2	16	12	22					
	16-16	9.525	16	16	100.0	16	16	20.5	ST16	STA16	ATE16	ATI22	TW10P
	20-16	9.525	20	20	128.6	20	20	30	0110	01/110	MEIO	711122	1 ** 101
	25-16	9.525	25	25	153.6	25	25	30					
	32-16	9.525	32	32	173.6	32	32	30					
	25-22	12.7	25	25	155.7	25	25	36					
	32-22	12.7	32	32	175.7	32	32	36	ST22	STA22	ATE22	ATI22	TW20P
	40-22	12.7	40	40	205.7	40	40	36					
	25-27	15.875	25	25	151.6	32	25	35					
	32-27	15.875	32	32	176.6	32	32	40	ST27	STA27	ATE27	ATI27	TW25L
	40-27	15.875	40	40	206.6	40	40	40	3127	O II (L)	,	, IL1	111202
	50-27	15.875	50	50	256.6	50	50	40					


<sup>→</sup> Applicable inserts D10~D13, D16, D18, D19, D22, D23~D26

# ER(L)H-C

### (Clamp on system)









Righthand drawing

													(mm)
	Designation	Inscribed circle	н	W	L	s	н	Q	Shim screw	Clamp	Screw RH	Screw LH	Wrench
ER(L)H	20-16C	9.525	20	20	128.6	20	20	30					TW10P
	25-16C	9.525	25	25	153.6	25	25	30	STA16	CTH16	ATE16	ATI16	TW15P
	32-16C	9.525	32	32	173.6	32	32	30					1 ** 101
	25-22C	12.7	25	25	155.7	25	25	36					
	32-22C	12.7	32	32	175.7	32	32	36	STA22	CTH22	ATE22	ATI22	TW20P
	40-22C	12.7	40	40	205.7	40	40	36					
	25-27C	15.875	25	25	151.6	25	25	35					
	32-27C	15.875	32	32	176.6	32	32	40	STA27	CTH27	ATE27	ATI27	TW25L
	40-27C	15.875	40	40	206.6	40	40	40	017/27	O I I I E I	, L.Z.	711127	
	50-27C	15.875	50	50	256.6	50	50	40					

<sup>→</sup> Applicable inserts D10~D13, D16, D18, D19, D22, D23~D26

 $<sup>\</sup>cdot$  Helix angle is 1.5° for all holders  $\cdot$  No shim needed for N type holder


<sup>•</sup> Helix angle is 1.5° for all holders

## **D** Internal Holder

## IR(L)H

### (Screw on system)







														(mm)
_		Inscribed		٠.	<b>.</b>					Insert screw	Shim screw	Screw RH	Screw LH	Wrench
	Designation	circle	ØD	Ød	Ød1	Н	L	S	Q	O)				Ø
IR(L)H	10DN-11	6.35	13	10	10.0	9.5	100	7.3	-					
	10N-11	6.35	13	20	10.0	18.0	180	7.3	25	ST11N	-	-	-	TW08P
	13N-11	6.35	16	20	13.0	18.0	180	8.9	32					
	13N-16	9.525	17	20	12.7	18.0	180	10.3	32					
	16N-16	9.525	20	20	16.0	18.0	180	11.5	40	ST16N	-	-	-	TW10P
	16DN-16	9.525	20	16	16.0	15.2	150	11.3	32					
	20-16	9.525	24	20	20.0	18.0	180	13.4	40	ST16				
	25-16	9.525	29	32	25.0	29.0	250	16.3	60					
	25D-16	9.525	29	25	24.5	22.6	200	16.1	45		STA16	ATI16	ATE16	TW10P
	32-16	9.525	36	32	32.0	29.0	250	19.6	60					
	40-16	9.525	44	40	40.0	36.0	300	23.8	60					
	20N-22	12.7	27	20	20.0	18.0	180	15.6	50	ST22N	-	-	-	TW20P
	25-22	12.7	32	32	25.0	29.0	250	17.4	60					
	25D-22	12.7	32	25	24.6	22.6	200	17.2	45	ST22	STA22	ATI22	ATE22	TW20P
	32-22	12.7	39	32	32.0	29.0	250	21.5	60	0122	STAZZ	ATIZZ	AILL	1 44201
	40-22	12.7	47	40	40.0	36.0	300	25.8	60					
	32-27	15.875	40	32	32.0	29.0	250	22.4	60					
	40-27	15.875	48	40	40.0	36.0	300	26.4	60	ST27	STA27	ATI27	ATE27	TW25L
50-27	50-27	15.875	58	50	50.0	45.0	350	31.4	75	3127	UIAZI	ALIZI	AILLI	IVVZJL
	60-27	15.875	69	60	60.0	54.0	400	36.4	75					

<sup>→</sup> Applicable inserts D10, D11, D14, D15, D17, D20~D25, D27~D30

# IR(L)H-C (Clamp on system)







Righthand drawing (mm)

Righthand drawing

D	esignation	Inscribed circle	ØD	Ød	Ød1	н	L	s	Q	Shim screw	Clamp	Screw RH	Screw LH	Wrench
IR(L)H	20-16C	9.525	24	20	20.0	18.0	180	13.4	50					
	25-16C	9.525	29	32	25.0	28.0	250	16.3	60					TW10P
	25D-16C	9.525	29	25	24.6	22.6	200	16.1	45	STA16	CTH16	ATI16	ATE16	TW15P
	32-16C	9.525	36	32	32.0	29.0	250	19.6	60					1 44 151
	40-16C	9.525	44	40	40.0	36.0	300	23.8	60					
	25-22C	12.7	32	32	25.0	29.0	250	17.4	60					
	25D-22C	12.7	32	25	24.6	22.6	200	17.2	45	STA22	CTH22	ATI22	ATE22	TW20P
	32-22C	12.7	39	32	32.0	29.0	250	21.5	60	JIAZZ	011122	ATIZZ	AILL	1 44201
	40-22C	12.7	47	40	40.0	36.0	300	25.8	60					
	32-27C	15.875	40	32	32.0	29.0	250	22.4	60					
	40-27C	15.875	48	40	40.0	36.0	300	26.4	60		CTH27	ATI27	ATE27	TW25L
	50-27C	15.875	58	50	50.0	45.0	350	31.4	75	SIAZI	011127	AHZI	AIEZ/	I VVZOL
	60-27C	15.875	69	60	60.5	54.0	400	36.4	75	1				

<sup>→</sup> Applicable inserts D10, D11, D14, D15, D17, D20~D25, D27~D30


<sup>•</sup> Helix angle is 1.5° for all holders • No shim needed for N type holder

Helix angle is 1.5° for all holders

## **VTH**



**VETR** 



rew	Screw	Wrench
		(mm)
	Ri	ighthand drawing
		5

	Designation	H = (h)	W	L	S	Insert	Clamp	Clamp screw	Screw	Wrench
VTH	2020R	20	20	125	26.4					TMACD
	2525R	25	25	150	33.4	VETR	CS6R1	DHA0617	FTKA03510	TW15P HW30L
	3225R	32	25	170	33.4					HVV3UL

### Vertical type thread insert

			Uncoated		Insert		
Picture	De	signation	ST10	Pitch (mm)	θ	f	Configuration
	VETR	080		0.8	60°	1.4	
		100	•	1.0	60°	1.4	f
		125		1.25	60°	1.4	d 20°
		150	•	1.5	60°	1.2	
		175		1.75	60°	1.2	
		200	•	2.0	60°	1.2	
		250		2.5	60°	1.4	t
		300	•	3.0	60°	1.6	d: 9.525 t: 4.76
		150F	•	0.8~1.5	60°	1.4	a. 0.020
		300F	•	1.5~3.0	60°	1.6	

•: Stock item

### Thread milling holders code system




















### Thread milling inserts code system
















# D

### Thread milling

### The right tool for the job

#### Small diameter type







**Tool holder**: TMSR Insert: TM L = 10.4 mm For small bore diameters down to 9.5 mm

#### Standard type







**Tool holder**: TMSR **Insert**: TM2 For standard length threads

#### Long type







**Tool holder**: TMSR **Insert**: TM2 For long or remote threads

#### **Tapered type**









**Tool holder**: TMSR **Insert**: TM2 (BSPT, NPT, NPTF) For standard length threads

### Thread milling methods


#### **External threading**




Right handed thread conventional milling



Left handed thread down milling




Right handed thread down milling




Left handed thread conventional milling


#### Internal threading




Right handed thread down milling



Left handed thread conventional milling



Right handed thread conventional milling





Left handed thread down milling



### **Technical Information for Thread Milling**

### **○** Tooling recommendation for given internal thread specification






### **ISO**


Pitch (mm)	Nominal dia. (mm)	Holder	Insert	ℓ-Tool holder overhang	D-Tool cutting dia.*	Min.Thread depth (Profile depth)
0.75	11	TMSR 12-10	TM2I 10-0.75ISO	12.0	9.0	0.43
	12-14	TMSR 12-10	TM2I 10-1.0ISO	12.0	9.0	
	15-18	TMSR 12-11	TM2I 11-1.0ISO	12.0	11.5	
1.0	20	TMSR 16-16	TM2I 16-1.0ISO	22.0	17.0	0.50
1.0	22	TMSR 20-22	TM2I 22-1.0ISO	29.0	19.0	0.58
	24	TMSR 20-16	TM2I 16-1.0ISO	43.0	20.0	
	25-28	TMSRL 25-16	TM2I 16-1.0ISO	25.0	22.0	
1.25	14	TMSR 12-10	TM2I 10-1.25ISO	12.0	9.0	0.72
	14-15	TMSR 12-10	TM2I 10-1.5ISO	12.0	9.0	
	16-20	TMSR 12-11	TM2I 11-1.5ISO	12.0	11.5	
	22	TMSR 16-16	TM2I 16-1.5ISO	22.0	17.0	
	24	TMSR 20-22	TM2I 22-1.5ISO	29.0	19.0	0.07
1.5	25-26	TMSR 20-16	TM2I 16-1.5ISO	43.0	20.0	0.87
	27-30	TMSRL 25-16	TM2I 16-1.5ISO	25.0	22.0	
	35-42	TMSR 25-27	TM2I 27-1.5ISO	52.0	30.0	
	45	TMSR 32-27	TM2I 27-1.5ISO	58.0	37.0	
	22	TMSRT 16-16	TM2I16-2.0ISO	22.0	15.5	
	24	TMSR 16-16	TM2I 16-2.0ISO	22.0	17.0	
	25	TMSR 20-22	TM2I 22-2.0ISO	29.0	19.0	
2.0	27	TMSR 20-16	TM2I 16-2.0ISO	43.0	20.0	1.15
	28-32	TMSRL 25-16	TM2I 16-2.0ISO	25.0	22.0	_
	39-42	TMSR 25-27	TM2I 27-2.0ISO	52.0	30.0	
	45-48	TMSR 32-27	TM2I 27-2.0ISO	58.0	37.0	
	42-48	TMSR 25-27	TM2I 27-3.0ISO	52.0	30.0	
3.0	50-52	TMSR 32-27	TM2I 27-3.0ISO	58.0	37.0	1.73
	45-52	TMSR 25-27	TM2I 27-4.0ISO	52.0	30.0	
	55	TMSR 32-38	TM2I 38-4.0ISO	55.0	35.0	1
4.0	56-58	TMSR 32-27	TM2I 27-4.0ISO	58.0	37.0	2.31
	60-65	TMSR 40-38	TM2I 38-4.0ISO	65.0	46.0	_
5.0	48-52	TMSR 32-38	TM2I 38-5.0ISO	55.0	35.0	2.89
	56	TMSR 32-38	TM2I 38-5.5ISO	55.0	35.0	0.47
5.5	60	TMSR 40-38	TM2I 38-5.5ISO	65.0		3.17
6.0	64-68	TMSR 40-38	TM2I 38-6.0ISO	65.0	46.0	3.46

<sup>•</sup> The recommended holder is the largest for the given thread specification

\* Holder with smaller or equal cutting diameters (D2) can also be used

### **○** Tooling recommendation for given internal thread specification






### UN


9/16-11/16 TMSR 12-11 TM2I 11-32UN 12 32 3/4-13/16 TMSR 16-16 TM2I 16-32UN 22 7/8-15/16 TMSR 20-16 TM2I 16-32UN 43 1 TMSR 25-16 TM2I 16-32UN 25	2.0 2.0 2.0 3.0 5.0 2.0 2.0	9.0 11.5 17.0 20.0 22.0 9.0	0.46
32 3/4-13/16 TMSR 16-16 TM2I 16-32UN 22 7/8-15/16 TMSR 20-16 TM2I 16-32UN 43 1 TMSR 25-16 TM2I 16-32UN 25	2.0 3.0 5.0 2.0 2.0	17.0 20.0 22.0 9.0	0.46
7/8-15/16         TMSR 20-16         TM2I 16-32UN         43           1         TMSR 25-16         TM2I 16-32UN         25	3.0 5.0 2.0 2.0 2.0	20.0 22.0 9.0	0.46
1 TMSR 25-16 TM2I 16-32UN 25	5.0 2.0 2.0 2.0	22.0 9.0	
	2.0 2.0 2.0	9.0	
T100 100 T100 10 10 T100 T100 T100 T100	2.0 2.0		
7/16-1/2 TMSR 12-10 TMI 10-28UN 12	2.0	115	
9/16-3/4 TMSR 12-11 TM2I 11-28UN 12			
28 13/16-7/8 TMSR 16-16 TM2I 16-28UN 22		17.0	0.52
15/16 TMSR 20-16 TM2I 16-28UN 43	3.0	20.0	
1-1 1/8 TMSRL 25-16 TM2I 16-28UN 25	5.0	22.0	
24 9/16-11/16 TMSR 12-11 TM2I 11-24UN 12	2.0	11.5	0.61
1/2-9/16 TMSR 12-10 TMI 10-20UN 12	2.0	9.0	
5/8-13/16 TMSR 12-11 TM2I 11-20UN 12	2.0	11.5	
7/8 TMSR 16-16 TM2I 16-20UN 22	2.0	17.0	
20 15/16-1 TMSR 20-16 TM2I 16-20UN 43	3.0	20.0	0.73
1 1/16-1 1/8 TMSRL 25-16 TM2I 16-20UN 25	5.0	22.0	
1 3/8-1 5/8 TMSR 25-27 TM2I 27-20UN 52	2.0	30.0	
1 11/16-1 13/16 TMSR 32-27 TM2I 27-20UN 28	8.0	37.0	
5/8 TMSR 12-11 TM2I 11-18UN 12	2.0	11.5	
1 1/16-1 3/16 TMSRL 25-16 TM2I 16-18UN 25	5.0	22.0	1
18 1 7/16-1 5/8 TMSR 25-27 TM2I 27-18UN 52	2.0	30.0	0.81
1 11/16 TMSR 32-27 TM2I 27-18UN 58	8.0	37.0	
11/16-13/16 TMSR 12-11 TM2I 11-16UN 12	2.0	11.5	
7/8-15/16 TMSR 16-16 TM2I 16-16UN 22	2.0	17.0	
1 TMSR 20-16 TM2I 16-16UN 43	3.0	20.0	1
16 1 1/16-1 3/16 TMSRL 25-16 TM2I 16-16UN 25	5.0	22.0	0.92
1 7/16-1 5/8 TMSR 25-27 TM2I 27-16UN 52	2.0	30.0	
1 11/16-1 7/8 TMSR 32-27 TM2I 27-16UN 58	8.0	37.0	
14 7/8 TMSR 12-11 TM2I 11-14UN 12	2.0	11.5	1.05
7/8 TMSRT 16-16 TM2I 16-12UN 22	2.0	15.5	
15/16 TMSR 16-16 TM2I 16-12UN 22	2.0	17.0	
1 TMSR 20-22 TM2I 22-12UN 29	9.0	19.0	
12 1 1/16 TMSR 20-16 TM2I 16-12UN 43	3.0	20.0	1.22
1 1/8-1 1/4 TMSRL 25-16 TM2I 16-12UN 25	5.0	22.0	
1 1/2-1 11/16 TMSR 25-27 TM2I 27-12UN 52	2.0	30.0	
1 3/4-1 15/16 TMSR 32-27 TM2I 27-12UN 58	8.0	37.0	
_ 1 11/16-1 15/16 TMSR 25-27 TM2I 27-8UN 52	2.0	30.0	
8 2-1 1/8 TMSR 32-27 TM2I 27-8UN 58	8.0	37.0	1.83
2-2 1/8 TMSR 25-27 TM2I 27-6UN 52	2.0	30.0	
	8.0	37.0	2.44
2 3/8-2 1/2 TMSR 40-38 TM2I 38-6UN 65	5.0	46.0	
	5.0	35.0	3.26
4 2 1/2 TMSR 40-38 TM2I 38-4UN 65	5.0	46.0	3.67

<sup>•</sup> The recommended holder is the largest for the given thread specification
• Holder with smaller or equal cutting diameters (D2) can also be used

### **Technical Information for Thread Milling**

### **○** Tooling recommendation for given internal thread specification





### **UNJ**

Pitch (tpi)	Nominal dia. (inch)	Holder	Insert	<b>ℓ-Tool holder</b> overhang	D-Tool cutting dia.*	Min.Thread depth (Profile depth)
24	9/16-11/16	TMSR 12-11	TM2I 11-24UNJ	12.0	11.5	0.55
	1/2	TMSR 12-10	TMI 10-20UNJ	12.0	9.0	
00	3/4-13/16	TMSR 12-11	TM2I 11-20UNJ	12.0	11.5	0.00
20	7/8 TMSR 16-16		TM2I 16-20UNJ	22.0	17.0	0.66
	15/16-1	TMSR 20-16	TM2I 16-20UNJ	43.0	20.0	
18	5/8	TMSR 12-11	TM2I 11-18UNJ	12.0	11.5	0.74
18	1 1/16-1 3/16	TMSRL 25-16	TM2I 16-18UNJ	25.0	22.0	0.74
	11/16-13/16	TMSR 12-11	TM2I 11-16UNJ	12.0	11.5	
	7/8-15/16	TMSR 16-16	TM2I 16-16UNJ	22.0	17.0	
16	1	TMSR 20-16	TM2I 16-16UNJ	43.0	20.0	0.83
10	1 1/16-1 3/16	TMSRL 25-16	TM2I 16-16UNJ	25.0	22.0	0.63
	1 7/16-1 5/8	TMSR 25-27	TM2I 27-16UNJ	52.0	30.0	]
	1 11/16-1 7/8	TMSR 32-27	TM2I 27-16UNJ	58.0	37.0	
14	7/8	TMSR 12-11	TM2I 11-14UNJ	12.0	11.5	0.95
	7/8	TMSRT 16-16	TM2I 16-12UNJ	22.0	15.5	
	15/16-1	TMSR 16-16	TM2I 16-12UNJ	22.0	17.0	]
12	1 1/16	TMSR 20-16	TM2I 16-12UNJ	43.0	20.0	1.11
12	1 1/8-1 1/4	TMSRL 25-16	TM2I 16-12UNJ	25.0	22.0	] '.''
	1 1/2-1 11/16	TMSR 25-27	TM2I 27-12UNJ	52.0	30.0	1
	1 3/4-1 15/16	TMSR 32-27	TM2I 27-12UNJ	58.0	37.0	]

### W


Pitch (tpi)	Nominal dia. (inch)	Holder	Insert	<b>ℓ-Tool holder</b> overhang	D-Tool cutting dia.*	Min.Thread depth (Profile depth)
	1/2-9/16	TMSR 12-10	TMEI 10-26W	12.0	9.0	
	5/8-3/4	TMSR 12-11	TM2EI 11-26 W	12.0	11.5	
26	13/16-7/8	TMSR 16-16	TM2EI 16-26W	22.0	17.0	0.63
	15/16-1	TMSR 20-16	TM2EI 16-26W	43.0	20.0	
	1 1/16-1 1/8	TMSRL 25-16	TM2EI 16-26W	25.0	22.0	
	9/16	TMSR 12-10	TM2EI 10-20W	12.0	9.0	
	5/8-13/16	TMSR 12-11	TM2EI 11-20W	12.0	11.5	
20	7/8-15/16	TMSR 16-16	TM2EI 16-20W	22.0	17.0	0.81
	1	TMSR 20-16	TM2EI 16-20W	43.0	20.0	
	1 1/16-1 3/16	TMSRL 25-16	TM2EI 16-20W	25.0	22.0	
	13/16	TMSR 16-16	TM2EI 16-16W	22.0	15.5	
	7/8-15/16	TMSR 16-16	TM2EI 16-16W	22.0	17.0	
16	1-1 1/16	TMSR 20-16	TM2EI 16-16W	43.0	20.0	1.02
10	1 1/8-1 1/4	TMSRL 25-16	TM2EI 16-16W	25.0	22.0	1.02
	1.4-1 5/8	TMSR 25-27	TM2EI 27-16W	52.0	30.0	
	1 3/4-1.9	TMSR 32-27	TM2EI 27-16W	28.0	37.0	
12	1 1/2-1 3/4	TMSR 25-27	TM2EI 27-12W	52.0	30.0	1.36
12	1 7/8	TMSR 32-27	TM2EI 27-12W	58.0	37.0	1.30
8	1 7/8-1.9	TMSR 25-27	TM2EI 27-8W	52.0	30.0	2.03
0	2.1-2 1/8	TMSR 32-27	TM2EI 27-8W	58.0	37.0	2.03
7	2	TMSR 25-27	TM2EI 27-7W	52.0	30.0	2.32
	2.1-2 1/8	TMSR 25-27	TM2EI 27-6W	52.0	30.0	
6	2 1/4	TMSR 32-38	TM2EI 38-6W	55.0	35.0	2.71
0	2 3/8-2.6	TMSR 32-27	TM2EI 27-6W	58.0	37.0	2./1
	2 5/8-2 3/4	TMSR 40-38	TM2EI 38-6W	65.0	46.0	
5	3	TMSR 40-38	TM2EI 38-5W	65.0	46.0	3.25
4.5	3 1/2	TMSR 40-38	TM2EI 38-4.5W	65.0	46.0	3.61




<sup>•</sup> The recommended holder is the largest for the given thread specification 

\* Holder with smaller or equal cutting diameters (D2) can also be used

### **○** Tooling recommendation for given internal thread specification





### **BSPT**

Pitch (tpi)	Nominal dia. (inch)	Holder	Insert	<b>ℓ-Tool holder</b> overhang	D-Tool cutting dia.*	Min.Thread depth (Profile depth)
19	3/8	TMSR 21-11	TM2EI 11-19 BSPT	20.0	11.5	0.86
14	1/2-3/4	TMSRT 16-11	TM2EI 16-14 BSPT	22.0	15.5	1.16
	1-1 1/4	TMSRT 20-16	TM2EI 16-11 BSPT	23.0	19.0	
11	1 1/2	TMSR 25-27	TM2EI 27-11 BSPT	52.0	30.0	1.48
	2-6	TMSRT 32-27	TM2EI 27-11 BSPT	58.0	37.0	

### **NPT**

Pitch (tpi)	Nominal dia. (inch)	Holder	Holder Insert		D-Tool cutting dia.*	Min.Thread depth (Profile depth)
14	1/2	TMSRT 16-16	TM2EI 16-14 NPT	22.0	15.5	1.33
14	3/4	TMSRT 20-16	TM2EI 16-14 NPT	23.0	19.0	1.33
	1	TMSRT 20-16	TM2EI 16-11.5 NPT	23.0	19.0	
11.5	1 1/4	TMSR 25-27	TM2EI 27-11.5 NPT	52.0	30.0	1.64
	1 1/2-2	TMSRT 32-27	TM2EI 27-11.5 NPT	58.0	37.0	
8	2 1/2	TMSRT 32-27	TM2EI 27-8 NPT	58.0	37.0	2.42
0	3-24	TMSR 40-38	TM2EI 38-8 NPT	65.0	46.0	2.42

### **NPTF**

Pitch (tpi)	Nominal dia. (inch)	Holder	Insert	ℓ-Tool holder overhang	D-Tool cutting dia.*	Min.Thread depth (Profile depth)
14	1/2	TMSRT 16-16	TM2EI 16-14 NPTF	22.0	15.5	1.05
14	3/4	TMSRT 20-16	TM2EI 16-14 NPTF	23.0	19.0	1.35
	1	TMSRT 20-16	TM2EI 16-11.5 NPTF	23.0	19.0	
11.5	1 1/2	TMSR 25-27	TM2EI 27-11.5 NPTF	52.0	30.0	1.63
	2	TMSRT 32-27	TM2EI 27-11.5 NPTF	58.0	37.0	
8	2 1/2	TMSRT 32-27	TM2EI 27-8 NPTF	58.0	37.0	2.38
8	3	TMSR 40-38	TM2EI 38-8 NPTF	65.0	46.0	2.38

<sup>•</sup> The recommended holder is the largest for the given thread specification
• Holder with smaller or equal cutting diameters (D2) can also be used




### **Technical Information for Thread Milling**

#### Minimum bore diameters for thread milling

Ditah	mm	0.5	0.6	0.7	0.75 0.80	0.9	1.0	1.25	1.5	1.75	2.0	-	2.5	3.0	3.5	4.0	4.5	5.0	5.5	-	6.0	-
Pitch	tpi	48	44	36	32	28	26 24	20 19	18 16	14	13 12	11.5 11	10	9 8	7	6	-	5	-	4.5	-	4
Holder designation	diameter									Minim	um dia	meter f	or mad	hining								
TMSR 12-10	9.0	9.5	9.7	9.9	10.0	10.4	10.7	11.4	12.0													
TMSR 20-10	9.0	9.5	9.7	9.9	10.0	10.4	10.7	11.4	12.0													
TMSR 12-11	11.5	12.0	12.2	12.4	12.5	12.9	13.2	13.9	14.5	15.1												
TMSR 20-11	11.5	12.0	12.2	12.4	12.5	12.9	13.2	13.9	14.5	15.1												
TMSRL 25-11	11.5	12.0	12.2	12.4	12.5	12.9	13.2	13.9	14.5	15.1												
TMSRT 16-16	15.5	16.0	16.2	16.4	16.5	16.9	17.2	17.9	18.5	19.0	19.5	20.0										
TMSR 16-16	17.0	17.6	17.8	18.0	18.2	18.7	19.0	19.6	20.0	20.5	21.0	21.5										
TMSR 16-22	17.0	17.6	17.8	18.0	18.2	18.7	19.0	19.6	20.0	20.5	21.0	21.5										
TMSR 20-22	19.0	19.7	20.0	20.2	20.4	20.8	21.0	21.6	22.0	22.5	23.0	23.5										
TMSRT 20-16	19.0	19.7	20.0	20.2	20.4	20.8	21.0	21.6	22.0	22.5	23.0	23.5										
TMSR 20-16	20.0	20.7	21.0	21.2	21.4	21.8	22.0	22.6	23.0	23.5	24.0	24.5										
TMSRW 25-22	22.0	22.7	23.0	23.2	23.4	23.8	24.0	24.6	25.0	25.5	26.0	26.5										
TMSRL 25-22	22.0	22.7	23.0	23.2	23.4	23.8	24.0	24.6	25.0	25.5	26.0	26.5										
TMSRL 25-16	22.0	22.7	23.0	23.2	23.4	23.8	24.0	24.6	25.0	25.5	26.0	26.5										
TMSR 25-27	30.0	30.7	31.0	31.2	31.4	31.8	32.0	32.8	33.5	34.1	34.6	35.6	36.6	39.0	42.0	45.0	48.0					
TMSRL 25-27	30.0	30.7	31.0	31.2	31.4	31.8	32.0	32.8	33.5	34.1	34.6	35.6	36.6	39.0	42.0	45.0	48.0					
TMSR 32-38	35.0								38.5	39.1	39.6	40.6	42.0	44.0	47.0	50.0	53.4	42.5	50.0	44.6	57.5	56.6
TMSR 32-27	37.0	38.0	38.2	38.4	38.6	39.1	39.5	40.4	41.0	41.5	42.0	43.0	44.0	46.5	49.0	52.0	55.5					
TMSRL 32-27	37.0	38.0	38.2	38.4	38.6	39.1	39.5	40.4	41.0	41.5	42.0	43.0	44.0	46.5	49.0	52.0	55.5					
TMSRT 32-27	37.0	38.0	38.2	38.4	38.6	39.1	39.5	40.0	41.0	41.5	42.0	43.0	44.0	46.5	49.0	52.0	55.5					
TMSR 40-38	46.0								49.5	50.1	50.6	51.6	53.0	55.0	55.2	55.6	55.0	52.5	54.0	54.5	57.5	56.6
TMSRL 40-38	46.0								49.5	50.1	50.6	51.6	53.0	55.0	55.2	55.6	55.0	52.5	54.0	54.5	57.5	56.6

- In order to perform a thread milling operation, a milling machine with three-axis control capability of helical interpolation is required
- Helical interpolation is a CNC function producing tool movement along a helical path. This helical motion combines circular movement in one plane with a simultaneous linear motion in a plane perpendicular to the first. For example, the path from point A to point B (Fig,A) on the envelope of the cylinder combines a circular movement in the x-y plane with a linear displacement in the z direction
- On most CNC systems this function can be executed in two different ways:
  - GO2: Helical interpolation in a clockwise direction
  - GO3: Helical interpolation in a counter-clockwise direction






Fig. B


- The thread milling operation (Fig. B) consists of circular rotation of fhe tool around its own axis togerther with an orbiting motion along the bore or workpiece circumference. During one such orbit, the tool will shift vertically one pitch length. These movements combined with the insert geometry create the required thread form. There are three acceptable ways of approaching the workpiece with the tool to initiate production of the thread:
  - 1. Tangential Arc Approach
  - 2. Radial Approach
  - 3. Tangential Line Approach


#### Tangential arc approach

• With this method, the tool enters and exits the workpiece smoothly. No marks are left on the workpiece and there is no vibration, even with harder materials. Although it requires slightly more complex programming than the radial approach (see below), this is the method recommended for machining the highest quality threads

Internal thread

**External thread** 






- 1-2: rapid approach
- 2-3: tool entry along tangential arc, with simultaneous feed along z-axis
- 3-4: helical movement during one full orbit (360°)
- 4-5: tool exit along tangential arc, with continuing feed along z-axis
- 5-6: rapid return


#### Radial approach

- This is the simplest method. There are two characteristics worth nothing about the radial approach:
  - A. a small vertical mark may be lift at the entry (and exit) point. This is of no significance to the thread itself
  - B. when using this method with very hard materials, there may be a tendency of the tool to vibrate as it approaches the full cutting depth
- Note: Radial feed during entry to the full profile depth should only be 1/3 of the subsequent circular feed

Internal thread

**External thread** 






- 1-2: radial entry
- 2-3: helical movement during one full orbit (360°)
- 3-4: radial exit

### Tangential line approach

 This method is very simple, and has all of the advantages of the tangential arc method However, it is applicable only with external threads


#### **External thread**



- 1-2: radial entry with simultaneous feed along z axis
- 2-3: helical movement during one full orbit (360°)
- 3-4: radial exit

### Preparing for the thread milling operation

#### Calculation of rotational velocity and feed at the cutting edge



$$n = \frac{vc \times 1000}{\pi \times D2}$$

$$vc = \frac{n \times \pi \times D2}{1000}$$

$$F1 = n \times z \times fn$$

n: Rotational Velocity (min-1)

vc: Cutting Speed (m/min)

D2: Tool holder Cutting Dia. (mm)


F1: Real Feed rate at the Cutting edges (mm/min)


z: No. of Cutting Edges

fn: Feed per Rooth per Rotation (mm/rev)

#### Calculation of feed rates at the tool center line

 On most CNC machines, the feed rate required for programming is that of the center-line of the tool.
 When dealing with linear tool movement, the feed rate at the cutting edge and the center line are identical, but with circular tool movement this is not the case
 The equations define the relationship between feed rates at the cutting edge and at the tool center line





#### Grades and applications

• Grade: PC9570T

 Application: First Choice for steel and cast iron A tough sub-micron substrate with TiCN coating Provides good fracture toughness and excellent wear resistance

### Trouble shooting

Pr	roblem	Possible	Solution
	Increased insert flank wear	Cutting speed too high Chip is too thin Insufficient coolant	
	Chipping of cutting edge	Chip is too thick Vibration	<ul> <li>Reduce feed rate/Use the tangential arc method Increase RPM</li> <li>Check stability</li> </ul>
	Material built-up on the cutting edge	Incorrect cutting speed Unsuitable carbide grade	Change cutting speed  Use a coated carbide grade
	Chatter/ vibration	Feed rate is too high Profile is too deep  Thread length is too long	<ul> <li>Execute two passes, each with increased cutting depth/</li> <li>Execute two passes, each cutting only half the thread length</li> </ul>
GG NOGG	Insufficient thread accuracy	Tool deflection	Reduce feed rate/Execute a "zero" cut

# Technical Information for Thread Milling


### Recommended cutting condition

				vc (m	n/min)	Feed fz	: (mm/t)		
		Workpiece	Hardness brinell (HB)	Gr	ade	Indexable	Solid		
			brillen (IID)	PC9570T	PC9070M	insert	endmill		
		Low carbon (C+0.1-0.25%)	125	100~210	80~250	0.05~0.3	0.03~0.15		
	Unalloyed steel	Medium carbon (C = 0.25-0.55%)	150	100~180	80~230	0.05~0.25	0.03~0.1		
		High carbon (C = 0.55-0.85%)	170	100~170	80~200	0.05~0.2	0.03~0.08		
		Non-hardened	180	90~160	60~180	0.05~0.25	0.03~0.1		
P	Low alloy steel	Hardened	275	80~150	60~170	0.05~0.2	0.03~0.07		
-		Hardened	350	70~140	60~160	0.05~0.15	0.01~0.03		
	Ligh allow stool	Annealed	200	60~130	40~100	0.05~0.2	0.03~0.05		
	High alloy steel	Hardened	325	70~110	30~80	0.05~0.1	0.01~0.03		
	Cast steel	Low alloy	200	100~170	80~250	0.05~0.15	0.03~0.1		
	Cast steel	High alloy	225	70~120	60~170	0.05~0.1	0.01~0.03		
	Ctainless steel forwitin	Non-hardened	200	100~170	60~150	0.05~0.15	0.04~0.1		
	Stainless steel ferritic	Hardened	330	100~170	60~120	0.05~0.1	0.01~0.05		
	Stainless steel	Austenitic	180	70~140	60~140	0.05~0.15	0.04~0.1		
	Austenitic	Super austenitic	200	70~140	60~130	0.05~0.1	0.04~0.1		
	Stainless steel	Non-hardened	200	70~140	60~160	0.05~0.15	0.04~0.1		
	cast ferritic	Hardened	330	70~140	60~110	0.05~0.1 0.03~0.			
М	Stainless steel	Austenitic	200	70~120	60~150	70 0.05~0.1 0.01~0.0 50 0.05~0.15 0.04~0.0 20 0.05~0.15 0.04~0.0 40 0.05~0.15 0.04~0.0 30 0.05~0.1 0.04~0.0 60 0.05~0.15 0.04~0.0 10 0.05~0.1 0.03~0.0 50 0.05~0.1 0.03~0.0 50 0.05~0.1 0.04~0.0 30 0.05~0.1 0.04~0.0 30 0.05~0.1 0.04~0.0 50 0.05~0.1 0.04~0.0 50 0.02~0.05 0.01~0.0 35 0.02~0.05 0.01~0.0 80 0.02~0.05 0.01~0.0	0.04~0.1		
IVI	cast austenitic	Hardened	330	70~120	60~100	Insert	0.03~0.05		
		Annealed (Iron based)	200	20~45	30~60	0.05~0.1	0.04~0.1		
	High temperature	Aged (Iron based)	280	20~30	20~50	170         0.05~0.1         0.0           150         0.05~0.15         0.0           120         0.05~0.1         0.0           140         0.05~0.15         0.0           130         0.05~0.1         0.0           160         0.05~0.1         0.0           110         0.05~0.1         0.0           150         0.05~0.1         0.0           60         0.05~0.1         0.0           50         0.02~0.05         0.0           35         0.02~0.05         0.0           30         0.02~0.05         0.0           80         0.02~0.05         0.0           45         0.01~0.03         0.0           160         0.02~0.08         0.0           150         0.02~0.05         0.0           160         0.05~0.15         0.0           160         0.05~0.15         0.0           120         0.05~0.1         0.0	0.01~0.03		
	alloys	Annealed (Nickel or Cobalt based)	250	15~20	15~35		0.01~0.03		
		Aged (Nickel or Cobalt based)	350	10~15	15~30	0.02~0.05	0.01~0.03		
	Titanium alloys	Pure 99.5 Ti	400Rm	70~140	40~80	0.02~0.05	0.03~0.05		
	mamum anoys	α+β alloys	1050Rm	20~50	20~50	0.02~0.05	0.03~0.05		
	Extra hard steel	Hardened & tempered	55HRC	20~45	15~45	0.01~0.03	0.005~0.01		
	Malleable	Ferritic (short chips)	130	60~130	70~160	0.02~0.08	0.01~0.03		
	cast iron	Pearlitic (long chips)	230	60~120	60~150	0.02~0.05	0.03~0.05		
K	Grey cast iron	Low tensile strength	180	60~130	70~160	0.05~0.15	0.05~0.1		
	Grey cast from	High tensile strength	260	60~100	40~120	0.05~0.1	0.03~0.05		
	Nodular SG iron	Ferritic	160	60~125	40~110	0.05~0.15	0.05~0.1		
	Nodular SG iron	Pearlitic	260	50~90	40~100	0.05~0.1	0.03~0.05		
	Aluminum alloys	Non-aging	60	100~250	200~300	0.1~0.4	0.1~0.25		
	Wrought	Aged	100	100~180	150~250	0.1~0.3	0.1~0.2		
		Cast	75	150~400	100~200	0.1~0.3	0.1~0.2		
N	Aluminum alloys	Cast & aged	90	150~280	120~220	0.05~0.25	0.1~0.15		
		Cast Si 13-22%	130	80~150	200~300	0.1~0.3	0.1~0.2		
	Copper and	Brass	90	120~210	200~300	0.1~0.3	0.1~0.25		
	copper alloys	Bronze and non-leaded copper	100	120~210	150~250	0.05~0.25	0.1~0.2		

#### Example

• At tool entry, set the Feed fz (mm/tooth) to 70% lower than the threading Feed


• Threading Feed: 0.3 (mm/t) • Tool entry Feed: 0.09 (mm/t)



### **ISO Metric**







Defined by: R262 (DIN 13) Tolerance class: 6g/6H

Insert	t size	Pitch			Desig	nation				_	
d	L	(mm)		External	PC9570T		Internal	PC9570T	L <sub>1</sub>	Tooth	Tool holde
		0.5		-		ТМІ	10-0.5ISO	•	10.0	20	
		0.75		-			10-0.75ISO		9.75	13	
6.0	10.4	1.0		-			10-1.0ISO	•	9.0	9	TMSR - 1
		1.25		-			10-1.25ISO		8.75	7	
		1.5		-			10-1.5ISO		9.0	6	
		0.5		-		TM2I	11-0.5ISO		10.0	20	
		0.75	TM2E	11-0.75ISO			11-0.75ISO	•	10.5	14	
		1.0		11-1.0ISO			11-1.0ISO	•	10.0	10	
6.35	11	1.25	1	11-1.25ISO			-		10.0	8	TMSR - 1
		1.25		-			11-1.25ISO		8.75	7	
		1.5		11-1.5ISO			-		9.0	6	
		1.5		-			11-1.5ISO	•	10.5	7	
		0.5		-		TM2I	16-0.5ISO		15.0	30	
		0.75	TM2E	16-0.75ISO			16-0.75ISO		15.0	20	
		0.8		-			16-0.8ISO		14.4	18	
		1.0		16-1.0ISO			-		14.0	14	
9.525	16	1.0		-			16-1.0ISO	•	15.0	15	TMSR - 1
		1.25		16-1.25ISO			16-1.25ISO		15.0	12	
		1.5		16-1.5ISO	•		16-1.5ISO	•	15.0	10	
		1.75		16-1.75ISO			16-1.75ISO		14.0	8	
		2.0		16-2.0ISO			16-2.0ISO	•	14.0	7	
		1.0	TM2E	22-1.0ISO		TM2I	22-1.0ISO		22.0	22	
		1.25		22-1.25ISO			22-1.25ISO		21.25	17	
9.525B	22	1.5		22-1.5ISO			22-1.5ISO	•	21.0	14	TMSR - 2
		1.75		22-1.75ISO			22-1.75ISO		21.0	12	
		2.0		22-2.0ISO	•		22-2.0ISO	•	22.0	11	
		1.0	TM2E	27-1.0ISO		TM2I	27-1.0ISO		26.0	26	
		1.25		27-1.25ISO			27-1.25ISO		25.0	20	
		1.5		27-1.5ISO			27-1.5ISO	•	25.5	17	
		1.75		27-1.75ISO			27-1.75ISO		24.5	14	
15.875	27	2.0		27-2.0ISO			27-2.0ISO	•	24.0	12	TMSR - 2
. 5.57 6	_,	2.5		27-2.5ISO			27-2.5ISO		25.0	10	
		3.0		27-3.0ISO			27-3.0ISO	•	24.0	8	
		3.5		27-3.5ISO			27-3.5ISO		24.5	7	
		4.0		27-4.0ISO			27-4.0ISO	•	24.0	6	
		4.5		27-4.5ISO			27-4.5ISO		22.5	5	
		1.5	TM2E	38-1.5ISO		TM2I	38-1.5ISO		36.0	24	
		2.0	-	38-2.0ISO			38-2.0ISO		36.0	18	
		3.0		38-3.0ISO			38-3.0ISO		36.0	12	
19.05B	38.5	4.0	-	38-4.0ISO			38-4.0ISO		32.0	8	TMSR - 3
		4.5	-	38-4.5ISO			38-4.5ISO		31.5	7	IMSR -
		5.0	-	38-5.0ISO			38-5.0ISO		30.0	6	
		5.5		38-5.5ISO			38-5.5ISO		33.0	6	
		6.0		38-6.0ISO			38-6.0ISO		30.0	5	

Applicable holders D49

All inserts except TMI10 code have 2 cutting edges


•: Stock item

### **American UNC**









Defined by: ANSI B1.1.74 Tolerance class: Class 2A/2B

lnoord	cizo	Dir. I			Doole	nation					(mm)
Insert	L	Pitch (tpi)		External	PC9570T	nation	Internal	PC9570T	L <sub>1</sub>	Tooth	Tool holder
u				External	PC95/01	TNAL		PC93/01	0.50	10	
		32 28		-		TMI	10-32UN 10-28UN		9.53 9.07	12 10	
		24	-	-			10-24UN		9.53	9	
6.0	10.4	20		-			10-20UN	•	8.89	7	TMSR - 10
		18	-	-		-	10-200N 10-18UN		8.47	6	
		16		-			10-16UN		7.94	5	
		48		-		TM2I	11-48UN		10.05	19	
		40		_		IIVIZI	11-40UN		10.05	16	
		32		_		-	11-32UN		10.10	13	
		28	TM2E	11-28UN			11-28UN		9.98	11	
		27		11-27UN			11-27UN		10.35	11	
6.35	11	24		11-24UN			11-24UN		9.53	9	TMSR - 11
		20		11-20UN		-	11-20UN		10.16	8	
		18		11-18UN			11-18UN	•	9.88	7	
		16		11-16UN			11-16UN		9.53	6	
		14		11-14UN			11-14UN		9.07	5	
		40		-		TM2I	16-40UN		14.61	40	
		32		-		110121	16-32UN		15.08	32	
		28	TM2E	16-28UN			16-28UN		14.51	28	
		27		16-27UN			16-27UN		14.11	27	
		24		16-24UN			16-24UN		14.82	24	
		20		16-20UN			16-20UN		13.97	20	
9.525	16	18		16-18UN			16-18UN		14.11	18	TMSR - 16
		16		16-16UN			16-16UN	•	14.29	16	
		14		16-14UN			16-14UN		14.51	14	
		13		16-13UN			16-13UN		13.68	13	
		12		16-12UN			16-12UN	•	14.82	12	
		11.5		16-11.5UN		1	16-11.5UN		13.25	11.5	
		24	TM2E	22-24UN		TM2I	22-24UN		21.16	20	
		20		22-20UN			22-20UN		21.59	17	
		18		22-18UN			22-18UN		21.17	15	
9.525B	22	16		22-16UN			22-16UN		20.64	13	TMSR - 22
		14	1	22-14UN			22-14UN		21.77	12	
		13		22-13UN			22-13UN		21.49	11	
		12		22-12UN			22-12UN		21.17	10	
		24	TM2E	27-24UN		TM2I	27-24UN		25.40	24	
		20		27-20UN		]	27-20UN		25.40	20	
		18		27-18UN			27-18UN		25.40	18	
		16		27-16UN			27-16UN		25.40	16	
		14		27-14UN			27-14UN		25.40	14	
		13		27-13UN			27-13UN		25.40	13	
		12		27-12UN			27-12UN		25.40	12	
		11.5		27-11.5UN			27-11.5UN		24.30	11	
15.875	27	11		27-11UN			27-11UN		25.40	11	TMSR - 27
		10		27-10UN			-		22.86	9	
		10		-			27-10UN		25.40	10	
		9		27-9UN			27-9UN		22.58	8	
		8		27-8UN			27-8UN		22.23	7	
		7		27-7UN			-		21.77	6	
		7		-			27-7UN		25.40	7	
		6		27-6UN			-		21.17	5	]
		6		-			27-6UN		25.40	6	
		6	TM2E	38-6UN		TM2I	38-6UN		38.87	8	
19.05	38.5	5		38-5UN			38-5UN		30.48	6	TMCD. 20
19.05	30.3	4.5		38-4.5UN			38-4.5UN		33.87	6	TMSR - 38


## D

## **UNJ(Unified Constant Thread)**









Defined by: MIL-S-8879C Tolerance class: 3A/3B

(mm)

Insert	Insert size			Designation						Taskh	Tool holder	
d	L	(tpi)		External	PC9570T	Internal		PC9570T	L <sub>1</sub>	Tooth	1001 Holder	
		24	-			TMI	10-24UNJ		9.53	9		
6.0	10.4	20		-			10-20UNJ		8.89	7	TMSR - 10	
6.0	10.4	18		-			10-18UNJ		8.47	6	TIVION - 10	
		16		-			10-16UNJ		9.53	8		
		24	TM2E	11-24UNJ		TM2I	11-24UNJ		9.53	9	TMSR - 11	
		20		11-20UNJ			11-20UNJ		10.16	8		
6.35	11	18		-			11-18UNJ		9.88	7		
		16		11-16UNJ			11-16UNJ		9.53	6		
		14		11-14UNJ			11-14UNJ		9.07	5		
		24	TM2E	16-24UNJ		TM2I	16-24UNJ		14.82	14		
		20		16-20UNJ			16-20UNJ		13.97	11		
		18		16-18UNJ			16-18UNJ		14.11	10		
9.525	16	16		16-16UNJ			16-16UNJ		14.29	9	TMSR - 16	
		14		16-14UNJ			16-14UNJ		14.51	8		
		13		16-13UNJ			-		13.68	7		
		12		16-12UNJ			16-12UNJ		14.82	7		
		16	TM2E	27-16UNJ		TM2I	27-16UNJ		25.40	16	TMSR - 27	
15.875	27	12		27-12UNJ			27-12UNJ		25.40	12		
		11		27-11UNJ			27-11UNJ		25.40	11		

Applicable holders D49

All inserts except TMI10 code have 2 cutting edges

•: Stock item


## rts **D**

### Whitworth (BSW, BSF, BSP, BSB)









BSW Defined by: B.S.84:1956, DIN 259, ISO228/1:1982 BSP Defind by: B.S.2779:1956 Tolerance class: BSW-Medium class A, BSP-Medium class

(mm)

Insert size		Pitch		Designation	PC9570T	Le	Tooth	Tool holder
d	L	(tpi)	Ex	ternal+Internal	FC95701	Li	100111	1001 Holder
		28	TMEI	10-28W		9.07	10	
		26		10-26W		8.79	9	
6.0 10.4	10.4	24		10-24W		9.53	9	TMSR - 10
		20		10-20W		8.89	7	
		19		10-19W		9.36	7	
		28	TM2EI	11-28W		9.98	11	
		26		11-26W		9.77	10	
		24		11-24W		9.53	9	T.40D 44
6.35	11	20	1	11-20W		10.16	8	TMSR - 11
		19		11-19W		9.36	7	
		14		11-14W		9.07	9 9 7 7 7 11 10 9 8 7 5 15 14 11 11 10 9 8 7 6 20 17 16 15 13 12 10 9 16 14 11 11 10 10 8 7 6 5 15 8 6	
		26	TM2EI	16-26W		14.65	15	
		24	1	16-24W		14.82		
		20		16-20W		13.97	11	1
		19		16-19W		14.71	9.07 10 8.79 9 9.53 9 8.89 7 9.36 7 9.98 11 9.77 10 9.53 9 10.16 8 9.36 7 9.07 5 14.65 15 14.82 14 13.97 11 14.71 11 14.11 10 14.29 9 14.51 8 14.82 7 13.85 6 21.17 20 21.59 17 21.39 16 21.17 15 20.64 13 21.77 12 21.17 10 20.78 9 25.4 16 25.4 14 23.28 11 23.09 10 25.40 10 22.58 8 22.23 7 21.77 6 21.17 5 34.64 15 33.87 8 30.48 6	1
9.525	16	18	1	16-18W				TMSR - 16
		16		16-16W		14.29	9	
		14		16-14W		14.51	8	
		12		16-12W		14.82	7	
		11		16-11W	•	13.85	7 6 20	
		24	TM2EI	22-24W		21.17	20	
		20		22-20W		21.59	17	
		19		22-19W		21.39	16	
		18		22-18W		21.17	15	
9.525B	22	16		22-16W		20.64	7 11 10 9 8 7 5 15 14 11 11 10 9 8 7 6 20 17 16 15 13 12 10 9 16 14 11 10 10 8 7 6 5 15	TMSR - 22
		14		22-14W		21.77		
		12		22-12W		21.17	10	
		11	1	22-11W			10 9 9 7 7 11 10 9 8 7 5 15 14 11 11 10 9 8 7 6 20 17 16 15 13 12 10 9 16 14 11 10 9 8 7 6 20 17 18 19 10 10 10 10 10 10 10 10 10 10	1
		16	TM2EI	27-16W				
		14		27-14W				
		12		27-12W		23.28	11	1
		11	1	27-11W		23.09	10	1
15.875	27	10		27-10W		25.40	10	TMSR - 27
		9		27-9W			8	1
		8		27-8W			7	1
		7	1	27-7W			6	1
		6		27-6W				
		11	TM2EI	38-11W				
		6	1 -	38-6W				1
19.05B	38.5	5		38-5W				TMSR - 38
		4.5		38-4.5W				
		-		38-15W				


Applicable holders D49


All inserts except TMI10 code have 2 cutting edges

: Stock item

### **NPT**







Defined by: USAS B2.1:1968 Tolerance class: Standard NPT

(mm)


Insert	Insert size		Designation		PC9570T	La	Tooth	Tool holder		
d	L	(tpi)	External+Internal		PC95/01	L <sub>1</sub>	100111	RH	LH	
		18	TM2E	16-18NPT *		14.11	10			
9.525 16	16	14	TM2EI	16-14NPT		14.51	8	TMSRT - 16	TMSLT - 16	
		11.5		16-11.5NPT		13.25	6			
9.525B	22	14	TM2EI	22-14NPT		21.77	12	TMSRT - 22	TMSLT - 22	
15.875	27	11.5	TM2EI	27-11.5NPT	•	24.30	11	TMSR - 27	TMSL - 27	
15.675	21	8		27-8NPT	•	22.23	7	TIVION - 27	TIVISL - 27	
10.0FP	20 E	11.5	TM2EI	38-11.5NPT		35.34	16	TMSR - 38	TMSL - 38	
19.05B	38.5	8		38-8NPT		31.75	10	1 IVION - 38	1 IVIOL - 38	


Applicable holders D49

• : Stock item

### **NPTF**







Defined by: ANSI 1.20.3-1976 Tolerance class: Standard NPTF

(mm)


Insert	Insert size		Designation		PC9570T	L <sub>1</sub>	Tooth	Tool holder		
d	L	(tpi)	External+Internal		PC95/01	Li	100111	RH	LH	
9.525	16	14	TM2EI	16-14NPTF	•	14.51	8	TMODT 16	TMSLT - 16	
9.525	10	11.5		16-11.5NPTF		13.25	6	TMSRT - 16	TWOLT - 10	
9.525B	00	14	TM2EI	22-14NPTF		21.77	12	TMSRT - 22	TMSLT - 22	
9.5256	22	11.5		22-11.5NPTF		19.88	9	1 IVION 1 - 22		
15.875	27	11.5	TM2EI	27-11.5NPTF		24.30	11	TMSR - 27	TMSL - 27	
13.073	21	8		27-8NPTF		22.23	7	TIVISH - 27		
19.05B	20 E	11.5	TM2EI	38-11.5NPTF		35.34	16	TMSR - 38	TMSL - 38	
19.05B	38.5	38.5		38-8NPTF		31.75	10	1 NOH - 38		


Applicable holders D49

•: Stock item

### **BSPT**







Defined by: B.S 21:1985 Tolerance class: Standard BSPT

(mm)

Insert size		Pitch	Designation		PC9570T L <sub>1</sub>	Tooth	Tool holder		
d	L	(tpi)	External+Internal		PC95/UI	L1 To	Tooth	RH	LH
6.35	11	19	TM2EI	11-19BSPT		9.36	7	TMSR - 10	TMSL - 10
9.525	16	14	TM2EI	16-14BSPT		14.51	8	TMSRT - 16	TMSLT - 16
	16	11		16-11BSPT		13.85	6	IIVIONI - IO	TIVISLI - 10
15.875	27	11	TM2EI	27-11BSPT		23.09	10	TMSR - 27	TMSL - 27


Applicable holders D49


• : Stock item

<sup>\*</sup> TM2E16-18NPT is for external threading

(mm)

#### **Standard Type**







Insert size			CD.	<b>~</b> .1	~ I.	0		Screw	Wrench
d		esignation	ØD	Ød	Ød1	Q	L		S
0.0	TMSR	12-10	9.0	12	6.8	12.0	69.0	STM10	TM07D
6.0	-	20-10	9.0	20	6.8	17.0	84.0	STIVITO	TW07P
6.35	TMSR	12-11	11.5	12	8.9	12.0	70.0	STM11	TW08P
0.33	TMSR TMSR TMSR TMSR TMSRW TMSRW	20-11	11.5	20	8.9	20.0	85.0	STIVITI	TVVOP
9.525	TMSR	16-16	17.0	16	13.6	22.0	90.0	STM1622	TW10P
9.525	20-16		20.0	20	16.6	43.0	95.0	31W1022	
	9.525B	16-22	17.0	16	13.5	29.0	79.5		
0.5050		20-22	19.0	20	15.5	29.0	81.5	STM1622	TW10P
9.3230		25-22	19.0	25	15.5	30.0	92.3	311/11022	TVVTOP
	TMSRW	25-22	22.0	25	18.5	30.0	90.8		
	TMSR	25-27	30.0	25	24.0	52.0	110.0		
15.875	TMSRW TMSR TMSL	25-27	30.0	25	24.0	52.0	110.0	STM27	TW25L
	TMSR	32-27	37.0	32	31.0	58.0	120.0		
10.05	TMSR	32-38	35.0	32	27.0	53.0	115.0	STM38	TM201
19.05		40-38	46.0	40	38.0	63.0	135.0	311/138	TW30L

<sup>●</sup> Applicable inserts D44~48

#### **Long Type**







			1						(11111)
Insert size		) a ciamatian	ØD	Ød	Ød1	0		Screw	Wrench
d		Designation	00	Øα	Юui	Ų	L		S
6.35	TMSRL	25-11	11.5	25	8.9	17.0	125.0	STM11	TW08P
9.525B	TMSRL	25-16	22.0	25	18.6	25.0	125.0	STM1622	TW10P
9.525B	TMSRL	20-22	19.0	20	15.5	44.0	96.5	CTM1000	TW10P
9.525B		25-22	22.0	25	18.6	63.5	125.0	STM1622	10010P
15.075	TMSRL	25-27	30.0	25	24.0	92.0	150.0	CTM07	TMOCI
15.875		32-27	37.0	32	31.0	98.0	160.0	STM27	TW25L
19.05B	TMSRL	40-38	46.0	40	38.0	93.0	168.0	STM38	TW30L

<sup>◆</sup> Applicable inserts D44~48

#### **Tapered Type**






								<u>'</u>	(mm)
Insert size		Designation	ØD	Ød	Ød1	0		Screw	Wrench
d		ocoignation		- Du	Sui	*	_		S
9.525	TMSRT	16-16	15.5	16	12.5	22.0	90.0	STM1622	TW10P
9.525		20-16	19.0	20	15.0	23.0	85.0	STMT16	1 44 10 P
9.525B	TMSRT	16-22	17.0	16	13.5	29.0	79.5	STM1622	TW10P
9.5256		20-22	19.0	20	15.5	29.0	81.5	311/11022	1 10 10 P
15.875	TMSRT	32-27	37.0	32	31.0	58.0	120.0	STM27	TW25L

#### **MILLING**

Milling tools that provide the best quality and improve productivity for every customer needs.



**Side Milling Cutters** 


E02 E04	Milling Insert Code System (ISO)	E262 E267	Technical Information for HFMD HFMD	E405	Technical Information for Side Milling Cutters
E34	Milling Inserts KORLOY Cutters	E277	Technical Information for HFM	E407	-
E42	KORLOY Shanks	E277	HFM	E411	Side Milling Cutters Side Cutter
E45	KORLOY Modular Adaptors	E284	Technical Information for	E414	Wind Mill
E40	NONLOT IVIOUUIAI AUAPIOIS	E204	HRMDouble	E414	Willia Willi
		E289	HRMDouble		
Г	Million Cuttons	E300	HRM	B.//:11:	an Coultan for Cook inch of
Face	Milling Cutters	E307	Tank Mill		ig Cutter for Cast iron at
E47	Mill-max/Mill-max Plus (E48, E54)	E308	Technical Information for TP2P	high	ieed
E57	Technical Information for	E311	TP2P	E418	Technical information for
	Mill-max Heavy	E317	Technical Information for	= 400	High feed Cutter
E58	Mill-max Heavy		Laser Mill/GBE/BRE	E420	Technical information for Cube Mill
E59	Turbo Mill	E326	Laser Mill	E421	Technical information for Couple Mill
E62	Double Mill	E331	BFE	E423	Technical information for Shave Mill
E64	Technical Information for	E332	GBE	E425	Technical information for Shave Mill Ultra
F00	Power Buster	E335	BRE		Onave Will Olda
E68	Power Buster	E337	Technical Information for HAVE		
E71	Technical Information for Rich Mill	E339	HAVE (Multi-edge, Single-edge)	Date	I before all as of BASIS as
E99	Rich Mill	E341	Technical Information for BT/HSK Tooling System		I Information of Milling
E147	Technical Information for Aero Mill/ Aero Mill-Plus/Aero Mill-Mini	E342	BT Tooling System (Alpha Mill)	Culle	er and Arbor
E151	Aero Mill	E347	BT Tooling System (Mono-Tool)	E426	Actual Designation of
E152	Aero Mill-Plus	E353	HSK Tooling System (Alpha Mill)		Milling Cutter and Arbor
E154	Aero Mill-Mini	E358	HSK Tooling System (Mono-Tool)		
E156	PCD face cutter	E363	HSK Tooling System (Pro-V Mill)		
		E364	O-ring Cutter	Gear	Tools
		E366	Chamfer Tool (Multi-functional, Solid)	E429	Technical information for
Cutte	rs for Molds	E374	T-Cutter (TFE)		Gear Cutter Tools
			,	E430	Gear Cutter Table
E157	Technical Information for Alpha Mill			E431	Gear Cutter
E158	Technical Information for Alpha Mill Nick	Millin	g Cutter for Aluminum	E439	Gear Cutter Order Form
E164	Alpha Mill			E440	Indexable HOB
	Technical Information for Alpha Mill-X	E375	Technical Information for Pro-A Mill/Pro-X Mill/Pro-L Mill/	E441	Indexable HOB Cutter Order Form
E197	Alpha Mill-X		Pro-XL Mill/Pro-V Mill		
E201	Technical Information for Future Mill	E385	Pro-A Mill		
E211	Technical Information for	E388	Pro-X Mill		
	Future Mill P-Positive	E394	Pro-L Mill		
E216	Future Mill	E398	Pro-XL Mill		
E242	Future Mill P-Positive	E399	Pro-V Mill		
E254	Technical Information for Triple Mill	E401	Modular Adaptor (MAT/BT/HSK)		
ESEO	Triple Mill				


**Cutters for Molds** 


E258 Triple Mill


Insert











■ Tolerance on C,E,H,M,O,P,R,S,T,W Insert Shape (exceptional case)

Class	d	m	t	d	J,
Α	±0.025	±0.005	±0.025	6.35	
С	±0.025	±0.013	±0.025	9.525	
-	-0.040			12.7	
Н	±0.013	±0.013	±0.025	15.875	
Е	±0.025	±0.025	±0.025	19.05	
G	±0.025	±0.025	±0.13	25.4	
J	±0.05~±0.15	±0.005	±0.025	Toleran	ce
ĸ	±0.05~±0.15	±0.013	±0.025	d	
				6.35	
L	±0.05~±0.15	±0.025	±0.025	9.528	5
М	±0.05~±0.15	±0.08~±0.20	±0.13	12.7	
	.0.00 .0.05	0.40 0.00	0.40	15.87	5
U	±0.08~±0.25	±0.13~±0.38	±0.13	19.0	5

d	Tolerand	e on d	Toleran	ce on m
u	J,K,L,M,N	U	M,N	U
6.35	±0.05	±0.08	±0.08	±0.13
9.525	±0.05	±0.08	±0.08	±0.13
12.7	±0.08	±0.13	±0.13	±0.20
15.875	±0.10	±0.18	±0.15	±0.27
19.05	±0.10	±0.18	±0.15	±0.27
25.4	±0.13	±0.25	±0.18	±0.38
Toleran	ce on D Ins	ert Shap	e (excepti	onal case

Tolerance	on D Insert Shape	(exceptional case)
d	Tolerance on d	Tolerance on m
6.35	±0.05	±0.11
9.525	±0.05	±0.11
12.7	±0.08	±0.15
15.875	±0.10	±0.18
19.05	±0.10	±0.18

Inscribed circle

Inch system

5/32" 7/32"


5

1/4" 3/8" 1/2" 5/8"

2 (8)

4

3/4" 1″



Height of cuttingedge

Nose radius (Nose R)


**Edge preparation** 

Hand


**Edge preparation** 


Chip breaker for milling





Sym	bol	Height of cu	utting-edge (t)
Metric	Inch	Metric	Inch
01	1 (2)	1.59	1/16
T0	1.125	1.79	9/128
T1	1.2	1.98	5/64
02	1.5 (3)	2.38	3/32
T2	1.75	2.78	7/64
03	2	3.18	1/8
T3	2.5	3.97	5/32
04	3	4.76	3/16
05	3.5	5.56	7/32
06	4	6.35	1/4
07	5	7.94	5/16
09	6	9.52	3/8
11	7	11.11	7/16
12	8 (16)	12.70	1/2
		( ) 5	Symbol for small size insert






### Nose radius (Nose R)






Sym	bol	r		Sym	bol	r		
Metric	Inch	Metric Inch I		Metric	Inch	Metric	Inch	
00	0	0.0		12	3	1.2	3/64	
02		0.2		15		1.5		
04	1	0.4	1/64	16	4	1.6	4/64	
05		0.5		24	6	2.4	6/64	
08	2	0.8	2/64	32	8	3.2	8/64	
10		1.0		40		4.0		



Parallel Land	Relief	Relief Angle					
kr	α°						
A - 45°	A - 3°	F - 25°					
D - 60°	B - 5°	G - 30°					
E - 75°	C - 7°	N - 0°					
F - 85°	D - 15°	P - 11°					
P - 90°	E - 20°						
Z - Special							



	Steel	1	Р	3		3	#	• (	9 1	1	t			3	#		Machining types
8	Stainless steel	<	M			3	#					3	#	3	#		wacrining types
bje	Cast iron	4	K		3			• (	9 1	ţ.	•			3	#	lacksquare	■ Continuous cutting
ž	Non-ferrous metal	<b>I</b>	N													3	
≥	Heat resistant alloy, Titanium alloy	<b>-</b>	S											3	#		General cutting
	Hardened steel	4	Н						1	r e				3	#		# Interrupted cutting

Harder	ned steel				3				#						# Ir	nterrupted cutting	
		Cermet				ated				Uncoated	I	Dimer	sions	(mm	)		
Inserts	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545 PC2010	PC3700	PC9530	PC9540 PC5300	PC5400	H05	1	d	t	r	d <sub>1</sub>	Geometries	Availal tools
ADKA	150308R										11.7	6.424		0.4	2.8		
ADNA	150308SR										14.5	7.813	4.824	0.8	3.4		-
9	150308TR	•									19.665	10.843	6.529	0.8	4.5	d d d 15°	
ADKT-ML	10T304PEER-ML			•		• •	) (	• •	•		11.7	6.424	3.819	0.4	2.8		E197
new	120408PESR-ML			•		• •	) (	• •	•		14.5	7.813	4.824	0.8	3.4		E200
6	170608PESR-ML			•		• •	) (	•	•		19.665	10.843	6.529	0.8	4.5	d d t	
	10T304PESR-MM			•		• •	)	• •	•		11.7	6.424	3.819	0.4	2.8		E197
	10T308PESR-MM								•		11.7	6.424	3.819	8.0	2.8		E200
ADKT-MM	10T312PESR-MM								•		11.7	6.424		1.2	2.8		
new	120408PESR-MM			•		• •	)	• •	•		14.5	7.813		0.8	3.4		
A	120412PESR-MM					• •		•	•		14.5	7.813		1.2	3.4	d <b>1</b> d 1	
	120416PESR-MM					• •	2	•	•		14.5	7.813		1.6	3.4		
	170604PESR-MM							•				10.843		0.4	4.5		
	170608PESR-MM 170616PESR-MM			•		• •	'	•	•		19.665 19.665			1.6	4.5	_	
	170616PESR-MM								-			10.843		2.0	4.5	-	
	150308R										15.00	9.525	3.18	0.8	4.5		E307
ADLT	150308SR								_		15.0	9.525	3.18	0.8	4.5		Loo
	150308TR								$\dashv$		15.0	9.525	3.18	0.8	4.5	d Id	
	10000111															88° 15°	
APKT	1604PDSR		•			• •	)				16.4	9.525	4.76	0.8	4.4	r di	E168
	4004DDED 114												. ==			85°	
APKT-MA	1604PDFR-MA 160416FR-MA									• •	16.4 16.4	9.525 9.525	4.76 4.76	1.6	4.4	<u></u>	E168
6	100410FN-IVIA										10.4	9.020	4.70	1.0	4.4	d	, 100
																85°	
PKT-MA2	1604PDFR-MA2 160416FR-MA2								$\dashv$	•	16.5	9.56	5.67	0.8	4.5	<u></u>	E158
	160432FR-MA2								$\dashv$		16.5	9.56	5.55	1.6 3.2	4.5		- 170
0	100402111 MAZ										10.0	0.00	3.33	0.2	7.0	85° d d d111°	
DUT 1440	1604PDFR-MA3									• •	16.4	9.525	5.0	0.8	4.4	r	E158
APKT-MA3	160420FR-MA3										16.0	9.525	5.0	2.0	4.4	la la	E170
																850 110	
APKT-MF	1604PDSR-MF		•					•			16.4	9.525	5.0	8.0	4.4	.r	E158
SERTIFIE																85 d d t 11°	E1/(
APKT-MM	1604PDSR-MM		•	•		• •	•	•			16.4	9.525	5.2	0.8	4.4		E168
AL IV I - IVIIVI																d d	E180

	Steel		Р	1		•	•	•	<b>3</b> :	•			1	#			Machining types
9	Stainless steel	<	M								1	1	# 3	#	;		waciiiiiig types
pie	Cast iron	<b>-</b>	K		3		3	3	3		•		3	#	3	•	● Continuous cutting
ž	Non-ferrous metal	<b>-</b>	N													•	i i
ĕ∣	Heat resistant alloy, Titanium alloy	<b>-</b>	S										3	#	;		General cutting
	Hardened steel	◂	Н				•	3	3				3	#	;		# Interrupted cutting

	ened steel H	1		_	3 3			3 1	5						***		
		Cermet				ated			Und	oated	ı	Dimer	nsions	(mm	)		
Inserts	Designation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC2510	PC3700	PC9530	PC9540 PC5300	G10	H01	ı	d	t	r	<b>d</b> 1	Geometries	Available tools
APLT	070304R								Ť		7.5	6.35	3.18	0.4	2.8	<u></u>	E305
																88° d d d d d d d d d d d d d d d d d d	
	0602PDFR-MA									•	6	4.24	2.6	0.4	2.0		E164
	060208PDFR-MA										6	4.24	2.6	0.8	2.0	78° d d d d d 111°	E175 E185 E188 E190
	0903PDFR-MA									•	9.4	6.21	3.6	0.4	2.8		E165
	090308PDFR-MA										9.4	6.21	3.6	0.8	2.8	85 d d d <sub>1</sub> 15°	E176 E177 E185 E191
	11T3PDFR-MA									•	11.2	6.467	3.6	0.5	2.9	<u>r</u>	E166
APMT-MA	11T308PDFR-MA										11.2	6.467	3.6	0.8	2.9	88 <sup>5</sup> d d <sub>10°</sub>	E172 E178 E186 E189 E192
	160404PDFR-MA										16.4	9.41	5.76	0.4	4.5	r	E167
•	1604PDFR-MA									•	16.4	9.41	5.76	0.8	4.5	85 d d d1	E173 E179
	180604PDFR-MA									•	17.4	10.98	6.35	0.4	4.5		E169
	1806PDFR-MA									•	17.4	10.98	6.35	0.4	4.5	r	E174
	180612PDFR-MA									•	17.4	10.98	6.35	1.2	4.5		E181
	180616PDFR-MA									•	17.4	10.98	6.35	1.6	4.5	d High	E182
	180620PDFR-MA									•	17.4	10.98	6.35	2.0	4.5	15°	E187
	180624PDFR-MA									•	17.4	10.98	6.35	2.4	4.5	85%	
	180630R-MA									•	17.4	10.98	6.35	3.0	4.5		
	11T3PDSR-MF					• •		• (			11.2	6.467	3.6	0.5	2.9	88 <sup>5</sup> 10°	E166, 170 E172, 178 E183, 186 E189, 192
APMT-MF	1604PDSR-MF		•			•		•			16.4	9.41	5.76	0.8	4.5		E167
																85 d d d 11°	E171 E173 E179 E184 E189
	1806PDSR-MF		•					•			17.4	10.98	6.35	0.8	4.5	ŗ	E169
	180612PDSR-MF										17.4	10.98	6.35	1.2	4.5	85° d d d 15°	E174 E181 E182 E187
	0903PDER-ML							• (			9.4	6.21	3.6	0.4	2.8		E165
APMT-ML	090308PDER-ML							•			9.4	6.21	3.6	0.8	2.8	85 dd 115°	E176 E177 E185 E191
	11T3PDER-ML							• (			11.2	6.467	3.6	0.5	2.9		E166
	11T308PDER-ML										11.2	6.467	3.6	0.8	2.9	88 <sup>5</sup> 10°	E172 E178 E186 E189 E192

ĺ	Steel	<b>—</b>	Р	3		3 (		<b>D</b> 1	<b>3</b>	3			1	#		Machining types
9	Stainless steel	<b>-</b>	M			3			•			3	# 3	#		waciiiiiig types
pie [	Cast iron	4	K		3		9 1	B 1	3		•		1	#		● Continuous cutting
ž	Non-ferrous metal	<b>-</b>	N												•	
8	Heat resistant alloy, Titanium alloy	<b>-</b>	S										1	#		General cutting
	Hardened steel	<b>=</b>	Н					<b>D</b> 1	: 3				1	#		★ Interrupted cutting

	ned steel H				• 1	•				<b>3</b> \$							
		Cermet					ate				PCD		Dime	nsion	s (mn	1)	
Inserts	Designation	CN2500 CN30	NC5330 NCM325	NCM535	PC2505	PC2010	PC3700	PC6510	PC9530 PC9540	PC5300	DP150 DP200	ı	d	t	r	d <sub>1</sub>	Geometries
	160404PDER-ML									•	)	16.4	9.41	5.76	0.4	4.5	, E
	1604PDER-ML									•	)	16.4	9.41	5.76	8.0	4.5	E
DRAT BAL																	
PMT-ML																	11°
new																	85°7
9	180604PDER-ML									• •		17.4	10.98	6.35	0.4	4.5	E
	1806PDER-ML									•		17.4	10.98		0.8	4.5	- E
	180612PDER-ML									• •		17.4	10.98	6.35	1.2	4.5	DOM PL
	180616PDER-ML									•		17.4	10.98	6.35	1.6	4.5	d did a
	180620PDER-ML									•		17.4	10.98	6.35	2.0	4.5	950 H
	180624PDER-ML									•	)	17.4	10.98	6.35	2.4	4.5	05 1
	180630R-ML									•		17.4	10.98	6.35	3.0	4.5	
	060202PDSR-MM		•				•	Ш		•		6	4.24	2.6	0.2	2.0	E
	0602PDSR-MM		•		•		•	•	•	• •		6	4.24		0.4	2.0	
	060208PDSR-MM		•				•					6	4.24		0.8	2.0	d di E
	060212R-MM							Н				6	4.24		1.2	2.0	78° 111° E
	060216R-MM * 0903PDSR-MM		•		• •			•				9.4	4.24 6.21	2.6	1.6 0.4	2.0	10 /  <del> - 1  </del>
	0903PDSR-MM		•		_		•	•				9.4	6.21	3.6	0.4	2.8	
	090308PD3R-IVIIVI						•					9.4	6.21	3.6	1.2	2.8	
	090316R-MM		•				•	_				9.4	6.21	3.6	1.6	2.8	d
	090320R-MM						•	_	_	•		9.2	6.21	3.6	2.0	2.8	85° t E
	090332R-MM *									• •		9.2	6.21	3.6	3.2	2.8	"
	11T3PDSR-MM		• •	•	• (		•	•	•	•	)	11.2	6.467		0.5	2.85	, E
	11T308PDSR-MM		•				•		• •	•	)	11.2	6.467	3.6	0.8	2.85	E
	11T312PDSR-MM		•				•		•	• •		11.2	6.467	3.6	1.2	2.85	d Allida E
МТ-ММ	11T316R-MM						•			•		11.0	6.467	3.6	1.6	2.85	10° E
	11T318R-MM											11.0	6.467	3.6	1.8	2.85	888 t t
	11T324R-MM		•				•	ш		•		11.0	6.467		2.4	2.85	
	160404PDSR-MM									•		16.4	9.41	5.76	0.4	4.5	  -
-	1604PDSR-MM		• •	•	•		•	•	• •			16.4	9.41	5.76	0.8	4.5	E
	160410PDSR-MM						•					16.4	9.41	5.76	1.0	4.5	
	160416PDSR-MM 160420R-MM		•				•	Н		•	<u>'</u>	16.4	9.41	5.76	1.6	4.5	
	160424R-MM		•		-		•					16.4	9.41	5.76 5.76	2.0	4.5 4.5	0
	160430R-MM						•					16	9.41	5.76	3.0	4.5	85° E
	160432R-MM		•				•					16	9.41	5.76	3.2	4.5	-
	160450R-MM *						•			•		16	9.41	5.76	5.0	4.5	-
	160464R-MM *									•		16	9.41	5.76	6.4	4.5	
	1806PDSR-MM		•		• •		•	•	• •	•		17.4	10.98		0.8	4.5	E
	180612PDSR-MM		•				•			• (		17.4	10.98	6.35	1.2	4.5	E
	180616PDSR-MM		•							•		17.4	10.98	6.35	1.6	4.5	E
	180620PDSR-MM											17.4	10.98		2.0	4.5	
	180624PDSR-MM		•							•		17.4	10.98		2.4	4.5	
	180630R-MM							Ш				16.7	10.98		3.0	4.5	
	180632R-MM		•								_	16.7	10.98		3.2	4.5	85° t
	180640R-MM *									0 0		16.7	10.98		4.0	4.5	
	180648R-MM * 180650R-MM *									• •		16.7	10.98		4.8	4.5	-
	180650R-MM *									-	7	16.7	10.98		5.0 6.0	4.5 4.5	-
	180664R-MM *							Н		•		16.7	10.98		6.4	4.5	-
	11T3PDSR-MN2							Н		•		11.2			0.4	2.85	E
	11T3PDSR-MN3							Н		•		11.2	6.467		0.5	2.85	
MT-MN	1604PDSR-MN3									•		16.4	9.41	5.76	0.8	4.5	E
new	1604PDSR-MN4									•		16.4	9.41	5.76	0.8	4.5	E E
	1806PDSR-MN3							П		•		17.4	10.98		0.8	4.5	111° E
500	1806PDSR-MN4							П		•		17.4	10.98		0.8	4.5	85° t E
												1					a · · · ·  =

Milling

<sup>\*</sup> Inserts marked with an asterisk (\*) require a custom-made order for special holders.

	Steel		Р	3		•	•	•	3					3	#			Τ	Machining types
9	Stainless steel	_	M									3	#	•	#				waciiiiiig types
bie	Cast iron	<b>-</b>	K		3	•	•	3	3	-	•			3	#		П	Т	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	<b>-</b>	N														•	•	· · · · · · · · · · · · · · · · · · ·
š	Heat resistant alloy, Titanium alloy	◂	S											3	#				<b>♣</b> General cutting
	Hardened steel		Н						3					3	#				* Interrupted cutting

		Cermet			Coa	ated			befores	P	CD	[	Dimer	nsions	(mm	1)		
Inserts	Designation	CN2500 CN30	3330 4535	M545	010	510	530	PC9540 PC5300		_		_	d	t	r	d <sub>1</sub>	Geometries	Available tools
		CNS	N C	NC CO	PC2	2 8	PCS	PCS PCS	P 5	DP150	DP2		<u> </u>		•	u i		
BAMPR- XAF	BAMPR-XAF											25.5	10.5	7	-	-	[5.5]	E152 E153
BAMPR-	BAMPR-XAW									•		25.5	10	7	-	-		E152
XAW																	[5.5]	E153
BAMPR- XAWR	BAMPR-XAWR											25.5	10	7	-	-		E152 E153
3																	[5.5]	
CDEW-NAF	1204R-NAF											12.7	9.525	4.76	-	4.4		E151
strengthened Edge	1204L-NAF											12.7	9.525	4.76	-	4.4	d d 15°	
CDEW-NAW	1204R-NAW											12.7	9.525	4.76	-	4.4		E151
Strengthened Edge Wiper Insert	1204L-NAW											12.7	9.525	4.76	-	4.4	d d 15°	
CDEW-XAW	1204R-XAW										•	12.7	9.525	4.76	-	4.4		E151
Sharp Edge Wiper Insert	1204L-XAW											12.7	9.525	4.76	-	4.4	d d 15°	
CDEW-XAF	1204R-XAF 1204L-XAF						Ш				•	12.7 12.7	9.525 9.525	4.76 4.76	-	4.4		E151
Sharp Edge	12U4L-XAP											12.7	9.020	4.70		4.4	d d 15°	
CDEW-XCF	1204R-XCF						П					12.7	9.525	4.76	-	4.4		E136
Sharp Edge	1204L-XCF											12.7	9.525	4.76	•	4.4	d d1	
CNHQ	1005-C0.5											10	10	5.4	-	4.7		E305
CHILD	1305-C0.5 1606-C0.5											12.7	10	5.4 6.4	-	5.9	d d t c	E306
	120408-MM										$\Box$	12.9	12.7	4.76	0.8	5.5	<u>1</u>	E372
СРМН																	d d d 111°	

g Stai	Steel P	0 3				3 1	* *	3	<b>3</b> 1		3					Ма	chining types	
	Cast iron K		•	9 1		3 1	+ +	•	- 1	*	_					• 0	continuous cutting	
Non-f	errous metal N			_		_			_	44	•						eneral cutting	
	t alloy, Titanium alloy  dened steel  H			•	•		• <b>*</b>			*							nterrupted cutting	
		Cermet				Co	oated	i			Uncoated		Dimer	nsions	(mn	1)		
Inserts	Designation			중 년	20				200	2 8					(		Geometries	Availal
		CN2500 CN30	NCM535	NCMS	PC2005	PC20	PC210F	PC37/	PC95	PC54	ST30A H01	I	d	t	r	d <sub>1</sub>	4.00.1104.100	tools
	060204-MM							•				6.4	6.35	2.38	0.4	2.75		E372
<b>CPMT</b>	080308-MM							•				8.1	7.938	3.18	0.8	3.40		
1	09T308-MM							•				9.7	9.525	3.97	0.8	4.4		
																	110	
																	/	
	090408FN								Ш			9.0	15.875	4.76	0.8	-	<u></u>	E417
HECN	090408SN											9.0	15.875	4.76	0.8	-		
	090408TN											9.0	15.875	4.76	0.8	-	<del>     </del>	
	110412FN								Н			11.0	19.05	4.76	1.2	-	20°	
1	110412TN											11.0	19.05	4.76	1.2	-	- t	
	090408FN											9.0	15.875	4.76	0.8	-	r	E417
HPEN	090408SN											9.0	15.875	4.76	0.8	-		
	090408EN											9.0	15.875	4.76	0.8	-		
	110412FN											11.0	19.05	4.76	1.2	-	110	
	090408-WC											9.0	15.875	4.76	0.8		r	E417
HPEN-WC	110412-WC											11.0	19.05	4.76	1.2	-		
																	d d 111°	
																	-t  /	
KEL-MF	150608-MF											15.88		6.35	8.0	-	-	E429
3/	150608-ML											15.88	15.23	6.35	0.8	-		
	45000000																<u>r(C)</u>	
<b>KEL-QNN</b>	1506QNN-MF											15.88		6.35	0.8	-		-
9	1506QNN-ML											15.88	15.23	6.35	0.8	-	- dı	
	4506 A N N P P											45.00	45.00	0.07	0.0		d t	
KEL-ANN	1506ANN-MF								Н				15.23		0.8	-		-
3	1506ANN-ML											15.88	15.23	6.35	0.8	-	-	
	080						•					7.0	8	2.4	4.0			E325
	100						•		П			8.5	10	2.6	5.0	-	1	E328
LBH	120						•					10.0	12	3.0	6.0	-		
= 1.	160						•					12.0	16	4.0	8.0	-		
	200						•		П			15.0	20	5.0	10.0	-		
	250						•					18.5	25	6.0	12.5	-		
	300						•					22.5	30	7.0	15.0	-		
	320						•					23.5	32	7.0	16.0	-	1 1	
	330											24.0	33	7.0	16.5	-	1	
	080-KF											7.0	8	2.4	4.0	-		E324
	100-KF					•						8.5	10	2.6	5.0	-		E325
	120-KE					4						10.0	10	3.0	60		1	

1		
		2
60	4	9
-	-	

LBH-KF

	100-KF		•		8.5	10	2.6	5.0	-
	120-KF		•		10.0	12	3.0	6.0	-
	130-KF		•		20.5	13	3.0	6.5	-
	160-KF		•		12.0	16	4.0	8.0	-
	170-KF		•		12.5	17	4.0	8.5	-
	200-KF		•		15.0	20	5.0	10.0	-
1	210-KF		•		15.5	21	5.0	10.5	-
	250-KF		•		18.5	25	6.0	12.5	-
	300-KF		•		22.5	30	7.0	15.0	-
	320-KF				23.5	32	7.0	16.0	-
	330-KF				24.0	33	7.0	16.5	-





• : Stock item

	Steel		Р	3		•	•	•	•	# :	3			1	<b>1</b>	3	;	Machining types
ဗ	Stainless steel	<	M							3		1	<b>B</b> 4	# 1	#	•		machining types
bje	Cast iron	<b>-</b>	K		3	•				#	(	•		1	#	:	•	<ul><li>Continuous cutting</li></ul>
ž	Non-ferrous metal	<b>-</b>	N							•							•	S S S S S S S S S S S S S S S S S S S
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S							•				1	#	:		General cutting
	Hardened steel	◂	Н							#				1	#	•		<b>★</b> Interrupted cutting

110.00	ened steel				<b>5</b> 4			<b>T</b>								
		Cermet			Co	ated			Uncoated	[	Dimen	sions	(mm	)		
Inserts	Designation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC2010	PC3700	PC9530	PC9540 PC5300	ST30A H01	1	d	t	r	d <sub>1</sub>	Geometries	Available tools
	080-KH				•					7.0	8	2.4	4.0	-		E324
	100-KH			•	•					8.5	10	2.6	5.0	-		E325
	120-KH			•	•					10.0	12	3.0	6.0	-		
	130-KH			•	•					20.5	13	3.0	6.5	-	r	
LBH-KH	160-KH			•	•					12.0	16	4.0	8.0	-		
	170-KH			•	•					12.5	17	4.0	8.5	-		
1000	200-KH			•	•					15.0	20	5.0	10.0	-		
3	210-KH			•	•					15.5	21	5.0	10.5	-		
	250-KH			•	•					18.5	25	6.0	12.5	-		
	260-KH			•						19.0	26	6.0	13.0	-		
	300-KH			•	_			_		22.5	30	7.0	15.0	-		
	320-KH 330-KH				•					23.5	32	7.0	16.0	-		
	080									7.0	33 8	7.0	16.5 4.0	-		E325~
	090				_			_		7.5	9	2.4	4.0	-		E328
	100				_			_		8.5	10	2.6	5.0	-		L020
	110									9.0	11	2.6	5.5	-		
	120									10.0	12	3.0	6.0	-		
	130									10.5	13	3.0	6.5	-		
LBS	160									12.0	16	4.0	8.0	-		
Ton	170									12.5	17	4.0	8.5	-		
	200									15.0	20	5.0	10.0	-		
	210									15.5	21	5.0	10.5	-	t	
	250									18.5	25	6.0	12.5	-		
	260									19.0	26	6.0	13.0	-		
	300									22.5	30	7.0	15.0	-		
	310									23.0	31	7.0	15.5	-		
	320									23.5	32	7.0	16.0	-		
LCF	160-D90				•	)				13.7	16	4.0	-	-		E325~
-	200-D90				•	)				17.0	20	5.0	-	-		E328
	250-D90									21.5	25	6.0	-	-	d (1)90°	
	100									8.5	10	2.6	1.0	-		E325~
LFH	120				•	)				10.0	12	3.0	1.0	-		E328
	160				•	)				12.0	16	4.0	1.5	-		
(D)	200									15.0	20	5.0	1.5	-		
	250				_					18.5	25	6.0	2.0	-		
•	300									22.5	30	7.0	2.0	-	t t	
	320									23.5	32	7.0	2.0	-		E325~
	100-R05 100-R10				•					8.5	10	2.6	1.0	-		E325~
LRH	100-R10 100-R20					_				8.5 8.5	10	2.6	2.0	-	ŗ	E326
	110-R05							_		9.0	11	2.6	0.5	÷		
(B)	120-R05				•	,				10.0	12	3.0	0.5			
	120-R10				•					10.0	12	3.0	1.0	-		
	120-R20				Ť					10.0	12	3.0	2.0	-		
	130-R05				•					10.5	13	3.0	0.5	-	- '   '	
	130-R10				•					10.5	13	3.0	1.0	-	LRH type	
	160-R05				•	)				12.0	16	4.0	0.5	-		
	160-R10				•					12.0	16	4.0	1.0	-		
	160-R20									12.0	16	4.0	2.0	-		
LR	160-R30				•					12.0	16	4.0	3.0	-		
	170-R05				•					12.5	17	4.0	0.5	-		
(0)	170-R10				•					12.5	17	4.0	1.0	-		
	200-R05				•					15.0	20	5.0	0.5	-		
(Special type)	200-R10				•					15.0	20	5.0	1.0	-		
(οροσίαι τγρο)	200-R20				•					15.0	20	5.0	2.0	-	I D hune	
	200-R30				•	)				15.0	20	5.0	3.0	-	LR type	
	210-R05									15.5	21	5.0	0.5	-		

	Steel P less steel M	- 3			• \$	3		<b>3</b> ‡	¢					Ма	chining types	
Non-fe Heat resistant	ast iron K rrous metal N alloy, Titanium alloy S ened steel H		3 0	• •	* * * • • • • • • • • • • • • • • • • •			<b>3</b> 1	t	-				<b>3</b> G	Continuous cutting General cutting Interrupted cutting	
		Cermet			Coa	ted			Uncoated	[	Dimer	nsions	s (mn	1)		
Inserts	Designation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC2010 PC210F	PC3700	PC9530	PC5300	ST30A H01	ı	d	t	r	d <sub>1</sub>	Geometries	Availab tools
	210-R10				•				- 0, <u>-</u>	15.5	21	5.0	1.0	-		E325~
	250-R05 250-R10									18.5 18.5	25 25	6.0	1.0	-		E328
	250-R10 250-R20				_					18.5	25	6.0	2.0			
LRH	250-R30									18.5	25	6.0	3.0	-		
	260-R05				•					19.0	26	6.0	0.5	-		
(0)	260-R10 300-R10				•					19.0	26 30	6.0 7.0	1.0	-		
6	300-R10									22.5	30	7.0	2.0	-	-   -   t  -	
LR	300-R30									22.5	30	7.0	3.0	-	LRH type	
	310-R05									23.0	31	7.0	0.5	-		
(0)	320-R10 320-R20				•					23.5	32 32	7.0	2.0	-		
	320-R30				•					23.5	32	7.0	3.0	-		
(Special type)	330-R05									24.0	33	7.0	0.5	-		
	330-R10 330-R20									24.0	33	7.0	1.0	-	LR type	
	330-R30									24.0	33	7.0	3.0		,po	
	CECE AODDED MA									0.5	45	F 00F	4.0	F F0		F000
DET-MA@	650540PPFR-MA 650550PPFR-MA									65 65	15 15	5.625 5.625	4.0 5.0	5.56 5.56	r	E396
JE I-IVIA															Ød Død Død	
3															t	
	1907-C1.5-WC									19.05	14.3	7	-	5.8	2-R124	E423
LNCS																
0															d <sub>1</sub> 1 30°	
															(1.5)	
															(13.7) d	
	1907-R3.0-WC									19.05	14.3	7	-	5.8	, 20	E423
LNCS															2-R124 4-R3 (1.3)	
															d <sub>1</sub>	
															(13.7) t	
	004 D0 0														d     ' ' '	
LNE	324-R0.8 324-C1.0									15.9 15.9	9.525 9.525		1.0	4.4	<u>r(C)</u>	E429/ E433
LIVE	02.10110															
															-   d1	
															d   t	
	080404PNR-MA									8.0	4.2	6.6	0.4	2.8		E309
	080408PNR-MA 080412PNR-MA									8.0	4.2	6.6	0.8 1.2	2.8		E314
	080412PNR-MA									8.0	4.2	6.6	1.2	2.8		
NKT-MA	140604PNR-MA									12.7	6.65	10.0	0.4	4.0		
new	140608PNR-MA									12.7	6.65	10.0	0.8	4.0		
	140612PNR-MA 140616PNR-MA									12.7 12.7	6.65	10.0	1.2	4.0		
	170704PNR-MA									16.5	7.0	11.0	0.4	4.0	d d	
	170708PNR-MA									16.5	7.0	11.0	0.8	4.5		
	170712PNR-MA									16.5	7.0	11.0	1.2	4.5		
	170716PNR-MA 170720PNR-MA									16.5 16.5	7.0	11.0	2.0	4.5 4.5		

170720PNR-MA



	Steel	Р	•	8 (			3	#	3			1	<b>B</b> 4	t 1	¢	Machining types
ဗ	Stainless steel	M						3			3	# 1	<b>B</b> 4	¢		wacming types
pie	Cast iron	K		1	6	3	3	#		•		1	<b>B</b> 4	¢	•	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N						•							•	•
×	Heat resistant alloy, Titanium alloy	S						•				1	<b>B</b> 1	¢		General cutting
	Hardened steel	H				•	3	#				1	<b>B</b> 1	¢		# Interrupted cutting

			Cermet				Co	atec	k			Uncoated		Dimer	nsions	(mm	)		
Inserts	De	signation	CN2500 CN30	NC5330	NCM535 NCM545	C2505	PC2010 PC210F	PC3700	PC6510	PC9540	PC5300 PC5400	ST30A H01	ı	d	t	r	<b>d</b> 1	Geometries	Available tools
	080404	PNR-ML										0,	8.0	4.2	6.6	0.4	2.8		E309~
		PNR-ML											8.0	4.2	6.6	8.0	2.8		E314
		PNR-ML				ш							8.0	4.2	6.6	1.2	2.8		
LNKT-ML		PNR-ML PNR-ML											8.0	4.2	6.6	1.6	2.8		
new		PNR-ML											12.7 12.7	6.65	10.0	0.4	4.0		
		PNR-ML							_				12.7	6.65	10.0	1.2	4.0		
0		PNR-ML											12.7	6.65	10.0	1.6	4.0		
		PNR-ML											16.5	7.0	11.0	0.4	4.5		
		PNR-ML							•		• •		16.5	7.0	11.0	0.8	4.5		
		PNR-ML											16.5	7.0	11.0	1.2	4.5		
		PNR-ML PNR-ML											16.5 16.5	7.0	11.0	2.0	4.5	│ ' <del> ♥ </del> {	
		PNR-MM											8.0	4.2	6.6	0.4	2.8		
		PNR-MM											8.0	4.2	6.6	0.8	2.8	d d	
	080412	PNR-MM											8.0	4.2	6.6	1.2	2.8		
		PNR-MM											8.0	4.2	6.6	1.6	2.8		
LNKT-MM		PNR-MM											12.7	6.65	10.0	0.8	4.0		
new		PNR-MM PNR-MM											12.7 12.7	6.65	10.0	1.2	4.0		
		PNR-MM				Н			-				12.7	6.65	10.0	1.6	4.0		
6		PNR-MM											16.5	7.0	11.0	0.4	4.5		
		PNR-MM									• •		16.5	7.0	11.0	0.8	4.5		
		PNR-MM											16.5	7.0	11.0	1.2	4.5		
		PNR-MM											16.5	7.0	11.0	1.6	4.5		
		PNR-MM				ш							16.5	7.0	11.0	2.0	4.5		E10E
LNEX-MA		PNR-MA										•	10.0 15.0	6.5	6.5	0.5	3.5 4.5	r	E105 E106
ENEX-WA		PNR-MA										•	15.0	10.0	10.0	0.8	4.5		E109
																		d d	E110 E113~ E117
	LNMX	100605PNR-MF							•		• •		10.0	6.5	6.5	0.5	3.5		E105
		100608PNR-MF							•		• •		10.0	6.5	6.5	8.0	3.5		E106
		151004PNR-MF						•	_		• •		15.0	10.0	10.0	0.4	4.5		E109
		151008PNR-MF 151016PNR-MF			•		_	•	•		• •		15.0 15.0	10.0	10.0	1.6	4.5		E110
LNM(E)X-MF		131010FNN-WIF											13.0	10.0	10.0	1.0	4.5		E113~ E117
	LNEX	100605PNR-MF							•		• •		10.0	6.5	6.5	0.5	3.5		L 117
		100608PNR-MF							•		• •		10.0	6.5	6.5	0.8	3.5		
		151004PNR-MF						_	•		• •		15.0	10.0	10.0	0.4	4.5	t	
		151008PNR-MF							•		• •		15.0	10.0	10.0	0.8	4.5		
		151016PNR-MF									• •		15.0	10.0	10.0	1.6	4.5		
	LNMX	100605PNR-MM						•	• (		• •		10.0	6.5	6.5	0.5	3.5		E105~
		100608PNR-MM				П		•			• •		10.0	6.5	6.5	0.8	3.5		E119
		100605PNL-MM						•			• •		10.0	6.5	6.5	0.5	3.5		
		151004PNR-MM	_						•		•		15.0	10.0	10.0	0.4	4.5		
		151008PNR-MM 151016PNR-MM			•	Н		•	_		• •		15.0 15.0	10.0	10.0	1.6	4.5 4.5		
LNM(E)X-MM		151008PNL-MM									• •		15.0	10.0	10.0	0.8	4.5	<u>, r</u>	
		. O TOOOT TIE WIN											10.0	10.0	10.0	0.0	1.0		
	LNEX	100605PNR-MM						•	•		• •		10.0	6.5	6.5	0.5	3.5		
		100608PNR-MM							•		• •		10.0	6.5	6.5	0.8	3.5		
		100605PNL-MM							•		• •		10.0	6.5	6.5	0.5	3.5		
		151004PNR-MM							•		• •		15.0	10.0	10.0	0.4	4.5		
		151008PNR-MM 151016PNR-MM	_			Н		•	•		• •		15.0 15.0	10.0	10.0	1.6	4.5 4.5		
	Ι							_	_									1	
		151008PNL-MM									• •		15.0	10.0	10.0	0.8	4.5		

	Steel		Р	3					3	# :	8			3	#	3		Machining types
ဗ	Stainless steel	<	M							3		1	#		#			macining types
bje	Cast iron	4	K		3	•	•	3	3	#	•			3	#			● Continuous cutting
ž	Non-ferrous metal	<b>I</b>	N							•							lacksquare	_
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S							•				3	#			General cutting
	Hardened steel	<b>-</b>	Н					•	3	#				3	#			# Interrupted cutting

									#							
	<b>.</b>	Cermet	o %	ਨ ਨ -		ated		0 0	Uncoated		Dimer	nsions	s (mm	)		Availab
Inserts	Designation	CN250 CN30	VC533	VCM54	0000	C2370	C923	2C954	PC5400 ST30A H01	I	d	t	r	d <sub>1</sub>	Geometries	tools
	060310R-MF				•	•		•	•	10.0	6.8	3.6	1.0	-		E269~
NIRAV RAE	100412R-MF							• •	•	12.2	10.0	4.2	1.2	-	, d , r , t	E273 E275
NMX-MF																E276
6																
	040205R-ML							•	_	6.2	4.2	2.35	0.5	-		E267~
	060310R-ML 100412R-ML							•	_	10.0	6.8	3.6 4.2	1.0	-	d r t	E276
NMX-ML	10041211-WL									12.2	10.0	7.2	1.2			7
6																
	040205R-MM				•	•		•		6.2	4.2	2.35	0.5	-		E267
184V 8484	060310R-MM 100412R-MM				•	•		•	-	10.0	6.8	3.6 4.2	1.0	-	d -  /  -t	E276
MM-XMV	100412H-WW									12.2	10.0	4.2	1.2			<del> </del>
	040210R			•	•			•		6.4	4.2	2.6	1.0	2.0		E281
LPEW															d t	d
	040220R			•	•			•		6.4	4.2	2.6	2.0	2.0		
																dı
	040210R-MF				•	•		•	•	6.4	4.2	2.6	2.0	2.0		E281
PMT-MF																E283
	040220R-MF				•	•		•	•	6.4	4.2	2.6	2.0	2.0		
																dı

	Steel		Р	3	•	•	•	•	3	<b>3</b> 1				•	#	3	Machining types
S	Stainless steel	_	M							•		3	#	•	#		waciiiiiig types
pie	Cast iron	<b>-</b>	K		3			3	3	\$	•	)	П	3	#		● Continuous cutting
ž	Non-ferrous metal	<b>-</b>	N														General cutting
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S											3	#		
	Hardened steel	<b>-</b>	Н					•	3	\$				3	#		# Interrupted cutting

		Cermet			Co	ated	d			Uncoa	ted	[	Dimen	sions	(mm	)		
Inserts	Designation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC2510	C3700	PC6510 PC9530	PC9540	PC5400	ST30A	5	ı	d	t	r	<b>d</b> 1	Geometries	Available tools
	040210R			•	_			•		Ο, .		6.4	4.2	2.6	1.0	2.0		E281~
LPMW																		E283
	040220R			•	•			•			#	6.4	4.2	2.6	2.0	2.0		
																	d t	
	250404PEFR-32-MA											25	10.775	4.76	0.4	4.5		E394~
	2504PEFR-32-MA									(		25	10.775	4.76	0.8	4.5		E397
	250412PEFR-32-MA 250416PEFR-32-MA							-	_		+	25 25	10.775	4.76 4.76	1.2	4.5		
	250404PEFR-40-MA											25	10.618	4.76	0.4	4.5		
	2504PEFR-40-MA										I	25	10.618	4.76	0.8	4.5		
	250412PEFR-40-MA										1	25	10.618		1.2	4.5		
LXET-MA	250416PEFR-40-MA										_	25	10.618	4.76	1.6	4.5		
new	340504PEFR-50-MA 3405PEFR-50-MA											34 34	13.765	5.56 5.56	0.4	5.56 5.56		
-	340512PEFR-50-MA									· '		34	13.765	5.56	1.2	5.56		
6	340516PEFR-50-MA								Т		$\dagger$	34	13.765	5.56	1.6	5.56	110	
4	340504PEFR-63-MA											34	13.803	5.56	0.4	5.56	t   '	
	3405PEFR-63-MA									(		34	13.803	5.56	0.8	5.56		
	340512PEFR-63-MA 340516PEFR-63-MA										+	34	13.803	5.56 5.56	1.2	5.56 5.56		
	250404PEER-32-ML											25	10.775		0.4	4.5		E394~
	250404FEER-32-ML										+	25	10.775		0.8	4.5	•	E397
	250412PEER-32-ML										1	25	10.775	4.76	1.2	4.5		
	250416PEER-32-ML										-	25	10.775		1.6	4.5		
	250404PEER-40-ML 2504PEER-40-ML										_	25 25	10.618		0.4	4.5 4.5		
	250412PEER-40-ML								-		-	25	10.618		1.2	4.5		
	250416PEER-40-ML										-	25	10.618		1.6	4.5		
LXET-ML	340504PEER-50-ML											34	13.765	5.56	0.4	5.56		
new	3405PEER-50-ML							•	)		1	34	13.765		8.0	5.56		
	340512PEER-50-ML										$\perp$	34	13.765		1.2	5.56	<b>1</b> d <sub>1</sub>	
6	340516PEER-50-ML 340504PEER-63-ML										+	34	13.765		0.4	5.56 5.56	1110	
4	3405PEER-63-ML										+	34	13.803		0.4	5.56		
	340512PEER-63-ML											34	13.803		1.2	5.56		
	340516PEER-63-ML											34	13.803	5.56	1.6	5.56		

	Steel	1	Р	0 1	# #	•		3 3	;		3	#	<b>3</b>	Machining types
9	Stainless steel	<b>-</b>	M		3 #			•		3 4	#	#		machining types
bje	Cast iron	4	K			•	3	3	•		3	#	•	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	<b>-</b>	N										•	,
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S								3	#		General cutting
	Hardened steel	=	Н				•	3			3	#		# Interrupted cutting

		Cermet				ated			Uncoated	ا	Dime	nsions	s (mm	1)		A
Inserts	Designation	CN2500 CN30	NCM325 NCM335	NCM535 NCM545	PC2505 PC2010	PC3700	PC9530	PC5300	ST30A H01	ı	d	t	r	d <sub>1</sub>	Geometries	Available tools
	090308									9.5	9.525	3.18	0.8	4.5		-
МРМТ	120408					•				12.7	12.7	4.76	0.8	5.5	d t 11°	
	0704SN					•				7.4	18	4.86	0.5	-		E63
	0704FN									7.4	18	4.86	0.5	-		
OFCN	070408SN 070408FN									7.4	18	4.86	0.8	-		
	070408FN 070408TN									7.4	18	4.86	0.8	-	d 126°	
	05T3SN									5.2	12.7	3.85	0.5	4.4		E62
OFCW	05T3FN									5.2		3.85	0.5	4.4		
	05T308FN									5.2	12.7	3.85	0.8	4.4	d d d1	
	0704FN-MA								•	7.4	18	4.76	0.5	-		E63
OFKR-MA	0704EN-MA									7.4	18	4.76	0.5	-	r d t 26°	
	0704SN-MF		• •							7.4	18	4.76	0.5	-		E63
OFKR-MF	070408SN-MF									7.4	18	4.76	0.8	-	d	
	0704SN-MM		• •			•	•	•		7.4	18	4.76	0.5	-		E63
OFKR-MM	070408SN-MM		•							7.4	18	4.76	0.8	-	d 126°	
	05T3FN-MA								•	5.2		3.97		4.4		E62
OFKT-MA	05T3EN-MA									5.2		3.97		4.4		E63
OFK I-IVIA	0704FN-MA								•		18	4.76		5.8		
	0704EN-MA									7.4	18	4.76	0.5	5.8	1 26°	
OFKT-MF	05T3SN-MF 05T308SN-MF									5.2		3.97 3.97		5.8	d d d dd	E62

	Steel		Р	3		3	•	•	•	3 1	8			3	#	3	Machining types
e	Stainless steel	1	M			3				•		3	#	•	#		machining types
bje	Cast iron	4	K		3			•	3	3			П	3	#		<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	4	N										П				· · · · · · · · · · · · · · · · · · ·
ĕ	Heat resistant alloy, Titanium alloy	<b>-</b>	S												#		General cutting
	Hardened steel		Н						•	3				3	#		* Interrupted cutting

		Commet			Cool	a d	3 8			_	None	me!-	unc 1	·ma \				
		Cermet	_ 10	юю.	Coat			Uncoated		L	ıme	nsic	ons (	mm)				Available
Inserts	Designation	CN2500 CN30	NC5330 NCM32	NCM53 NCM54	PC2505 PC2010	PC53/00 PC6510 PC9530	PC9540 PC5300 PC5400	ST30A H01	1	d	t	r	d <sub>1</sub>	а	W	g	Geometries	tools
	05T3SN-MM		•			•			_	12.7			4.4	-	-	-		E62
OFKT-MM	05T308SN-MM								_	12.7			4.4	-	-	-		E63
	0704SN-MM								7.4	18	4.76	0.5	5.5	-	-	-	d   d   d   26	o
ONHX-MF	060608-MF					•	• •		_	16.0			5.6	-	-	-	°√a	E143
ONHX-IVIF	080608-MF					•	• •	)	_	20.2			5.6	-	-	-		E144
1	0606ANN-MF					•	• •	)		16.0			5.6		-	-		
	0806ANN-MF					•	• •		8.4	20.2	6.0	0.8	5.6	1.53	-	-	1	
ONHX-ML	060608-ML						• •		_	16.0		8.0	5.6	-	-	-	%√a	E143
new	080608-ML						• •		8.4	20.2	6.0	8.0	5.6	-	-	-		E144
(3)																	d d	
ONLY MM	060608-MM					•	• •		6.6	16.0	6.0	0.8	5.6	-	-	-	o√a r	E143
ONHX-MM	080608-MM					•	• •		8.4	20.2	6.0	8.0	5.6	-	-	-		E144
	0606ANN-MM					•	• •	)		16.0			5.6		-	-		
	0806ANN-MM					•	• •		8.4	20.2	6.0	0.8	5.6	1.53	-	-		
ONLLY MA	060608-MA							•	6.6	16.0	6.0	8.0	5.6	-	-	-	o√a r	E143
ONHX-MA	080608-MA							•	8.4	20.2	6.0	8.0	5.6	-	-	-		E144
(9)																	d t	
	060608-W					• •	•		6.5	16.0	6.0	8.0	5.6	-	-	-		E143
ONHX-W	080608-W					•	•		8.2	20.2	6.0	8.0	5.6	-	-	-		E144
																	d d	
	060608-MF			•		•	• •		6.6	16.0	6.0	0.8	5.6	-	-	-		E143
ONMX-MF	080608-MF			•		•	• •		8.4	20.2	6.0	0.8	5.6	-	-	-	a r	E144
	0606ANN-MF			•		• •	• •	)		16.0					-	-		
	0806ANN-MF			•		• •	• •		8.4	20.2	6.0	0.8	5.6	1.53	-	-	d d	
	060608-MM			•		•	• • •		_	16.0		8.0		-	-	-		E143
ONMX-MM	080608-MM			•	•	• • •	• •			20.2				-	-	-	a r	E144
1600	0606ANN-MM			•			• •		_	16.0					-	-		
	0806ANN-MM			•		••	• •		8.4	20.2	6.0	0.8	5.6	1.53	-	-	d + td	
	265								10	7		0.3	3.5	-	2.65	2.8		E365
	325					•			10	7		0.3			3.25			
ORG	405								15						4.05			
	470								15	12	4.5	0.5	4.5	-	4.70	4.5		
																	w g d d d	

	Steel	<b>—</b>	Р	3		•	• ;	<b>8</b> 1	# 3	;			<b>3</b> 1	1		Machining types
9	Stainless steel	<b>-</b>	M				- (	<b>9</b> 1	E		3	#	<b>3</b> 1	¢		Machining types
pie	Cast iron	4	K		3		3 :	<b>8</b> 1	r)	•			<b>3</b> 1	¢	•	<ul> <li>Continuous cutting</li> </ul>
Ŧ	Non-ferrous metal	<b>-</b>	N												•	· · · · · · · · · · · · · · · · · · ·
8	Heat resistant alloy, Titanium alloy	<b>-</b>	S										<b>3</b> 1	¢		General cutting
ĺ	Hardened steel	<b>T</b>	Н				• :	<b>8</b> 1					<b>3</b> 1	¢		Interrupted cutting

		Cermet			Coate				Incoated		Dim	nensio	ons (n	nm)			
Inserts	Designation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC210F PC3700	PC6510	PC9540 PC5300	PC5400	S130A H01	ı	d	t	r	d <sub>1</sub>	Cutter width	Geometries	Avail too
	1223N				•					-	12.7	2.3	-	5.0	4.0		E41
	1225N									-	12.7	2.5	-	5.0	4.5		E41
	1230N									-	12.7	3.0	-	5.0	5.0		
	1235N				•	)	•			-	12.7	3.5	-	5.0	6.0		
PNEJ	1240N				•	)	•			-	12.7	4.0	-	5.0	7.0	1	
FILE	1245N				•	)	•			-	12.7	4.5	-	5.0	8.0		
	1250N									-	12.7	5.0	-	5.0	9.0		1
	1255N				•	)				-	12.7	5.5	-	5.0	10.0		
	1260N									-	12.7	6.0	-	5.0	11.0	108°	
	1265N						•			-	12.7	6.5	-	5.0	12.0	7	
	1270N									-	12.7	7.0	-	5.0	13.0		
	1275N						•			-	12.7	7.5	-	5.0	14.0		
	1285N									-	12.7	8.5	-	5.0	16.0		
	1223N-C03									-	12.7	2.3	-	5.0	4.0		E41
	1230N-C03									-	12.7	3.0	-	5.0	5.0		E41
	1235N-C03									-	12.7	3.5	-	5.0	6.0		
PNEJ-C	1240N-C05									-	12.7	4.0	-	5.0	7.0		
	1245N-C05									-	12.7	4.5	-	5.0	8.0		1
0	1250N-C05									-	12.7	5.0	-	5.0	9.0		
	1255N-C05									-	12.7	5.5	-	5.0	10.0	108	
	1260N-C05									-	12.7	6.0	-	5.0	11.0		
	1265N-C05									-	12.7	6.5	-	5.0	12.0	* C03: Chamfer 0.3 mm C05: Chamfer 0.5 mm	
	1270N-C05									-	12.7	7.0	-	5.0	13.0	Odd. Gridinior 0.0 min	
	1275N-C05									-	12.7	7.5	-	5.0	14.0		
	16				•					15.8	16	3.5	8	-	-		E33
	20				•					17.8	20	4	10	-	-		
RC	25				•					22.0	25	5	12.5	-	-		
	30 32				•					26.8	30	6	15 16	-	-		
																t	
	10T3M0-MA								•	-	10	3.97	-	3.85	-		E22
	1204M0-MA								•	-	12	4.76	-	4.5	-		E22
DCT-MA																d 15	F24
	0501M0F									-	5	1.59	-	2.3	-		E23
	0501M0E					•	'	_		-	5	1.59	-	2.3	-		E23
	0501M0S 06T1M0F									-	5 6	1.59	-	2.3	-		E24
	06T1M0E										6	1.98	-	2.5	-		
	06T1M0S					_					6	1.98		2.5			
	0702M0F									-	7	2.38	-	2.8	-		
	0702M0E						,				7	2.38		2.8	-		
RDHW	0702M0E										7	2.38		2.8			
	0803M0F									-	8	3.18	-	3.4	-		
	0803M0E					•				-	8	3.18	-	3.4	-		1
	0803M0S									-	8	3.18	-	3.4	-		5°
	1605M0F									-	16	5.56	-	5.5	-		
	1605M0E									-	16	5.56	-	5.5	-		
	1605M0S									-	16	5.56	-	5.5	-		
	2006M0F									-	20	6.35	-	5.5	-		
	2006M0E										20	6.35		5.5	-		
											20	0.55	-	5.5	- 1		

	Steel	Р	3	• 1	0	•	• ;	8 3	<b>:</b>	3	#	3	Machining types
9	Stainless steel	M		1	D.					2 # 3	#		Machining types
pie	Cast iron	K		3			3 3	•		3	#	•	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N										•	· · · · · · · · · · · · · · · · · · ·
ĕ	Heat resistant alloy, Titanium alloy	S								3	#		General cutting
	Hardened steel	Н					• :	8		3	#		# Interrupted cutting

		Cermet				oate	d			Uncoated		Din	nensio	ons (r	nm)				
Inserts	Designation		NC5330 NCM325	ICM535	NCM545 PC2505		PC6510 PC9530	PC9540	PC5400	ST30A H01	ı	d	t	r	d <sub>1</sub>	а	Geometr	ries	Available tools
	10T3M0-MF	00	ZZ	2 2	2 0.	<u> </u>	•	•		O I	-	10	3.97	-	3.85	-			E228~
	1204M0-MF					•	•	•			-	12	4.76	-	4.5	-			E230
RDKT-MF	1605M0-MF										-	16	5.56	-	5.5	-			E234~
																	d	d <sub>1</sub>	E236 E240 E241
	1605M0-ML										-	16	5.56	-	5.5	-			E230
RDKT-ML																	d	d1   15°	E236 E240 E241
	10T3M0-MM		•			•	• •	•			-	10	3.97	-	3.85	-			E228~
	1204M0-MM		•			•	• •	•			-	12	4.76	-	4.5	-	_		E231
<b>RDKT-MM</b>	1605M0-MM					•					-	16	5.56	-	5.5	-			E234~
	2006M0-MM					•					-	20	6.35	-	5.5	-		d <sub>1</sub>	E237 E240 E241
	0501M0E					•					-	5	1.59	-	2.3	-			E232
	06T1M0E					•					-	6	1.98	-	2.5	-			E233
<b>RDKW</b>	0702M0E					•					-	7	2.38	-	2.8	-			E238
	0803M0E					•					-	8	3.18	-	3.4	-	d	d <sub>1</sub>	E239
	170400-MM										-	17.8	4.76	-	-	-			E63
REKR-MM																	d	20°	
	1204M0E-ML										-	12.0	4.75	6.0	-	2.0			E145
RNMX-ML																	s a	t	E146
	10T3M0-MA									•	-	10	3.97		4.0				E242~
RPCT-MA	1204M0-MA									•	-	12	4.76	-	4.5	-	1 .		E245
RPC I-IVIA	1606M0-MA									•	-	16	6.35	•	5.5	-			E247~
0	2007M0-MA									•	-	20	7.00	-	7.0	-	d	11°	E253

Stainles			3			* * * *						M	achini	ing types	
Non-ferro Heat resistant allo	iron K us metal N ny, Titanium alloy S		8	• • •		* * * * * * * * * * * * * * * * * * *	•					<b>≇</b> Ge	neral o	us cutting cutting ed cutting	
		Cormot			`ootod		Unacoted		Dir	manaid	ono (n	nm)			
Inserts	Designation					PC9530 PC9540 PC5300 PC5400		ı	d	t	r	d <sub>1</sub>	а	Geometries	Available tools
PMT-MF	0803M0E-MF 10T3M0E-MF 1204M0E-MF 1606M0E-MF 2007M0E-MF					• • •			8 10 12 16 20	3.18 3.97 4.76 6.35 7.00	-	3.4 4.0 4.5 5.5 7.0	-	d 11°	E242~ E253
RPET-ML	0803M0E-ML 103TM0E-ML 1204M0E-ML 1606M0E-ML 2007M0E-ML					0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0			8 10 12 16 20	3.18 3.97 4.76 6.35 7.00		3.4 4.0 4.5 5.5 7.0		d    d	E242~ E253
РМТ-ММ	0803M0S-MM 10T3M0S-MM 1204M0S-MM 1606M0S-MM 2007M0S-MM			•	• • • • • • • • • • • • • • • • • • •	000000000000000000000000000000000000000		-	8 10 12 16 20	3.18 3.97 4.76 6.35 7.00		3.4 4.0 4.5 5.5 7.0		d d <sub>111°</sub>	E242~ E253
RPMW	0803M0E1 10T3M0E1 1204M0S1 1204M0S2 1606M0S1 2007M0S1			•	•	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		-	8 10 12 12 16 20	3.18 3.97 4.76 4.76 6.35 7.00		3.4 4.0 4.5 4.5 5.5 7.0		d d <sub>1</sub>	E242~ E253
AGX-ML	140808ANER-M	L				• •		-	14	6.58	0.8	-	1.21		E141
AGX-MM	140808ANER-MI	VI				•		-	14	6.58	0.8	-	1.21	d ra	E141
NMX-MM	140808ANER-MI	M Control of the cont			• •	•		-	14	6.58	0.8	-	1.21		E141
	PMT-MM PET-ML PMT-MM AGX-ML AGX-MM	Designation	Designation	Designation	Designation   Cemet   Company   Cemet   Company   Cemet   Company   Cemet   Company   Cemet   Company   Cemet   Company   Cemet   Ce	Designation	Designation	Designation	Designation	Designation	Designation	Designation	Inserts   Designation   Desi	Inserts   Designation   Coated   State   Dimensions (mm)	Designation   Coate   Coate   Dimensions (mm)
	Steel	Р		• :	<b>B</b> (	B (	¢ (	9 (	9	3			3		1
------	--------------------------------------	---	------------------	-----	------------	-----	-----	-----	---	---	---	---	---	-----	---
9	Stainless steel	M	$\triangleright$		1	B 1	¢				1	#			
bje.	Cast iron	K					•			•			3		
ž	Non-ferrous metal	N												# (	•
Š	Heat resistant alloy, Titanium alloy	S											3		
	Hardened steel	Н											3		

		Cermet				oate					nco	ated		Di	mens	ions	(mn	n)			
Inserts	Designation	CN2500 CN30	NCM325	NCM535	NCM545 PC3700	PC6510	PC9530	PC5300	PD1010	ST30A	G10	H05	1	d	t	r		d₁	а	Geometries	Availa
	220715DDSR-MM			•	•			•					-	22.0		1.5		-	2.5		E58
SCKN	280920DDSR-MM									+			-	28.0	9.0	2.0		-	3.0	a	
																				r t	
	42M										•		-	12.7				-	1.5		E47
	42M-G											•	-	12.7	3.18			-	1.5	-	E48
	42MT	• •		_				_		•			-	12.7				-	1.5	-	E59
	42MT-RH 42MT-S20						•	_	-				-	12.7 12.7				-	1.5	-	E60
	53M										•	-	-	15.87				-	1.5	-	
	53M-G											•	-	15.87				-	1.5		
	53MT	•	•							•			-	15.87				-	1.5		
	53MT-RH												-	15.87	4.76	-		-	1.5	1 <del>( -                                  </del>	
SDCN	53MT-S20						•						-	15.87	4.76	-		-	1.5	15°	
	1203AEEN								Ш				-	12.7				-	1.5	d   t   '	
	1203AEEN-RH												-	12.7				-	1.43	b Cutting adaptation	
	1203AESN												-	12.7	3.18			-	1.5	► Cutting-edge geometry - G: Light Side, Sharpe Edge	
	1203AESN-RH 1504AEEN									-			-	12.7				-	1.43	- S20: STS	
	1504AEEN-RH			_		•		•		+		-	-	15.87				÷	1.43	- RH: Strengthened edge	
	1504AESN					Ť		Ť					-	15.87				_	1.5	. O. b	
	1504AESN-RH					•			П				-	15.87					1.43	► Sub-cutting-edge geometry	
	09M402R-MA								4			• •	_	9.525	i 3.92	3 0.2		4.0	1.2		E222
	09M404R-MA								_				-	9.525				4.0	1.2		E227
SDET-MA	09M405R-MA												-	9.525				4.0	1.2	a h	
	130504R-MA								•			• •	-	13.5	5.56	0.4		5.56	2.2		
	09M405R-MF												-	9.525	i 4	0.5		4	1.2	15	E222
	130508R-MF												-	13.5				5.56	2.2	<u>+</u>	E227
SDET-MF																				d t	
	09M405R-MM												-	9.525		0.5		4	1.2		E222
SDET-MM	130508R-MM												-	13.5	5.56	8.0	5	5.56	2.2		E227
9																				d t 15	>
													-	12.7	3.18			-	1.5		-
	42MT-CM	•								_											

		teel Pess steel M	• \$	0 2 #	• • •	* * * *	3					Ma	achini	ng types	
Workpiece	Non-fer Heat resistant a	st iron K rous metal N Illoy, Titanium alloy S ned steel H		3		3 H 3 H	• 3					<b>3</b> G	enera	ious cutting I cutting Ited cutting	
			Cermet		Coated	d	Uncoated		Din	nensi	ons (n	nm)			
	Inserts	Designation	CN2500 CN30	NC5330 NCM325 NCM335	NCM535 NCM545 PC3700	PC9530 PC9540 PC5300	ST30A H01 H05	ı	d	t	r	d <sub>1</sub>	а	Geometries	Available tools
		1203AESN-MU 1504AESN-MU			•			-	12.7	3.18	-	-	2.08		E47
SI	DKN-MU	1304AESN-IMU			•			-	15.875	4.76			2.10	a d t 15	E48 E53 E54
		1203AESN-SU			•	• •		-	12.7	3.18	-	-	2.08		E47
S	DKN-SU	1504AESN-SU			•	• •		-	15.875	4.76	-	-	2.10	a d t	E48 E53 E54
		1203AESN-MX						-	12.7	3.18	-	-	1.46		E47
61	DKR-MX	1203AETN-MX 1203AEN-MX		•				-	12.7 12.7	3.18 3.18	-	-	1.46 1.46	\a_	E48 E53
3	DRK-IVIA	1504AESN-MX		•	)			-	15.875	4.76	-	-	1.45		E54
5		1504AETN-MX						-	15.875	4.76	-	-	1.45		
		1504AEN-MX		•				-	15.875	4.76	-	-	1.45	d t	
		090308-MM			•	•		-	9.525	3.18	0.8	4.4	-		E307 E336
SI	OMT-MM													r d d 14	•
		09M405R-MA					• •	-	9.525	4.0	0.5	4.0	1.2	,	E222~
S	DXT-MA	130508R-MA					• •	-	13.5	5.56	0.8	5.56	2.2	d d	E227
		09M403R-MF						-	9.525	4.0	0.3	4.0	1.2		E222~
		09M403L-MF 09M404R-MF						-	9.525 9.525	4.0	0.3	4.0	1.2	<u></u>	E227
S	DXT-MF	09M404L-MF						-	9.525		0.4	4.0	1.2	a h	
4	6	09M405R-MF		•	•	• • •		-	9.525	4.0	0.5	4.0	1.2		
1		09M405L-MF 130508R-MF		•		• • •		-	9.525 13.5	4.0 5.56	0.5	4.0 5.56	1.2 2.2	d t	
_		09M405R-MM		• •	•			-	9.525	4.0	0.5	4.0	1.2		E222~
_		09M405L-MM						-	9.525	4.0	0.5	4.0	1.2	r	E227
S	DXT-MM	130508R-MM		• •	•	• • •		-	13.5	5.56	0.8	5.56	2.2	a D	
	9	130508L-MM 130538-MM						-	13.5 13.5	5.56 5.56	3.8	5.56 5.56	2.2	d t	•
		1204AFSN		•				-	12.7	4.76	-	5.56	2.66		-
	SECA	1204AFTN	•		•	•		-	12.7	4.76	-	5.56	2.66	a	
		1204AFFN 1204AFEN						-	12.7 12.7	4.76 4.76	-	5.56 5.56	2.66	I A	
		1504AFSN						-	15.875	4.76	-	5.5	2.8	720	
		1504AFTN						-	15.875	4.76	-	5.5	2.8	d	
		1504AFFN						-	15.875	4.76	-	5.5	2.8		

	Steel	<b>—</b>	Р	0 3	2 # 1	;	1	#		3		Machining types
9	Stainless steel	<b>-</b>	M		<b>*</b>	1	# 1	#				machining types
bje	Cast iron	4	K			•	1	#			<b>\$ 0 0</b>	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	<b>-</b>	N						# •		• 3	-
≥	Heat resistant alloy, Titanium alloy	<b>-</b>	S				1	#				General cutting
	Hardened steel	=	Н				1	#				# Interrupted cutting

		Cermet			oated	d	Und	coated		Dim	ensio	ns (n	nm)			
Inserts	Designation	CN2500 CN30	NCM325 NCM335	C3700 C6510	PC9530 PC9540	PC5300 PC5400 PD1010	ST30A	H H H H	ı	d	t	r	<b>d</b> 1	а	Geometries	Available tools
	1203AFFN	00	ZZI	<u>а</u> а	<u>а</u> а			5 I I	-	12.7	3.18			2.36		E49
	1203AFTN	• •							-	12.7	3.18			2.36		E50
	1203AFEN								-	12.7	3.18	-	-	2.36		
	1203AFSN		• •						-	12.7	3.18	-	-	2.36		
	1203AFEN-RH			•		•			-	12.7	3.18	-		2.36	\\ a	
	1203AFSN-RH								-	12.7	3.18	-	-	2.36		
	1203AFTN-S20				•				-	12.7	3.18	-	-	2.36		
SECN	1504AFFN								-	15.875	4.76	-	-	2.4	20	,
	1504AFTN	•							-	15.875	4.76	-	-	2.4		
	1504AFEN								-	15.875	4.76	-	-	2.4		
	1504AFSN								-	15.875	4.76	-	-	2.4	► Shape of Edge	
	1504AFEN-RH								-	15.875	4.76	-	-	2.4	- S20: STS	
	1504AFSN-RH			•					-	15.875	4.76	-	-	2.4	- RH: Strengthened edge, STS	
	1504AFTN-S20								-	15.875	4.76	-	-	2.4		
	00024 CEN MA									0.505	0.10		0.4	0.44		E216~
	0903AGFN-MA					• •		• •	-	9.525	3.18 4.0	•	3.4 4.4	2.11	, 🔀 a	E210~
SEET-MA	14M4AGFN-MA								-	14.0	4.0	-	4.4	2.04	d d	E221
	0903AGSN-MF			•	•	• •			-	9.525	3.18	-	3.4	2.11		E216~
SEET-MF	14M4AGSN-MF			•	•	• •			-	14.0	4.0	-	4.4	2.64	a d,	E221
	0903AGSN-MM		•	•		• •			-	9.525	3.18	-	3.4	2.11		E216~
SEET-MM	14M4AGSN-MM		•	•	•	• •			-	14.0	4.0	-	4.4	2.64	d d1	E221
	0903AGTN								-	9.525	3.18	-	3.4	2.11		E216~
SEEW	14M4AGTN	•							-	14.0	4.0	-	4.4	2.64	A A	E221
6															d 1/20	
	14M4AGFN-W								-	14.0	4.0	-	4.4	8.5		E217
SEEW-W	14M4AGSN-W					•			-	14.0	4.0	-	4.4	8.5	d 20°	E219
	14M4AGTN-W			•					-	14.0	4.0	-	4.4	8.5	a a 1	E221
	1203AFSN-SU		(	•					-	12.7	3.18	-	-	1.98		E49
SEKN-SU	1504AFSN-SU			•		•			-	15.875	4.76	-	-	2.04		E50
															d t	

	steel Pess steel M	• 3	2 # 2 #	• • •	0	_	<b>*</b> * :	2 # 2 #						Machi	ning types	
Non-fer Heat resistant a	st iron K rous metal N alloy, Titanium alloy S ned steel H			• • 1			;	2 # 2 # 2 #	•				1	Gene	nuous cutting ral cutting upted cutting	
		Cermet			Coate				Uncoated		Dimer	nsions	(mm)			
Inserts	Designation	CN2500 CN30	NCM325 NCM335	NCM535 NCM545	PC2010	PC6510	PC9530 PC9540	PC5300 PC5400	ST30A H01	ı	d	t	d <sub>1</sub>	а	Geometries	Available tools
SEKR-MX	1203AFSN-MX 1504AFSN-MX		• •				•			-	12.7 15.875	3.18 4.76	-	2.3	×a	E49 E50
												-			d	20°
	1204AZ									-	12.7	4.76	-	2.0		-
SEMN															a t	20°
	0903AGSN-MF					•		• •		-	9.525	3.18	3.4	2.11		E216~
SEXT-MF	14M4AGSN-MF					•		• •		-	14.0	4.0	4.4	2.64	a	E221
SEXT-IIII															d	d1 20°
	0903AGSN-MM				•	•		• •		-	9.525	3.18	3.4	2.11		E216~
SEXT-MM	14M4AGSN-MM		•		•			• •		-	14.0	4.0	4.4	2.64	a d	E221
	0903AGSN-MR									-	9.525	3.18	3.4	2.11		E216~
SEXT-MR	14M4AGSN-MR						•	•		-	14.0	4.0	4.4	2.64	a t	E221
	1203EFR								•	-	12.7	3.18	-	2.5	,	E51
SFCN															a t	
	SNMF 1206ANN-MF									-	12.7	6.6	-	2.0		E136
SNC(M)F-MF	1507ANN-MF SNCF 1206ANN-MF					Н				-	15.875 12.7	7.35 6.6	-	2.1	a	E137
•	1507ANN-MF					•				-	15.875	7.35	-	2.1	d	-
CNO/ESS SS	SNMF 1206ENN-MF				•	)				-	12.7	6.6	-	1.8	2	E138
SNC(M)F-MF	1507ENN-MF SNCF 1206ENN-MF					•				-	15.875 12.7	7.35 6.6	-	1.8	a a a	E139
•	1507ENN-MF					•				-	15.875	7.35	-	1.8	d t	-

	Steel	Р	3	0 1		• •	<b>3</b> 1	E .		3 1	<b>‡</b> 3	t	Machining types
8	Stainless steel	M		1	ţ.				3 #	3 (	¢		Machining types
pie	Cast iron	K		3		0 3	3			3 1	¢		<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N											· · · · · · · · · · · · · · · · · · ·
ĕ	Heat resistant alloy, Titanium alloy	S								3 1	¢		<b>◆</b> General cutting  ■ Interpretable to the control of the co
	Hardened steel	Н					3			3 1	¢		# Interrupted cutting

	a steel	Courset			<b>O</b> 3				<b>3</b> #				Niman	olone	- /m-	۵۱			
Inserts	Designation	Cermet	S 73 F	8 <del>8</del>		ated		0	<u> </u>	Uncoated			imen	ISIONS	s (IIIII)	i)		Geometries	Available
inserts	Designation	CN250 CN30	NC5330 NCM325	NCM5	PC250	PC370	PC651 PC953	PC954	PC530 PC540	ST30A H01	1	d	t	r	d <sub>1</sub>	а	b	Geometries	tools
	SNMF 1206QNN-MF SNCF 1206QNN-MF					•	•	Н			-	12.7 12.7	6.6	0.8	-	1	-		E140
SNC(M)F-MF												12.7	0.0	0.0		ı		a a d	
	SNMF 1206ANN-MM 1507ANN-MM							Н			-	12.7 15.875	6.6 7.35	-	-	2.1	-		E136 E137
SNC(M)F-MM	SNCF 1206ANN-MM										-	12.7	6.6	-	-	2	-	a	
	1507ANN-MM										-	15.875	7.35	-	-	2.1	-	d	
	SNMF 1206ENN-MM 1507ENN-MM					•					-	12.7	6.6 7.35	-	-	1.8	-		E138 E139
SNC(M)F-MM	SNCF 1206ENN-MM										-	15.875 12.7	6.6	-	-	1.8	-	a la	E139
0	1507ENN-MM										-	15.875	7.35	-	-	1.8	-	d	
	SNMF 1206QNN-MM SNCF 1206QNN-MM					•	•				-	12.7 12.7	6.6 6.6	0.8	-	1	-		E140
SNC(M)F-MM	SNCF 1200QIVIN-IVIIVI										•	12.7	0.0	0.8	-	1	-	a a a t	
	1204ENN		•							•	-	12.7	4.76	-	-	1.4	1.0		E52
SNCN	1504ENN										-	15.875	4.76	-	-	1.4	1.0	a b	
	435 535					(	•				-	12.7 15.875		2.0	-	-	-	_r_	-
SNEF	333											10.073	4.70	2.0				d	
	120420-MF					(	•				-	12.7	4.76	2.0	5.7	(2.3)	-	r	E423
SNEU-MF																		d t	
	1204ANN-MF										-	12.7	4.76	-	5.7	(2.0)	-		E423
SNEU-MF																		a t	

	steel Pess steel M	0 \$	• • •	• : :	* * * *	_					М	achin	ing types	
Non-feri	st iron  rous metal  N  Illoy, Titanium alloy  seel  H		200	• •	3 # 3 # 3 #	•	• •				•	Gener	nuous cutting ral cutting upted cutting	
		Cermet	10.10	Coated			PCD		Dimensi	ons (r	nm)			Available
Inserts	Designation	CN2500 CN30	NC5330 NCM535 NCM545	PC2505 PC2010 PC3700 PC6510	PC9530 PC9540 PC5300 PC5400	H01	DP150 DP200	1	d t	r	<b>d</b> 1	а	Geometries	Available tools
SNEU-TBW	1204-TBW								2.7 4.76		5.7	(2.1)	d a t	E423
SNEU-WMF	1204R-WMF							- 1	2.7 4.76	-	5.7	-	d t	E423
SNEX	101010 1010ZNN			•					10 10 10 10	1.0 (1.0)	4.6 4.6	-	r dı	-
SNEX-CU1	101010-CU1 1010ZNN-CU1 121212-CU1 1212ZNN-CU1			•				- 1	10 10 10 10 2.7 12.7 2.7 12.7	1.0 (1.0) 1.2 (1.2)	4.6 4.6 5.6 5.6		r di	-
SNEX-MA	1206ANN-MA 1206ENN-MA 1206QNN-MA 120612-MA			•		•		- 1 - 1	2.7 6.35 2.7 6.35 2.7 6.35 2.7 6.35	- - 1.2	4.5 5.2 5.2 5.2	2.36 1.82 1.39	d t	E126 E127 E130 E131 E134 E135
SNEX-ML	1206ANN-ML 1206ENN-ML 1206QNN-ML 120612-ML 1507ANN-ML 1507ENN-ML				• • •			- 1 - 1 - 1	2.7 6.35 2.7 6.35 2.7 6.35 2.7 6.35 2.7 6.35 875 7.94 875 7.94	- - 1.2 -	4.5 5.2 5.2 5.2 5.6 5.6	2.36 1.82 1.39 - 3.16 2.66	a d	E126~ E135
SNEW	09T3ADFR					•		9.525 9.	525 3.97	-	4.4	-	d c t	E154 E155
SNEW-NAF	09T3ADTR-NAF 09T3ADTR-NAW NAW: Wiper insert								525 3.97 525 3.97	-	4.4	-	d c t 15	E154 E155
SNEW-XAF	09T3ADTR-XAF 09T3ADTR-XAW XAW: Wiper insert								525 3.97 525 3.97	-	4.4	-	d c t	E154 E155

	Steel	1	Р	0 1	B (		3	•		1	B #	;	Machining types
9	Stainless steel	<b>-</b>	M				•			# 1	#	;	Machining types
pie	Cast iron	<b>-</b>	K		1	B (	3		•	1	#	;	<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	<b>-</b>	N				П						· · · · · · · · · · · · · · · · · · ·
ĕ	Heat resistant alloy, Titanium alloy	⋜	S				П			1	#	;	General cutting     Hattananta di autting
	Hardened steel	◂	Н				3			1	B #	;	Interrupted cutting

			Cermet			Coated		PCD		D	imen	sion	s (mr	n)				
Inserts	De	esignation	CN2500 CN30	NC5330 NCM535	NCM545 PC2010	PC3700 PC6510	PC9530 PC5300 PC5400	DP150 DP200	ı	d	t	r	d <sub>1</sub>	а	b	Geometr	ies	Available tools
		08R-WX					•		-	11	2.30	-	4	-	-			E416
		8R-WX					•		-	11	3.00	-	4	-	-			E417
		08R-WX 8R-WX					•		-	12.7	3.50 4.00	-	5 5	-	-			
		08R-WX					•		-	12.7	4.54	-	5	-	-			
		8R-WX					•		-	12.7	5.00	-	5	-	-			
		08R-WX					•		-	12.7	5.47	-	5	-	-			
		8R-WX 08R-WX							-	12.7	6.00	-	5 5	-	-			
		8R-WX								12.7	7.00	-	5	-	-			
		08R-WX							-	12.7	7.5	-	5	-	-			
SNHT-WX		08L-WX					•		-	11	2.30	-	4	-	-	The same of the sa		
		8L-WX					•		-	11	3.00	-	4	-	-		d <sub>1</sub>	
		8L-WX 08L-WX					•		-	12.7	3.25	-	5 5	-	-			
		8L-WX							-	12.7	4.00	-	5	-	-	d	t	
10.40	12045	08L-WX					•		-	12.7	4.54	-	5		•			
		8L-WX					•		-	12.7	5.00	-	5	-	-			
		08L-WX					•		-	12.7	5.47	-	5	-	-			
		8L-WX 08L-WX							-	12.7	6.00	-	5 5	-	-			
		8L-WX							-	12.7	7.00	-	5	-	-			
		08L-WX							-	12.7	7.5	-	5	-	-			
SNKN	1204E 1504E					•			-	12.7 15.875	4.76 4.76	-	-	1.4	1.0			E52
																Ta da		
	SNMX	1206ANN-MF 1507ANN-MF		•		• •	• • •		-	12.7 15.875	6.35 7.94	-	4.5	2.36	-	, Xa		E126~ E129
SNM(E)X-MF	SNEX	1206ANN-MF				• •	• •		-	12.7	6.35	÷	5.6 4.5	2.36				E129
		1507ANN-MF				•	• •		-	15.875		-	5.6	3.15	-	d -	d <sub>1</sub>	
	SNMX	1206ENN-MF		•		• •	• • •		-	12.7	6.35	-	5.2	1.82	-	_		E130~
SNM(E)X-MF	SNEX	1507ENN-MF 1206ENN-MF		•		• •	• •		-	15.875 12.7		-	5.6 5.2	2.66	-	a		E133
	SINEX	1507ENN-MF				•	• •		-	15.875	6.35 7.94	-	5.6	1.82 2.66	-	d d	d <sub>1</sub>	
	SNMX	1206QNN-MF		•		• •	• •		-	12.7	6.35	-	5.2	2.36	-			E135
SNM/E/V ME		120612-MF				•	• •		-	12.7	6.35	1.2	5.2	-		<u>a</u>		
SNM(E)X-MF	SNEX	1206QNN-MF				• •	• •		-	12.7	6.35	-	5.2	2.36	•	a		
		120612-MF				•	• •		-	12.7	6.35	1.2	5.2	-	-	d	d <sub>1</sub>	
	SNMX	1206ANN-MM		• •		• • •	• • •		-	12.7	6.35	-	4.5	2.36	-			E126~
		1507ANN-MM		•		• •	• •		-	15.875		-	5.6	3.15	-			E129
SNM(E)X-MM	SNEX	1206ANN-MM				• • •			-	12.7	6.35	-	4.5	2.36	-	X		
		1507ANN-MM				•	• •		-	15.875	7.94	-	5.6	3.15	-	d	t d1	

SNM(E)X-MM       1206ENN-MM       ● ● ● ● ● ● ● ● ● 12.7 6.35 - 5.2 1.82         SNM(E)X-MM       ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ● ●	cutting
Inserts   Designation	Geometries tools  E130~ E133  E134 E135
Inserts   Designation	Geometries tools  E130~ E133  E134 E135
SNMX     1206ENN-MM     • • • • • • • • • 12.7     6.35     - 5.2     1.82       SNM(E)X-MM     • • • • • • • • • 15.875     7.94     - 5.6     2.66       SNEX     1206ENN-MM     • • • • 12.7     6.35     - 5.2     1.82	E133  E134  E135
SNEX 1206ENN-MM	a E134 E135
	a E134 E135
	E135
CITIFIX 1200GITT WITH	
12.0 0.00 1.2 0.2	
LEON CONTROL C	d t
SNEX-W - 12.7 6.35 - 4.5 7.6	E126 E127
1203EDR • • • - 12.7 3.18 1.4 1	0 E53
	0 E54
	0
	0
	0
	8 8
	8 + + + + + + + + + + + + + + + + + + +
1202EDD C20	1110
SPCN 4504405	d   t   '
1504EDR	0
1001=201	0
	0
	0 0 d t
	8
	SPCN150412T
	8
	0
120410 110	<u> </u>
OF EN-IVO	
100101 110	d 11°
120022111	11° E53
SPEX	11° E53 E54
1007-1011	a 14°
200-N 8.8 2.2 - 0.2	E413
000 N	
SPFN	d l

	Steel		Р		3		1	: 4	•	•	3				3	#	3		
S	Stainless steel		M				1	#					3	#	3	#			
pie	Cast iron	4	K		П	3	;		•			•			3	#		3	•
ž	Non-ferrous metal	<b>-</b>	N				П												
×	Heat resistant alloy, Titanium alloy	<b>-</b>	S				П								3	#			
	Hardened steel	◂	Н				П								3	#			

Harde	ened steel H	1					3 1	¢							<b>49</b> III	torrup	ned cutting	
		Cermet			Coat	ed		U	Incoated		Di	imen	sion	s (mı	m)			
Inserts	Designation		NC5330 NCM325	NCM335 NCM535		PC6510 PC9530	PC9540 PC5300		G10 H01	ı	d	t	r	d <sub>1</sub>	a	b	Geometries	Available tools
SPKN-MU	1203EDSR-MU 1504EDSR-MU				•					-		3.18 4.76	-	-	0.86 0.84		a la	E53 E54
	1203EDSR-SU				•		•			-	12.7	3.18	_	-	1.66	0.92	d t 11°	E53
SPKN-SU	1203EDSL-SU				•					-		3.18	-	-		0.92		E54
	1504EDSR-SU				•		•			-	15.875	4.76	-	-	1.62	0.93		
	1504EDSL-SU				•					-		4.76	-	-		0.93	d t 11°	
	1203EDSR-MX		•	•				+		-		3.18	-	-	1.4	-	+ + ·	E53
SPKR-MX	1203EDSL-MX 1504EDR-MX		•							-	15.875	3.18	-	-	1.45	-		E54
	1504EDSR-MX										15.875			÷	1.45		<del>  {                                   </del>	
	1304LD3N-WX										13.073	4.70			1.40		d t 11°	
	120308									-	12.7	3.18	0.8	-	-	-	r	E369
SPMN																	d 110	
SPMT	060304		•							-	6.35	3.18	0.4	2.8	-	-	r	E307
																	d 11°	E334 E335
	110408-KC				•				•	-	11.5	4.8	0.8	4.5	-	-	<u> </u>	E369
SPMT-KC																	1 d d d d d d d d d d d d d d d d d d d	
001171111	120408-MM				•		•			-		4.76		5.6	-	-		E307
SPMT-MM	120508-MMN									-		5.56		5.6	-	-	d1	E334 E336 E352
	TECN 22R	•									6.35		- 0.0	_	1.0	0.5	60°	E61
	22TR 32R								•	_	6.35 9.525		0.8	-	1.0	0.5		
TEC(E)N	32R-G									_	9.525		-	-	1.0			
	32TR	•		•						_	9.525			-	0.5	-	120°	
	32TR-S20					•		ľ			9.525			-	0.5	-	d a t	
	43R-G									_	12.7		-	-	2.0	0.5		
	43TR-Z									22.0	12.7	4.76	0.8	-	1.5	-	60°	
	43TR									22.0	12.7	4.76	0.8		1.5	-		
	TEEN 32TR									_	9.525		0.8	-	0.5	-		
	43R-Z									_	12.7		-	-	2.0	0.5		
TEEN	43TR-Z							•		22.0		4.76		-	1.5	-	20°	
	43TR-ZH					•				22.0		4.76		-	1.5	-		
	43R								•	22.0		4.76	•	•	2.0	0.5	►Shape of Edge	
	43R-G							1	•	_		4.76	-	-		0.5	- G: Light side, Sharp edge	
	43TR	• •	•	•		•			•	22.0		4.76		-	1.5	-	- S20: STS	
	43TR-S20					•				22.0	12.7	4.76	0.8	-	1.5	-	- ZH: Hole added	

9	Ste Stainles		• 3	0 1	£ #	• •	3	<b>3</b> :		##	3							Mac	hinir	ng types	
Workpiece	Cast Non-ferro Heat resistant allo Hardene	us metal N ny, Titanium alloy S		3		• •	•		<b>3</b>	#	3	•					3	Gen	eral c	us cutting cutting d cutting	
										**							,				
lı	nserts	Designation	CN2500 CN30		NCM335 NCM335		PC3700 PC6510		PC9540 PC5300	PC5400	ST30A G10		ı	d	)imen t	sion: r	s (mn	n) a	b	Geometries	Available tools
		2203PFR										•	22.0	12.7	3.18	-	-	2.42		600	E55
4	FEN	2203PFL											22.0	12.7	3.18	-	-	2.42	0.71	d a t	
		110508PEER-ML					•	-	• •				-	8.0	4.500	0.8	-	1.3	-		E258~
TN	KT-ML	160608PEER-ML					•		•				-	11.7	5.500	0.8	-	1.5	-		E261
	new	200708PEER-ML					•		• •				-	14.5	7.000	0.8	-	2.0	-		
4		110508PESR-MM					• •		•				-	8.0	4.531	0.8		1.3			E258~
TN	KT-MM	160608PESR-MM					• •		•				-	11.7	5.531	0.8	-	1.5	-		E261
4	new	200708PESR-MM					• •		•				-	14.5	7.031	0.8	-	2.0	-	-	
		2710AZNR-NM		•		•	•	•	•				27	15.875	10	0.8	5.6	2.63	-		E68~
TN	MX-NM	2710AZNL-NM 3012PNR-NM											27	15.875	10	0.8	5.6 5.6	2.63	-	60°	E70
1																				d t	
		1103PPN	•								• •	)	11.0	6.35	3.18	-	-	0.7	0.7	_	E56
		1103PPTN						Н					11.0	6.35 9.525	3.18	-	-	0.7	0.7	_	
		1603PDR 1603PPN	•	_		-	•	Н			•			9.525		-		1.2	1.2	-	
		1603PPR	•	-				Н	_		• •			9.525		-	-	1.2	1.0	-	
		1603PPR-RH						П						9.525		-	-	1.2	1.0	-	
		1603PPR-G										•	16.5	9.525	3.18	-	-	1.2	1.0		
		1603PPSR												9.525		-	-	1.2	1.0		
		1603PPTN						Ш							3.18	-	-	1.2	1.2	-	
		1603PPTR 1603PPTR-RH						Н						9.525 9.525		-	-	1.2	1.0	- - -	
		1603PDER-RH					•	Н	•						3.18			1.5	1.0	- XX	
		1603PDSR-RH					•		Ť						3.18		-	1.5	-		
		1603PDR-S20						•					16.5	9.525	3.18	-		1.2	0.7		
1	<b>TPCN</b>	1603PDR-RN													3.18	-	-	1.5	1.1		0
		2204PDR	•					Ш			• •	)	22.0	12.7		-	-	1.4	0.7	d Xa t /	
		2204PDR-RH						Н					22.0		4.76	-	_	1.4	0.7	600	
		2204PDR-RN 2204PDR-G						Н				•			4.76 4.76	-	-	1.42	0.52		
		2204PDL						Н			•			12.7		÷	÷	1.4	0.7		
		2204PDSR			•			Н							4.76	-	-	1.4	0.7		
		2204PDTR												12.7		-	-	1.4	0.7		0
		2204PPN												12.7		-	-	1.2	1.2	d la t	
		2204PPTN												12.7		-	-	1.2	1.2		
		2204PDR-RH						Н							4.76		•	1.8	-	-	
		2204PDER-RH					•	_	•					12.7			-	1.8	-	-	
		2204PDSR-RH 2204PDR-S20					•	•						12.7	4.76	0.8	-	1.8	0.7	-	
		ZZU4F DN-3ZU																1.4	0.7		
					>	∦ In th	nis paq	e, TP	C(K)N	ΙD		]P~N	N is for	FC·F	IC and					• : 5	Stock item

	Steel	<b>4</b>	Р	3	3	#	•	•	•	<b>3</b>	•				#	Machining types
8	Stainless steel	<	M		3	#						1	#		#	wacrining types
bje	Cast iron	4	K				•	•	3	3		•		3	#	● Continuous cutting
ž	Non-ferrous metal	4	N													,
ĕ	Heat resistant alloy, Titanium alloy	<	S											3	#	● General cutting
	Hardened steel	◂	Н						•	3				3	#	# Interrupted cutting

Traide	ned steel H					<b>.</b>			<b>3</b> 8										, and the same of	
		Cermet				oate	d			Uncoded			Dime	ensi	ons	(mm	)	1		
Inserts	Designation	CN2500 CN30	NCM325 NCM335	NCM535 NCM545	PC2505	PC2510 PC3700	PC6510	PC9540	PC5300 PC5400	H01	ı	d	t	r	d <sub>1</sub>	а	b	f	Geometries	Available tools
	2204PDSR-MU					•					22.0	12.7	4.76	0.8	-	1.96	-	-		E56
TPKN-MU																			60°	
	1603PDSL-SU					•					16.5	9.525	3.18	1.0	-	1.70	-	-		E56
	1603PDSR-SU					•							3.18		-	1.70	-	-	60°	
TPKN-SU	2204PDSL-SU					•							4.76		-	1.91	•	-		
	2204PDSR-SU					•				1	22.0	12.7	4.76	1.0	-	1.91	-	-	111°	
	1603PDSN-MX										16.5	9.525	3.18	-	-	1.2	1.2	-	60°	E56
	1603PDSR-MX										16.5	9.525	3.18	-	-	1.2	0.7	-		
	1603PPR-MX		•								16.5	9.525	3.18	-	-	1.2	1.0	-		
<b>TPKR-MX</b>	1603PPSN-MX										16.5	9.525	3.18	-	-	1.2	1.2	-		
A.	1603PPSR-MX		•									9.525		-	-	1.2	1.0	-	1110	
	2204PDR-MX												4.76		-	1.4	-	-	60°	
2233	2204PDSR-MX		• •										4.76		-	1.4	-	-		
	2204PPR-MX										22.0	12.7	4.76	1.0	-	1.4	-	-	d a t	
	16R-KC					•			•			9.52		0.8		-	-	-		E371
тwх-кс	22R-KC					•					22.0	12.7	4.76	0.0	4.40	-	-	-	60° dd d1	
	220530N-MA									•	15.6	12.7	5.56	3.0	5.6	-	-	-		E385 E386
VCKT-MA																			36° 1 7°	
	11T210N-MA 11T220N-MA									•	8.8		2.87	1.0		-	-	-		E386 E387
VDKT-MA	11122UN-WA										6.7	0.30	2.87	2.0	2.8	-	-	-		E387
																			35°   1   1   5′	
	080316ZDSR-MH				•	• •	• •		• •		-		3.18		3.3	-	-	1.8	-	E300~
	10T320ZDSR-MH				-	• •	• •		• •		-		3.97		4.3	-	-	2.3		E306
WDVT	130520ZDSR-MH 150625ZDSR-MH					_			• •	-	-		5.56 6.35		5.56	_	-	3.1		
WDKT-MH	1300232DSR-WIT										-	15.0	0.33	2.5	5.50			3.4	d 15°	

	Steel	P	0 \$	• •	<b>\$ 0</b>			_	# 1	<b>B</b>					N	/lachir	ning types		
C C	less steel ast iron rrous metal	M K		• •	\$ \$	*		# 3	-	•					• (	Contin	uous cutting		
	alloy, Titanium alloy ened steel	S	<b>•</b>		3 0		Н	3									al cutting pted cutting		
			Cermet			Coated	i		U	Incoated		Dim	ensio	ons (r	nm)				
Inserts	Design	nation	CN2500 CN30	NCM535 NCM545	PC2010 PC2505	PC2510 PC3700	PC9530	PC9540 PC5300	5400	S130A H01	1	d	t	r	d <sub>1</sub>	f	Geometri	es	Available tools
	040304PN	IER-MA	ប៊ីប៊	žž	2 2	2 2 2	2 2	2 2	2 2	<u>5</u> Ξ	4.3	7.0	3.46	0.4	_	-			E120~
	040304FN										4.3	7.0	3.46	0.4	-	-			E125
WNGX-MA	040312PN									•	4.3	7.0	3.46	1.2	-	-	d	+	
new	040316PN 080604PN						-		+	•	4.3 8.2	7.0	3.46 6.4	1.6 0.4	-	-	<u> </u>		
	080608PN									•	8.2	13.0	6.4	0.8	-				
	080612PN										8.2	13.0	6.4	1.2	-	-			
	080616PN 080620PN						-		-		8.2	13.0	6.4	1.6	-		<u></u>		
	000020FI	IFN-IVIA									0.2	13.0	0.4	2.0	-	-			
	040304PN	IER-MI						• •			4.3	7.0	3.46	0.4		_			E120~
	040304FN							•	•		4.3	7.0	3.46	0.4	-	-			E125
WNGX-ML	040312PN							•			4.3	7.0	3.46	1.2	-	-	d	, t .	
new)	040316PN 080604PN						_	•			4.3 8.2	7.0	3.46 6.4	1.6 0.4	-	-			
	080608PN			•		•	)	• •	•		8.2	13.0	6.4	0.4	-				
	080612PN							•			8.2	13.0	6.4	1.2	-	-			
	080616PN							•			8.2	13.0	6.4	1.6	•		, ,	_	
	080620PN	IEK-WL						•			8.2	13.0	6.4	2.0	-	-			
	040304PN	ICD MM						•			4.3	7.0	3.46	0.4		_			E120~
	040304FN							•	-		4.3	7.0	3.46	0.4	-				E125
	040312PN	ISR-MM						•			4.3	7.0	3.46	1.2	•	-			
WNGX-MM	040316PN							•			4.3	7.0	3.46	1.6	-		d		
new	080604PN 080608PN			•		•		•			8.2	13.0	6.4	0.4	-	-			
	080612PN							•			8.2	13.0	6.4	1.2	-				
	080616PN							•			8.2	13.0	6.4	1.6	-	-	r		
	080620PN	ISR-MM						•			8.2	13.0	6.4	2.0	-	-			
	060312ZN							•	•		-	6.35	3.18	1.2	2.86	1.2			E289~
	09T316ZN					•		•	•		-	9.525	3.97	1.6	3.6	1.7	I		E299
WNMX-MF	130520ZN 160720ZN						Н	•			_	12.7	5.56 7.0	2.0	4.7 5.8	2.5 3.0			
new	10072021	114-1011										10.0	7.0		0.0	0.0			d <sub>1</sub>
																	r d	t	
																	ı <del></del>	ı <del>* •</del> 1	
	060312ZN							•	•		-	6.35	3.18	1.2	2.86	1.2			E289~
14/1:12/2	09T316ZN							•	•		-	9.525	3.97	1.6	3.6	1.7	L	_	E299
WNMX-ML	130520ZN 160720ZN							•			-	12.7	5.56 7.0	2.0	4.7 5.8	2.5 3.0			
	10072021	IIV-IVIL										10.0	7.0	2.0	5.0	0.0			dı
																	r		
																	l d	<u>- t -</u>	
	060312ZN	IN-MM			•	• •		•	•		_	6.35	3.18	1.2	2.86	1.2			E289~
	09T316ZN	IN-MM			•	•	•	•	•		-	9.525	3.97	1.6	3.6	1.7	1		E299
WNMX-MM	130520ZN 160720ZN				•	• •	•	• •	•		-	12.7	5.56 7.0	2.0	4.7	2.5			
	100/202N	IIA-IAIIA				•		•			-	16.0	7.0	2.0	5.8	3.0			d1
																	d	t	
	1		1																Ctook itom

	Steel	Р	0 2 0 0 0 2 2 # 2	Machining types
8	Stainless steel	M	3 # 3 #	macriffing types
bje	Cast iron	K		<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	N	# • • •	
š	Heat resistant alloy, Titanium alloy	S	<b>3 *</b>	General cutting
	Hardened steel	H	3 #	# Interrupted cutting

Hardene	ed steel H					;	<b>\$</b> #										<b>ac</b> int	erru	ptea cutting	
		Cermet			Coa	ated			Unco	oated		-	Dime	ensi	ons	(mn	n)			
Inserts	Designation		NC5330 NCM535	NCM545 PC3700			PC5300 PC5400	PD1010 PD2000	ST30A G10	H01 H05	ı	12	l <sub>1</sub>	d	t	r	d <sub>1</sub>	а	Geometries	Available tools
	310404ER-KC			•					• •		30.9	-	-	9.525	4.5	0.4	4.4	-		E370
XCET-KC																			5 d d d d 7 7 °	
	190504PEFR-MA									• •	22	-	-	11.3	5.04	0.4	4.5	-		E399
	190508PEFR-MA									• •	22	-	-		5.00			-		E400
XDET-MA	190512PEFR-MA									0 0	22	-	-		5.00			-	<u>r</u>	
new	190516PEFR-MA 190520PEFR-MA						-	_			22	_	-		4.99 4.97		4.5	-		
	190520PEFR-MA									• •	22	-	-		4.95		4.5	-	d + d1	
	190530PEFR-MA									• •	22	-	-		4.93		4.5	-		
	190532PEFR-MA									• •	22	-	-		4.92		4.5	-	t   -   t   -	
	190540PEFR-MA									• •	21	-	-	11.3	4.85	4.0	4.5	-		
	190550PEFR-MA									• •	21	-	-	11.3	4.81	5.0	4.5	-		
	19M504FR-MA							• •		• •	18		1.4	-	5	0.4		-		E388~
	19M508FR-MA							• •		• •	18	16.4		-	5	0.8	_	-		E393
	19M512FR-MA 19M516FR-MA							•		• •	17.5	16.4	0.6	-	5	1.2		÷		
	19M518FR-MA							_			17.5		0.5	_	5	1.8		_		
	19M520FR-MA							• •		• •	17.5			-	5	2.0		-		
	19M530FR-MA							•		• •	17		0.7	-	5	3.0		-		
XEKT-MA	19M532FR-MA							• •		• •	17	16.4	0.5	-	5	3.2	4.4	-	<u> </u>	
1	19M540FR-MA							• •		• •	16.5	16.4	0.5	-	5	4.0	4.4	-		
	19M550FR-MA							• •		• •	16	16.4		-	5	5.0		-	di di	
	250604FR-MA									• •	24.5			-	6.35			-	120°	
	250608FR-MA 250612FR-MA										24.5			-	6.35	1.2		-		
	250612FR-MA											21.9		÷		1.6		-		
	250620FR-MA									• •	24	21.9		_		2.0		-		
	250630FR-MA										23.7			-	6.35			-		
	250632FR-MA									• •	23.7	21.9	0.4	-	6.35	3.2	6.0	-		
	250640FR-MA										22.8	21.9	1.2	-	6.35	4.0	6.0	-		
	250650FR-MA									• •	22.7	21.9	0.4	-	6.35	5.0	6.0	-		
	19M504ER-ML										18	16.4	1.4	_	5	0.4	4.4	-		E388~
	19M508ER-ML										18	16.4	1.0	-	5	0.8	4.4	-		E393
	19M512ER-ML										18	16.4	0.6	-	5	1.2	4.4	-		
	19M516ER-ML										_			-			4.4	-		
	19M518ER-ML						_				_	16.4		-	5			-		
	19M520ER-ML 19M530ER-ML											16.4		-			4.4	-		
XEKT-ML	19M530ER-ME							_			_	16.4		÷	5		4.4	-		
new	19M540ER-ML										_	16.4		-	5		4.4	-		
	19M550ER-ML										_	16.4		-	5		4.4	-		
10	250604ER-ML										24.5	21.9	1.5	-	6.35	0.4	6.0	-	11 200	
	250608ER-ML										_	21.9		-			6.0	-	12 / t /	
	250612ER-ML										_	21.9		-			6.0	-	·	
	250616ER-ML 250620ER-ML						_			_	_	21.9		-			6.0	_		
	250620ER-ML 250630ER-ML							-		H	_	21.9		-			6.0	÷	-	
	250630ER-ML										_	21.9		÷			6.0	-	-	
	250640ER-ML									T	_	21.9		-			6.0	-		
	250650ER-ML										_	21.9		-			6.0	-		
XNCT-MA	080504PNFR-MA									•	8.2	-	-	10.0	5.5	0.4	4.5	2.9	d	E100
AITOI-MA	080508PNFR-MA									•	8.2		-				4.5			E101
Tev	080512PNFR-MA									•	8.2		-				4.5		di la	E103
	080520PNFR-MA 120608PNFR-MA									•	8.2		-				4.5			E104
	120000PINFK-IVIA									•	12.0	-	-	13.0	0.5	0.8	5.5	ა.5	a r t	
																			+ 1   + 1	

	Steel		Р		0 3		•	•	•	<b>\$</b>			1	<b>B</b> #	3		Machining types
9	Stainless steel		M								;	8	# 1	#	:		wacrining types
- je	Cast iron	<b>—</b>	K			3	•	•	3	3			1	#	:	•	● Continuous cutting
۲	Non-ferrous metal		N													•	
ĕ	Heat resistant alloy, Titanium allo	у 🤇	S									П	1	#	:		● General cutting
	Hardened steel		Н						•	3		П	1	#	:		# Interrupted cutting
				- 1	۸					0	1				Here		Dimensions (mm)

	alloy, Titanium alloy  ned steel  H	•		•	<b>3</b>		3 H								ral cutting upted cutting	
		Cermet			Coated	1		Uncoated		Dim	ensi	ons (r	mm)			
Inserts	Designation	CN2500 CN30	NC5330 NCM535 NCM545 PC2505 PC2510 PC3700 PC6510		PC9530	PC9540 PC5300 PC5400	ST30A H01	ı	d	t r		d <sub>1</sub>	а	Geometries	Available tools	
	060405PNER-ML				• • •		• • •		5.7	6.5	4.0	0.5	3.4	1.8		E99~
	060408PNER-ML				•		• •		5.7	6.5	4.0	0.8	3.4	1.8		E104
	080504PNER-ML						• •		8.2	10.0	5.5	0.4	4.5	2.9	-	
	080508PNER-ML 080512PNER-ML		•		• • •	_	• • •		8.2 8.2	10.0	5.5 5.5	1.2	4.5 4.5	2.9	_	
3731177 111	080516PNER-ML					_	• •		8.2	10.0	5.5	1.6	4.5	2.9	-   - d	
XNKT-ML	080520PNER-ML						• •		8.2	10.0	5.5	2.0	4.5	2.9		
new	120608PNER-ML				• •	)	• • •		12.0	13.0	6.5	0.8	5.5	3.5		11
	120612PNER-ML						• •		12.0	13.0	6.5	1.2	5.5	3.5		
	120616PNER-ML						• •		12.0	13.0	6.5	1.6	5.5	3.5		
	120620PNER-ML						• •		12.0	13.0	6.5	2.0	5.5	3.5		
	060405PNSR-MM			•	• • •	)	• • •		5.7	6.5	4.0	0.5	3.4	1.8		E99~
	060408PNSR-MM			•	• • •		• •		5.7	6.5	4.0	0.8	3.4	1.8		E104
	080504PNSR-MM				•		• •		8.2	10.0	5.5	0.4	4.5	2.9	_	
	080508PNSR-MM 080512PNSR-MM		•	•	• • •	_	• • •		8.2 8.2	10.0	5.5 5.5	0.8	4.5	2.9		
	080516PNSR-MM						• •		8.2	10.0	5.5	1.2	4.5	2.9		
XNKT-MM	080520PNSR-MM			•	•	_	• •		8.2	10.0	5.5	2.0	4.5	2.9	d	
new	120604PNSR-MM						• •		12.0	13.0	6.5	0.4	5.5	3.5		
	120608PNSR-MM			•	• • •		• •		12.0	13.0	6.5	0.8	5.5	3.5		i <sub>1</sub>
	120612PNSR-MM			•	•		• •		12.0	13.0	6.5	1.2	5.5	3.5		
	120616PNSR-MM			•	•		• •		12.0	13.0	6.5	1.6	5.5	3.5	a r t	
	120620PNSR-MM 0606XNR-ML		•		•	•	• • •		6.7	13.0	6.5	0.8	5.5 4.6	1.0		E142
XNMX-ML															d t	
	060608-ML		•		•		• • •		6.7	14.0	6.0	0.8	4.6	-		E142
XNMX-ML															d d	
	0802ER-MM						•		10.5	7.25	3.18	0.8				E339
	1003ER-MM				•		•		10.5	7.25	3.18	0.8	-	-	1	E340
	13T3ER-MM						•		13.1	9	3.97	0.8	-	-	1	
V	1604ER-MM						•		16.5	11.5	4.76	0.8	-	-		
ХРМТ-ММ	1805ER-MM						•		18	12.4	5.56	0.8	-	-		
101	2006ER-MM						•		20.5	14.1	6.35	0.8	-	-		1
100	2507ER-MM						•		25.5	17.6	7.94	0.8	-	-		

	Steel		Р		1			•	•			1	# #	3	;	Machining types
8	Stainless steel	<	M								3 1	# 1	# #	;		waciiiiiig types
bje	Cast iron	4	K			3		3		•		1	#	;		<ul> <li>Continuous cutting</li> </ul>
ž	Non-ferrous metal	4	N	N												9
ĕ	Heat resistant alloy, Titanium alloy	4	S									1	#	;		<b>S</b> General cutting
	Hardened steel	4	Н					•				1	#	;		Interrupted cutting

	ned steel				<b>U</b> (				<b>3</b> #						, ,		l	
		Cermet									oated		Dimer	nsions	(mm)			Augilahla
Inserts	Designation	CN2500 CN30	NC5330 NCM535	NCM545	PC2505	PC3700	PC6510 PC9530	PC9540	PC5300 PC5400	ST30A	H01	ı	d	t	r	<b>d</b> 1	Geometries	Available tools
ZDMT D MM	080310R-MM					•			•			8.4	6.73	3.2	10	2.8		E339
ZDMT-R-MM	110312.5R-MM 130416R-MM					•			•			10.6	8.5 10.5	3.65 4.76	12.5 16	2.8		E340
	1304 TON-IVIIVI											13.2	10.5	4.70	10	4.4	114	c
	080M-MM											16	8.0	3.5	8	2.9		E332~
	090M-MM											17.7	7.2	4.3	9	3.4		E334
ZPET-MM	100M-MM				_	•			•			19	10.4	4.5	10	3.4		
2P L 1-WW	110M-MM 125M-MM				_	•			•			22.2	11.4	4.8 5.3	11 12.5	4.5	_	
	130M-MM											25.7	13.4	5.3	13	4.5		
	140M-MM											27.2	14.3	6.3	14	5.6		
Internal	150M-MM					•			•			28	15.4	7	15	5.6		
	160M-MM					•			•			28.5	16.4	7	16	5.6		
	200M-MM					•						38	20.7	8	20	6.6		
	250M-MM											48	25.9	9.5	25	8.6		
	080S-MM 090S-MM											15 15.5	6.6 7.4	3.1	9	2.9	d the Id-	1
	100S-MM				-	•	_		•			15.5	8.4	3.8	10	3.4	111	
	110S-MM											18.1	9	4.4	11	4.5	-  -    - t-	
ZPET-MM	125S-MM					•			•			20.5	10.7	4.5	12.5	4.5		
ZPL I-WW	130S-MM											22.2	11	4.4	13	4.5		
	140S-MM											24.1	11.2	5.7	14	5.6		
	150S-MM					•			•			25	12.4	6.5	15	5.6		
External	160S-MM					•			•			26	13.4	6.5	16	5.6		
	200S-MM 250S-MM				_	•						32 40	16.7	7 8.5	20 25	6.6 8.6		
	1504PPSR-MM					•			•			15.9	12.7	4.76	-	5.6		E307
<b>ZPMT-MM</b>	1505PPSR-MMN											15.9	12.7	5.76	-	5.6	d d	E352
	160520R-MM					•			•			16.1	12.7	5.56	20	5.6		E336
	160525R-MM 160531.5R-MM				-	•			•			16.9 17.6	12.7	5.56 5.56	25 31.5	5.6 5.6		
ZPMT-R-MM												17.0	12.7	5.56	31.5	5.0	d d	
	160525R-MR											17.6	12.7	5.56	25	5.6		E335
ZPMT-R-MR																		E336

#### **E** KORLOY Cutters

									olicat			
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		ADN(M) 4000/5000 <sup>+</sup>		45°	Ø80~Ø315	Excellent cutting-edge strength and chip flow	•					E47 E48
		AE(M) 4000/5000		45°	Ø80~Ø315	Low cutting load and good machinability	•					E49 E50
		EF(M) 4000	Al	75°	Ø80~Ø315	High rake angle to prevents welding	•					E51
	Mill-max	EN(M) 4000		75°	Ø80~Ø315	Economical because double sided inserts applied	•					E52
		EPN(M) 4000/5000 <sup>+</sup>		75°	Ø80~Ø315	Double posi rake angle and low cutting force	•					E53 E54
Cutters for face milling		PF(M) 4000	Al	90°	Ø80~Ø315	High rake angle and good machinability	•	•	•			E55
Cutters for		PPN(M) 4000		90°	Ø80~Ø315	Double posi rake angle and low cutting force	•	•	•			E56
	Mill-max Heavy	HDDCM 7000/9000 ©		55°	Ø125~Ø315	Deep roughing availability thanks to highly rigid inserts	•					E58
	Mill o	ADS 4000/5000		45°	Ø50~Ø63	Anti-vibration	•					E59 E60
	Turbo Mill	PES 2000/3000/ 4000	Ser.	90°	Ø20~Ø63	High rake angle, Cutting efficiency	•	•	•			E61
	e Mill	AFO(M)4000			Ø80~Ø125	High rake angle low cutting force						E62
	Double Mill	AFO(M)5000		45°	Ø80~Ø315	Economical (8 corners available)	•					E63

								App	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		PBAC(M)5000		45°	Ø80~Ø315		•					E68
	Power Buster	PBZC(M)5000		- 90°	Ø80~Ø315	Double-sided Insert High depth High feed roughing	•					E69
		PBPCM6000 @		90	Ø80~Ø315		•	•				E70
	Aero Mill Aero	APD(M) A type	A	90°	Ø80~Ø315	Aluminum cutter body suitable for high speed machining, Both cemented carbides and PCD inserts are available, G2.5 balance possible	•					E151
ling	Aero Mill - Plus	APD(M)-PB	AI	90°	Ø80~Ø315	Prevent overload to the spindle bearings through weight reduction of the Al alloy body and enable high-speed processing	•					E152 E153
Cutters for face milling	ero Mill-Mini	MAPDS	A	90°	Ø40~Ø63	Available with small Machining center-Carbide, PCD insert	•					E154
Cri	Aero N	MAPD	A	90°	Ø32~Ø40	Application-Balancing class G2.5	•					E155
		RM8AC(M)4000 RMH8AC(M)4000		45°	Ø50~Ø400	8 corners available Double-sided insert for steel,	•					E126 E127
	Rich Mill	RM8AC(M)5000 RMH8AC(M)5000			Ø80~Ø400	cast iron, stainless steel, aluminum	•					E128 E129
	Rich	RM8EC(M)4000 RMH8EC(M)4000		75°	Ø50~Ø400	8 corners available	•					E130 E131
		RM8EC(M)5000 RM8HEC(M)5000	11-11-3	73	Ø80~Ø400	Double-sided insert for steel, cast iron	•					E132 E133

# **E** KORLOY Cutters

									olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		RM8QC(M)4000 RMH8QC(M)4000	11 18-5	88°	Ø63~Ø200	8 corners available Reduced cutting interruption at cast Iron	•					E134 E135
		RMT8A(M) 4000/5000		45°	Ø80~Ø315		•					E136 E137
		RMT8E(M) 4000/5000	9	75°	Ø80~Ø315	Easy insert change and good machinability due to latch clamping system 8 corners available Excellent surface finish	•					E138 E139
illing		RMT8Q(M) 4000		88°	Ø80~Ø315		•					E140
Cutters for face milling	Rich Mill	RMX8AC(M)- SA14 <sup>©</sup>		45°	Ø50~Ø125	Double sided insert with 8 corners Stable cutting performance due to double reversal positive relief surface Good machinability in stainless cutting with High helix cutting edge	•					E141
		RM14XCM- XN06 ©		51°	Ø50~Ø160	Double sided insert with 14 corners Suitable for automobile components machining	•					E142
		RM16AC(M) 6000/8000		45°	Ø63~Ø400	16 corners available Wiper inserts can be applied for good surface finish Strong insert and powerful clamping	•					E143 E144
		RMRC(M)-RN12		-	Ø50~Ø125	High cost efficiency due to double sided round typed cutting edge Excellent rotating prevention by strong clamping system Suitable for Inconel cutting	•					E145
		RM3PC(M)3000	iew)		Ø40~Ø80							E99
spic		RM3PC(M)4000		90°	Ø40~Ø125	Perfect perpendicularity Strong clamping	•	•	•		•	E100
ers for m	Cutters for molds	RM3PC(M)5000	iew)		Ø80~Ø125							E101
Cutt		RM4PC(M)3000		90°	Ø40~Ø100	4 corners available High rake angle insert						E105
		RM4PC(M)4000	THE STATE OF THE S	30	Ø50~Ø160	reduces cutting force. Excellent insert rigidity			•		•	E106

								Apı	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		RM4ZCM3000		90°	Ø40~Ø52	4 corners available In vertical machining, the maximum cutting depth for		•	•		•	E118
	Rich Mill	RM4ZC(M)4000			Ø63~Ø100	RM4Z3000: 9.00 mm, RM4Z4000: 14.0 mm						
	Rich	RM6PCM-WN04	new)	90°	Ø40~Ø63	Improved productivity and high-quality shouldering	•	•	•		•	E120
		RM6PC(M)-WN08	new)		Ø50~Ø125	through high speed and high feed machining						E121
	Alpha Mill-X	AMXCM- AD10/12/17		90°	Ø40~Ø125	High rake angle cutting edge and chip breaker reduce cutting load and improve chip evacuation. High rigidity due to special design	•	•	•	•	•	E197 E198
splou		AMC(M) 1000S/1500S/ 2000S		90°	Ø32~Ø100	3-dimensional shape and high	•	•	•	•	•	E164~ E166
Cutters for molds	Alpha Mill	AMC(M) 3000S/3000S-K /4000S	A RES	90°	Ø40~Ø200	rake angle lowers cutting load and ensures better chip evacuation Inner coolant system for better chip control increases	•	•	•	•	•	E167~ E169
	Alpha	AMC(M) 1000SE 2000SE 3000SE		75°	Ø40~Ø100	tool life Wide size range of inserts enlarges application range. Various types of Alpha Mills available for high depth of cut	•					E170 E171
		AMC(M) 2000M 3000M 4000M		90°	Ø50~Ø125	and high feed machining	•	•	•	•	•	E172~ E174
		FMAC(M)3000		45°	Ø50~Ø125	Accurate inserts and cutter,	•					E226
	Future Mill	FMAC(M)4000		70	Ø50~Ø200	Excellent chip flow						E227
	Futur	FMAC(M)3000-A		45°	Ø63~Ø125	Excellent in high speed cutting and tapping center,	•					E228
		FMAC(M)4000-A		73	Ø63~Ø315	low power machine due to light aluminum body						E229

# **E** KORLOY Cutters

								App	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		FMPC(M)3000	800	90°	Ø50~Ø100	4 corners available various inserts can be applied to						E222
		FMPC(M)4000		90	Ø63~Ø125	machine for different types of workpiece						E223
		FMPC(M)3000A		200	Ø63~Ø100	Excellent in high speed cutting and tapping center,						E224
	e Mill	FMPC(M)4000A		90°	Ø63~Ø315	low power machine due to light aluminum body	•	•	•			E225
	Future Mill	FMRC(M)3000			Ø40~Ø100							E228
		FMRC(M)4000		-	Ø50~Ø125	4~8 corners available  Double contact faces between insert & seat part of	•	•	•	•		E229
		FMRC(M)5000	<b>6</b>		Ø50~Ø125	cutter for stable clamping Excellent rotating-free machining						E230
		FMRC(M)6000		-	Ø63~Ø160	_ maoning	•	•	•	•	•	E231
splo	Future Mill P-positive	FMRC(M) (12) 3000 4000 5000 6000		-	Ø40~Ø250	Stable clamping system enables stable machining and productivity  Varied product line-up ensures wide application range  Optimal shape and grade with high hardness for hard-to-cut material machining.	•	•	•	•	•	E242~ E245
Cutters for molds	Mill	TPMCM-TN16		200	Ø50~Ø125	3-cornered insert for shouldering						E258
Cutter	Triple Mill	TPMCM-TN20	77.77	90°	Ø63~Ø125	-Reduced cutting resistance due to high rake angled cutting edge and chip breaker			•			E259
	НЕМБ	HFMDCM-LN06	0	-	Ø32~Ø66	Double sided with 4 corners insert for small diameter machining						E272
	뚶	HFMDC(M)-LN10		-	Ø40~Ø100	For high feed and multi- functional machining Strong clamping realizes stable machining.	•	•				E273
	HRM	HRMC(M)13	W. P.	15°	Ø50~Ø80	Powerful clamping by double clamping system						E300
	生	HRMC(M)15	8	13	Ø63~Ø160	3 corners available high feed cutting with low cutting load						E301
		HRMDC(M)09			Ø40~Ø100	Double side in control 11 0						E289
	HRMD	HRMDC(M)13	N. S.	14°	Ø50~Ø125	Double side insert with 6 corner High feed cutting with strong simple screw-on clamp	•	•	•		•	E290
		HRMDC(M)16 @			Ø80~Ø315							E291
	)ro	TP2PC(M)-LN08			Ø40~Ø63	High-quality results available						E311
	Tangen-Pro	TP2PC(M)-LN14	SOURT	90°	Ø40~Ø125	even under harsh cutting conditions, thanks to the stable clamping force	•	•	•			E312
	Tange	TP2PC(M)-LN17	9		Ø40~Ø125	, •						E313



										olicat	ion		
Туре	Cut	tter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
			BT30/40/50										E342~ E346
			HSK63	3	90°	Ø10~Ø50	BT/HSK one solid type has been accepted to increase the precision	•	•	•		•	E353~ E357
			BT30/40/50		90°	Ø16~Ø100	Inner coolant system can also make it possible to evacuate the chip effectively						E347~ E351
splo	G. C.	System	HSK63/100	1	30	210-2100	High feed and high depth						E358~ E362
Cutters for molds	UCK Tooling	BI/NSA 10011119 System	BT30/40/50- MAT		- 90°	Ø12~Ø40	Alpha Mill, Rich Mill, FMR, Laser Mill, HRM(D), Pro-A,						E403
	)±0	<u> </u>	HSK63/100- MAT	The same		512-540	Pro-X Modular head M06~M16 applicable						E404
		BT50 HAT4000		90°	Ø50~Ø80	Head only replacement possible and higher efficiency by self assembly head	•	•	•			E352	
	Pro-A Mill	Pro-A MIII	PAC(M) 2000/4000	Al	90°	Ø40~Ø100	Buffed insert controls chip flow without built-up edge	•	•	•	•	•	E385
m <sub>m</sub>	III V		PAXC(M)5000	A	000	Ø40~Ø125	Powerful clamping Excellent body rigidity for						E388
rs for aluminum	USA V MIII	-014 -014	PAXC(M)6000		90°	Ø50~Ø125	rectangular and curve machining		•	•	•		E389
Cutters fo	IIIM I O'G	Pro-L MIII	PALC(M)	Al	90°	Ø63	High helix and high depth of cut High perpendicularity Low cutting load	•	•	•	•	•	E394
	DVO V Mill	A-O-A	PAVCM-XD19	Al	90°	Ø40~Ø125	Exclusive milling tool for high speed aluminum machining with key to key way structure ensures stable clamping.	•	•	•	•	•	E399
		e cutter	TAFCP		-	Ø100~Ø315			•	•			E407
side cutter	tial type	Full-side cutter	TAFCB		-	Ø100~Ø315	Various cutting depth can be possible because of adjustable length control.	•	•	•			E407
Indexable side cutter	Tangential type	Half-side cutter	ТАНСР		-	Ø100~Ø315	Medium to Roughing based on strengthened edge		•	•			E408
	<u> </u>	Half-sid	ТАНСВ		-	Ø100~Ø315		•	•	•			E408

# **E** KORLOY Cutters

									App	olicat	ion		
Туре	Cu	tter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		Full-side cutter	RAFCP		-	Ø100~Ø315			•	•			E409
Indexable side cutter	Radial type	Full-sid	RAFCB		-	Ø100~Ø315	Wide range of machining width with only one side cutter due to adjustable cutting-edge height	•	•	•			E409
Indexable	Radia	e cutter	RAHCP		-	Ø100~Ø315	Suitable for medium and finishing in narrow width side cutting due to good chip evacuation by 3-dimensional chip breaker		•	•			E410
		Half-side cutter	RAHCB		-	Ø100~Ø315		•	•	•			E410
	cutter	SPP(M)	(0)	-	Ø80~Ø200	Economical by using pentagonal insert Suitable for narrow & deep grooving			•			E411	
		-uii-side cutter	SPB(M)		-	Ø80~Ø200	Economical by using pentagonal insert Suitable for narrow & deep grooving			•			E412
		-	SPS		-	Ø50~Ø200	For narrow and deep width grooving			•			E413
	1	Full-side cutter	RM4PFCB		-	Ø80~Ø160	4 corner usage with double-sided insert can be			•			E107 E108
Side cutters		FUII-SIQ	RM4PFCP	P	-	Ø80~Ø160	economical			•			E111 E112
		e cutter	RM4PHCB		-	Ø80~Ø160	4 corner usage with			•			E109 E110
	Lie Mell	Hair-side cutter	RM4PHCP		-	Ø80~Ø160	double-sided insert can be economical			•			E113 E114
			WFSB(M)	O	-	Ø100~Ø250	The nose R shape of insert ensures long tool life.	•	•	•			E416
	7.344	WING IVIII	WFSP(M)		-	Ø100~Ø250	Wide applications with various widths and corner R sizes.		•	•			E417

								App	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
Cutters for face milling	Turbo Mill	ADS 4000/5000	Or and the second	45°	Ø50~Ø63	Uneven insert spacing prevents chattering	•					E59 E60
Cutters for	Turb	PES 2000/3000/4000	and the same	90°	Ø20~Ø63	Good machinability due to the high rake angle	•	•	•			E61
		RM3PS3000		90°	Ø20~Ø40	Perfect perpendicularity						E102
		RM3PS4000 @		90	Ø32~Ø63	Strong clamping						E103
		RM4PS3000		90°	Ø14~Ø50	4 corners available High rake angle insert	•	•	•		•	E115
		RM4PS4000 @	1	30	Ø32~Ø63	reduces cutting force Excellent insert rigidity	•	•	•		•	E116
	Rich Mill	RM4ZS3000		90°	Ø25~Ø40	In vertical machining, the maximum cutting width: 9.0 mm	•	•	•		•	E119
		RM6PS-WN04		90°	Ø20~Ø32	Improved productivity and high-quality shouldering						E122
g		RM6PS-WN08		90	Ø32~Ø50	through high speed and high feed machining						E123
Cutters for molds		RMRS-RN12 🚥		-	Ø32~Ø63	High cost efficiency due to double sided round typed cutting edge Excellent rotating prevention by strong clamping system Suitable for Inconel cutting	•					E146
	Alpha Mill-X	AMXS- AD10/12/17 @	No.	90°	Ø20~Ø40	High rake angle cutting edge and chip breaker reduce cutting resistance and improve chip evacuation. High rigidity due to special design	•	•	•	•	•	E199 E200
		AMS 1000S/1500S 2000S/3000S 3000S-K/4000S	Nie of	90°	Ø10~Ø63	The combination of a 3-dimensional curve design	•	•	•	•	•	E175~ E182
	Alpha Mill	AMS 1000SE/2000SE 3000SE		75°	Ø25~Ø63	& high rake angle helps chip-evacuation effectively with a low cutting force Inner coolant system	•					E183 E184
	Alph	AMS 1000M/1500M 2000M/4000M	13.5	90°	Ø16~Ø50	The various range of inserts can provide the widened choice  High depth and high feed	•	•	•	•	•	E185~ E187
		AMS 1000MH/1500MH 2000MH/3000MH(-K)	-	90°	Ø14~Ø40	can be available during operation	•	•	•	•	•	E188 E189

# E KORLOY Shanks


								App	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
		FMAS3000		450	Ø25~Ø63	For precision machining						E220
		FMAS4000		45°	Ø50~Ø63	Excellent chip evacuation	•					E221
	W W	FMPS3000		90°	Ø25~Ø63	4 corners available						E226
	Future Mill	FMPS4000	Was a series	90*	Ø40~Ø63	Strong cutting-edge with low cutting load	•					E227
		FMRS 1000/1500/2000 2500/3000/4000 5000/6000		-	Ø8~Ø63	2 touch clamping system, convenient insert change	•	•	•	•	•	E232~ E237
	Future Mill P-positive	FMRS (2500/3000 4000/5000 6000		-	Ø17~Ø50	P-positive relief angle ensures high rigidity and high machinability in die steel and high-resistant alloy machining Flat clearance face of insert prevents interference and revolution while machining	•	•	•	•	•	E246~ E249
	Miii	TPMS-TN11			Ø25~Ø40	3-cornered insert for shouldering						E260
	Triple Mill	TPMS-TN16		90°	Ø32~Ø40	Reduced cutting resistance due to high rake angled cutting edge and chip breaker	•	•	•			E261
		HFMDS-LN04			Ø8~Ø21	Double sided insert with 4 corners for small diameter						E267 E268
splou	HFMD	HFMDS-LN06		-	Ø16~Ø40	machining  For high feed and multi- functional machining	•	•	•	•	•	E269 E270
Cutters for molds		HFMDS-LN10			Ø25~Ø42	Strong clamping system for stable machining						E271
Cutter	HFM	HFMS @ 1000		13°	Ø8~Ø21	Apply helix cutting-edge on insert, low cutting load and reinforce toughness on corner Increased rigidity with double relief angle (11, 13), prevent interference with high feed To apply the negative axial rake angle when set up the holder, increased chipping resistance	•	•	•	•	•	E281 E282
	HRM	HRMS 08/10/13/15		15°	Ø20~Ø63	Powerful clamping by double clamping system 3 corners available High feed cutting with low cutting load	•	•	•	•	•	E302~ E304
	HRMD	HRMDS 06/09/13		14°	Ø16~Ø63	6 corners available, High feed, multi-function, only one screw application	•	•	•	•	•	E292~ E296
	orc.	TP2PS-LN08			Ø16~Ø25	High-quality results available						E311
	Tangen-Pro	TP2PS-LN14		90°	Ø25~Ø50	even under harsh cutting conditions, thanks to the	•	•	•			E312
	Tal	TP2PS-LN17			Ø32~Ø50	stable clamping force						E313
	Tank Mill	THE	and the same of th	90°	Ø25~Ø50	Right-hand helix angle employed for good chip evacuation. Special surface treatment prevents body breaking and improves rigidity. Strong cutting-edge	•	•				E307

								App	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
	Laser Mill	LBE		-	Ø8~Ø32	Indexable ball endmill for precise mold. Rigid holder with simple design finishing MQL is available	•	•	•	•		E326~ E330
	Lase	LBE□□-C LRE□□-C		-	Ø8~Ø32	Indexable ball endmill for precise mold. Rigid holder with simple design finishing MQL is available Carbide shank	•	•	•			E326~ E330
		BFE		-	Ø16~Ø32	Upgraded cutting performance with S type curve design V clamping application	•	•	•	•		E331
	Mach Mill	GBE	82	-	Ø16~Ø50	Helical design of edge can reduce the force during operation. Safe application to prevent rotation guarantee the increased tool life	•	•	•	•		E332 E333
		BRE	100	-	Ø20~Ø63	Flute type chip-pocket can make chip-evacuation Customized edge design can prevent the breakage of holder's body	•	•	•	•		E335
splom	HAVE	Multi-edge	No.	- 90°	Ø16~Ø50	Tools for Z-axis feed plunge machining to cut faster and more effectively in vertical machining	•	•	•		•	E339
Cutters for molds	Ĩ	Single-edge	E. Carlotte			Machining with whole diameter						E340
	O-ring Cutter	ORC	6	90°	Ø11~Ø46	For grooving the seat of an O-Ring in a plastic mold Superior surface roughness and cutting performance compared to HSS and brazed tool	-	-	-	-	-	E365
				75°	Ø25~Ø30							
			100	60°	Ø25~Ø35	For Back & Front high quality chamfering and various						<b>5000</b>
			30	45°	Ø7~Ø39	Chamfering angle machining	•					E369
	<u> </u>			30°	Ø25~Ø42							
	Chamfer Tool	CE		30°	Ø5~Ø35	Various chamfer degrees						
	້ວ		Ser.	45°	Ø5~Ø48	available Effective long chamfer	•	•	•			E370
				60°	Ø5~Ø57	cutting available						
				45°	~Ø28	Centering, Grooving, Chamfering	•	•	•		•	E371


# **E** KORLOY Shanks

								App	olicat	ion		
Туре	Cutter	Designation	Shape	A.A	Diameter range	Features	Facing	Shouldering	Slotting	Copying	Ramping, Helical	Page
				30°								
		ССТ		45°	Ø3~Ø16	Centering, Countersinking, Chamfering						E373
Ø	er Tool			60°								
ır mold	Chamfer Tool			30°								
Cutters for molds		CET		45°	Ø4~Ø16	Countersinking, Chamfering, Shouldering	•	•	•		•	E372
3				60°								
	T-Cutter	TFE		90°	Ø21~Ø50	For slotting	•	•	•	•	•	E374
	Pro-A Mill	PAS 2000/4000	600	90°	Ø12~Ø42 Ø32~Ø40	Polished face increases chip flow and reduces built-up edge	•	•	•	•	•	E386
	Pro-X Mill	PAXS 5000/6000		90°	Ø20~Ø40 Ø25~Ø40	Square shoulder and corner machining	•	•	•	•	•	E390 E391
w <sub>n</sub>		PALS-HR (Single-edge)		- 00°	Ø32~Ø63	High helix and high depth of cut	•	•	•	•	•	E395 E396
Cutters for aluminum	Pro-L	PALS-HM (Multi-edge)		90°	Ø63	High perpendicularity Low cutting load	•	•	•	•	•	E397
Cut	Pro-XL Mill	PXLS ®		90°	Ø40~Ø80	Improved surface finish and perpendicularity achieved by a single pass with the deep cutting-edges	•	•				E398
	/ Mill	PAVS-XD19 @	i at	- 90°	Ø25~Ø40	Exclusive milling tool for high speed aluminum machining with key to key way structure	•	•	•	•	•	E400
	Pro-	HSK-XD19 @		30	Ø32~Ø50	ensures stable machining.	•	•	•	•	•	E363
Thread milling		тм	The Park	-	Ø32~Ø50	For internal and external threading	•					D49







# **E** KORLOY Modular Adaptors





# **ADN(M)4000**















• AR: 15° • RR: -4°

(mm)

Des	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
ADN	4080R/L	4	80	57	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	6	1.9	1
(ADNM)	4100R/L	5	100	67	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	6	2.5	2
	4125R/L	6	125	87	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	6	4.3	2
	4160R/L	8	160	107	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	6	6.4	2
	4200R/L	10	200	130	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	8.7	3
	4250R/L	12	250	180	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	14.0	3
	4315R/L	14	315	240	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	21.0	4

( )Metric size

### Available inserts

S	DCN	SDKN	-MU	SDKN-SU	SE	KR-MX	
				•			)
			Cermet	Coated		Uncoated	

		Cer	met					Cc	at	ed					Un	coa	ted	
ı	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
SDCN	42M															•		
	42M-G																•	
	42MT		•			•									•			
	42MT-RH																	
	42MT-S20										•							E19
	1203AEEN																	
	1203AEEN-RH																	
	1203AESN																	
	1203AESN-RH																	
SDKN	1203AESN-MU								•									E20
	1203AESN-SU								•				•	•				E20
SDKR	1203AESN-MX																	
	1203AETN-MX																	E20
	1203AEN-MX				•													

### Available arbors


Dooig	nation	General arbor	NC arbors	
Desig	паноп	General arbor	ADN	ADNM
ADN	4080R/L	NT*□□ (M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27
(ADNM)	4100R/L	NT* (M/U)-FMA31.75-	BT**□□-FMA31.75-□□	FMC32
	4125R/L	NT* (M/U)-FMA38.1-	BT** - FMA38.1	FMB40
	4160R/L	NT* (M/U)-FMA50.8-	BT** - FMA50.8	FMB40
	4200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	4250R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	4315R/L	KCP-8*** (Center ring plug)		

\* -NT number \*\* -BT number \*\*\*Over milling 5

### Recommended cutting condition

Workniego	Cutting of	ondition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
	190~320	0.05~0.20	NCM325
P	161~270	0.05~0.20	PC3700
	80~140	0.05~0.20	ST30A
M	90~150	0.05~0.20	PC9530
K	140~230	0.05~0.30	PC6510
P.	50~90	0.05~0.30	G10
	00 00	0.00 0.00	410

Assembling




Specification					
	Locator	Wedge	Wedge screw	Locator screw	Wrench
Ø80~Ø315	LADN4R/L	WEPN4R/L	DHA0821F	LTX0514	HW40


Available inserts E19, E20


Available arbors and bolt E426∼E428


# ADN(M)5000+















(mm)

Des	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
ADN	5080R/L+	4	80	107	65	25.4(27)	9.5 (12.4)	6 (7)	25 (22)	63	8	2.4	1
(ADNM)	5100R/L+	5	100	126	75	31.75(32)	12.7 (14.4)	8 (8)	32 (28)	63	8	3.0	2
	5125R/L+	6	125	150	100	38.1(40)	15.9 (16.4)	10 (9)	38 (30)	63	8	4.7	2
	5160R/L+	8	160	185	120	50.8(40)	19.0 (16.4)	11 (9)	38 (30)	63	8	6.5	2
	5200R/L+	10	200	225	140	47.625(60)	25.4 (25.7)	14 (14)	38 (38)	63	8	8.7	3
	5250R/L+	12	250	275	220	47.625(60)	25.4 (25.7)	14 (14)	38 (38)	63	8	15.5	3
	5315R/L+	14	315	340	280	47.625(60)	25.4 (25.7)	14 (14)	38 (38)	63	8	23.7	4

( )Metric size

### Available inserts

SDCN	SDKN-MU	SDKN-SU	SDKR-MX	
		•		

															_			
		Cer	met				(	Co	at	ed					Un	coa	ted	
I	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	면	page
SDCN	53M															•		
	53M-G																•	
	53MT		•		•										•			
	53MT-RH																	
	53MT-S20										•							E19
	1504AEEN																	
	1504AEEN-RH									•			•					
	1504AESN																	
	1504AESN-RH									•								
SDKN	1504AESN-MU								•									F00
	1504AESN-SU								•				•	•				E20
SDKR	1504AESN-MX					•												
	1504AETN-MX																	E20
	1504AEN-MX				•													

### Available arbors


Doois	unation	General arbor	NC arbors	
Desig	gnation	General arbor	ADN	ADNM
ADN	5080R/L+	NT*□□ (M/U)-FMA25.4-25	BT**□□ -FMA25.4-□□	FMC27
(ADNM)	5100R/L+	NT*□□ (M/U)-FMA31.75-□□	BT** - FMA31.75-	FMC32
	5125R/L+	NT*□□ (M/U)-FMA38.1-□□	BT**□□-FMA38.1-□□	FMB40
	5160R/L+	NT* (M/U)-FMA50.8-	BT** - FMA50.8	FMB40
	5200R/L+	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	5250R/L+	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	5315R/L+	KCP-8*** (Center ring plug)		

\* -NT number \*\* -BT number \*\*\*Over milling 5

### Recommended cutting condition

Washniaga	Cutting o	ondition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
K	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10

Assembling





Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench	
Ø80~Ø315	LADN5R/L	WHPS5R/L	WHX0817 WHX0813*	LTX0514	HW40	





# **AE(M)4000**















• AR: 20° • RR: -3°

(mm)

De	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
AE	4080R/L	4	80	103	60	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	5.5	1.7	1
(AEM)	4100R/L	5	100	122	80	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	5.5	2.9	2
	4125R/L	6	125	146	100	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	5.5	4.4	2
	4160R/L	8	160	181	120	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	5.5	6.1	2
	4200R/L	10	200	220	130	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	5.5	8.9	3
	4250R/L	12	250	270	180	47.625 (60)	25.4( 25.7)	13.5 (14)	38 (38)	63	5.5	15.7	3
	4315R/L	15	315	335	240	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	5.5	25.1	4

( )Metric size

### Available inserts

SECN	SEKN-SU	SEKR-MX	
	•		

		Cer	met				(	Сс	at	ed					Un	coa	ted	
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
SECN	1203AFFN															•	•	
	1203AFTN	•	•												•			
	1203AFEN																	
	1203AFSN				•	•												E21
	1203AFEN-RH									•			•					
	1203AFSN-RH																	
	1203AFTN-S20										•							
SEKN	1203AFSN-SU								•									E21
SEKR	1203AFSN-MX				•	•					•							E22

### Available arbors


Dooi	gnation	General arbor	NC arbors	
Desi	griation	General arbor	ADN	ADNM
AE	4080R/L	NT*□□ (M/U)-FMA25.4-25	BT**□□ -FMA25.4-□□	FMC27
(AEM)	4100R/L	NT* (M/U)-FMA31.75-	BT**□□-FMA31.75-□□	FMC32
	4125R/L	NT*□□ (M/U)-FMA38.1-□□	BT** - FMA38.1	FMB40
	4160R/L	NT* (M/U)-FMA50.8-	BT** - FMA50.8-	FMB40
	4200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□ -FMA47.625-□□	FMB60
	4250R/L	NT*□□ (M/U)-FMA47.625-25, KCP-8***	BT**□□ -FMA47.625-□□	FMB60
	4315R/L	KCP-8*** (Center ring plug)		

\* $\square$ -NT number \*\* $\square$ -BT number \*\*\*Over milling 5


### Recommended cutting condition

Morkeiges	Cutting of	Grades	
Workpiece	vc (m/min)	fz (mm/t)	Grades
P	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
K	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10

**Assembling** 




Locator         Wedge         Wedge screw         Locator screw         Wrench           Ø80~Ø315         LAE4R/L         WAE4R/L         DHA0821F         LTX0512         HW40








# **AE(M)5000**















(mm)

De	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
AE	5080R/L	4	80	103	60	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	7.5	1.7	1
(AEM)	5100R/L	5	100	122	80	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	7.5	2.9	2
	5125R/L	6	125	146	100	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	7.5	4.4	2
	5160R/L	8	160	181	120	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	7.5	6.1	2
	5200R/L	10	200	220	130	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	7.5	8.9	3
	5250R/L	12	250	270	180	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	7.5	15.7	3
	5315R/L	15	315	335	240	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	7.5	25.1	4

( )Metric size

### Available inserts



		Cer	rmet				(	Co	at	ed					Un	coat	ed	
ı	Designation		CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SECN	1504AFFN															•		
	1504AFTN		•															
	1504AFEN																	
	1504AFSN																	E21
	1504AFEN-RH																	
	1504AFSN-RH									•								
	1504AFTN-S20																	
SEKN	1504AFSN-SU		П						•					•				F01
	1504AFSN-MX				•						•							E21
SEKR	1504AFSN-MX				•						•							E22

### Available arbors


Dooi	anation	General arbor	NC arbors						
Designation		General arbor	AE	AEM					
AE	5080R/L	NT*□□ (M/U)-FMA25.4-25	BT**□□ -FMA25.4-□□	FMC27					
(AEM)	5100R/L	NT* (M/U)-FMA31.75-	BT** - FMA31.75-	FMC32					
	5125R/L	NT*□□ (M/U)-FMA38.1-□□	BT** - FMA38.1	FMB40					
	5160R/L	NT*□□ (M/U)-FMA50.8-□□	BT** - FMA50.8-	FMB40					
	5200R/L	NT*□□ (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60					
	5250R/L	NT*□□ (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60					
	5315R/L	KCP-8*** (Center ring plug)							

\*□□-NT number \*\*□□-BT number \*\*\*Over milling 5

### Recommended cutting condition

Worknings	Cutting c	Cutting condition								
Workpiece	vc (m/min)	fz (mm/t)	Grades							
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A							
M	90~150	0.05~0.20	PC9530							
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10							


Assembling



Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench
Ø80~Ø315	LAE5R/L	WAE5R/L	DHA0821F	LTX0512	HW40

# **EF(M)4000**







75°

• AR: 18° • RR: 11°

(mm)


De	esignation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
EF	4080R/L	4	80	89	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	8.0	1.5	1
(EFM)	4100R/L	5	100	108	70	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	8.0	2.1	2
	4125R/L	6	125	133	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	8.0	3.8	2
	4160R/L	8	160	168	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	8.0	5.5	2
	4200R/L	10	200	208	130	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	8.0	8.2	3
	4250R/L	12	250	257	180	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	8.0	13.4	3
	4315R/L	16	315	322	240	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	8.0	21.2	4

● E22

( )Metric size

### Available inserts

1203EFR




Dooi	gnation	General arbor	NC arbors	
Desi	gnation	General arbor	EF	EFM
EF	4080R/L	NT* (M/U)-FMA25.4-25-	BT** - FMA25.4-	FMC27
(EFM)	4100R/L	NT* (M/U)-FMA31.75-	BT** - FMA31.75-	FMC32
	4125R/L	NT* (M/U)-FMA38.1-	BT** - FMA38.1	FMB40
	4160R/L	NT* (M/U)-FMA50.8-	BT** - FMA50.8-	FMB40
	4200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	4250R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	4315R/L	KCP-8*** (Center ring plug)		

\* - NT number \*\* - BT number \*\*\* Over milling 5

### Recommended cutting condition


Worknings	Cutting of	ondition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
K	75~125	0.05~0.30	H01




### Parts

SFCN


•						
Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench	
Ø80~Ø315	LEF4R/L LEF4R1*/L1*	WEFR/L	DHA0821F	LTX0512	HW40	





### **EN(M)4000**










(mm)

De	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
EN	4080R/L	5	80	87	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	8.5	1.4	1
(ENM)	4100R/L	6	100	107	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	8.5	2.1	2
	4125R/L	8	125	132	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	8.5	3.8	2
	4160R/L	10	160	167	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	8.5	5.7	2
	4200R/L	12	200	207	130	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	8.5	8.4	3
	4250R/L	16	250	257	180	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	8.5	13.8	3
	4315R/L	20	315	322	240	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	8.5	21.6	4

( )Metric size

### Available inserts



### Available arbors


Doois	unation.	General arbor	NC arbors	
Desig	gnation	General arbor	EN	ENM
EF	4080R/L	NT* (M/U)-FMA25.4-25-	BT** - FMA25.4-	FMC27
(EFM)	4100R/L	NT* (M/U)-FMA31.75-	BT** - FMA31.75-	FMC32
	4125R/L	NT*□□ (M/U)-FMA38.1-□□	BT**□□ -FMA38.1-□□	FMB40
	4160R/L	NT*□□ (M/U)-FMA50.8-□□	BT**□□ -FMA50.8-□□	FMB40
	4200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60
	4250R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□ -FMA47.625-□□	FMB60
	4315R/L	KCP-8*** (Center ring plug)		

\* - NT number \*\* - BT number \*\*\*Over milling 5

### Recommended cutting condition

_		•	
Marknings	Cutting of	condition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
K	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10


Assembling




Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench
Ø80~Ø315	LEN4R/L	WENR/L WENR1*/L1*	DHA0830 DHA0825*	LTX0512	HW40



# **EPN(M)4000**







75°

• AR: 7° • RR: 0°

(mm)

De	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
EPN	4080R/L	5	80	86	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	9	1.4	1
(EPNM)	4100R/L	6	100	107	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	9	2.1	2
	4125R/L	8	125	132	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	9	3.8	2
	4160R/L	10	160	166	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	9	5.7	2
	4200R/L	12	200	206	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	9	8.2	3
	4250R/L	16	250	256	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	9	13.5	3
	4315R/L	20	315	321	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	9	21.1	4

( )Metric size

### Available inserts

SPCN	SPKN-SU	SPKN-MU	SPKR-MX	SPEX
	•			

		Cer	met				(	Co	at	ed					Un	coa	ted	
ı	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
SPCN	1203EDR		•		•	•									•	•	•	
	1203EDL														•			
	1203EDR-G																•	
	1203EDER-RH									•			•					E26
	1203EDSR-RH									•								
	1203EDTR-RH																	
	1203EDR-S20										•							
SPKN	1203EDSR-MU								•									
	1203EDSR-SU								•				•	•				E27
	1203EDSL-SU								•									
SPKR	1203EDSR-MX				•	•												E27
	1203EDSL-MX																	E2/
SPEX	1203EDR/L-1																	E26

### Available arbors


Design	notion	General arbor	NC arbors	
Desigi	ilation	General arbor	EPN	<b>EPNM</b>
EPN	4080R/L	NT*□□ (M/U)-FMA25.4-25	BT** - FMA25.4-	FMC27
(EPNM)	4100R/L	NT* (M/U)-FMA31.75-	BT** - FMA31.75-	FMC32
	4125R/L	NT* (M/U)-FMA38.1-	BT** - FMA38.1	FMB40
	4160R/L	NT* (M/U)-FMA50.8-	BT** - FMA50.8-	FMB40
	4200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	4250R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60
	4315R/L	KCP-8*** (Center ring plug)		

\* $\square$ -NT number \*\* $\square$ -BT number \*\*\*Over milling 5

### Recommended cutting condition

Workpiece	Cutting of	condition	Grades
workpiece	vc (m/min)	fz (mm/t)	Grades
P	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
K	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10

Assembling



### Parts


Specification					San Constant of the Constant o	
	Locator	Wedge	Wedge screw	Locator screw	Wrench	
Ø80~Ø315	LEPN4R/L	WEDNAD/I	DHA0821F	LTX0514	HW40	
Ø60~Ø315	LEPN4R1*/L1*	WEPN4R/L	DHA0817F*	L1X0514	MVV40	




Available arbors and bolt E426~E428



# **EPN(M)5000**+









(mm)

Des	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
EPN	5080R/L+	5	80	91	60	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	63	12	1.7	1
(EPNM)	5100R/L+	6	100	110	70	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	63	12	2.5	1
	5125R/L+	8	125	134	90	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	12	3.8	2
	5160R/L+	10	160	169	110	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	12	5.5	2
	5200R/L+	12	200	209	150	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	12	8.0	3
	5250R/L+	16	250	259	230	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	12	14.8	3
	5315R/L+	20	315	324	270	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	12	22.4	4

( )Metric size

### Available inserts

SPCN	SPKN-SU	SPKN-MU	SPKR-MX	SPEX
	•			

		Cer	met					Co	at	ed	l				Un	coa	ted	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
SPCN	150412T																	
	1504EDR		•		•										•	•		
	1504EDSR																	
	1504EDL									•								
	1504EDR-G																•	E26
	1504EDER-RH									•			•					
	1504EDSR-RH									•								
	1504EDTR-RH																	
	1504EDR-S20										•							
SPKN	1504EDSR-MU								•									
	1504EDSR-SU								•				•	•				E27
	1504EDSL-SU								•									
SPKR	1504EDR-MX				•													E27
	1504EDSR-MX																	E2/
SPEX	1504EDR/L-1																	E26

### Available arbors


Doois	gnation	General arbor	NC arbors	
Desi	griation	General arbor	EPN	<b>EPNM</b>
EPN	5080R/L+	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27
(EPNM)	5100R/L+	NT* (M/U)-FMA31.75-	BT**□□-FMA31.75-□□	FMC32
	5125R/L+	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1-□□	FMB40
	5160R/L+	NT* (M/U)-FMA50.8-	BT** - FMA50.8	FMB40
	5200R/L+	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	5250R/L+	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60
	5315R/L+	KCP-8*** (Center ring plug)		

\* -NT number \*\* -BT number \*\*\*Over milling 5

### Recommended cutting condition

Workpiece	Cutting of	condition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10


Assembling



Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench
Ø80~Ø315	LEPN5R/L LEPN5R1*/L1*	WHPS5R/L	WHX0817 WHX0813*	LTX0514	HW40



# **PF(M)4000**







90°

• AR: 15° • RR: 14°

(mm)

De	signation	(i)	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	(kg)	Fig.
PF	4080R/L	4	80	79	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	16	1.2	1
(PFM)	4100R/L	4	100	97	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	16	1.8	2
	4125R/L	7	125	122	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	16	3.1	2
	4160R/L	9	160	158	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	16	5.6	2
	4200R/L	11	200	197	130	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	16	8.8	3
	4250R/L	15	250	247	180	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	16	16	3
	4315R/L	19	315	311	240	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	16	22	4

( )Metric size

### Available inserts



		Cer	met				(	Cc	at	ed					Un	coa	ted	
Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
TFCN	2203PFR																•	F00
	2203PFL																	E28


### Available arbors

Dooi	gnation	General arbor	NC arbors	
Desi	gnation	General arbor	PF	PFM
PF	4080R/L	NT*□□ (M/U)-FMA25.4-25	BT** - FMA25.4-	FMC27
(PFM)	4100R/L	NT*□□ (M/U)-FMA31.75-□□	BT**□□-FMA31.75-□□	FMC32
	4125R/L	NT*□□ (M/U)-FMA38.1-□□	BT** - FMA38.1-	FMB40
	4160R/L	NT*□□ (M/U)-FMA50.8-□□	BT** - FMA50.8-	FMB40
	4200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□ -FMA47.625-□□	FMB60
	4250R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT**□□ -FMA47.625-□□	FMB60
	4315R/L	KCP-8*** (Center ring plug)		

\* -NT number \*\* -BT number \*\*\*Over milling 5


### Recommended cutting condition

Worknings	Cutting of	ondition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10



• • • • • • • • • • • • • • • • • • • •						
Specification					Monor	
	Locator	Wedge	Wedge screw	Locator screw	Wrench	
Ø80~Ø315	LPF4R/L	WPFR/L	DHA0821F	LTX0512	HW40	
Ø80~Ø315	LPF4R1**/L1**	VVFFN/L	DHA0817F*	LIXUSIZ	HVV40	

### PPN(M)4000









•A R : 7° • RR: 0°

(mm)

Des	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
PPN	4080R/L	5	80	79	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	18	1.3	1
(PPNM)	4100R/L	6	100	99	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	18	1.9	2
	4125R/L	8	125	124	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	18	3.5	2
	4160R/L	10	160	158	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	18	5.6	2
	4200R/L	12	200	198	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	18	8.1	3
	4250R/L	16	250	248	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	18	13.3	3
	4315R/L	20	315	313	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	18	21.4	4

( )Metric size

### Available inserts

TPCN	TPKN-SU	TPKN-MU	TPKR-MX
			Marie

		Cei	met							ed						coa		
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
TPCN	2204PDR		•		•										•	•		
	2204PDR-G																•	
	2204PDL														•			
	2204PDSR					•												
	2204PDTR																	E28
	2204PDR-RH																	
	2204PDER-RH									•			•					
	2204PDSR-RH									•								
	2204PDR-S20										•							
TPKN	2204PDSR-MU								•									
	2204PDSR-SU								•				•	•				E29
	2204PDSL-SU								•									
TPKR	2204PDR-MX				•													$\top$
	2204PDSR-MX				•	•												E29
	2204PPR-MX																	

### Available arbors

Doois	nation	General arbor	NC arbors				
Desig	Hauon	General arbor	PPN	PPNM			
PPN	4080R/L	NT*□□ (M/U)-FMA25.4-25	BT**□□ -FMA25.4-□□	FMC27			
(PPNM)	4100R/L	NT* (M/U)-FMA31.75-	BT**□□-FMA31.75-□□	FMC32			
	4125R/L	NT* (M/U)-FMA38.1-	BT** - FMA38.1	FMB40			
	4160R/L	NT* (M/U)-FMA50.8-	BT**□□ -FMA50.8-□□	FMB40			
	4200R/L	NT*□□ (M/U)-FMA47.625-25, KCP-8***	BT**□□ -FMA47.625-□□	FMB60			
	4250R/L	NT*□□ (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60			
	4315R/L	KCP-8*** (Center ring plug)					

\* -NT number \*\* -BT number \*\*\*Over milling 5

### Recommended cutting condition

Marknings	Cutting of	Cutting condition						
Workpiece	vc (m/min)	fz (mm/t)	Grades					
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A					
M	90~150	0.05~0.20	PC9530					
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10					

Assembling

### Parts

Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench
Ø80~Ø315	LPPN4R/L LPPN4R1*/L1*	WPPN4R/L	DHA0821F DHA0817F*	LTX0514	HW40

Milling

even at high feed rates

### **Highly rigid inserts for roughing**

# Mill-max Heavy ••••

- Productivity Cutting time is reduced by the cutting-edge design specialized for rough facing at high depth of cuts
- High rigidity The highly rigid inserts and cutter seams prevent tool breakage in rough facing
- Clamping stability- The wedge-type clamping system, which is easy-to-use and strong, reduces time for replacing inserts, and improves clamping stability

#### Features of insert · Highly rigid inserts Major cutting-edge - Ideally suited for roughing - High rake angle at high depth of cuts · Wide chip pocket area · 2-level flank relief - Improved chip evacuation surface - Reduced cutting loads - Relief angle availability

MAX. ap

SCKN22: 10.5 mm

SCKN28: 14.5 mm

### · Minor cutting-edge

- Improved surface finish thanks to the wiper function

### Features of chip breakers

	Insert Cutting-edge		Uses	Features
ММ	<b>&gt;</b>		For roughing	Highly rigid chip breaker ideally suited for roughing at high depth of cuts





### Recommended cutting condition


	Workpiece	Grades	Cutting condition						
	workpiece	Grades	vc (m/min)	fz (mm/t)	ap (mm)				
	Low carbon steel/Mild steel	PC5300, NC5340, NCM535	140~270	0.2~0.4	2.0~10.0 [SCKN22], 3.0~14.0 [SCKN28]				
P	High carbon steel	PC5300, NC5340, NCM535	100~220	0.2~0.4	2.0~10.0 [SCKN22], 3.0~14.0 [SCKN28]				
	Alloy steel	PC5300, NC5340, NCM535	100~180	0.2~0.4	2.0~10.0 [SCKN22], 3.0~14.0 [SCKN28]				
M	Stainless steel	PC5300, NC5340, NCM535	90~180	0.2~0.4	2.0~10.0 [SCKN22], 3.0~14.0 [SCKN28]				
K	Cast iron	PC5300, NC5340, NCM535	100~180	0.2~0.4	2.0~10.0 [SCKN22], 3.0~14.0 [SCKN28]				

# 













(mm)

De	signation	(i)	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
HDDCM	7125R/L-5	5	125	135.6	90	40	16.4	9	32	63	10.5	3.43	1
	7160R/L-6	6	160	169.8	110	40	16.4	9	32	63	10.5	4.89	2
	7160R/L-8	8	160	169.8	110	40	16.4	9	32	63	10.5	4.62	2
	7200R/L-8	8	200	209.2	130	60	25.7	14	38	80	10.5	8.49	2
	7200R/L-10	10	200	209.2	130	60	25.7	14	38	80	10.5	8.74	2
	7250R/L-10	12	250	258.6	180	60	25.7	14	38	80	10.5	13.44	2
	7250R/L-12	10	250	258.6	180	60	25.7	14	38	80	10.5	13.41	2
	7315R/L-12	12	315	323.2	240	60	25.7	14	38	80	10.5	21.69	3
	7315R/L-14	14	315	323.2	240	60	25.7	14	38	80	10.5	21.41	3
HDDCM	9125R/L-5	5	125	140.4	90	40	16.4	9	32	63	14.5	3.4	1
	9160R/L-6	6	160	177.6	110	40	16.4	9	32	80	14.5	6.39	2
	9200R/L-8	8	200	213.6	130	60	25.7	14	38	80	14.5	8.76	2
	9250R/L-10	10	250	265	180	60	25.7	14	38	80	14.5	13.84	2
	9250R/L-12	12	250	265	180	60	25.7	14	38	80	14.5	13.41	2
	9315R/L-12	12	315	327.4	240	60	25.7	14	38	80	14.5	21.02	3

### Available inserts

# | Cemet | Coated | Uncoated | Designation | Cemet | Coated | Uncoated | Coated | Coa

### Recommended cutting condition

Maykniaaa	Cutting of	condition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
Р	140~270 100~220 100~180	0.2~0.4	NC5340 NCM535
M	90~180		140101303
K	100~180		

### Available arbors


	Designation	General arbor
HDDCM	7125R/L-5	
	7160R/L-6	NT*□□(M/U)-FMC40
	7160R/L-8	
	7200R/L-8	
	7200R/L-10	
	7250R/L-10	NT*□□(M/U)-FMC60
	7250R/L-12	INT LL(IM/O)-FIVIC60
	7315R/L-12	
	7315R/L-14	
	9125R/L-5	NIT* (NA/LI) FNAC 40
	9160R/L-6	NT*□□(M/U)-FMC40
	9200R/L-8	
	9250R/L-10	NIT* \( \( \lambda \) \( \lambda \) \( \lambda \) \( \lambda \)
	9250R/L-12	NT*□□(M/U)-FMC60
	9315R/L-12	

\* - NT number \*\* - BT number \*\*\*Over milling 5

Specification	Wedge	Wedge screw	Shim	Shim screw	Wrench	
Ø125~Ø315 (7000 type)	WHD7R/L	WHX0817	SS64DPR	FTGA0614	HW40	
Ø125~Ø315 (9000 type)	WHD9R/L	WHX0817	SS84DPR	FTGA0818	HW40	

### **ADS4000**









SDKN-MU

45°	• AR: 15°

(mm)

D	Designation	<b>©</b>	ØD	ØD1	Ød	Q	L	ар	(kg)
ADS	4050R/L	3	50	75	32	40	120	6.5	1.8
	4050R/L-S42	3	50	75	42	40	120	6.5	2.2
	4063R/L	4	63	87	32	40	120	6.5	2.3
	4063R/L-S42	4	63	87	42	40	120	6.5	2.7

### Available inserts

SDCN


				•							)		•			1		)
			rmet					Co							-	coa		
ı			CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	910	된	page
SDCN	42M															•		
	42M-G																•	
	42MT		•			•									•			
	42MT-RH																	
	42MT-S20										•							E19
	1203AEEN																	
	1203AEEN-RH																	
	1203AESN																	
	1203AESN-RH																	
SDKN	1203AESN-MU								•									E20
	1203AESN-SU								•				•	•				LZU
SDKR	1203AESN-MX																	
	1203AETN-MX																	E20
	1203AEN-MX				•													

SDKN-SU

SDKR-MX

### Recommended cutting condition


Wayleniaga	Cutting of	Cutting condition						
Workpiece	vc (m/min)	fz (mm/t)	Grades					
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A					
M	90~150	0.05~0.20	PC9530					
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10					



Specification				<b>9</b> Timin	Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Salar Sa	
	Locator	Wedge	Wedge screw	Locator screw	Wrench	
Ø50~Ø63	LASS4R/L	WASR/L	WTX0817	LTX0512	TW25	

### **ADS5000**









(mm)


	Designation	©	ØD	ØD1	Ød	Q	L	ар	(kg)
ADS	5050R/L	3	50	75	32	40	120	8.5	1.9
	5050R/L-S42	3	50	75	42	40	120	8.5	2.3
	5063R/L	4	63	87	32	40	120	8.5	2.4
	5063R/L-S42	4	63	87	42	40	120	8.5	2.8

### Available inserts

	SDCN SD	KN-N	ΙU				SD	ΚI	N-S	U				SI	ΣK	R-I	ΙX	
		9		•									•			1		)
		Ce	rmet					Co	at	ed	l				Un	coa	ted	
ı	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	99	된	page
SDCN	53M															•		
	53M-G																•	
	53MT		•		•										•			
	53MT-RH																	
	53MT-S20										•							E19
	1504AEEN																	
	1504AEEN-RH									•			•					
	1504AESN																	
	1504AESN-RH									•								
SDKN	1504AESN-MU								•									E20
	1504AESN-SU								•				•	•				
SDKR	1504AESN-MX					•												
	1504AETN-MX																	E20
	1504AEN-MX				•													

### Recommended cutting condition

Workpiece	Cutting of	Cutting condition						
workpiece	vc (m/min)	fz (mm/t)	Grades					
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A					
M	90~150	0.05~0.20	PC9530					
K	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10					



Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench	
Ø50~Ø63	LASS5R/L	WASR/L	WTX0817	LTX0512	TW25	

### PES2000/3000/4000







Fig. 1












(mm)

D	esignation	©	ØD	Ød	Q	L	ар	kg	Fig.
PES	2020R/L	2	20	20	30	110	8	0.3	1
	2025R/L	2	25	25	35	120	8	0.5	1
	3030R/L	2	30	32	45	160	13	0.9	1
	3032R/L	2	32	32	45	160	13	1.0	1
	3033R/L	2	33	32	45	160	13	1.1	1
	3035R/L	2	35	32	45	160	13	1.2	1
	3036R/L	2	36	32	45	160	13	1.3	1
	3040R/L	2	40	32	45	160	13	1.4	1
	4050R/L	3	50	32	40	120	16.5	1.2	2
	4050R/L-S42	3	50	42	40	120	16.5	1.5	2
	4063R/L	4	63	32	40	120	16.5	1.5	2
	4063R/L-S42	4	63	42	40	120	16.5	1.8	2


### Available inserts



### Recommended cutting condition

Workniego	Cutting of	Cutting condition						
Workpiece	vc (m/min)	fz (mm/t)	Grades					
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A					
M	90~150	0.05~0.20	PC9530					
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10					






Specification	Locator	Wedge	Wedge screw	Locator screw	Wrench	Wrench	Clamp	Ring
Ø20~Ø25 (2000 type)	-	-	-	CHX0407	HW25L	-	CH4R1	ER03
Ø30~Ø40 (3000 type)	-	-	-	CHX0510	HW30L	-	CH5R1	ER04
Ø50~Ø63 (4000 type)	LPTS4R/L	WPTSR	DHA0815	LTX0512	-	HW40	-	-

# **AFO(M)4000**









(mm)

Des	signation	<b>(a)</b>	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg
AFO	4080R/L	5	80	88	60	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	3.3	1.4
(AFOM)	4100R/L	6	100	108	80	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	3.3	2.0
	4125R/L	8	125	133	100	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	3.3	3.1

( )Metric size

### Available inserts

OFKT-MF

OFCW

	9			•		•					<b>&gt;</b>			S. S. S. S.			200	
		Cer	met					Co	at	ed	l				Un	coa	ted	
I	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	문	page
OFCW	05T3SN																	
	05T3FN																	E14
	05T308FN																	
OFKT	05T3SN-MF									•								
	05T308SN-MF																	
	05T3SN-MM				•				•		•							E14
	05T308SN-MM																	E15
	05T3FN-MA																•	
	05T3EN-MA																П	

OFKT-MM

OFKT-MA

### Available arbors


Designation		Canaval arbay	NC arbors					
Desig	nauon	General arbor	AFO	AFOM				
AFO	4080R/L	NT* (M/U)-FMA25.4-25	BT**	FMC27				
(AFOM)	4100R/L	NT* (M/U)-FMA31.75-	BT** - FMA31.75-	FMC32				
	4125R/L	NT* (M/U)-FMA38.1-	BT** - FMA38.1	FMB40				

\* $\square$ -NT number \*\* $\square$ -BT number \*\*\*Over milling 5

### Recommended cutting condition


Workpiece	Cutting of	Grades	
workpiece	vc (m/min)	fz (mm/t)	Grades
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A
M	90~150	0.05~0.20	PC9530
К	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10

Assembling



Specification						
	Locator	Wedge	Wedge screw	Screw	Wrench	
Ø80~Ø125	LAF04R/L	WAFO4R/L	DHA0815	FTKA0408	TW15S	

# **AFO(M)5000**







• AR: 15° • RR: 5°

(mm)

De	signation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
AFO	5080R/L	5	80	91	60	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	4.8	1.4	1
(AFOM)	5100R/L	6	100	111	80	31.75	12.7 (14.4)	8 (8)	32 (28)	50	4.8	2.0	2
	5125R/L	8	125	136	100	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	4.8	3.1	2
	5160R/L	10	160	171	120	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	4.8	5.2	2
	5200R/L	12	200	211	130	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	4.8	7.5	3
	5250R/L	16	250	261	180	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	4.8	16.1	3
	5315R/L	20	315	326	240	47.625 (60)	25.4 (25.7)	13.5 (14)	38 (38)	63	4.8	22.8	4

( )Metric size

### Available inserts

OFKT-MM	OFK	T-MA O	FCN	OFKR-MF
	C			The state of the s
OFKF	R-MM	OFKR-MA	REK	R-MM
-	The same of the sa			3
320	THE		1	W. S.

		Cer	met					Cc	at	ed					Un	coa	ted	
ı	Designation		CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
OFCN	0704SN									•								
	0704FN																	E14
	070408SN																	⊏14
	070408FN																	
OFKR	0704SN-MF				•	•												
	070408SN-MF																	
	0704SN-MM				•	•			•	•	•			•				-44
	070408SN-MM				•													E14
	0704FN-MA																•	
	0704EN-MA																	
OFKT	0704SN-MM																	F4.4
	0704FN-MA																•	E14 E15
	0704EN-MA																	_I3
REKR	170400-MM																	E17

### Available arbors

Docian	ation	General arbor	NC arbors	
Designation		General arbor	AFO	AFOM
	5080R/L	NT*□□ (M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27
(AFOM)	5100R/L	NT* (M/U)-FMA31.75-	BT** - FMA31.75-	FMC32
	5125R/L	NT* (M/U)-FMA38.1-	BT** - FMA38.1	FMB40
-	5160R/L	NT* (M/U)-FMA50.8-	BT** - FMA50.8-	FMB40
	5200R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60
	5250R/L	NT* (M/U)-FMA47.625-25, KCP-8***	BT** - FMA47.625	FMB60
	5315R/L	KCP-8*** (Center ring plug)		

\* -NT number \*\* -BT number \*\*\*Over milling 5


### Recommended cutting condition

Maukniaaa	Cutting of	Cutting condition					
Workpiece	vc (m/min)	fz (mm/t)	Grades				
Р	190~320 161~270 80~140	0.05~0.20 0.05~0.20 0.05~0.20	NCM325 PC3700 ST30A				
M	90~150	0.05~0.20	PC9530				
K	140~230 50~90	0.05~0.30 0.05~0.30	PC6510 G10				

Assembling

### Parts

Specification					MONOT
	Locator	Wedge	Wedge screw	Locator screw	Wrench
Ø80~Ø315	LAF05R/L	WEFR/L	DHA0821F	LTX0512	HW40
Ø00~Ø313	LAF05R*/L-1*	WEFN/L	DHAU021F	LIAUSIZ	HVV40



Available arbors and bolt E426∼E428






### New serrated edge design increases productivity by reducing insert cutting load

### **Power Buster**

- New tooling utilizing a specially designed serrated edge to increase productivity by reducing the cutting load.
- Double-sided 6 corner insert geometry ensures high rigidity, long tool life and cost efficiency
- The serrated edge divides the chips into smaller pieces. This feature provides excellent chip control, reduces interference of the cutter and ensures good durability of the cutter body.
- Two types of inserts are available-TNMX27 for PBA (Approach angle: 45°) and PBZ (AA: 80°), and TNMX30 for PBP (AA: 90°)
- Application: High depth of cut and feed rate (Steel, Cast iron)

### Code system





### Features of insert

### 1 Major cutting-edge (Serrated edge)

- · Low cutting force
- Ideal for chip control, divides chips into small pieces for proper chip evacuation.
- · Ideal edge design for Steel and Cast iron rough milling

### · Comparison of chip control and cutting force






- Workpiece SCM440
- Cutting vc = 200 m/min, ap = 8 mm, condition ae = 90 mm, fz = 0.3 mm/t


#### 2 Thicker insert

- · Thick insert quarantees high rigidity
- · Balanced insert design for stable mounting



### **8** NM Chip breaker

- · High rake angle for low cutting force
- Good chip flow at various feed and depth of cut
- · Inserts are protected with seats for a precise mounting
- · Low friction and good heat evacuation at high depth cut






### **Technical Information for Power Buster**

er E

- Insert shape applied to PBA/Z cutters (AA: 45°/80°)
  - · High rake angle to avoid interference with chip
  - Calculated minor cutting-edge angel for both AA 45° & 80° cutter




### 6 Mirror system


· Cutting-edge on the both side of insert covers all overlapped cutting area



### Features of cutter

- 1 Screw-on clamping system
  - · Simple and strong screw on clamping system
- Better rigidity & Stable Assembly system
  - The shim protects the cutter from insert damage
  - · High accuracy shim ensures tighter clamping







### **8** Foolproof System

· Insert serrations match pocket design to prevent improper seating and alignment











### **Technical Information for Power Buster**

### 4 Multi-application system

• Same insert for multi-use (45° and 80°)





The serrations are effective with a depth of cut larger than 1 mm






The serrations are effective with a depth of cut larger than 3 mm






For the AA 90° cutter, nicks function properly at depth of cuts over 5 mm



66


### Recommended cutting condition

				NC5330	NCM335	PC5300
ISO	Workpi	000	Material			
130	WOIKPI	ece	Material	0.1-0.2-0.3	0.1-0.2-0.3	0.1-0.2-0.3
					vc (m/min)	
		-	SUM22, C = 0.1~25	400	335	280
	Carbon steel -		C = 0.30~55	365	305	255
		-	C = 0.55~80	340	285	240
P	Eon andy older	-	SCM415(H), SCM420, SCM440	280	235	195
	(Alloy constituent < 5%)	Hardened		165	140	115
	High alloy steel	Annealed	SKD61	210	180	150
	(Alloy constituent > 5%)	Hardened	SKH51, SKH55	175	145	120
		Low tensile	FC200, FC250	125	-	145
K	Overv each iven	Hight tensile	FC300, FC350	105	-	120
-	Gray cast iron	Ferric	FCD400, FCD500	80	-	95
		Pearlitic	FCD600, FCD700	75	-	85



### Power Buster test


### ■ Cylinder block for ship engine (Cast iron)



Item	Power buster	Conventional tool					
Diameter (ØD)	200 mm	200 mm					
©	12 tooth	12 tooth					
Grades	NC5330	PVD coating for Cast iron					
VC	170 m/min	130 m/min					
fz	0.24 mm/t	0.16 mm/t					
ар	10 mm x 2 passes	4 mm x 5 passes					
min	28.2 min/ea	137.5 min/ea					
4.8 times produ	4.8 times productivity increased						

### ■ Heavy machinery part (Alloy steel)


Cutting width (ae) = 35 mm Cutting depth (ap) = 10 mm



Item	Power Buster	Conventional tool
Diameter (ØD)	125 mm	100 mm
<b>(</b> )	8 tooth	8 tooth
Grades	NCM335	PVD coating for Cast iron
VC	180 m/min	150 m/min
fz	0.15 mm/t	0.10 mm/t
ар	5 mm x 2 passes	2.5 mm x 4 passes
min	5 min/ea	14.7 min/ea
2.9 times produ	ctivity increased	Double-sided 8 corner insert (Without nick)     AA 45° cutter

# **PBAC(M)5000**









Fig. 3







• AR: -5° • RR: -11°

(mm)

Desig	gnation	(i)	ØD	Ød	Ød1	Ød2	а	b	E	F	ар	Fig.
PBAC	5080R/L	4	80	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (22)	50	12	1
(PBACM)	5100R/L	4	100	31.75 (32)	-	45	12.7 (14.4)	8 (8)	32 (28)	50	12	2
호	5125R/L	6	125	38.1 (40)	-	56	15.9 (16.4)	10 (9)	38 (32)	63	12	2
Coarse pitch	5160R/L	8	160	50.8 (40)	-	100	19 (16.4)	11 (9)	38 (32)	63	12	2
Ş	5200R/L	10	200	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	12	3
	5250R/L	12	250	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	12	3
	5315R/L	14	315	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	12	4
PBAC	5080R/L-M	6	80	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (22)	50	12	1
(PBACM)	5100R/L-M	6	100	31.75 (32)	-	45	12.7 (14.4)	8 (8)	32 (28)	50	12	2
itch	5125R/L-M	8	125	38.1 (40)	-	56	15.9 (16.4)	10 (9)	38 (32)	63	12	2
Close pitch	5160R/L-M	10	160	50.8 (40)	-	100	19 (16.4)	11 (9)	38 (32)	63	12	2
S	5200R/L-M	12	200	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	12	3
	5250R/L-M	14	250	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	12	3
	5315R/L-M	16	315	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	12	4

### ( )Metric size

### Available inserts

#### TNMX-NM




		Cer	met	Coated Uncoated																
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
TNMX	2710AZNR-NM			•			•				•		•		•					E28
	2710AZNL-NM																			E20

### Available arbors

	Decimation	Available arbors											
	Designation	PBAC	PBACM										
PBAC	5080R/L-□	BT□□-FMA25.4-□□	BT□□-FMC27-□□										
(PBACM)	5100R/L-	BT□□-FMA31.75-□□	BT□□-FMC32-□□										
	5125R/L-	BT□□-FMA38.1-□□	BT□□-FMB40-□□										
	5160R/L-	BT□□-FMA50.8-□□	BT□□-FMC40-□□										
	5200R/L-												
	5250R/L-	BT□□-FMA47.625-□□	BT□□-FMB60-□□										
	5315R/L-												

Specification	Screw	Shim	Shim screw	Wrench
Ø80~Ø315	FTGA0518	ST53AZR	SHXN0712F	TW20-100

# PBZC(M)5000







• AR: -5° • RR: -12°

(mm)

Desi	gnation	0	ØD	Ød	Ød1	Ød2	а	b	E	F	ар	Fig.
PBZC	5080R/L	4	80	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (22)	50	18	1
(PBZCM)	5100R/L	4	100	31.75 (32)	-	45	12.7 (14.4)	8 (8)	32 (28)	50	18	2
itc	5125R/L	6	125	38.1 (40)	-	56	15.9 (16.4)	10 (9)	38 (32)	63	18	2
e s	5160R/L	8	160	50.8 (40)	-	100	19 (16.4)	11 (9)	38 (32)	63	18	2
Coarse pitch	5200R/L	10	200	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	18	3
	5250R/L	12	250	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	18	3
	5315R/L	14	315	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	18	4
PBZC	5080R/L-M	6	80	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (22)	50	18	1
(PBZCM)	5100R/L-M	6	100	31.75 (32)	-	45	12.7 (14.4)	8 (8)	32 (28)	50	18	2
İţch	5125R/L-M	8	125	38.1 (40)	-	56	15.9 (16.4)	10 (9)	38 (32)	63	18	2
e D	5160R/L-M	10	160	50.8 (40)	-	100	19 (16.4)	11 (9)	38 (32)	63	18	2
Close pitch	5200R/L-M	12	200	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	18	3
	5250R/L-M	14	250	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	18	3
	5315R/L-M	16	315	47.625 (60)	-	-	25.4 (25.7)	14 (14)	38 (38)	63	18	4

( )Metric size

### Available inserts

### TNMX-NM




						Coated								Ur	ncoat	ted				
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
TNMX	2710AZNR-NM			•			•				•		•		•					E28
	2710AZNL-NM																			⊑28

### Available arbors

	Decimation	Available arbors											
	Designation	PBZC	PBZCM										
PBZC	5080R/L-	BT□□ -FMA25.4-□□	BT□□ -FMC27-□□										
(PBZCM)	5100R/L-	BT□□ -FMA31.75-□□	BT□□ -FMC32-□□										
	5125R/L-	BT□□ -FMA38.1-□□	BT□□ -FMB40-□□										
	5160R/L-	BT□□ -FMA50.8-□□	BT□□ -FMC40-□□										
	5200R/L-												
	5250R/L-	BT□□ -FMA47.625-□□	BT□□ -FMB60-□□										
	5315R/L-												

Specification	Screw	Shim	Shim screw	Wrench
Ø80~Ø315	FTGA0518	ST53AZR	SHXN0712F	TW20-100

# PBPCM6000 (1997)





														(mm)
De	esignation	<b>(</b>	ØD	ØD1	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
PBPCM	6080R-4	4	80	60	27	14	20	12.4	7	24	50	20	0.85	1
	6100R-6	6	100	70	32	-	54	14.4	8	30	50	20	1.16	2
	6125R-6	6	125	90	40	-	56	16.4	9	32	63	20	2.84	2
	6160R-8	8	160	107	40	-	90	16.4	9	32	63	20	3.58	3
	6200R-10	10	200	130	60	-	132	25.7	14	38	63	20	5.13	3
	6250R-12	12	250	180	60	-	180	25.7	14	38	63	20	9.6	3
	6315R-14	14	315	240	60	-	238	25.7	14	38	63	20	16.85	4

### Available inserts

								1		eW										
		Cer	met						(	Coate	d						1U	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
TNMX	3012PNR-NM																			E28

TNMX-NM

### Available arbors

	Designation	General arbor
PBPCM	6080R-4	BT□□ -FMC27-□□
	6100R-6	BT□□ -FMC32-□□
	6125R-6	BT□□-FMC40-□□
	6160R-8	BIFMIC4U
	6200R-10	
	6250R-12	BT□□ -FMC60-□□
	6315R-14	

Specification		Oh: ina		Manaka
	Screw	Shim	Shim Screw	Wrench
Ø80~Ø315	FTGA0518	ST53PNR	SHXN0712F	TW20-100




Rich Mill series is one of innovations that provides more available cutting-edges by double-sided insert and longer tool life for our customers

# **Rich Mill Series**

- Rich Mill series is one of the innovations that provides more available cutting-edges with double-sided inserts and longer tool life for our customers
- The unique geometry and special cutting-edge guarantees low cutting loads and long tool life
- Rich Mill series has a wide application range from steel and stainless steel to cast iron and aluminum
- Applying negative inserts makes it even stronger and provides longer tool life
- Rich Mill series has both screw-on clamping system and latch clamping system

#### Code system



## **Rich Mill RM3**

#### Features


- High Quality True 90° shouldering operation
- · High Productivity Strong thick insert and 3-face clamping ensure stable operation even tough condition.
- · High Economics Long tool life due to optimized manufacturing process

#### Features of insert





#### Features of cutter



#### Through coolant system


- Exclusive through coolant bolt required
- Effective coolant distribution directly to cutting-edge
- · Coolant supporting arbor required



#### Features of chip breakers

In	sert	Cutting-edge	Uses	Features
MA			Aluminum	Superior cutting quality for aluminum due to sharp cutting-edge and buffed surface
ML			Light	Superior cutting quality for light and light cutting, difficult-to-cut material machining through the low cutting load of chip breaker
ММ	6		General	Suitable for various cutting due to special shape design for general cutting

## Max step in plunging



Туре	max. ae
3000 type	2.5
4000 type	3.0
5000 type	3.5

		Cutter Diameter (Ø)												
ae	Ø20	Ø21	Ø25	Ø26	Ø32	Ø33	Ø40	Ø50	Ø63	Ø80	Ø100	Ø125		
	max step (mm)													
1	8.5	8.9	9.7	10	11.1	11.3	12.4	14	15.7	17.7	19.9	22.2		
2	12	12.3	13.5	13.8	15.4	15.7	17.4	19.5	22	24.9	28	31.3		
3	-	-	-	-	-	-	21	23.7	26.8	30.3	34.1	38.2		





### Ramping and helical cutting


1. Ramping

2. Helical cutting for blind hole

3. Helical cutting for through hole







(mm)

			1. Ram	ping	2. H	elical cutti	ing for blind ho	le	3.Helical cutting for through hole		
Туре	Tool Dia. ØD	ар	Max. rake angle q°	Lmin	Min. machining Dia. ØDHmin	Max. pitch	Max. machining Dia. ØDHmax	Max. pitch	Min. machining Dia. ØDHmin	Max. pitch	
	20	5.5	15.5	19.8	36.5	5.5	38.5	5.5	33.0	5.5	
	21	5.5	14.0	22.1	38.5	5.5	40.5	5.5	35.0	5.5	
	25	5.5	10.0	31.2	46.5	5.5	48.5	5.5	43.0	5.5	
	26	5.5	9.5	32.9	48.34	5.5	51.0	5.5	45.0	5.5	
	32	5.5	6.5	48.3	60.5	5.5	62.5	5.5	59.0	5.5	
2000 +	33	5.5	6.0	52.3	62.5	5.5	64.5	5.5	59.0	5.5	
3000 type	40	5.5	4.5	69.9	46.5	5.5	78.5	5.5	73.0	5.5	
	50	5.5	3.5	89.9	96.5	5.5	98.5	5.5	93.0	5.5	
	63	5.5	2.5	126.0	122.5	5.5	124.5	5.5	119.0	5.5	
	80	8	2.0	157.5	156.5	5.5	158.5	5.5	153.0	5.5	
	100	8	1.5	210.0	194.5	5.5	198.5	5.5	193.0	5.5	
	125	8	1.0	315.1	246.5	5.5	248.5	5.5	243.0	5.5	
	25	8	24.0	18.0	44.5	8.0	48.0	8.0	38.5	8.0	
	32	8	13.0	34.7	58.5	8.0	62.0	8.0	52.5	8.0	
	33	8	12.0	37.6	60.02	8.0	64.4	8.0	54.5	8.0	
	40	8	8.5	53.5	74.5	8.0	78.0	8.0	68.5	8.0	
4000 type	50	8	6.0	76.1	94.5	8.0	98.0	8.0	88.5	8.0	
	63	8	4.0	114.4	120.5	8.0	124.0	8.0	114.5	8.0	
	80	8	3.0	152.6	154.5	8.0	158.0	8.0	148.5	8.0	
	100	8	2.0	229.1	194.5	8.0	198.0	8.0	188.5	8.0	
	125	8	1.5	305.5	244.5	7.7	248.0	7.8	238.5	7.7	
	80	12	5.5	124.6	153.5	12.0	158.0	12.0	146.5	12.0	
5000 type	100	12	4.5	152.5	193.5	12.0	198.0	12.0	159.5	12.0	
	125	12	3.5	196.2	242.5	12.0	248.0	12.0	236.5	12.0	

<sup>\*</sup> Please be sure to use cutting oil or air for ramping and helical machining Lmin = ap/tan ( $\alpha^\circ$ )



## Application guideline for grade

,	Mouleniage	F		M	K	N
	Workpiece	Carbon steel Alloy steel		Stainless steel	Cast iron	Aluminum
Chip breaker	First choice	MM	MM	ML	ML	MA
Chip breaker	Second choice	ML	ML	-	MM	-
	High speed machining	PC3700	PC3700	PC5300	PC6510	
Grades	General machining	PC5400	PC5300	PC5400	PC5300	H01
	Interrupted machining	PC5400	PC5400	PC5400	PC5400	

## Recommended cutting condition

### · RM3 3000 type

				Cutting	conditions		Cutting conditions				
V	/orkpiece	Grades	vc (m/min)	fz (mm/t)	max ap (mm)	Available inserts	vc (m/min)	fz (mm/t)	max ap (mm)	Available inserts	
		PC3700	160~270	0.25~0.05		XNKT0604□□ PNSR-MM	160~270	0.2~0.05		XNKT0604□□ PNER-ML	
Р	steel	PC5300	150~240	0.25~0.05	5.5		150~240	0.25~0.05	5.5		
		PC5400	130~210	0.25~0.05			130~210	0.25~0.05			
М	Stainless	PC5300	90~150	0.2~0.05			90~150	0.1~0.05			
IVI	steel	PC5400	70~120	0.2~0.05			70~120	0.1~0.05			
K	Cast	PC6510	140~230	0.3~0.08			140~230	0.25~0.08			
	iron	PC5300	120~200	0.3~0.08			120~200	0.25~0.08			

<sup>\*</sup> Maximum cutting condition: vc = 350 m/min, fz = 0.5 mm/t according to cutting environment

#### · RM3 4000 type

				Cutting	conditions		Cutting conditions				
W	orkpiece	Grades	vc (m/min)	fz (mm/t)	max ap (mm)	Available inserts	vc (m/min)	fz (mm/t)	max ap (mm)	Available inserts	
		PC3700	160~270	0.3~0.05		XNKT0805	160~270	0.25~0.05			
Р	steel	PC5300	150~240	0.3~0.05			150~240	0.25~0.05	8.0		
		PC5400	130~210	0.3~0.05	8.0		130~210	0.25~0.05		XNKT0805□□ PNER-ML	
М	Stainless	PC5300	90~150	0.25~0.05			90~150	0.2~0.05			
IVI	steel	PC5400	70~120	0.25~0.05			70~120	0.2~0.05			
14	Cast	PC6510	140~230	0.35~0.08			140~230	0.3~0.08			
K	iron	PC5300	120~200	0.35~0.08			120~200	0.3~0.08			
N	Aluminum	H01	400~1200	0.4~0.1		XNCT0805□□PNFR-MA	-	-	-	-	

<sup>\*</sup> Maximum cutting condition: vc = 350 m/min, fz = 0.5 mm/t according to cutting environment

#### · RM3 5000 type

				Cutting	conditions		Cutting conditions				
W	orkpiece	Grades	vc (m/min)	fz (mm/t)	max ap (mm)	Available inserts	vc (m/min)	fz (mm/t)	max ap (mm)	Available inserts	
		PC3700	160~270	0.3~0.05		XNKT1206	160~270	0.25~0.05			
Р	steel	PC5300	150~240	0.3~0.05			150~240	0.25~0.05	12.0		
		PC5400	130~210	0.3~0.05			130~210	0.25~0.05		XNKT1206□□ PNER-ML	
М	Stainless	PC5300	90~150	0.25~0.05	12.0		90~150	0.2~0.05			
IVI	steel	PC5400	70~120	0.25~0.05			70~120	0.2~0.05			
V	Cast	PC6510	140~230	0.35~0.08			140~230	0.3~0.08			
K	iron	PC5300	120~200	0.35~0.08			120~200	0.3~0.08			
N	Aluminum	H01	400~1200	0.4~0.1		XNCT1206□□PNFR-MA	-	-	-	-	



\* Maximum cutting condition: vc = 350 m/min, fz = 0.5 mm/t according to cutting environment

# ιΕ

# **Rich Mill RM4**

#### Features

- · Economical 4 cutting-edges by using double-sided insert
- RM4, as a multi-functional milling tool, offers economical 4 cutting-edges by using an innovative double-sided insert
- Special designed chip breaker consists of high rake angle and strong cutting-edge to decrease the cutting load
- RM4 is multi-functional tool that can cover facing, side cutting, shouldering, slotting, ramping & helical cutting
- Optimal matching of the special cutting-edge geometry with variety of new grades provides consistence & long tool life of insert



#### Features of cutter

- · 4 cutting edges can be used by using double-sided insert
- · High rake angle chip breaker and cutting-edge can make smooth cutting with low cutting load
- Strong negative insert
- · High efficiency, economical, multi-functional tool



#### Through coolant system


• Longer tool life due to direct cooling injection into the cutting-edge of insert

Wide chip pocket for better chip evacuation Simple screw on system


- Improving chip control

#### Features of insert

- · Double-sided insert using 4 cutting-edges
- High rake angle chip breaker, cutting-edge
- · Flexibility of product
- · High efficiency, economical, multi-functional tool
- · Negative insert has strong cutting-edge



#### Uses



7



#### Features of chip breakers


Ir	sert	Cutting-edge	Uses	Features
MA			Aluminum, Light machining	With sharp edge application the better productivity has been accomplished, especially for Aluminum or low force cut
MF	<b>3</b>		Light cutting	Due to low cutting load, it is good for light cutting and difficult-to-cut material
ММ			General cutting	It is suitable design for general milling

## Setting configuration

Shape	Setting angle of insert	Features
		High rake chip breaker & positive setting angle for low cutting load  → Improving machinability
	- 90.	Multi applications for facing, shouldering, slotting, ramping, helical cutting, etc

## Through coolant system

- By using on exclusive coolant bolt (hexagonal socket bolt) powerful cooling & better chip evacuation can be acquired
- To get optimal chip control, the direction of coolant injection has been designed to reach to each cutting-edge directly (through coolant arbor is required)





Through coolant system for decreasing cutting heat and good chip evacuation





### Ramping and helical cutting


#### ig and neneal cattin











(mm)

			1. Ram	ping	2. He	lical cutt	ing for blind ho	ole	le 3.Helical cutting for through		
Designation	Tool Dia. ØD	ар	Max. rake angle o°	Lmin	Min. machining Dia. Ø DHmin	Max. pitch	Max. machining Dia. Ø DHmax	Max. pitch	Min. machining Dia. Ø DHmin	Max. pitch	
RM4PS3014HR	14	9	4.5	125	25	2.7	27	3.1	19	1.3	
RM4PS3016HR	16	9	3.5	160	29	2.5	31	2.7	23	1.4	
RM4PS3018HR	18	9	3.0	185	33	2.4	35	2.7	27	1.5	
RM4PS3020HR	20	9	2.7	204	37	2.5	39	2.7	31	1.6	
RM4PS3025HR	25	9	1.8	301	47	2.1	49	2.3	41	1.6	
RM4PS3032HR	32	9	1.2	451	61	1.9	63	2.0	55	1.5	
RM4PS3040HR	40	9	0.9	616	77	1.8	79	1.8	71	1.5	
RM4PS3050HR	50	9	0.6	843	97	1.5	99	1.5	91	1.3	
RM4PC(M)3040HR	40	9	0.9	616	77	1.8	79	1.8	71	1.5	
RM4PC(M)3050HR	50	9	0.6	843	97	1.5	99	1.5	91	1.3	
RM4PC(M)3063HR	63	9	0.5	1123	123	1.6	125	1.6	117	1.4	
RM4PC(M)3080HR	80	9	0.3	1508	157	1.2	159	1.2	151	1.1	
RM4PC(M)3100HR	100	9	0.2	1910	197	1.0	199	1.0	191	0.9	
RM4PS4032HR	32	14	2.5	229	59.5	3.0	62	4	49	2.0	
RM4PS4040HR	40	14	2.0	286	75.5	3.0	78	4	65	2.0	
RM4PS4050HR	50	14	2.0	286	95.5	4.0	98	5	85	3.5	
RM4PS4063HR	63	14	2.0	286	121.5	5.0	124	5	111	5.0	
RM4PC(M)4050HR	50	14	2.0	286	95.5	4.0	98	5	85	3.5	
RM4PC(M)4063HR	63	14	2.0	286	121.5	5.0	124	5	111	5.0	
RM4PC(M)4080HR	80 14 1.5 382		382	155.5	5.0	158	5	145	5.0		
RM4PC(M)4100HR	100	14	1.0	573	195.5	4.5	198	5	185	4.0	
RM4PC(M)4125HR	125	14	1.0	573	245.5	5.0	248	5	235	5.0	
RM4PC(M)4160R	160	14	0.5	1146	315.5	3.5	318	4	305	3.5	

<sup>\*</sup> Please be sure to use cutting oil or air for ramping and helical machining Lmin = ap/tan  $(\alpha^{\circ})$ 


#### Recommended cutting condition

2 Hosonimenaca datang condition																
	20	Grades	LNM(E)X100605PNR-MF		LNM(E)X100605PNR-MM		LNEX100605PNR-MA		Мах-ар	LNM(E)X151008PNR-MF		F LNM(E)X151008PNR-MM		LNEX151008PNR-MA		Max-ap
•	50	Grades	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	(mm)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	(mm)
	Б	NCM535	-	-	-	-	-	-		150~300	0.05~0.30	120~300	0.05~0.35	150~300	0.03~0.20	
		PC3700	150~300	0.05~0.25	120~300	0.05~0.30	150~300	0.03~0.20		150~300	0.05~0.30	120~300	0.05~0.35	150~300	0.03~0.20	
	M	PC5300	120~180	0.05~0.25	100~180	0.05~0.30	120~200	0.03~0.20	9.0	120~180	0.05~0.30	100~180	0.05~0.3	120~200	0.03~0.20	14.0
	K	PC6510	150~300	0.08~0.30	120~300	0.08~0.35	-	-		150~300	0.08~0.35	120~300	0.08~0.35	-	-	




#### Features

- Rich mill series RM4Z is a plunge mill for high efficiency vertical machining such as slotting and pocketing in roughing applications
- Rich mill series RM4Z is a highly efficient milling tool for plunging, shouldering and facing. It makes operations more economical with the use of its double-sided 4-corner insert
- Plunge machining reduces lead time for high productivity and precision machining.
- In plunging the max depth of RM4Z 3000 type is 9.0 mm and that of RM4Z 4000 type is 14.0 mm



#### Features of insert



#### Uses








#### The depth of cut by machining type

• In horizontal machining, Depth of cut = ap (mm)




• In plunging, Depth of cut = ae (mm)



RM4Z	Horizontality	Verticality			
RIVI4Z	max ap (mm)	max ae (mm)	step		
RM4Z3000	1.5	9	< 0.7D		
RM4Z4000	2.5	14	< 0.7D		

## Max step in plunging



				Cut	tter Diameter (	mm)			
ae	25	32	40	50	52	63	66	80	100
		'	<u>'</u>		Max step (mm	)	<u>'</u>	'	
1	9.7	11.1	12.4	14	14.2	15.7	16.1	17.7	19.9
2	13.5	15.4	17.4	19.5	20	22	22.6	24.9	28
3	16.2	18.6	21	23.7	24.2	26.8	27.4	30.3	34.1
4	18.3	21.1	24	27.1	27.7	30.7	31.4	34.8	39.1
5	20	23.2	26.4	30	30.6	34	34.9	38.7	43.5
6	21.3	24.9	28.5	32.4	33.2	36.9	37.9	42.1	47.4
7	22.4	26.4	30.3	34.6	35.4	39.5	40.6	45.2	51
8	23.3	27.7	32	36.6	37.5	41.9	43	48	54.2
9	24	28.7	33.4	38.4	39.3	44	45.2	50.5	57.2
10	-	-	-	-	-	46	47.3	52.9	60
11	-	-	-	-	-	47.8	49.1	55.1	62.5
12	-	-	-	-	-	49.4	50.9	57.1	64.9
13	-	-	-	-	-	50.9	52.4	59	67.2
14	-	-	-	-	-	52.3	53.9	60.7	69.3

# Through coolant system


- Exclusive hexagonal coolant socket bolt provides excellent cooling and chip evacuation
- Direct coolant injection to cutting-edge improves cooling effectiveness
- · Coolant type arbor should be used
- \*Coolant bolt is not included, it is for sale







#### Programming tip




Plunging feed direction


Tool escape

β Escape angle  $(\beta \ge 1^{\circ})$ 

• When your tool steps back after plunging, please get over 1° more escape angle

## Helical machining





 $\emptyset Dc = \emptyset Dh - \emptyset D$ 

ØDc = Tool center path ØDh = Desired hole diameter

 $\emptyset D = Tool Dia.$ 

(mm)

				Hel	ical data	
D	Designation	Diameter ØD (mm)	Min. machining Dia. ØDHmin	Max. pitch	Max. machining Dia. ØDHmax	Max. pitch
RM4ZS	3025HR-L25	25	30	0.4	48	1.8
	3032HR-L32	32	43	0.3	62	0.9
	3040HR-L32	40	59	0.3	78	0.6
RM4ZCM	3040HR	40	59	0.3	78	0.6
	3050HR	50	79	0.3	98	0.5
	3052HR	52	83	0.3	102	0.5
RM4ZM	3025HR-M12	25	30	0.4	48	1.8
	3032HR-M16	32	43	0.3	62	0.9
	3040HR-M16	40	59	0.3	78	0.6
RM4ZCM	4063HR	63	95	0.5	124	1.0
	4066HR	66	101	0.5	130	1.0
	4080HR	80	129	0.5	158	0.8
	4100HR	100	169	0.3	198	0.5

#### Recommended cutting condition

ISO	Cuadaa		LNM(E)X100	605PNL-MM		LNM(E)X151008PNL-MM					
150	Grades	vc (m/min)	fz (mm/t)	* max ae (mm)	** max ap (mm)	vc (m/min)	fz (mm/t)	* max ae (mm)	** max ap (mm)		
Р	PC3700	100~250	0.05~0.25			120~250	0.05~0.25				
M	PC5300	100~250	0.08~0.30	9	9	9	1.5	120~250	0.08~0.30	14	2.5
K	PC6510	80~180	0.05~0.20			100~180	0.05~0.20				




#### Features

- $\bullet$  Stable clamping 3 clamping surfaces on the side and strong clamping screws
  - → Improves cutting stability
- High quality results High precision, excellent perpendicularity, outstanding surface finish on the flank, accurate tolerance
- · High productivity High rake angle and sharp cutting-edges for lower cutting resistance
  - → Ideal for high speed and high feed machining

#### Features of insert



#### Features of cutter





### Features of chip breakers

Ir	nsert	Cutting-edge	Uses	Features
MA			For aluminum	Sharp cutting-edges for excellent cutting performance in aluminum machining Buffed surface for excellent chip flow and welding resistance
ML	6		For light cutting	Chip breaker design of low cutting resistance, ideal for light cutting and machining hard-to-cut materials  Excellent tool life and quality results
ММ			For general cutting	Chip breaker design ideal for general shoulder milling and most applications

### Application guideline for grade

,	Manteniaaa	F		М	K	N
'	Workpiece		Alloy steel	Stainless steel	Cast iron	Non-ferrous metal
Chana	1st recommended	MM	MM	ML	ML	MA
Shape	2nd recommended	ML	ML	-	MM	MA
	High speed milling	PC3700	PC3700	PC5300	PC6510	H01
Grades	General milling	PC5400	PC5300	PC5400	PC5300	H01
	Interrupted milling	PC5400	PC5400	PC5400	PC5400	H01

## Recommended cutting condition

#### · WNGX04

			WNG	X040304PNS	R-MM	WNG	X040304PNE	R-ML	WNG	WNGX040304PNFR-MA		
	Workpiece	Grades	vc (m/min)	fz (mm/t)	max. ap(mm)	vc (m/min)	fz (mm/t)	max. ap(mm)	vc (m/min)	fz (mm/t)	max. ap(mm)	
		PC3700	160~270	0.25~0.05		160~270	0.20~0.05		-	-		
Р	Steel	PC5300	150~240	0.25~0.05		150~240	0.25~0.05		-	-		
		<b>PC5400</b> 130~210 0.25~0.05		130~210	0.25~0.05		-	-				
	Stainless	PC5300	90~150	0.20~0.05	4.3	90~150	0.10~0.05	4.3	-	-	4.3	
M	steel	PC5400	70~120	0.20~0.05		70~120	0.10~0.05		-	-		
14		PC6510	140~230	0.30~0.08		140~230	0.25~0.08		-	-		
K	Cast iron	PC5300	120~200	0.30~0.08		120~200	0.25~0.08		-	-		
N	Non-ferrous metal	H01	-	-	-	-	-	-	500~1000	0.2~0.05	4.3	

 <sup>※</sup> The above data refer to general cutting conditions and can be adjustable up to 300 m/min and 0.4 mm/t depending on user environment.

#### · WNGX08

			WNG	WNGX080608PNSR-MM			X080608PNE	R-ML	WNG	X080608PNF	R-MA
	Workpiece	Grades	vc (m/min)	fz (mm/t)	max. ap(mm)	vc (m/min)	fz (mm/t)	max. ap(mm)	vc (m/min)	fz (mm/t)	max. ap(mm)
		PC3700	160~270	0.25~0.05		160~270	0.20~0.05	8.2	-	-	
Р	Steel	PC5300	150~240	0.25~0.05		150~240	0.25~0.05		-	-	
		PC5400	130~210	0.25~0.05		130~210	0.25~0.05		-	-	
	Stainless	PC5300	90~150	0.20~0.05	8.2	90~150	0.10~0.05		-	-	8.2
M	steel	PC5400	70~120	0.20~0.05		70~120	0.10~0.05		-	-	
10	01	PC6510	140~230	0.30~0.08		140~230	0.25~0.08		-	-	
K	Cast iron	PC5300	120~200	0.30~0.08		120~200	0.25~0.08		-	-	
N	Non-ferrous metal	H01	-	-	-	-	-	-	500~1000	0.2~0.05	8.2



<sup>\*</sup> The above data refer to general cutting conditions and can be adjustable up to 300 m/min and 0.4 mm/t depending on user environment.





## Ramping


1. Ramping

2. Helical cutting for blind holes

3. Helical cutting for through holes







(mm)

		Tool		1. Ram	ping	2. Hel	ical cutti	ng for blind h	oles	3. Helical cutting fo	3. Helical cutting for through holes	
Designation		Dia. ØD	ар	Max. rake angle α°	Lmin	Min. machining Dia. ØDHmin	Max. pitch	Max. machining Dia. ØDHmax	Max. pitch	Min. machining Dia. ØDHmin	Max. pitch	
RM6PS	032R-2W32-120-WN08	32	8	0.8	572.9	54	0.96	62	1.3	38 .5	0.5	
	040R-3W32-120-WN08	40	8	0.5	916.7	70	0.82	78	1.0	54 .5	0.4	
	050R-4W32-120-WN08	50	8	0.3	1527.9	90	0.66	98	0.8	74.5	0.3	
RM6PCM	063R-22-6-WN08	63	8	0.2	2291.3	116	0.58	124	0.6	100.5	0.3	
	080R-27-7-WN08	80	8	0.1	4583.7	150	0.38	158	0.4	134.5	0.2	
	100R-32-8-WN08	100	8	0.1	4583.7	190	0.49	198	0.5	174.5	0.3	
	125R-40-11-WN08	125	8	0.1	4583.7	240	0.63	248	0.6	224.5	0.3	

 $Lmin = ap/tan \; (\alpha^\circ)$ 

Lmin: Cutting length at min. rake angle

ap: Axial depth of cut α°: Available rake angle for ramping



#### Features

- Double-sided insert to use 8 cutting-edges
- Innovative double-sided insert makes it possible to use 8 cutting-edges It is more economical than conventional single sided insert
- The unique geometry and high rake angle of cutting-edge guarantees excellent surface finish Applicable for various workpieces like steel, stainless steel, cast iron, aluminum
- · Combined with the innovative geometry and various grades provided the tool offers durability and excellent tool life
- · Various pitches and chip breakers can be applicable for diverse machining
- Light Rich Mill cutter can be useful for high speed machining and low power machine

#### Through coolant system

· Exclusive coolant bolt is adapted to get better chip evacuation and more powerful cooling. To get optimal chip evacuation, the direction of coolant injection has been designed to reach to each cutting-edge directly. Through coolant arbor is required





Through coolant system for decreasing cutting heat and good chip evacuation

#### Features of chip breakers

Ir	nsert	Cutting-edge	Uses	Features
MA			For aluminum	Due to sharp cutting-edge and buffed surface, it has good chip flow and welding resistance
ML			For hard-to-cut material	Chip breaker with low cutting load is optimal for machining hard-to-cut materials
MF			For light cutting	Due to low cutting load, it is good for light cutting and difficult-to-cut material
ММ			For general cutting	It is suitable design for general milling
W			For wiper	Specialized edge design can be suitable for excellent surface roughness operation

#### Uses



#### Features of insert

Insert	Cutting-edge	Features
	View-A	High rake chip breaker & positive setting angle for low cutting load
	View-B	Designed wiper technology in minor cutting-edge for improved surface roughness
B † A	Chip breaker	Low cutting load due to the positive setting and high rake angle chip breaker



#### Features of cutter

Shape	Setting angle of insert	Features
	e a	High rake angle makes positive setting angle for low cutting load
	A	Suitable for facing and chamfering  • RM8A A = 45°  • RM8E A = 75°  • RM8Q A = 88°


#### Recommended cutting condition

10		Grades	SNM(E)X120	6A(E)NN-MF	SNM(E)X120	SNM(E)X1206A(E)NN-MM		A(E)NN-MA	Max-ap	SNM(E)X1507A(E)NN-MF		SNM(E)X1507A(E)NN-MM		Max-ap
13	0		vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	(mm)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	(mm)
		NC5330	-	-	150~300	0.10~0.35	150~300	0.10~0.35		-	-	150~300	0.10~0.35	
ı	P	NCM535	200~300	0.05~0.30	150~300	0.10~0.35	150~300	0.10~0.35	RM8A 6.0	200~300	0.05~0.30	150~300	0.10~0.35	
		PC3700	200~300	0.05~0.30	150~300	0.10~0.35	150~300	0.10~0.35		200~300	0.05~0.30	150~300	0.10~0.35	RM8A 7.5
	v	PC9530	90~150	0.05~0.25	90~150	0.10~0.35	-	-	RM8E 9.0	90~150	0.10~0.30	90~150	0.10~0.35	
		PC5300	90~150	0.05~0.25	90~150	0.10~0.35	-	-		90~150	0.10~0.30	90~150	0.10~0.35	RM8E 11
		PC6510	150~300	0.08~0.35	150~300	0.10~0.40	150~300	0.10~0.40	RM8Q 11.5	150~300	0.08~0.35	150~300	0.10~0.40	
		PC5300	150~300	0.08~0.35	150~300	0.10~0.40	150~300	0.10~0.40		150~300	0.08~0.35	150~300	0.10~0.40	

# **Rich Mill RMH8**

#### Features

- Screw on clamping system Adaptable and Stable clamping system
- · Reinforced rigidity and enhanced clamping power
- Appling shim system, prevent cutter damage when insert breaks
- · Adapting/exchangeable shim
- Using various kinds of cutter (Approach angle 45°, 75°, 88°)
- Stable clamping power with insert







RMH8A





RMH8E








#### Features


- New latch clamping system provides a powerful cutting force and an easy insert change
- · New grades with chipping resistance provides good surface roughness and better tool life
- Due to the specially designed chip breaker, all operations are possible
- RMT with various pitches can replace conventional ISO milling tool




#### Features of insert (Using R/L)



#### Clamping force analysis





### Features of chip breakers

In	sert	Cutting-edge	Uses	Features
MF			For fine finishing	Our specialized insert design creates low cutting forces suitable for light cutting, HRSA
ММ	•		For strengthen	Suitable geometry design for general milling has wider ranges of machining

#### Recommended grades and chip breakers

ISO	Grades	ММ	MF
Р	NCM535	0	0
-	PC5300	0	0
M	PC9530	0	0
K	PC6510	0	0

⊚: Optimum o: Proper

#### Recommended cutting condition

ISO	Cuadas	М	M	MF			
150	Grades	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)		
	NC5330	190~310	0.10~0.35	190~310	0.05~0.30		
Р	NCM535 160~270		0.10~0.35	160~270	0.05~0.30		
	PC3700	130~210	0.10~0.35	130~210	0.05~0.30		
M	PC9530	90~150	0.05~0.30	90~150	0.05~0.30		
K	PC6510	140~230	0.10~0.40	140~230	0.08~0.35		




# Rich Mill RM8-X

#### Features


- High helix face milling tool with 8-cornered double-side inserts
- High performance in stainless steel machining due to sharp cutting edge and double reverse positive relief surface structure
- Economic tool by double-sided 8 corners and high helix right-handed shape realizing high depth of cut machining

#### Insert features



- Protects its corner on the opposite side
- Increased chipping resistance and prevents unexpected breakage

#### Cutter features





# Rich Mill RM8-X


#### Recommended grade and cutting edge


Туре		SAGX		SN	MX
Features		Strong relief surface		Relief surface for	or surface finish
Workpiece	M	S	Н	Р	K
Geometry	SAGX-ML		SAGX-MM	SNN	IX-MM
	(Dauble of		of and	(Negative e	
	[Double r	everse positive relief su	rface]	[Negative re	elief surface]


	Recommended insert and grade for different workpieces (•: 1st recommendation)										
Туре	Р		М		K		S		Н		
	C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades	
SAGX140808ANER	○ML ○MM	○ PC5300 ○ PC3700	• ML • MM	• PC9540 • PC5300	○ML ○MM	o PC6510 o PC5300	• ML • MM	• PC5300	• MM	● PC2510 ○ PC2505	
SNMX140808ANER	• MM	• PC3700	-	-	• MM	• PC6510	-	-	-	-	


## Recommended cutting condition

	Grades	Machining types	Recommended grade	Recommended cutting speed (m/min)	ISO	Application range
Р	Steel	Continuous cutting	PC3700 🚭	235 (180~290)	P30	PC3700 PC5300
-	Steel	Interrupted cutting	PC5300	195 (150~240)	P40	PC3300
		Continuous sutting	PC5300	120 (100 160)	M20	PC5300
M	Stainless steel	Continuous cutting	PC5300	130 (100~160)	M30	PC3300
		Interrupted cutting	PC9540	110 (80~140)	M40	PC9540
		Continuous cutting	PC6510	180 (140~230)	K05	PC6510
K	Cast iron	Continuous cutting	PC0510	160 (140~230)	K10	FC0510
K	Cast IIOII	Interrupted cutting	PC5300	145 (110~180)	K20	PC5300
		interrupted cutting	FC3300	145 (110~160)	K30	FC3300
Н	Hardened steel	Continuous cutting	PC2510 @W	55 (40~70)	H10	PC2510 (1997)












Milling

#### Features

- · Economical face mill with 14 double-sided corners
- · Minimized chattering of workpiece due to minimum lead angle and sharp cutting edge
- · Reduced cutting resistance and improved chip emissions by high helix angle application


#### Insert features

- · Wide supporting area of insert ensures stable clamping system.
- High rake angle cutting edge reduces cutting load and increases chip evacuation.
- · Thicker insert realizes stability in machining.



#### Cutter features

- The biggest heptagonal lead angle reduces chatter in machining.
- Wedge type clamping system ensures stable clamping.
- Stepped machining is available without interruption of side wall of insert.





# The biggest heptagonal lead angle

 Reduced workpiece chattering by reducing axial force



# Preventing interruption of side wall

 Prevented interruption of side wall by using the most number of corners in deep facing (heptagonal 14 double-sided corners)





### Features of chip breakes

	Insert	Cutting-edge	Uses	Features
Flat			Neutral type Flat cutting edge	1st recommended for heat resistant stainless steel machining Generally applied in various machining Applicable for both right handed and left handed
Helix			Right handed type High helix cutting edge	1st recommended for cast iron machining Applicable for stainless steel machining with less than 3 mm depth of cut For high speed and high feed machining

## Recommended grade and cutting edge

( •: 1st recommendation)

			Recommended grade and cutting edge by workpiece										
	Tuno	M					K						
	Туре	Austenitic stainless steel		Heat resistance stainless steel		Gray cast iron		Duct	ile cast iron				
		Туре	Grade	Type Grade		Туре	Grade	Туре	Grade				
Flat		-	● PC9540 ○ PC5300 ○ PC5400	•	● PC9540 ○ PC5300 ○ PC5400	-	○ PC6510 ○ PC5300 • NCM535	-	● PC6510 ○ PC5300 ○ NCM535				
Helix		•	● PC9540 ○ PC5300 ○ PC5400	-	● PC9540 ○ PC5300 ○ PC5400	•	○ PC6510 ○ PC5300 ● NCM535	•	● PC6510 ○ PC5300 ○ NCM535				

## Recommended cutting condition

						Grades	Cutting conditions						
ISC	Workpiece	ISO (DIN)*	AISI	KS	НВ		Helix			Flat			
		(2,					vc (m/min)	fz (mm/t)	ap (mm)	vc (m/min)	fz (mm/t)	ap (mm)	
M	Austenite	STS304 STS316	X5CrNi18-9 X5CrNiMo17-12-2	304 316	160-180	PC9540 (PC5300)	80-160	0.3-0.05	1-3	90-150	0.25-0.05	1-3	
141	Heat resistance stainless steel	-	(1.48□□)	-	160-200	PC9540 (PC5300)	60-100	0.2-0.05	1-2	60-100	0.25-0.05	1-3	
	Gray cast iron	GC250	250 (GG 25)	No 35 B	180-240	NCM535 (PC6510)	200-300	0.3-0.1	2-3	200-300	0.25-0.1	2-3	
K	Ductile cast iron	GCD500	500-7 (GGG 50)	80-55-06	150-230	PC6510 (PC5300)	110-230	0.3-0.1	2-3	150-200	0.3-0.1	2-3	
	Ductile cast iron	GCD600	600-3 (GGG 60)	-	170-270	PC6510 (PC5300)	85-200	0.25-0.15	2-3	150-200	0.25-0.15	2-3	


#### Features

- · Economical 16 cutting-edges
- · Reduces cost in medium cutting
- Wiper insert can be used for good surface roughness
- Optimal matching of the special cutting-edge geometry with variety of new grades provides consistence & long tool
- When it is used 16 corners, maximum cutting depth is 5.5 mm, but it is used 8 corners, maximum cutting depth is 13 mm
- Wiper insert is placed 0.05 mm lower than facing insert in cutter
- When feed is bigger than wiper cutting-edge length (7 mm), 2 wiper inserts are placed in symmetrical position

#### Features of chip breakers

Ir	nsert	Cutting-edge	Uses	Features
MA	•		For aluminum cutting light	With sharp edge application, the better productivity has been accomplished, especially for aluminum cutting
ML	6		For hard-to-cut material	Chip breaker with low cutting load is optimal for machining hard-to-cut materials
MF	(		For light cutting	Due to low cutting load, it is good for light cutting and difficult-to-cut material
ММ	(0)		For general cutting	It is suitable design for general milling
W			For wiper	It has better surface roughness than MM and MF chip breakers

#### Instruction for wiper insert



## Through coolant system

- Well designed chip pocket for better chip flow
- Through coolant system reduces cutting heat and improves chip evacuation



### Recommended cutting condition


(mm)

	20				ONM(H)X060608-MF		ONHX060608-W		ONM(H)X080608-MM		ONM(H)X080608-MF		ONHX080608-W	
•	30	Grades	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)
	Б	NCM535	150~300	0.10~0.35	200~300	0.05~0.30	200~300	0.05~0.20	150~300	0.10~0.40	200~300	0.05~0.35	200~300	0.05~0.25
		PC3700	150~300	0.10~0.35	200~300	0.05~0.30	200~300	0.05~0.20	150~300	0.10~0.40	200~300	0.05~0.35	200~300	0.05~0.25
	М	PC9530	120~180	0.10~0.35	100~180	0.05~0.30	100~180	0.05~0.20	120~180	0.10~0.40	100~180	0.05~0.35	100~180	0.05~0.25
	K	PC6510	150~300	0.10~0.40	150~300	0.08~0.35	150~300	0.05~0.25	150~300	0.10~0.45	150~300	0.08~0.40	150~300	0.05~0.30




#### Features

- · Improved machining stability with the combination of the reversal positive structure preventing rotation and wide upper and lower clamping sides.
- · Helix cutting edge and sharp chip breaker realize smooth cutting.
- · Wide minor cutting edge and optimized holder angle enhance high surface finish.



#### Cutter features





#### Recommended grade and cutting edge

		Recommended grade and cutting edge	by workpiece (•: 1st recommendation)
Chip breaker	Cutting-edge	S	M
		Grade	Grade
ML		● UNC840 ○ UPC845	● PC9540 ○ UPC845

#### Recommended cutting condition

	/ <b>!</b>		ISO	AISI	KS	Cutting conditions					
VV	orkpiece	Grades	150	AISI		vc (m/min)	fz (mm/t)	ap (mm)			
6	High	UNC840	15156-3	7718	Inconel718	30-50	0.4-0.1	1.0-3.0			
S	temperature alloys	UPC845	15156-3	7718	Inconel718	20-40	0.6-0.2	1.5-4.0			
	Stainless	PC9540	X5CrNi18-9	304	STS304	90 160	0.3-0.05	1020			
M	steel	PC9540	X5CrNiMo17-12-2	316	STS316	00-100	0.3-0.05	1.0-3.0			







Туре	A.A	Designation	Shape	Cutter Diameter		Application		Features	Page
		RM3PC(M)3000		Ø40~Ø80	XNKT060405PNER-ML	XNKT060405PNSR-MM			E99
RM3	90°	RM3PC(M)4000		Ø40~Ø125	XNCT080508PNFR-MA XNKT080508PNER-ML XNKT080508PNSR-MM	XNKT080512PNSR-MM XNKT080516PNSR-MM XNKT080520PNSR-MM	ô	Economical 3 corners     Perfect     perpendicularity     Longer tool life due to direct injection into the cutting-edge of insert	E100
		RM3PC(M)5000 @		Ø80~Ø125	XNCT120608PNER-MA XNKT120608PNER-ML XNKT120612PNER-ML XNKT120616PNER-ML XNKT120620PNER-ML	XNKT120608PNSR-MM XNKT120612PNSR-MM XNKT120616PNSR-MM XNKT120620PNSR-MM			E101
		RM4PC(M)3000		Ø40~Ø100	LNEX100605PNR-MF LNMX100605aPNR-MF LNEX100605PNR-MM LNMX100605PNR-MM LNEX100608PNR-MF LNMX100608PNR-MF	LNEX100608PNR-MM LNMX100608PNR-MM LNEX100605PNR-MA LNEX100605PNL-MM LNMX100605PNL-MM		• Economical 4 corner	E105
14	200	RM4PC(M)4000		Ø50~Ø160	LNEX151004PNR-MF LNMX151004PNR-MF LNEX151004PNR-MM LNMX151004PNR-MM LNEX151008PNR-MF LNMX151008PNR-MF LNEX151008PNR-MM LNMX151008PNR-MM	LNEX151016PNR-MF LNMX151016PNR-MF LNEX151016PNR-MM LNMX151016PNR-MM LNEX151004PNR-MA LNEX151008PNR-MA LNEX151008PNL-MM LNMX151008PNL-MM		Screw on type for slotting, facing	E106
RM4	90°	RM4ZCM3000		Ø40~Ø52	LNEX100605PNL-MM	LNMX100605PNL-MM		Economical 4 corners     Optimal insert	
		RM4ZC(M)4000		Ø63~Ø100	LNEX151008PNL-MM	LNMX151008PNL-MM		application for vertical machining	E118

# **E** Rich Mill Table

Туре	A.A	Designation	Shape	Cutter Diameter		Application		Features	Page
9		RM6PCM-WN04		Ø40~Ø63	WNGX040304PNER-ML	WNGX040308PNSR-MM	6	Improved productivity and high-quality	E120
RM6	90°	RM6PC(M)-WN08 4		Ø50~Ø125	WNGX080604PNFR-MA WNGX080608PNFR-MA WNGX080612PNFR-MA WNGX080616PNFR-MA WNGX080620PNFR-MA WNGX080604PNER-ML WNGX080608PNER-ML WNGX080612PNER-ML	WNGX080620PNER-ML WNGX080604PNSR-MM WNGX080608PNSR-MM WNGX080612PNSR-MM WNGX080616PNSR-MM		shouldering through high speed and high feed machining	E121
	45°	RM8AC(M)4000		Ø50~Ø400	SNEX1206ANN-MA SNEX1206ANN-MF SNMX1206ANN-MF SNEX1206ANN-ML	SNEX1206ANN-MM SNMX1206ANN-MM SNEX1206ANN-W			E126
	43	RM8AC(M)5000	Secretary 199	Ø80~Ø400	SNEX1507ANN-MF SNMX1507ANN-MF SNEX1507ANN-ML	SNEX1507ANN-MM SNMX1507ANN-MM			E128
RM8	750	RM8EC(M)4000		Ø50~Ø400	SNEX1206ENN-MA SNEX1206ENN-MF SNMX1206ENN-MF	SNEX1206ENN-ML SNEX1206ENN-MM SNMX1206ENN-MM		Economical 8 corners     Low cutting load and excellent smooth cutting	E130
	75°	RM8EC(M)5000	11-1-3	Ø80~Ø400	SNEX1507ENN-MF SNMX1507ENN-MF SNEX1507ENN-ML	SNEX1507ENN-MM SNMX1507ENN-MM	*		E132
	88°	RM8QC(M)4000	A 18-37	Ø63~Ø200	SNEX1206QNN-MA SNEX1206QNN-MF SNMX1206QNN-MF SNEX1206QNN-ML SNEX1206QNN-MM SNMX1206QNN-MM	SNEX120612-MA SNEX120612-MF SNMX120612-MF SNEX120612-ML SNEX120612-MM SNMX120612-MM	•		E134

Туре	A.A	Designation	Shape	Cutter Diameter		Application		Features	Page
	45°	RMH8AC(M)4000		Ø50~Ø400	SNEX1206ANN-MA SNEX1206ANN-MF SNMX1206ANN-MF	SNEX1206ANN-ML SNEX1206ANN-MM SNMX1206ANN-MM SNEX1206ANN-W			E127
	45*	RMH8AC(M)5000		Ø80~Ø400	SNEX1507ANN-MF SNMX1507ANN-MF SNEX1507ANN-ML	SNEX1507ANN-MM SNMX1507ANN-MM			E129
RM8	75°	RMH8EC(M)4000		Ø50~Ø400	SNEX1206ENN-MA SNEX1206ENN-MF SNMX1206ENN-MF	SNEX1206ENN-ML SNEX1206ENN-MM SNMX1206ENN-MM		Economical 8 corners     Low cutting load and excellent smooth cutting	E131
	75	RMH8EC(M)5000		Ø80~Ø400	SNEX1507ENN-MF SNMX1507ENN-MF SNEX1507ENN-ML	SNEX1507ENN-MM SNMX1507ENN-MM			E133
	88°	RMH8QC(M)4000		Ø63~Ø200	SNEX1206QNN-MA SNEX1206QNN-MF SNMX1206QNN-MF SNEX1206QNN-ML SNEX1206QNN-MM SNMX1206QNN-MM	SNEX120612-MA SNEX120612-MF SNMX120612-MF SNEX120612-ML SNEX120612-MM SNMX120612-MM			E135
	45°	RMT8A(M) 4000/5000		Ø80~Ø315	SNCF1206ANN-MF SNCF1507ANN-MF SNMF1206ANN-MF SNMF1507ANN-MF	SNCF1206ANN-MM SNCF1507ANN-MM SNMF1206ANN-MM SNMF1507ANN-MM	•	• Economical 8	E136 E137
RMT8	75°	RMT8E(M) 4000/5000	9	Ø80~Ø315	SNCF1206ENN-MF SNCF1507ENN-MF SNMF1206ENN-MF SNMF1507ENN-MF	SNCF1206ENN-MM SNCF1507ENN-MM SNMF1206ENN-MM SNMF1507ENN-MM		Excellent tool life and surface toughness due to low cutting resistance and high rake edge geometry     Good performance with increased	E138 E139
	88°	RMT8Q(M)4000		Ø80~Ø315	SNCF1206QNN-MF	SNMF1206QNN-MF	•	chipping resistance and grade	E140

# E Rich Mill Table

Туре	A.A	Designation	Shape	Cutter Diameter		Application		Features	Page
RM8-X	45°	RMX8AC(M)-SA14		Ø50~Ø125	SAGX140808ANER-ML	SAGX140808ANER-MM SNMX140808ANER-MM		Double sided insert with 8 corners     Stable cutting performance due to double reversal positive relief surface     Good machinability in stainless cutting with High helix cutting edge	E141
RM14	51°	RM14XCM-XN06		Ø50~Ø160	XNMX0606XNR-ML	XNMX060608-ML	0	Reduced vibration with the application of maximum approach angle on heptangonal shape Stable clamping from wedge type clamping structure Available for multiple-staged cutting without interference of the cutter's side wall	E 142
RM16	45°	RM16AC(M) 6000/8000		Ø63~Ø400	ONHX060608-MF ONMX0606ANN-MF ONMX0606ANN-MF ONMX080608-MF ONMX080608-MF ONMX0806ANN-MF ONMX0806ANN-MF ONMX080608-ML ONHX080608-ML ONHX080608-MM	ONMX060608-MM ONHX0606ANN-MM ONMX0606ANN-MM ONHX080608-MM ONHX0806ANN-MM ONMX0806ANN-MM ONMX080668-MA ONHX060608-W ONHX080608-MA ONHX080608-W		Economical 16 corners     Wiper insert for surface roughness	E143 E144
RMR	-	RMRC(M)-RN12		Ø50~Ø125	RNMX1204M0E-ML		9	High cost efficiency due to double sided round typed cutting edge Excellent rotating prevention by strong clamping system Suitable for Inconel cutting	E145

## Shanks/Modulars

Туре	A.A	Designation	Shape	Cutter Diameter		Application		Features	Page
		RM3PS3000 @		Ø20~Ø40	XNKT060405PNER-ML	XNKT060405PNSR-MM			E102
RM3	90°	RM3PS4000 @		Ø32~Ø63	XNKT080508PNER-ML XNKT080508PNSR-MM XNKT080512PNSR-MM	XNKT080516PNSR-MM XNKT080520PNSR-MM	Ô	Economical 3 corners     Perfect perpendicular shouldering operation multimilling tool	E103
		RM3PM <sup>©©</sup> 3000/4000		Ø20~Ø50	XNKT060405PNER-ML XNKT060405PNSR-MM XNKT060408PNER-ML XNKT060408PNSR-MM XNCT080504PNFR-MA XNCT080514PNFR-MA XNCT080512PNFR-MA XNCT080520PNFR-MA	XNKT080508PNER-ML XNKT080508PNSR-MM XNKT080512PNER-ML XNKT080512PNSR-MM XNKT080516PNER-ML XNKT080516PNSR-MM XNKT080520PNSR-ML XNKT080520PNSR-MM			E104
		RM4PS3000		Ø14~Ø50	LNEX100605PNR-MF LNMX100605PNR-MF LNEX100605PNR-MM LNMX100605PNR-MM LNEX100608PNR-MF LNMX100608PNR-MF	LNEX100608PNR-MM LNMX100608PNR-MM LNEX100605PNR-MA LNEX100605PNL-MM LNMX100605PNL-MM		• Economical 4 corners	E115
		RM4PS4000		Ø32~Ø63	LNEX151004PNR-MF LNMX151004PNR-MF LNEX151004PNR-MM LNMX151004PNR-MM LNEX151008PNR-MF LNMX151008PNR-MF LNEX151008PNR-MM LNEX151008PNR-MM	LNEX151016PNR-MF LNMX151016PNR-MF LNEX151016PNR-MM LNMX151016PNR-MM LNEX151004PNR-MA LNEX151008PNR-MA LNEX151008PNL-MM LNMX151008PNL-MM		Screw on type for slotting, facing	E116
RM4	90°	RM4ZS3000	100	Ø25~Ø40	LNEX100605PNL-MM	LNMX100605PNL-MM		Economical 4 corners     Optimal insert application for vertical machining	E119
		RM4PM3000	The state of the s	Ø14~Ø50	LNEX100605PNR-MF LNMX100605PNR-MF LNEX100605PNR-MM LNMX100605PNR-MM LNEX100608PNR-MF LNMX100608PNR-MF	LNEX100608PNR-MM LNMX100608PNR-MM LNEX100605PNR-MA LNEX100605PNL-MM LNMX100605PNL-MM		Economical 4 corners     Screw on type for slotting, facing	E117
		RM4ZM3000		Ø25~Ø40	LNEX100605PNL-MM	LNMX100605PNL-MM		Economical 4 corners     Optimal insert application for vertical machining	E119


# E Rich Mill Table

#### Shanks/Modulars

Туре	A.A	Designation	Shape	Cutter Diameter	Application		Features	Page
		RM6PS-WN04		Ø20~Ø32	WNGX040304PNFR-MA WNGX040308PNFR-MA WNGX040312PNFR-MA WNGX040312PNFR-MA WNGX040304PNSR-MM WNGX040304PNER-ML WNGX040304PNER-ML WNGX040312PNSR-MM WNGX040308PNER-ML WNGX040316PNSR-MM			E122
RM6	90°	RM6PS-WN08	2.	Ø32~Ø50	WNGX080604PNFR-MA WNGX080608PNFR-MA WNGX080612PNFR-MA WNGX080612PNFR-MA WNGX080616PNER-ML WNGX080604PNSR-MM WNGX080620PNFR-MA WNGX080620PNSR-MM WNGX080604PNSR-MM WNGX080604PNER-ML WNGX080612PNSR-MM WNGX080608PNER-ML WNGX080620PNSR-MM WNGX080612PNER-ML		Improved productivity and high-quality	E123
RN	90	RM6PM-WN04 @		Ø20~Ø32	WNGX040304PNFR-MA WNGX040312PNER-ML WNGX040315PNFR-MA WNGX040316PNER-ML WNGX040316PNFR-MA WNGX040316PNFR-ML WNGX040304PNFR-ML WNGX040304PNFR-ML WNGX040316PNSR-MM WNGX040308PNER-ML WNGX040316PNSR-MM		shouldering through high speed and high feed machining	E124
		RM6PM-WN08		Ø32~Ø40	WNGX080604PNFR-MA WNGX080608PNFR-MA WNGX080612PNFR-MA WNGX080612PNFR-MA WNGX080616PNFR-MA WNGX080612PNFR-MA WNGX080604PNSR-MM WNGX080602PNFR-MA WNGX080612PNSR-MM WNGX080604PNSR-MM WNGX080612PNSR-MM WNGX080604PNSR-MM WNGX080612PNSR-MM WNGX080604PNSR-MM WNGX080604PNSR-MM WNGX080604PNSR-MM WNGX080604PNSR-MM WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080604PNFR-ML WNGX080616PNER-ML WNGX080616PNFR-ML WNGX080616PNFR-ML WNGX080616PNFR-ML WNGX080616PNFR-ML WNGX080616PNFR-ML WNGX080604PNSR-MM WNGX080616PNFR-ML WNGX080604PNSR-MM			E125
RMR		RMRS-RN12 <sup>©©</sup>		Ø32~Ø63	RNMX1204M0E-ML	9	High cost efficiency due to double sided round typed cutting edge     Excellent rotating prevention by strong clamping system     Suitable for Inconel cutting	E146

# RM3PC(M)3000 @





















														(mm)
Desi	gnation	<b>(</b>	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg
RM3PCM	3040HR	5	40	35	16	9	14	-	8.4	5.6	16	40	5.5	0.2
	3040HR-M	6	40	35	16	9	14	-	8.4	5.6	16	40	5.5	0.2
	3050HR	6	50	41	22	11	18	-	10.4	6.3	20	40	5.5	0.3
	3050HR-M	7	50	41	22	11	18	-	10.4	6.3	20	40	5.5	0.3
	3063HR	7	63	49	22	11	18	-	10.4	6.3	20	40	5.5	0.49
	3063HR-M	8	63	49	22	11	18	-	10.4	6.3	20	40	5.5	0.49
RM3PC	3080HR	8	80	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	25 (23)	50	5.5	0.87
(RM3PCM)	3080HR-M	10	80	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	25 (23)	50	5.5	0.88

( )Metric size

#### Available inserts




					Coated						Uncoated									
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
XNKT	060405PNER-ML									•	•	•		•	•	•				
	060405PNSR-MM								•	•	•	•		•	•	•				F00
	060408PNER-ML											•			•	•				E32
	060408PNSR-MM								•	•	•	•			•	•				

#### Available arbors

	Designation	Availabl	e arbors			
	Designation	RM3PC	RM3PCM			
RM3PC(M)	3040HR		PT C FMC16			
	3040HR-M	-	BT□□ -FMC16-□□			
	3050HR					
	3050HR-M		BT□□ -FMC22-□□			
	3063HR	- 	BILL -FMC22-LL			
-	3063HR-M					
	3080HR	BT□□-FMA25.4-□□	BT□□ -FMC27-□□			
	3080HR-M	1 DILL-FMA25.4-LL				

# RM3PC(M)4000 (W)





















• AR: -5° • RR: -8°~-6°

														(mm)
Desi	gnation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg
<b>RM3PCM</b>	4040HR	3	40	35	16	9	14	-	8.4	5.6	19	40	8.0	0.19
	4040HR-M	4	40	35	16	9	14	-	8.4	5.6	19	40	8.0	0.19
	4050HR	4	50	42	22	11	18	-	10.4	6.3	20	40	8.0	0.28
	4050HR-M	5	50	42	22	11	18	-	10.4	6.3	20	40	8.0	0.29
	4063HR	5	63	49	22	11	18	-	10.4	6.3	20	40	8.0	0.54
	4063HR-M	6	63	49	22	11	18	-	10.4	6.3	20	40	8.0	0.53
RM3PC	4080HR	5	80	57	25.4 (27)	14	20	35	9.5 (12.4)	6 (7)	25 (23)	50	8.0	1.08
(RM3PCM)	4080HR-M	7	80	57	25.4 (27)	14	20	35	9.5 (12.4)	6 (7)	25 (23)	50	8.0	1.06
	4100HR	7	100	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	33 (25)	63 (50)	8.0	1.68
	4100HR-M	8	100	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	33 (25)	63 (50)	8.0	1.67
4125HR		8	125	90	38.1 (40)	22	32	52	15.9 (16.4)	9 (10)	38 (29)	63	8.0	3.45
	4125HR-M	10	125	90	38.1 (40)	22	32	52	15.9 (16.4)	9 (10)	38 (29)	63	8.0	3.45

#### Available inserts


XNCT-MA

XNKT-ML









#### Available arbors

	Designation	Availabl	e arbors
	Designation	RM3PC	RM3PCM
RM3PC(M)	4040HR	-	BT□□ -FMC16-□□
	4050HR	_	BT□□ -FMC22-□□
	4063HR	-	DI
	4080HR	BT□□ -FMA25.4-□□	BT□□ -FMC27-□□
	4100HR	BT□□ -FMA31.75-□□	BT□□ -FMC32-□□
	4125HR	BT□□ -FMA38.1-□□	BT□□-FMC40-□□


#### Parts

Specification			
	Screw	Wrench	
Ø40~Ø125	FTNA0408	TW15S	

( )Metric size

# RM3PC(M)5000 @





















Desi	gnation	(a)	ØD	ØD2	Ød	Ød1	Ød2	Ødз	а	b	E	F	ар	kg
RM3PC 5080HR		5	80	57	25.4 (27)	14	20	35	9.5 (12.4)	6 (7)	24 (23)	50	12.0	0.84
(RM3PCM)	(RM3PCM) 5080HR-M 5100HR		80	57	25.4 (27)	14	20	35	9.5 (12.4)	6 (7)	24 (23)	50	12.0	0.84
			100	67	31.75 (32)	18	28	45	12.7 (14.4)	8 (8)	32 (25)	63	12.0	1.76
5100HR-M 5125HR		8	100	67	31.75 (32)	18	28	45	12.7 (14.4)	8 (8)	32 (25)	63	12.0	1.76
		8	125	90	38.1 (40)	22	32	52	15.9 (16.4)	9 (10)	38 (30)	63	12.0	2.70
5125HR-M		10	125	90	38.1 (40)	22	32	52	15.9 (16.4)	9 (10)	38 (30)	63	12.0	2.70

( )Metric size

### Available inserts




		Cer	met						C	coate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
XNCT	120608PNFR-MA																		•	
XNKT	120604PNSR-MM														•	•				
	120608PNER-ML										•	•		•	•	•				
	120608PNSR-MM								•	•	•	•		•	•	•				
	120612PNER-ML														•	•				E31
	120612PNSR-MM								•	•					•	•				E32
	120616PNER-ML														•	•				
	120616PNSR-MM								•	•					•	•				
	120620PNER-ML														•	•				
	120620PNSR-MM								•	•					•	•				

#### Available arbors

	Designation	Availabl	e arbors
	Designation	RM3PC	RM3PCM
RM3PC(M)	5080HR	BT□□ -FMA25.4-□□	BT□□ -FMC27-□□
	5100HR	BT□□ -FMA31.75-□□	BT□□ -FMC32-□□
	5125HR	BT□□ -FMA38.1-□□	BT□□ -FMC40-□□



# RM3PS3000 @W





De	esignation	0	ØD	Ød	Q	L	ар	kg	Fig.
RM3PS	3020HR-2S20	2	20	20	35	100	5.5	0.21	2
	3020HR-2L20	2	20	20	35	200	5.5	0.43	1
	3021HR-2S20	2	21	20	30	100	5.5	0.21	2
	3021HR-2L20	2	21	20	30	200	5.5	0.43	1
	3025HR-3S20	3	25	20	35	115	5.5	0.27	2
	3025HR-3L20	3	25	20	35	200	5.5	0.46	1
	3025HR-3S25	3	25	25	40	115	5.5	0.36	2
	3025HR-3L25	3	25	25	40	200	5.5	0.66	1
	3026HR-2S20	2	26	20	35	115	5.5	0.29	2
	3026HR-2L20	2	26	20	35	200	5.5	0.47	1
	3026HR-3S20	3	26	20	35	115	5.5	0.28	2
	3026HR-3L20	3	26	20	35	200	5.5	0.47	1
	3026HR-2S25	2	26	25	35	115	5.5	0.37	2
	3026HR-2L25	2	26	25	35	200	5.5	0.68	1
	3026HR-3S25	3	26	25	35	115	5.5	0.37	2
	3026HR-3L25	3	26	25	35	200	5.5	0.68	1
	3032HR-3S25	3	32	25	42	125	5.5	0.48	2
	3032HR-3L25	3	32	25	42	200	5.5	0.74	1
	3032HR-4S25	4	32	25	42	125	5.5	0.48	2
	3032HR-4L25	4	32	25	42	200	5.5	0.74	1
	3032HR-4S32	4	32	32	42	125	5.5	0.68	2
	3032HR-4L32	4	32	32	42	200	5.5	1.13	1
	3033HR-3S25	3	33	25	42	125	5.5	0.49	2
	3033HR-3L25	3	33	25	42	200	5.5	0.75	1
	3033HR-4S25	4	33	25	42	125	5.5	0.49	2
	3033HR-4L25	4	33	25	42	200	5.5	0.75	1
	3033HR-4S32	4	33	32	42	125	5.5	0.70	2
	3033HR-4L32	4	33	32	42	200	5.5	1.14	1
	3040HR-4S32	4	40	32	45	130	5.5	0.83	2
	3040HR-4L32	4	40	32	45	200	5.5	1.24	1
	3040HR-5S32	5	40	32	45	130	5.5	0.83	2
	3040HR-5L32	5	40	32	45	200	5.5	1.24	1


#### Available inserts

XNKT-ML	XNKT-MM
new	new

		Cer	met		Coated											Ur	ncoat	ed		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
XNKT	060405PNER-ML									•	•	•		•	•	•				
	060405PNSR-MM								•	•	•	•		•	•	•				E32
	060408PNER-ML											•			•	•				E3Z
	060408PNSR-MM								•	•	•	•			•	•				

Specification			
	Screw	Wrench	
Ø20~Ø40	FTNA0306	TW09S	

# RM3PS4000 new



						<b>Inn</b>			90°	• AR: -5° • RR: -11°~-7°
		Д					Ц	Л	30	• HH111-~-/

									(mm
D	esignation	©	ØD	Ød	Q	L	ар		Fig.
RM3PS	4032HR-3S32	3	32	32	42	125	8	0.67	2
	4032HR-3L32	3	32	32	42	200	8	1.11	1
	4033HR-3S32	3	33	32	42	125	8	0.68	2
	4033HR-3L32	3	33	32	42	200	8	1.13	1
	4040HR-3S32	3	40	32	42	130	8	0.8	2
	4040HR-3L32	3	40	32	42	200	8	1.21	1
	4040HR-4S32	4	40	32	42	130	8	0.81	2
	4040HR-4L32	4	40	32	42	200	8	1.22	1
	4050HR-4S32	4	50	32	42	135	8	0.99	2
	4050HR-4L32	4	50	32	42	200	8	1.38	1
	4050HR-4S40	4	50	40	42	135	8	1.32	2
	4050HR-4L40	4	50	40	42	200	8	1.94	1
	4050HR-5S32	5	50	32	42	135	8	1.02	2
	4050HR-5L32	5	50	32	42	200	8	1.4	1
	4050HR-5S40	5	50	40	42	135	8	1.35	2
	4050HR-5L40	5	50	40	42	200	8	1.96	1
	4063HR-5S32	5	63	32	42	135	8	1.31	2
	4063HR-5L32	5	63	32	42	200	8	1.7	1
	4063HR-5S40	5	63	40	42	135	8	1.64	2
	4063HR-5L40	5	63	40	42	200	8	2.25	1
	4063HR-6S32	6	63	32	42	135	8	1.31	2
	4063HR-6L32	6	63	32	42	200	8	1.7	1
	4063HR-6S40	6	63	40	42	135	8	1.64	2
	4063HR-6L40	6	63	40	42	200	8	2.26	1

#### Available inserts




		Car	met							oate	d						Hr	ncoat	-pd	
			met														UI	icoat	cu	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
XNCT	080504PNFR-MA																		•	
	080508PNFR-MA																		•	
	080512PNFR-MA																		•	
	080520PNFR-MA																			
XNKT	080504PNER-ML																			
	080504PNSR-MM																			
	080508PNER-ML						•								•					E31
	080508PNSR-MM						•		•						•	•				E32
	080512PNER-ML														•	•				
	080512PNSR-MM								•	•					•	•				
	080516PNER-ML														•	•				
	080516PNSR-MM								•	•					•	•				
	080520PNER-ML																			
	080520PNSR-MM									•					•	•				

Specification		No.	
	Screw	Wrench	
Ø32~Ø63	FTNA0408	TW15S	

# RM3PM3000/4000 000





















(mm)

De	esignation	©	ØD	Ød	Ød1	I	L	М	ар	kg \
RM3PM	3020HR-2-M10	2	20	18	10.5	30	50	M10	5.5	0.06
	3025HR-3-M12	3	25	21	12.5	35	58	M12	5.5	0.1
	3032HR-4-M16	4	32	29	17	40	66	M16	5.5	0.21
	3040HR-5-M16	5	40	29	17	40	66	M16	5.5	0.26
RM3PM	4032HR-3-M16	3	32	29	17	40	66	M16	8	0.21
	4040HR-4-M16	4	40	29	17	50	76	M16	8	0.33
	4050HR-5-M16	5	50	29	17	55	81	M16	8	0.49

#### Available inserts









			Cer	met						C	Coate	d						Ur	ncoat	ed	
	Desi	gnation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	HG4	page
	XNKT	060405PNER-ML									•	•	•		•	•	•				
3000		060405PNSR-MM								•	•	•	•		•	•	•				E32
type		060408PNER-ML																			E32
		060408PNSR-MM																			
	XNCT	080504PNFR-MA																			
		080508PNFR-MA																		•	
		080512PNFR-MA																		•	
		080520PNFR-MA																		•	
	XNKT	080504PNER-ML														•	•				
		080504PNSR-MM										•				•	•				
4000		080508PNER-ML						•			•	•	•		•	•	•				E31
type		080508PNSR-MM						•		•	•	•	•		•	•	•				E32
		080512PNER-ML														•	•				
		080512PNSR-MM								•	•					•	•				
		080516PNER-ML														•	•				
		080516PNSR-MM								•	•					•	•				
		080520PNER-ML														•	•				
		080520PNSR-MM								•	•					•	•				

#### Available adaptor

	Designation	Available adaptor
RM3PM	3020HR-2-M10	MAT-M10
	3025HR-3-M12	MAT-M12
	3032HR-4-M16	MAT-M16
	3040HR-5-M16	MAT-M16
<b>RM3PM</b>	4032HR-3-M16	MAT-M16
	4040HR-4-M16	MAT-M16
	4050HR-5-M16	MAT-M16


Designation: RM3PM4032HR-M16 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

Specification	Screw	Wrench	
Ø20~Ø40 (3000 type)	FTNA0306	TW09S	
Ø32~Ø50 (4000 type)	FTNA0408	TW15S	

# RM4PC(M)3000





















(mm)

Designati	ion	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Bolt
RM4PCM 3040	0HR	4	40	35	16	9	14	8.4	5.6	19	40	9.0	0.24	SB0825
3040	0HR-M	5	40	35	16	9	14	8.4	5.6	19	40	9.0	0.23	SB0825
3050	0HR	5	50	42	22	11	18	10.4	6.3	20	40	9.0	0.36	SB1025
3050	0HR-M	7	50	42	22	11	18	10.4	6.3	20	40	9.0	0.35	SB1025
306	3HR	7	63	49	22	11	18	10.4	6.3	20	40	9.0	0.61	SB1025
306	3HR-M	9	63	49	22	11	18	10.4	6.3	20	40	9.0	0.6	SB1025
RM4PC 3086	0HR	8	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (23)	50	9.0	1.25 (1.24)	SB1230
(RM4PCM) 3086	0HR-M	10	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (23)	50	9.0	1.24 (1.23)	SB1230
3100	0HR	9	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	33 (25)	63 (50)	9.0	2.46 (1.94)	SB1630
3100	0HR-M	12	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	33 (25)	63 (50)	9.0	2.44 (1.93)	SB1630

( )Metric size

#### Available inserts







LNM(E)X-MM

		Cer	met						(	Coate	d						Ur	icoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•			•	•				
	100605PNR-MA																		•	
	100608PNR-MF										•	•			•	•				
	100608PNR-MM											•			•	•				E11
LNMX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•	•		•	•				
	100608PNR-MF											•			•	•				
	100608PNR-MM										•				•	•				

#### Available arbors


Doois	notion	Available arbors							
Desig	nation	RM4PC	RM4PCM						
RM4PC(M)	3040HR		BT -FMC16-						
	3040HR-M	•							
	3050HR								
	3050HR-M	_	BT -FMC22-						
	3063HR	-	BILL-FIVIOZZ-LL						
	3063HR-M								


Dooig	nation	Available arbors								
Desig	nation	RM4PC	RM4PCM							
RM4PC(M)	3080HR	BT□□ -FMA25.4-□□	BT□□-FMC27-□□							
	3080HR-M	DI FIVIA23.4								
	3100HR	BT□□-FMA31.75-□□	BT□□-FMC32-□□							
	3100HR-M	DII WASI.75								

• · u			
Specification			
	Screw	Wrench	
Ø40~Ø100	FTKA0307	TW09S	

# RM4PC(M)4000





















(mm)

Desi	gnation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Bolt	Fig.
RM4PCM	4040HR	3	40	36	16	11	18	8.4	5.6	19	40	14	0.23	SB0825	1
	4050HR	3	50	46	22	11	18	10.4	6.3	20	40	14	0.36	SB1025	1
	4050HR-M	4	50	46	22	11	18	10.4	6.3	20	40	14	0.35	SB1025	1
	4050HR-H	5	50	46	22	11	18	10.4	6.3	20	40	14	0.36	SB1025	1
	4063HR	4	63	49	22	11	18	10.4	6.3	20	40	14	0.56	SB1025	1
	4063HR-M	6	63	49	22	11	18	10.4	6.3	20	40	14	0.57	SB1025	1
RM4PC	4080HR	5	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (23)	50	14	1.18 (1.16)	SB1230	1
(RM4PCM)	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (23)	50	14	1.17 (1.14)	SB1230	1
	4080HR-H	8	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (23)	50	14	1.17 (1.14)	SB1230	1
	4100HR	5	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	33 (25)	63 (50)	14	2.35 (1.84)	SB1630	1
	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	33 (25)	63 (50)	14	2.31 (1.82)	SB1630	1
	4100HR-H	9	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	33 (25)	63 (50)	14	2.31 (1.82)	SB1630	1
	4125HR	7	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9.0)	35 (30)	63	14	3.87 (3.79)	SB2040	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9.0)	35 (30)	63	14	3.82 (3.70)	SB2040	1
	4160R	8	160	107	50.8 (40)	-	100	19 (16.4)	11 (9.0)	38 (32)	63	14	5.0 (4.75)	MBA	2
	4160R-M	12	160	107	50.8 (40)	-	100	19 (16.4)	11 (9.0)	38 (32)	63	14	4.97 (4.71)	MBA	2

( )Metric size

### Available inserts

LNEX-MA

LNM(E)X-MF

LNM(E)X-MM







		Cerme	t		Co	ate	t				Uncoated				Cermet				Coa	ted			Uncoate	i
D	esignation	CN2500 CN30	NC5330	$\circ$	PC2505	PC2010	PC6510	PC9530	PC9540 PC5300	PC5400	ST30A H01	page	e Designation		CN2500 CN30	NC5330 NCM325	NCM335	NCM545	PC2505	0 1	PC9530		ST30A H01	page
LNEX	151004PNR-MF						•		•	•			LNMX	151004PNR-MF						• (		•	•	
	151004PNR-MM								•					151004PNR-MM									•	
	151004PNR-MA							П			•			151008PNR-MF						• (		•	•	
	151008PNR-MF						•	П	•	•		E11		151008PNR-MM						•	•	•	•	E11
	151008PNR-MM					•	•		•	•		EII		151016PNR-MF								•	•	EII
	151008PNR-MA										•			151016PNR-MM						• (			•	1
	151016PNR-MF								•	•														7
	151016PNR-MM						•			•														

#### Available arbors


Dooin	notion	Available arbors						
Desig	nation	RM4PC	RM4PCM					
RM4PC(M)	4050HR							
` ,	4050HR-M		BT□□-FMC22-□□					
	4063HR	_	BI UU-FIVICZZ-UU					
	4063HR-M							
	4080HR	BT□□-FMA25.4-□□	BT - FMC27-					
	4080HR-M	DIFIVIA23.4						


Doois	notion	Available arbors						
Desig	gnation	RM4PC	RM4PCM					
RM4PC(M)	4100HR	BT - FMA31.75-	BT -FMC32-					
	4100HR-M	BILL-I WAST.75-LL						
	4125HR	BT -FMA38.1-						
	4125HR-M	DILL-FIVIASO.I-LL	BT□□-FMB40-□□					
	4160R	BT -FMA50.8-	BT FMC40-					
	4160R-M	BILL-FIVIASU.0-LL						

Specification			
	Screw	Wrench	
Ø50~Ø160	FTKA0412B	TW15S	

### RM4PFCB3000







(mm)

Desi	ignation	0	ØD	ØD2	Ød	а	b	E	F	W	T-max
RM4PFCB	308015R	10	80	40	25.4	9.5	6	25	50	15	19
	308017R 1 310015R 1		80	40	25.4	9.5	6	25	50	17	19
	310015R		100	54	31.75	12.7	8	32	50	15	22
	310017R	12	100	54	31.75	12.7	8	32	50	17	22
	312515R	14	125	70	38.1	15.9	10	38	60	15	26
	312517R	14	125	70	38.1	15.9	10	38	60	17	26
	316015R	16	160	70	38.1	15.9	10	38	60	15	44
	316017R	16	160	70	38.1	15.9	10	38	60	17	44

#### Available inserts

LNM(E)X-MM



		Cer	met		Coated													ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	100605PNR-MM										•	•			•	•				
	100605PNL-MM											•			•	•				F44
LNMX	100605PNR-MM										•	•	•		•	•				E11
	100605PNL-MM										•	•			•	•				

#### Available arbors


	Designation	Available arbors
RM4PFCB	308015R	BT□□ -FMA25.4-□□
	308017R	DI
	310015R	BT□□ -FMA31.75-□□
	310017R	DILL-PWASI.73-LL
	312515R	
	312517R	BT□□ -FMA38.1-□□
	316015R	
	316017R	


Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0307	TW09S	



### RM4PFCB4000







(mm)

Desi	gnation	0	ØD	ØD2	Ød	а	b	Е	F	W	T-max
RM4PFCB	408022R	6	80	40	25.4	9.5	6	25	50	22	19
	408024R	6	80	40	25.4	9.5	6	25	50	24	19
	408026R	6	80	40	25.4	9.5	6	25	50	26	19
	408028R	6	80	40	25.4	9.5	6	25	50	28	19
	410022R	8	100	54	31.75	12.7	8	32	50	22	22
	410024R	8	100	54	31.75	12.7	8	32	50	24	22
	410026R	0026R 8		54	31.75	12.7	8	32	50	26	22
	410028R	8	100	54	31.75	12.7	8	32	50	28	22
	412522R	10	125	70	38.1	15.9	10	38	60	22	26
	412524R	10	125	70	38.1	15.9	10	38	60	24	26
	412526R	10	125	70	38.1	15.9	10	38	60	26	26
	412528R	10	125	70	38.1	15.9	10	38	60	28	26
	416022R	12	160	70	38.1	15.9	10	38	60	22	44
	416024R	12	160	70	38.1	15.9	10	38	60	24	44
	416026R	12	160	70	38.1	15.9	10	38	60	26	44
	416028R	12	160	70	38.1	15.9	10	38	60	28	44

#### Available inserts

LNM(E)X-MM



		Cer	met		Coated Uncoated								ed							
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	151008PNR-MM										•	•			•	•				
	151008PNL-MM											•			•	•				F44
LNMX	151008PNR-MM						•				•	•	•		•	•				E11
	151008PNL-MM														•	•				

#### Available arbors


De	esignation	Available arbors
RM4PFCB	408022R	
	408024R	BT□□ -FMA25.4-□□
	408026R	
	408028R	
	410022R	
	410024R	BT□□ -FMA31.75-□□
	410026R	
	410028B	


De	esignation	Available arbors
RM4PFCB	412522R	
	412524R	
	412526R	
	412528R	BT - FMA38.1-
	416022R	BILL -FINA38.1-LL
	416024R	
	416026R	
	416028R	

Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0412B	TW15S	

### RM4PHCB3000







(mm)

Desi	gnation	0	ØD	ØD2	Ød	а	b	E	F	W	T-max
RM4PHCB	308015R	10	80	40	25.4	9.5	6	25	50	15	19
	310015R	12	100	54	31.75	12.7	8	32	50	15	22
	312515R	14	125	70	38.1	15.9	10	38	60	15	26
	316015R	16	160	70	38.1	15.9	10	38	60	15	44

#### Available inserts

.001.10				
	LNEX-MA	LNM(E)X-MF	LNM(E)X-MM	
		3		

			met														Uncoated			
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 1	page
LNEX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•			•	•				
	100605PNR-MA																		•	
	100608PNR-MF										•	•			•	•				
	100608PNR-MM											•			•	•				E11
LNMX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•	•		•	•				
	100608PNR-MF											•			•	•				
	100608PNR-MM										•				•	•				

#### Available arbors

	Designation	Available arbors
RM4PHCB	308015R	BT□□ -FMA25.4-□□
	310015R	BT□□ -FMA31.75-□□
	312515R	BT□□-FMA38.1-□□
	316015R	BIFMA38.1


<b>.</b>			
Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0307	TW09S	






### RM4PHCB4000







(mm)

Desig	gnation	<b>(</b>	ØD	ØD2	Ød	а	b	E	F	W	T-max
RM4PHCB	408020R	6	80	40	25.4	9.5	6	25	50	20	19
	410020R	8	100	54	31.75	12.7	8	32	50	20	22
	412520R	10	125	70	38.1	15.9	10	38	60	20	26
	416020R	12	160	70	38.1	15.9	10	38	60	20	44

#### Available inserts

LNEX-MA LNM(E)X-MM







		Cer	met						C	coate	d						U	ncoa	ted	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	문	page
LNEX	151004PNR-MF											•			•	•				
	151004PNR-MM											•			•	•				
	151004PNR-MA																		•	
	151008PNR-MF											•			•	•				
	151008PNR-MM										•	•			•	•				
	151008PNR-MA																		•	
	151016PNR-MF											•			•	•				E11
	151016PNR-MM											•			•	•				
LNMX	151004PNR-MF										•	•			•	•				
	151004PNR-MM											•				•				
	151008PNR-MF						•				•	•			•	•				
	151008PNR-MM						•				•	•	•		•	•				
	151016PNR-MF											•			•	•				
	151016PNR-MM											•				•				


#### Available arbors


	Designation	Available arbors
RM4PHCB	408020R	BT□□ -FMA25.4-□□
	410020R	BT□□ -FMA31.75-□□
	412520R	BT□□ -FMA38.1-□□
	416020R	DILL-FMA30.1-LL

Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0412B	TW15S	

### RM4PFCP3000







(mm)

Desi	gnation	©	ØD	ØD2	Ød	а	b	E	W	T-max
RM4PFCP	308015R	10	80	41.5	25.4	6.35	28	15	15	17
	308017R	10	80	41.5	25.4	6.35	28	17	17	17
	310015R	12	100	48	31.75	7.94	35.2	15	15	24
	310017R	12	100	48	31.75	7.94	35.2	17	17	24
	312515R	14	125	58	38.1	9.53	42.3	15	15	32
	312517R	14	125	58	38.1	9.53	42.3	17	17	32
	316015R	16	160	58	38.1	9.53	42.3	15	15	49
	316017R	16	160	58	38.1	9.53	42.3	17	17	49

#### Available inserts

LNM(E)X-MM



		Cei	rmet		Coated Un												icoat	ed		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	100605PNR-MM										•	•			•	•				
	100605PNL-MM											•			•	•				
LNMX	100605PNR-MM										•	•	•		•	•				E11
	100605PNL-MM										•	•			•	•				

#### Available arbors


	Designation	Available arbors
RM4PFCP	308015R	BT□□-SCA25.4-□□
	308017R	BI3CA23.4
	310015R	BT□□-SCA31.75-□□
	310017R	B13CA31./3
	312515R	
	312517R	BT□□-SCA38.1-□□
	316015R	BI3CA30. I
	316017R	


Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0307	TW09S	



### RM4PFCP4000







(mm)

Desi	gnation	<b>©</b>	ØD	ØD2	Ød	а	b	E	W	T-max
RM4PFCP	408022R	6	80	41.5	25.4	6.35	28	22	22	17
	408024R	6	80	41.5	25.4	6.35	28	24	24	17
	408026R	6	80	41.5	25.4	6.35	28	26	26	17
	408028R	6	80	41.5	25.4	6.35	28	28	28	17
	410022R	8	100	48	31.75	7.94	35.2	22	22	24
	410024R	8	100	48	31.75	7.94	35.2	24	24	24
	410026R	8	100	48	31.75	7.94	35.2	26	26	24
	410028R	8	100	48	31.75	7.94	35.2	28	28	24
	412522R	10	125	58	38.1	9.53	42.3	22	22	32
	412524R	10	125	58	38.1	9.53	42.3	24	24	32
	412526R	10	125	58	38.1	9.53	42.3	26	26	32
	412528R	10	125	58	38.1	9.53	42.3	28	28	32
	416022R	12	160	58	38.1	9.53	42.3	22	22	49
	416024R	12	160	58	38.1	9.53	42.3	24	24	49
	416026R	12	160	58	38.1	9.53	42.3	26	26	49
	416028R	12	160	58	38.1	9.53	42.3	28	28	49

#### Available inserts

LNM(E)X-MM



		Cer	met		Coated											Uı	ncoat	ed		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H0.1	page
LNEX	151008PNR-MM										•	•			•	•				
	151008PNL-MM											•			•	•				E11
LNMX	151008PNR-MM						•				•	•	•		•	•				EII
	151008PNL-MM														•	•				

#### Available arbors


De	signation	Available arbors
RM4PFCP	408022R	
	408024R	BT□□-SCA25.4-□□
	408026R	B1
	408028R	
	410022R	
	410024R	BT□□ -SCA31.75-□□
	410026R	BI3CA31.75
	410028R	


De	signation	Available arbors
RM4PFCP	412522R	
	412524R	
	412526R	
	412528R	PTCC CCASO 4 CC
	416022R	BT□□-SCA38.1-□□
	416024R	
	416026R	
	416028R	

Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0412B	TW15S	

### RM4PHCP3000







(mm)

Desi	gnation	<b>(</b>	ØD	ØD2	Ød	а	b	E	W	T-max
RM4PHCP	308015R	10	80	41.5	25.4	6.35	28	16.5	15.1	17
	310015R	12	100	48	31.75	7.94	35.2	16.5	15.1	24
	312515R	14	125	58	38.1	9.52	42.3	16.5	15.1	32
	316015R	16	160	58	38.1	9.52	42.3	16.5	15.1	49

#### Available inserts

LNM(E)X-MF LNM(E)X-MM LNEX-MA

1	

		Cer	met						C	oate	d						Uı	ncoat	ed	
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•			•	•				
	100605PNR-MA																		•	
	100608PNR-MF										•	•			•	•				
	100608PNR-MM											•			•	•				E11
LNMX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•	•		•	•				
	100608PNR-MF											•			•	•				1
	100608PNR-MM										•				•	•				

#### Available arbors


	Designation	Available arbors
RM4PHCP	308015R	BT□□ -SCA25.4-□□
310015R		BT□□ -SCA31.75-□□
	312515R	BT□□-SCA38.1-□□
	316015R	DI5CA38.1


Specification		
	Screw	Wrench
Ø80~Ø160	FTKA0307	TW09S



### RM4PHCP4000







(mm)

Desi	gnation	0	ØD	ØD2	Ød	а	b	E	W	T-max
RM4PHCP	408020R	6	80	41.5	25.4	6.35	28	22	19.8	17
	410020R	8	100	48	31.75	7.94	35.2	22	19.8	24
	412520R	10	125	58	38.1	9.53	42.3	22	19.8	32
	416020R	12	160	58	38.1	9.53	42.3	22	19.8	49

#### Available inserts

LNEX-MA LNM(E)X-MF LNM(E)X-MM

		Cer	met						C	oate	d						Uı	ncoat	ted	
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	151004PNR-MF											•			•	•				
	151004PNR-MM											•			•	•				
	151004PNR-MA																			
	151008PNR-MF											•			•	•				
	151008PNR-MM										•	•			•	•				
	151008PNR-MA																			
	151016PNR-MF											•			•	•				E11
	151016PNR-MM											•			•	•				E11
LNMX	151004PNR-MF										•	•			•	•				
	151004PNR-MM											•				•				
	151008PNR-MF						•				•	•			•	•				
	151008PNR-MM						•				•	•			•	•				
	151016PNR-MF											•			•	•				
	151016PNR-MM											•				•				


#### Available arbors

	Designation	Available arbors
RM4PHCP	408020R	BT □ -SCA25.4- □ □
	410020R	BT□□ -SCA31.75-□□
	412520R	BT□□ -SCA38.1-□□
	416020R	- DI 3CA30.1

Specification			
	Screw	Wrench	
Ø80~Ø160	FTKA0412B	TW15S	

### RM4PS3000



















(mm)

D	Designation	©	ØD	Ød	Q	L	ар	kg
RM4PS	3014HR-S16	1	14	16	23	90	9.0	0.11
	3016HR-S16	1	16	16	25	90	9.0	0.11
	3018HR-S16	2	18	16	23	90	9.0	0.12
	3020HR-S20	2	20	20	30	100	9.0	0.21
	3020HR-S20M	3	20	20	30	100	9.0	0.21
	3025HR-S25	2	25	25	35	115	9.0	0.38
	3025HR-S25M	3	25	25	35	115	9.0	0.38
	3032HR-S32	3	32	32	40	125	9.0	0.69
	3032HR-S32M	4	32	32	40	125	9.0	0.7
	3040HR-S32	4	40	32	42	130	9.0	0.86
	3040HR-S32M	5	40	32	42	130	9.0	0.85
	3040HR-S40	4	40	40	42	130	9.0	1.17
	3040HR-S40M	5	40	40	42	130	9.0	1.17
	3040HR-S42	4	40	42	42	130	9.0	1.26
	3040HR-S42M	5	40	42	42	130	9.0	1.25
	3050HR-S32	5	50	32	45	135	9.0	1.06
	3050HR-S32M	7	50	32	45	135	9.0	1.05
	3050HR-S40	5	50	40	45	135	9.0	1.38
	3050HR-S40M	7	50	40	45	135	9.0	1.37
	3050HR-S42	5	50	42	45	135	9.0	1.48
	3050HR-S42M	7	50	42	45	135	9.0	1.48

#### Available inserts

LNEX-MA L

LNM(E)X-MF

LNM(E)X-MM








												•								
		Cer	met						C	Coate	d						U	ncoat	ted	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	F9	page
LNEX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•			•	•				
	100605PNR-MA																		•	
	100605PNL-MM										•	•			•	•				
	100608PNR-MF											•			•	•				E11
	100608PNR-MM											•			•	•				_ EII
LNMX	100605PNR-MF										•	•	•		•	•				
	100605PNR-MM											•			•	•				1
100608PNR-MF	100608PNR-MF										•				•	•				
	100608PNR-MM											•	•							

Specification			
	Screw	Wrench	
Ø14~Ø50	FTKA0307	TW09S	



### RM4PS4000

















• AR: -6° • RR: -24°~-14°

(mm)

D	esignation	<b>(</b>	ØD	Ød	Q	L	ар	kg
RM4PS	4032HR-S32	2	32	32	40	125	14	0.68
	4032HR-S32M	3	32	32	40	125	14	0.69
	4040HR-S32	3	40	32	42	125	14	0.83
	4040HR-S32M	4	40	32	42	125	14	0.83
	4040HR-S40	3	40	40	42	125	14	1.14
	4040HR-S42	3	40	42	42	125	14	1.23
	4050HR-S32	3	50	32	45	125	14	1.02
	4050HR-S32M	4	50	32	45	125	14	1.02
	4050HR-S40	3	50	40	45	125	14	1.35
	4050HR-S40M	4	50	40	45	125	14	1.34
	4050HR-S42	3	50	42	45	125	14	1.45
	4050HR-S42M	4	50	42	45	125	14	1.45
	4063HR-S32	4	63	32	45	125	14	1.25
	4063HR-S32M	6	63	32	45	125	14	1.24
	4063HR-S40	4	63	40	45	125	14	1.62
	4063HR-S40M	6	63	40	45	125	14	1.61
	4063HR-S42	4	63	42	45	125	14	1.71
4063HR-S42M		6	63	42	45	125	14	1.7

#### Available inserts

LNEX-MA

LNM(E)X-MF

LNM(E)X-MM








		Cer	met						(	Coate	d						Uı	ncoat	ted	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 1	page
LNEX	151004PNR-MF											•			•	•				
	151004PNR-MM											•			•	•				
	151004PNR-MA																		•	
	151008PNR-MF											•			•	•				
	151008PNR-MM										•	•			•	•				
	151008PNR-MA																		•	
	151016PNR-MF											•			•	•				E11
	151016PNR-MM											•			•	•				
LNMX	151004PNR-MF										•	•			•	•				
	151004PNR-MM											•				•				
	151008PNR-MF						•				•	•			•	•				
	151008PNR-MM						•				•	•	•		•	•				
	151016PNR-MF											•			•	•				
	151016PNR-MM											•				•				1

Specification			
	Screw	Wrench	
Ø32~Ø63	FTKA0412B	TW15S	

### **RM4PM3000**



















(mm)

De	esignation	<b>©</b>	ØD	Ød	Ød1	Q	L	М	ар	kg
RM4PM	3014HR-M06	1	14	12	6.5	25	40	M06	9.0	0.02
	3016HR-M08	1	16	14.5	8.5	25	42	M08	9.0	0.02
	3018HR-M08	2	18	14.5	8.5	25	42	M08	9.0	0.03
	3020HR-M10	2	20	18	10.5	30	51	M10	9.0	0.06
	3025HR-M12	2	25	23	12.5	35	59	M12	9.0	0.11
	3032HR-M16	3	32	29	17	40	67	M16	9.0	0.21
	3040HR-M16	4	40	29	17	40	67	M16	9.0	0.26
	3050HR-M16	5	50	30	17	45	72	M16	9.0	0.41

#### Available inserts

LNEX-MA

LNM(E)X-MF

LNM(E)X-MM







		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•			•	•				
	100605PNR-MA																		•	
	100608PNR-MF										•	•			•	•				
	100608PNR-MM											•			•	•				E11
LNMX	100605PNR-MF											•			•	•				
	100605PNR-MM										•	•	•		•	•				
	100608PNR-MF											•			•	•				
	100608PNR-MM										•				•	•				

#### Available adaptor


	Designation	Available adaptor
RM4PM	3014HR-M06	MAT-M06
	3016HR-M08	MAT-M08
	3018HR-M08	IVIAT-IVIU8
	3020HR-M10	MAT-M10
	3025HR-M12	MAT-M12
	3032HR-M16	
	3040HR-M16	MAT-M16
	3050HR-M16	

Designation : RM4PM3032HR-M16 Modular head threading measure size (M16)

П

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)


• • • • • • • • • • • • • • • • • • • •			
Specification			
	Screw	Wrench	
Ø14~Ø50	FTKA0307	TW09S	





## RM4ZC(M)3000/4000





















(mm)

Des	ignation	(i)	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	ae	
RM4ZCM	3040HR	4	40	37	16	9	14	-	8.4	5.6	19	40	1.5	9.0	0.21
	3050HR	5	50	47	22	11	18	-	10.4	6.3	20	40	1.5	9.0	0.33
	3052HR	5	52	48	22	11	18	-	10.4	6.3	20	40	1.5	9.0	0.37
	4063HR	5	63	58	22	11	18	-	10.4	6.3	20	40	2.5	14.0	0.56
RM4ZC	4066HR	5	66	61	25.4 (27)	14	20	-	9.5 (12.4)	6 (7)	25	50	2.5	14.0	0.74
(RM4ZCM)	4080HR	6	80	70	25.4 (27)	14	20	35	9.5 (12.4)	6 (7)	25 (23)	50	2.5	14.0	1.09
	4100HR	7	100	80	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	25 (33)	63 (50)	2.5	14.0	1.71

( )Metric size

#### Available inserts

LNM(E)X-MM



			Cer	met						C	oate	d						Ur	ncoat	ed	
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page	
3000	LNEX	100605PNL-MM											•			•	•				
type	LNMX	100605PNL-MM										•	•			•	•				F44
4000	LNEX	151008PNL-MM											•			•	•				E11
type	LNMX	151008PNL-MM														•	•				


#### Available arbors

	Designation	Availabl	e arbors
	Designation	RM4ZC	RM4ZCM
RM4ZCM	3040HR		MC16-□□ CA16-□□
	3050HR 3052HR	BT□□-FI	MC22-□□
RM4ZCM	4063HR	BT□□-FI	MC22-□□
RM4ZC(M)	4066HR	BT□□ -FMA25.4-□□	BT□□ -FMC27-□□
	4080HR		
	4100HR	BT□□ -FMA31.75-□□ BT□□ -SCA31.75-□□	BT□□ -FMC32-□□

Specification	OMM)		
	Screw	Wrench	
052 (3000 type)	FTKA0307	TW09S	
3~Ø100 (4000 type)	FTKA0412B	TW15S	

### RM4ZS3000






















(mm)

De	signation	©	ØD	Ød	Q	L	ар	ae	O kg
RM4ZS	3025HR-L25	2	25	25	120	200	1.5	9.0	0.62
	3032HR-L32	3	32	32	120	210	1.5	9.0	1.13
	3040HR-L32	4	40	32	120	250	1.5	9.0	1.53

### RM4ZM3000





















•AR : -11° •RR : -17°~-14°

(mm)


Des	signation	0	ØD	Ød	Ød1	Q	L	М	ар	ae	
RM4ZM	3025HR-M12	2	25	23	12.5	35	59	M12	1.5	9.0	0.11
	3032HR-M16	3	32	29	17	40	67	M16	1.5	9.0	0.21
	3040HR-M16	4	40	29	17	40	67	M16	1.5	9.0	0.28

#### Available inserts

LNM(E)X-MM




		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation		CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNEX	100605PNL-MM											•			•	•				E11
LNMX	100605PNL-MM										•	•			•	•				



# RM6PCM-WN04





















(mm)

D	Designation	©	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	Е	F	ар		Available screw
RM6PCM	040R-16-6-WN04	6	40	35	16	9	14	-	8.4	5.6	19	40	4.3	0.19	ETNA02506
	040R-16-7-WN04	7	40	35	16	9	14	-	8.4	5.6	19	40	4.3	0.19	ETNA02506
	050R-22-8-WN04	8	50	42	22	11	18	-	10.4	6.3	20	40	4.3	0.28	ETNA02506
	050R-22-9-WN04	9	50	42	22	11	18	-	10.4	6.3	20	40	4.3	0.28	ETNA02506
	063R-22-10-WN04	10	63	49	22	11	18	-	10.4	6.3	20	40	4.3	0.47	ETNA02506
	063R-22-11-WN04	11	63	49	22	11	18	-	10.4	6.3	20	40	4.3	0.47	ETNA02506

#### Available inserts

WNGX-MA

WNGX-ML

WNGX-MM







		Cer	met						C	oate	d						Uı	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
WNGX	040304PNFR-MA																		•	
	040308PNFR-MA																			
	040312PNFR-MA																		•	
	040316PNFR-MA																		•	
	040304PNER-ML											•		•	•	•				
	040308PNER-ML														•	•				E30
	040312PNER-ML														•					L30
	040316PNER-ML														•					
	040304PNSR-MM											•			•	•				
	040308PNSR-MM														•	•				
	040312PNSR-MM														•					
	040316PNSR-MM														•					


#### Available arbors

	Designation	NC arbors
RM6PCM	040R-16-6-WN04	BT□□-FMC16-□□
	040R-16-7-WN04	
	050R-22-8-WN04	
	050R-22-9-WN04	BT□□-FMC22-□□
	063R-22-10-WN04	- 
	063R-22-11-WN04	

Specification			
	Screw	Wrench	
Ø40~Ø63	ETNA02506	TW07S	

## RM6PC(M)-WN08



















• AR: -6° • RR: -14°~-11°

(mm)

															(11111)
	Designation	<b>(</b>	ØD	ØD2	Ød	Ød1	Ød2	Ø <b>d</b> 3	а	b	E	F	ар	kg	Available screw
RM6PCM	050R-22-4-WN08	4	50	42	22	11	18	-	10.4	6.3	20	40	8.2	0.28	FTNA0513
	050R-22-5-WN08	5	50	42	22	11	18	-	10.4	6.3	20	40	8.2	0.27	FTNA0511
	063R-22-5-WN08	5	63	49	22	11	18	-	10.4	6.3	20	40	8.2	0.45	FTNA0513
	063R-22-6-WN08	6	63	49	22	11	18	-	10.4	6.3	20	40	8.2	0.45	FTNA0513
	080R-27-7-WN08	7	80	57	27	14	20	35	12.4	7	23	50	8.2	0.90	FTNA0513
	080R-27-9-WN08	9	80	57	27	14	20	35	12.4	7	23	50	8.2	0.89	FTNA0511
	100R-32-8-WN08	8	100	67	32	18	26	42	14.4	8	25	50	8.2	1.47	FTNA0513
	100R-32-11-WN08	11	100	67	32	18	26	42	14.4	8	25	50	8.2	1.45	FTNA0511
	125R-40-11-WN08	11	125	90	40	22	32	52	16.4	9	29	63	8.2	2.94	FTNA0513
	125R-40-14-WN08	14	125	90	40	22	32	52	16.4	9	29	63	8.2	2.91	FTNA0511
RM6PC	080R-25.4-7-WN08	7	80	57	25.4	14	20	35	9.5	6	25	50	8.2	0.91	FTNA0513
	080R-25.4-9-WN08	9	80	57	25.4	14	20	35	9.5	6	25	50	8.2	0.91	FTNA0511
	100R-31.75-8-WN08	8	100	67	31.75	18	26	42	12.7	8	32	63	8.2	1.69	FTNA0513
	100R-31.75-11-WN08	11	100	67	31.75	18	26	42	12.7	8	32	63	8.2	1.73	FTNA0511
	125R-38.1-11-WN08	11	125	90	38.1	22	32	52	15.9	10	35	63	8.2	1.98	FTNA0513
	125R-38.1-14-WN08	14	125	90	38.1	22	32	52	15.9	10	35	63	8.2	2.90	FTNA0511

#### Available inserts

WNGX-MA

WNGX-ML

WNGX-MM







		Cermet			Co	ated				Uncoate	d			Cermet			C	oate	ed			Uncoated	
1	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545 PC2505	PC2010 PC3700	PC6510 PC9530	PC9540	PC5300	ST30A H01	page	ı	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC2010	PC3700 PC6510	PC9530 PC9540	PC5300 PC5400	ST30A H01	page
WNGX	080604PNFR-MA									•	)	WNGX	080616PNER-ML								•		
	080608PNFR-MA									•	)		080620PNER-ML								•		
	080612PNFR-MA												080604PNSR-MM						•		• •		
	080616PNFR-MA										E30		080608PNSR-MM			•	)		• •		• •		E30
	080620PNFR-MA										E30		080612PNSR-MM								•		E30
	080604PNER-ML					•		•	•				080616PNSR-MM								•		
	080608PNER-ML			•		•	•	•	9 0				080620PNSR-MM								•		
	080612PNER-ML																						

#### Available arbors

	Designation	NC arbors
RM6PC	080R-25.4-7-WN08	BT - FMA25.4-
	080R-25.4-9-WN08	BIFIVIA25.4
	100R-31.75-8-WN08	BT□□-FMA31.75-□□
	100R-31.75-11-WN08	B11 WA31.73
	125R-38.1-11-WN08	BT□□-FMA38.1-□□
	125R-38.1-14-WN08	BIFIVIA36.1
RM6PCM	050R-22-4-WN08	BT□□-FMC22-□□
	050R-22-5-WN08	


	Designation	NC arbors
RM6PCM	063R-22-5-WN08	BT□□-FMC22-□□
	063R-22-6-WN08	BI LL-FIVICZZ-LL
	080R-27-7-WN08	BT□□-FMC27-□□
	080R-27-9-WN08	BIFIVIOZ7
	100R-32-8-WN08	BT□□-FMC32-□□
	100R-32-11-WN08	BTFIVIC32
	125R-40-11-WN08	BT□□-FMC40-□□
	125R-40-14-WN08	

Specification		Mary	
	Screw	Wrench	
Ø50~Ø125	FTNA0511/FTNA0513	TW20-100	



## RM6PS-WN04



















• AR: -6° • RR: -20°~-14°

(mm)

	Designation	0	ØD	Ød	Q	L	ар	(kg	Available screw
RM6PS	020R-2W20-110-WN04	2	20	20	35	110	4.3	0.22	ETNA02506
	020R-3W20-110-WN04	3	20	20	35	110	4.3	0.22	ETNA02506
	025R-3W25-110-WN04	3	25	25	35	110	4.3	0.36	ETNA02506
	025R-4W25-110-WN04	4	25	25	35	110	4.3	0.35	ETNA02506
	032R-5W32-110-WN04	5	32	32	35	110	4.3	0.60	ETNA02506
	032R-6W32-110-WN04	6	32	32	35	110	4.3	0.60	ETNA02506

#### Available inserts


WNGX-MA WNGX-ML WNGX-MM

		Cer	met					C	Coate	d					Ur	ncoat	ed	
Designation		CN2500	CN30	NC5330	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H21	page
WNGX	040304PNFR-MA																•	
	040308PNFR-MA																	
	040312PNFR-MA																•	
	040316PNFR-MA																•	
	040304PNER-ML									•		•	•	•				
	040308PNER-ML												•	•				E30
	040312PNER-ML												•					E30
	040316PNER-ML												•					
	040304PNSR-MM									•			•	•				
	040308PNSR-MM												•	•				
	040312PNSR-MM												•					
	040316PNSR-MM												•					

Specification Screw Wrench
<b>Ø20~Ø32</b> ETNA02506 TW07S

## RM6PS-WN08



















• AR: -6° • RR: -20°~-14°

(mm)

	Designation	<b>©</b>	ØD	Ød	Q	L	ар	kg	Available screw
RM6PS	032R-2W32-120-WN08	2	32	32	40	120	8.2	0.65	FTNA0513
	040R-3W32-120-WN08	3	40	32	40	120	8.2	0.69	FTNA0513
	040R-4W32-120-WN08	4	40	32	40	120	8.2	0.69	FTNA0513
	050R-4W32-120-WN08	4	50	32	40	120	8.2	0.76	FTNA0513
	050R-5W32-120-WN08	5	50	32	40	120	8.2	0.76	FTNA0513

#### Available inserts


WNGX-MA WNGX-ML





		Cermet Coated									Uı	ncoat	ted							
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	돧	page
WNGX	080604PNFR-MA																		•	
	080608PNFR-MA																		•	
	080612PNFR-MA																			
	080616PNFR-MA																		•	
	080620PNFR-MA																		•	
	080604PNER-ML										•			•	•	•				
	080608PNER-ML						•				•	•		•	•	•				
	080612PNER-ML														•					E30
	080616PNER-ML														•					
	080620PNER-ML														•					
	080604PNSR-MM										•				•	•				
	080608PNSR-MM						•				•	•		•	•	•				
	080612PNSR-MM														•					
	080616PNSR-MM														•					
	080620PNSR-MM														•					

#### Parts




123



### RM6PM-WN04





















(mm)

	Designation	©	ØD	Ød	Ød1	Q	L	М	ар	O
RM6PM	020R-2-M10-WN04	2	20	18	10.5	30	50	10	4.3	0.06
	020R-3-M10-WN04	3	20	18	10.5	30	50	10	4.3	0.06
	025R-4-M12-WN04	4	25	23	12.5	30	53	12	4.3	0.1
	025R-5-M12-WN04	5	25	23	12.5	30	53	12	4.3	0.09
	032R-5-M16-WN04	5	32	29	17	40	66	16	4.3	0.25
	032R-6-M16-WN04	6	32	29	17	40	66	16	4.3	0.24

#### Available inserts

WNGX-MA

WNGX-ML

WNGX-MM







	Cermet			Uncoated			Cermet	Coated	Incoated	
Designation	CN2500 CN30	NCM325 NCM325 NCM335 NCM535 NCM545 PC2505 PC2010 PC3700	PC9530 PC9540 PC5300 PC5400	ST30A H01	page	Designation	CN2500 CN30	NC5330 NCM325 NCM325 NCM545 NCM645 PC2010 PC2010 PC6510 PC6510 PC9540 PC9540 PC5300	ST30A FG bai	age
WNGX 040304PNFR-MA				•		WNGX 080604PNFR-MA				
040308PNFR-MA						080608PNFR-MA				
040312PNFR-MA				•		080612PNFR-MA				
040316PNFR-MA				•		080616PNFR-MA				
040304PNER-ML			• • •			080620PNFR-MA				
040308PNER-ML			• •			080604PNER-ML		• •		
040312PNER-ML			•			080608PNER-ML		• • • •		
040316PNER-ML			•		E30	080612PNER-ML		•	E3	30
040304PNSR-MM			• •			080616PNER-ML		•		
040308PNSR-MM			• •			080620PNER-ML		•		
040312PNSR-MM			•			080604PNSR-MM		• •		
040316PNSR-MM			•			080608PNSR-MM		• • • • •		
						080612PNSR-MM		•		
						080616PNSR-MM		•		
						080620PNSR-MM		•		

#### Available adaptor

_	•	
	Designation	Available adaptor
RM6PM	020R-2-M10-WN04	MAT-M10
	020R-3-M10-WN04	MAT-M10
	025R-4-M12-WN04	MAT-M12
	025R-5-M12-WN04	MAT-M12
	032R-5-M16-WN04	MAT-M16
	032R-6-M16-WN04	MAT-M16


Designation : RM6PM032R-5-M16-WN04 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

Specification			
	Screw	Wrench	
Ø20~Ø32	ETNA02506	TW07S	

### RM6PM-WN08





















(mm)

	Designation	<b>(</b>	ØD	Ød	Ød1	Q	L	M	ар	kg
RM6PM	032R-2-M16-WN08	2	32	29	17	43	69	16	8.2	0.22
	040R-3-M16-WN08	3	40	29	17	43	69	16	8.2	0.31
	040R-4-M16-WN08	4	40	29	17	43	69	16	8.2	0.30

#### Available inserts







	Cermet	Coated		Uncoated			Cermet	Coated	Uncoate	t
Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC2505 PC2010 PC3700	PC9530 PC9540 PC5300 PC5400	ST30A H01	page	Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC2505 PC2501 PC2700 PC6510 PC6510	PC5400 ST30A H01	page
WNGX 040304PNFR-MA				•		WNGX 080604PNFR-MA			•	
040308PNFR-MA						080608PNFR-MA			•	
040312PNFR-MA				•		080612PNFR-MA				
040316PNFR-MA				•		080616PNFR-MA			•	
040304PNER-ML		•				080620PNFR-MA			•	
040308PNER-ML			• •			080604PNER-ML		• •	•	
040312PNER-ML			•			080608PNER-ML		• • •	•	
040316PNER-ML			•		E30	080612PNER-ML		•		E30
040304PNSR-MM		•	• •			080616PNER-ML		•		
040308PNSR-MM			• •			080620PNER-ML		•		
040312PNSR-MM			•			080604PNSR-MM		• •		
040316PNSR-MM			•			080608PNSR-MM		• • • •		
						080612PNSR-MM		•		
						080616PNSR-MM		•		
						080620PNSR-MM		•		

#### Available adaptor

	Designation	Available adaptor
RM6PM	032R-2-M16-WN08	MAT-M16
	040R-3-M16-WN08	MAT-M16
	040R-4-M16-WN08	MAT-M16


Designation : RM6PM032R-5-M16-WN04 Modular head threading measure size (M16)

Ш

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

#### Parts


<u> </u>			
Specification		San Control of the Co	
	Screw	Wrench	
Ø32~Ø40	FTNA0513	TW20-100	




⊕ Available adaptor E401~E402

## RM8AC(M)4000













• AR: -6° • RR: -9°~-6°

(mm)

Desi	ignation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
RM8ACM	4050HR-M	4	50	49	22	11	18	10.4	6.3	20	40	6.0	0.5	1
	4050HR-H	6	50	49	22	11	18	10.4	6.3	20	40	6.0	0.5	1
	4063HR-M	6	63	49	22	11	18	10.4	6.3	20	40	6.0	0.7	1
	4063HR-H	8	63	49	22	11	18	10.4	6.3	20	40	6.0	0.7	1
RM8AC	4080HR	5	80	57	25.4 (27)	14	20	9.5 (12.4)	6(7)	25 (23)	50	6.0	1.2	1
(RM8ACM)	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6(7)	25 (23)	50	6.0	1.2	1
	4080HR-H	10	80	57	25.4 (27)	14	20	9.5 (12.4)	6(7)	25 (23)	50	6.0	1.3	1
	4100HR	6	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	6.0	1.7	1
	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	6.0	1.7	1
	4100HR-H	12	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	6.0	1.7	1
	4125HR	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10(9)	36 (30)	63	6.0	3.6	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10(9)	36 (30)	63	6.0	3.6	1
	4125HR-H	16	125	87	38.1 (40)	22	32	15.9 (16.4)	10(9)	36 (30)	63	6.0	3.7	1
	4160R	10	160	107	50.8 (40)	-	107	19 (16.4)	11(9)	38 (32)	63	6.0	4.8	2
	4160R-M	12	160	107	50.8 (40)	-	107	19 (16.4)	11(9)	38 (32)	63	6.0	5.3	2
	4160R-H	20	160	107	50.8 (40)	-	107	19 (16.4)	11(9)	38 (32)	63	6.0	5.4	2
	4200R-M	14	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	6.0	7.1	2
	4200R-H	24	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	6.0	7.1	2
	4250R-M	16	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38 (32)	63	6.0	11.9	2
	4250R-H	30	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38 (32)	63	6.0	12.0	2
	4315R	18	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	6.0	18.8 (18.6)	2
	4315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	6.0	18.8 (18.6)	2
	4400R-M	28	400	260	47.625 (60)	-	238	25.4 (25.7)	14	38	80	6.0	37.7 (37.4)	2

( )Metric size

#### Available inserts

SNM(E)X	-MF	SNEX-M	L		S	ΝN	I(E)	X-	ΜN	1		SI	NE)	X-N	ΙA			5	SNE	X-W
9		0	nev	9		100	F					4	Ś					The same of	0	9
			Cer	met						Cc	at	ed						Unc	oated	
De	esigna	tion	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
SNEX	1206	ANN-MF										•	•			•	•			
	1206	ANN-ML														•	•			
	1206	ANN-MM										•	•	•		•	•			E24
	1206	ANN-MA																	•	E25
	1206	ANN-W										•	•			•				E26
SNMX	1206	ANN-MF						•				•	•		•	•	•			
	1206	ANN-MM			•			•				•	•	•	•	•	•			

#### Available arbors


Dooise	nation	Available	e arbors				
Desig	nation	RM8AC	RM8ACM				
RM8ACM	4050HR- 4063HR-	-	BT -FMC22-				
RM8AC	4080HR-	BT□□ -FMA25.4-□□	BT FMC27-				
(RM8ACM)	4100HR-	BT□□ -FMA31.75-□□	BT□□-FMC32-□□				
	4125HR-	BT□□ -FMA38.1-□□	BT□□-FMB40-□□				
	4160R-	BT□□ -FMA50.8-□□	BT□□-FMC40-□□				
	4200R-						
	4250R-	BT□□ -FMA47.625-□□	BT□□-FMB60-□□				
	4315R-□	DI FIVIA47.025					
	4400R-						


Specification			
	Screw	Wrench	
Ø50~Ø400	FTKA0410	TW15S	

### RMH8AC(M)4000

### Shim type













• AR: -6° • RR: -9°~-6°

(mm)

Desig	nation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
RMH8AC	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	6.0	1.2	1
(RMH8ACM)	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	6.0	1.7	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	6.0	3.6	1
	4160R-M	12	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	6.0	5.3	2
	4200R-M	14	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	6.0	7.1	2
	4250R-M	16	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38 (32)	63	6.0	11.9	2
	4315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	6.0	18.8 (18.6)	2
	4400R-M	26	400	260	47.625 (60)	-	238	25.4 (25.7)	14	38	80	6.0	37.7 (37.4)	2

( )Metric size

#### Available inserts









SNEX-MA



		Cer	met		Coated									Uı	ncoat	ed				
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 1	page
SNEX	1206ANN-MF										•	•			•	•				
	1206ANN-ML														•	•				
	1206ANN-MM										•	•	•		•	•				E24
	1206ANN-MA																		•	E25
	1206ANN-W										•	•			•					E26
SNMX	1206ANN-MF						•				•	•		•	•	•				
	1206ANN-MM			•			•					•	•		•	•				

#### Available arbors


	Decimation	Available	e arbors
	Designation	RMH8AC	RMH8ACM
RMH8AC	4080HR-□	BT□□ -FMA25.4-□□	BT□□ -FMC27-□□
(RMH8ACM)	4100HR-	BT□□ -FMA31.75-□□	BT□□ -FMC32-□□
	4125HR-	BT□□ -FMA38.1-□□	BT□□ -FMB40-□□
	4160R-	BT□□ -FMA50.8-□□	BT□□ -FMC40-□□
	4200R-		
	4250R-	DTCC FMAAZ COF CC	PT - FMPCO -
	4315R-□	BT□□ -FMA47.625-□□	BT□□ -FMB60-□□
	4400R-□		


<u> </u>				
Specification				
	Screw	Shim	Shim Screw	Wrench
Ø80~Ø400	FTKA0412B	SS42RM8	SHXN0609F	TW15S

<sup>→</sup> Available inserts E24~E26

## RM8AC(M)5000















(mm)

Desi	gnation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	Е	F	ар	kg	Fig.
RM8AC	5080HR-M	6	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	7.5	1.2	1
(RM8ACM)	5100HR-M	7	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0	33 (25)	63 (50)	7.5	2.5 (1.8)	1
	5125HR-M	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (30)	63	7.5	3.6	1
	5160R-M	10	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	7.5	5 (4.56)	2
	5200R-M	12	200	130	47.625 (60)	-	135	25.4 (25.7)	14.0	38	63	7.5	7.1 (6.8)	2
	5250R-M	15	250	180	47.625 (60)	-	180	25.4 (25.7)	14.0	38	63	7.5	11.9 (10.6)	2
	5315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14.0	38	63	7.5	19.1 (18.9)	2
	5400R-M	28	400	260	47.625 (60)	-	238	25.4 (25.7)	14.0	38	80	7.5	37.7 (37.5)	2

( )Metric size

#### Available inserts

SNM(E)X-MF SNEX-ML SNM(E)X-MM

		Cer	met		Coated												Uncoated			
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1507ANN-MF											•			•	•				
	1507ANN-ML														•	•				E24
	1507ANN-MM											•			•	•				E25
SNMX	1507ANN-MF						•				•	•			•	•				E26
	1507ANN-MM						•				•	•			•	•				

#### Available arbors


	Designation	Availabl	e arbors
	Designation	RM8AC	RM8ACM
RM8AC	5080HR-□	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RM8ACM)	5100HR-□	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	5125HR-□	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	5160R-□	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	5200R-□		
	5250R-□	BT□□-FMA47.625-□□	BT□□-FMB60-□□
	5315R-□	DIFIVIA47.025	
	5400R-□		


Specification			
	Screw	Wrench	
Ø80~Ø400	FTGA0513	TW20-100	

### RMH8AC(M)5000

### Shim type













• AR: -6° • RR: -9°~-6°

(mm)

Desig	gnation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	√ kg \	Fig.
RMH8AC	5080HR-M	6	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	7.5	1.2	1
(RMH8ACM)	5100HR-M	7	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0	33 (25)	63 (50)	7.5	2.5 (1.8)	1
	5125HR-M	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	7.5	3.6	1
	5160R-M	10	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	7.5	5 (4.56)	2
	5200R-M	12	200	130	47.625 (60)	-	135	25.4 (25.7)	14.0	38 (32)	63	7.5	7.1 (6.8)	2
	5250R-M	15	250	180	47.625 (60)	-	180	25.4 (25.7)	14.0	38 (32)	63	7.5	11.9 (10.6)	2
	5315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14.0	38	63	7.5	19.1 (18.9)	2
	5400R-M	22	400	260	47.625 (60)	-	238	25.4 (25.7)	14.0	38	80	7.5	37.7 (37.5)	2

( )Metric size

#### Available inserts

SNM(E)X-MF SNEX-ML SNM(E)X-MM







Ce					Coated										Ur	ncoat	ed			
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1507ANN-MF											•			•	•				
	1507ANN-ML														•	•				E24
	1507ANN-MM											•			•	•				E25
SNMX	1507ANN-MF						•				•	•			•	•				E26
	1507ANN-MM						•				•	•			•	•				

#### Available arbors

	Designation	Availabl	le arbors
'	Designation	RMH8AC	RMH8ACM
RMH8AC	5080HR-	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RMH8ACM)	5100HR-	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	5125HR-	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	5160R-□	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	5200R-□		
	5250R-	BT□□-FMA47.625-□□	BT□□-FMB60-□□
	5315R-□	BIFWA47.023	
	5400R-		









### RM8EC(M)4000













• AR: -6° • RR: -8°~-6°

(mm)

Desi	gnation	<b>(a)</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар		Fig.
RM8ECM	4050HR-M	4	50	49	22	11	18	10.4	6.3	20	40	9.0	0.4	1
	4063HR-M	6	63	49	22	11	18	10.4	6.3	20	40	9.0	0.6	1
RM8EC	4080HR	5	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	9.0	1.2	1
(RM8ECM)	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	9.0	1.1	1
	4100HR	6	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25)	63 (50)	9.0	1.6	1
	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25)	63 (50)	9.0	2.5	1
	4125HR	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	9.0	2.9 (3.3)	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	9.0	3.0	1
	4160R	10	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	9.0	4.4	2
	4160R-M	12	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	9.0	4.0	2
	4200R-M	16	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	9.0	5.9	2
	4250R-M	16	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38	63	9.0	10.9 (10.6)	2
	4315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	9.0	18.1 (17.9)	2
	4400R-M	28	400	260	47.625 (60)	-	238	25.4 (25.7)	14	38	80	9.0	31.8 (31.5)	2

#### Available inserts

( )Metric size









SNEX-MA

	Cermet								C	oate	d						Uı	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1206ENN-MF											•			•	•				
	1206ENN-ML														•	•				E24
	1206ENN-MM											•			•	•				E25
	1206ENN-MA											•							•	
SNMX	1206ENN-MF						•				•	•		•	•	•				E26
	1206ENN-MM						•				•	•		•	•	•				

#### Available arbors


	Decimation	NC a	rbors
	Designation	RM8EC	RM8ECM
RM8ECM	4050HR-□		BT - FMC22-
	4063HR-□	-	BI LL-FMC22-LL
RM8EC	4080HR-□	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RM8ECM)	4100HR-	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	4125HR-□	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	4160R-□	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	4200R-		
	4250R-	BT□□-FMA47.625-□□	BT□□-FMB60-□□
	4315R-	D1FIVIA47.025	
	4400R-		


Specification		
	Screw	Wrench
Ø50~Ø400	PTKA0411-R3	TW15S

### RMH8EC(M)4000

### Shim type













• AR: -6° • RR: -8°~-6°

(mm)

Desig	gnation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	∑ kg \	Fig.
RMH8EC	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	9.0	1.1	1
(RMH8ECM)	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	9.0	2.5	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	9.0	3.0	1
	4160R-M	12	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	9.0	4.0	2
	4200R-M	16	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	9.0	5.9	2
	4250R-M	16	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38 (32)	63	9.0	10.9 (10.6)	2
	4315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	9.0	18.1 (17.9)	2
	4400R-M	24	400	260	47.625 (60)	-	238	25.4 (25.7)	14	38	80	9.0	31.8 (31.5)	2

( )Metric size

#### Available inserts

SNM(E)X-MF

SNEX-ML

SNM(E)X-MM

SNEX-MA










							_						_							
		Cei	rmet						C	oate	d						Uncoated			
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	F04	page
SNEX	1206ENN-MF											•			•	•				
	1206ENN-ML														•	•				F04
	1206ENN-MM											•			•	•				E24 E25
	1206ENN-MA											•							•	E25 E26
SNMX	1206ENN-MF						•				•	•		•	•	•				E20
	1206ENN-MM						•				•	•		•	•	•				

#### Available arbors


	Designation	Availabl	e arbors
'	Designation	RMH8EC	RMH8ECM
RMH8EC	4080HR-	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RMH8ECM)	4100HR-	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	4125HR-	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	4160R-	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	4200R-□		
	4250R-□	BT□□-FMA47.625-□□	BT□□-FMB60-□□
	4315R-□	BIFIVIA47.023	
	4400R-		






# RM8EC(M)5000













• AR: -6° • RR: -8°~-6°

(mm)

nation	$\odot$	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
5080HR-M	6	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	11.0	1.1	1
5100HR-M	7	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0	33 (25)	63 (50)	11.0	2.1 (1.7)	1
5125HR-M	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (30)	63	11.0	3.4 (3.3)	1
5160R-M	10	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	11.0	4.4 (4.1)	2
5200R-M	12	200	130	47.625 (60)	-	135	25.4 (25.7)	14.0	38	63	11.0	6.4 (6.1)	2
5250R-M	15	250	180	47.625 (60)	-	180	25.4 (25.7)	14.0	38	63	11.0	11.0 (10.7)	2
5315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14.0	38	63	11.0	18.0 (17.7)	2
5400R-M	28	400	260	47.625 (60)	-	238	25.4 (25.7)	14.0	38	80	11.0	35.7 (35.4)	2
5 5 5 5	6080HR-M 6100HR-M 6125HR-M 6160R-M 6200R-M 6250R-M 6315R-M	6080HR-M 6 6100HR-M 7 6125HR-M 8 6160R-M 10 6200R-M 12 6250R-M 15 6315R-M 20	6 80 6100HR-M 7 100 6125HR-M 8 125 6160R-M 10 160 6200R-M 12 200 6250R-M 15 250 6315R-M 20 315	6 80 57 6100HR-M 7 100 67 6125HR-M 8 125 87 6160R-M 10 160 107 6200R-M 12 200 130 6250R-M 15 250 180 6315R-M 20 315 240	6     80     57     25.4 (27)       6100HR-M     7     100     67     31.75 (32)       6125HR-M     8     125     87     38.1 (40)       6160R-M     10     160     107     50.8 (40)       6200R-M     12     200     130     47.625 (60)       6250R-M     15     250     180     47.625 (60)       6315R-M     20     315     240     47.625 (60)	100   100	6080HR-M         6         80         57         25.4 (27)         14         20           6100HR-M         7         100         67         31.75 (32)         18         26           6125HR-M         8         125         87         38.1 (40)         22         32           6160R-M         10         160         107         50.8 (40)         -         107           6200R-M         12         200         130         47.625 (60)         -         135           6250R-M         15         250         180         47.625 (60)         -         180           6315R-M         20         315         240         47.625 (60)         -         238	6080HR-M       6       80       57       25.4 (27)       14       20       9.5 (12.4)         6100HR-M       7       100       67       31.75 (32)       18       26       12.7 (14.4)         6125HR-M       8       125       87       38.1 (40)       22       32       15.9 (16.4)         6160R-M       10       160       107       50.8 (40)       -       107       19 (16.4)         6200R-M       12       200       130       47.625 (60)       -       135       25.4 (25.7)         6315R-M       20       315       240       47.625 (60)       -       238       25.4 (25.7)	6080HR-M         6         80         57         25.4 (27)         14         20         9.5 (12.4)         6 (7)           6100HR-M         7         100         67         31.75 (32)         18         26         12.7 (14.4)         8.0           6125HR-M         8         125         87         38.1 (40)         22         32         15.9 (16.4)         10 (9)           6160R-M         10         160         107         50.8 (40)         -         107         19 (16.4)         11 (9)           6200R-M         12         200         130         47.625 (60)         -         135         25.4 (25.7)         14.0           6250R-M         15         250         180         47.625 (60)         -         180         25.4 (25.7)         14.0           6315R-M         20         315         240         47.625 (60)         -         238         25.4 (25.7)         14.0	6080HR-M         6         80         57         25.4 (27)         14         20         9.5 (12.4)         6 (7)         25 (23)           6100HR-M         7         100         67         31.75 (32)         18         26         12.7 (14.4)         8.0         33 (25)           6125HR-M         8         125         87         38.1 (40)         22         32         15.9 (16.4)         10 (9)         35 (30)           6160R-M         10         160         107         50.8 (40)         -         107         19 (16.4)         11 (9)         38 (32)           6200R-M         12         200         130         47.625 (60)         -         135         25.4 (25.7)         14.0         38           6250R-M         15         250         180         47.625 (60)         -         180         25.4 (25.7)         14.0         38           315R-M         20         315         240         47.625 (60)         -         238         25.4 (25.7)         14.0         38	6080HR-M         6         80         57         25.4 (27)         14         20         9.5 (12.4)         6 (7)         25 (23)         50           6100HR-M         7         100         67         31.75 (32)         18         26         12.7 (14.4)         8.0         33 (25)         63 (50)           6125HR-M         8         125         87         38.1 (40)         22         32         15.9 (16.4)         10 (9)         35 (30)         63           6160R-M         10         160         107         50.8 (40)         -         107         19 (16.4)         11 (9)         38 (32)         63           6200R-M         12         200         130         47.625 (60)         -         135         25.4 (25.7)         14.0         38         63           6250R-M         15         250         180         47.625 (60)         -         180         25.4 (25.7)         14.0         38         63           3315R-M         20         315         240         47.625 (60)         -         238         25.4 (25.7)         14.0         38         63	6080HR-M         6         80         57         25.4 (27)         14         20         9.5 (12.4)         6 (7)         25 (23)         50         11.0           6100HR-M         7         100         67         31.75 (32)         18         26         12.7 (14.4)         8.0         33 (25)         63 (50)         11.0           6125HR-M         8         125         87         38.1 (40)         22         32         15.9 (16.4)         10 (9)         35 (30)         63         11.0           6160R-M         10         160         107         50.8 (40)         -         107         19 (16.4)         11 (9)         38 (32)         63         11.0           6200R-M         12         200         130         47.625 (60)         -         135         25.4 (25.7)         14.0         38         63         11.0           6250R-M         15         250         180         47.625 (60)         -         180         25.4 (25.7)         14.0         38         63         11.0           6315R-M         20         315         240         47.625 (60)         -         238         25.4 (25.7)         14.0         38         63         11.0	6080HR-M         6         80         57         25.4 (27)         14         20         9.5 (12.4)         6 (7)         25 (23)         50         11.0         1.1           6100HR-M         7         100         67         31.75 (32)         18         26         12.7 (14.4)         8.0         33 (25)         63 (50)         11.0         2.1 (1.7)           6125HR-M         8         125         87         38.1 (40)         22         32         15.9 (16.4)         10 (9)         35 (30)         63         11.0         3.4 (3.3)           6160R-M         10         160         107         50.8 (40)         -         107         19 (16.4)         11 (9)         38 (32)         63         11.0         4.4 (4.1)           6200R-M         12         200         130         47.625 (60)         -         135         25.4 (25.7)         14.0         38         63         11.0         6.4 (6.1)           6250R-M         15         250         180         47.625 (60)         -         180         25.4 (25.7)         14.0         38         63         11.0         11.0 (10.7)           6315R-M         20         315         240         47.625 (60)         -

( )Metric size

#### Available inserts

SNM(E)X-MF

SNEX-ML

SNM(E)X-MM







		Cer	met		Coated										Uı	ncoat	ted			
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1507ENN-MF											•			•	•				
	1507ENN-ML														•	•				E24
	1507ENN-MM											•			•	•				E25
SNMX	1507ENN-MF						•				•	•			•	•				E26
	1507ENN-MM						•				•	•			•	•				

#### Available arbors


	Designation	Availabl	e arbors
	Designation	RM8EC	RM8ECM
RM8EC	5080HR-□	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RM8ECM)	5100HR-□	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	5125HR-□	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	5160R-□	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	5200R-		
	5250R-□	BT□□-FMA47.625-□□	BT□□-FMB60-□□
	5315R-□	DIFIMA47.023	
	5400R-□		


Specification			
	Screw	Wrench	
Ø80~Ø400	FTGA0513	TW20-100	

# RMH8EC(M)5000

### Shim type













• AR: -6° • RR: -8°~-6°

(mm)

Desi	gnation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
RMH8EC	5080HR-M	6	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	11.0	1.1	1
(RMH8ECM)	5100HR-M	7	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0	33 (25.5)	63 (50)	11.0	2.1 (1.7)	1
	5125HR-M	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	11.0	3.4 (3.3)	1
	5160HR-M	10	160	107	50.8 (60)	-	107	19 (16.4)	11 (9)	38 (32)	63	11.0	4.4 (4.1)	2
	5200R-M	12	200	130	47.625 (60)	-	135	25.4 (25.7)	14.0	38 (32)	63	11.0	6.4 (6.1)	2
	5250R-M	15	250	180	47.625 (60)	-	180	25.4 (25.7)	14.0	38 (32)	63	11.0	110 (10.7)	2
	5315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14.0	38	63	11.0	18.0 (17.7)	2
	5400R-H	22	400	260	47.625 (60)	-	238	25.4 (25.7)	14.0	38	80	11.0	35.7 (35.4)	2

( )Metric size

#### Available inserts


SNM(E)X-MF SNEX-ML SNM(E)X-MM

		Cer	met		Coated Uncoated									ed						
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1507ENN-MF											•			•	•				
	1507ENN-ML														•	•				E24
	1507ENN-MM											•			•	•				E25
SNMX	1507ENN-MF						•				•	•			•	•				E26
	1507ENN-MM						•				•	•			•	•				

#### Available arbors

	Designation	Availabl	le arbors
	Designation	RMH8EC	RMH8ECM
RMH8EC	5080HR-	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RMH8ECM)	5100HR-	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	5125HR-□	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	5160R-	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	5200R-		
	5250R-	BT□□-FMA47.625-□□	BT□□-FMB60-□□
	5315R-	DIFIVIA47.025	DIPIVIDOU
	5400R-		


Specification				
	Screw	Shim	Shim Screw	Wrench
Ø80~Ø400	FTGA0513	SS53RM8	SHXN0712F	TW20-100






## RM8QC(M)4000













• AR: -6° • RR: -8°~-6°

(mm)

Desi	gnation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
RM8QCM	4063HR-M	6	63	49	22	11	18	10.4	6.3	20	40	11.5	0.6	1
	4063HR-H	8	63	49	22	11	18	10.4	6.3	20	40	11.5	0.6	1
RM8QC	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	11.5	1.1	1
(RM8QCM)	4080HR-H	10	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	11.5	1.0	1
•	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	11.5	1.7	1
	4100HR-H	12	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	11.5	1.6	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	11.5	3.3	1
	4125HR-H	14	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	11.5	3.3	1
	4160R-M	12	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	11.5	3.9	2
	4160R-H	18	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	11.5	3.9	2
	4200R-M	14	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	11.5	6.4	2
	4200R-H	22	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	11.5	6.4	2

#### Available inserts

( )Metric size









													_							
		Cer	met						C	oate	d						IU	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1206QNN-MF										•	•			•	•				
	1206QNN-ML																			
	1206QNN-MM											•			•	•				
	1206QNN-MA																		•	
	120612-MF											•			•	•				E24
	120612-ML														•	•				E25
	120612-MM											•								
	120612-MA																		•	E26
SNMX	1206QNN-MF						•				•	•			•	•				
	1206QNN-MM						•				•	•		•	•	•				
	120612-MF											•			•	•				
	120612-MM											•			•					

#### Available arbors


	Decimation	Available	e arbors
	Designation	RM8QC	RM8QCM
RM8QCM	4063HR-□	-	BT□□-FMC22-□□
RM8QC	4080HR-□	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RM8QCM)	4100HR-□	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	4125HR-□	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	4160R-□	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	4200R-	BT□□-FMA47.625-□□	BT□□-FMB60-□□


Specification		
	Screw	Wrench
Ø63~Ø200	PTKA0411-R3	TW15S

# RMH8QC(M)4000

### Shim type















(mm)

Desig	ınation	<b>(b)</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	Е	F	ар	kg	Fig.
RMH8QC	4080HR-M	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	11.5	1.1	1
(RMH8QCM)	4100HR-M	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25.5)	63 (50)	11.5	2.5	1
	4125HR-M	10	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (30)	63	11.5	3.0	1
	4160R-M	12	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	11.5	4.0	2
	4200R-M	16	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	11.5	5.9	2

( )Metric size

#### Available inserts

SNM(E)X-MF	SNEX-ML	SNM(E)X-MM	SNEX-MA	
	new			

		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNEX	1206QNN-MF										•	•			•	•				
	1206QNN-ML														•	•				
	1206QNN-MM											•			•	•				
	1206QNN-MA																		•	
	120612-MF											•			•	•				E24
	120612-ML														•	•				E24 E25
	120612-MM											•								E25
	120612-MA																		•	
SNMX	1206QNN-MF						•				•	•			•	•				
	1206QNN-MM						•				•	•		•	•	•				
	120612-MF											•			•	•				
	120612-MM											•			•	•				

#### Available arbors

	Decimation	Available	e arbors
·	Designation	RMH8QC	RMH8QCM
RMH8QC	4080HR-	BT□□-FMA25.4-□□	BT□□-FMC27-□□
(RMH8QCM)	4100HR-	BT□□-FMA31.75-□□	BT□□-FMC32-□□
	4125HR-	BT□□-FMA38.1-□□	BT□□-FMB40-□□
	4160R-	BT□□-FMA50.8-□□	BT□□-FMC40-□□
	4200R-	BT□□-FMA47.625-□□	BT□□-FMB60-□□

#### Parts

J 1 011 10				
Specification				
	Screw	Shim	Shim Screw	Wrench
Ø80~Ø200	PTKA0411-R3	SS42RM8	SHXN0609F	TW15S




→ Available inserts E24~E26 → Available arbors and bolt E426~E428



### RMT8A(M)4000









(mm)

Desi	gnation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
RMT8A	4080R	5	80	100	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	4	1.6	1
(RMT8AM)	4080R-M	6	80	100	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	4	1.6	1
	4100R	6	100	120	70	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	4	2.3	2
	4100R-M	8	100	120	70	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	4	2.3	2
	4125R	8	125	144	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	4	4.3	2
	4125R-M	10	125	144	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	4	4.3	2
	4160R	10	160	179	110	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	4	6.5	2
	4160R-M	14	160	179	110	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	4	6.5	2
	4200R	12	200	219	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	4	8.8	3
	4200R-M	18	200	219	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	4	8.8	3
	4250R	16	250	269	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	4	14.1	3
	4250R-M	22	250	269	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	4	14.1	3
	4315R	20	315	334	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	4	22.3	4
	4315R-M	28	315	334	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	4	22.3	4

#### Available inserts

( )Metric size





		Cer	Cermet Coated Uncoated										ed							
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNCF	1206ANN-MF																			
	1206ANN-MM																			E22
SNMF	1206ANN-MF																			E23
	1206ANN-MM																			

#### Available arbors


	Decimation	Canaval aubava	NC arbors							
	Designation	General arbors	RMT8A	RMT8AM						
RMT8A	□080R	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27						
(RMT8AM)	□100R	NT*□□(M/U)-FMA31.75-□□	BT**□□-FMA31.75-□□	FMC32						
	□125R	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1-□□	EMD40						
	□160R	NT*□□(M/U)-FMA50.8-□□	BT**□□-FMA50.8-□□	FMB40						
	□200R	NT*□□(M/U)-FMA47.625-25,	DT**	EMPOO						
	□250R	KCP-8***	BT**□□-FMA47.625-□□	FMB60						
	315R	KCP-8*** (Center ring plug)	-	-						

#### Parts

Specification	Screw	Screw	Spring	Latch	Wrench	
Ø80~Ø315	ETKA0523	KHB0417	SPR0315	LTC05SR-RM4	TW20-100	



### RMT8A(M)5000









• AR: -6° • RR: -6°

(mm)

( )Metric size

													()
Des	ignation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	(kg)	Fig.
RMT8A	5080R	5	80	104	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	6	1.8	1
(RMT8AM)	5080R-M	6	80	104	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	6	1.8	1
	5100R	6	100	124	70	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	6	2.6	2
	5100R-M	8	100	124	70	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	6	2.6	2
	5125R	8	125	149	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	6	4.3	2
	5125R-M		125	149	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	6	4.3	2
	5160R	10	160	184	110	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	6	6.5	2
	5160R-M	14	160	184	110	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	6	6.5	2
	5200R	12	200	224	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	9.0	3
	5200R-M	18	200	224	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	9.0	3
	5250R	16	250	274	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	14.4	3
	5250R-M	22	250	274	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	14.4	3
	5315R	20	315	339	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	22.2	4
	5315R-M	28	315	339	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	6	22.2	4

#### Available inserts

SNC(M)F-MF SNC(M)F-MM





							_			_										
		Cer	met						C	oate	d						Uı	ncoat	ted	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNCF	1507ANN-MF											•								
	1507ANN-MM																			E22
SNMF	1507ANN-MF																			E23
	1507ANN-MM																			

#### Available arbors

	Designation	Canaval aubava	NC arbors							
	Designation	General arbors	RMT8A	RMT8AM						
RMT8A	□080R	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27						
(RMT8AM)	□100R	NT*□□(M/U)-FMA31.75-□□	BT**□□-FMA31.75	FMC32						
	□125R	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1	EMP 40						
	□160R	NT* (M/U)-FMA50.8-	BT**□□-FMA50.8	FMB40						
	□200R	NT*□□(M/U)-FMA47.625-25,	DT**	EMBCO						
	□250R	KCP-8***	BT**□□-FMA47.625-□□	FMB60						
	□315R	KCP-8*** (Center ring plug)	-	-						


#### Parts

Specification	Screw	Screw	Spring	Latch	Wrench	
Ø80~Ø315	ETKA0625	KHB0417	SPR0415	LTC06SR-RM5	TW20-100	

Available inserts E22, E23



### RMT8E(M)4000











(mm)

Des	ignation	<b>(b)</b>	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
RMT8E	4080R	5	80	100	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	5	1.5	1
(RMT8EM)	4080R-M	6	80	100	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	5	1.5	1
	4100R	6	100	120	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	5	2	2
	4100R-M	8	100	120	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	5	2	2
	4125R	8	125	144	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	5	3.8	2
	4125R-M	10	125	144	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	5	3.8	2
	4160R	10	160	179	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	5	5.8	2
	4160R-M	14	160	179	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	5	5.8	2
	4200R	12	200	219	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	7.9	3
	4200R-M	18	200	219	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	7.9	3
	4250R	16	250	269	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	13.0	3
	4250R-M	22	250	269	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	13.0	3
	4315R	20	315	334	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	20.5	4
	4315R-M	28	315	334	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	20.5	4

#### Available inserts

( )Metric size



SNC(M)F-MF



		Cer	rmet						C	oate	d						Uı	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNCF	1206ENN-MF											•								
	1206ENN-MM																			E22
SNMF	1206ENN-MF										•									E23
	1206ENN-MM										•									


#### Available arbors

	Designation	General arbors	NC a	rbors				
	Designation	General arbors	RMT8E	RMT8EM				
RMT8E	□080R	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27				
(RMT8EM)	□100R	NT*□□(M/U)-FMA31.75-□□	BT**□□-FMA31.75-□□	FMC32				
	□125R	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1-□□	FMB40				
	□160R	NT*□□(M/U)-FMA50.8-□□	BT**□□-FMA50.8-□□	FIVIB40				
	□200R	NT*□□(M/U)-FMA47.625-25, KCP-8***	BT**□□-FMA47.625-□□	FMB60				
	□250R □315R	KCP-8*** (Center ring plug)		-				

#### Parts

Specification					San Control of the Co	
	Screw	Screw	Spring	Latch	Wrench	
Ø80~Ø315	ETKA0523	KHB0417	SPR0315	LTC05SR-RM4	TW20-100	

### RMT8E(M)5000







75°

A • AR: -6° • RR: -8°~-6°

(mm)

Desi	gnation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	kg	Fig.
RMT8E	5080R	5	80	88	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	8	1.4	1
(RMT8EM)	5080R-M	6	80	88	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	8	1.4	1
	5100R	6	100	108	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	8	1.9	2
	5100R-M	8	100	108	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	8	1.9	2
	5125R	8	125	133	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	8	3.7	2
	5125R-M			87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	8	3.7	2	
	5160R	10	160	168	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	8	5.7	2
	5160R-M	14	160	168	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	8	5.7	2
	5200R	12	200	208	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	8	7.5	3
	5200R-M	18	200	208	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	8	7.5	3
	5250R	16	250	258	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	8	12.4	3
	5250R-M	22	250	258	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	8	12.4	3
	5315R	20	20 315 323 240		240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	8	19.9	4
	<b>5315R-M</b> 28 315 323 240		47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	8	19.9	4			

( )Metric size

#### Available inserts

SNC(M)F-MF

SNC(M)F-MM





		Cer	met						C	oate	d						Ur	icoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNCF	1507ENN-MF											•								
	1507ENN-MM																			E22
SNMF	1507ENN-MF																			E23
	1507ENN-MM										•									


#### Available arbors

	Decimation	Compared pulpage	NC a	rbors
	Designation	General arbors	RMT8E	RMT8EM
RMT8E	□080R	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27
(RMT8EM)	□100R	NT*□□(M/U)-FMA31.75-□□	BT**□□-FMA31.75-□□	FMC32
,	□125R	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1-□□	FMB40
	□160R	NT*□□(M/U)-FMA50.8-□□	BT**□□-FMA50.8-□□	FINID40
	□200R	NT*□□(M/U)-FMA47.625-25,	BT**□□-FMA47.625-□□	FMB60
	□250R	KCP-8***	DIFIVIA47.025	FIVIDOU
	□315R	KCP-8*** (Center ring plug)	-	-


\* -NT number \*\* -BT number \*\*\*Over milling 5

Available inserts E22, E23

### RMT8Q(M)4000







(mm)

Desi	gnation	0	ØD	ØD1	ØD2	Ød	а	b	E	F	ар	(kg)	Fig.
RMT8Q	4080R	5	80	79	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	5	1.4	1
(RMT8QM)	4080R-M	6	80	79	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	5	1.4	1
	4100R	6	100	99	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	5	1.8	2
	4100R-M	8	100	99	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	5	1.8	2
	4125R	8	125	124	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	5	3.6	2
	4125R-M	10	125	124	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	5	3.6	2
	4160R	10	160	159	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	5	5.7	2
	4160R-M	14	160	159	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	5	5.7	2
	4200R	12	200	199	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	7.5	3
	4200R-M	18	200	199	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	7.5	3
	4250R	16	250	249	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	12.5	3
	4250R-M	22	250	249	180	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	12.5	3
	4315R	20	315	314	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	19.9	4
	4315R-M	28	315	314	240	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	5	19.9	4

#### Available inserts

( )Metric size





		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SNCF	1206QNN-MF											•								
	1206QNN-MM											•								E22
SNMF	1206QNN-MF										•									E23
	1206QNN-MM										•									

#### Available arbors


	Designation	General arbors	NC a	rbors
	Designation	General arbors	RMT8Q	RMT8QM
RMT8Q	□080R	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4-□□	FMC27
(RMT8QM)	□100R	NT*□□(M/U)-FMA31.75-□□	BT**□□-FMA31.75-□□	FMC32
	□125R	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1-□□	FMB40
	□160R	NT*□□(M/U)-FMA50.8-□□	BT**□□-FMA50.8-□□	FMB40
	□200R	NT*□□(M/U)-FMA47.625-25,	BT**□□-FMA47.625-□□	EMPCO
	□250R	KCP-8***	B1***[FMA47.625	FMB60
	□315R	KCP-8*** (Center ring plug)	-	-

#### Parts

Specification	Screw	Screw	Spring	Latch	Wrench	
Ø80~Ø315	ETKA0523	KHB0417	SPR0315	LTC05SR-RM4	TW20-100	

# RMX8AC(M)-SA14











• AR: -8° • RR: -11°~-9°

(mm)

									(*****)
ı	Designation	$\odot$	ØDX	ØD	ØD2	Ød	F	ар	kg
RMX8ACM	050R-22-4-SA14	4	62.5	50	42	22	40	5.5	0.34
	050R-22-5-SA14	5	62.5	50	42	22	40	5.5	0.38
	063R-22-5-SA14	5	75.5	63	42	22	40	5.5	0.56
	063R-22-6-SA14	6	75.5	63	42	22	40	5.5	0.54
	080R-27-6-SA14	6	92.5	80	60	27	50	5.5	1.00
	080R-27-8-SA14	8	92.5	80	60	27	50	5.5	1.04
	100R-32-8-SA14	8	112.5	100	70	32	50	5.5	2.05
	100R-32-10-SA14	10	112.5	100	70	32	50	5.5	2.06
	125R-40-8-SA14	8	137.5	125	90	40	63	5.5	3.34
	125R-40-12-SA14	12	137.5	125	90	40	63	5.5	3.34
RMX8AC	080R-25.4-6-SA14	6	92.5	80	60	25.4	50	5.5	1.02
	080R-25.4-8-SA14	8	92.5	80	60	25.4	50	5.5	1.06
	100R-31.75-8-SA14	8	112.5	100	70	31.75	63	5.5	2.08
	100R-31.75-10-SA14	10	112.5	100	70	31.75	63	5.5	2.09
	125R-38.1-8-SA14	8	137.5	125	90	38.1	63	5.5	3.43
	125R-38.1-12-SA14	12	137.5	125	90	38.1	63	5.5	3.35

#### Available inserts

SAGX-ML	SAGX-MM	SNMX-MM
		6

		Cei	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	ST30A	G10	亨	page
SAGX	140808ANER-ML														•	•				
	140808ANER-MM															•				E18
SNMX	140808ANER-MM											•	•			•				

#### Available arbors

	Designation	Ød	Available arborss
RMX8ACM	050R-22-□-SA14	22	BT□□-FMC22-□□
	063R-22-□-SA14		
	080R-27-□-SA14	27	BT□□-FMC27-□□
	100R-32-□-SA14	32	BT□□-FMC32-□□
	125R-40-□-SΔ14	40	BT□□-FMC40-□□


		Designation	Ød	Available arbors
	RMX8AC	080R-25.4-□-SA14	25.4	BT□□-FMC25.4-□□
125R-38 1-□-S∆14 38 1 BT□□-FMC38 1-□□		100R-31.75-□-SA14	31.75	BT□□-FMC31.75-□□
12511-00:1		125R-38.1-□-SA14	38.1	BT□□-FMC38.1-□□


Specification	Screw	Wrench	
Ø50~Ø125	FTNA0513	TW20-100	



# RM14XCM-XN06















(mm)

De	esignation	<b>(</b>	ØD	ØD1	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	(Na)	Fig.
RM14XCM	050R-22-5-XN06	5	50	58.6	42	22	11	18	-	10.4	6.3	21	40	3.5	0.34	1
	050R-22-6-XN06	6	50	58.6	42	22	11	18	-	10.4	6.3	21	40	3.5	0.34	1
	063R-22-6-XN06	6	63	71.6	42	22	11	18	-	10.4	6.3	21	40	3.5	0.51	1
	063R-22-8-XN06	8	63	71.6	42	22	11	18	-	10.4	6.3	21	40	3.5	0.58	1
	080R-27-6-XN06	6	80	88.6	57	27	14	20	35	12.4	7.0	23	50	3.5	0.98	1
	080R-27-8-XN06	8	80	88.6	57	27	14	20	35	12.4	7.0	23	50	3.5	1.08	1
	080R-27-10-XN06	10	80	88.6	57	27	14	20	35	12.4	7.0	23	50	3.5	1.07	1
	100R-32-10-XN06	10	100	108.6	67	32	18	26	42	14.4	8.0	25	63	3.5	1.60	1
	100R-32-12-XN06	12	100	108.6	67	32	18	26	42	14.4	8.0	25	63	3.5	1.58	1
	125R-40-12-XN06	12	125	133.6	90	40	22	32	54	16.4	9.0	29	63	3.5	3.43	1
	125R-40-14-XN06	14	125	133.6	90	40	22	32	54	16.4	9.0	29	63		3.40	1
	160NR-40-16-XN06	16	160	168.6	110	40	90	-	-	16.4	9.0	32	63	3.5	4.86	2
	160NR-40-18-XN06	18	160	168.6	110	40	90	-	-	16.4	9.0	32	63	3.5	4.84	2

 $<sup>\</sup>times$  In applying XNMX060608- $\square$ , Max. ap = 4.8 mm

#### Available inserts

						XNN	IX-ML		XN	MX-N	1L									
		Cermet									Coated					Und			ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
XNMX	0606XNR-ML						•					•		•	•	•				E32
	060608-ML													•	•	•				E32


#### Available arbors


Designation		Ød	Available arbors				
RM14XCM	050R	22	BT - FMC22-				
	063R	22					
	080R	27	BT□□-FMC27-□□				
	100R	32	BT□□-FMC32-□□				
	125R	40	BT□□-FMC40-□□				
	160R	40	DI UU-FINIC4U-UU				

Specification			
	Screw	Wrench	
Ø50~Ø160	FTKA0412B	TW15S	

# RM16AC(M)6000













(mm)

Desig	nation	<b>(b)</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар		Fig.
RM16ACM	6063HR-M	5	63	49	22	11	18	10.4	6.3	20	40	4.0	0.7	1
RM16AC	6080HR-M	6	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	4.0	1.2	1
(RM16ACM)	6100HR-M	7	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25)	63 (50)	4.0	1.9	1
	6125HR-M	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	4.0	3.5	1
	6160R-M	10	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	4.0	4.1	2
	6200R-M	12	200	130	47.625 (60)	-	135	25.4 (25.7)	14	38 (32)	63	4.0	6.1	2
	6250R-M	15	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38	63	4.0	11.5	2
	6315R-M	20	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	4.0	18.9	2
	6400R-M	26	400	260	47.625 (60)	-	238	25.4 (25.7)	14	38	80	4.0	32.7	2

### Available inserts

( )Metric size



ONHX-MF







ONHX-W



ONHX-MA





		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	문	page
ONHX	060608-MM											•			•	•				
	060608-MF											•			•	•				
	060608-ML														•	•				
	060608-MA																		•	
	060608-W											•	•		•					
	0606ANN-MM											•			•	•				E15
	0606ANN-MF											•			•	•				
ONMX	060608-MM						•				•	•		•	•	•				
	060608-MF						•					•			•	•				
	0606ANN-MM						•				•	•			•	•				
	0606ANN-MF						•					•	•		•	•				


### Available arbors


	Designation	Available arbors									
1	Designation	RM16AC	RM16ACM								
RM16AC	6063HR-M		BT□□-FMC22-□□								
(RM16ACM)	6080HR-M	BT□□-FMA25.4-□□	BT□□-FMC27-□□								
	6100HR-M	BT□□-FMA31.75-□□	BT□□-FMC32-□□								
	6125HR-M	BT□□-FMA38.1-□□	BT□□-FMB40-□□								
	6160R-M	BT□□-FMA50.8-□□	BT□□-FMC40-□□								
	6200R-M										
	6250R-M	BT□□-FMA47.625-□□	BT□□-FMB60-□□								
	6315R-M	DIFIWA47.023									
	6400R-M										

Specification	Screw	Wrench	
Ø63~Ø400	FTGA0513	TW20-100	

# RM16AC(M)8000















(mm)

Design	nation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Fig.
RM16ACM	8063HR-M	5	63	49	22	11	18	10.4	6.3	20	40	5.5	0.7	1
RM16AC	8080HR-M	6	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	5.5	1.2	1
(RM16ACM)	8100HR-M	7	100	67	31.75 (32)	18	26	12.7 (14.4)	8	33 (25)	63 (50)	5.5	1.8	1
	8125HR-M	8	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	5.5	3.5	1
	8160R-M	10	160	107	50.8 (40)	-	107	19 (16.4)	11 (9)	38 (32)	63	5.5	4.5	2
	8200R-M	12	200	130	47.625 (60)	-	135	25.4 (25.7)	14 (14)	38 (32)	63	5.5	5.8	2
	8250R-M	14	250	180	47.625 (60)	-	180	25.4 (25.7)	14	38	63	5.5	11.4	2
	8315R-M	18	315	240	47.625 (60)	-	238	25.4 (25.7)	14	38	63	5.5	18.8	2
	8400R-M	24	400	260	47.625 (60)	-	238	25.4 (25.7)	14	38	80	5.5	32.7	2

( )Metric size

### Available inserts















		Cerr	net						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
ONHX	080608-MM											•			•	•				
	080608-MF											•			•	•				
	080608-ML														•	•				
	080608-MA																		•	
	080608-W											•			•					
	0806ANN-MM											•			•	•				E15
	0806ANN-MF											•			•	•				
ONMX	080608-MM						•				•	•	•		•	•				
	080608-MF						•					•			•	•				
	0806ANN-MM						•					•	•		•	•				
	0806ANN-MF						•				•	•			•	•				

### Available arbors

	Decimation	Available arbors									
	Designation	RM16AC	RM16ACM								
RM16AC	8063HR-M	-	BT□□ -FMC22-□□								
(RM16ACM)	8080HR-M	BT□□ -FMA25.4-□□	BT□□ -FMC27-□□								
	8100HR-M	BT□□ -FMA31.75-□□	BT□□-FMC32-□□								
	8125HR-M	BT□□ -FMA38.1-□□	BT□□ -FMB40-□□								
	8160R-M	BT□□ -FMA50.8-□□	BT□□ -FMC40-□□								
	8200R-M										
	8250R-M	BT□□ -FMA47.625-□□	BT -FMB60-								
	8315R-M	DI									
	8400R-M										

Specification		No.	
	Screw	Wrench	
Ø63~Ø400	FTGA0513	TW20-100	

# RMRC(M)-RN12














(mm)

	Designation	<b>©</b>	ØD	ØС	ØD <sub>2</sub>	Ød	F	ар	(kg)
RMRCM	050R-22-5-RN12	5	50	40.4	42	22	40	3.5	0.28
	050R-22-6-RN12	6	50	40.4	42	22	40	3.5	0.29
	063R-22-6-RN12	6	63	53.4	42	22	40	3.5	0.45
	063R-22-7-RN12	7	63	53.4	42	22	40	3.5	0.46
	080R-27-6-RN12	6	80	70.4	60	27	50	3.5	0.83
	080R-27-8-RN12	8	80	70.4	60	27	50	3.5	0.82
	100R-32-7-RN12	7	100	90.4	70	32	63	3.5	1.67
	100R-32-9-RN12	9	100	90.4	70	32	63	3.5	1.67
	125R-40-10-RN12	10	125	115.4	90	40	63	3.5	2.82
	125R-40-12-RN12	12	125	115.4	90	40	63	3.5	2.83
RMRC	080R-25.4-6-RN12	6	80	70.4	60	25.4	50	3.5	0.85
	080R-25.4-8-RN12	8	80	70.4	60	25.4	50	3.5	0.85
	100R-31.75-7-RN12	7	100	90.4	70	31.75	63	3.5	1.71
	100R-31.75-9-RN12	9	100	90.4	70	31.75	63	3.5	1.71
	125R-38.1-10-RN12	10	125	115.4	90	38.1	63	3.5	2.88
	125R-38.1-12-RN12	12	125	115.4	90	38.1	63	3.5	2.88

### Available inserts

RNMX-ML




					Coated Uncoated															
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	UNC840	UPC845	ST30A	G10	H01	page
RNMX	1204M0E-ML														•	•				E17

### Available arbors

	Designation	Ød	Available arbors
	Designation	Du	Available albois
RMRCM	050R-22-□-RN12	22	BT -FMC22-
	063R-22-□-RN12	22	
	080R-27-□-RN12	27	BT□□-FMC27-□□
	100R-32-□-RN12	32	BT□□-FMC32-□□
	125R-40-□-RN12	40	BT -FMC40-

	Designation	Ød	Available arbors
RMRC	080R-25.4-□-RN12	25.4	BT□□-FMC25.4-□□
	100R-31.75-□-RN12	31.75	BT□□-FMC31.75-□□
	125R-38.1-□-RN12	38.1	BT□□-FMC38.1-□□

Specification		
	Screw	Wrench
Ø50~Ø125	FTNA0411-A	TW15S








# RMRS-RN12











• AR: -7° • RR: -15°~-13°

(mm)

	Designation	<b>(b)</b>	ØD	ØС	Ød	Q	L	Shank	ар	, C √ kg \
		<u> </u>	~-						**-	
RMRS	032R-2W32-110-RN12	2	32	22.4	32	40	110	W	3.5	0.56
	032R-3W32-110-RN12	3	32	22.4	32	40	110	W	3.5	0.55
	032R-2C32-200-RN12	2	32	22.4	32	40	200	С	3.5	1.09
	032R-3C32-200-RN12	3	32	22.4	32	40	200	С	3.5	1.09
	040R-3W32-110-RN12	3	40	30.4	32	40	110	W	3.5	0.62
	040R-4W32-110-RN12	4	40	30.4	32	40	110	W	3.5	0.62
	040R-3C32-200-RN12	3	40	30.4	32	40	200	С	3.5	1.15
	040R-4C32-200-RN12	4	40	30.4	32	40	200	С	3.5	1.15
	050R-5W40-120-RN12	5	50	40.4	40	40	120	W	3.5	1.08
	050R-6W40-120-RN12	6	50	40.4	40	40	120	W	3.5	1.08
	050R-5C42-300-RN12	5	50	40.4	42	40	300	С	3.5	3.05
	050R-6C42-300-RN12	6	50	40.4	42	40	300	С	3.5	3.05
	063R-6W40-130-RN12	6	63	53.4	40	50	130	W	3.5	1.43
	063R-7W40-130-RN12	7	63	53.4	40	50	130	W	3.5	1.43
	063R-6C42-300-RN12	6	63	53.4	42	50	300	С	3.5	3.30
	063R-7C42-300-RN12	7	63	53.4	42	50	300	С	3.5	3.26

### Available inserts

RNMX-ML



			met						C	oate	d						Uı	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	UNC840	UPC845	ST30A	G10	F0.1	page
RNMX	1204M0E-ML														•	•				E17


Specification			
	Screw	Wrench	
Ø32~Ø63	FTNA0411-A	TW15S	

### Lighter tool ensures excellent performance in high speed machining

### **Aero Mill**

- Excellent machining performance can be acquired especially at the high speeds due to the light aluminum cutter body that is 50% of the weight of a conventional steel cutter body
- High speed milling cutter for precise machining
- · Special aluminum material and high rake angle of insert provide rigid & stable machining
- High tolerance surface finishes can be acquired due to the low cutting load provided from the high rake angle
- Balanceable up to G2.5 level

### Assembly structure of cutter





#### Features of cutter

- · Increased stability based on cartridge type application
- · Both insert and blade can be available in the same cutter
- Finishing to roughing can be possible because of wide chip pocket space
- · Roughing and finishing available with carbide, PCD insert application
- · Cutter breakage can be solved by making use of the chip cover

### Coolant through system

- · Specially designed coolant through system provides coolant from the center of the cutter to the insert enhances the cooling rate and chip evacuation.
- · Direction of coolant has designed to focus directly to the insert cutting-edge to maximize chip evacuation and improve tool life
- Coolant bolt is applicable up to Ø160, coolant cover is applicable from Ø200 and over. Coolant devices are sold separately for through coolant system, through coolant arbor has to be used






For Ø200 and over




### **Aero Mill**

### Application range



### Recommended cutting condition




### Surface finish

■ Workpiece

■ Cutting vc = 1570 m/min vf = 3000 mm/minS = 5000 rpmfz = 0.1 mm/tcondition Machine = PCV620  $ap = 0.5 \, mm$ 

Designation Cutter APD100R-A6Z (6 Flutes) Insert CDEW1204R-XCF (H01)



- Rmax: 2.1 μm
- Rz: 1.6 μm
- Ra: 0.3 μm

### Max. revolution

Diameter (mm)	Max. revolution (rpm)
Ø80	16,000
Ø100	15,000
Ø125	12,500
Ø160	10,000
Ø200	8,000
Ø250	6,500
Ø315	5,000

### Coolant parts

Diameter (mm)	Туре	Desiç	Shape	Note	
Ø80	Coolant Bolt	CBP08	-0-0		
Ø100	Coolant Bolt	CBP100-IN	CBP100-MM-1		Extra _ charge
Ø125	Coolant Bolt	CBP125-IN	CBP125-MM-1		
Ø160	Coolant Bolt	CBP160-IN	CBP160-MM		
Ø200	Coolant Cover	CC		ondige	
Ø250	Coolant Cover	CC	4		
Ø315	Coolant Cover	CC	P315		



• Choice: CBP100-IN:APD type, General for unmarked item

# E

### High speed milling tool with PCD blade

### **Aero Mill-Plus**

- Improve tool life up to 20% with a coolant system that enables direct spray cooling to cutting blades
- Enable high feed milling by increasing the number of cutting blades by 20% through a simply structured coupling method for clamps
- Reduces set up time up to 40% by applying a spanner adjustment method
- Introduce an aluminum cutter body to provide a superior cutting performance during high speed milling


### Assembly structure of cutter




### Features of cutter

- · Prevent overload to the spindle bearings through weight reduction of the Al alloy body and enable high-speed processing
- Provide PCD Blade-dedicated cutter design to offer stable tool life and increase of applied blades
- Improve the blade life by applying a coolant system that enables direct spray cooling to cutting blades
- · Adopt a clamping method with simple structure without set screw
- · Reduce weight and apply a coolant bolt that is exclusively used for Aero-Mill Plus that applies coolant to remove internal chip


### Code system



### Application range



### Recommended cutting speed



### Max. RPM

Diameter (mm)	Max. revolution (rpm)
Ø80	20,000
Ø100	18,000
Ø125	16,000
Ø160	13,000
Ø200	10,000
Ø250	8,000
Ø315	7,000

#### Coolant parts

Diameter (mm)	Туре	inch/mm	Designation	Shape	Material	Note	
Ø80		inch, mm	CB12-AMaP80			Included	
Ø100		inch	CB16-AMP100	100	Steel		
Ø100		mm	CB16-AMP100M				
Ø125	Coolant bolt	inch	CB20-AMP125				
Ø125		mm	CB20-AMP125M	100			
Ø160		inch	CB24-AMP160				
Ø160		mm	CB20-AMP125M				
Ø200			CCV-AMP200	1			
Ø250	Coolant cover	inch, mm	CCV-AMP250	$6^{\circ}$	Aluminum	Extra charge	
Ø315			CCV-AMP315				




### Good performance in small-medium size of operations

### Aero Mill-Mini

- · Good performance in small-medium size of operations
- Good duration of the steel body
- · Choice of Uncoated carbide/PCD grades can be applied to various kind of work material
- Balance level: G2.5

### Features of cutter


- Simple and strong design of Screw-on clamping.
- Adjustable range: ± 0.1 mm Max
- · Adjustable step: Min. 2 micro meter
- · Wide chip pocket area for Roughing and Aluminum machining.
- · Inner coolant system




### Code system



### Application range



### Recommended cutting condition





#### Max. RPM

Diameter	Max. RPM (min <sup>-1</sup> )
Ø32	26,000
Ø40	24,500
Ø50	22,000
Ø63	20,000

# APD(M)-A

### Cartridge + insert









• AR: 6° • RR: 5°~9°

(mm)

D	esignation	0	ØD	ØD1	Ød	а	b	E	F	ар	Max rpm	∑ kg \	Fig.
APD	080R/L-A6Z	6	80	76	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	10	16000	0.75	1
(APDM)	100R/L-A6Z	6	100	95	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	50	10	15000	0.95	2
	125R/L-A8Z	8	125	120	38.1 (40)	15.9 (16.4)	10 (9)	38 (30)	63	10	12500	1.8	2
	160R/L-A10Z	10	160	155	50.8 (40)	19.0 (16.4)	11 (9)	38 (30)	63	10	10000	2.9	2
	200R/L-A12Z	12	200	195	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	10	8000	4.0	3
	250R/L-A16Z	16	250	245	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	63	10	6500	6.3	3
	315R/L-A18Z	18	315	310	47.625 (60)	25.4 (25.7)	14 (14)	38 (38)	80	10	5000	11.3	4
	200R/L-A12Z 250R/L-A16Z	12 16	200 250	195 245	47.625 (60) 47.625 (60)	25.4 (25.7) 25.4 (25.7)	14 (14) 14 (14)	38 (38) 38 (38)	63 63	10	8000 6500	4.0	

( )Metric size

### Available inserts

CDEW-XCF CDEW-XAF,NAF CDEW-XAW,NAW







			-			1
			Uncoated		PCD	
Designation		H01	G10	ST30A	DP200	page
CDEW	1204R-XCF	•				
	1204L-XCF					
	1204R-XAF				•	
	1204L-XAF					
	1204R-NAF				•	E07
	1204L-NAF					E07
	1204R-XAW				•	
	1204L-XAW					
	1204R-NAW		·		•	
	1204L-NAW					

### Available arbors


Desig	nation	General arbors	NC arbors		
APD	080R/L	NT*□□(M/U)-FMA25.4-25	BT**□□-FMA25.4		
(APDM)	100R/L	NT*□□(M/U)-FMA31.75-□□	BT**□□-FMA31.75		
	125R/L	NT*□□(M/U)-FMA38.1-□□	BT**□□-FMA38.1		
	160R/L	NT*□□(M/U)-FMA50.8-□□	BT**□□-FMA50.8		
	200R/L	NT*□□(M/U)-FMA47.625-25,	BT** -FMA47.625-		
	250R/L	KCP-8***	DIFIVIA47.025		
	315R/L	KCP-8*** (Center ring plug)	-		

<sup>\* -</sup>NT number \*\* -BT number \*\*\*Over milling 5

### Recommended cutting condition

Workpiece	Cutting c	Cutting condition						
Workpiece	vc (m/min)	fz (mm/t)	Grades					
Aluminum	1,000~4,000 500~2,500	0.05~0.30 0.05~0.20	DP200 H01					


Specification	Cartridge	Chip cover	Chip cover Screw	Insert screw	Adjust screw	Cartridge Screw	Wrench for insert	Wrench for cartridge
Ø80~Ø315	LAPDR/L-AJ	CAPDR/L-AJ	PTMA0411	FTNA0411	AZ0514	BHA0619-NYLOK	TW15S	HW50




# APD(M)-PB

### **Blade**













• AR: 6° • RR: -4°~1°

(mm)

De	esignation	0	Max	ØD	ØD1	Ød	а	b	E	F	ар	kg	Fig.
APD	080R/L-PB6Z	6	10	80	77	25.4 (27)	9.5 (12.4)	6 (7)	23.5	50	5	0.55	1
(APDM)	080R/L-PB8Z	8	10	80	77	25.4 (27)	9.5 (12.4)	6 (7)	23.5	50	5	0.55	1
	100R/L-PB6Z	6	12	100	97	31.75 (32)	12.7 (14.4)	8	34 (32)	50	5	0.92	2
	100R/L-PB8Z	8	12	100	97	31.75 (32)	12.7 (14.4)	8	34 (32)	50	5	0.92	2
	125R/L-PB8Z	8	14	125	122	38.1 (40)	15.9 (16.4)	10 (9)	40 (35)	63	5	1.9	2
	125R/L-PB10Z	10	14	125	122	38.1 (40)	15.9 (16.4)	10 (9)	40 (35)	63	5	1.9	2
	160R/L-PB10Z	10	20	160	157	50.8 (40)	19.0 (16.4)	11 (9)	41 (35)	63	5	3.3	2
	160R/L-PB12Z	12	20	160	157	50.8 (40)	19.0 (16.4)	11 (9)	41 (35)	63	5	3.3	2

( )Metric size

### Available blades

Available blades	BAMPR-XAF	BAMPR-XAW	BAMPR-XAWR
	20	20	20

	PCD	
Designation	DP150	page
BAMPR-XAF		
BAMPR-XAW	•	E07
BAMPR-XAWR	•	

### Available arbors


	Designation	NC arbors
APD-PB	080R/L-PB□□Z	BT□□-FMA25.4(FMC27)-□□
(APDM-PB)	100R/L-PB□□Z	BT□□-FMA31.75(FMC32)-□□
	125R/L-PB□□Z	BT□□-FMA38.1(FMB40)-□□
	160R/L-PB□□Z	BT□□-FMA50.8(FMB/FMC40)-□□


Specification						anor)	
	Blade screw	Blade adjustable screw	Al-body protecting tap	Balancing screw	Wrench for insert	Wrench for cartridge	
Ø80~Ø160	ETKA0620	AZ0514-SPN6	UZD1010	KHE0610	SPN-6	TW25-100	

# APD(M)-PB

### Blade













(mm)

De	esignation	0	Max	ØD	ØD1	Ød	а	b	Е	F	ар		Fig.
APD	200R/L-PB12Z	12	26	200	197	47.625 (60)	25.4 (25.7)	14	40	63	5	4.0	1
(APDM)	250R/L-PB16Z	16	32	250	247	47.625 (60)	25.4 (25.7)	14	40	63	5	6.5	1
	315R/L-PB18Z	18	42	315	312	47.625 (60)	25.4 (25.7)	14	40	63	5	11.3	2

( )Metric size

### Available blades


BAMPR-XAF	F BAMPR-XAW	BAMPR-XAWI
20	20	- 5


	PCD	
Designation	DP150	page
BAMPR-XAF		
BAMPR-XAW	•	E07
BAMPR-XAWR	•	

### Available arbors

	Designation	NC arbors
APD-PB	200R/L-PB□□Z	
(APDM-PB)	250R/L-PB□□Z	BT□□-FMA47.625(FMB60)-□□
	315R/L-PB□□Z	

Specification						South State of the	
	Blade screw	Blade adjustable screw	Al-body protecting tap	Balancing screw	Wrench for insert	Wrench for cartridge	
Ø200~Ø315	ETKA0620	AZ0514-SPN6	UZD1010	KHE0610	SPN-6	TW25-100	










# MAPDS000HR/L-Z0













(mm)

Designation		<b>©</b>	ØD	Ød	Q	L	ар	Max rpm	kg
MAPDS	032HR/L-Z3	3	32	20	35	100	9.5	26,000	0.35
	040HR/L-Z4	4	40	20	35	100	9.5	24,500	0.42

### Available inserts

SNEW SNEW-XAF SNEW-NAF


Strengthened edge

Designation			Uncoated		PCD			
		H01	G10	ST30A	DP200	page		
SNEW	09T3ADFR	•						
	09T3ADTR-XAF				•			
	09T3ADTR-XAW				•	E24		
	09T3ADTR-NAF				•			
	09T3ADTR-NAW				•			

Specification						
	Insert screw	Adjust screw	Balance screw	Wrench for insert	Adjust wrench	
Ø32~Ø63	FTKA0408	AHX0617F-NYLOK	KHD0405	TW15S	HW20L	

### MAPD000HR/L-Z0













(mm)

D	esignation	<b>(b)</b>	ØD	ØD2	Ød	а	b	E	F	Ød1	Ød2	ар	Max rpm	kg
MAPD	040HR/L-Z4	4	40	34	16	8.4	5.6	18	40	9	14	9.5	24,000	0.24
	050HR/L-Z5	5	50	42	22	10.4	6.3	20	40	11	18	9.5	22,000	0.35
	063HR/L-Z6	6	63	42	22	10.4	6.3	20	40	11	18	9.5	20,000	0.65

### Available inserts

SNEW SNEW-XAF SNEW-NAF







Strengthened edge

			Unco	oated		PCD	
Designation		H01	G10	ST30A	ST20	DP200	page
SNEW	09T3ADFR	•					
	09T3ADTR-XAF					•	
	09T3ADTR-XAW					•	E24
	09T3ADTR-NAF					•	
	09T3ADTR-NAW					•	

### Available arbors

	Designation	NC arbors					
MAPD	040HR/L-Z4	BT**□□-FMC16-□□					
	050HR/L-Z5	BT**□□-FMC22-□□					
	063HR/L-Z6	BT**□□-FMC22-□□					

### Recommended cutting condition

Moukniese	Cutting of	Grades	
Workpiece	vc (m/min)	fz (mm/t)	Grades
Aluminum	1,000~4,000 500~2,500	0.05~0.30 0.05~0.20	DP200 H01

### Coolant bolt (Not included)

Designation	Applicable cutter	Available cutters
CB0525	MAPD040HR/L-Z4	Ø40
CB1025	MAPD050HR/L-Z5	Ø50
CB1025	MAPD063HR/L-Z6	Ø63

Specification					
•	Insert screw	Adjust screw	Balance screw	Wrench for insert	Adjust wrench
Ø32~Ø63	FTKA0408	AHX0617F-NYLOK	KHD0405	TW15S	HW20L


# **E** PCD Face Cutter

### Code system



### **PCD Face cutter**









(mm)

	Designation	©	ØD	r	ар	Q	L
PDF	4032-HSK50A	4	32	0.5	8	50	120
	4040-HSK50A	4	40	0.5	8	50	120
	4032-HSK63A	4	32	0.5	8	50	120
	4040-HSK63A	4	40	0.5	8	50	120
	4050-HSK63A	4	50	0.5	8	50	120
	6063-HSK63A	6	63	0.5	12	-	100
	6063-HSK100A	6	63	0.5	12	-	100


### Recommended cutting condition


Workpiece	vc (m/min)	fz (mm/t)	ap (mm)
Al, Brass, Alloy	200~2,000	0.02~0.1	0.05~4.0

### **Special PCD order sheet**









Designation	Fig	tooth	Dimensions (mm)							
Designation	Fig.	tooth	ØD	r	ар	Q	L	Shank spec.		
PDF										


### Various applications are available with multi-functional cutters

# Alpha Mill

- Innovative curve cutting-edge and chip-breaker design ensures ideal 90-degree cutting, lower cutting resistance, and improved insert life.
- Various applications are available with multi-functional cutters. (Facing, Slotting, Square shoulder milling, etc.)
- Excellent performance ensured at large depth of cut operations due to strong cutting-edge and low cutting resistance.


### Features of insert

- · Long tool life at high speed, high feed and deeper cutting by low cutting resistance and strong cutting-edge
- Distinguished features of Alpha-Curve reduce cutting resistance and improve cutting-edge strength and wear resistance



- Low cutting resistance is realized by KORLOY unique design-the alpha curve cutting-edge and optimal convex and concave design
- · Highly efficient machining is available by the ideal application of the grade to material

### Application example





# E Technical Information for Alpha Mill


## Alpha Mill Nick new

- New nick cutting edge reduces cutting load
- High productivity
- APMT standard holders are compatible with Alpha Mill nick that is reducing stock management cost.

### Features

· Lower cutting load due to the overlapping system





- ※ Nick types require both chip breaker types for application.
- \*\* Can be used with the existing Alpha Mill holders. Use multi-edges for maximum results. (cutters with even-numbered teeth)

Туре	Nick	type	General type
Required No. of teeth	2	20	20
For AMCM3080M (4 Flute x 5 teeth)	x 10 APMT16-MN3	x 10 APMT16-MN4	x 20 APMT16- <b>MM, MF, ML, MA</b>

### How to clamp

· Alternate the two types of chip breakers when clamping an insert.





### Min. depth of cut

• The depth of cut must be greater than ap min1 for chip breaking.




ap min1	ap min2
1.6 mm	4.1 mm
2.2 mm	5 mm
2.3 mm	5.5 mm
	1.6 mm 2.2 mm

### Application examples

Deep cutting	Long overhang	Unstable clamping

### Application area



• 30% or higher cutting conditions available compared to normal types

### Recommended cutting condition

100	ISO Grades	А	PMT 2000 typ	е	А	PMT 3000 typ	е	APMT 4000 type			
150	Grades	vc (m/min)	fz (mm/t)	ap (mm)	vc (m/min)	fz (mm/t)	ap (mm)	vc (m/min)	fz (mm/t)	ap (mm)	
P	PC3700	180~280	0.05~0.15		160~270	0.05~0.18		160~270	0.05~0.18		
	PC5300	150~250	0.05~0.15	44	150~240	0.05~0.18	16	150~240	0.05~0.18	17	
M	PC5300	90~170	0.05~0.15	11	90~150	0.05~0.18		90~150	0.05~0.18		
К	PC5300	120~240	0.1~0.2		120~200	0.1~0.23		120~200	0.1~0.23		

### Features of chip breakers

	Insert	Cutting-edge	Uses	Features
MA			Al	Optimal cutting-edge and buffed surface for aluminum workpieces ensure high performance in machining
ML			Hard-to-cut material	Chip breaker with low cutting load is optimal for machining hard-to-cut materials
MF			Light cutting	Chip breaker with low cutting load and harder cutting-edge than ML's are optimal for light cutting
ММ			General cutting	Optimal for milling in general ranges
MN			Roughing (Nick)	Design for easy chip cutting ensures high machinability in toughing



# E Technical Information for Alpha Mill

### Product constitution


Item description	Туре	Nose R	MA	ML
	1000 h	0.4	APMT0602PDFR-MA	-
	1000 type	0.8	APMT060208PDFR-MA	-
	4500 h	0.4	APMT0903PDFR-MA	APMT0903PDER-ML
	1500 type	0.8	APMT090308PDFR-MA	APMT090308PDER-ML
	0000 to	0.5	APMT11T3PDFR-MA	APMT11T3PDER-ML
	2000 type	0.8	APMT11T308PDFR-MA	APMT11T308PDER-ML
	0000 to	0.4	APMT160404PDFR-MA	APMT160404PDER-ML
APMT	3000 type	0.8	APMT1604PDFR-MA	APMT1604PDER-ML
		0.4	APMT180604PDFR-MA	APMT180604PDER-ML
		0.8	APMT1806PDFR-MA	APMT1806PDER-ML
		1.2	APMT180612PDFR-MA	APMT180612PDER-ML
	4000 type	1.6	APMT180616PDFR-MA	APMT180616PDER-ML
		2.0	APMT180620PDFR-MA	APMT180620PDER-ML
		2.4	APMT180624PDFR-MA	APMT180624PDER-ML
		3.0	APMT180630R-MA	APMT180630R-ML


<sup>-</sup> The inserts can switch to the APMT type holders.


### ▶ Recommended grades and chip breakers by workpiece

ær					Recomi	mended C	/B and gra	de as per	workpiece	(•: 1 <sup>st</sup> )			
Chip breaker	Cutter		I	•		ľ	M		K		N		S
d qi	edge	Low carbon s	teel/Mild steel	High carbon steel/Mild steel		Stainless steel		Cast iron		Aluminum alloy		Ti/Inconel	
בֿ		C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades
MA		-	-	-	-	-	-	-	-	•	• H01	-	-
ML		-	-	-	-	•	● PC5300 ○ PC5400 ○ PC9530	-	-	-	-	•	● PC5300 ○ PC5400
MF		•	<ul><li>PC3700</li><li>PC5300</li><li>PC5400</li><li>NCM325</li><li>NCM335</li></ul>	-	○ PC3700 ○ NCM325 ○ NCM335	-	• PC5300 • PC5400 • PC9530	-	● PC6510 ○ PC5300 ○ PC5400	-	-	-	● PC5300 ○ PC5400
ММ		-	<ul><li>PC3700</li><li>PC5300</li><li>PC5400</li><li>NCM325</li><li>NCM335</li></ul>	•	<ul><li>PC3700</li><li>PC5300</li><li>PC5400</li><li>NCM325</li><li>NCM335</li></ul>	-	• PC5300 • PC5400 • PC9530	•	● PC6510 ○ PC5300 ○ PC5400	-	-	-	● PC5300 ○ PC5400
MN		-	• PC3700 • PC5300 • PC5400	-	-	-	<ul><li>PC5300</li><li>PC5400</li><li>PC9530</li></ul>	-	• PC6510 • PC5300 • PC5400	-	-	-	• PC5300 • PC5400

### Recommended depth of cut







### **○** Recommended cutting condition (for Multi-edge type)

							Tool	dia.				
Workpiece	Grades	Fig.	Ø10	, 16	Ø20	, 25	Ø32	, 40	Ø50	, 63	Ø80,	100
			vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)
Mild steel,	NCM535	1	50~80	0.05~0.08	80~100	0.05~0.08	100~120	0.05~0.08	100~120	0.05~0.08	100~120	0.05~0.08
Low carbon	NCM325 PC5400 PC5300	2	65~90	0.08~0.1	100~120	0.08~0.1	120~140	0.08~0.1	120~140	0.08~0.1	120~140	0.08~0.1
steel)	PC3700	3	65~95	0.1~0.15	100~120	0.1~0.15	120~140	0.1~0.15	120~140	0.1~0.15	130~150	0.1~0.15
High carbon	NCM535	1	45~60	0.05	60~80	0.05	80~100	0.05	80~100	0.05	80~100	0.05
steel,	NCM325 PC5300	2	50~80	0.05~0.08	80~100	0.05~0.08	100~120	0.08~0.1	100~120	0.08~0.1	100~120	0.08~0.1
Alloy steel	PC3700	3	50~80	0.1~0.15	80~100	0.1~0.15	110~130	0.1~0.15	100~120	0.1~0.15	110~130	0.1~0.15
Allendeel	PC5300	1	40~55	0.05	50~70	0.05	70~90	0.05	70~90	0.05	70~90	0.05
Alloy tool steel	PC3700 PC2510	2	45~60	0.05~0.08	60~80	0.05~0.08	90~120	0.05~0.08	100~120	0.05~0.08	100~120	0.05~0.08
steel	PC2505	3	50~75	0.12~0.18	90~110	0.12~0.18	100~130	0.1~0.15	100~120	0.1~0.15	110~130	0.1~0.15
Otoinlass	PC5300 PC9530	1	35~50	0.054	50~70	0.054	70~90	0.05	70~90	0.05	70~90	0.05
Stainless steel		2	45~60	0.05~0.08	60~80	0.05~0.08	90~120	0.05~0.08	100~120	0.05~0.08	100~120	0.05~0.08
Steel		3	50~75	0.1~0.15	90~110	0.1~0.15	100~130	0.1~0.15	110~130	0.1~0.15	110~130	0.1~0.15
		1	50~70	0.1~0.12	70~90	0.1~0.12	70~90	0.1~0.12	90~120	0.1~0.12	90~120	0.1~0.12
Cast iron	PC6510 PC5300	2	50~80	0.12	80~100	0.12	90~120	0.12	100~140	0.12	100~140	0.12
		3	50~80	0.15~0.2	80~100	0.15~0.2	100~130	0.15~0.2	120~150	0.15~0.2	120~150	0.15~0.2
		1	160~600	0.1~0.2	200~800	0.1~0.2	300~900	0.1~0.2	400~1,000	0.1~0.2	400~1,000	0.1~0.2
Aluminum alloy	H01	2	200~650	0.15~0.3	250~900	0.15~0.3	300~950	0.15~0.3	400~1,000	0.1~0.4	400~1,000	0.1~0.4
anoy		3	200~650	0.15~0.3	250~900	0.15~0.3	300~950	0.15~0.3	400~1,000	0.1~0.4	400~1,000	0.1~0.4
Handanad	PC5300	1	35~50	0.03	50~70	0.03	60~90	0.03	60~90	0.03	60~90	0.03
Hardened steel	PC2510	2	45~60	0.05~0.08	60~80	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08
	PC2505	3	50~80	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08

### Recommended cutting condition (for Single-edge type)

							Tool					
Workpiece	Grades	Fig.	Ø10	, 16	Ø20	, 25	Ø32	, 40	Ø50	, 63	Ø80,	100
			vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)
Mild steel,	NCM535 NCM325	1	45~60	0.05~0.08	60~80	0.05~0.08	80~120	0.05~0.08	120~200	0.05~0.08	150~200	0.05~0.08
low carbon	PC5400 PC5300	2	60~90	0.08~0.1	80~120	0.08~0.1	120~180	0.08~0.1	180~250	0.08~0.1	200~250	0.08~0.1
steel	PC3700	3	60~90	0.1~0.15	80~120	0.1~0.15	120~180	0.1~0.15	180~250	0.1~0.15	200~250	0.1~0.15
High carbon	NCM535	1	40~60	0.05	50~80	0.05	80~110	0.05	100~150	0.05	100~150	0.05
steel,	NCM325 PC5300	2	50~80	0.05~0.08	80~100	0.05~0.08	110~150	0.05~0.1	150~200	0.05~0.1	150~200	0.05~0.1
alloy steel	PC3700	3	50~80	0.1~0.15	80~100	0.1~0.15	120~150	0.1~0.15	180~200	0.1~0.15	180~200	0.1~0.15
Alleraterat	PC5300	1	35~50	0.05	50~70	0.05	80~100	0.05	100~130	0.05	100~130	0.05
Alloy tool steel	PC3700 PC2510	2	45~70	0.05~0.08	70~100	0.05~0.08	100~130	0.05~0.1	130~180	0.05~0.1	130~180	0.05~0.1
steel	PC2505	3	45~70	0.1~0.15	70~100	0.1~0.15	100~150	0.1~0.15	130~180	0.1~0.15	130~180	0.1~0.15
Stainless steel		1	35~50	0.05	50~70	0.05	80~100	0.05	100~130	0.05	100~130	0.05
	PC5300 PC9530	2	45~70	0.05~0.08	70~100	0.05~0.08	100~130	0.05~0.1	130~180	0.05~0.1	130~180	0.05~0.1
Steel		3	45~70	0.1~0.15	70~100	0.1~0.15	100~150	0.1~0.15	130~180	0.1~0.15	130~180	0.1~0.15
		1	50~80	0.08~0.12	80~100	0.08~0.12	80~100	0.15	120~150	0.15	120~150	0.15
Cast iron	PC6510 PC5300	2	65~90	0.12~0.15	100~120	0.12~0.15	100~130	0.15~0.18	150~200	0.15~0.18	150~200	0.15~0.18
		3	65~90	0.15~0.2	100~120	0.15~0.2	100~130	0.15~0.2	150~200	0.15~0.2	150~200	0.15~0.2
A1		1	200~600	0.15~0.2	250~800	0.15~0.2	300~900	0.15~0.2	400~1,000	0.1~0.2	400~1,000	0.1~0.2
Aluminum alloy	H01	2	200~650	0.2~0.25	250~900	0.2~0.25	350~950	0.2~0.25	400~1,000	0.2~0.3	400~1,000	0.2~0.3
anoy		3	200~650	0.25~0.3	250~900	0.25~0.3	350~950	0.25~0.3	400~1,000	0.3~0.4	400~1,000	0.3~0.4
	PC5300	1	35~50	0.03	50~70	0.03	60~90	0.03	60~90	0.03	60~90	0.03
Hardened steel	PC2510	2	45~65	0.05~0.08	60~80	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08
31661	PC2505	3	50~80	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08	80~100	0.05~0.08




# E Technical Information for Alpha Mill


### Cutting condition for ramping and helical operation


1. Ramping

2. Helical cutting for blind hole

3. Helical cutting for through hole







(mm)

			1. Ran	nping	2. I	Helical cutti	ng for blind ho	le	3. Helical cutting	for through hole
Designation	Tool dia. ØD (min)	ар	Maximum angle α(°)	Lmin	Min. desirable hole dia. ØDHmin	Max. pitch dmax	Max. desirable hole dia. ØDHmax	Max. pitch dmax	Min. desirable hole dia. ØDHmin	Max. pitch dmax
AMS1010HS	10		6.5	44	17.6	2.0	18.8	2.1	13	1.5
AMS1011HS	11		5.6	51	19.6	1.9	20.8	2.0	15	1.5
AMS1012HS	12		4.9	58	21.6	1.9	22.8	2.0	17	1.5
AMS1014HS	14		3.9	73	25.6	1.8	26.8	1.8	21	1.4
AMS1015HS	15		3.6	80	27.6	1.7	28.8	1.8	23	1.4
AMS1016HS	16		3.3	87	29.6	1.7	30.8	1.8	25	1.4
AMS1017HS	17		3.0	94	31.6	1.7	32.8	1.7	27	1.4
AMS1018HS	18		2.8	101	33.6	1.7	34.8	1.7	29	1.4
AMS1020HS	20		2.5	115	37.6	1.6	38.8	1.7	33	1.4
AMS1021HS	21	5	2.3	123	39.6	1.6	40.8	1.7	35	1.4
AMS1022HS	22		2.2	130	41.6	1.6	42.8	1.6	37	1.4
AMS1025HS	25		1.9	151	47.6	1.6	48.8	1.6	43	1.4
AMS1026HS	26		1.8	158	49.6	1.6	50.8	1.6	45	1.4
AMS1032HS	32		1.4	201	61.6	1.5	62.8	1.6	57	1.4
AMS1033HS	33		1.4	208	63.6	1.5	64.8	1.6	59	1.4
AMCM1032HS	32		1.4	201	61.6	1.5	62.8	1.6	57	1.4
AMCM1040HS	40		1.1	258	77.6	1.5	78.8	1.5	73	1.4
AMCM1050HS	50		0.9	330	97.6	1.5	98.8	1.5	93	1.4
AMCM1063HS	63		0.7	423	123.6	1.5	124.8	1.5	119	1.4
AMS1510HS	10		7.5	68	17.4	2.3	18.8	2.5	11	1.5
AMS1512HS	12		6.5	79	21.4	2.4	22.8	2.6	15	1.7
AMS1513HS	13		5.7	90	23.4	2.3	24.8	2.5	17	1.7
AMS1514HS	14		6.3	82	25.4	2.8	26.8	2.9	19	2.1
AMS1516HS	16		5.0	102	29.4	2.6	30.8	2.7	23	2.0
AMS1517HS	17		4.6	112	31.4	2.5	32.8	2.6	25	2.0
AMS1518HS	18		4.2	122	33.4	2.5	34.8	2.6	27	2.0
AMS1519HS	19		3.9	132	35.4	2.4	36.8	2.5	29	2.0
AMS1520HS	20		3.6	142	37.4	2.4	38.8	2.5	31	2.0
AMS1521HS	21		3.4	152	39.4	2.3	40.8	2.4	33	2.0
AMS1522HS	22		3.2	162	41.4	2.3	42.8	2.4	35	1.9
AMS1524HS	24	9	2.8	182	45.4	2.2	46.8	2.3	39	1.9
AMS1525HS	25		2.7	192	47.4	2.2	48.8	2.3	41	1.9
AMS1528HS	28		2.3	222	53.4	2.2	54.8	2.2	47	1.9
AMS1530HS	30		2.1	242	57.4	2.1	58.8	2.2	51	1.9
AMS1532HS	32		2.0	262	61.4	2.1	62.8	2.2	55	1.9
AMS1535HS	35		1.8	292	67.4	2.1	68.8	2.1	61	1.9
AMS1540HS	40		1.5	342	77.4	2.0	78.8	2.1	71	1.9
AMCM15040HS	40		1.5	342	77.4	2.0	78.8	2.1	71	1.9
AMCM15050HS	50		1.2	442	97.4	2.0	98.8	2.0	91	1.9
AMCM15063HS	63		0.9	572	123.4	1.9	124.8	2.0	117	1.8
AMCM15080HS	80		0.7	742	157.4	1.9	158.8	1.9	151	1.8
AMCM15100HS	100		0.5	942	197.4	1.9	198.8	1.9	191	1.8





### Cutting condition for ramping and helical operation


1. Ramping

2. Helical cutting for blind hole

3. Helical cutting for through hole








(mm)

			1. Ran	nping	2. I	Helical cutti	ng for blind ho	le	3. Helical cutting	for through hole
Designation	Tool dia. ØD (min)	ар	Maximum angle α(°)	Lmin	Min. desirable hole dia. ØDHmin	Max. pitch dmax	Max. desirable hole dia. ØDHmax	Max. pitch dmax	Min. desirable hole dia. ØDHmin	Max. pitch dmax
AMS2010HS	10		16.82	33	16.4	5.0	18	5.4	11	3.3
AMS2012HS	12		11.69	48	20.4	4.2	22	4.6	15	3.1
AMS2014HS	14		7.55	75	24.4	3.2	26	3.4	19	2.5
AMS2016HS	16		10.30	55	28	5.1	30	5.5	23	4.2
AMS2018HS	18		8.23	69	32	4.6	34	4.9	27	3.9
AMS2020HS	20		5.60	102	36	3.5	38	3.7	31	3.0
AMS2022HS	22		5.15	111	40	3.6	42	3.8	35	3.2
AMS2025HS	25		3.92	146	46	3.2	48	3.3	41	2.8
AMS2032HS	32	10	2.70	212	60	2.8	62	2.9	55	2.6
AMS2040HS	40		1.98	289	76	2.6	78	2.7	71	2.5
AMS2050HS	50		1.48	386	96	2.5	98	2.5	91	2.4
AMS2063HS	63		1.11	514	122	2.4	124	2.4	117	2.3
AMCM2040HS	40		1.29	445	76	2.5	78	2.6	71	2.1
AMCM2050HS	50		0.36	1576	96	0.6	98	0.6	91	0.6
AMCM2063HS	63		0.27	2104	122	0.6	124	0.6	117	0.6
AMCM2080HS	80		0.21	2784	156	0.6	158	0.6	151	0.5
AMCM2100HS	100		0.16	3584	196	0.5	198	0.6	191	0.5
AMS3025HS	25		4.72	121	46	3.8	48	4.0	36	3.0
AMS3032HS	32		3.00	191	60	3.1	62	3.2	50	2.6
AMS3040HS	40		2.29	250	76	3.0	78	3.1	66	2.6
AMS3050HS	50		1.64	350	96	2.7	98	2.8	86	2.5
AMS3063HS	63	10	1.22	470	122	2.6	124	2.6	112	2.4
AMCM3040HS	40		1.99	288	76	2.6	78	2.7	66	2.3
AMCM3050HS	50		1.67	343	96	2.8	98	2.9	86	2.5
AMCM3063HS	63		1.22	470	122	2.6	124	2.6	112	2.4
AMCM3080HS	80		0.90	636	156	2.5	158	2.5	146	2.3
AMCM3100HS	100		0.69	830	196	2.4	198	2.4	186	2.2
AMS2025MH	25	10	1.50	764	46	1.2	48	1.3	-	
AMS2032MH	32		1.50	1146	60	1.6	62	1.6	-	
AMS3040MH	40	16	1.50	1528	76	2.0	78	2.0	-	
AMS4020HS	20		9.5	98	37.4	6.2	38.8	6.5	31	5.2
AMS4021HS	21		5.2	179	39.4	3.6	40.8	3.7	33	3.0
AMS4025HS	25		7.6	122	47.4	6.3	48.8	6.5	41	5.5
AMS4026HS	26		7.1	130	49.4	6.2	50.8	6.4	43	5.4
AMS4032HS	32		3.4	276	61.4	3.6	62.8	3.7	55	3.3
AMS4033HS	33		3.2	288	63.4	3.6	64.8	3.7	57	3.2
AMS4040HS	40	16	2.5	376	77.4	3.4	78.8	3.4	71	3.1
AMS4050HS	50		1.9	502	97.4	3.2	98.8	3.2	91	3.0
AMS4063HS	63		1.4	665	123.4	3.0	124.8	3.1	117	2.9
AMCM4050HS	50		1.9	502	97.4	3.2	98.8	3.2	91	3.0
AMCM4063HS	63		1.4	665	123.4	3.0	124.8	3.1	117	2.9
AMCM4080HS	80		1.1	878	157.4	2.9	158.8	2.9	151	2.8
AMCM4100HS	100		0.8	1128	197.4	2.9	198.8	2.9	191	2.8
AMCM4125HS	125		0.6	1442	247.4	2.8	248.8	2.8	241	2.7



# **AMC(M)1000S**

















• AR: 9°~13° • RR: -14°~5°

Des	signation	<b>(</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg
AMCM	1032HS	8	32	30	16	9	14	8.4	5.6	19	40	5.6	0.15
	1040HS-16	10	40	34	16	9	14	8.4	5.6	19	40	5.6	0.24
	1040HS-22	10	40	34	22	11	18	10.4	6.3	21	40	5.6	0.24
	1050HS	12	50	42	22	11	18	10.4	6.3	21	40	5.6	0.36
	1063HS	14	63	49	22	11	18	10.4	6.3	21	40	5.6	0.61

### Available inserts

APMT-MA







		Cer	met						C	oate	d						Unc	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0602PDFR-MA																	•	
	060208PDFR-MA																		
	060202PDSR-MM			•							•				•	•			
	0602PDSR-MM			•					•	•	•	•	•		•	•			E05
	060208PDSR-MM			•							•				•	•			
	060212R-MM			•											•	•			
	060216R-MM														•	•			


### Available arbors

	Designation	Ød	NC arbors
AMCM	1032HS	16	BT□□-FMC16-□□
	1040HS-16	10	BIFMC10
	1040HS-22		
	1050HS	22	BT□□-FMC22-□□
	1063HS		

Specification	<b>6</b>		
	Screw	Wrench	
Ø32~Ø63	FTKA01842	TW06S-A	

# **AMC(M)1500S**



















(mm)

														()
De	signation	0	ØD	ØD2	Ød	Ød1	Ød2	Ødз	а	b	E	F	ар	kg
AMCM	15040HS	5	40	34	16	9	14	-	8.4	5.6	19	40	9	0.22
	15050HS	6	50	42	22	11	18	-	10.4	6.3	21	40	9	0.34
	15063HS	8	63	49	22	11	18	-	10.4	6.3	21	40	9	0.57
AMC	15080HS	10	80	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	9	1.10
(AMCM)	15100HS	12	100	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (26)	63	9	2.10

( )Metric size

### Available inserts




					-														
		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E05
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

### Available arbors

	Designation	Ød	NC arbors
AMCM	15040HS	16	BT□□-FMC16-□□
	15050HS 15063HS	22	BT FMC22-
AMC	15080HS	25.4	BT□□-FMA25.4-□□
(AMCM)	13000013	27	BT□□-FMC27-□□
	15100HS	31.75	BT□□-FMA31.75-□□
		32	BT□□-FMC32-□□

### Parts


Specification		
Specification	₩/	
	Screw	Wrench
Ø40~Ø100	FTKA02565S	TW08S



Available arbors and bolt E426~E428

# **AMC(M)2000S**

















• AR: 9°~13° • RR: -14°~5°

(mm)

Des	signation	0	ØD	ØD2	Ød	Ød1	Ød2	Ødз	а	b	E	F	ар	kg
AMCM	2040HS	5	40	34	16	9	14	-	8.4	5.6	18	40	11	0.22
	2050HS	6	50	42	22	11	18	-	10.4	6.3	20	40	11	0.34
	2063HS	8	63	49	22	11	18	-	10.4	6.3	20	40	11	0.57
AMC	2080HS	8	80	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	25 (22)	50	11	1.10
(AMCM)	2100HS	10	100	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (28)	63	11	2.10

( )Metric size

### Available inserts

	APMT-M	Α	ļ	APMT-	ML		APM	Т-ММ		AP	мт-м	F	-	APMT-	MN			
	6	new	(	6	nev	9	-		,	•	9		4		nev	<b>y</b>		
	Cei	rmet						(	Coate	d						Unc	oated	
Designation	V2500	130	25330	CM325	CM335	CM535	CM545	22505	2510	33700	36510	39230	39540	25300	5400	0	=	ı

		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	11T3PDFR-MA																	•	
	11T308PDFR-MA																		
	11T3PDER-ML														•	•			
	11T308PDER-ML														•	•			
	11T3PDSR-MM			•	•		•		•	•	•	•	•		•	•			
	11T3PDSR-MF			•							•	•			•	•			
	11T308PDSR-MM			•							•		•	•	•	•			E06
	11T312PDSR-MM			•							•		•		•	•			
	11T316R-MM			•							•				•	•			
	11T318R-MM																		
	11T324R-MM			•							•				•	•			
	11T3PDSR-MN2														•				
	11T3PDSR-MN3														•				

#### \*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.


### Available arbors

	Designation	Ød	NC arbors				
AMCM	2040HS	16	BT□□-FMC16-□□				
	2050HS 2063HS	22	BT□□-FMC22-□□				
AMC	2080HS	25.4	BT□□-FMA25.4-□□				
(AMCM)	2000113	27	BT□□-FMC27-□□				
	2100HS	31.75	BT□□-FMA31.75-□□				
	210003	32	BT□□-FMC32-□□				

Specification			
	Screw	Wrench	
Ø40~Ø100	FTKA02565S	TW08S	

# **AMC(M)3000S**





APMT-MN









APMT-MA



APMT-ML



• AR: 14° • RR: -12°~8°

r	Υ	٦	r	٦	٦	١	

De	signation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg
AMCM	3040HS	4	40	34	16	9	14	-	8.4	5.6	18	40	16	0.18
	3050HS	5	50	42	22	11	18	-	10.4	6.3	20	40	16	0.28
	3063HS	6	63	49	22	11	18	-	10.4	6.3	20	40	16	0.50
AMC	3080HS	7	80	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	25 (22)	50	16	1.02
(AMCM)	3100HS	8	100	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (28)	63	16	2.05

APMT-MM

APMT-MF

( )Metric size

### Available inserts

		6	new	(	6	net		4			•			4	\$	nev	<b>y</b>		
		Cei	rmet						C	coate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	ᅙ	page
APMT	1604PDFR-MA																	•	
	160404PDFR-MA																		
	1604PDER-ML														•	•			
	160404PDER-ML														•	•			
	1604PDSR-MM			•	•		•		•	•	•	•	•	•	•	•			
	1604PDSR-MF			•							•	•			•	•			
	160410PDSR-MM										•				•	•			E06
	160416PDSR-MM			•							•				•	•			
	160424R-MM			•							•				•	•			
	160430R-MM										•				•	•			
	160432R-MM			•							•				•	•			
	1604PDSR-MN3														•				
	1604PDSR-MN4														•				

\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 

\*\* Please use the cutters with even teeth.


### Available arbors

	Designation	Ød	NC arbors
AMCM	3040HS	16	BT□□-FMC16-□□
	3050HS 3063HS	22	BT□□-FMC22-□□
AMC	3080HS	25.4	BT□□-FMA25.4-□□
(AMCM)	3000113	27	BT□□-FMC27-□□
	3100HS	31.75	BT□□-FMA31.75-□□
	310003	32	BT□□-FMC32-□□

Specification	6		
	Screw	Wrench	
Ø40~Ø100	FTKA0410	TW15S	

# AMC(M)3000S-K



















De	signation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg
AMCM	3040HS-K	4	40	34	16	9	14	8.4	5.6	18	40	16	0.15
	3050HS-K	5	50	42	22	11	18	10.4	6.3	20	40	16	0.24
	3063HS-K	6	63	49	22	11	18	10.4	6.3	20	40	16	0.24
AMC	3080HS-K	7	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (22)	50	16	0.36
(AMCM)	3100HS-K	8	100	67	31.75 (32)	18	26	12.7 (14.4)	8 (8)	32 (28)	63	16	0.61

( )Metric size

### Available inserts

	APKT		APKT	-MF		APK	T-MM		AF	PKT-M	Α	-	APKT-	MA2		APK	T-MA3	3		
	6									9			6			4		7		
		Cer	rmet						C	oate	d						U	ncoat	ed	
	Designation	CN2500	CN30	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD2000	G10	H04	H05	page
APKT	1604PDSR			•						•	•									
	1604PDSR-MF			•										•						1
	1604PDSR-MM			•	•					•	•	•		•						1
	1604PDFR-MA															•		•	•	1
	1604PDFR-MA2																	•		E04
	160416FR-MA2																	•		1
	160432FR-MA2																			1
	1604PDFR-MA3																•	•	•	1
	160420FR-MA3																			1


### Available arbors

	Designation	Ød	NC arbors
AMCM	3040HS-K	16	BT□□-FMC16-□□
	3050HS-K	00	BT□□-FMC22-□□
	3063HS-K	22	BI LL-FMC22-LL
AMC	3080HS-K	25.4	BT□□-FMA25.4-□□
(AMCM)	3000H3-K	27	BT□□-FMC27-□□
	3100HS-K	31.75	BT□□-FMA31.75-□□
	3100H3-K	32	BT□□-FMC32-□□

Specification	<b>6</b>		
	Screw	Wrench	
Ø40~Ø100	FTKA0410	TW15S	

# **AMC(M)4000S**

















• AR: 13°~15° • RR: -12°~7°

(mm)

Des	signation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg
AMCM	4050HS	5	50	42	22	11	18	-	10.4	6.3	21	40	17	0.28
	4063HS	6	63	49	22	11	18	-	10.4	6.3	21	40	17	0.50
AMC	4080HS	7	80	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	17	1.00
(AMCM)	4100HS	8	100	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (25)	63 (50)	17	2.10
	4125HS	9	125	87	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	35 (29)	63	17	3.30
	4160S	10	160	107	50.8 (40)	-	-	100	19 (16.4)	11 (9)	38 (32)	63	17	3.6
	4200S	10	200	108	47.625 (60)	-	-	132	25.4 (25.7)	14 (14)	40 (38)	63	17	6

( )Metric size

### Available inserts

				APMT	-MA		Α	PMT-M	L		APN	лт-мм	APMT-MF	-	APMT	-MN							
			,	6		new	4	6	nev	W	4	-	•	4		O C	ew						
		Cermet			Co	oated			Un	ncoated				Cermet			(	Coate	d			Uncoated	
	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545 PC2505	PC2010 PC3700	PC6510	PC9540 PC5300	PC5400	유	page		Designation	CN2500 CN30	NC5330 NCM325	NCM335	NCM545	PC2505 PC2510	PC3700 PC6510	PC9530	PC5300	G10 H01	page
APMT	1806PDFR-MA									•		APMT	180624PDER-ML								• •	,	
	180604PDFR-MA									•			180630R-ML								• •	,	
	180612PDFR-MA									•			1806PDSR-MM		•			• •		•	•	,	
	180616PDFR-MA									•			1806PDSR-MF		•					)	• •	,	
	180620PDFR-MA									•			180612PDSR-MM		•				•		• •	,	
	180624PDFR-MA									•	F00		180616PDSR-MM		•						• •	,	F00
	180630R-MA									•	E06		180620PDSR-MM										E06
	1806PDER-ML							•	•				180624PDSR-MM		•						• •		
	180604PDER-ML							•	•				180630R-MM								• •	,	
	180612PDER-ML							•	•				180632R-MM		•						• •	,	
	180616PDER-ML							•					1806PDSR-MN3								•		
	180620PDER-ML							•	•				1806PDSR-MN4								•		

\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.

### Available arbors


Desi	gnation	Ød	NC arbors
AMCM	4050HS 4063HS	22	BT□□-FMC22-□□
AMC	4080HS	25.4	BT□□-FMA25.4-□□
(AMCM)	400003	27	BT□□-FMC27-□□
	4100HS	31.75	BT□□-FMA31.75-□□
	410005	32	BT□□-FMC32-□□

Desig	gnation	Ød	NC arbors
AMC	4125HS	38.1	BT□□-FMA38.1-□□
(AMCM)	412303	40	BT□□-FMC40-□□
	4160S	50.8	BT□□-FMA50.8-□□
	41005	40	BT□□-FMC40-□□
	4200S	47.625	BT□□-FMA47.625-□□
	42005	60	BT□□-FMB60-□□

Specification	61		
	Screw	Wrench	
Ø50~Ø200	FTKA0410	TW15S	

# AMC(M)1000SE/2000SE











• AR: 45° • RR: 0°

(mm)

Des	signation	<b>(</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	
AMCM	1040HSE	4	40	34	16	9	14	8.4	5.6	19	40	2.5	0.26
	1050HSE	5	50	42	22	11	18	10.4	6.3	21	40	2.5	0.39
AMC	2080HSE	5	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (22)	50	4	1.2
(AMCM)	2100HSE	6	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	32 (28)	63	4	2.33

( )Metric size

### Available inserts







			Cer	met						C	oate	d						Unco	oated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
	APMT	060202PDSR-MM			•							•				•	•			
1000		0602PDSR-MM			•					•	•	•	•	•		•	•			
type		060208PDSR-MM			•							•				•	•			
		060212R-MM			•											•	•			
	APMT	11T3PDSR-MM			•	•		•		•	•	•	•	•		•	•			
		11T3PDSR-MF			•							•	•			•	•			E06
		11T308PDSR-MM			•							•		•	•	•	•			
2000 type		11T312PDSR-MM			•							•		•		•	•			
type		11T316R-MM			•							•				•	•			
		11T318R-MM																		
		11T324R-MM			•							•				•	•			


### Available arbors

Туре		Designation	Ød	NC arbors
1000	AMC	1040HSE	16	BT□□-FMC16-□□
type	(AMCM)	1050HSE	22	BT□□-FMC22-□□
	AMC	2080HSE	25.4	BT□□-FMA25.4-□□
2000	(AMCM)	2000H3E	27	BT□□-FMC27-□□
2000 type		2100HSE	31.75	BT□□-FMA31.75-□□
		210005E	32	BT□□-FMC32-□□

Specification	Screw	Wrench	Wrench	
Ø40~Ø50 (1000 type)	FTKA01842	-	TW06S-A	
Ø80~Ø100 (2000 type)	FTKA02565S	TW08S	-	

# **AMC(M)3000SE**











• AR: 45° • RR: 0°

(mm)

Des	signation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	(kg)
AMC	3080HSE	4	80	57	25.4 (27)	14	20	9.5 (12.4)	6.0 (7.0)	25 (22)	50	6	1.3
(AMCM)	3100HSE	5	100	67	31.75 (32)	18	26	12.7 (14.4)	8.0 (8.0)	32 (28)	63	6	2.3

( )Metric size

### Available inserts

APMT-MM	APMT-MF

		Cer	met						(	coate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
APMT	1604PDSR-MM			•	•		•		•	•	•	•	•	•	•	•			
	1604PDSR-MF			•							•	•			•	•			
	160410PDSR-MM										•				•	•			
	160416PDSR-MM			•							•				•	•			E06
	160424R-MM			•							•				•	•			
	160430R-MM										•				•	•			
	160432R-MM			•							•				•	•			


### Available arbors

	Designation	Ød	NC arbors
AMC	3080HSE	25.4	BT□□-FMA25.4-□□
(AMCM)	(AMCM)	27	BT□□-FMC27-□□
	3100HSE	31.75	BT□□-FMA31.75-□□
	310005E	32	BT□□-FMC32-□□

J 1 0.11 1.0			
Specification			
	Screw	Wrench	
Ø80~Ø100	FTKA0410	TW08S	

# **AMC(M)2000M**













(mm)

Des	ignation	(i)	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	No. of flute	ар	kg
AMCM	2050M	16	50	40	22	11	18	10.4	6.3	21	58	4	39	0.7
AMC	2063M	16	63	50	25.4 (27)	13.5	20	9.5 (12.4)	6 (7)	25 (25)	58	4	39	0.8
(AMCM)	2080M	20	80	60	31.75 (32)	-	45	12.7 (14.4)	8 (8)	35 (28)	63	5	39	0.96
	2100M	24	100	80	38.1 (40)	-	56	15.9 (16.4)	10 (9)	38 (30)	63	6	39	1.2

( )Metric size

### Available inserts


		APM	IT-M	Α	A	APMT-	ML		APM	T-MM		AP	MT-M	F	A	APMT-	MN			
		0	6	new		6	nev		-		C.	•			4		ne	<b>»</b>		
			Cer	met						С	oate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	문	page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML															•	•			
	11T3PDSR-MM				•	•		•		•	•	•	•	•		•	•			
	11T3PDSR-MF				•							•	•			•	•			
	11T308PDSR-MM				•							•		•	•	•	•			E06
	11T312PDSR-MM				•							•		•		•	•			
	11T316R-MM				•							•				•	•			
	11T318R-MM																			
	11T324R-MM				•							•				•	•			
	11T3PDSR-MN2															•				
	11T3PDSR-MN3															•				

<sup>\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 
\* Please use the cutters with even teeth.

### Available arbors

Desig	nation	Ød	NC a	rbors
AMC	2050M	22	BT□□-FMC22-□□	BT□□-SMC22-□□
(AMCM)	2063M	25.4	BT□□-FMA25.4-□□	BT□□-SMA25.4-□□
	2003IVI	27	BT□□-FMC27-□□	BT□□-SMC27-□□
	2080M	31.75	BT□□-FMA31.75-□□	BT□□-SMA31.75-□□
	2000IVI	32	BT□□-FMC32-□□	BT -SMC32-
	2100M	38.1	BT□□-FMA38.1-□□	BT□□-SMA38.1-□□
	2100W	40	BT FMC40-	BT SMC40-


### Caution when clamping the inserts



Specification	Screw	Wrench	
Ø50~Ø100	FTKA02565S	TW08S	

# **AMC(M)3000M**













(mm)

Des	signation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	No. of flute	ар	
AMC	3063M	16	63	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	38 (38)	85	4	57	1.1
(AMCM)	3080M	20	80	67	31.75 (32)	14	26	12.7 (14.4)	8 (8)	40 (40)	100	4	71	2.23
	3100M	30	100	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	40 (40)	100	6	71	3.59

( )Metric size

### Available inserts


		API	ит-м	Α	ļ	APMT-	ML		APM'	T-MM		AP	MT-M	F	-	APMT-	MN			
		3		new	•	6	nev		-			•			4		nev	V		
			Cer	met						С	oate	d						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	1604PDFR-MA																		•	
	160404PDFR-MA																			
	1604PDER-ML															•	•			
	160404PDER-ML															•	•			
	1604PDSR-MM				•	•		•		•	•	•	•	•	•	•	•			
	1604PDSR-MF				•							•	•			•	•			
	160410PDSR-MM											•				•	•			E06
	160416PDSR-MM				•							•				•	•			
	160424R-MM				•							•				•	•			
	160430R-MM											•				•	•			
	160432R-MM				•							•				•	•			
	1604PDSR-MN3															•				
	1604PDSR-MN4															•				

\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \* Please use the cutters with even teeth.

### Available arbors

Design	nation	Ød	NC a	rbors
AMC	3063M	25.4	BT□□-FMA25.4-□□	BT□□-SMA25.4-□□
(AMCM)	SUGSIVI	27	BT□□-FMC27-□□	BT□□-SMC27-□□
	200084	31.75	BT□□-FMA31.75-□□	BT□□-SMA31.75-□□
	3080M	32	BT□□-FMC32-□□	BT□□-SMC32-□□
	210084	38.1	BT□□-FMA38.1-□□	BT□□-SMA38.1-□□
	3100M	40	BT FMC40-	BT□□-SMC40-□□


### Caution when clamping the inserts



<b>O</b> 1 0 10			
Specification			
	Screw	Wrench	
Ø63~Ø100	FTKA0410	TW15S	

# **AMC(M)4000M**













• AR: 9° • RR: -9°~-5°

(mm)

Des	signation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	No. of flute	ар	kg
AMC	4063M	16	63	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	38 (38)	85	4	61.1	1.1
(AMCM)	4080M	20	80	67	31.75 (32)	14	26	12.7 (14.4)	8 (8)	40 (40)	100	4	76.1	2.23
	4100M	30	100	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	40 (40)	100	6	76.1	3.59
	4125M	18	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	36 (29)	68	6	46.1	4.0

### Available inserts

( )Metric size


			Al	PMT-MA	١		APM	T-ML		APN	/IT-MM	APMT-MF	1	APMT	-MN						
			4	0	new	4	4		new	4	-		•		ne	<b>W</b>					
		Cermet		С	oate	d			Uncoated	i			Cermet	t		С	oated	1		Uncoate	t
	Designation	CN2500 CN30	NC5330 NCM325 NCM335	NCM535 NCM545 PC2505	PC2010	PC6510	PC9530 PC9540	PC5300 PC5400	G10 HO1	page		Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC2510	PC6510 PC9530	PC9540 PC5300	G10	page
APMT	1806PDFR-MA								•		APMT	180624PDER-ML							• •		
	180604PDFR-MA								•			180630R-ML							• •		1
	180612PDFR-MA								•			1806PDSR-MM				•	•	• •			
	180616PDFR-MA								•			1806PDSR-MF							• •		
	180620PDFR-MA								•			180612PDSR-MM					•		• •		
	180624PDFR-MA								•	F06		180616PDSR-MM		•					• •		F06
	180630R-MA								•	E06		180620PDSR-MM									E06
	1806PDER-ML							• •				180624PDSR-MM							• •		1
	180604PDER-ML							• •				180630R-MM							• •		1
	180612PDER-ML							• •				180632R-MM							• •		Ī
	180616PDER-ML							• •				1806PDSR-MN3							•		]
	180620PDER-ML							• •				1806PDSR-MN4							•		

<sup>\*\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.

### Available arbors

Desig	nation	Ød	NC a	rbors
AMC	4063M	25.4	BT□□-FMA25.4-□□	BT□□-SMA25.4-□□
(AMCM)	4003W	27	BT□□-FMC27-□□	BT□□-SMC27-□□
	4080M	31.75	BT FMA31.75-	BT□□-SMA31.75-□□
	4000IVI	32	BT□□-FMC32-□□	BT□□-SMC32-□□
	4100M	38.1	BT□□-FMA38.1-□□	BT□□-SMA38.1-□□
	4 1 0 0 W	40	BT -FMC40-	BT□□-SMC40-□□
	4125M	38.1	BT□□-FMA38.1-□□	BT□□-SMA38.1-□□
	4123W	40	BT -FMC40-	BT SMC40-


### Caution when clamping the inserts




Specification	6		
	Screw	Wrench	
Ø63~Ø125	FTKA0410	TW15S	

# **AMS1000S**



















• AR: 7.5°~13° • RR: -17°~-6°

(mm)

									(11111)
ı	Designation	<b>(</b>	ØD	Ød	Q	L	ар	kg	Fig.
AMS	1010HS	2	10	10	20	80	5.6	0.04	2
	1011HS	2	11	10	20	80	5.6	0.04	2
	1012HS-2	2	12	12	25	80	5.6	0.06	2
	1012HS-2L12	2	12	12	25	120	5.6	0.09	1
	1012HS-3	3	12	12	25	80	5.6	0.06	2
	1014HS-2	2	14	16	25	90	5.6	0.11	2
	1014HS-2L16	2	14	16	25	140	5.6	0.18	1
	1014HS-3	3	14	16	25	90	5.6	0.11	2
	1015HS	3	15	16	25	90	5.6	0.11	2
	1015HS-3L16	3	15	16	25	140	5.6	0.18	1
	1016HS-3	3	16	16	25	90	5.6	0.12	2
	1016HS-3L16	3	16	16	25	160	5.6	0.22	1
	1016HS-4	4	16	16	25	90	5.6	0.12	2
	1017HS	4	17	16	25	90	5.6	0.12	2
	1017HS-3L16	3	17	16	25	160	5.6	0.22	1
	1018HS	4	18	16	25	90	5.6	0.12	2
	1018HS-4L16	4	18	16	25	180	5.6	0.25	1
	1020HS-4	4	20	20	30	110	5.6	0.23	2
	1020HS-4L20	4	20	20	30	200	5.6	0.43	1
	1020HS-5	5	20	20	30	110	5.6	0.23	2
	1021HS	5	21	20	30	110	5.6	0.24	2
	1021HS-4L20	4	21	20	30	200	5.6	0.43	1
	1022HS	5	22	20	30	110	5.6	0.27	2
	1025HS	7	25	25	30	120	5.6	0.39	2
	1026HS	7	26	25	30	120	5.6	0.39	2
	1032HS	8	32	32	35	120	5.6	0.65	2
	1033HS	8	33	32	35	120	5.6	0.65	2

### Available inserts




APMT-MM






					_													
		Cermet						C	oate	d						Unco	oated	
	Designation	CN2500 CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0602PDFR-MA																•	
	060208PDFR-MA																	
	060202PDSR-MM		•							•				•	•			
	0602PDSR-MM		•					•	•	•	•	•		•	•			E06
	060208PDSR-MM		•							•				•	•			
	060212R-MM		•											•	•			
	060216R-MM													•	•			




# E Alpha Mill

# **AMS1500S**





















(mm)

	Designation	<b>(</b>	ØD	Ød	Q	L	ар	O kg	Fig.
MS	15010HS	1	10	10	25	80	9	0.04	2
	15010HS-1L16	1	10	16	30	160	9	0.21	1
	15012HS	1	12	16	25	80	9	0.10	2
	15012HS-1L16	1	12	16	30	160	9	0.21	1
	15013HS	1	13	16	25	80	9	0.10	2
	15014HS	1	14	16	25	80	9	0.10	2
	15014HS-1L16	1	14	16	30	160	9	0.21	1
	15016HS	2	16	16	30	90	9	0.11	2
	15016HS-2L16	2	16	16	30	160	9	0.21	1
	15017HS	2	17	16	30	90	9	0.12	2
	15017HS-2L16	2	17	16	30	160	9	0.21	1
	15018HS	2	18	16	30	90	9	0.14	2
	15018HS-2L16	2	18	16	30	160	9	0.21	1
	15019HS	2	19	16	30	90	9	0.16	2
	15020HS	2	20	20	30	90	9	0.18	2
	15020HS-2L20	2	20	20	30	160	9	0.34	1
	15020HS-3	3	20	20	30	90	9	0.18	2
	15021HS	2	21	20	30	90	9	0.20	2
	15021HS-2L20	2	21	20	30	160	9	0.34	1
	15021HS-3	3	21	20	30	90	9	0.20	2
	15022HS	3	22	20	30	110	9	0.23	2
	15022HS-3L20	3	22	20	30	180	9	0.38	1
	15024HS	3	24	20	30	110	9	0.30	2
	15024HS-4	4	24	20	30	110	9	0.30	2
	15025HS-3S20	3	25	20	30	110	9	0.35	2
	15025HS	3	25	25	30	110	9	0.35	2
	15025HS-3L25	3	25	25	30	180	9	0.59	1

### Available inserts





		Cer	met						(	oate	d						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

Specification	Screw	Wrench
Ø10~Ø14 Ø16~Ø25	FTKA02555S FTKA02565S	TW08S

# **AMS1500S**






















(mm)


	Designation	<b>(</b>	ØD	Ød	Q	L	ар	(kg)	Fig.
MS	15025HS-4S20	4	25	20	30	110	9	0.25	2
	15025HS-4S25	4	25	25	30	110	9	0.25	2
	15028HS	4	28	25	30	110	9	0.36	2
	15028HS-4L25	4	28	25	30	180	9	0.61	1
	15028HS-5	5	28	25	30	110	9	0.36	2
	15030HS	4	30	25	30	110	9	0.38	2
	15030HS-4L25	4	30	25	30	180	9	0.62	1
	15030HS-5	5	30	25	30	110	9	0.38	2
	15032HS	4	32	32	30	110	9	0.60	2
	15032HS-4L32	4	32	32	30	180	9	1.00	1
	15032HS-5	5	32	32	30	110	9	0.60	2
	15035HS	5	35	32	30	110	9	0.70	2
	15035HS-6	6	35	32	30	110	9	0.70	2
	15040HS-S32	5	40	32	35	130	9	0.80	2
	15040HS-5L32	5	40	32	35	200	9	1.20	1
	15040HS-6S32	6	40	32	35	130	9	0.80	2
	15040HS-S40	5	40	40	35	130	9	1.13	2
	15040HS-6S40	6	40	40	35	130	9	1.13	2
	15040HS-S42	5	40	42	35	130	9	1.23	2
	15040HS-6S42	6	40	42	35	130	9	1.23	2

### Available inserts




				,															
		Cer	rmet						C	oate	d						Unc	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

J 1 0.1 10			
Specification			
	Screw	Wrench	
Ø25~Ø40	FTKA02565S	TW08S	



# E Alpha Mill

## **AMS2000S**



					90°	• AR: 3°~14° • RR: -25°~-18°
--	--	--	--	--	-----	---------------------------------

(1) Designation ØD Ød Q L kg Fig. ар AMS 2010HS 0.04 2010HS-1L16 0.21 2012HS 0.10 2012HS-1L16 0.21 2014HS 0.12 2014HS-1L16 0.21 2016HS 0.12 2016HS-2L16 0.21 2018HS 0.12 2018HS-2L16 0.21 2020HS 0.21 2020HS-2L20 0.49 2022HS 0.25 2022HS-3L20 0.38 2025HS 0.40 2025HS-3L25 0.59 2032HS 0.70 2032HS-4L32 1.00 2040HS 0.84 2040HS-5L32 2040HS-S40 1.20 1.15 2040HS-S42 2.00 2050HS 1.06 2050HS-S40 1.38 2050HS-S42 1 50 2063HS 1.31 2063HS-S40 1.62 2063HS-S42 1.70 

### Available inserts

		API	MT-M	Α	A	PMT-	ML		APM'	T-MM		AP	МТ-М	F	A	PMT-	MN			
			0	new	•	6	nev		4			•	9		4		ne	<b>»</b>		
			Cer	met						C	oate	d						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10		page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML																•			
	11T308PDER-ML															•	•			
	11T3PDSR-MM				•	•		•		•	•	•	•	•		•	•			
	11T3PDSR-MF				•							•	•							
	11T308PDSR-MM														•					E06
	11T312PDSR-MM				•															
	11T316R-MM				•							•								
	11T318R-MM																			
	11T324R-MM											•				•	•			
	11T3PDSR-MN2															•				
	11T3PDSR-MN3															•				


#### Parts

\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 
\*\* Please use the cutters with even teeth.

Specification	Screw	Wrench	
Ø10~Ø14 Ø16~Ø63	FTKA02555S FTKA02565S	TW08S	

(mm)

## **AMS3000S**





									(r
	Designation	<b>(</b>	ØD	Ød	Q	L	ар	kg	Fig.
MS	3025HS	2	25	25	35	115	16	0.40	2
	3025HS-2M25	2	25	25	35	180	16	0.65	1
	3025HS-2L25	2	25	25	60	220	16	0.75	1
	3032HS	3	32	32	40	125	16	0.69	2
	3032HS-2M32	2	32	32	40	200	16	1.13	1
	3032HS-2L32	2	32	32	65	260	16	1.52	1
	3032HS-3M32	3	32	32	40	200	16	1.12	1
	3032HS-3L32	3	32	32	65	260	16	1.48	1
	3040HS	4	40	32	42	130	16	0.80	2
	3040HS-3M32	3	40	32	42	200	16	1.24	1
	3040HS-3L32	3	40	32	42	260	16	1.61	1
	3040HS-4M32	4	40	32	42	200	16	1.21	1
	3040HS-4L32	4	40	32	42	260	16	1.58	1
	3040HS-S40	4	40	40	42	130	16	1.10	2
	3040HS-S42	4	40	42	42	130	16	1.20	2
	3050HS	5	50	32	45	135	16	1.00	2
	3050HS-S40	5	50	40	45	135	16	1.30	2
	3050HS-S42	5	50	42	45	135	16	1.40	2
	3063HS	6	63	32	45	135	16	1.25	2
	3063HS-S40	6	63	40	45	135	16	1.50	2
	3063HS-S42	6	63	42	45	135	16	1.54	2


#### Available inserts

		API	MT-M	Α	Α	PMT-	ML		APM	T-MM		AP	MT-MI	F	A	APMT-	-MN			
			0	new	•	6	nev	9	-			•			4		nev	<b>V</b>		
			Cer	met						С	oate	t						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
APMT	1604PDFR-MA																		•	
	160404PDFR-MA																			
	1604PDER-ML															•	•			
	160404PDER-ML															•	•			
	1604PDSR-MM				•						•				•	•	•			
	1604PDSR-MF				•							•	•			•	•			
	160410PDSR-MM																•			E06
	160416PDSR-MM				•							•				•	•			
	160424R-MM				•											•				
	160430R-MM											•				•	•			
	160432R-MM				•							•				•				
	1604PDSR-MN3															•				
	1604PDSR-MN4																			

\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.

## **AMS3000S-K**

















AA • AR: 14° • RR: -18°~-10°

(mm)


	Designation	©	ØD	Ød	Q	L	ар	kg
AMS	3025HS-K	2	25	25	35	115	16	0.4
	3032HS-K	3	32	32	40	125	16	0.69
	3040HS-K	4	40	32	42	130	16	0.8
	3040HS-K-S40	4	40	40	42	130	16	1.1
	3040HS-K-S42	4	40	42	42	130	16	1.2
	3050HS-K	5	50	32	45	135	16	1.0
	3050HS-K-S40	5	50	40	45	135	16	1.3
	3050HS-K-S42	5	50	42	45	135	16	1.4
	3063HS-K	6	63	32	45	135	16	1.25
	3063HS-K-S40	6	63	40	45	135	16	1.5
	3063HS-K-S42	6	63	42	45	135	16	1.54

#### Available inserts

	APKT		APK	г-МЕ		APK	Т-ММ		AF	KT-M	A	Α	PKT-N	IA2		APKT-	MA3			
	6	•	9						4	9			0		-	•				
		Cer	met						C	oate	d						U	ncoate	ed	
	Designation	CN2500	CN30	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD2000	G10	된	H05	page
APKT	1604PDSR			•						•	•									
	1604PDSR-MF			•										•						
	1604PDSR-MM			•	•					•	•	•		•						
	1604PDFR-MA															•		•	•	E04
	1604PDFR-MA2																	•		E04
	160416FR-MA2																	•		
	160432FR-MA2																			
	1604PDFR-MA3																•	•	•	

Specification	Screw	Wrench
Ø25 Ø32~Ø63	FTKA0408 FTKA0410	TW15S

## **AMS4000S**






									(mm)
	Designation	©	ØD	Ød	Q	L	ар	kg	Fig.
AMS	4020HS	1	20	20	30	90	17	0.18	2
	4020HS-M	1	20	20	30	160	17	0.17	1
	4021HS	1	21	20	30	90	17	0.19	2
	4021HS-M	1	21	20	30	160	17	0.34	1
	4025HS	2	25	25	40	110	17	0.35	2
	4025HS-2M25	2	25	25	40	180	17	0.58	1
	4025HS-2L25	2	25	25	40	230	17	0.80	1
	4026HS	2	26	25	40	110	17	0.37	2
	4026HS-2M25	2	26	25	40	180	17	0.60	1
	4026HS-2L25	2	26	25	40	230	17	0.82	1
	4032HS	3	32	32	40	125	17	0.65	2
	4032HS-2M32	2	32	32	50	200	17	1.17	1
	4032HS-2L32	2	32	32	50	260	17	1.50	1
	4032HS-3M32	3	32	32	50	200	17	1.10	1
	4032HS-3L32	3	32	32	50	260	17	1.48	1
	4033HS	3	33	32	40	125	17	0.68	2
	4033HS-2M32	2	33	32	50	200	17	1.12	1
	4033HS-2L32	2	33	32	50	260	17	1.55	1
	4033HS-3M32	3	33	32	50	200	17	1.12	1
	4033HS-3L32	3	33	32	50	260	17	1.55	1

#### Available inserts

				APN	IT-MA	١		APM	IT-ML		APN	ит-мм	APMT-MF		APMT	-MN							
			,	00		new	4	9		new	4		•	4	\$	n	·W						
		Cermet			С	oate	t			Uncoated				Cermet			C	oate	d			Uncoated	j
	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545 PC2505	PC2010	PC6510	PC9530 PC9540	PC5300 PC5400	G10 H01	page		Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC2510	PC6510	PC9530 PC9540	PC5300 PC5400	G10 H01	page
APMT	1806PDFR-MA									•		APMT	180624PDER-ML								• •		
	180604PDFR-MA									•			180630R-ML								• •		1
	180612PDFR-MA									•			1806PDSR-MM						•	•	• •		1
	180616PDFR-MA									•			1806PDSR-MF						•		• •		
	180620PDFR-MA									•			180612PDSR-MM								• •		
	180624PDFR-MA									•	F00		180616PDSR-MM								• •		F00
	180630R-MA									•	E06		180620PDSR-MM										E06
	1806PDER-ML								• •				180624PDSR-MM								• •		1
	180604PDER-ML								• •				180630R-MM								• •		
	180612PDER-ML								• •				180632R-MM								• •		
	180616PDER-ML								•				1806PDSR-MN3								•		
	180620PDER-ML								• •				1806PDSR-MN4								•		1


\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.

Specification	6		
	Screw	Wrench	
Ø20~Ø21 Ø25~Ø33	FTKA0408 FTKA0410	TW15S	



# E Alpha Mill

## **AMS4000S**





(mm)

	Designation	0	ØD	Ød	Q	L	ар	∑ kg \	Fig.
AMS	4040HS-3M32	3	40	32	50	200	17	1.20	1
	4040HS-3L32	3	40	32	50	260	17	1.60	1
	4040HS-4M32	4	40	32	50	200	17	1.20	1
	4040HS-4L32	4	40	32	50	260	17	1.60	1
	4040HS-S32	4	40	32	40	130	17	0.76	2
	4040HS-S40	4	40	40	40	130	17	1.10	2
	4040HS-S42	4	40	42	40	130	17	1.20	2
	4050HS-S32	5	50	32	40	135	17	0.95	2
	4050HS-S40	5	50	40	40	135	17	1.30	2
	4050HS-S42	5	50	42	40	135	17	1.40	2
	4063HS-S32	6	63	32	40	135	17	1.25	2
	4063HS-S40	6	63	40	40	135	17	1.60	2
	4063HS-S42	6	63	42	40	135	17	1.70	2

#### Available inserts

				APMT-	-MA		AP	MT-ML		APN	IT-MM	APMT-MF		APMT	MN						
			•	6	N. C	ew	4		new	4	-	•	4	Ş	ne	<b>»</b>					
		Cermet			Coa	ated			Uncoated				Cermet			С	oate	ŀ		Uncoate	d
ı	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	PC2505	PC3700	PC6510 PC9530	PC9540 PC5300	G10 H01	page		Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC2510	PC6510	PC9540 PC5300	G10 H01	page
APMT	1806PDFR-MA								•		APMT	180624PDER-ML							•	•	
-	180604PDFR-MA								•			180630R-ML							•	•	
	180612PDFR-MA								•			1806PDSR-MM				•	•	•	• •	•	
	180616PDFR-MA								•			1806PDSR-MF							•	•	
	180620PDFR-MA								•			180612PDSR-MM					•	)	•		
	180624PDFR-MA								•	E06		180616PDSR-MM							•		E06
	180630R-MA								•			180620PDSR-MM									
	1806PDER-ML							• •				180624PDSR-MM							•	•	
	180604PDER-ML							• •				180630R-MM							•	•	
	180612PDER-ML							• •				180632R-MM							•	•	
	180616PDER-ML							•				1806PDSR-MN3							•		
-	180620PDER-ML							• •				1806PDSR-MN4							•		

<sup>\*\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 


\*\* Please use the cutters with even teeth.

Specification	Screw	Wrench	
Ø40~Ø63	FTKA0410	TW15S	



## AMS1000SE/2000SE











• AR: -4.5°~-1° • RR: -3°~0°

(mm)

С	Designation	0	ØD	Ød	Q	L	ар	
AMS	1025HSE	3	25	25	30	115	2.5	0.41
AMS	2025HSE	2	25	25	30	115	4	0.4
	2032HSE	3	32	32	40	125	4	0.72
	2040HSE	3	40	32	40	130	4	0.86
	2040HSE-S40	3	40	40	40	130	4	1.2
	2040HSE-S42	3	40	42	40	130	4	1.3
	2050HSE	4	50	32	40	135	4	0.98
	2050HSE-S40	4	50	40	40	135	4	1.3
	2050HSE-S42	4	50	42	40	135	4	1.4
	2063HSE	5	63	32	40	135	4	1.24
	2063HSE-S40	5	63	40	40	135	4	1.57
	2063HSE-S42	5	63	42	40	135	4	1.62

#### Available inserts

APMT-MF




			Cer	met						C	oate	d						Unc	oated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
	APMT	060202PDSR-MM			•							•				•	•			
		0602PDSR-MM			•					•	•	•	•	•		•	•			
1000 type		060208PDSR-MM			•							•				•	•			
typo		060212R-MM			•											•	•			
		060216R-MM														•	•			
	APMT	11T3PDSR-MM			•	•		•		•	•	•	•	•		•	•			E06
		11T3PDSR-MF			•							•	•			•	•			
		11T308PDSR-MM			•							•		•	•	•	•			
2000 type		11T312PDSR-MM			•							•		•		•	•			
type		11T316R-MM			•							•				•	•			
		11T318R-MM																		
		11T324R-MM			•							•				•	•			

## E Alpha Mill

## **AMS3000SE**









<sup>AA</sup> 75°

• AR: -4.5°~-1° • RR: -3°~0°

(mm)

	Designation	©	ØD	Ød	Q	L	ар	kg
AMS	3050HSE	3	50	32	45	135	6	1.0
	3050HSE-S40	3	50	40	45	135	6	1.3
	3050HSE-S42	3	50	42	45	135	6	1.4
	3063HSE	4	63	32	45	135	6	1.3
	3063HSE-S40	4	63	40	45	135	6	1.6
	3063HSE-S42	4	63	42	45	135	6	1.7

#### Available inserts

APMT-MF APMT-MM


Cermet Coated Uncoated

		Cer	rmet						(	coate	d						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	1604PDSR-MM			•	•		•		•	•	•	•	•	•	•	•			
	1604PDSR-MF			•							•	•			•	•			
	160410PDSR-MM										•				•	•			
	160416PDSR-MM			•							•				•	•			E06
	160424R-MM			•							•				•	•			
	160430R-MM										•				•	•			
	160432R-MM			•							•				•	•			

Specification	<b>6</b>		
	Screw	Wrench	
Ø50~Ø63	FTKA0410	TW15S	

## AMS1000M/1500M














(mm)

	Designation	<b>©</b>	ØD	Ød	Q	L	No. of flute	ар	kg
AMS	1016M	6	16	16	30	80	2	15.5	0.3
	1020M	12	20	20	32	85	3	20.5	0.3
	1025M	20	25	25	39	95	4	25.5	0.3
AMS	15020M	3	20	20	42	105	1	26.5	0.3
	15025M	8	25	25	50	110	2	35	0.3
	15032M	10	32	32	60	120	2	44	0.3

#### Available inserts




					_															
			Cer	met						C	oate	d						Unco	oated	
Туре	Г	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
	APMT	0602PDFR-MA																	•	
		060208PDFR-MA																		
4000		060202PDSR-MM			•							•				•	•			
1000 type		0602PDSR-MM			•					•	•	•	•	•			•			
type		060208PDSR-MM			•							•					•			
		060212R-MM			•											•	•			
		060216R-MM														•	•			
	APMT	0903PDFR-MA																	•	E06
		090308PDFR-MA																		
		0903PDER-ML														•	•			
4500		090308PDER-ML															•			
1500 type		0903PDSR-MM			•					•	•	•	•			•	•			
type		090308PDSR-MM			•							•					•			
		090312R-MM										•				•	•			
		090316R-MM			•							•				•	•			
		090320R-MM										•				•	•			

#### Parts

Specification	<b>6</b>		
	Screw	Wrench	Wrench
Ø16~Ø25 (1000 type)	FTKA01842	-	TW06S-A
Ø20~Ø32 (1500 type)	FTKA02565S	TW08S	-


→ Available inserts E06

## Caution when clamping the inserts



## **AMS2000M**















• AR: 7°~9° • RR: -13°~-10°

(mm)

D	esignation	©	ØD	Ød	Q	L	No. of flute	ар	O kg \
AMS	2020M	3	20	20	45	120	1	29.4	0.32
	2025M	8	25	25	55	130	2	38.9	0.40
	2032M	10	32	32	65	140	2	48.5	0.65
	2040M	14	40	40	75	150	2	58	0.75

#### Available inserts

		APM	IT-M	4	A	PMT-	ML		APM	Т-ММ		AP	MT-M	F	A	PMT-	MN			
		0		new	•	6	nev		4			•	0		4		nev	<b>D</b>		
			Cer	met						C	oate	d						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML																•			
	11T3PDSR-MM				•	•		•					•	•			•			
	11T3PDSR-MF				•							•	•				•			
	11T308PDSR-MM				•							•		•	•	•	•			E06
	11T312PDSR-MM				•							•		•			•			
	11T316R-MM				•							•				•	•			
	11T318R-MM																			
	11T324R-MM				•							•				•	•			
	11T3PDSR-MN2															•				
	11T3PDSR-MN3																			


\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 

\*\* Please use the cutters with even teeth.

#### Parts


Specification	Screw	Wrench
Ø20~Ø40	FTKA02565S	TW08S

#### Caution when clamping the inserts



## **AMS4000M**













A DIMT MA



A DMT MI

• AR: 7°~9° • RR: -13°~-10°

(mm)

	Designation	©	ØD	Ød	Q	L	No. of flute	ар	(kg)
AMS	4032M	4	32	32	60	130	2	31.6	0.65
	4040M	6	40	40	70	140	2	46	1.11
	4050M-S40	6	50	40	55	125	2	46	1.22
	4050M	8	50	40	70	140	2	61	1.37

A DMT MM

ADMT ME

A DMT MN

#### Available inserts


		AP	MT-M	A		APMT-	ML		APM	T-MM		AP	MT-M	F		APMT-	MN			
				new	•	6	nev		-			•	9		4		ne	0		
			Cer	met						(	coate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	1806PDFR-MA																		•	
	180604PDFR-MA																		•	
	180612PDFR-MA																		•	
	180616PDFR-MA																		•	
	180620PDFR-MA																		•	
	180624PDFR-MA																		•	
	180630R-MA																		•	
	1806PDER-ML																			
	180604PDER-ML																			
	180612PDER-ML															•	•			
	180616PDER-ML															•				
	180620PDER-ML															•	•			E06
	180624PDER-ML																			
	180630R-ML															•	•			
	1806PDSR-MM				•					•				•						
	1806PDSR-MF				•								•			•	•			
	180612PDSR-MM				•															
	180616PDSR-MM				•											•	•			
	180620PDSR-MM																			
	180624PDSR-MM				•											•	•			
	180630R-MM															•	•			
	180632R-MM				•											•	•			
	1806PDSR-MN3															•				
	1806PDSR-MN4																			

#### Parts

Specification	Screw	Wrench
Ø32~Ø50	FTKA0410	TW15S


→ Available inserts E06

#### Caution when clamping the inserts



## AMS1000MH/1500MH

















• AR: 9°~12° • RR: -12°~-10°

(mm)

	Designation	<b>(b)</b>	ØD	Ød	Q	L	ар	kg	APMT 0602	APMT 0903	APM(X)T 11T3 -	APMT 1604	APKT 1604 -
AMS	1014MH	3	14	12	30	120	11	0.16	3	-	-	-	-
	1016MH	3	16	14	30	140	11	0.20	3	-	-	-	-
	1018MH	3	18	16	30	140	11	0.21	3	-	-	-	-
AMS	15020MH	3	20	20	35	140	17	0.31	1	2	-	-	-

#### Available inserts

				AF	MT-M	IA		APMT	-ML		APM	IT-MM								
				4	0	nev	1	6		ew	4		)							
			Cer	met						C	oate	d						Unco	oated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
	APMT	0602PDFR-MA																	•	
		060208PDFR-MA																		
1000 type		060202PDSR-MM			•							•				•	•			
type		0602PDSR-MM			•					•	•	•	•	•		•	•			
		060208PDSR-MM			•							•				•	•			
	APMT	0903PDFR-MA																	•	E06
		090308PDFR-MA																		
1500		090308PDFR-MA 0903PDER-ML														•	•			
type		0903PDER-ML 090308PDER-ML 0903PDSR-MM 090308PDSR-MM														•	•			
					•					•	•	•	•			•	•			
					•							•				•	•			

#### Parts

Specification	Screw	Wrench	Wrench
Ø14~Ø18 (1000 type)	FTKA01842	-	TW06S-A
Ø20 (1500 type)	FTKA02565S	TW08S	-


#### Recommended cutting condition


	Drilling	Shouldering	Slotting
vc(m/min)	80~200	80~200	80~200
fz(mm/t)	0.03~0.06	0.05~0.25	0.05~0.20

- Please keep the drill depth under 0.25D when you're drilling
- Please keep the step depth from 0.2 to 0.3mm

## AMS2000MH/3000MH(-K)





















(mm)

ı	Designation	0	ØD	Ød	Q	L	ар	kg	APMT 0602	APMT 0903	APM(X)T 11T3 -	APMT 1604	APKT 1604 -	Fig.
AMS	2025MH	3	25	25	40	130	20	0.45	-	-	3	-	-	1
	2032MH	3	32	32	50	140	30	0.75	-	-	1	2	-	1
AMS	3040MH	4	40	32	60	150	40	0.90	-	-	-	4	-	2
	3040MH-K	4	40	32	60	150	40	0.90	-	-	-	-	4	2

#### Available inserts

		APKT-MF	APKT	-MM		APN	IT-MA		AF	PMT-M	IF		APMT	-ML		APM	IT-MM		
			-			00		new	•	6		1	6	0	e <b>W</b>	4			
			Cei	rmet						С	oate	d						Uncoated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	H01	page
	APMT	11T3PDFR-MA																•	
		11T308PDFR-MA																	
		11T3PDER-ML														•	•		
		11T308PDER-ML														•	•		
		11T3PDSR-MM			•	•		•		•	•	•	•	•		•	•		
2000 type		11T3PDSR-MF			•							•	•			•	•		
type		11T308PDSR-MM			•							•		•	•	•	•		
		11T312PDSR-MM			•							•		•		•	•		E06
		11T316R-MM			•							•				•	•		
		11T318R-MM			•														
		11T324R-MM			•							•				•	•		
3000	APMT	1604PDSR-MM			•	•				•	•	•	•	•		•	•		
type		1604PDSR-MF			•							•	•			•	•		
3000-K	APKT	1604PDSR-MM				•	•					•	•	•		•			
type		1604PDSR-MF				•										•			

#### Parts

Specification		A	
	Screw	Wrench	Wrench
Ø25 (2000 type)	FTKA02565S	TW08S	-
Ø32 (2000 type)	FTKA02565S+FTKA0410	TW08S+TW15S	
Ø40 (3000 type)	FTKA0410	TW15S	-

#### Available inserts E06


## Recommended cutting condition

	Drilling	Shouldering	Slotting
vc(m/min)	80~200	80~200	80~200
fz(mm/t)	0.03~0.06	0.05~0.25	0.05~0.20

- Please keep the drill depth under 0.25D when you're drilling
- Please keep the step depth from 0.2 to 0.3mm

## **AMM1000**

















• AR: 7.5°~12.5° • RR: -28°~-6°

(mm)

1	Designation	<b>©</b>	ØD	Ød	Ød1	Q	L	M	ар	kg
AMM	1012HR-M06	3	12	11	6.5	25	40	M06	5.6	0.02
	1016HR-M08	4	16	14.5	8.5	25	42	M08	5.6	0.03
	1020HR-M10	5	20	18	10.5	30	51	M10	5.6	0.07
	1025HR-M12	7	25	23	12.5	35	59	M12	5.6	0.12
	1032HR-M16	8	32	29	17	40	67	M16	5.6	0.23

#### Available inserts

APMT-MA APMT-MM

7	5	new	1	9	
			C	oate	d
10	10	10		_	

		Cei	met		Coated									Unco	oated				
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0602PDFR-MA																	•	
	060208PDFR-MA																		
	060202PDSR-MM			•							•				•	•			
	0602PDSR-MM			•					•	•	•	•	•		•	•			E06
	060208PDSR-MM			•							•				•	•			
	060212R-MM			•											•	•			
	060216R-MM														•	•			

#### Available adaptor

	Designation	Available adaptor
AMM	1012HR-M06	MAT-M06
	1016HR-M08	MAT-M08
	1020HR-M10	MAT-M10
	1025HR-M12	MAT-M12
	1032HR-M16	MAT-M16


Designation : AMM1032HR-M16 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

Specification	67		
	Screw	Wrench	
Ø12~Ø32	FTKA01842	TW06S-A	

## **AMM1500**

















• AR: 7.5°~12.5° • RR: -28°~-6°

(mm)

	Designation	<b>©</b>	ØD	Ød	Ød1	Q	L	М	ар	kg
AMM	15010HR-M06	1	10	9.5	6.5	25	40	M06	9	0.01
	15012HR-M06	1	12	11	6.5	25	40	M06	9	0.02
	15016HR-M08	2	16	14.5	8.5	25	42	M08	9	0.03
	15020HR-M10	2	20	18	10.5	30	51	M10	9	0.06
	15025HR-M12	3	25	23	12.5	35	59	M12	9	0.12
	15032HR-M16	4	32	29	17	40	67	M16	9	0.22

#### Available inserts



		Cer	met							oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H04	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

## Available adaptor


	Designation	Available adaptor
AMM	15010HR-M06	MAT-M06
	15012HR-M06	IVIAT-IVIUO
	15016HR-M08	MAT-M08
	15020HR-M10	MAT-M10
	15025HR-M12	MAT-M12
	15032HR-M16	MAT-M16


Designation : AMM15032HR-M16 Modular head threading measure size (M16)

п

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)


O I di to		
Specification	6	R
	Screw	Wrench
Ø10~Ø14 Ø16~Ø100	FTKA02555S FTKA02565S	TW08S





## **AMM2000**

















• AR: 7.5°~12.5° • RR: -28°~-6°

(mm)

	Designation	<b>©</b>	ØD	Ød	Ød1	Q	L	М	ар	kg
AMM	2016HR-M08	2	16	14.5	8.5	25	42	M08	11	0.04
	2020HR-M10	2	20	18	10.5	30	51	M10	11	0.07
	2025HR-M12	3	25	23	12.5	35	59	M12	11	0.04
	2032HR-M16	4	32	29	17	40	67	M16	11	0.23
	2040HR-M16	5	40	29	17	40	67	M16	11	0.25

#### Available inserts

		AP	MT-M	Α	ı	APMT-	ML		APM	Т-ММ		AP	МТ-М	F	4	РМТ-	MN			
				new	•	6	nev		-			•			4		nev	<b>9</b>		
			Cer	met						С	oate	d						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML																•			
	11T3PDSR-MM				•	•		•		•	•	•	•	•		•	•			
	11T3PDSR-MF				•								•				•			
	11T308PDSR-MM				•							•		•	•		•			E06
	11T312PDSR-MM				•							•		•		•	•			
	11T316R-MM				•							•				•	•			
	11T318R-MM																			
	11T324R-MM				•							•				•	•			
	11T3PDSR-MN2															•				
	11T3PDSR-MN3																			

\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.

#### Available adaptor

	Designation	Available adaptor
AMM	2016HR-M08	MAT-M08
	2020HR-M10	MAT-M10
	2025HR-M12	MAT-M12
	2032HR-M16	NAT MAC
	2040HR-M16	MAT-M16

Designation : AMM2032HR-M16 Modular head threading measure size (M16)

П

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

Specification	Screw	Wrench	
	Sciew	VVIEIICII	
Ø16~Ø40	FTKA02565S	TW08S	


#### Shoulder milling tool for high helix

## Alpha Mill-X 🚭


- High helix cutting edge realizes high speed and high feed machining (15% higher speed than conventional tool's machining) and increases 20% higher productivity.
- Highly precise cutting edge ensures high quality surface finish in milling.

#### Code system


#### Cutter




#### Shank




#### Application area






# E Technical Information for Alpha Mill-X


#### Features of insert



#### Cutter features



#### Cutting load



#### Recommended cutting conditions

#### · In face machining and shouldering

14	la ulmia a a	Grade	Cutting speed		Feed, fz (mm/t)	
V	/orkpiece	Grade	vc (m/min)	ADKT17	ADKT12	ADKT10
	PC5300 150-240					
Р	Steel	PC5400	130-210	0.3-0.05	0.25-0.05	0.2-0.05
P	Sieei	PC3700	160-270	0.3-0.05	0.25-0.05	0.2-0.05
		NCM535	250-350			
		PC5300	90-150			
M	Stainless steel	PC5400	70-120	0.25-0.05	0.2-0.05	0.15-0.05
	Sieei	PC9540	50-120			
		PC6510	150-200			
K	Cast iron	PC5300	120-200	0.35-0.08	0.3-0.08	0.25-0.08
		NCM535	200-300			
s	LIDCA	PC5300	40-70	0.2-0.05	0.15.0.05	0.1.0.05
3	HRSA	PC5400	30-50	0.2-0.05	0.15-0.05	0.1-0.05

<sup>\*</sup> The above data refer to general cutting conditions and can be adjustable up to 350 m/min and 0.4 mm/t depending on user environment

#### · In grooving, ramping and helical machining

14	/outraines	Cuada	Cutting speed		Feed, fz (mm/t)			
V	/orkpiece	Grade	vc (m/min)	ADKT17	ADKT12	ADKT10		
		PC5300	150-240					
Р	Otes	PC5400	130-210	0.45.0.05	0.45.0.05	0.45.0.05		
Ρ.	Steel	PC3700	160-270	0.15-0.05	0.15-0.05	0.15-0.05		
		NCM535	250-350					
		PC5300	90-150					
M	Stainless steel	PC5400	70-120	0.15-0.05	0.15-0.05	0.15-0.05		
	steer	PC9540	50-120					
		PC6510	150-250					
K	Cast iron	PC5300	120-200	0.2-0.08	0.2-0.08	0.2-0.08		
		NCM535	200-300					
c	LIDCA	PC5300	40-70	0.45.0.05	0.45.0.05	0.1.0.05		
S	HRSA	PC5400	30-50	0.15-0.05	0.15-0.05	0.1-0.05		

<sup>\*</sup> In deep grooving, set the ap under 5 mm and use coolant and air.

#### Recommended grades and chip breakers

○ NCM535

○ NCM535

Р M N S High carbon steel/ Cutting Low carbon steel/ C/B Stainless steel Cast iron Non-ferrous metal **HRSA** edge Mild steel Alloy steel C/B C/B C/B C/B C/B C/B Grade Grade Grade Grade Grade Grade PC3700 PC3700 ● PC6510 PC5300 PC5300 OPC5300 ○ PC5300 ○ PC5300 OPC5400 ML OPC5400 ○PC5400 ○PC5400 OPC5400 OPC9540 ○ NCM535 ○ NCM535 ○ NCM535 PC3700 PC3700 PC6510 PC5300 PC5300 ○ PC5300 ○PC5300 ○PC5300 OPC5400 MM ○PC5400 ○PC5400 ○PC5400 OPC5400

OPC9540


○ NCM535


( : 1st Recommendation)

# E Technical Information for Alpha Mill-X

#### Cutting condition for ramping and helical operation

Ramping **Helical cutting** 





(mm)

			Ramp	ing		Blind hole he	elical cutting	l	Through hole helical cutting				
Designation	Tool dia. ØD (min)	ар	Max. rake angle α°	Lmin	Min. desirable hole dia. ØDHmin	Max. pitch dmax	Max. desirable hole dia. ØDHmax	Max. pitch dmax	Min. desirable hole dia. ØDHmin	Max. pitch dmax			
	20		13	71	30	7.0	38	8.9	21	4.8			
	25		8.0	117	40	5.7	48	6.8	31	4.3			
	32		3.7	255	54	3.5	62	4.0	45	2.9			
	33		3.6	262	56	3.5	64	4.1	47	2.9			
ADKT17	40	16.5	2.6	363	70	3.2	78	3.6	61	2.8			
ADKI17	50	10.5	1.9	497	90	3.0	98	3.3	81	2.7			
	63		1.3	727	116	2.6	124	2.8	107	2.4			
	80		1.1	859	150	2.9	158	3.0	141	2.7			
	100		0.7	1350	190	2.3	198	2.4	181	2.2			
	125		0.5	1891	240	2.1	248	2.2	231	2.0			
	18		7.0	98	29	3.6	34	4.2	23	2.8			
	20		5.5	125	33	3.2	38	3.7	27	2.6			
	25		3.5	196	43	2.7	48	3.0	37	2.3			
	32		2.5	275	57	2.5	62	2.7	51	2.2			
ADKT12	33	11.5	11.5	11.5	2.4	286	59	2.5	64	2.7	53	2.2	
	40		1.5	458	73	1.9	78	2.1	67	1.7			
	50		1.2	573	93	2.0	98	2.1	87	1.8			
	63		1.0	687	119	2.1	124	2.2	113	2.0			
	80		0.7	982	153	1.9	158	1.9	147	1.8			
	16		4.5	121	28	2.2	31	2.5	24	1.9			
	18		3.5	155	32	2.0	35	2.2	28	1.7			
	20		3.0	181	36	1.9	39	2.1	32	1.7			
	25		2.2	247	46	1.8	49	1.9	42	1.6			
A DICTA O	32	0.5	1.5	363	60	1.6	63	1.7	56	1.5			
ADKT10	33	9.5	1.4	389	62	1.5	65	1.6	58	1.4			
	40		1.2	454	76	1.6	79	1.7	72	1.5			
	50	1	0.8	680	96	1.3	99	1.4	92	1.3			
	63	1	0.6	907	122	1.3	125	1.3	118	1.2			
	80		0.5	1089	156	1.4	159	1.4	152	1.3			

 $<sup>\</sup>ensuremath{\mathbb{X}}$  In ramping and helical machining, use coolant and air.

\* Lmin : Cutting length in machining with Min. rake angle

 $\alpha^{\circ}$  : Rake angle for ramping


: Depth of cut in axial direction

$$Lmin = \frac{ap}{\tan \alpha^{\circ}} (mm)$$



## AMXCM-AD10/12 rew



















• RR: -10°~-3°

(kg)
0.18
0.18
0.23

														(mm)
	Designation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg
AMXCM	040R-16-5-AD10	5	40	35	16	9	14	-	8.4	5.6	19	40	9.5	0.18
	040R-16-6-AD10	6	40	35	16	9	14	-	8.4	5.6	19	40	9.5	0.18
	050R-22-6-AD10	6	50	42	22	11	18	-	10.4	6.3	20	40	9.5	0.23
	050R-22-7-AD10	7	50	42	22	11	18	-	10.4	6.3	20	40	9.5	0.20
	063R-22-7-AD10	7	63	49	22	11	18	-	10.4	6.3	20	40	9.5	0.44
	063R-22-8-AD10	8	63	49	22	11	18	-	10.4	6.3	20	40	9.5	0.49
	080R-27-8-AD10	8	80	57	27	14	25	38	12.4	7	23	50	9.5	0.88
	080R-27-9-AD10	9	80	57	27	14	25	38	12.4	7	23	50	9.5	0.90
<b>AMXCM</b>	040R-16-4-AD12	4	40	35	16	9	14	-	8.4	5.6	19	40	11.5	0.18
	040R-16-5-AD12	5	40	35	16	9	14	-	8.4	5.6	19	40	11.5	0.16
	050R-22-5-AD12	5	50	42	22	11	18	-	10.4	6.3	20	40	11.5	0.23
	050R-22-7-AD12	7	50	42	22	11	18	-	10.4	6.3	20	40	11.5	0.20
	063R-22-6-AD12	6	63	49	22	11	18	-	10.4	6.3	20	40	11.5	0.44
	063R-22-7-AD12	7	63	49	22	11	18	-	10.4	6.3	20	40	11.5	0.49
	080R-27-7-AD12	7	80	57	27	14	25	38	12.4	7	23	50	11.5	0.88
	080R-27-8-AD12	8	80	57	27	14	25	38	12.4	7	23	50	11.5	0.90

#### Available inserts







			Cer	met						C	oate	d						Unco	ated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	193	page
	ADKT	10T304PEER-ML						•				•	•		•	•	•			
10		10T304PESR-MM						•				•	•		•	•	•			
type		10T308PESR-MM														•	•			
		10T312PESR-MM															•			F0.4
	ADKT	120408PESR-ML						•				•	•		•	•	•			E04
12		120408PESR-MM						•				•	•		•	•	•			
type		120412PESR-MM										•	•			•	•			
		120416PESR-MM										•	•			•	•			

#### Available arbors


	Designation	Ød	Available arbors
AMXCM	040R-16-□-AD□□	16	BT□□-FMC16-□□
	050B-22-□-AD□□	22	BT□□-FMC22-□□

	Designation	Ød	Available arbors
AMXCM	063R-22-□-AD□□	22	BT□□-FMC22-□□
	080R-27-□-AD□□	27	BT□□-FMC27-□□

Specification		NONE OF THE PERSON OF THE PERS
	Screw	Wrench
Ø40~Ø80 (10 type)	FTKA02555S	TW08S
Ø40~Ø80 (12 type)	FTNA0306	TW09S

## AMXCM-AD17 (1997)



















(mm)

														(11111)
	Designation	(i)	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg
AMXCM	040R-16-3-AD17	3	40	35	16	9	14	-	8.4	5.6	19	40	16.5	0.18
	040R-16-4-AD17	4	40	35	16	9	14	-	8.4	5.6	19	40	16.5	0.18
	050R-22-4-AD17	4	50	42	22	11	18	-	10.4	6.3	20	40	16.5	0.23
	050R-22-5-AD17	5	50	42	22	11	18	-	10.4	6.3	20	40	16.5	0.20
	063R-22-5-AD17	5	63	49	22	11	18	-	10.4	6.3	20	40	16.5	0.44
	063R-22-6-AD17	6	63	49	22	11	18	-	10.4	6.3	20	40	16.5	0.49
	080R-27-6-AD17	6	80	57	27	14	25	38	12.4	7	23	50	16.5	0.88
	080R-27-7-AD17	7	80	57	27	14	25	38	12.4	7	23	50	16.5	0.90
	100R-32-8-AD17	8	100	70	32	18	28	45	14.4	8	28	63	16.5	1.76
	100R-32-10-AD17	10	100	70	32	18	28	45	14.4	8	28	63	16.5	1.68
	125R-40-8-AD17	8	125	90	40	22	32	54	16.4	9	30	63	16.5	2.89
	125R-40-10-AD17	10	125	90	40	22	32	54	16.4	9	30	63	16.5	4.83

#### Available inserts

ADKT-ML

ADKT-MM





					Coated Uncoated														
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
ADKT	170608PESR-ML						•				•	•		•	•	•			
	170604PESR-MM										•				•				
	170608PESR-MM						•				•	•		•	•	•			E04
	170616PESR-MM														•	•			
	170620PESR-MM														•	•			


#### Available arbors


	Designation	Ød	Available arbors
AMXCM	040R-16-□-AD□□	16	BT□□-FMC16-□□
	050R-22-□-AD□□	22	BT□□-FMC22-□□
	063R-22 AD	22	BILL-FINICZZ-LL

	Designation	Ød	Available arbors
AMXCM	080R-27-□-AD□□	27	BT□□-FMC27-□□
	100R-32-□-AD□□	32	BT□□-FMC32-□□
	125R-40-□-AD□□	40	BT□□-FMC40-□□

## AMXS-AD10/12 (1997)





















				J					(mm)
	Designation	<b>(</b>	ØD	Ød	Q	L	ар	kg	Fig.
AMXS	016R-2W16-90-AD10	2	16	16	25	90	9.5	0.110	2
	016R-2C16-180-AD10	2	16	16	25	180	9.5	0.190	1
	018R-2W16-100-AD10	2	18	16	35	100	9.5	0.120	2
	018R-2C16-200-AD10	2	18	16	35	200	9.5	0.210	1
	020R-3W20-100-AD10	3	20	20	35	100	9.5	0.250	2
	020R-3C20-200-AD10	3	20	20	35	200	9.5	0.490	1
	025R-4W25-115-AD10	4	25	25	40	115	9.5	0.400	2
	025R-4C25-200-AD10	4	25	25	40	200	9.5	0.590	1
	032R-4W32-125-AD10	4	32	32	45	125	9.5	0.700	2
	032R-4C32-200-AD10	4	32	32	45	200	9.5	1.000	1
	040R-5W32-130-AD10	5	40	32	50	130	9.5	1.050	2
	040R-5C32-200-AD10	5	40	32	50	200	9.5	1.200	1
AMXS	018R-2W16-100-AD12	2	18	16	35	100	11.5	0.120	2
	018R-2C16-200-AD12	2	18	16	35	200	11.5	0.210	1
	020R-2W20-100-AD12	2	20	20	35	100	11.5	0.250	2
	020R-2C20-200-AD12	2	20	20	35	200	11.5	0.490	1
	025R-3W25-115-AD12	3	25	25	40	115	11.5	0.400	2
	025R-3C25-200-AD12	3	25	25	40	200	11.5	0.590	1
	032R-4W32-125-AD12	4	32	32	45	125	11.5	0.700	2
	032R-4C32-200-AD12	4	32	32	45	200	11.5	1.000	1
	040R-4W32-130-AD12	4	40	32	50	130	11.5	1.050	2
	040R-4C32-200-AD12	4	40	32	50	200	11.5	1.200	1

#### Available inserts



ADKT-MM






	Cer	met						C	coate	d						Unco	oated			
Туре	ype Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H0.1	page
	ADKT	10T304PEER-ML						•				•	•		•	•	•			
10		10T304PESR-MM						•				•	•		•	•	•			
type		10T308PESR-MM														•	•			
		10T312PESR-MM															•			F04
	ADKT	120408PESR-ML						•				•	•		•	•	•			E04
12		120408PESR-MM						•				•	•		•	•	•			
type		120412PESR-MM										•	•			•	•			
		120416PESR-MM										•	•			•	•			


Specification		Secono Se	
	Screw	Wrench	
Ø16~Ø40 (10 type)	FTKA02555S	TW08S	
Ø18~Ø40 (12 type)	FTNA0306	TW09S	

# E Alpha Mill-X

## AMXS-AD17



















• AR: 8° • RR: -10°~-3°

(mm)

	Designation	0	ØD	Ød	Q	L	ар	(kg)	Fig.
AMXS	020R-1W20-100-AD17	1	20	20	35	100	16.5	0.170	2
	020R-1C20-200-AD17	1	20	20	35	200	16.5	0.360	1
	025R-2W25-115-AD17	2	25	25	35	115	16.5	0.610	2
	025R-2C25-200-AD17	2	25	25	35	200	16.5	0.450	1
	032R-3W32-125-AD17	3	32	32	45	125	16.5	0.620	2
	032R-3C32-200-AD17	3	32	32	45	200	16.5	1.050	1
	033R-3W32-125-AD17	3	33	32	45	125	16.5	0.620	2
	033R-3C32-200-AD17	3	33	32	45	200	16.5	1.050	1
	040R-3W32-130-AD17	3	40	32	50	130	16.5	0.750	2
	040R-3C32-200-AD17	3	40	32	50	200	16.5	1.170	1
	040R-4W32-130-AD17	4	40	32	50	130	16.5	0.740	2
	040R-4C32-200-AD17	4	40	32	50	200	16.5	1.200	1

#### Available inserts





						-													
					Coated								Unco	Uncoated					
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	F94	page
ADKT	170608PESR-ML						•				•	•		•	•	•			
	170604PESR-MM										•				•				
	170608PESR-MM						•				•	•		•	•	•			E04
	170616PESR-MM														•	•			
	170620PESR-MM														•	•			

Specification			
	Screw	Wrench	
Ø20~Ø40	FTKA0408	TW15S	

#### Rigid body employs high tensile aluminum


## **Future Mill**


- Light-weight aluminum body (50% of steel body) can be used for high speed cutting, tapping center, and on low power machines
- Easy handling
- It can be used for aluminum alloys, medium cutting of steel, and cast iron
- Rigid body employs high tensile aluminum
- Locators for excellent durability
- A variety of chip breaker are available
- The high rake angle provides low cutting loads and good surface roughness


#### Features of cutter

- · Strong clamping between aluminum body and locator with double screw provides high efficiency
- · Acute angle of locator seat provides strong clamping
- · Wide chip pocket area provides good chip evacuation
- · High tensile strength aluminum body

#### Assembly structure of cutter








## Through coolant system

- · Exclusively designed coolant bolt and cover provide excellent coolant action and chip evacuation for improved tool life
- · Exact coolant direction to cutting area
- · Exclusive coolant bolt and cover are sold separately. Through coolant arbor is required

# Bolt: Ø63~Ø160 Cover: Over Ø200

#### Application range



#### Cutting speed





## E Technical Information for Future Mill

#### Max. available revolution

Cutter diameter	Max. revolution (rpm)
Ø63	20,000
Ø80	16,000
Ø100	13,000
Ø125	10,000
Ø160	8,000
Ø200	6,500
Ø250	5,000
Ø315	4,000

## **Future Mill (FMA)**

#### Features

- · General milling cutter for high productivity
- · Adjustable pitch of cutter and various chip breaker offer wide application range.
- Light cutter body allows high speed cutting and can be used in low horse power machine
- Smooth cutting with low cutting load is accomplished with high-rake angle



#### Features of chip breaker


	Insert	Cutting-edge	Uses	Features
	None C/B		Light cutting	Superior surface roughness at finishing due to ground type cermet insert
MF			Light cutting	Superior cutting quality for light and difficult-to-cut material machining through the low cutting load of chip breaker
ММ	•	•		Suitable for various cutting due to special shape design for general cutting
MR			Roughing	Tough cutting-edge provides stable cutting performance in severe interruption
MA	MA O		For aluminum	Superior cutting quality for aluminum due to sharp cutting-edge and buffed surface - S□ET-MA: Sharp cutting-edge due to high accurate grinding - S□XT-MA: Suitable cutting-edge for roughing

#### Recommended cutting condition


		•				
ISO Grades		(m/min)	MF	MM	MR	MA
iso Grades	vc (m/min)	fz (mm/t)	fz (mm/t)	fz (mm/t)	fz (mm/t)	
	NC5330	210~350	0.05~0.20	0.10~0.30	0.10~0.30	-
Р	NCM325	190~310	0.05~0.20	0.10~0.30	0.10~0.30	-
	PC3700	160~270	0.05~0.20	0.10~0.30	0.10~0.30	-
8.6	PC9530	90~150	0.05~0.15	0.10~0.30	-	-
M	NCM335	70~120	0.05~0.15	0.10~0.30	-	-
K	PC5300	110~180	0.05~0.20	0.10~0.30	-	-
N	H01	260~440	-	-	-	0.10~0.35

#### Features

- The strong cutting-edge ensures excellent tool life in high feed and high speed, deep depth of cut, with low cutting loads
- Optimal grades for most workpieces make high efficiency cutting possible
- Unique chip breaker makes good chip evacuation and lower cutting loads (1)
- Innovative curve cutting-edge lowers cutting load and provides a stronger cutting-edge  $({\bf 2})$











#### Features of chip breaker

- Innovative special cutting-edge and chip breaker design ensures ideal 90° cutting and low cutting load
- · Various applications are available with multi functional cutters (Facing, Slotting, Shouldering)
- Improved tool life due to special coated grades
- · Superior cutting quality at deep cutting depth through the low cutting load and strong cutting-edge

#### Recommended C/B and grade as per workpiece

						Recom	mended C/	B and gra	ade as per	workpiec	e (•: 1 <sup>st</sup> )		
Ir	nsert	Cutting- edge	Uses	Low carbon s	teel/Mild steel	High carbon s	teel/Mild steel	Stainle	ss steel	Cast	iron	Alumin	um alloy
		cugo		C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades	C/B	Grades
MF	•		Low cutting load type	•	○ NCM325 ○ NC5330 • NCM335		• NCM325 • NC5330 • NCM335	•	○ NCM325 ○ NC5330 • NCM335	•	• PC6510 • PC215K	-	-
ММ	•	0	Reinforced cutting edge type		○ NCM325 ○ NC5330 • NCM335		• NCM325 • NC5330 • NCM335		○ NCM325 ○ NC5330 • NCM335		• PC6510 • PC215K	-	-
MA	6		Sharp cutting edge type	-	-	-	-	-	-	-	-	•	○ H01 ○ G10

#### Recommended cutting condition

				Cutting Spec	ed vc (m/min)			
ISO	CVD	Coated			PVD Coated			Carbide
	NCM325	NCM335	PC3700	PC6510	PC5300	PC9530	PC5400	H01
Р	190~310	180~290	160-270	-	150-240	-	130-210	-
M	110~180	100~160	-	-	90-150	90-150	70-120	-
K	-	-	-	140-230	120-200	-	100-160	-
N	-	-	-	-	-	-	-	260-440

#### Features

- · Wide coverage for medium to roughing, general steel to high hardness mold materials
- 2 step shape of insert provides strong clamping and can minimize components to replace the shim
- 4-8 cutting-edge available per insert (Inscribed circle 05, 06, 07, 08, 10, 12, 16, 20)
- · Uneven flute spacing prevents vibration on high speed applications and provides more stable machining
- Precise design of the insert seat prevents insert from chattering
- Special design of the insert bottom prevents movement and chatter of insert
- Easy to change cutting-edge due to the rotation prevention design of the insert

#### Uses







Side cutting



Ramping

FMR Insert cutting-edge shape

Designation	RDHW M0F	RDHW M0E	RDHW M0S
Cutting edge shape (G calss)			


#### Features of chip breaker

	Insert	Cutting-edge	Uses	Features
MF			Light cutting	Low cutting resistance chip breaker design guarantees long tool life good performance at finishing and difficult-to-cut material machining
ММ			General	Suitable for general milling at wide application range
MA			Aluminum	Sharp cutting-edge and buffed top face for aluminum machining prevent welding and control chip flow

#### Clamping system







Good surface finish due to the precise design of insert seat part of cutter

Uneven flute spacing prevents vibration at high speed application and provides stable machining






Rotate prevention design of insert seat part

RDKT10T3M0-RDKT1204M0-

4-8 cutting-edge

available per insert

RDKT1605M0-MM RDKT2006M0-MM



Minimized heat generation due to smooth chip flow

Smooth cutting-edge preparation Inclined land angle Low cutting load and better surface roughness

Facial contact through curved face Prevent rotation at high speed

Stable and tight clamping of insert Good positioning of insert repeatedly





#### Chip removal rate (cm³/min)

	Workpiece	Grades	Ø8	Ø10	Ø12	Ø15	Ø16	Ø20	Ø21	Ø25	Ø26	Ø32	Ø33	Ø40	Ø50	Ø63	Ø80	Ø100	Ø125	Ø160
	General		4.97	9.94	9.94	14.92	31.83	31.83	47.74	47.74	47.74	71.61	38.19	95.49	119.36	143.23	167.11	190.98	133.69	509.29
	structure steel (under 200HB)		vc = 250	, fz = 0.25,	ap = 0.5, a	ae = 0.5D	vc = 300 ap = 1.0,					vc = 2	50, fz = 0	.4, ap =	1.5, ae =	0.5D				vc = 200, fz = 0.5 ap = 4.0, ae = 0.5D
	General		3.97	7.95	7.95	11.93	25.46	25.46	38.19	38.19	38.19	57.29	38.19	76.39	95.49	114.59	133.69	152.78	133.69	458.36
	carbon steel (under 30 HRC)		vc = 200	, fz = 0.25,	ap = 0.5,	ae = 0.5D	vc = 250 ap = 1.0,					vc = 20	00, fz = 0	.4, ap =	1.5, ae =	0.5D				vc = 180, fz = 0.5 ap = 4.0, ae = 0.5D
P	High carbon steel,	PC3700	2.86	5.72	5.72	8.59	22.91	22.91	34.37	34.37	34.37	51.56	34.37	68.75	85.94	103.13	120.32	137.5	120.32	407.43
-	Alloy steel (30~40 HrC)	PC5300	vc = 180	, fz = 0.20,	ap = 0.5,	ae = 0.5D	vc = 200 ap = 1.0,	), fz = 0.4 ae = 0.5D				vc = 18	30, fz = 0	.4, ap =	1.5, ae =	0.5D				vc = 160, fz = 0.5 ap = 4.0, ae = 0.5D
	High carbon steel, Alloy steel		1.24	2.48	2.48	3.72	11.45	11.45	14.32	17.18	14.32	21.48	14.32	28.64	35.8	42.97	50.13	57.29	50.13	249.55
			vc = 130	, fz = 0.15,	ap = 0.4,	ae = 0.5D	vc = 170 ap = 0.9,	), fz = 0.3 ae = 0.5D				vc = 1	50, fz = 0	.3, ap =	1.0, ae =	0.5D				vc = 140, fz = 0.4 ap = 3.5, ae = 0.5D
	Alloy steel		0.95	1.9	1.9	2.86	7.63	7.63	9.54	11.45	9.54	14.32	9.54	19.09	23.87	28.64	33.42	38.19	33.42	152.78
	(over 50 HRC)		vc = 100	, fz = 0.15,	ap = 0.4,	ae = 0.5D	vc = 130 ap = 0.9,	), fz = 0.3 ae = 0.5D				vc = 1	00, fz = 0	.3, ap =	1.0, ae =	0.5D				vc = 100, fz = 0.4 ap = 3.0, ae = 0.5D
В.Л	0	DOESOO	2.06	4.13	4.13	6.2	16.55	16.55	12.41	24.82	12.41	18.62	12.41	24.82	31.03	37.24	43.44	49.65	43.44	331.04
M	Stainless steel	PC5300	vc = 130	, fz = 0.20,	ap = 0.5,	ae = 0.5D	vc = 200 ap = 1.0,	), fz = 0.2 ae = 0.5D				vc = 1	00, fz = 0	.3, ap =	1.0, ae =	0.5D				vc = 130, fz = 0.5 ap = 4.0, ae = 0.5D
ĸ	04:	DOESCO	2.86	5.72	5.72	8.59	14.32	14.32	21.48	21.48	21.48	32.22	21.48	42.97	53.71	64.45	75.2	85.94	75.2	366.69
-K	Cast iron	PC5300	vc = 180	, fz = 0.20,	ap = 0.5,	ae = 0.5D	vc = 180 ap = 1.0,	), fz = 0.2 ae = 0.5D				vc = 18	30, fz = 0	.2, ap =	1.5, ae =	0.5D				vc = 180, fz = 0.4 ap = 4.0, ae = 0.5D

#### **○** Required machine power (P<sub>KW</sub> = 0.75 x P<sub>HP</sub>)

#### • RDKT10 □ □

	Workpiece	Grades	Ø21	Ø25	Ø26	Ø32	Ø40	Ø50	Ø63	Ø80	Ø100		Cutting of	condition	1
	Workpiece	Graues	021	W25	Ø20	<b>Ø</b> 32	940	Ø50	203	טסט	00100	vc	fz	ар	ae
	General structure steel (under 200HB)		2.2	2.2	2.2	3.3	4.4	5.5	6.6	7.7	8.8	250	0.4	1.5	0.5D
	General carbon steel (under 30 HRC)		2.1	2.1	2.1	3.1	4.1	5.2	6.2	7.3	8.3	200	0.4	1.5	0.5D
P	High carbon steel, Alloy steel (30~40 HRC)	PC3700 PC5300	2.2	2.2	2.2	3.3	4.5	5.6	6.7	7.9	9	180	0.4	1.5	0.5D
	High carbon steel, Alloy steel (40~50 HRC)		1.1	1.1	1.1	1.6	2.1	2.6	3.2	3.7	4.2	150	0.3	1.0	0.5D
	Alloy steel (over 50 HrC)		0.7	0.7	0.7	1.1	1.4	1.7	2.1	2.4	2.8	100	0.3	1.0	0.5D
M	Stainless steel	PC5300	0.6	0.6	0.6	0.8	1.2	1.5	1.7	2	2.3	130	0.2	1.5	0.5D
K	Cast iron	PC5300	0.6	0.6	0.6	0.9	1.2	1.5	1.8	2.1	2.4	180	0.2	1.5	0.5D

#### • RDKT12 □ □


<sup>•</sup> The figures in the above chart means Php value.

	Waylmiaaa	Cuadas	an	Ø33	Ø40	Ø50	Ø63	Ø80	Ø100	Ø125		Cutting of	condition	1
	Workpiece	Grades	Ø32	øss –	940	<i>1</i> 050	<i>1</i> 003	Ø80	0100	Ø125	vc	fz	ар	ae
	General structure steel (under 200HB)		1.7	1.7	2.6	3.5	3.5	4.4	5.3	6.1	200	0.4	1.5	0.5D
	General carbon steel (under 30 HRC)		2	2	3.1	4.1	2.6	5.2	6.2	7.2	180	0.4	1.5	0.5D
P	High carbon steel, Alloy steel (30~40 HRC)	PC3700 PC5300	2.2	2.2	3.3	4.4	2.8	5.6	6.7	7.8	160	0.4	1.5	0.5D
	High carbon steel, Alloy steel (40~50 HRC)		1	1	1.5	1.6	2.1	2.6	3.1	3.6	140	0.3	1.0	0.5D
	Alloy steel (over 50 HrC)		0.7	0.7	1	1.4	0.8	1.7	2.1	2.4	100	0.3	1.0	0.5D
M	Stainless steel	PC5300	0.5	0.5	0.8	1.1	0.7	1.4	1.7	2	130	0.2	1.5	0.5D
K	Cast iron	PC5300	0.6	0.6	0.9	1.2	0.7	1.5	1.8	2.1	180	0.2	1.5	0.5D

<sup>•</sup> The figures in the above chart means Php value.

#### Chip removal rate by cutting condition

#### Used insert: RDKT10□□



#### · Variation of cutting condition

Standard	ISO
Standard	vc = 200 fz = 0.4 ap = 1.5 ae = 0.5D
Speed (+)	250
Speed (-)	150
Feed (+)	0.6
Feed (-)	0.2
ap (+)	2
ap (–)	1
ae (+)	D
ae (–)	0.2D



## E

# S Recommended cutting condition

Side milling, slotting, ramping, copying

	)		)																	
	Worksign	000000	o do	Cutting speed	FMR1000	1000		FMR1500	FMR2000	000	FMR2500	2500	FMR3000	3000	FMR4000	4000	FMR5000	2000	FMR6000	0000
	and violation in the control of the	nardiless		(m/min)	ap (mm)	(m/min) ap (mm) fz (mm/t)	ap (mm)	ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t)	ap (mm)	z (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	'z (mm/t)	ap (mm)	fz (mm/t)	ap (mm) 1	fz (mm/t)	ap (mm) 1	(mm/t)
		000	PC5300	280		0	l	ı	1		,	,	0				, \	,		0
	10000	< aL002	PC5400	245	) -  -	√ 4.	Z:   <	√ 4.0	\  υ	√ 4.	<u>`</u> . ✓I	4.0 </td <td>C.U &lt; U.S &lt;</td> <td>\ O.O .O</td> <td>≥ Z.4 ≥ U.0</td> <td></td> <td>0.0</td> <td>NO.7</td> <td>\ V.4.∪</td> <td>0.</td>	C.U < U.S <	\ O.O .O	≥ Z.4 ≥ U.0		0.0	NO.7	\ V.4.∪	0.
	Cabon steel	\ C-1100	PC5300	250	0 /	0	C +	0	4			0	0	0	0 /		0	0 /		0
		7 OHLOS	PC5400	210	\ \ \ \	\l 2 4.	Λ 	\l \ \ \ \ \ \ \ \	\	\l > 4.	<u>.</u>	\l 2 4	N N	Ω. Ο.	\ \ 4.	0.0	0.0	, , , ,	\l 4	0.
٥	locto well A	0-101	PC5300	195	\ C \	0 \	C \	C \	C +	0	1	0	7 + 7	0	0		7 0 /	\ C	707	\ \ \
L	Alloy steel	00~40 CXE04~00	PC5400	170	\. O.\	N. ∪	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	≥ 0.Z	√.   ✓	N. V.	\	N.V.	\. 	\ 0.0	V.0	\ \ \ \ \ \ \	V Z./	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	\	0.0
		0-103 01	PC5300	150	0 /	0	0	0	C +	-		0				0	0 /		10 /	u 0
	High alloy steel	40~00ED	PC5400	130	\ \ \ 	N. O.	) (0	N. O.	Ŋ.  -	N. O.	\	N. O.	\. /I	\ 0.	N.O.	\l	/.7 <		\ 0.	0.0
	(alloy constituent > 5%)	Tensile strength	PC5300	120	0 /	0	0	0	C +	0	1	0	7 + 7	0	0		0 /	0	0 /	0
		350MPa ≤	PC5400	105	\ \ \ \	V.	N O.	N.O.	Δ.	N. O.	\	N.O.	\.	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	N.O.	\l 2 4.	V Z./	VI O	\ \ \ \ \	0.0
2	Cto coolaioto	/dI1070	PC5300	130	\ \ \	0 \	0	0 \	C + \	0 0	1	0	7 + 7	0	0 \		0 /	7	7.07	9
Ξ	oldilless steel	∠d⊓0/2	PC5400	110	\ \ \ \	N. O.	) (0	N. O.	Ŋ. //	N. O.	\	N.O.	`- /I	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	N.O.	\/\ 2 4.	/. V	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	\/ O	0.0
2	doi: too olitorid aosi too	oliogot wo	PC5300	145	0 /		C +		4		7 + 7	0	0	0	0 /	0	0	. 0	0	0
2	Cast Holl, Ductile cast Holl	Low tellslie	PC5400	110	\ \ \ \		N	\l 2.0 4.	Ω. Ω.	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	<u>`</u> .	V.4	N /	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	V.7.	o. /l	o.o		\I 2.	0.


Plunging

	, י																			
	Morking	7	ochor	Cutting speed	FME	FMR1000	FMR	FMR1500	FMR2000	2000	FMR2500	500	FMR3000	3000	FMR4000	4000	FMR5000	2000	FMR6000	000
	Workpiece	naldiess	diades	(m/min)	(m/min) ap (mm) fz (mm/l	fz (mm/t)	ap (mm)	(f) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t) ap (mm) fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm) 1	z (mm/t)
		0000	PC5300	280	C /	0		C \	C /	-		0	, I	0	0		C C	, ,	0	0
	10000	√ QLI007	PC5400	245	√ V.O	N. O.	\ 0.0	N.V.	\ 0.0	V.V.	V.2 V.2 V.3.U	N. V. Z	0.0	\/ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	4.0 V	\ 2. 4.	o.o √I	√ O.	N.O.	ο. Ο.
	Capoli steel	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	PC5300	250	0 /	0	0 \	0	0 /	0		0	\ \ \	0	0	0	0 \	0	0 0 0	0
		200HC	PC5400	210	\ \ \ \ \ \ \ \	N. O.	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	N.	\	N. O.	\l 2.	N.O.	0.0	\ 0.	0.0	\l 2. 4.	O. /I	Ω Ο	0.0	) )
2	looto roll A	00 00	PC5300	195	0 /	0	0	· ·	0 /	-		· ·	\ \ \	C \	0	0	0	0	0	0
L	Alloy steel	00~40 0HL04~00	PC5400	170	\ \ \ \ \ \ \	- - /l	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	- /I	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	- - /I	\l 2.	- - - /I	0.0	N.V.	0.0	\ 0.	O. /I	\l 2 4	0.0	Ω Ο.
		040	PC5300	150	0 /	,	0 \	-					\ \	0	ر د ا	0	0		7	\ \
	High alloy steel	40~00HI	PC5400	130	V.7	- - - /I	\ 0.0	- - - -	\ 0.0	- - - -	√l 5.	- - - - -	0.0	N.V.	O.O ⊲	√ ວ.ວ	O. ⊘	\ 4.	N.O.	N.O.
	(alloy constituent > 5%)	Tensile strength	PC5300	120	0 /	-	0 \	,	0 /	-	0	,	\ \ \	0	0	0	0 \		0 0 0	0
		350MPa ≤	PC5400	105	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	- - //	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	- /I	\	- - //	\l 2.	- - /I	0.0	N.O.	0.0	ا/ ن	O. /I	\l 2 4.	0.0	) ()
2	loote acolaieta	\d \020	PC5300	130	0 /	,	0 \	, ,	0 / 0 / 1	, ,	0 7		И	0	ر د ا	0	0	~	1	\ \ \
Ξ	Ordiness steel	ZUIID/Z	PC5400	110	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	- - //	\/ \ \ \ \ \	- /I			\l \.	- - /I	) )	N. O.	0.0	\l	) /I	\l 5 - 5	0.00	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
2	activity of the Control of the Contr	oliogot wo	PC5300	145	C /	0 0	0 \	0 0	0 /			0	\ \	0	ر د د		0	7	100	0
<	cast from, Ductille cast from	POW TELISITE	PC5400	110	V.7		\ 0.0	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	\ 0.0	V.V.	√l O.	N. V. Z	0.0	\ 0.0	O.O ⊲	\ 2. 4.	o.o √I	\ \ \ \ \ \ \	N.O.	o. ∕l

Helical cutting

			Programme.	FMB1000	000	FMR1500	200	FMR2000	0000	FMR2500	2500	EMB	FMB3000	FMB4000	1000	FMR5000	2000	FMB6000	2000
Worknippe	Hardnoee	Gradee	Commission Speed		3		3				200		3		200		3		9
9000		ol adds	(m/min)	(m/min) ap (mm) fz (mm/t)		ap (mm) fa	z (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm) tz (mm/t) ap (mm) tz (mm/t) ap (mm) tz (mm/t) ap (mm) tz (mm/t) ap (mm) tz (mm/t) ap (mm/t) ap (mm/t)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)
	000	PC5300	280				0			,			0					,	,
100	N GLOON	PC5400	245	S U.N S U.Z	N. O.	N.U ≤ 0.1 ≤		N.U ≤ U.Z	N. V.	N.U & U.Z		N Z.O	5.0 ≥ 0.3 ≥	V Z.O	^I 4.	≥ 4.0 ≤ 0.3	ν Ο.	√l 0.4	o. O.
Cabon steel	0.1100	PC5300	250		0		0	10 /	0	. 0	C \	C \	0	0	0		0	\ \ \	0
	SUTING	PC5400	210	√.V	N. V. Z	\. O.\	N. O.	√. O./	N. V.	\. O.\	≥ 0.Z	V. ∠.	∧ ວ.ວ	V Z.O	^I 4.	^l 0.4	√ C.O	∧ 7.	ο. Ο.
loops well w	0-1101	PC5300	195		-		-	7	-		,	7 + 7	0	7	0	707	0	7 0 /	0
Alloy steel	0.02×40⊓EC	PC5400	170	\. \.	- O VI	\.O.\	- - - - -	\. O.\	- - - - -	\. O.\	- - - -	\. \.	√ 7.0 <	/-	ا\ 5.	\/ 	\ 4.	\. 	√ O:O
	0	PC5300	150		,	,	,	,	,	,	,	, ,	0	7	0	,	,	,	
High alloy steel	40~30TRC	PC5400	130	\. O.\	- O VI	\. O.\	-	√. O./	- ⊙ ∨I	\. O.\	- - - -	\. ✓I	√ N.O.	\. 	∧ ວ.	ا\ ن.	∧ 9.	\. ن.	N.O.
(alloy constituent > 5%)	Tensile strength	PC5300	120	0			-	,	-		· ·		0	. 4	0	0 /		0 /	, ,
	350MPa ≤	PC5400	105	\. \.	- - - -	\ \ \ \	- /I	\. O.	- - - - -	\. O./	- - - - -	\.	√ 7.0 <	/	\ ວ.ວ	\.	√l 4.	\ 0.	√ O:O
In the second second	701070	PC5300	130	,				,			,	, ,	0	,	0	,		0 /	0
VI Stalliess steel	NGLIO / Z	PC5400	110	· · · · · · · · · · · · · · · · · · ·	- - /I	· · · · · · · · · · · · · · · · · · ·	- - //	/l	- - /I	\ \ \ !	- - /I	\. /I	N 0.1	\. /I	ا/ ن	\ O	√l 5.	\ 0.	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
	9	PC5300	145	7		7	0			7	0		0	0			L	,	0
Cast Iron, Ductile cast Iron	Low terisine	PC5400	110	ν. Ο:	N. O.	ν - -	N 0.2	).  - 	N	) - VI	∆ N.O.	N.O.	ا ای	N.O.	∆ 4.	∆ 0.4	ν Ο.Ο	^ \ 0.4	o.∨ 

#### FMR Vibration test



#### **Machining example**



■ Workpiece STD11

Cutting vc (m/min) = 200**condition** fz (mm/t) = 0.40

ap (mm) = 2.0

ae (mm) = 4.0■ Tools Insert RDKT10T3M0-MM

(PC3500)

Holder FMRS3032RD-S

#### Cutting condition formulas for milling

#### **Cutting speed**

#### RPM

$$vc = \frac{\pi \times D \times n}{1000} \text{ (m/min)}$$

$$n = \frac{vc \times 1000}{\pi \times D} \text{ (min}^{-1}\text{)}$$

#### Feed (per tooth)

#### Feed (per minute)

$$fz = \frac{vf}{Z \times n} (mm/t)$$

$$vf = fz \times n \times z \text{ (mm/min)}$$


#### Chip removal rate

#### Required machine power

$$Q = \frac{ap \times ae \times vf}{1000} \text{ (cm}^3\text{/min)}$$

$$Pkw = \frac{Q \times kc}{60 \times 102 \times \eta} (kW)$$

$$Php = \frac{Pc}{0.75} (hp)$$




vc = Cutting speed (m/min)	Pkw = Required machine power (kW)
<b>n</b> = Revolution per a minute (min <sup>-1</sup> )	Php = Horsepower requirement (hp)
D = Cutting diameter (mm)	Q = Chip removal amount (cm³/min)
De = Efficient cutting diameter (mm)	ap = Depth of cut (mm)
vf = Feed per a minute (mm/min)	ae = Width of cut (mm)
fz = Feed per tooth (mm/t)	kc = Specific cutting resistance (MPa)
z = Number of tooth	η = Mechanical efficiency (%)
Pc = Power requirement (kW)	

#### Feed as per cutting depth

			Depth of cut (mm)												
Designation	Chip breaker	0.2~0.5	0.5~1.0	2.0	3.0	4.0	5.0	6.0	7.0	8.0					
RDHW0501M0	-	0.25	0.15	-	-	-	-	-	-	-					
RDHW06T1M0	-	0.30	0.20	0.10	-	-	-	-	-	-					
RDHW0702M0	-	0.35	0.25	0.10	0.07	-	-	-	-	-					
RDHW0803M0	-	0.40	0.30	0.15	0.01	-	-	-	-	-					
RDKT10T3M0 -	MF/MM	-	0.40	0.35	0.30	0.20	-	-	-	-					
RDKT1204M0 -	MF/MM	-	0.50	0.45	0.30	0.25	0.22	-	-	-					
RDHW1605M0	-	-	0.60	0.50	0.45	0.35	0.30	0.20	0.10	-					
RDHW2006M0	-	-	-	0.60	0.50	0.40	0.30	0.25	0.15	0.10					
RDKT1605M0 -	ММ	-	0.60	0.50	0.45	0.35	0.30	0.20	0.10	-					
RDKT2006M0 -	ММ	-	-	0.60	0.50	0.40	0.30	0.25	0.15	0.10					



#### Ramping technical data



$$Lmin = \frac{ap}{\tan \alpha^{\circ}} (mm)$$


\* Lmin: Min. inclination cutting length

 $\alpha^{\circ} {:}~$  Max. ramping angle ap: Depth of cut

Cooties	To all alli-	Ramping				Cutting le	ength L (mr	n) by ram	ping angle			
Section	Tool dia.	angle a° (Max)	ap = 1	ap = 2	ap = 2.5	ap = 3	ap = 3.5	ap = 4	ap = 5	ap = 6	ap = 8	ap = 10
	08	18.14	3	6	8	-	-	-	-	-	-	-
EMD4000	10	11.7	5	10	12	-	-	-	-	-	-	-
FMR1000	12	8.43	7	13	17	-	-	-	-	-	-	-
	15	5.93	10	19	24	-	-	-	-	-	-	-
	10	20.67	21	5	7	8	-	-	-	-	-	-
FMR1500	12	10.05	10	11	14	17	-	-	-	-	-	-
FINIT 1300	16	6.12	6	19	23	28	-	-	-	-	-	-
	20	4.36	4	26	33	39	-	-	-	-	-	-
FMR2000	15	9.42	6	12	15	18	21	-	-	-	-	-
rivin2000	20	5.85	10	20	24	29	34	-	-	-	-	-
	16	13.7	4	8	10	12	14	16	-	-	-	-
FMR2500	20	9.29	6	12	15	18	21	24	-	-	-	-
	25	6.56	9	17	22	26	30	35	-	-	-	-
	25	21.8	3	5	6	8	9	10	13	-	-	-
	32	13.24	4	9	11	13	15	17	21	-	-	-
	40	9.09	6	13	16	19	22	25	31	-	-	-
FMR3000	50	6.52	9	17	22	26	31	35	44	-	-	-
	63	4.76	12	24	30	36	42	48	60	-	-	-
	80	3.52	16	33	41	49	57	65	81	-	-	-
	100	2.69	21	43	53	64	74	85	106	-	-	-
	32	15.95	3	7	9	10	12	14	17	21	-	-
	40	10.3	6	11	14	17	19	22	28	33	-	-
	50	7.13	8	16	20	24	28	32	40	48	-	-
FMR4000	63	5.08	11	22	28	34	39	45	56	67	-	-
	80	3.69	16	31	39	47	54	62	78	93	-	-
	100	2.79	21	41	51	62	72	82	103	123	-	-
	125	2.14	27	54	67	80	94	107	134	161	-	-
	40	7.4	8	15	19	23	27	31	38	46	62	-
	50	5.22	11	22	27	33	38	44	55	66	88	-
FMR5000	63	3.79	15	30	38	45	53	60	75	91	121	-
rivinguuu	80	2.97	19	39	48	58	67	77	96	116	154	-
	100	2.09	27	55	69	82	96	110	137	164	219	-
	125	1.63	35	70	88	105	123	141	176	211	281	-
	40	7.44	8	15	19	23	27	31	38	46	61	77
	50	4.97	11	23	29	34	40	46	57	69	92	46
FMR6000	63	3.69	16	31	39	47	54	62	78	93	124	62
LINIDOUOU	80	2.72	21	42	53	63	74	84	105	126	168	84
	100	2.12	27	54	68	81	95	108	135	162	216	108
	125	1.57	36	73	91	109	128	146	182	219	292	146



#### Helical cutting technical data - ØDHmin




- ØD = Tool dia. (mm), ØDHmin, Max = Min, Max diameter (mm)
- Ød = Tool path (mm) ØDHmin (Min diameter) = ØD × 2 Insert size, ØDHmax (Max diameter) = ØD × 2 2
- $\emptyset$ d (Tool path) =  $\emptyset$ DHmin, Max  $\emptyset$ D

(mm)

									Ramping	angle (a	°)			(111111)
Section	Insert	Tool dia.	ØDHmin	Ød	ap = 1	ap = 2	ap = 2.5	ap = 3	ap = 3.5	ap = 4	ap = 5	ap = 6	ap = 8	ap = 10
	5	08	11	3	6.11	12.35	15.57	· -	· .	-	-	-	-	-
	5	10	15	5	3.65	7.34	7.34	-	-	-	-	-	-	-
FMR1000	5	12	19	7	2.61	5.23	5.23	-	-	-	-	-	-	-
	5	15	25	10	1.83	3.65	3.65	-	-	-	-	-	-	-
	6	10	14	4	4.57	9.20	9.20	13.95	-	-	-	-	-	-
EMD4500	6	12	18	6	3.04	6.11	6.11	9.20	-	-	-	-	-	-
FMR1500	6	16	26	10	1.83	3.65	3.65	5.49	-	-	-	-	-	-
	6	20	34	14	1.30	2.61	2.61	3.92	-	-	-	-	-	-
FMR2000	7	15	23	8	2.28	4.57	4.57	6.88	8.04	-	-	-	-	-
FININZUUU	7	20	33	13	1.40	2.81	2.81	4.22	4.92	-	-	-	-	-
	8	16	24	8	2.28	4.57	4.57	6.88	8.04	9.20	-	-	-	-
FMR2500	8	20	32	12	1.52	3.04	3.04	4.57	5.34	6.11	-	-	-	-
	8	25	42	17	1.07	2.15	2.15	3.22	3.76	4.30	-	-	-	-
	10	25	40	15	1.22	2.43	2.43	3.65	4.27	4.88	6.11	-	-	-
	10	32	54	22	0.83	1.66	1.66	2.49	2.91	3.32	4.15	-	-	-
	10	40	70	30	0.61	1.22	1.22	1.83	2.13	2.43 3.04 -		-	-	-
FMR3000	10	50	90	40	0.46	0.91	0.91	1.37	1.60	1.83	2.28	-	-	-
	10	63	116	53	0.34	0.69	0.69	1.03	1.21	1.38	1.72	-	-	-
	10	80	150	70	0.26	0.52	0.52	0.78	0.91	1.04	1.30	-	-	-
	10	100	190	90	0.20	0.41	0.41	0.61	1 0.71 0.81 1.01 -		-	-	-	
	12	32	52	20	0.91	1.83	1.83	2.74	3.20	3.65	4.57	5.49	-	-
	12	40	68	28	0.65	1.30	1.30	1.96	2.28	2.61	3.26	3.92	-	-
	12	50	88	38	0.48	0.96	0.96	1.44	1.68	1.92	2.40	2.88	-	-
FMR4000	12	63	114	51	0.36	0.72	0.72	1.07	1.25	1.43	1.79	2.15	-	-
	12	80	148	68	0.27	0.54	0.54	0.81	0.94	1.07	1.34	1.61	-	-
	12	100	188	88	0.21	0.41	0.41	0.62	0.73	0.83	1.04	1.24	-	-
	12	125	238	113	0.16	0.32	0.32	0.48	0.57	0.65	0.81	0.97	-	-
	16	40	64	24	0.76	1.52	1.52	2.28	2.66	3.04	3.81	4.57	6.11	-
	16	50	84	34	0.54	1.07	1.07	1.61	1.88	2.15	2.69	3.22	4.30	-
FMR5000	16	63	110	47	0.39	0.78	0.78	1.16	1.36	1.55	1.94	2.33	3.11	-
1 101113000	16	80	144	64	0.29	0.57	0.57	0.86	1.00	1.14	1.43	1.71	2.28	-
	16	100	184	84	0.22	0.43	0.43	0.65	0.76	0.87	1.09	1.30	1.74	-
	16	125	234	109	0.17	0.33	0.33	0.50	0.59	0.67	0.84	1.00	1.34	-
	20	50	80	30	0.61	1.22	1.22	1.83	2.13	2.43	3.04	3.65	4.88	6.11
	20	63	106	43	0.42	0.85	0.85	1.27	1.49	1.70	2.12	2.55	3.40	4.25
FMR6000	20	80	140	60	0.30	0.61	0.61	0.91	1.06	1.22	1.52	1.83	2.43	3.04
. IVII 10000	20	100	180	80	0.23	0.46	0.46	0.68	0.80	0.91	1.14	1.37	1.83	2.28
	20	125	230	105	0.17	0.35	0.35	0.52	0.61	0.70	0.87	1.04	1.39	1.74
	20	160	300	140	0.13	0.26	0.26	0.39	0.46	0.52	0.65	0.78	1.04	1.30



#### Helical cutting technical data - ØDHmax



- ØD = Tool dia. (mm), ØDHmin, Max = Min, Max diameter (mm)
- $\emptyset$ d = Tool path (mm)
- ØDHmin (Min diameter) = ØD  $\times$  2 Insert size, ØDHmax (Max diameter) = ØD  $\times$  2 2
- Ød (Tool path) = ØDHmin, Max ØD

(mm)

									Ramping	angle (a°	?)			(111111)
Section	Insert	Tool dia.	ØDHmax	Ød	ap = 1	ap = 2	ap = 2.5	ap = 3	ap = 3.5	ap = 4	ap = 5	ap = 6	ap = 8	ap = 10
	5	08	14	6	3.04	6.11	7.65		-	-	-	-	-	-
<b>EMB</b> 4000	5	10	18	8	2.28	4.57	5.72	-	-	-	-	-	-	-
FMR1000	5	12	22	10	1.83	3.65	4.57	-	-	-	-	-	-	-
	5	15	28	13	1.40	2.81	3.51	-	-	-	-	-	-	-
	6	10	18	8	2.28	4.57	5.72	6.88	-	-	-	-	-	-
FMD4500	6	12	22	10	1.83	3.65	4.57	5.49	-	-	-	-	-	-
FMR1500	6	16	30	14	1.30	2.61	3.26	3.92	-	-	-	-	-	-
	6	20	38	18	1.01	2.03	2.54	3.04	-	-	-	-	-	-
EMBOOOO	7	15	28	13	1.40	2.81	3.51	4.22	4.92	-	-	-	-	-
FMR2000	7	20	38	18	1.01	2.03	2.54	3.04	3.55	-	-	-	-	-
	8	16	30	14	1.30	2.61	3.26	3.92	4.57	5.23	-	-	-	-
FMR2500	8	20	38	18	1.01	2.03	2.54	3.04	3.55	4.06	-	-	-	-
	8	25	48	23	0.79	1.59	1.98	2.38	2.78	3.18	-	-	-	-
	10	25	48	23	0.79	1.59	1.98	2.38	2.78	3.18	3.97	-	-	-
	10	32	62	30	0.61	1.22	1.52	1.83	2.13	2.43	3.04	-	-	-
	10	40	78	38	0.48	0.96	1.20	1.44	1.68	1.92	2.40	-	-	-
FMR3000	10	50	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	-	-	-
	10	63	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	-	-	-
	10	80	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	-	-	-
	10	100	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	-	-	-
	12	32	62	30	0.61	1.22	1.52	1.83	2.13	2.43	3.04	3.65	-	-
	12	40	78	38	0.48	0.96	1.20	1.44	1.68	1.92	2.40	2.88	-	-
	12	50	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	2.28	-	-
FMR4000	12	63	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	1.80	-	-
	12	80	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	1.40	-	-
	12	100	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	1.12	-	-
	12	125	248	123	0.15	0.30	0.37	0.45	0.52	0.59	0.74	0.89	-	-
	16	40	78	38	0.48	0.96	1.20	1.44	1.68	1.92	2.40	2.88	3.85	-
	16	50	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	2.28	3.04	-
EMBEO00	16	63	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	1.80	2.39	-
FMR5000	16	80	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	1.40	1.87	-
	16	100	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	1.12	1.49	-
	16	125	248	123	0.15	0.30	0.37	0.45	0.52	0.59	0.74	0.89	1.19	-
	20	50	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	2.28	3.04	3.81
	20	63	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	1.80	2.39	2.99
FMR6000	20	80	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	1.40	1.87	2.34
LINIMOUUU	20	100	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	1.12	1.49	1.86
	20	125	248	123	0.15	0.30	0.37	0.45	0.52	0.59	0.74	0.89	1.19	1.48
	20	160	318	158	0.12	0.23	0.29	0.35	0.40	0.46	0.58	0.69	0.92	1.16

#### **Future Mill series for mold making**

## **FMR P-positive**

- Stable clamping system enables stable machining and productivity
- Varied product line-up ensures wide application range
- Optimal shape and grade with high hardness for hard-to-cut material machining

#### Features

- P-positive relief angle (11°) ensures high rigidity and high machinability in die steel and high-resistant alloy machining
- Flat clearance face of insert prevents interference and revolution while machining
- · Optimal grades and chip breakers for various workpieces
- · Chip breaker
- Concave shape ensures wide chip pocket and lowers cutting temperature
- · Clearance face for preventing rotation
- Prevents rotation in machining
- Divides corners
- Prevents interference in high-feed machining
- Ensures stable clamping
- · Through-coolant system
- Superb chip evacuation
- Low cutting heat ensures long tool life

#### Features of chip breaker

I	nsert	Cutting-edge	Uses	Features
MA			Aluminum machining	Optimal cutting-edge for aluminum machining and buffed surface ensure high machinability
ML	9		Titanium & Inconel machining	Excellent results in titanium machining thanks to a high hardness cutting-edge and the chip breaker reducing the cutting load
MF			Light machining	Chip breaker for low cutting resistance enables fine finishing.
ММ			General machining	Optimal for general machining
None C/B	9		Super hard material machining	Optimal for high hardness die steel and heat resistant alloy

#### Recommended cutting condition

\*Recommended chip breaker: • First OSecond

						Cutting c	onditions			С	hip b	ip breaker		
	Workpi	ece	Hardness	Grades	vc (m/min)	fz (mm/t)	ap (mm)	ae (mm)	MA	ML	MF	ММ	None 1	e C/B
	Low carb	on steel	HB80~180	PC5400	100~250	0.12~0.70	0.3~6.0	0.7D~0.1D	-	-	•	0	-	-
	High carl	oon steel	HB180~280	PC5400	100~220	0.12~0.70	0.3~6.0	0.7D~0.1D	-	-	•	0	-	-
	Lawalli		Under H <sub>R</sub> C27	PC3700	180~290	0.20~0.60	0.3~6.0	0.7D~0.1D	-	-	-	•	0	-
	Low allo	by steel	Under HRC27	PC5400/PC5300	100~200	0.20~0.60	0.3~6.0	0.7D~0.1D	-	-	-	•	0	-
P			HRC20~50	PC3700	130~250	0.30~0.50	~ 0.5	0.7D~0.1D	-	-	-	-	•	0
	Low pre-har	aenea steei	HRU20~50	PC2510/PC5300	50~150	0.30~0.50	~ 0.5	0.7D~0.1D	-	-	-	-	•	0
	Illiah allamatasi		Linday II-CO7	PC3700	130~250	0.30~0.50	~ 0.5	0.7D~0.1D	-	-	-	•	0	-
	High alloy steel	oy steel	Under HRC27	PC5300	100~220	0.30~0.50	~ 0.5	0.7D~0.1D	-	-	-	•	0	-
	High pre-hardened steel		HRC20~48	PC2510/PC5300	50~150	0.30~0.50	~ 0.5	0.7D~0.1D	-	-	-	-	•	0
M	Stainles	ss steel	Under HB270	PC5300/PC5400	100~150	0.20~0.60	0.3~6.0	0.7D~0.1D	-	-	0	•	-	-
K	Gray cast iron, [	Ductile cast iron	Under 350MPa	PC5300	120~210	0.20~0.60	0.3~6.0	0.7D~0.1D	-	-	0	•	-	-
N	Alum	inum	-	H01	300~800	0.30~0.60	0.3~6.0	0.7D~0.1D	•	-	-	-	-	-
	Heat resistant	Fe	HRC20~30	PC5300/PC5400	35~60	0.30~0.50	~ 0.5	0.7D~0.1D	-	•	0	-	-	-
S	alloy	Ni or Co	HRC40~45	PC5300/PC5400	30~50	0.30~0.50	~ 0.5	0.7D~0.1D	-	•	0	-	-	-
	Titar	nium	HRC35~45	PC5300/PC5400	40~70	0.30~0.50	~ 1.5	0.7D~0.1D	-	•	0	-	-	-
Н	H High hardened materials		Over HRC50	PC2505/PC2510	30~50	0~50 0.30~0.50 ~ 0.5 0.7D~		0.7D~0.1D	-	-	-	-	•	0



# Technical Information for FMR P-positive

#### Feed per tooth according to ap (fz, mm/t)

(mm)

Insert	Insert size (d)		Feed per tooth according to ap												
insert		ap = 1	ap = 2	ap = 3	ap = 4	ap = 5	ap = 6	ap = 8	ap = 10						
RPMT08	8	0.30	0.22	0.18	0.15	-	-	-	-						
RPMT10	10	0.40	0.28	0.25	0.20	0.12	-	-	-						
RPMT12	12	0.60	0.45	0.35	0.30	0.25	0.20	-	-						
RPMT16	16	0.65	0.45	0.40	0.32	0.30	0.28	0.23	-						
RPMT20	20	0.70	0.50	0.42	0.35	0.32	0.29	0.25	0.22						

#### Performance evaluation

#### Alloy steel (SM490A Heat treatment, HRC 38~40)

Cutting vc (m/min) = 250conditions fz (mm/tooth) = 0.6

> ap (mm) = 1wet

RPMT1204M0E-MF (PC5300) ■ Tools Insert

Holder FMRS4032HRP-3L25





RPMT-MF Competitor

#### Low pre-hardened steel (KP4M Heat treatment, HRC 30~45)


vc (m/min) = 178 Cutting **conditions** fz (mm/tooth) = 0.72

ap (mm) = 1.5

dry

■ Tools RPMT1606M0S-MM (PC5300) Insert

> Holder FMRCM5063HRP-4





#### Low pre-hardened steel (KP1, HRC 28~33)

Cutting vc (m/min) = 178conditions fz (mm/tooth) = 0.74

ap (mm) = 0.8dry

■ Tools Insert RPMT1204M0E-MF (PC5300)

> FMRCM4063HRP-6 Holder

Result .2 times more Tool life (%) 120 00 RPMT-MF Competitor



#### High pre-hardened steel (STD61, HRC 50~52)


Cutting vc (m/min) = 50conditions fz (mm/tooth) = 0.15

ap (mm) = 4.0

dry

RPMW1204M0S1 (PC5300) ■ Tools Insert

Holder FMRS4032HRP-3L25









## **FMR P-positive**

## Maximum angle table for ramping machining



$$Lmin = \frac{ap}{tan \, a^{\circ}} (mm$$




	Incort size	Tooldia	Domning and				Cutti	ing length	I (mm)	hv an			(mm)
Section	Insert size (d)	Tool dia. (ØD)	Ramping angle a° (max)	ap = 1	ap = 2	ap = 2.5		ap = 3.5		ap = 5	ap = 6	ap = 8	ap = 10
	8	17	4.7	12	24	30	36	42	48			-	-
	8	18	4.1	14	28	34	41	48	55	-	_		
	8	20	15.4	4	7	9	11	13	14	-		-	_
FMR2500	8	21	13.9	4	8	10	12	14	16	-		-	
	8	25	9.8	6	12	14	17	20	23	-	-	-	-
	8	26	9.2	6	12	16	19	22	25	-	-	-	-
	10	25	13.8	4	8	10	12	14	16	20	-	-	-
	10	26	12.6	4	9	11	13	16	18	22	-	-	-
	10	32	8.4	7	14	17	20	24	27	34	-	-	-
	10	33	8.0	7	14	18	21	25	29	36	_	-	-
FMR3000	10	40	5.8	10	20	25	30	34	39	49	_	-	-
	10	50	4.2	14	27	34	41	48	55	68	-	-	-
	10	63	3.1	19	37	47	56	65	75	93	-	-	-
	10	66	2.9	20	40	50	60	69	79	99	-	-	-
	12	25	4.5	13	25	32	38	44	51	63	76	-	-
	12	26	4.1	14	28	35	42	49	56	70	84	-	-
FMR4000	12	32	14.7	4	8	10	11	13	15	19	23	-	-
	12	33	13.8	4	8	10	12	14	16	20	24	-	-
	12	40	9.6	6	12	15	18	21	24	30	36	-	-
	12	50	6.7	9	17	21	26	30	34	43	51	-	-
	12	63	4.8	12	24	30	36	42	48	60	72	-	-
	12	66	4.5	13	26	32	38	45	51	64	77	-	-
	12	80	3.5	17	33	41	50	58	66	83	99	-	-
	12	100	2.6	22	44	55	65	76	87	109	131	-	-
	16	40	17.8	3	6	8	9	11	12	16	19	25	-
	16	50	11.3	5	10	13	15	18	20	25	30	40	-
	16	63	7.6	7	15	19	22	26	30	37	45	60	-
FMDF000	16	66	7.1	8	16	20	24	28	32	40	48	64	-
FMR5000	16	80	5.3	11	21	27	32	37	43	53	64	85	-
	16	100	4.0	14	29	36	43	51	58	72	87	116	-
	16	125	3.0	19	38	48	58	67	77	96	115	154	-
	16	160	2.2	26	52	65	78	90	103	129	155	207	-
	20	50	17.8	3	6	8	9	11	12	16	19	25	31
	20	63	11.1	5	10	13	15	18	20	25	30	41	51
	20	80	7.4	8	15	19	23	27	31	38	46	61	77
EMBCOOC	20	100	5.3	11	21	27	32	37	43	53	64	85	107
FMR6000	20	125	4.0	14	29	36	43	51	58	72	87	116	145
	20	160	2.9	20	40	49	59	69	79	99	119	158	198
	20	200	2.2	26	52	65	78	90	103	129	155	207	258
	20	250	1.7	33	67	84	100	117	134	167	200	267	334

 $<sup>\</sup>ast$  Insert size (d): Please refer page E16 applicable insert drawing.




## **FMR P-positive**

#### Minimum hole diameter table for helical machining (ØDHmin)



- ØD = Tool dia. (mm)
- Ød (Tool path, mm) = ØDHmin, Max ØD
- ØDHmin (Minimum hole diameter) =  $\emptyset$ D × 2 Insert size (d)
- ØDHmax (Maximum hole diameter) =  $\emptyset$ D × 2 2
- Ramping angle by ap  $(\alpha^{\circ}) = tan^{-1} \left( \frac{ap}{\pi \times \ensuremath{\text{Od}}} \right)$ Helical angle adjusted by ap cannot exceed maximum angle
- ap = Depth of cut




			1												(mm)
Section	Insert	Tool dia.	Ramping	ØDHmin	Ød				Ran	nping and	gle (a°) l	by ap			
Section	size (d)	(ØD)	angle a° (max)	וווווחטש	Øu	ap = 1	ap = 2	ap = 2.5	ap = 3	ap = 3.5	ap = 4	ap = 5	ap = 6	ap = 8	ap = 10
	8	17	4.7	26	9	2.03	4.06	-	-	-	-	-	-	-	-
	8	18	4.1	28	10	1.83	3.65	-	-	-	-	-	-	-	-
FMR2500	8	20	15.4	32	12	1.52	3.04	3.81	4.57	5.34	6.11	-	-	-	-
1 101112300	8	21	13.9	34	13	1.40	2.81	3.51	4.22	4.92	5.63	-	-	-	-
	8	25	9.8	42	17	1.07	2.15	2.69	3.22	3.76	4.30	-	-	-	-
	8	26	9.2	44	18	1.01	2.03	2.54	3.04	3.55	4.06	-	-	-	-
	10	25	13.8	40	15	1.22	2.43	3.04	3.65	4.27	4.88	-	-	-	-
	10	26	12.6	42	16	1.14	2.28	2.85	3.43	4.00	4.57	-	-	-	-
	10	32	8.4	54	22	0.83	1.66	2.07	2.49	2.91	3.32	-	-	-	-
FMR3000	10	33	8.0	56	23	0.79	1.59	1.98	2.38	2.78	3.18	-	-	-	-
FININGUUU	10	40	5.8	70	30	0.61	1.22	1.52	1.83	2.13	2.43	-	-	-	-
	10	50	4.2	90	40	0.46	0.91	1.14	1.37	1.60	1.83	-	-	-	-
	10	63	3.1	116	53	0.34	0.69	0.86	1.03	1.21	1.38	-	-	-	-
	10	66	2.9	122	56	0.33	0.65	0.81	0.98	1.14	1.30	-	-	-	-
	12	25	4.5	38	13	1.40	2.81	3.51	-	-	-	-	-	-	-
	12	26	4.1	40	14	1.30	2.61	3.26	-	-	-	-	-	-	-
	12	32	14.7	52	20	0.91	1.83	2.28	2.74	3.20	3.65	4.57	5.49	-	-
	12	33	13.8	54	21	0.87	1.74	2.17	2.61	3.04	3.48	4.35	5.23	-	-
FMR4000	12	40	9.6	68	28	0.65	1.30	1.63	1.96	2.28	2.61	3.26	3.92	-	-
rivin4000	12	50	6.7	88	38	0.48	0.96	1.20	1.44	1.68	1.92	2.40	2.88	-	-
	12	63	4.8	114	51	0.36	0.72	0.89	1.07	1.25	1.43	1.79	2.15	-	-
	12	66	4.5	120	54	0.34	0.68	0.84	1.01	1.18	1.35	1.69	2.03	-	-
	12	80	3.5	148	68	0.27	0.54	0.67	0.81	0.94	1.07	1.34	1.61	-	-
	12	100	2.6	188	88	0.21	0.41	0.52	0.62	0.73	0.83	1.04	1.24	-	-
	16	40	17.8	64	24	0.76	1.52	1.90	2.28	2.66	3.04	3.81	4.57	6.11	-
	16	50	11.3	84	34	0.54	1.07	1.34	1.61	1.88	2.15	2.69	3.22	4.30	-
	16	63	7.6	110	47	0.39	0.78	0.97	1.16	1.36	1.55	1.94	2.33	3.11	-
FMR5000	16	66	7.1	116	50	0.36	0.73	0.91	1.09	1.28	1.46	1.83	2.19	2.92	-
FININGUUU	16	80	5.3	144	64	0.29	0.57	0.71	0.86	1.00	1.14	1.43	1.71	2.28	-
	16	100	4.0	184	84	0.22	0.43	0.54	0.65	0.76	0.87	1.09	1.30	1.74	-
	16	125	3.0	234	109	0.17	0.33	0.42	0.50	0.59	0.67	0.84	1.00	1.34	-
	16	160	2.2	304	144	0.13	0.25	0.32	0.38	0.44	0.51	0.63	0.76	1.01	-
	20	50	17.8	80	30	0.61	1.22	1.52	1.83	2.13	2.43	3.04	3.65	4.88	6.11
	20	63	11.1	106	43	0.42	0.85	1.06	1.27	1.49	1.70	2.12	2.55	3.40	4.25
	20	80	7.4	140	60	0.30	0.61	0.76	0.91	1.06	1.22	1.52	1.83	2.43	3.04
EMDC000	20	100	5.3	180	80	0.23	0.46	0.57	0.68	0.80	0.91	1.14	1.37	1.83	2.28
FMR6000	20	125	4.0	230	105	0.17	0.35	0.43	0.52	0.61	0.70	0.87	1.04	1.39	1.74
	20	160	2.9	300	140	0.13	0.26	0.33	0.39	0.46	0.52	0.65	0.78	1.04	1.30
	20	200	2.2	380	180	0.10	0.20	0.25	0.30	0.35	0.41	0.51	0.61	0.81	1.01
	20	250	1.7	480	230	0.08	0.16	0.20	0.24	0.28	0.32	0.40	0.48	0.63	0.79




 $<sup>\</sup>ast$  Insert size (d): Please refer page E16 applicable insert drawing.

### **FMR P-positive**

### Maximum hole diameter table for helical machining (ØDHmax)



- ØD = Tool dia. (mm)
- Ød (Tool path, mm) = ØDHmin, Max ØD
- ØDHmin (Minimum hole diameter) =  $\emptyset$ D × 2 Insert size (d)
- ØDHmax (Maximum hole diameter) =  $\emptyset$ D × 2 2
- Ramping angle by ap  $(\alpha^{\circ}) = tan^{-1} \left( \frac{ap}{\pi \times \emptyset d} \right)$ Helical angle adjusted by ap cannot exceed maximum angle
- ap = Depth of cut




(mm)


	Insert	Tool dia.	Ramping						Ram	ping ang	jle (α°) l	by ap			(11111)
Section	size (d)	(ØD)	angle a°(max)	ØDHmax	Ød	ap = 1	ap = 2	ap = 2.5	ap = 3	ap = 3.5	ap = 4	ap = 5	ap = 6	ap = 8	ap = 10
	8	17	4.7	32	15	1.22	2.43	3.04	3.65	-	-	-	-	-	-
	8	18	4.1	34	16	1.14	2.28	2.85	3.43	-	-	-	-	-	-
FMR2500	8	20	15.4	38	18	1.01	2.03	2.54	3.04	3.55	4.06	-	-	-	-
FININ2500	8	21	13.9	40	19	0.96	1.92	2.40	2.88	3.37	3.85	-	-	-	-
	8	25	9.8	48	23	0.79	1.59	1.98	2.38	2.78	3.18	-	-	-	-
	8	26	9.2	50	24	0.76	1.52	1.90	2.28	2.66	3.04	-	-	-	-
	10	25	13.8	48	23	0.79	1.59	1.98	2.38	2.78	3.18	-	-	-	-
	10	26	12.6	50	24	0.76	1.52	1.90	2.28	2.66	3.04	-	-	-	-
	10	32	8.4	62	30	0.61	1.22	1.52	1.83	2.13	2.43	-	-	-	-
FMR3000	10	33	8.0	64	31	0.59	1.18	1.47	1.77	2.06	2.36	-	-	-	-
FININGUUU	10	40	5.8	78	38	0.48	0.96	1.20	1.44	1.68	1.92	-	-	-	-
	10	50	4.2	98	48	0.38	0.76	0.95	1.14	1.33	1.52	-	-	-	-
	10	63	3.1	124	61	0.30	0.60	0.75	0.90	1.05	1.20	-	-	-	-
	10	66	2.9	130	64	0.29	0.57	0.71	0.86	1.00	1.14	-	-	-	-
	12	25	4.5	48	23	0.79	1.59	1.98	2.38	2.78	3.18	-	-	-	-
	12	26	4.1	50	24	0.76	1.52	1.90	2.28	2.66	3.04	-	-	-	-
	12	32	14.7	62	30	0.61	1.22	1.52	1.83	2.13	2.43	3.04	3.65	-	-
	12	33	13.8	64	31	0.59	1.18	1.47	1.77	2.06	2.36	2.95	3.54	-	-
FMR4000	12	40	9.6	78	38	0.48	0.96	1.20	1.44	1.68	1.92	2.40	2.88	-	-
1 101114000	12	50	6.7	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	2.28	-	-
	12	63	4.8	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	1.80	-	-
	12	66	4.5	130	64	0.29	0.57	0.71	0.86	1.00	1.14	1.43	1.71	-	-
	12	80	3.5	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	1.40	-	-
	12	100	2.6	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	1.12	-	-
	16	40	17.8	78	38	0.48	0.96	1.20	1.44	1.68	1.92	2.40	2.88	3.85	-
	16	50	11.3	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	2.28	3.04	-
	16	63	7.6	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	1.80	2.39	-
FMR5000	16	66	7.1	130	64	0.29	0.57	0.71	0.86	1.00	1.14	1.43	1.71	2.28	-
1 10113000	16	80	5.3	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	1.40	1.87	-
	16	100	4.0	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	1.12	1.49	-
	16	125	3.0	248	123	0.15	0.30	0.37	0.45	0.52	0.59	0.74	0.89	1.19	-
	16	160	2.2	318	158	0.12	0.23	0.29	0.35	0.40	0.46	0.58	0.69	0.92	-
	20	50	17.8	98	48	0.38	0.76	0.95	1.14	1.33	1.52	1.90	2.28	3.04	3.81
	20	63	11.1	124	61	0.30	0.60	0.75	0.90	1.05	1.20	1.50	1.80	2.39	2.99
	20	80	7.4	158	78	0.23	0.47	0.58	0.70	0.82	0.94	1.17	1.40	1.87	2.34
FMR6000	20	100	5.3	198	98	0.19	0.37	0.47	0.56	0.65	0.74	0.93	1.12	1.49	1.86
. 1911 10000	20	125	4.0	248	123	0.15	0.30	0.37	0.45	0.52	0.59	0.74	0.89	1.19	1.48
	20	160	2.9	318	158	0.12	0.23	0.29	0.35	0.40	0.46	0.58	0.69	0.92	1.16
	20	200	2.2	398	198	0.09	0.18	0.23	0.28	0.32	0.37	0.46	0.55	0.74	0.92
	20	250	1.7	498	248	0.07	0.15	0.18	0.22	0.26	0.29	0.37	0.44	0.59	0.74



# FMAC(M)3000













• AR: 21° • RR: -17°~-12°

(mm)

De	esignation	0	ØD	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg	Fig.
FMACM	3050HR	4	50	42	22	10.4	6.3	20	40	11	17.5	4.0	0.4	1
	3050HR-H	6	50	42	22	10.4	6.3	20	40	11	17.5	4.0	0.4	1
	3063HR	5	63	49	22	10.4	6.3	20	40	11	17.5	4.0	0.5	1
	3063HR-H	8	63	49	22	10.4	6.3	20	40	11	17.5	4.0	0.6	1
FMAC	3080HR	6	80	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (23)	50	14	20	4.0	1.1	1
(FMACM)	3080HR-H	10	80	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (23)	50	14	20	4.0	1.2	1
	3100HR	7	100	67	31.75 (32)	12.7 (14.4)	8 (8)	35 (25.5)	50	(18)	45( 26)	4.0	1.7	2 (1)
	3100HR-H	12	100	67	31.75 (32)	12.7 (14.4)	8 (8)	35 (25.5)	50	(18)	45 (26)	4.0	1.7	2 (1)
	3125HR	8	125	87	38.1 (40)	15.9 (16.4)	10 (9)	42 (29)	63	(22)	55 (32)	4.0	3.3 (3.5)	2 (1)
	3125HR-H	14	125	87	38.1 (40)	15.9 (16.4)	10 (9)	42 (29)	63	(22)	55 (32)	4.0	3.3 (3.5)	2 (1)

### Available inserts

( )Metric size

	SEE I-MF	SEE I-I	VIIVI		SEE	I-IVIA	١	S	EXT-I	MF		SEX	I-MIN	/1	S	EXT-	MR		SI	=EW	
		6			0	9	•		0				3			6		)			
		Cei	rmet						C	coate	d							Unc	oated		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	H05	page
SEET	0903AGFN-MA																		•	•	
	0903AGSN-MF											•	•		•	•					
	0903AGSN-MM				•							•			•	•					E21
SEXT	0903AGSN-MF											•			•	•					
	0903AGSN-MM										•	•			•	•					E22
	0903AGSN-MR																				
SEEW	0903AGTN																				


### Available arbors


	Designation	Ød	NC arbors
FMACM	3050HR-□ 3063HR-□	22	BT□□-FMC22-□□
FMAC	3080HR-□	25.4	BT□□-FMA25.4-□□
(FMACM)	JUOUTIN-	27	BT□□-FMC27-□□
	3100HR-	31.75	BT□□-FMA31.75-□□
	3100HH-	32	BT□□-FMC32-□□
	3125HR-□	38.1	BT□□-FMA38.1-□□
3	3123NN-	40	BT□□-FMB/FMC40-□□


		Specification
Insert wrench		
07 TW09S	FTKA0307 TW09S	Ø50~Ø125

### **FMAC(M)4000**















• AR: 21° • RR: -17°~-12°

De	esignation	0	ØD	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg	Fig.
FMACM	4050HR	3	50	42	22	10.4	6.3	20	40	11	18	6.5	0.4	1
	4063HR	4	63	49	22	10.4	6.3	20	40	11	18	6.5	0.6	1
	4063HR-M	5	63	49	22	10.4	6.3	20	40	11	18	6.5	0.6	1
	4063HR-H	6	63	49	22	10.4	6.3	20	40	11	18	6.5	0.6	1
FMAC	4080HR	5	80	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (23)	50	14	20	6.5	1.1	1
(FMACM)	4080HR-M	6	80	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (23)	50	14	20	6.5	1.1	1
	4080HR-H	8	80	57	25.4 (27)	9.5 (12.4)	6 (7)	25 (23)	50	14	20	6.5	1.1	1
	4100HR	5	100	67	31.75 (32)	12.7 (14.4)	8 (8)	33 (25)	63 (50)	18	26	6.5	2 (1.6)	1
	4100HR-M	7	100	67	31.75 (32)	12.7 (14.4)	8 (8)	33 (25)	63 (50)	18	26	6.5	2 (1.6)	1
	4100HR-H	10	100	67	31.75 (32)	12.7 (14.4)	8 (8)	33 (25)	63 (50)	18	26	6.5	2 (1.6)	1
	4125HR	6	125	87	38.1 (40)	15.9 (16.4)	10 (9)	35 (29)	63	22	32	6.5	3.1	1
	4125HR-M	8	125	87	38.1 (40)	15.9 (16.4)	10 (9)	35 (29)	63	22	32	6.5	3.1	1
	4125HR-H	12	125	87	38.1 (40)	15.9 (16.4)	10 (9)	35 (29)	63	22	32	6.5	3.1	1
	4160R	7	160	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (35)	63	-	-	6.5	4.8	2
	4160R-M	10	160	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (35)	63	-	-	6.5	4.8	2
	4160R-H	16	160	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (35)	63	-	-	6.5	4.8	2
	4200R	8	200	130	47.625 (60)	25.4 (25.7)	14	38 (32)	63	-	-	6.5	6.1	3

### Available inserts SEET-MF

4200R-M

4200R-H

3 ( )Metric size

3

6.1

6.1





SEET-MM

12

18



SEET-MA

200

200

130

130



SEXT-MF

47.625 (60)

47.625 (60) 25.4 (25.7)



25.4 (25.7)



SEXT-MR

38 (32)

38 (32)

63

63

14

14

SEXT-MM



SEEW



SEEW-W

6.5

6.5

		Cermet			С	oate	ed				Uncoated				Cerme	t		(	Coate	ed			Uncoated	
	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC6510	PC9530	PC5300	PC5400 PD2000	PD1010	를 일 일	page		Designation	CN2500	NC5330	NCM325 NCM335 NCM535	NCM545	PC2505 PC2010	PC3700 PC6510	PC9530	PC5400	192 192 192 193 193 193 193 193 193 193 193 193 193	page
SEET	14M4AGFN-MA								•	•	• •		SEXT	14M4AGSN-MR							•	•		
	14M4AGSN-MF			•		•	•	•	•			E21	SEEW	14M4AGTN	•									E21
	14M4AGSN-MM			•	•	•	•	•	•					14M4AGFN-W										
SEXT	14M4AGSN-MF							•	•			E22		14M4AGSN-W								•		E22
	14M4AGSN-MM		•		•	•	•	•	•					14M4AGTN-W						•				

### Available arbors

Desig	nation	Ød	NC arbors
FMACM	4050HR- 4063HR-	22	BT -FMC22-
FMAC	4080HR-	25.4	BT□□-FMA25.4-□□
(FMACM)	4000NN-	27	BT□□-FMC27-□□
	4100HR-	31.75	BT□□-FMA31.75-□□
	4100NK-	32	BT -FMC32-


	Desigr	nation	Ød	NC arbors
F	FMAC	4125HR-	38.1	BT□□-FMA38.1-□□
(	(FMACM)	4123NN-	40	BT□□-FMB40-□□
		4160R-	50.8 BT -FMA50.8-	BT□□-FMA50.8-□□
		4100h	40	BT FMB/FMC40-
		4200R-	47.625	BT□□-FMA47.625-□□
		4200H	60	BT -FMB60-


Specification	611				
	Screw	Shim	Shim screw	Insert wrench	Shim wrench
Ø50~Ø200	FTGA03512	SS42SAF	SHXN0509F	TW15S	HW35L

# FMAC(M)3000-A

### **Aluminum body**











(mm)

De	signation	0	ØD	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg	Fig.
FMACM	3063R-A	3	63	49	22	10.4	6.3	20	40	11	18	4	0.5	1
FMAC	3080R-A	4	80	57	25.4 (27)	9.5 (12.4)	6 (7)	25	50	13.5	20	4	0.6	1
(FMACM)	3100R-A	5	100	67	31.75 (32)	12.7 (14.4)	8 (8)	32	50	-	45	4	0.8	2
	3100R-25.4-A	5	100	67	25.4	9.5	6	25	50	-	38	4	0.9	2
	3125R-A	6	125	87	38.1 (40)	15.9 (16.4)	10 (9)	38	63	-	56	4	1.6	2
	3125R-25.4-A	6	125	70	25.4	9.5	6	25	63	-	38	4	1.7	2

( )Metric size

### Available inserts

	SEET-MF	SEET	Г-ММ		SE	ET-MA	١	5	SEXT-I	ИF		SEXT	Г-ММ		SE	XT-MF	₹		SEEV	V	
	•	•		)		0	>		9			(	9	)		9			6		
		Cer	met						(	Coate	d							Unco	oated		
Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	Н05	page
SEET	0903AGFN-MA																		•	•	
	0903AGSN-MF											•	•		•	•					
	0903AGSN-MM				•							•			•	•					F04
SEXT	0903AGSN-MF											•			•	•					E21
	0903AGSN-MM										•	•			•	•					E22
	0903AGSN-MR																				
SEEW	0903AGTN																				

### Available arbors


I	Designation	Ød	NC arbors
FMACM	3063R-□	22	BT□□-FMC22-□□
FMAC	3080R-□	25.4	BT□□-FMA25.4-□□
(FMACM)	3000H-	27	BT□□-FMC27-□□
	3100R-	31.75	BT□□-FMA31.75-□□
	3100n	32	BT□□-FMC32-□□
	3125R-□	38.1	BT□□-FMA38.1-□□
	3123N	40	BT□□-FMB40-□□

Specification						
	Screw	Insert wrench	Locator wrench	Locator	Locator screw	
Ø63~Ø125	FTKA0307	TW09S	HW30L	LFMA3R-A	DHA0620	

# FMAC(M)4000-A

### **Aluminum body**









• AR: 21° • RR: -16°~-12°

(mm)

De	signation	0	ØD	ØD2	Ød	а	b	E	F	Ød1	Ød2	ар	kg	Fig.
FMACM	4063R-A	3	63	49	22	10.4	6.3	20	50	11	18	6.5	0.6	1
FMAC	4080R-A	4	80	67	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	13.5	20	6.5	0.8	1
(FMACM)	4100R-A	5	100	67	31.75 (32)	12.7 (14.4)	8 (8)	32	50	-	45	6.5	1.1	2
	4100R-25.4-A	5	100	67	25.4	9.5	6	25	50	-	38	6.5	1.2	2
	4125R-A	6	125	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (35)	63	-	56	6.5	1.7	2
	4125R-25.4-A	6	125	70	25.4	9.5	6	25	63	-	38	6.5	1.8	2
	4160R-A	7	160	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (35)	63	-	75	6.5	2.5	2
	4200R-A	8	200	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (32)	63	-	-	6.5	3.2	3
	4250R-A	10	250	180	47.625 (60)	25.4 (25.7)	14 (14)	38	63	-	-	6.5	4.1	3
	4315R-A	12	315	240	47.625 (60)	25.4 (25.7)	14 (14)	38	63	-	-	6.5	6.7	4

Note) Through coolant type between Ø50~Ø125

( )Metric size

### Available inserts

SEET-MF	SEET-MM	SEET-MA	SEXT-MF	SEXT-MM SEX	Γ-MR	SEEW	SEEW-W
	9	6		•		•	
Designation	N2500 N30 C5330 CM325	COAted COA535 COS540 CO	102 D D D D D D D D D D D D D D D D D D D	Designation	ZZ	CC5330 CM325 CM335 CM535 CM545 C2505 C2501 C3700	P C C 5 2 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
SEET 14M4AGFN-MA	OOZZ	2224444		SEXT 14M4AGSN-MR	00	2222244	
14M4AGSN-MF		• • • •		SEEW 14M4AGTN	•		
14M4AGSN-MM		• • • • •		14M4AGFN-W			E21
SEXT 14M4AGSN-MF		• • •	E22	14M4AGSN-W			• E22
14M4AGSN-MM	•	• • • • •		14M4AGTN-W			•

### Available arbors

Desig	gnation	Ød	NC arbors
FMACM	4063R-	22	BT□□-FMC22-□□
FMAC	4080R-	25.4	BT□□-FMA25.4-□□
(FMACM)	4000n	27	BT□□-FMC27-□□
,	4100HR-	31.75	BT□□-FMA31.75-□□
	4100NN-	32	BT□□-FMC32-□□
	4125R-	38.1	BT -FMA38.1-


Des	ignation	Ød	NC arbors
FMAC	4125R-	40	BT□□-FMB40-□□
(FMACM)	4160R-	50.8	BT□□-FMA50.8-□□
	4100N	40	BT□□-FMB/FMC40-□□
	4200R-	47.625	BT□□-FMA47.625-□□
	4250R-	60	BT□□-FMB60-□□
	4315R-	60	BT□□-FMB60-□□

Specification	Screw	Insert wrench	Locator wrench	Locator	Locator screw
Ø63~Ø315	FTGA03510	TW15S	HW40L	LFMA4R-A	DHA0830



## **FMAS3000**











• AR: 23° • RR: -17°~-13°

(mm)

	Designation	<b>(</b>	ØD	Ød	Q	L	ар	O kg
FMAS	3025HR	2	25	25	35	115	4	0.4
	3032HR	3	32	25	40	125	4	0.5
	3032HR-S32	3	32	32	40	130	4	0.8
	3040HR	3	40	32	40	130	4	0.9
	3040HR-S40	3	40	40	40	140	4	1.3
	3040HR-S42	3	40	42	40	140	4	1.4
	3050HR	4	50	32	40	135	4	1
	3050HR-S40	4	50	40	40	140	4	1.3
	3050HR-S42	4	50	42	40	140	4	1.5
	3063HR	5	63	32	45	135	4	1.2
	3063HR-S40	5	63	40	45	145	4	1.6
	3063HR-S42	5	63	42	45	145	4	1.7


### Available inserts

	SEET-MF	SEE1	Г-ММ		SE	ET-MA	١	S	EXT-N	ИF		SEXT	-MM		SE	XT-MF	}		SEEV						
	•	•		0		0		)		0	>		C			¢		l					5		
		Cer	Cermet						C	Coate	d							Unco	oated						
	Designation		CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	H05	page				
SEET	0903AGFN-MA																		•	•					
	0903AGSN-MF											•	•		•	•									
	0903AGSN-MM				•							•			•	•					F04				
SEXT	0903AGSN-MF											•			•	•					E21 E22				
	0903AGSN-MM										•	•			•	•					E22				
	0903AGSN-MR																								
SEEW	0903AGTN																								

Specification	Screw	Insert wrench		
Ø25~Ø63	FTKA0307	TW09S		

### **FMAS4000**













(mm)

	Designation	©	ØD	Ød	Q	L	ар	O kg
FMAS	4050HR	3	50	32	45	135	6.5	1
	4050HR-S40	3	50	40	45	135	6.5	1.3
	4050HR-S42	3	50	42	45	135	6.5	1.45
	4063HR	4	63	32	45	135	6.5	1.2
	4063HR-S40	4	63	40	45	135	6.5	1.5
	4063HR-S42	4	63	42	45	135	6.5	1.6


### Available inserts


	SEET-MF SEET-	MM	5	SEET-N	MA		SEXT	Г-МЕ		SE	XT-MN	1	S	EXT-N	ΛR		SEI	EW		SE	EW-W
	•		Source !				C				3			6		•	-				
			rmet							Coa	ated							Uı	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD2000	PD1010	ST30A	亨	H05	page
SEET	14M4AGFN-MA															•	•		•	•	
	14M4AGSN-MF					•					•	•		•	•						
	14M4AGSN-MM					•				•	•	•		•	•						
SEXT	14M4AGSN-MF										•			•	•						
	14M4AGSN-MM				•					•	•	•		•	•						E21
	14M4AGSN-MR											•		•							E22
SEEW	14M4AGTN		•																		
	14M4AGFN-W																				
	14M4AGSN-W													•							
	14M4AGTN-W										•										

Specification					
	Screw	Shim	Shim screw	Insert wrench	Shim wrench
Ø50~Ø63	FTGA03512	SS42SAF	SHXN0509F	TW15S	HW35L

# FMPC(M)3000

















(mm)

Des	signation	0	ØD	ØD <sub>2</sub>	Ød	a	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg	Fig.
FMPCM	3050HS	5	50	40	22	10.4	6.3	20	40	11	18	7	0.3	1
	3063HS	6	63	40	22	10.4	6.3	20	40	11	18	7	0.5	1
FMPC	3080HS	7	80	55	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	14	20	7	1.0	1
(FMPCM)	3100HS	8	100	67	31.75 (32)	12.7 (14.4)	8 (8)	36 (26)	50	18	45 (26)	7	1.5	2 (1)

( )Metric size

### Available inserts


	SDET-MI	=	S	DET-N	ИМ		SDET	Г-МА		SD	XT-MF	;	S	DXT-N	ЛM		SDX	Т-МА					
	•	•		6		4			7					6					>				
		Cermet						C	Coated							Uncoated							
	Designation	_		CN2500 CN30 NC5330		NC5330	NC5330 NCM325		NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD2000	ST30A	G10	亨	Н05	page
SDET	09M402R-MA															•			•	•			
	09M405R-MF																						
	09M405R-MM																						
SDXT	09M405R-MF				•					•	•	•		•	•						E19		
	09M405L-MF																				E20		
	09M405R-MM				•	•				•	•	•		•	•								
	09M405L-MM										•												
	09M405R-MA																		•	•			

### Available arbors

I	Designation	Ød	NC arbors
FMPCM	3050HS 3063HS	22	BT□□-FMC22-□□
FMPC	3080HS	25.4	BT□□-FMA25.4-□□ BT□□-FMC27-□□
(FMPCM)	3100HS	27 31.75	BTFMC27
	310003	32	BT□□-FMC32-□□

Specification		
	Screw	Wrench
Ø50~Ø100	FTGA03508	TW15S








# FMPC(M)4000

















De	esignation	0	ØD	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg
FMPCM	4063HS	5	63	49	22	10.4	6.3	20 (20)	50 (50)	11	18	11	0.4
FMPC	4080HS	6	80	57	25.4 (27)	9.5( 12.4)	6 (7)	25 (23)	50 (50)	14	20	11	0.9
(FMPCM)	4100HS	7	100	67	31.75 (32)	12.7 (14.4)	8 (8)	33 (25)	63 (50)	18	26	11	1.9 (1.5)
	4125HS	8	125	87	38.1 (40)	15.9 (16.4)	10 (9)	35 (29)	63	22	32	11	3.1

( )Metric size

### Available inserts

	SDET-N	ЛF	S	DET-N	ИΜ		SDET	Г-МА		SD	XT-MF		S	DXT-I	ИΜ		SDX	T-MA			
	Ġ			Ġ		4			7					Ġ		•			•		
		Cei	rmet						(	Coate	d							Unco	ated		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD1010	ST30A	G10	H21	H05	page
SDET	130504R-MA															•			•	•	
	130508R-MF																				
	130508R-MM																				E19
SDXT	130508R-MF				•						•	•		•	•						E20

### Available arbors


130508R-MM 130508R-MA


	Designation	Ød	NC arbors
FMPCM	4063HS	22	BT□□-FMC22-□□
FMPC	400000	25.4	BT□□-FMA25.4-□□
(FMPCM)	4080HS	27	BT□□-FMC27-□□
	4100HS	31.75	BT□□-FMA31.75-□□
	410005	32	BT□□-FMC32-□□
	440540	38.1	BT□□-FMA38.1-□□
	4125HS	40	BT -FMB/FMC40-

Pa	rts

Specification		
	Screw	Wrench
Ø63~Ø125	FTNC04511	TW20S

**Assembling** 










# FMPC(M)3000-A

### **Aluminum body**













• AR: 10° • RR: -9°~-7.3°

(mm)

De	esignation	0	ØD	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg	Fig.
FMPCM	3063S-A	3	63	40	22	10.4	6.3	20	40	11.0	18	7	0.2	1
FMPC	3080S-A	4	80	55	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	13.5	20	7	0.4	1
(FMPCM)	3100S-A	5	100	67	31.75 (32)	12.7 (14.4)	8 (8)	32	50	-	45	7	0.6	2
	3100S-25.4-A	5	100	67	25.4	9.5	6	25	50	-	38	7	0.7	2

( )Metric size

### Available inserts

	SDET-MI	•	S	DET-N	ИΜ		SDE	Г-МА		SD	XT-MF		S	DXT-N	ИΜ		SDX	Г-МА				
	•					4			,	9			9		•	0		>				
		Cermet								Coate	d							Unc	oated			
	Designation			CN2500 CN30 NC5330		NCM325	NCM335 NCM535		NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD2000	ST30A	G10	된	H05	page
SDET	09M402R-MA															•			•	•		
	09M405R-MF																					
	09M405R-MM																					
SDXT	09M405R-MF				•					•	•	•		•	•						E19	
	09M405L-MF																				E20	
	09M405R-MM				•	•				•	•	•		•	•							
	09M405L-MM										•											
	09M405R-MA																		•	•		


### Available arbors

	Designation	Ød	NC arbors
<b>FMPCM</b>	3063S-□	22	BT□□-FMC22-□□
FMPC	3080\$-□	25.4	BT□□-FMA25.4-□□
(FMPCM)	30003	27	BT□□-FMC27-□□
	3100S-	31.75	BT□□-FMA31.75-□□
	31005	32	BT□□-FMC32-□□
	3100S-25.4-	25.4	BT□□-FMA25.4-□□

Specification	Screw	Insert wrench	Locator wrench	Locator	Locator screw	Chip cover	Chip cover screw
Ø63	FTGA03508	TW15S	HW30L	LFMP3R-A	DHA0624	CFMP3R14R1-A	PXMA0306
Ø80~Ø100	FTGA03508	TW15S	HW30L	LFMP3R-A	DHA0624	CFMP3R-A	PXMA0306

# FMPC(M)4000-A

### **Aluminum body**










• AR: 10° • RR: -9°~-7.3°

(mm)

De	esignation	0	ØD	ØD2	Ød	а	b	E	F	Ød1	Ød2	ар	kg	Fig.
FMPCM	4063S-A	3	63	49	22	10.4	6.3	20	50	11	18	11	0.6	1
FMPC	4080S-A	4	80	67	25.4 (27)	9.5 (12.4)	6 (7)	25 (22)	50	13.5	20	11	0.8	1
(FMPCM)	4100S-A	5	100	67	31.75 (32)	12.7 (14.4)	8(8)	32	50	-	45	11	1.1	2
	4100S-25.4-A	5	100	67	25.4	9.5	6	25	50	-	38	11	1.2	2
	4125S-A	6	125	87	38.1 (40)	15.9 (16.4)	10 (9)	38 (35)	63	-	56	11	1.7	2
	4125S-25.4-A	6	125	70	25.4	9.5	6	25	63	-	38	11	1.8	2
	4160S-A	8	160	107	50.8 (40)	19.0 (16.4)	11 (9)	38 (35)	63	-	75	11	2.5	2
	4200S-A	10	200	130	47.625 (60)	25.4 (25.7)	14 (14)	38 (32)	63	-	-	11	3.2	3
	4250S-A	12	250	180	47.625 (60)	25.4 (25.7)	14 (14)	38	63	-	-	11	4.1	3
	4315S-A	15	315	240	47.625 (60)	25.4 (25.7)	14 (14)	38	63	-	-	11	6.7	4

( )Metric size

### Available inserts



		Cer	met						C	Coate	d							Unco	ated		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD1010	ST30A	G10	된	H05	page
SDET	130504R-MA															•			•	•	
	130508R-MF																				
	130508R-MM																				E19
SDXT	130508R-MF				•						•	•		•	•						E20
	130508R-MM				•	•				•	•	•		•	•						
	130508R-MA																		•	•	

### Available arbors

De	signation	Ød	NC arbors
FMPCM	4063S-	22	BT□□-FMC22-□□
FMPC	4080S-	25.4	BT□□-FMA25.4-□□
(FMPCM)	40003-	27	BT□□-FMC27-□□
	4100S-	31.75	BT□□-FMA31.75-□□
	41005-	32	BT□□-FMC32-□□
	4100S-25.4-	25.4	BT□□-FMA25.4-□□


De	esignation	Ød	NC arbors
FMPC	4125S-	38.1	BT□□-FMA38.1-□□
(FMPCM)	41235-	40	BT□□-FMB40-□□
	4125S-25.4-	25.4	BT□□-FMA25.4-□□
	4160S-	50.8	BT□□-FMA38.1-□□
	41005-	40	BT□□-FMB/FMC40-□□
	4200S-	47.625	BT□□-FMA47.625-□□
	4250S-□	60	BT□□-FMB60-□□
	421EC -	60	DTCC EMPSO CC

Specification	Screw	Insert wrench	Locator wrench	Locator	Locator screw	Chip cover	Chip cover screw
Ø63~Ø80	FTNC04509	TW20S	HW40L	LFMP4R1-A	DHA0825	CFMP3R14R1-A	PXMA0306
Ø100~Ø315	FTNC04509	TW20S	HW40L	LFMP4R-A	DHA0830	CFMP4R-A	PXMA0306

Available inserts E19, E20

### **FMPS3000**















• AR: 10° • RR: -9°~-8°

(mm)

ı	Designation	<b>©</b>	ØD	Ød	Q	L	ар	kg
FMPS	3025HS	2	25	25	35	115	7	0.4
	3032HS	3	32	25	40	125	7	0.5
	3040HS	4	40	32	40	130	7	0.8
	3040HS-S40	4	40	40	45	140	7	1.2
	3040HS-S42	4	40	42	45	140	7	1.3
	3050HS	5	50	32	40	135	7	1
	3050HS-S40	5	50	40	40	140	7	1.3
	3050HS-S42	5	50	42	40	140	7	1.4
	3063HS	6	63	32	45	135	7	1.2
	3063HS-S40	6	63	40	45	145	7	1.6
	3063HS-S42	6	63	42	45	145	7	1.7


### Available inserts

	SDET-MF	=	S	DET-N	ИM		SDET	-МА		SD	XT-MF		S	DXT-N	ИM		SDX	Г-МА			
	Ġ			6		4			Ÿ										•		
		Cer	met						C	oate	d							Unc	oated		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD2000	ST30A	G10	된	H05	page
SDET	09M402R-MA															•			•	•	
	09M405R-MF																				
	09M405R-MM																				l
SDXT	09M405R-MF				•					•	•	•		•	•						E19
	09M405L-MF																				E20
	09M405R-MM				•	•				•	•	•		•	•						
	09M405L-MM										•										
	09M405R-MA																		•	•	l

### Parts


Specification		
	Screw	Wrench
Ø25~Ø63	FTGA03508	TW15S

Assembling



### **FMPS4000**















• AR: 10° • RR: -9°~-8°


D	Designation	©	ØD	Ød	Q	L	ар	kg
FMPS	4040HS	3	40	32	40	130	11	1
	4040HS-S40	3	40	40	40	140	11	1.3
	4040HS-S42	3	40	42	40	140	11	1.4
	4050HS	4	50	32	45	135	11	1.5
	4050HS-S40	4	50	40	45	145	11	1.7
	4050HS-S42	4	50	42	45	145	11	1.6
	4063HS	5	63	32	45	135	11	2.1
	4063HS-S40	5	63	40	45	145	11	2.4
	4063HS-S42	5	63	42	45	145	11	2.6


### Available inserts

	SDET-MI	SDET-MF			ЛM		SDET	Г-МА		SD	XT-MF		S	DXT-N	ИM		SDX	Г-МА			
	Cermet		S		1			Ÿ					Ŝ					•			
		Cer	met						C	Coate	d							Unco	oated		
	Designation		CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	PD1010	ST30A	G10	된	H05	page
SDET	130504R-MA															•			•	•	
	130508R-MF																				
	130508R-MM																				E19
SDXT	130508R-MF				•						•	•		•	•						E20
	130508R-MM				•	•				•	•	•		•	•						
	130508R-MA																		•	•	


Parts

Specification Wrench Ø40~Ø63 FTNC04511 TW20S Assembling

























(mm
-----

Des	ignation	0	ØD	øс	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg
FMRCM	3040HRD	3	40	30	36	16	8.4	5.6	18	40	9	14	5.0	0.2
	3040HRD-H	4	40	30	36	16	8.4	5.6	18	40	9	14	5.0	0.2
	3050HRD	4	50	40	42	22	10.4	6.3	20	40	11	16.5	5.0	0.3
	3050HRD-H	5	50	40	42	22	10.4	6.3	20	40	11	16.5	5.0	0.3
	3063HRD	5	63	53	49	22	10.4	6.3	20	50	11	16.5	5.0	0.64
	3063HRD-H	6	63	53	49	22	10.4	6.3	20	50	11	16.5	5.0	0.64
FMRC	3080HRD	6	80	70	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (22)	50 (50)	14	19	5.0	1.1
(FMRCM)	3080HRD-H	7	80	70	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (22)	50 (50)	14	19	5.0	1.1
	3100HRD	7	100	90	67	31.75 (32)	12.7 (14.4)	8 (8.0)	32 (28)	63 (63)	18	26	5.0	2.1
	3100HRD-H	8	100	90	67	31.75 (32)	12.7 (14.4)	8 (8.0)	32 (28)	63 (63)	18	26	5.0	2.1

Note) It's general that you measure of inner diameter when the diameter of FMRC/FMRCM is  $\emptyset 40 \sim \!\! \emptyset 63$ 

( )Metric size

### Available inserts

Tranable moone			
	RDKT-MF	RDKT-MM	RDCT-MA


		Cer	met	Coated Uncoated														
Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RDCT	10T3M0-MA																•	F16
RDKT	10T3M0-MF											•		•				E16
	10T3M0-MM				•					•	•	•		•				E17

### Available arbors

	Designation	Ød	NC arbors							
FMRCM	3040HRD	16	BT□□-FMC16-□□							
	3040HRD-H	10	BTFINICTO							
	3050HRD									
	3050HRD-H	22	BT□□-FMC22-□□							
	3063HRD	22	BTFIVIOZZ							
	3063HRD-H									
FMRC	3080HRD	25.4	BT□□-FMA/FMB25.4-□□							
(FMRCM)	3080HRD-H	27	BT□□-FMB/FMC27-□□							
	3100HRD	31.75	BT□□-FMA31.75-□□							
	3100HRD-H	32	BT□□-FMC32-□□							

Specification			
	Screw	Wrench	
Ø40~Ø100	FTGA03508	TW15S	



















• RR: -5°

														(mm)
Des	signation	0	ØD	ØС	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg
FMRCM	4050HRD	4	50	38	42	22	10.4	6.3	20	50	11	18	6.0	0.4
	4063HRD	4	63	51	49	22	10.4	6.3	20	50	11	18	6.0	0.6
	4063HRD-M	5	63	51	49	22	10.4	6.3	20	50	11	18	6.0	0.6
FMRC	4080HRD	5	80	68	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (23)	50 (50)	14	20	6.0	1.0
(FMRCM)	4080HRD-M	6	80	68	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (23)	50 (50)	14	20	6.0	1.0
	4100HRD	6	100	88	67	31.75 (32)	12.7 (14.4)	8 (8.0)	33 (25)	63 (50)	18	26	6.0	1.9 (1.5)
	4100HRD-M	7	100	88	67	31.75 (32)	12.7 (14.4)	8 (8.0)	33 (25)	63 (50)	18	26	6.0	1.9 (1.5)
4125HRD		7	125	113	87	38.1 (40)	15.9 (16.4)	10 (9.0)	35 (29)	63 (63)	22	32	6.0	3.0
	4125HRD-M	8	125	113	87	38.1 (40)	15.9 (16.4)	10 (9.0)	35 (29)	63 (63)	22	32	6.0	3.0

Note) It's general that you measure of inner diameter when the diameter of FMRC/FMRCM is  $\emptyset$ 50~ $\emptyset$ 63

( )Metric size

### Available inserts

Available inserts				
	RDKT-MF	RDKT-MM	RDCT-MA	

									Coa	ted						Unco	ated	
Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RDCT	1204M0-MA																•	F16
RDKT	1204M0-MF									•		•		•				E16 E17
	1204M0-MM				•					•	•	•		•				E17


### Available arbors

	Designation	Ød	NC arbors
FMRCM	4063HRD	00	BT□□-FMC22-□□
	4063HRD-M	22	BILLI-FMC22-LL
FMRC	4080HRD		
(FMRCM)	4080HRD	25.4	BT□□-FMA/FMB25.4-□□
	4080HRD-M	27	BT□□-FMB/FMC27-□□
	4100HRD	31.75	BT□□-FMA31.75-□□
	4100HRD-M	32	BT□□-FMC32-□□
4125HRD		38.1	BT□□-FMA/FMB38.1-□□
	4125HRD-M	40	BT□□-FMB/FMC40-□□

Specification		
	Screw	Wrench
Ø50~Ø125	FTKA0410	TW15S





















• AR: 5° • RR: -5°

	(mm)														
De	esignation	0	ØD	øс	ØD <sub>2</sub>	Ød	а	b	E	F	Ød <sub>1</sub>	Ød <sub>2</sub>	ар	kg	
FMRCM	5050HRD	3	50	34	42	22	10.4	6.3	20	50	11	16.5	8.0	0.4	
	5063HRD	4	63	47	49	22	10.4	6.3	20	50	11	18	8.0	0.6	
	5063HRD-H	5	63	47	49	22	10.4	6.3)	20	50	11	18	8.0	0.6	
FMRC	5080HRD	5	80	64	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (23)	50 (50)	14	20	8.0	0.9	
(FMRCM)	5080HRD-H	6	80	64	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (23)	50 (50)	14	20	8.0	0.9	
	5100HRD	6	100	84	67	31.75 (32)	12.7 (14.4)	8 (8)	33 (25)	63 (50)	18	26	8.0	1.9 (1.4)	
	5100HRD-H	7	100	84	67	31.75 (32)	12.7 (14.4)	8 (8)	33 (25)	63 (50)	18	26	8.0	1.9 (1.4)	
	5125HRD	7	125	109	87	38.1 (40)	15.9 (16.4)	10 (9)	35 (29)	63 (63)	22	32	8.0	3	
	5125HRD-H	8	125	109	87	38.1 (40)	15.9 (16.4)	10 (9)	35 (29)	63 (63)	22	32	8.0	3	

Note) It's general that you measure of inner diameter when the diameter of FMRC/FMRCM is  $\emptyset$ 50~ $\emptyset$ 63

( )Metric size

#### Available inserts

/ tranable intente					
	RDHW-E,F,S	RDKT-MF	RDKT-ML	RDKT-MM	


		Cer	met						Coa	ated						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
RDHW	1605M0E																	
	1605M0F																	
	1605M0S																	E16
RDKT	1605M0-MM									•								E17
	1605M0-MF																	
	1605M0-ML																	


### Available arbors


	Designation	Ød	NC arbors
FMRCM	5050HRD		
	5063HRD	22	BT□□-FMC22-□□
	5063HRD-H		
FMRC	5080HRD	25.4	BT□□-FMA/FMB25.4-□□
(FMRCM)	5080HRD-H	27	BT□□-FMB/FMC27-□□
	5100HRD	31.75	BT□□-FMA31.75-□□
	5100HRD-H	32	BT□□-FMC32-□□
	5125HRD	38.1	BT□□-FMA/FMB38.1-□□
	5125HRD-H	40	BT□□-FMB/FMC40-□□

Specification		
	Screw	Wrench
Ø50~Ø125 FT0	GA0513-P	TW20-100























(mm)

															(111111)
Des	signation	0	ØD	øс	ØD2	Ød	а	b	E	F	Ød1	Ød2	ар	kg	Fig.
FMRCM	6063HRD	3	63	43	49	22	10.4	6.3	20	50	11	17	10.0	0.5	1
	6063HRD-M	4	63	43	49	22	10.4	6.3	20	50	11	17	10.0	0.5	1
FMRC	6080HRD	4	80	60	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (22)	50	14	20	10.0	0.8	1
(FMRCM)	6080HRD-M	5	80	60	57	25.4 (27)	9.5 (12.4)	6 (7.0)	25 (22)	50	14	20	10.0	0.8	1
	6100HRD	5	100	80	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	63	18	26	10.0	1.6	1
	6100HRD-M	6	100	80	67	31.75 (32)	12.7 (14.4)	8 (8)	32 (28)	63	18	26	10.0	1.6	1
	6125HRD	6	125	105	87	38.1 (40)	15.9 (16.4)	10 (9)	41 (29)	63	- (22)	55 (32)	10.0	2.7 (2.9)	2 (1)
	6125HRD-M	7	125	105	87	38.1 (40)	15.9 (16.4)	10 (9)	41 (29)	63	- (22)	55 (32)	10.0	2.7 (2.9)	2 (1)
	6160RD	7	160	140	107	50.8 (40)	19 (16.4)	11 (9)	38 (35)	63	-	78	10.0	4.4	3
	6160RD-M	8	160	140	107	50.8 (40)	19 (16.4)	11 (9)	38 (35)	63	-	78	10.0	4.4	3

( )Metric size

### Available inserts

RDHW-E,F,S

RDKT-MM





		Cer	met						Coa	ted						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RDHW	2006M0E																	
	2006M0F																	E16
	2006M0S																	E17
RDKT	2006M0-MM									•								

### Available arbors


	Designation	Ød	NC arbors
FMRCM	6063HRD	00	DTCC FMOOD CC
	6063HRD-M	22	BT□□-FMC22-□□
FMRC	6080HRD	25.4	BT□□-FMA/FMB25.4-□□
(FMRCM)	6080HRD-M	27	BT□□-FMB/FMC27-□□
	6100HRD	31.75	BT□□-FMA31.75-□□
	6100HRD-M	32	BT□□-FMC32-□□
	6125HRD	38.1	BT□□-FMA/FMB38.1-□□
	6125HRD-M	40	BT□□-FMB/FMC40-□□
	6160RD	50.8	BT□□-FMA50.8-□□
	6160RD-M	40	BT□□-FMB/FMC40-□□

Specification		
	Screw	Wrench
Ø63~Ø160	FTGA0515-P	TW20-100





### FMRS1000/1500





					' HH: -5°~-1°					(mm)
	Designation	(i)	ØD	ØC	Ød	Q	L	ар	kg	Fig.
FMRS	1008HRD-M	1	8	5.5	10	30	80	2.5	0.2	1
	1008HRD-L	1	8	5.5	10	50	100	2.5	0.2	1
	1010HRD-M	1	10	5	12	44	100	2.5	0.2	1
	1010HRD-L	1	10	5	12	64	120	2.5	0.2	1
	1012HRD-M	2	12	7	12	44	100	2.5	0.3	1
	1012HRD-L	2	12	7	16	80	160	2.5	0.3	1
	1015HRD-M	3	15	10	16	80	160	2.5	0.3	1
	1015HRD-L	3	15	10	16	100	200	2.5	0.4	1
<b>FMRS</b>	1510HRD-M	1	10	6	12	44	100	3.0	0.2	1
	1510HRD-L	1	10	6	12	64	120	3.0	0.2	1
	1512HRD-M	2	12	6	12	54	110	3.0	0.3	1
	1512HRD-L	2	12	6	16	80	160	3.0	0.3	1
	1516HRD-M	3	16	10	16	60	130	3.0	0.3	1
	1516HRD-L	3	16	10	20	90	180	3.0	0.4	1
	1520HRD-M	3	20	14	20	80	150	3.0	0.4	1
	1520HRD-L	3	20	14	20	90	200	3.0	0.5	1


### Available inserts

	anable miserts												
				RDH	IW-E,F	;s	RDKV	٧					
				0									
		Cer	met				Coa	ated				Uncoated	
<b>T</b>	Danie de la constante de la co			Ŋ	Ŋ	ιĊ	 _			_			

			Cer	met						Coa	ited						Unco	ated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
	RDHW	0501M0E											•						
1000		0501M0F																	
type		0501M0S																	
	RDKW	0501M0E									•								E16
	RDHW	06T1M0E											•						E17
1500		06T1M0F																	
type		06T1M0S																	
	RDKW	06T1M0E									•								

Specification		S	
Ø8~Ø15 (1000 type)	Screw FTNA0203	Wrench TW06P	
Ø10~Ø20 (1500 type)	FTNA02205	TW06P	

### FMRS2000/2500





										(mm
I	Designation	0	ØD	ØC	Ød	Q	L	ар	kg	Fig.
FMRS	2015HRD-S	2	15	8	16	55	115	3.5	0.3	2
	2015HRD-M	2	15	8	20	80	150	3.5	0.4	1
	2015HRD-L	2	15	8	20	90	200	3.5	0.5	1
	2020HRD-S	3	20	14	20	65	125	3.5	0.3	2
	2020HRD-M	3	20	14	20	80	150	3.5	0.4	1
	2020HRD-L	3	20	14	25	90	200	3.5	0.5	1
FMRS	2516HRD-S	2	16	8	16	65	125	4.0	0.3	2
	2516HRD-M	2	16	8	16	80	150	4.0	0.4	1
	2516HRD-L	2	16	8	20	90	200	4.0	0.5	1
	2520HRD-S	2	20	12	20	65	125	4.0	0.4	2
	2520HRD-M	2	20	12	20	80	150	4.0	0.5	1
	2520HRD-L	2	20	12	25	90	200	4.0	0.6	1
	2525HRD-S	3	25	17	25	55	125	4.0	0.5	2
	2525HRD-M	3	25	17	25	90	200	4.0	0.6	1
	2525HRD-L	3	25	17	32	110	250	4.0	0.7	1

### Available inserts

0803M0F

0803M0S

0803M0E


						RDH	W-E,F	;s		RDKV	V								
						0													
			Cer	met						Coa	ated						Unco	ated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
	RDHW	0702M0E											•						
2000		0702M0F																	
type		0702M0S																	
	RDKW	0702M0E									•								E16
	RDHW	0803M0E											•						E17


### Parts

2500 type

RDKW





















• RR: -8°~-5°

										(mm
	Designation	<b>(</b>	ØD	ØC	Ød	Q	L	ар	kg	Fig.
FMRS	3021HRD-M	1	21	11	20	40	150	5	0.4	1
	3021HRD-M2	2	21	11	20	40	150	5	0.4	1
	3021HRD-L	1	21	11	20	50	200	5	0.6	1
	3021HRD-L2	2	21	11	20	50	200	5	0.6	1
	3025HRD-S	2	25	15	25	35	115	5	0.5	2
	3025HRD-M	2	25	15	25	70	200	5	0.7	1
	3025HRD-L	2	25	15	25	100	250	5	1	1
	3026HRD-M	2	26	16	25	70	200	5	0.65	1
	3026HRD-L	2	26	16	25	100	250	5	0.7	1
	3032HRD-S	3	32	22	32	40	125	5	1	2
	3032HRD-M	3	32	22	32	70	200	5	1.3	1
	3032HRD-L	3	32	22	32	150	300	5	1.6	1
	3040HRD-S	4	40	30	32	40	125	5	1.3	2
	3040HRD-M	4	40	30	32	70	200	5	1.5	1
	3040HRD-L	4	40	30	32	150	300	5	1.8	1


#### Available inserts


2 Available intente				
	RDKT-MF	RDKT-MM	RDCT-MA	

		Cer	met						Coa	ited						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
RDCT	10T3M0-MA																•	F40
RDKT	10T3M0-MF											•		•				E16 E17
	10T3M0-MM				•					•	•	•		•				L17

Specification	Screw	Wrench
<u>Ø21</u> <u>Ø25~Ø40</u>	FTGA03507 FTGA03508	TW15S























(mm)

										(111111)
	Designation	<b>(</b>	ØD	ØС	Ød	Q	L	ар	kg	Fig.
FMRS	4032HRD-S	2	32	20	32	40	125	6	0.8	2
	4032HRD-M	2	32	20	32	70	200	6	1.1	1
	4032HRD-L	2	32	20	32	150	300	6	1.6	1
	4033HRD-S	2	33	21	32	40	125	6	0.9	2
	4033HRD-M	2	33	21	32	70	200	6	1.1	1
	4033HRD-L	2	33	21	32	150	300	6	1.7	1
	4040HRD-S	3	40	28	32	40	125	6	1	2
	4040HRD-M	3	40	28	32	70	200	6	1.6	1
	4040HRD-L	3	40	28	32	150	300	6	1.8	1
	4040HRD-S40	3	40	28	40	40	125	6	1.3	2
	4040HRD-M40	3	40	28	40	70	200	6	2	1
	4040HRD-L40	3	40	28	40	150	300	6	2.4	1
	4040HRD-S42	3	40	28	42	40	125	6	1.6	2
	4040HRD-M42	3	40	28	42	70	200	6	2.4	1
	4040HRD-L42	3	40	28	42	150	300	6	2.8	1
	4050HRD-S	4	50	38	42	50	125	6	1.5	2
	4050HRD-M	4	50	38	42	50	250	6	2.1	1
	4050HRD-L	4	50	38	42	50	300	6	2.7	1
	4050HRD-S40	4	50	38	40	50	150	6	2	2
	4050HRD-M40	4	50	38	40	50	250	6	2.6	1
	4050HRD-L40	4	50	38	40	50	300	6	3.2	1


### Available inserts



		Cer	met						Coa	ited						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
RDCT	1204M0-MA																•	F40
RDKT	1204M0-MF									•		•		•				E16 E17
	1204M0-MM				•					•	•	•		•				E1/

Specification		
	Screw	Wrench
Ø32~Ø50	FTKA0410	TW15S








					HH: -8°~-5°					(mm)
	Designation	<b>(</b>	ØD	øс	Ød	Q	L	ар	kg	Fig.
FMRS	5040HRD-S	2	40	24	32	40	125	8	1.4	2
	5040HRD-M	2	40	24	32	70	200	8	1.8	1
	5040HRD-L	2	40	24	32	150	300	8	2.0	1
	5040HRD-S40	2	40	24	40	40	125	8	1.6	2
	5040HRD-M40	2	40	24	40	70	200	8	2.0	1
	5040HRD-L40	2	40	24	40	150	300	8	2.4	1
	5040HRD-S42	2	40	24	42	40	125	8	2.0	2
	5040HRD-M42	2	40	24	42	70	200	8	2.4	1
	5040HRD-L42	2	40	24	42	150	300	8	2.8	1
	5050HRD-S40	3	50	34	40	50	150	8	2.0	2
	5050HRD-M40	3	50	34	40	50	250	8	2.4	1
	5050HRD-L40	3	50	34	40	50	300	8	2.6	1
	5050HRD-S	3	50	34	42	50	150	8	1.5	2
	5050HRD-M	3	50	34	42	50	250	8	1.8	1
	5050HRD-L	3	50	34	42	50	300	8	2.0	1
	5063HRD-S40	4	63	47	40	50	150	8	1.7	2
	5063HRD-M40	4	63	47	40	50	250	8	2.0	1
	5063HRD-L40	4	63	47	40	50	300	8	2.3	1
	5063HRD-S	4	63	47	42	50	150	8	1.6	2
	5063HRD-M	4	63	47	42	50	250	8	1.8	1
	5063HRD-L	4	63	47	42	50	300	8	2.0	1

### Available inserts

1605M0-MM 1605M0-ML

		F	RDHW-	E,F,S		RDK	T-MF		RI	DKT-M	L		RDKT-	-MM				
						6				9								
		Cei	rmet						Coa	ated						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RDHW	1605M0E																	
	1605M0F																	
	1605M0S																	E16
RDKT	1605M0-MF									•								E17

Specification	6)		
	Screw	Wrench	
Ø40~Ø63	FTGA0513-P	TW20-100	





					HH: -0'~-0'					(mm)
	Designation	©	ØD	ØС	Ød	Q	L	ар	kg	Fig.
FMRS	6050HRD-S40	3	50	31	40	50	150	10	1.3	2
	6050HRD-S42	3	50	31	42	50	150	10	1.4	2
	6050HRD-M40	3	50	31	40	50	250	10	2.2	1
	6050HRD-M42	3	50	31	42	50	250	10	2.4	1
	6050HRD-L40	3	50	31	40	50	300	10	2.7	1
	6050HRD-L42	3	50	31	42	50	300	10	3.0	1
	6063HRD-S40	4	63	44	40	50	150	10	1.5	2
	6063HRD-S42	4	63	44	42	50	150	10	1.6	2
	6063HRD-M40	4	63	44	40	50	250	10	2.5	1
	6063HRD-M42	4	63	44	42	50	250	10	2.7	1
	6063HRD-L40	4	63	44	40	50	300	10	3.0	1
	6063HRD-L42	4	63	44	42	50	300	10	3.2	1

Available inserts			
	RDHW-E,F,S	RDKT-MM	


			met						Coa	ited						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
RDHW	2006M0E																	
	2006M0F																	E16
	2006M0S																	E17
RDKT	2006M0-MM									•								

Specification		
	Screw	Wrench
Ø50~Ø63	FTGA0515-P	TW20-100
_		



### FMRM1000/1500



















(mm)

	Designation	<b>(</b>	ØD	øc	Ød	Ød1	Q	L	М	ар	(kg
<b>FMRM</b>	1008HRD-M06	1	8	5.5	9.5	6.5	25	40	M06	2.5	0.02
	1010HRD-M06	2	10	5	9.5	6.5	25	40	M06	2.5	0.02
	1012HRD-M06	2	12	7	11	6.5	25	40	M06	2.5	0.02
	1015HRD-M08	3	15	10	14.5	8.5	30	47	M08	2.5	0.04
<b>FMRM</b>	1510HRD-M06	1	10	7	9.5	6.5	25	40	M06	3.0	0.02
	1512HRD-M06	2	12	6	11	6.5	25	40	M06	3.0	0.02
	1516HRD-M08	3	16	10	14.5	8.5	30	47	M08	3.0	0.02
	1520HRD-M10	3	20	14	18	10.5	35	56	M10	3.0	0.07

### Available inserts

RDHW-E,F,S

RDKW





			Cer	met						Coa	ited						Unco	ated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
	RDHW	0501M0E											•						
1000		0501M0F																	
type		0501M0S																	
	RDKW	0501M0E									•								E16
	RDHW	06T1M0E											•						E17
1500		06T1M0F																	
type		06T1M0S																	
	RDKW	06T1M0E									•								

### Available adaptor

	Designation	Available adaptor
FMRM	1008HRD-M06	
	1010HRD-M06	MAT-M06
	1012HRD-M06	
	1015HRD-M08	MAT-M08
	1510HRD-M06	MAT-M06
	1512HRD-M06	IVIA I - IVIUO
	1515HRD-M08	MAT-M08
	1520HRD-M10	MAT-M10


Designation: FMRM1008HRD-M06 Modular head threading measure size (M06)

Adaptor spec.: MAT-M06-020-S10S Adaptor threading measure (M06)

Specification	Screw	Wrench	
Ø8~Ø15 (1000 type)	FTNA0203	TW06P	
Ø10~Ø20 (1500 type)	FTNA02205	TW06P	

### FMRM2000/2500



















(mm)

Ι	Designation	©	ØD	øc	Ød	Ød1	Q	L	М	ар	_ kg \
FMRM	2015HRD-M08	2	15	8	14.5	8.5	30	47	M08	3.5	0.04
	2020HRD-M10	3	20	13	18	10.5	35	56	M10	3.5	0.07
FMRM	2516HRD-M08	2	16	8	14.5	8.5	30	47	M08	4.0	0.04
	2520HRD-M10	2	20	12	18	10.5	35	56	M10	4.0	0.07
	2525HRD-M12	3	25	17	22.5	12.5	45	69	M12	4.0	0.13

### Available inserts

RDHW-E,F,S

RDKW





			Cer	met						Coa	ated						Unco	oated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
	RDHW	0702M0E											•						
2000		0702M0F																	
type		0702M0S																	
	RDKW	0702M0E									•								E16
	RDHW	0803M0E											•						E17
2500		0803M0F																	
type		0803M0S																	
	RDKW	0803M0E									•								

### Available adaptor

	Designation	Available adaptor
FMRM	2015HRD-M08	MAT-M08
	2020HRD-M10	MAT-M10
	2516HRD-M08	MAT-M08
	2520HRD-M10	MAT-M10
	2525HRD-M12	MAT-M12

Designation: FMRM2015HRD-M08 Modular head threading measure size (M08)


Adaptor spec.: MAT-M08-020-S16S Adaptor threading measure (M08)

Specification	Screw	Wrench	
Ø15~Ø20 (2000 type)	FTNA02555	TW07S	
Ø16~Ø25 (2500 type)	FTNA0305	TW09S	

<sup>→</sup> Available inserts E16, E17 → Available adaptor E401~E402

### **FMRM3000**



















(mm)

	Designation	0	ØD	øс	Ød	Ød <sub>1</sub>	Q	L	M	ар	(kg)
<b>FMRM</b>	3021HRD-M10	2	21	11	18	10.5	35	56	M10	5.0	0.1
	3025HRD-M12	2	25	15	22.5	12.5	45	69	M12	5.0	0.15
	3032HRD-M16	3	32	22	29	17	50	77	M16	5.0	0.2
	3042HRD-M16	4	42	32	29	17	50	77	M16	5.0	0.24

### Available inserts

		RDHV	V-E,F,S	3	RI	OCT-M	Α		RDKT	-MF		RDK	T-ML		RI	OKT-M	M		
		Cermet			0														
			Cer	met						Coa	ated						Unco	ated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	亨	page
RDCT	10T3M0-MA																	•	F40
RDKT	10T3M0-MF												•		•				E16
	10T3M0-MM					•					•	•	•		•				E17

### Available adaptor

	Designation	Available adaptor
FMRM	3021HRD-M10	MAT-M10
	3025HRD-M12	MAT-M12
	3032HRD-M16	MATAMO
	3042HRD-M16	MAT-M16


Designation : FMRM3021HRD-M10 Modular head threading measure size (M10)

Adaptor spec.: MAT-M10-030-S20S Adaptor threading measure (M10)

Specification	Screw	Wrench
<u>Ø21</u> Ø25∼Ø42	FTGA03507 FTGA03508	TW15S

### FMRM4000/5000



















(mm)

	Designation	©	ØD	ØС	Ød	Ød <sub>1</sub>	Q	L	М	ар	kg
<b>FMRM</b>	4025HRD-M12	2	25	13	22.5	12.5	45	69	M12	6.0	0.12
	4032HRD-M16	2	32	20	29	17	50	77	M16	6.0	0.22
	4040HRD-M16	3	40	28	29	17	50	77	M16	6.0	0.23
	4042HRD-M16	4	42	28	29	17	50	77	M16	6.0	0.25
FMRM	5040HRD-M16	2	40	24	29	17	50	77	M16	8.0	0.25

#### ♠ Available inserts

	anabic																		
		RDHW-E		RDCT-	·MA		RDK	CT-MF		RI	OKT-M	L		RDKT-	MM				
				C			6												
			Cei	rmet						Coa	ated						Unco	oated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
	RDCT	1204M0-MA																•	
4000 type	RDKT	1204M0-MF									•		•		•				
type		1204M0-MM				•					•	•	•		•				E40
	RDHW	1605M0-E																	E16

### Available adaptor

**RDKT** 

5000

1605M0-MF

1605M0-ML 1605M0-MM

	Designation	Available adaptor
FMRM	4025HRD-M12	MAT-M12
	4032HRD-M16	
	4040HRD-M16	MAT-M16
	4042HRD-M16	
	5040HRD-M16	MAT-M16

Designation: FMRM4025HRD-M12 Modular head threading measure size (M12)

E17


Adaptor spec.: MAT-M12-030-S25S Adaptor threading measure (M12)

Specification	Screw	Wrench	
Ø25~Ø42 (4000 type)	FTKA0410	TW15S	
Ø40 (5000 type)	FTGA0513-P	TW20-100	

# **E** FMR P-positive

# **FMRCM3000**





















															(111111)
De	esignation	(i)	ØD	ØС	ØD <sub>2</sub>	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	d <sub>3</sub>	а	b	E	F	ар	kg
FMRCM	3040HRP-5	5	40	30	38	16	9	14	-	8.4	5.6	19	40	5	0.22
	3050HRP-6	6	50	40	45	22	11	18	-	10.4	6.3	20	40	5	0.35
	3052HRP-6	6	52	42	45	22	11	18	-	10.4	6.3	20	40	5	0.37
	3063HRP-6	6	63	53	50	22	11	18	-	10.4	6.3	20	40	5	0.55
	3063HRP-7	7	63	53	50	22	11	18	-	10.4	6.3	20	40	5	0.56
	3066HRP-7	7	66	56	50	22	11	18	-	10.4	6.3	20	40	5	0.60

### Available inserts


	RPCT-MA RPET-ML I			RPMT-MF RPMT-MM						F	RPMW	'							
						ew	9		new		6	new	)						
			Cer	met						Coa	ated						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RPCT	10T3M0-MA																	•	
RPET	10T3M0E-ML														•	•			
RPMT	10T3M0E-MF														•	•			E17 E18
	10T3M0S-MM								•	•	•				•	•			E10
RPMW	10T3M0E1								•	•					•	•			

### Available arbors

	Designation	Ød	Available arbors
FMRCM	3040HRP-5	16	BT□□-FMC16-□□
	3050HRP-6		
	3052HRP-6		
	3063HRP-6	22	BT□□-FMC22-□□
	3063HRP-7		
	3066HRP-7		

# FMRC(M)4000 @



















															(mm)
De	esignation	0	ØD	øс	ØD <sub>2</sub>	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	Ød3	а	b	E	F	ар	kg
FMRCM	4050HRP-4	4	50	38	45	22	11	18	-	10.4	6.3	20	40	6	0.26
	4050HRP-5	5	50	38	45	22	11	18	-	10.4	6.3	20	40	6	0.28
	4052HRP-5	5	52	40	45	22	11	18	-	10.4	6.3	20	40	6	0.30
	4063HRP-5	5	63	51	50	22	11	18	-	10.4	6.3	20	40	6	0.44
	4063HRP-6	6	63	51	50	22	11	18	-	10.4	6.3	20	40	6	0.48
	4066HRP-6	6	66	54	50	22	11	18	-	10.4	6.3	20	40	6	0.50
FMRC	4080HRP-6	6	80	68	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	6	0.92
(FMRCM)	4080HRP-7	7	80	68	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	6	0.90
	4100HRP-7	7	100	88	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (25)	63 (53)	6	1.46

( )Metric size

### Available inserts



					Coated Uncoated													
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
RPCT	1204M0-MA																•	
RPET	1204M0E-ML													•	•			
RPMT	1204M0E-MF												•	•	•			E17
	1204M0S-MM							•	•	•			•	•	•			E18
RPMW	1204M0S1							•	•	•				•	•			
	1204M0S2													•	•			

### Available arbors

	Designation	Ød	Available arbors
FMRCM	4050HRP-4		
	4050HRP-5		
	4052HRP-5		PT TMC00
	4063HRP-5	22	BT□□-FMC22-□□
	4063HRP-6		
	4066HRP-6		
FMRC	4080HRP-6	25.4	BT□□-FMA25.4-□□
(FMRCM)	4000NNP-0	27	BT□□-FMC27-□□
` ,	4000UDD 7	25.4	BT□□-FMA25.4-□□
	4080HRP-7	27	BT□□-FMC27-□□
	4100HDD-7	31.75	BT□□-FMA31.75-□□
	4100HRP-7	32	BT□□-FMC32-□□


### Parts



243

# **E** FMR P-positive

# FMRC(M)5000 @



















(mm)

De	signation	0	ØD	øс	ØD <sub>2</sub>	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	Ød3	а	b	Е	F	ар	kg	Fig.
FMRCM	5063HRP-4	4	63	47	50	22	11	18	-	10.4	6.3	20	40	8	0.43	1
	5063HRP-5	5	63	47	50	22	11	18	-	10.4	6.3	20	40	8	0.44	1
	5066HRP-5	5	66	50	50	22	11	18	-	10.4	6.3	20	40	8	0.48	1
FMRC	5080HRP-5	5	80	64	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	8	0.77	1
(FMRCM)	5080HRP-6	6	80	64	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	8	0.82	1
,	5100HRP-6	6	100	84	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (25)	63 (55)	8	1.42	1
	5125HRP-7	7	125	109	87	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	35 (29)	68 (63)	8	2.78	1
	5125HRP-8	8	125	109	87	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	35 (29)	68 (63)	8	2.79	1
	5160RP-8	8	160	144	107	50.8 (40)	-	-	100	19 (16.4)	11 (9)	38 (32)	63	8	4.01	2(3)

( )Metric size

### Available inserts




					Coated Uncoated													
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	HOI	page
RPCT	1606M0-MA																•	
RPET	1606M0E-ML													•	•			E17
RPMT	1606M0E-MF													•	•			
	1606M0S-MM							•	•	•				•	•			E18
RPMW	1606M0S1							•	•					•	•			

### Available arbors

	Designation	Ød	Available arbors
FMRCM	5063HRP-4		
	5063HRP-5	22	BT□□-FMC22-□□
	5066HRP-5		
FMRC	5080HRP-5	25.4	BT□□-FMA25.4-□□
(FMRCM)	3000UHP-3	27	BT□□-FMC27-□□
,	5080HRP-6	25.4	BT□□-FMA25.4-□□
	3000HHF-0	27	BT□□-FMC27-□□
	5100HRP-6	31.75	BT□□-FMA31.75-□□
	3100HRP-0	32	BT□□-FMC32-□□
	5125HRP-7	38.1	BT□□-FMA38.1-□□
	3123NRP-1	40	BT□□-FMC40-□□
	E10EUDD 0	38.1	BT□□-FMA38.1-□□
	5125HRP-8	40	BT□□-FMC40-□□
	E160DD 0	50.8	BT□□-FMA50.8-□□
	5160RP-8	40	BT□□-FMC40-□□

Specification		Sour Sour	
	Screw	Wrench	
Ø63~Ø160	FTGA0512-P	TW20-100	

# FMRC(M)6000 @

















(mm)

																()
Des	signation	0	ØD	ØС	ØD <sub>2</sub>	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	Ød3	а	b	E	F	ар	kg	Fig.
FMRCM	6063HRP-4	4	63	43	50	22	11	18	-	10.4	6.3	20	40	10	0.37	1
FMRC	6080HRP-5	5	80	60	57	25.4 (27)	14	25	35	9.5 (12.4)	6 (7)	24 (23)	50	10	0.87	1
(FMRCM)	6100HRP-5	5	100	80	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (25)	63 (55)	10	1.31	1
	6100HRP-6	6	100	80	67	31.75 (32)	18	26	42	12.7 (14.4)	8 (8)	32 (25)	63 (55)	10	1.40	1
	6125HRP-5	5	125	105	87	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	35 (29)	68 (63)	10	2.77	1
	6125HRP-7	7	125	105	87	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	35 (29)	68 (63)	10	2.89	1
	6160RP-6	6	160	140	107	50.8 (40)	-	-	100	19 (16.4)	11 (9)	38 (32)	63	10	3.58	2 (3)
	6160RP-8	8	160	140	107	50.8 (40)	-	-	100	19 (16.4)	11 (9)	38 (32)	63	10	3.53	2 (3)
	6200RP-8	8	200	180	130	47.625 (60)	-	-	132	25.4 (25.7)	14 (14)	38	63	10	5.15	4
	6250RP-9	9	250	230	180	47.625 (60)	-	-	180	25.4 (25.7)	14 (14)	38	63	10	9.72	4

( )Metric size

### Available inserts



	Designation	CN2500	CN30	NC533(	NCM32	NCM53	NCM54	PC2508	PC251(	PC3700	PC651(	PC953(	PC954(	PC530(	PC5400	ST30A	된	page
RPCT	2007M0-MA																•	
RPET	2007M0E-ML													•	•			F47
RPMT	2007M0E-MF													•	•			E17 E18
	2007M0S-MM							•	•	•				•	•			E10
RPMW	2007M0S1							•	•					•	•			

### Available arbors

Des	ignation	Ød	NC arbors
FMRCM	6063HRP-4	22	BT -FMC22-
FMRC	6080HRP-5	25.4	BT□□-FMA25.4-□□
(FMRCM)	000UNNF-3	27	BT□□-FMC27-□□
	6100HRP-5	31.75	BT□□-FMA31.75-□□
	0100HHF-3	32	BT□□-FMC32-□□
	6100HRP-6	31.75	BT□□-FMA31.75-□□
	0100HHP-0	32	BT□□-FMC32-□□
	6125HRP-5	38.1	BT□□-FMA38.1-□□
	0123HRP-3	40	BT -FMC40-


Desi	gnation	Ød	NC arbors
FMRC	6125HRP-7	38.1	BT□□-FMA38.1-□□
(FMRCM)	0123HRP-1	40	BT□□-FMC40-□□
	6160RP-6	50.8	BT□□-FMA50.8-□□
	0100HP-0	40	BT□□-FMC40-□□
	6160RP-8	50.8	BT□□-FMA50.8-□□
	0100HP-0	40	BT□□-FMC40-□□
	6200RP-8	47.625	BT□□-FMA47.625-□□
	0200NP-0	60	BT□□-FMC60-□□
	6250RP-9	47.625	BT□□-FMA47.625-□□
	023UNF-9	60	BT□□-FMC60-□□

Wrench	Screw
TW25-100	FTKA0615-P

# **E** FMR P-positive

# FMRS2500 @W






















									(mm)
	Designation	<b>©</b>	ØD	ØC	Ød	Q	L	ар	kg
FMRS	2517HRP-2S16	2	17	9	16	35	90	4	0.11
	2517HRP-2M16	2	17	9	16	35	150	4	0.20
	2517HRP-2L16	2	17	9	16	35	200	4	0.27
	2518HRP-2M16	2	18	10	16	35	150	4	0.20
	2518HRP-2L16	2	18	10	16	35	200	4	0.28
	2520HRP-3S20	3	20	12	20	35	130	4	0.27
	2520HRP-3M20	3	20	12	20	100	180	4	0.36
	2520HRP-3L20	3	20	12	20	130	250	4	0.50
	2521HRP-3S20	3	21	13	20	35	130	4	0.28
	2521HRP-3M20	3	21	13	20	35	180	4	0.40
	2521HRP-3L20	3	21	13	20	35	250	4	0.55
	2525HRP-4S25	4	25	17	25	35	150	4	0.48
	2525HRP-4M25	4	25	17	25	60	180	4	0.60
	2525HRP-4L25	4	25	17	25	130	250	4	0.81
	2526HRP-4S25	4	26	18	25	35	150	4	0.48
	2526HRP-4L25	4	26	18	25	130	250	4	0.85

### Available inserts

			RPET-	ML		RPN	IT-MF		RF	РМТ-М	M		RPM	W				
					ew	0		new			new		5		ew			
		Cer	met						Coa	ated						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RPET	0803M0E-ML													•	•			
RPMT	0803M0E-MF													•	•			E17
	0803M0S-MM							•	•					•	•			E18
RPMW	0803M0E1							•	•					•	•			

Specification			
	Screw	Wrench	
<u>Ø17</u> Ø18~Ø26	FTNA0305 FTNA0306	TW09S	

# FMRS3000 @





					1111. 1					(mm)
	Designation	<b>(</b>	ØD	ØC	Ød	Q	L	ар	kg	Fig.
FMRS	3025HRP-2M20	2	25	15	20	40	170	5	0.40	2
	3025HRP-2S25	2	25	15	25	40	120	5	0.39	1
	3025HRP-2M25	2	25	15	25	60	160	5	0.52	2
	3025HRP-2L25	2	25	15	25	130	250	5	0.80	2
	3026HRP-2L25	2	26	16	25	30	200	5	0.69	2
	3032HRP-3S32	3	32	22	32	40	125	5	0.68	1
	3032HRP-3L32	3	32	22	32	60	200	5	1.08	2
	3032HRP-4S32	4	32	22	32	40	125	5	0.66	1
	3032HRP-4L25	4	32	22	25	60	200	5	0.74	2
	3033HRP-4S32	4	33	23	32	40	125	5	0.67	1
	3033HRP-4M32	4	33	23	32	60	180	5	1.00	2
	3033HRP-4L32	4	33	23	32	180	300	5	1.64	2

### Available inserts

		RPC	T-MA		R	PET-M	L		RPMT	-MF		RPN	IT-MM		-	RPMW	1		
				new			new		6		ew	0		new			nev		
			Cer	met						Coa	ated						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H0.1	page
RPCT	10T3M0-MA																	•	
RPET	10T3M0E-ML														•	•			E17
RPMT	10T3M0E-MF														•	•			
	10T3M0S-MM								•	•	•				•	•			E18
RPMW	10T3M0E1								•	•					•	•			


Specification		
	Screw	Wrench
Ø25~Ø26	FTGA03507	TW15S
Ø32~Ø33	FTGA03508	1W100




# **E** FMR P-positive

# FMRS4000 @





















• RR: -2°~ 0°

										(mı
1	Designation	$\odot$	ØD	ØС	Ød	Q	L	ар	kg	Fig.
FMRS	4025HRP-2S25	2	25	13	25	60	160	6	0.46	1
	4026HRP-2L25	2	26	14	25	60	200	6	0.48	2
	4032HRP-2L25	2	32	20	25	40	190	6	0.68	2
	4032HRP-2S32	2	32	20	32	50	125	6	0.64	1
	4032HRP-2L32	2	32	20	32	50	250	6	1.40	2
	4032HRP-3S32	3	32	20	32	50	125	6	0.64	1
	4032HRP-3M32	3	32	20	32	60	160	6	0.85	2
	4033HRP-3M32	3	33	21	32	60	200	6	1.01	2
	4033HRP-3L32	3	33	21	32	60	300	6	1.67	2
	4040HRP-3S32	3	40	28	32	35	105	6	0.60	1
	4040HRP-3M32	3	40	28	32	50	160	6	0.96	2
	4040HRP-4S32	4	40	28	32	35	105	6	0.60	1
	4040HRP-4M32	4	40	28	32	35	150	6	0.87	2
	4040HRP-4L32	4	40	28	32	35	250	6	1.46	2
	4050HRP-4M32	4	50	38	32	50	150	6	1.10	2
	4050HRP-4M40	4	50	38	40	50	150	6	1.44	2
	4050HRP-4M42	4	50	38	42	50	150	6	1.55	2


### Available inserts

- Available illectio																	
RP	CT-MA		RI	PET-M	IL		RPMT	-MF		RPM	IT-MM		F	RPMW			
3	0	new			nev		6		eW	0		new			new		
	Ce	rmet						Coa	ited						Unco	ated	
Designation	200		330	325	535	545	202	510	90	510	230	540	300	9	¥		page

		Cer	met						Coa	ited						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RPCT	1204M0-MA																•	
RPET	1204M0E-ML													•	•			
RPMT	1204M0E-MF												•	•	•			E17
	1204M0S-MM							•	•	•			•	•	•			E18
RPMW	1204M0S1							•	•	•				•	•			
	1204M0S2													•	•			

Specification		
	Screw	Wrench
Ø25~Ø26 Ø32~Ø50	FTKA0408 FTKA0410	TW15S

# FMRS5000/6000 (1997)





(mm)													
	Designation	<b>(a)</b>	ØD	ØC	Ød	Q	L	ар	kg	Fig.			
FMRS	5040HRP-2M32	2	40	24	32	50	160	8	0.92	2			
	5040HRP-2L32	2	40	24	32	50	250	8	1.45	2			
	5050HRP-3M40	3	50	34	40	50	160	8	1.48	2			
	5050HRP-3L40	3	50	34	40	50	300	8	2.86	2			
<b>FMRS</b>	6050HRP-3S32	3	50	30	32	50	160	10	1.06	1			
	6050HRP-3M32	3	50	30	32	50	200	10	1.30	2			
	6050HRP-3S40	3	50	30	40	50	125	10	1.45	1			
	6050HRP-3M40	3	50	30	40	50	200	10	1.85	2			


### Available inserts

		RPCT-MA		RPET-	ML		RPN	IT-MF		RF	PMT-M	M		RPM	W				
			•			eW	6		new			new		5		ew			
			Cer	met						Coa	ated						Unc	oated	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
	RPCT	1606M0-MA																•	
	RPET	1606M0E-ML													•	•			
5000 type	RPMT	1606M0E-MF													•	•			
type	1	1606M0S-MM							•	•	•				•	•			
	RPMW	1606M0S1							•	•					•	•			E17
	RPCT	2007M0-MA																•	E18
6000 type	RPET	2007M0E-ML													•	•			
	RPMT	2007M0E-MF													•	•			
		2007M0S-MM							•	•	•				•	•			
	RPMW	2007M0S1							•	•					•	•			

# **E** FMR P-positive

# FMRM2500 (mw)



















(mm)

С	Designation	<b>(a)</b>	ØD	ØС	Ød	Ød <sub>1</sub>	Q	L	M	ар	kg
FMRM	2517HRP-M08	2	17	9	14.5	8.5	25	42	M08	4	0.03
	2521HRP-M10	3	21	13	18	10.5	30	51	M10	4	0.06
	2526HRP-M12	4	26	18	23	12.5	35	59	M12	4	0.11
	2533HRP-M16	4	33	25	29	17	40	67	M16	4	0.22
	2540HRP-M16	5	40	32	29	17	40	67	M16	4	0.26

### Available inserts

		RPCT-MA			RPET-ML			RPMT-MF			RPMT-MM			RPMW				
					new (		new		new		)							
	Ce	rmet	et				Coated				Uncoa				ated			
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RPET	0803M0E-ML													•	•			
RPMT	0803M0E-MF													•	•			E17
	0803M0S-MM							•	•					•	•			E18
RPMW	0803M0E1							•	•					•	•			

### Available adaptor

	Designation	Available adaptor
FMRM	2517HRP-M08	MAT-M08
	2521HRP-M10	MAT-M10
	2526HRP-M12	MAT-M12
	2533HRP-M16	MAT M4C
	2540HRP-M16	MAT-M16


Designation : FMRM2517HRP-M08 Modular head threading measure size (M08)

Adaptor spec.: MAT-M08-020-S16S Adaptor threading measure (M08)

Specification	Screw	Wrench	
Ø17 Ø21~Ø40	FTNA0305 FTNA0306	TW09S	

### **FMRM3000** new







**FMRM** 



Designation



3026HRP-M12

3033HRP-M16

3035HRP-M16

3040HRP-M16

3042HRP-M16



(i)

2

3

3

3

3





ØС

16

23

25

30

32

ØD

26

33

35

40

42



29

29

17

17

40

40

(mm) L Ød  $\emptyset d_1$ Q M kg ар 23 12.5 35 59 M12 5 0.10 29 17 40 67 M16 5 0.20 29 17 40 67 M16 5 0.22

67

67

M16

M16

5

5

0.25

0.27

#### Available inserts

O AV																			
		RPC	RPCT-MA		RPET-ML				RPMT-MF				IT-MM		F	RPMW	1		
		new			new new				ew	new C					new				
			Cer	met						Coa	ated						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RPCT	10T3M0-MA																	•	
RPET	10T3M0E-ML														•	•			F47
RPMT	10T3M0E-MF														•	•			E17 E18
	10T3M0S-MM								•	•	•				•	•			E10

#### Available adaptor

10T3M0E1

	Designation	Available adaptor
FMRM	3026HRP-M12	MAT-M12
	3033HRP-M16	
	3035HRP-M16	NAT NAC
	3040HRP-M16	MAT-M16
	3042HRP-M16	

Designation: FMRM3026HRP-M12 Modular head threading measure size (M12)

Adaptor spec.: MAT-M12-030-S25S Adaptor threading measure (M12)

#### Parts


**RPMW** 



## **E** FMR P-positive

### FMRM4000 **(EV)**

















• AR: -4° • RR: 0°

											(mm)
	Designation	<b>(</b>	ØD	ØС	Ød	Ød <sub>1</sub>	Q	L	M	ар	kg
FMRM	4026HRP-M12	2	26	14	23	12.5	35	59	M12	6	0.10
	4033HRP-M16	3	33	21	29	17	40	67	M16	6	0.21
	4035HRP-M16	3	35	23	29	17	40	67	M16	6	0.21
	4040HRP-M16	4	40	28	29	17	40	67	M16	6	0.24
	4042HRP-M16	4	42	30	29	17	40	67	M16	6	0.25

#### Available inserts

		RPC	Т-МА	A RPET-ML			RPMT-MF RF			RPN	IT-MM		F	RPMW					
			3	new	ALIAN TO THE PARTY OF THE PARTY		nev		6		ew	0		new			new	)	
			Cer	met						Coa	ated						Unco	ated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
RPCT	1204M0-MA																	•	
RPET	1204M0E-ML														•	•			
RPMT	1204M0E-MF													•	•	•			E17
	1204M0S-MM								•	•	•			•	•	•			E18
RPMW	1204M0S1								•	•	•				•	•			
	1204M0S2														•	•			

#### Available adaptor

	Designation	Available adaptor
FMRM	4026HRP-M12	MAT-M12
	4033HRP-M16	
	4035HRP-M16	NAT NAC
	4040HRP-M16	MAT-M16
	4042HRP-M16	


Designation: FMRM4026HRP-M12 Modular head threading measure size (M12)

Adaptor spec.: MAT-M12-030-S25S Adaptor threading measure (M12)

Specification	Screw	Wrench	
Ø26 Ø33~Ø42	FTKA0408 FTKA0410	TW15S	

### FMRM5000 **@W**



















												(mm)
	Designation		<b>(</b>	ØD	ØС	Ød	Ød <sub>1</sub>	Q	L	M	ар	kg
FMRN	/ 5040HR	P-M16	2	40	24	29	17	40	67	M16	8	0.21
	5042HRF	P-M16	2	42	26	29	17	40	67	M16	8	0.23

#### Available inserts

		RPC	RPCT-MA RPET-ML			RPMT-MF RPMT-MM			F	RPMW	1								
				new			new		6		eW	6		new			nev	9	
			Cer	met						Coa	ited						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	F04	page
RPCT	1606M0-MA																	•	
RPET	1606M0E-ML														•	•			F47
RPMT	1606M0E-MF														•	•			E17
	1606M0S-MM								•	•	•				•	•			E18
RPMW	1606M0S1								•	•					•	•			

#### Available adaptor

	Designation	Available adaptor
FMRM	5040HRP-M16	MAT M16
	5042HRP-M16	MAT-M16

Designation: FMRM5040HRP-M16 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

Specification			
	Screw	Wrench	Wrench
Ø40~Ø42	FTGA0511-P	-	TW20-100





# Technical Information for Triple Mill


#### High depth of cut milling tool with 3 corners for perpendicularity

### Triple Mill


- Economical milling tool with 3 corners with positive cutting edge for high depth of cut machining
- Stable machinability in high feed machining due to enhanced chip evacuation and thicker insert
- High precision machining from less cutting load due to high helix and sharp cutting edge

#### Code system


#### · Insert



#### Cutter




#### Shank




#### Insert features

- Economical insert with 3 corners due to high depth of cut cutting edge
- · Lowered cutting load and enhanced chip evacuation by sharp chip breaker and high helix cutting edge
- Stable machinability even in high cutting conditions from high rigidity design



#### Cutter features





### **Technical Information for Triple Mill**

#### Recommended grade and chip breaker

( : 1st Recommendation)

	Cutting edge		1	P			М		K	S			
C/B			carbon steel/ Mild steel	_	carbon steel/ Alloy steel	Sta	inless steel		Cast iron	HRSA			
		C/B	Grade	C/B	Grade	C/B	Grade	C/B	Grade	C/B	Grade		
ML	125	-	● PC3700 ○ PC5300 ○ PC5400	-	● PC3700 ○ PC5300 ○ PC5400	•	● PC5300 ○ PC5400 ○ PC9540	-	● PC6510 ○ PC5300 ○ PC5400	-	○ PC5300 ○ PC5400		
ММ	20	•	● PC3700 ○ PC5300 ○ PC5400	•	● PC3700 ○ PC5300 ○ PC5400	-	● PC5300 ○ PC5400 ○ PC9540	•	● PC6510 ○ PC5300 ○ PC5400	-	○ PC5300 ○ PC5400		


#### Recommended cutting condition

			Cutting speed	TNK	CT11	TNK	T16	TNK	T20
V	/orkpiece	Grade	vc(m/min)	fz (mm/t)	Max. ap (mm)	fz (mm/t)	Max. ap (mm)	fz (mm/t)	Max. ap (mm)
P	Steel	PC3700	160-270	0.25-0.1	8.0	0.25-0.1	11.5	0.25-0.1	15.5
	Steel	PC5300	140-240	0.25-0.1	8.0	0.25-0.1	11.5	0.25-0.1	15.5
		PC5300	90-150	0.2 - 0.05	8.0	0.2-0.05	11.5	0.2-0.05	15.5
M	Stainless steel	PC5400	70-120	0.2 - 0.05	8.0	0.2-0.05	11.5	0.2-0.05	15.5
		PC9540	70-120	0.2-0.05	8.0	0.2-0.05	11.5	0.2-0.05	15.5
K	Cast iron	PC6510	150-250	0.3-0.1	8.0	0.3-0.10	11.5	0.3-0.1	15.5
S	HRSA	PC5300	20-50	0.15-0.05	8.0	0.15-0.05	11.5	0.15-0.05	15.5

X The above data refer to general cutting conditions and can be adjustable to the speed of 350 m/min and the feed per tooth of 0.3 mm/t depending on user environment.

#### Application range






#### Performance evaluation

#### Perpendicularity

■ Workpiece Alloy steel (SCM440, HB200), 300(L) x 200(W) x 100(H)

■ Cutting conditions vc (m/min) = 200, fz (mm/t) = 0.2, ap (mm) = 12 mm x 2Passes (Total 24 mm), ae (mm) = 5, dry

■ Tools Insert TNKT200708PESR-MM (PC5300) Holder TPMCM080R-27-7-TN20



[Graph of measured perpendicularities]



**Triple Mill** 



Competitor

[Comparison picture of flank surface finish]


#### Wear resistance

57% longer tool life


■ Workpiece Alloy steel (SCM440, HB200), 300(L) x 200(W) x 100(H)

■ Cutting conditions vc (m/min) = 200, fz (mm/t) = 0.2, ap (mm) = 7, ae (mm) = 10, dry

■ Tools Insert TNKT160608PESR-MM (PC5300) Holder TPMCM063R-22-6-TN16



Triple Mill



Competitor

#### Surface finish

■ Workpiece Alloy steel (SCM440, HB200), 300(L) x 200(W) x 100(H)

■ Cutting conditions vc (m/min) = 200, fz (mm/t) = 0.2, ap (mm) = 7, ae (mm) = 10, dry


■ Tools Insert TNKT160608PESR-MM (PC5300) Holder TPMCM063R-22-6-TN16



**Triple Mill** 





Competitor



### TPMCM-TN16

















(mm)

	Designation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg	Fig.	Available insert
TPMCM	050R-22-4-TN16	4	50	42	22	11	18	-	10.4	6.3	21	40	11.5	0.26	1	
	050R-22-5-TN16	5	50	42	22	11	18	-	10.4	6.3	21	40	11.5	0.26	1	
	063R-22-4-TN16	4	63	50	22	11	18	-	10.4	6.3	21	40	11.5	0.50	1	
	063R-22-6-TN16	6	63	50	22	11	18	-	10.4	6.3	21	40	11.5	0.48	1	
	080R-27-6-TN16	6	80	60	27	14	20	-	12.4	7	24	50	11.5	0.99	1	TNKT16
	080R-27-8-TN16	8	80	60	27	14	20	-	12.4	7	24	50	11.5	0.99	1	INKIIO
	100R-32-8-TN16	8	100	70	32	18	28	45	14.4	8	28	63	11.5	1.85	2	
	100R-32-10-TN16	10	100	70	32	18	28	45	14.4	8	28	63	11.5	1.83	2	
	125R-40-12-TN16	12	125	90	40	22	32	54	16.4	9	30	63	11.5	3.12	2	
	125R-40-14-TN16	14	125	90	40	22	32	54	16.4	9	30	63	11.5	3.10	2	

#### Available inserts

TNKT-ML TNKT-MM





		Cer	met						C	oate	d						
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC2015	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	page
TNKT	160608PEER-ML										•				•		E28
	160608PESR-MM										•	•			•		⊏28


#### Available arbors


	Designation	Ød	NC arbors
TPMCM	050R-22-□-TN□□	22	BT□□-FMC22-□□
	063R-22-□-TN□□	22	DI UU-FIVIOZZ-UU
	080R-27-□-TN□□	27	BT□□-FMC27-□□
	100R-32-□-TN□□	32	BT□□-FMC32-□□
	125R-40-□-TN□□	40	BT□□-FMC40-□□

Specification			
	Screw	Wrench	
Ø50~Ø125	FTKA0410	TW15S	

### TPMCM-TN20 (1997)















• AR: 10° • RR: -10.5°~-14°

(mm)

1	Designation	<b>()</b>	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg	Fig.	Available insert
TPMCM	063R-22-5-TN20	5	63	50	22	11	18	-	10.4	6.3	21	50	15.5	0.57	1	
	063R-22-6-TN20	6	63	50	22	11	18	-	10.4	6.3	21	50	15.5	0.58	1	
	080R-27-5-TN20	5	80	60	27	14	20	-	12.4	7	24	50	15.5	0.92	1	
	080R-27-7-TN20	7	80	60	27	14	20	-	12.4	7	24	50	15.5	0.86	1	TNKT20
	100R-32-7-TN20	7	100	70	32	18	28	45	14.4	8	28	63	15.5	1.79	2	TINKIZU
	100R-32-9-TN20	9	100	70	32	18	28	45	14.4	8	28	63	15.5	1.68	2	
	125R-40-8-TN20	8	125	90	40	22	32	52	16.4	9	30	63	15.5	3.08	2	
	125R-40-11-TN20	11	125	90	40	22	32	52	16.4	9	30	63	15.5	2.99	2	

#### Available inserts

TNKT-ML TNKT-MM





		Cer	met						(	oate	d						
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC2015	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	page
TNKT	200708PEER-ML										•			•	•		F00
	200708PESR-MM										•	•			•		E28

#### Available arbors


	Designation	Ød	NC arbors
TPMCM	063R-22-□-TN□□	22	BT□□-FMC22-□□
	080R-27-□-TN□□	27	BT□□-FMC27-□□
	100R-32-□-TN□□	32	BT□□-FMC32-□□
	125R-40-□-TN□□	40	BT□□-FMC40-□□


Specification			
	Screw	Wrench	
Ø63~Ø125	FTGA0511-P	TW20-100	



### TPMS-TN11















• AR: 8°~10° • RR: -14°~-15°

(mm)

	Designation	<b>©</b>	ØD	Ød	Q	L	ар	∫ kg	Fig.	Available insert
TPMS	025R-2W25-120-TN11	2	25	25	35	120	8	0.37	1	
	025R-2C25-200-TN11	2	25	25	35	200	8	0.65	2	
	025R-3W25-120-TN11	3	25	25	35	120	8	0.36	1	
	025R-3C25-200-TN11	3	25	25	35	200	8	0.64	2	
	032R-2W32-130-TN11	2	32	32	40	130	8	0.71	1	
	032R-2C32-200-TN11	2	32	32	40	200	8	1.12	2	TNKT11
	032R-3W32-130-TN11	3	32	32	40	130	8	0.70	1	TINKTTT
	032R-3C32-200-TN11	3	32	32	40	200	8	1.14	2	
	032R-4W32-130-TN11	4	32	32	40	130	8	0.70	1	
	032R-4C32-200-TN11	4	32	32	40	200	8	1.11	2	
	040R-4W40-130-TN11	4	40	40	40	130	8	1.12	1	
	040R-5W40-130-TN11	5	40	40	40	130	8	1.11	1	

#### Available inserts

TNKT-ML TNKT-MM







		Cer	met						C	coate	d						
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC2015	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	page
TNKT	110508PEER-ML										•			•	•		F00
	110508PESR-MM										•	•			•		E28

Specification			
	Screw	Wrench	
Ø25~Ø40	FTKA0307	TW09S	

### TPMS-TN16















(mm)

	Designation	0	ØD	Ød	Q	L	ар	kg	Fig.	Available insert
TPMS	032R-2W32-130-TN16	2	32	32	40	130	11.5	0.68	1	
	032R-2C32-200-TN16	2	32	32	40	200	11.5	1.10	2	
	040R-3W40-130-TN16	3	40	40	40	130	11.5	1.09	1	TNKT16
	040R-3C40-200-TN16	3	40	40	40	200	11.5	1.75	2	
	040R-4W40-130-TN16	4	40	40	40	130	11.5	1.08	1	


#### Available inserts

TNKT-ML TNKT-MM





	Designation		met		Coated												
			CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2010	PC2015	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	page
TNKT	160608PEER-ML										•				•		F00
	160608PESR-MM										•	•			•		E28





### Technical Information for HFMD


#### High Feed Milling Tool with 4 Corners for Small Diameter




- Economical 4-corner double sided insert
- Increased productivity due to thinner and elongated shape of the insert which makes fine pitch available
- Insert designed for low cutting resistance with high rake angle and helix angle which reduces cutting load
- Inhibiting chipping and breakage due to concave clamping system and stronger screw

#### Code system


Cutter



#### Shank



#### Modular






#### Features




#### Features of chip breaker

ı	Insert	Cutting-edge	Uses	Features
ML		220	For heat resistant alloy and titanium	Ensures superior machining quality by applying a low cutting resistance chip breaker and high-strength cutting edge design suitable for machining heat resistant alloy
MF			For light cutting	Suitable for light cutting with a low cutting resistance chip breaker design
ММ			For multi-purpose	Available for most cutting area with its exclusive design suitable for general high feed machining

### Application area







### E Technical Information for HFMD

### Recommended cutting condition

※ Recommended chip breaker: ●1st ○2nd











A .
-

		Wor	kpiece				LNN	IX04	LNN	1X06	LNN	1X10		Availa	breaker	
ISO		kpiece erials	KS	HB (H <sub>R</sub> C)	Grade	vc (m/min)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	fz (mm/t)	ap (mm)	ae	ML	MF	ММ
	Mild	l steel	SM20C	120 - 180	PC5400 (PC5300)	100-240	1.2-0.3	0.2-0.5	1.2-0.3	0.2-1.0	1.4-0.3	0.3-1.5	0.7D-0.1D	0	•	
	Carbo	on steel	SM45C	200	PC5400 (PC5300)	100-240	1.2-0.3	0.2-0.5	1.2-0.3	0.2-1.0	1.4-0.3	0.3-1.5	0.7D-0.1D	0	•	
	Allo	y steel	SCM440	270 (28)	PC3700 (PC5300)	100-220	1.2-0.3	0.2-0.5	1.2-0.3	0.2-1.0	1.4-0.3	0.3-1.5	0.7D-0.1D		•	0
			KP4M	300 (32)	PC3700 (PC5300)	100-200	1.0-0.3	0.2-0.4	1.0-0.3	0.2-0.8	1.2-0.3	0.3-1.2	0.7D-0.1D		0	•
P			NIMAX	370 (40)	PC3700 (PC5300)	100-200	1.0-0.3	0.2-0.4	1.0-0.3	0.2-0.8	1.2-0.3	0.3-1.2	0.7D-0.1D		0	•
	hard	re- dened teel	CENA1	370 (40)	PC3700 (PC5300)	100-200	1.0-0.3	0.2-0.4	1.0-0.3	0.2-0.8	1.2-0.3	0.3-1.2	0.7D-0.1D		0	•
			NAK80	400 (43)	PC5300 (PC3700)	100-200	1.0-0.3	0.2-0.4	1.0-0.3	0.2-0.8	1.2-0.3	0.3-1.2	0.7D-0.1D		0	•
			STAVAX	510 (52)	PC3700 (PC2510)	80-160	0.7-0.3	0.2-0.4	0.7-0.3	0.2-0.8	0.9-0.3	0.3-1.2	0.7D-0.1D		0	•
	Alloy t	ool steel	STD11 STD61	- (40-50)	PC2510 (PC5300)	80-130	0.7-0.3	0.2-0.3	0.65-0.3	0.2-0.6	0.8-0.3	0.3-0.9	0.7D-0.1D		0	•
M		inless teel	STS316	Under 270	PC9540 (PC5400)	90-180	0.8-0.3	0.2-0.5	0.8-0.3	0.2-0.8	1.0-0.3	0.3-1.2	0.7D-0.1D	•	0	
K	Ducti	east iron, ile cast ron	GCD450	Tensile Strength Over 450Mpa	PC5300 (PC5400)	130-220	0.9-0.3	0.2-0.5	0.9-0.3	0.2-1.0	1.2-0.3	0.3-1.5	0.7D-0.1D		•	0
	UD04	Fe series	Incoroy901	- (25-35)	PC9540 (PC5300)	30-100	0.7-0.3	0.2-0.3	0.6-0.3	0.2-0.6	0.7-0.3	0.3-0.9	0.7D-0.4D	•	0	
S	HRSA	Ni or Co series	Inconel718	- (35-45)	PC9540 (PC5300)	30-45	0.7-0.3	0.2-0.3	0.7-0.3	0.2-0.6	0.8-0.3	0.3-0.9	0.7D-0.4D	0	•	
	Tita	inium	Ti-6AL-4V	- (40-45)	PC9540 (PC5300)	30-50	08-0.3	0.2-0.3	1.0-0.3	0.2-0.6	1.2-0.3	0.3-0.9	0.7D-0.1D	•	0	

#### Performance evaluation

#### Carbon steel (SM45C, HB200)


■ Workpiece Steel rectangular tube (300  $\times$  200  $\times$  100)


■ Cutting conditions vc (m/min) = 200, fz (mm/t) = 1.2,

ap (mm) = 0.8, ae (mm) = 20, dry

■ Tools Insert LNMX060310R-MF (PC5300)

Holder HFMDS032R-5C32-200-LN06





**HFMD** 



Competitor

- Material removal rate Q (cm3/min): 191.0
- · Cutting time (min): 75.4

#### Pre-hardened steel (KP4M, HRC30)


■ Tools

■ Workpiece Steel rectangular tube (300  $\times$  200  $\times$  100)

■ Cutting conditions vc (m/min) = 160, fz (mm/t) = 1.2,

ap (mm) = 1.2, ae (mm) = 20, dry

Insert LNMX100412R-MF (PC5300) Holder HFMDS032R-4C32-200-LN10







Competitor

- · Material removal rate Q (cm3/min): 183.3
- · Cutting time (min): 4.7

#### Alloy tool steel (STD11, HRC40-45)


■ Workpiece Steel rectangular tube (300  $\times$  200  $\times$  100)

■ Cutting conditions vc (m/min) = 160, fz (mm/t) = 1.2,

ap (mm) = 0.9, ae (mm) = 20, dry

■ Tools Insert LNMX100412R-MF (PC2510)

Holder HFMDS032R-4C32-200-LN10





- Competitor
- · Material removal rate Q (cm3/min): 91.7
- · Cutting time (min): 2.0

#### Corner R programming

	Over cut
Corner R programming	
Uncut	
E.	

----- Corner R programming

					(mm)
	Corner R	Cutting c	onditions		
Insert	programming	Nose R	Мах. ар	Over Cut	Uncut
	R0.8			0	0.27
LNMX040205R-ML LNMX040205R-MM	R0.9 (Standard)	0.5	0.5	0	0.24
	R1.0			0.01	0.22
LNMX060310R-ML	R1.5			0	0.41
LNMX060310R-MF	R1.6 (Standard)	1.0	1.0	0	0.41
LNMX060310R-MM	R2.0			0.06	0.38
LNMX100412R-ML	R2.0			0	0.84
LNMX100412R-MF	R2.5 (Standard)	1.2	1.5	0	0.60
LNMX100412R-MM	R3.0			0.06	0.51

- During usage of CNC program, over cut & uncut would be occurred on the corner processing site if entering the correct program corner R value for each insert
- $\bullet$  To prevent overcut, you will need to complete a CNC program considering the above overcut



### E Technical Information for HFMD

#### Ramping and helical cutting

# Ramping Lmin Direction

ØDHmin

**Helical cutting** 

ØDHmax

(mm)

		Depth of	Rampin	g		Blind hole h	elical cutting		Thru hole helical cutting															
Designation	Tool dia. ØD	cut ap	Max ramping angle a (°)	Lmin	Max diameter ØDHmax	Max pitch	Min diameter ØDHmin	Max pitch	Min diameter ØDHmin	Max pitch														
	8	0.4	0.5	45	12	0.2	10	0.2	9	0.2														
	10	0.4	0.6	37	16	0.3	14	0.3	13	0.3														
	11		0.8	37	18	0.3	15	0.3	15	0.3														
	12		1.0	28	20	0.4	17	0.4	17	0.4														
	13		1.0	27	22	0.4	19	0.4	19	0.4														
	16		1.0	28	28	0.5	25	0.5	25	0.5														
LNMX04	17		1.0	29	30	0.5	27	0.5	27	0.5														
	20	0.5	0.9	33	36	0.5	33	0.5	33	0.5														
	21		0.7	44	38	0.5	35	0.5	35	0.5														
	25		0.7	43	46	0.5	43	0.5	43	0.5														
	32		0.5	57	60	0.5	57	0.5	57	0.5														
	33		0.4	74	62	0.5	59	0.5	59	0.5														
	35		0.4	79	66	0.5	63	0.5	63	0.5														
	16	0.7	3.0	13	30	0.7	22	0.7	21	0.7														
	17		2.3	25	32	1.0	24	1.0	22	1.0														
	18		2.1	27	34	1.0	26	1.0	24	1.0														
	19		1.9	30	36	1.0	28	1.0	26	1.0														
	20		1.5	37	38	1.0	30	1.0	28	1.0														
	21		1.5	39	40	1.0	32	1.0	30	1.0														
	25		1.4	40	48	1.0	40	1.0	38	1.0														
	26		1.4	42	50	1.0	42	1.0	40	1.0														
LNINAVOO	30		1.1	51	58	1.0	50	1.0	48	1.0														
LNMX06	32			1.0	1.0	55	62	1.0	54	1.0	52	1.0												
	33	-			1.0					1.0	57	64	1.0	56	1.0	54	1.0							
	35																_			1				-
	40		0.8	71	78	1.0	70	1.0	68	1.0														
	42	_	_	_	_	-	0.8	76	82	1.0	74	1.0	72	1.0										
	50		0.6	92	98	1.0	90	1.0	88	1.0														
	52		0.6	96	102	1.0	94	1.0	92	1.0														
	63		0.5	119	124	1.0	116	1.0	114	1.0														
	66		0.5	126	130	1.0	122	1.0	120	1.0														
	25		2.9	30	42	1.5	35	1.5	32	1.5														
	26		2.7	32	44	1.5	37	1.5	34	1.5														
	30		2.2	39	52	1.5	45	1.5	42	1.5														
	32		2.0	43	56	1.5	49	1.5	46	1.5														
	33		1.9	45	58	1.5	51	1.5	48	1.5														
	35		1.8	49	62	1.5	55	1.5	52	1.5														
I NIMY40	40	1	1.5	58	72	1.5	65	1.5	62	1.5														
LNMX10	42	1.5	1.4	62	76	1.5	69	1.5	66	1.5														
	50	1	1.1	77	92	1.5	85	1.5	82	1.5														
	52	1	1.1	81	96	1.5	89	1.5	86	1.5														
	63	1	0.8	101	118	1.5	111	1.5	108	1.5														
	66	1	0.8	107	124	1.5	117	1.5	114	1.5														
	80	1	0.6	133	152	1.5	145	1.5	142	1.5														
	100		0.5	171	192	1.5	185	1.5	182	1.5														



<sup>•</sup> When helical milling, Max. pitch, DHmax should be lower than max. depth of cut, ap.



<sup>•</sup> When ramping, the depth of cut should be lower than max. depth of cut, ap.

<sup>•</sup> Lmin = ap/tan ( $\alpha$ °) (mm)


<sup>•</sup> Lmin: Min. length of ramping

 $<sup>\</sup>bullet$  ap: Depth of cut

<sup>•</sup>  $\alpha^{\circ} \text{:}$  Max. rake angle in ramping

### HFMDS-LN04 rew


















• AR: -8°~-7° • RR: -19°~-15°

(mm)

	Designation	<b>(</b>	ØD	Ød	Q	L	ар	kg
HFMDS	008NR-1C08-080-LN04	1	8	8	20	80	0.4	0.03
	008NR-1C10-100-LN04	1	8	10	20	100	0.4	0.05
	010NR-2C08-080-LN04	2	10	8	20	80	0.4	0.03
	010NR-2C10-100-LN04	2	10	10	20	100	0.4	0.06
	010NR-2C10-150-LN04	2	10	10	40	150	0.4	0.08
	011NR-2C10-100-LN04	2	11	10	20	100	0.5	0.06
	011NR-2C10-150-LN04	2	11	10	20	150	0.5	0.09
	008R-1C08-080-LN04	1	8	8	20	80	0.5	0.02
	008R-1C10-100-LN04	1	8	10	20	100	0.5	0.05
	010R-2C08-080-LN04	2	10	8	20	80	0.4	0.03
	010R-2C10-080-LN04	2	10	10	35	80	0.4	0.05
	010R-2C10-100-LN04	2	10	10	20	100	0.4	0.05
	010R-2C10-150-LN04	2	10	10	40	150	0.4	0.07
	011R-2C10-100-LN04	2	11	10	20	100	0.5	0.05
	011R-2C10-150-LN04	2	11	10	20	150	0.5	0.08
	012R-3C12-100-LN04	3	12	12	50	100	0.5	0.07
	012R-3C12-105-LN04	3	12	12	20	105	0.5	0.07
	012R-3C12-150-LN04	3	12	12	40	150	0.5	0.11

#### Available inserts


→ Avai																			
						I	LNMX	-ML		LN	MX-N	1M							
							Ç												
		Cei	rmet						Coated							Unco	oated		
	Designation		CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	Н01	page
LNMX	040205R-ML														•	•			E12
	040205R-MM									•	•				•	•			EIZ





### HFMDS-LN04 rew

















• AR: -8° • RR: -14°~-13°

(mm)

	Designation	<b>(</b>	ØD	Ød	Q	L	ар	∑ kg
HFMDS	013R-3C12-100-LN04	3	13	12	20	100	0.5	0.08
	013R-3C12-120-LN04	3	13	12	20	120	0.5	0.09
	013R-3C12-150-LN04	3	13	12	20	150	0.5	0.12
	016R-4C16-100-LN04	4	16	16	50	100	0.5	0.13
	016R-4C16-120-LN04	4	16	16	70	120	0.5	0.20
	016R-4C16-150-LN04	4	16	16	80	150	0.5	0.20
	016R-4C16-200-LN04	4	16	16	120	200	0.5	0.26
	017R-4C16-100-LN04	4	17	16	20	100	0.5	0.14
	017R-4C16-150-LN04	4	17	16	20	150	0.5	0.20
	017R-4C16-200-LN04	4	17	16	20	200	0.5	0.29
	020R-5C20-100-LN04	5	20	20	20	100	0.5	0.22
	020R-5C20-150-LN04	5	20	20	40	150	0.5	0.30
	020R-5C20-200-LN04	5	20	20	80	200	0.5	0.40
	021R-5C20-100-LN04	5	21	20	20	100	0.5	0.22
	021R-5C20-150-LN04	5	21	20	20	150	0.5	0.30
	021R-5C20-200-LN04	5	21	20	20	200	0.5	0.46


#### Available inserts

						ı	_NMX	-ML		LN	IMX-M	IM							
		Cer	met			Coated											oated		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
LNMX	040205R-ML														•	•			E12
	040205R-MM									•	•				•	•			_ E12



### HFMDS-LN06


















• AR: -9° • RR: -14°~-13°

(mm)

	Designation	<b>(</b>	ØD	Ød	Q	L	ар	kg
HFMDS	016R-2C16-100-LN06	2	16	16	30	100	0.7	0.13
	016R-2C16-150-LN06	2	16	16	50	150	0.7	0.19
	017R-2C16-100-LN06	2	17	16	30	100	1.0	0.13
	017R-2C16-150-LN06	2	17	16	40	150	1.0	0.20
	017R-2C16-200-LN06	2	17	16	40	200	1.0	0.27
	018R-2C16-100-LN06	2	18	16	40	100	1.0	0.14
	018R-2C16-160-LN06	2	18	16	40	160	1.0	0.18
	018R-2C16-200-LN06	2	18	16	40	200	1.0	0.28
	019R-2C16-100-LN06	2	19	16	40	100	1.0	0.15
	019R-2C16-160-LN06	2	19	16	40	160	1.0	0.19
	019R-2C16-200-LN06	2	19	16	40	200	1.0	0.29
	020R-3C20-100-LN06	3	20	20	40	100	1.0	0.20
	020R-3C20-130-LN06	3	20	20	50	130	1.0	0.26
	020R-3C20-160-LN06	3	20	20	80	160	1.0	0.31
	020R-3C20-200-LN06	3	20	20	120	200	1.0	0.40
	021R-3C20-100-LN06	3	21	20	30	100	1.0	0.21
	021R-3C20-130-LN06	3	21	20	40	130	1.0	0.27
	021R-3C20-160-LN06	3	21	20	40	160	1.0	0.34
	021R-3C20-200-LN06	3	21	20	40	200	1.0	0.42

#### Available inserts


					LNI	MX-ML	-	L	NMX-I	MF		LNMX	K-MM						
					-	5						5							
		Coated							d						ated				
Designation Cermet Cermet Control Cermet Control Cermet Ce				NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
LNMX	060310R-ML														•	•			
	060310R-MF									•	•				•	•			E12
	060310R-MM									•	•				•	•			





### HFMDS-LN06

















• AR: -9°

• RR: -12°~-10°

(mm)

	Designation	(i)	ØD	Ød	Q	L	ар	kg
<b>HFMDS</b>	025R-4C25-100-LN06	4	25	25	40	100	1.0	0.33
	025R-4C25-140-LN06	4	25	25	60	140	1.0	0.46
	025R-4C25-180-LN06	4	25	25	100	180	1.0	0.58
	025R-4C25-250-LN06	4	25	25	150	250	1.0	0.67
	026R-4C25-100-LN06	4	26	25	30	100	1.0	0.34
	026R-4C25-140-LN06	4	26	25	40	140	1.0	0.48
	026R-4C25-180-LN06	4	26	25	40	180	1.0	0.63
	026R-4C25-250-LN06	4	26	25	40	250	1.0	0.72
	032R-5C32-150-LN06	5	32	32	70	150	1.0	0.82
	032R-5C32-200-LN06	5	32	32	120	200	1.0	1.08
	032R-5C32-250-LN06	5	32	32	150	250	1.0	1.20
	033R-5C32-150-LN06	5	33	32	40	150	1.0	0.82
	033R-5C32-200-LN06	5	33	32	40	200	1.0	1.08
	033R-5C32-250-LN06	5	33	32	40	250	1.0	1.20
	035R-5C32-150-LN06	5	35	32	40	150	1.0	0.87
	035R-5C32-200-LN06	5	35	32	40	200	1.0	1.13
	035R-5C32-250-LN06	5	35	32	40	250	1.0	1.25
	040R-6C32-150-LN06	6	40	32	40	150	1.0	0.97
	040R-6C32-200-LN06	6	40	32	40	200	1.0	1.28
	040R-6C32-250-LN06	6	40	32	40	250	1.0	1.38


#### Available inserts

					LNI	VIX-ML		L	NMX-N	ΛF		LNMX	C-MM						
					-	5		•	Ś			5							
		Coated												Unco	ated				
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	년 1	page
LNMX	060310R-ML														•	•			
	060310R-MF									•	•				•	•			E12
	060310R-MM									•	•				•	•			

Specification			
	Screw	Wrench	
Ø25~Ø40	FTNA0306	TW09S	

### HFMDS-LN10 000

















• AR: -9° • RR: -16°~-13°

(mm)

	Designation	0	ØD	Ød	Q	L	ар	∑ kg \
HFMDS	025R-2C25-150-LN10	2	25	25	70	150	1.5	0.46
	025R-2C25-200-LN10	2	25	25	100	200	1.5	0.60
	025R-3C25-150-LN10	3	25	25	70	150	1.5	0.45
	025R-3C25-200-LN10	3	25	25	100	200	1.5	0.60
	026R-3C25-150-LN10	3	26	25	40	150	1.5	0.49
	026R-3C25-200-LN10	3	26	25	40	200	1.5	0.68
	030R-3C32-150-LN10	3	30	32	70	150	1.5	0.71
	030R-3C32-200-LN10	3	30	32	100	200	1.5	0.94
	032R-4C32-150-LN10	4	32	32	70	150	1.5	0.75
	032R-4C32-200-LN10	4	32	32	100	200	1.5	1.00
	032R-4C32-250-LN10	4	32	32	150	250	1.5	1.20
	033R-4C32-150-LN10	4	33	32	40	150	1.5	0.80
	033R-4C32-200-LN10	4	33	32	40	200	1.5	1.00
	033R-4C32-250-LN10	4	33	32	40	250	1.5	1.40
	035R-4C32-150-LN10	4	35	32	40	150	1.5	0.85
	035R-4C32-200-LN10	4	35	32	40	200	1.5	1.10
	035R-4C32-250-LN10	4	35	32	40	250	1.5	1.44
	040R-4C32-150-LN10	4	40	32	40	150	1.5	0.89
	040R-4C32-200-LN10	4	40	32	40	200	1.5	1.20
	040R-4C32-250-LN10	4	40	32	40	250	1.5	1.48
	040R-5C32-150-LN10	5	40	32	40	150	1.5	0.89
	040R-5C32-200-LN10	5	40	32	40	200	1.5	1.19
	040R-5C32-250-LN10	5	40	32	40	250	1.5	1.48
	042R-5C32-150-LN10	5	42	32	40	150	1.5	0.92
	042R-5C32-200-LN10	5	42	32	40	200	1.5	1.23
	042R-5C32-250-LN10	5	42	32	40	250	1.5	1.51

#### Available inserts


LNMX-ML LNMX-MF LNMX-MM

		met						C	oate	d						Unco	ated		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
LNMX	100412R-ML													•	•	•			
	100412R-MF									•	•			•	•	•			E12
	100412R-MM									•	•				•	•			



### HFMDCM-LN06



















(mm)

	Designation	<b>(</b> )	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg
HFMDCM	032R-16-5-LN06	5	32	30	16	9	13.5	8.4	5.6	19	40	1.0	0.12
	040R-16-6-LN06	6	40	34	16	9	14	8.4	5.6	19	40	1.0	0.21
	050R-22-6-LN06	6	50	42	22	11	18	10.4	6.3	21	40	1.0	0.32
	050R-22-7-LN06	7	50	42	22	11	18	10.4	6.3	21	40	1.0	0.32
	050R-22-8-LN06	8	50	42	22	11	18	10.4	6.3	21	40	1.0	0.32
	052R-22-7-LN06	7	52	42	22	11	18	10.4	6.3	21	40	1.0	0.34
	052R-22-8-LN06	8	52	42	22	11	18	10.4	6.3	21	40	1.0	0.34
	063R-22-8-LN06	8	63	49	22	11	18	10.4	6.3	21	40	1.0	0.53
	063R-22-9-LN06	9	63	49	22	11	18	10.4	6.3	21	40	1.0	0.53
	066R-22-8-LN06	8	66	49	22	11	18	10.4	6.3	21	40	1.0	0.57
	066R-22-9-LN06	9	66	49	22	11	18	10.4	6.3	21	40	1.0	0.57

#### Available inserts

LNMX-ML LNMX-MF LNMX-MM

				Coated Uncoated															
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	191	page
LNMX	060310R-ML														•	•			
	060310R-MF									•	•				•	•			E12
	060310R-MM									•	•				•	•			

#### Available arbors


	Designation	Ød	Available arbors
HFMDCM	032R-16-□-LN06	Ø32	BT□□-FMC16-□□
	040R-16-□-LN06	Ø40	
	050R-22-□-LN06	Ø50	BT□□-FMC22-□□


	Designation	Ød	Available arbors
HFMDCM	052R-22-□-LN06	Ø52	
	063R-22-□-LN06	Ø63	BT□□-FMC22-□□
	066R-22-□-LN06	Ø66	

Specification		
	Screw	Wrench
Ø32~Ø66	FTNA0306	TW09S

### HFMDC(M)-LN10





















				•	RR: -16°	~-13°									(mm)
	Designation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	Е	F	ар	kg	Fig.
HFMDCM	040R-16-4-LN10	4	40	38	16	9	14	-	8.4	5.6	19	40	1.5	0.19	1
	040R-16-5-LN10	5	40	38	16	9	14	-	8.4	5.6	19	40	1.5	0.19	1
	042R-16-4-LN10	4	42	38	16	9	14	-	8.4	5.6	19	40	1.5	0.20	1
	042R-16-5-LN10	5	42	38	16	9	14	-	8.4	5.6	19	40	1.5	0.20	1
	050R-22-6-LN10	6	50	42	22	11	18	-	10.4	6.3	21	40	1.5	0.26	1
	050R-22-7-LN10	7	50	42	22	11	18	-	10.4	6.3	21	40	1.5	0.26	1
	052R-22-6-LN10	6	52	42	22	11	18	-	10.4	6.3	21	40	1.5	0.27	1
	052R-22-7-LN10	7	52	42	22	11	18	-	10.4	6.3	21	40	1.5	0.27	1
	063R-22-7-LN10	7	63	49	22	11	18	-	10.4	6.3	21	40	1.5	0.47	1
	063R-22-8-LN10	8	63	49	22	11	18	-	10.4	6.3	21	40	1.5	0.47	1
	066R-22-7-LN10	7	66	49	22	11	18	-	10.4	6.3	21	40	1.5	0.49	1
	066R-22-8-LN10	8	66	49	22	11	18	-	10.4	6.3	21	40	1.5	0.50	1
	080R-27-9-LN10	9	80	60	27	14	25	35	12.4	7.0	24	50	1.5	0.84	2
	080R-27-10-LN10	10	80	60	27	14	25	35	12.4	7.0	24	50	1.5	0.84	2
	100R-32-10-LN10	10	100	67	32	18	26	42	14.4	8.0	28	56	1.5	1.48	2
	100R-32-11-LN10	11	100	67	32	18	26	42	14.4	8.0	28	56	1.5	1.48	2
	100R-32-12-LN10	12	100	67	32	18	26	42	14.4	8.0	28	56	1.5	1.48	2
HFMDC	080R-25.4-9-LN10	9	80	60	25.4	14	25	35	9.5	6	25	50	1.5	0.84	2
	080R-25.4-10-LN10	10	80	60	25.4	14	25	35	9.5	6	25	50	1.5	0.84	2
	100R-31.75-10-LN10	10	100	67	31.75	18	26	42	12.7	8	32	56	1.5	1.48	2
	100R-31.75-11-LN10	11	100	67	31.75	18	26	42	12.7	8	32	56	1.5	1.48	2
	100R-31.75-12-LN10	12	100	67	31.75	18	26	42	12.7	8	32	56	1.5	1.48	2

#### Available inserts







LNMX-MM

												-							
			met						(	Coate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H0.1	page
LNMX	100412R-ML													•	•	•			
	100412R-MF									•	•			•	•	•			E12
	100412R-MM									•	•				•	•			

#### Available arbors

	Designation	Ød	Available arbors
HFMDCM	040R-16-□-LN10	Ø40	BT -FMC16-
	042R-16-□-LN10	Ø42	BILL-FMC16-LL
	050R-22-□-LN10	Ø50	
	052R-22-□-LN10	Ø52	BT□□-FMC22-□□
	062D 22 T I N10	aco	


	Designation	Ød	Available arbors
HFMDCM	066R-22-□-LN10	Ø66	BT□□-FMC22-□□
	080R-27-□-LN10	Ø80	BT□□-FMC27-□□
	100R-32-□-LN10	Ø100	BT□□-FMC32-□□
HFMDC	080R-25.4-□-LN10	Ø80	BT□□-FMA25.4-□□
	100D_21 75_ L N10	Ø100	BT - FMA31 75-

Specification	
pecification	rew Wren
Ø40~Ø100	A0408 TW15S



### HFMDM-LN04 rew

















• AR: -8° • RR: -16°~-10°

(mm)

	Designation	(i)	ØD	Ød	Ød1	Q	L	M	ар	kg
HFMDM	010R-2-M06-LN04	2	10	9.5	6.5	22	37	M6	0.4	0.01
	011R-2-M06-LN04	2	11	11	6.5	22	37	M6	0.5	0.01
	012R-3-M06-LN04	3	12	11	6.5	22	37	M6	0.5	0.01
	013R-3-M06-LN04	3	13	11	6.5	22	37	M6	0.5	0.02
	016R-4-M08-LN04	4	16	14.5	8.5	22	39	M8	0.5	0.03
	017R-4-M08-LN04	4	17	14.5	8.5	22	39	M8	0.5	0.03
	020R-5-M10-LN04	5	20	18	10.5	30	51	M10	0.5	0.06
	025R-7-M12-LN04	7	25	23	12.5	30	54	M12	0.5	0.1
	032R-8-M16-LN04	8	32	29	17	35	62	M16	0.5	0.2
	033R-8-M16-LN04	8	33	29	17	35	62	M16	0.5	0.2
	035R-9-M16-LN04	9	35	29	17	35	62	M16	0.5	0.21

#### Available inserts

LNMX-ML LNMX-MM



		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
LNMX	040205R-ML														•	•			F10
	040205R-MM									•	•				•	•			E12

#### Available adaptor

	Designation	Available adaptor			
HFMDM	010R-2-M06-LN04				
	011R-2-M06-LN04	MAT-M06			
	012R-3-M06-LN04	IVIA I-IVIUO			
	013R-3-M06-LN04				
	016R-4-M08-LN04	MAT-M08			
	017R-4-M08-LN04	IVIA I -IVIUO			


	Designation	Available adaptor
HFMDM	020R-5-M10-LN04	MAT-M10
	025R-7-M12-LN04	MAT-M12
	032R-8-M16-LN04	
	033R-8-M16-LN04	MAT-M16
	035R-8-M16-LN04	

Designation: HFMDM016R-4-M08-LN04 Modular head threading measure size (M08)

Adaptor spec.: MAT-M08-040-S16T Adaptor threading measure (M08)

### HFMDM-LN06 mew

















• AR: -9° • RR: -15°~-10°

(mm)

	Designation	0	ØD	Ød	Ød1	Q	L	M	ар	kg
HFMDM	016R-2-M08-LN06	2	16	14.5	8.5	25	42	M08	0.7	0.03
	017R-2-M08-LN06	2	17	14.5	8.5	25	42	M08	1.0	0.03
	018R-2-M08-LN06	2	18	14.5	8.5	25	42	M08	1.0	0.04
	019R-2-M08-LN06	2	19	14.5	8.5	25	42	M08	1.0	0.05
	020R-3-M10-LN06	3	20	18	10.5	30	51	M10	1.0	0.06
	021R-3-M10-LN06	3	21	18	10.5	30	51	M10	1.0	0.07
	025R-4-M12-LN06	4	25	23	12.5	35	59	M12	1.0	0.10
	026R-4-M12-LN06	4	26	23	12.5	35	59	M12	1.0	0.10
	032R-5-M16-LN06	5	32	29	17	40	67	M16	1.0	0.20
	033R-5-M16-LN06	5	33	29	17	40	67	M16	1.0	0.20
	035R-5-M16-LN06	5	35	29	17	40	67	M16	1.0	0.21
	040R-6-M16-LN06	6	40	29	17	40	67	M16	1.0	0.24
	042R-6-M16-LN06	6	42	29	17	40	67	M16	1.0	0.25

#### Available inserts



					_														
		Cer	met						C	coate	d						Unco	ated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	H01	page
LNMX	060310R-ML														•	•			
	060310R-MF									•	•				•	•			E12
	060310R-MM									•	•				•	•			

#### Available adaptor

	Designation	Available adaptor			
HFMDM	016R-□-M08-LN06				
	017R-□-M08-LN06	MAT-M08			
	018R-□-M08-LN06	IVIA I -IVIUO			
	019R-□-M08-LN06				
	020R-□-M10-LN06	MAT-M10			
	021R-□-M10-LN06	IVIAT-IVITO			
	025RM12-I N06	MAT-M12			

	Designation	Available adaptor
HFMDM	026R-□-M12-LN06	MAT-M12
	030R-□-M16-LN06	
	032R-□-M16-LN06	
	033R-□-M16-LN06	MAT-M16
	040R-□-M16-LN06	
	042R M16-LN06	

Designation : HFMDM025R-□-M12-LN06 Modular head threading measure size (M12)

Adaptor spec.: MAT-M12-050-S25T Adaptor threading measure (M06)

Specification		
	Screw	Wrench
Ø16~Ø42	FTNA0306	TW09S








### HFMDM-LN10 W

















• AR: -9° • RR: -16°~-13°

(mm)

	Designation	<b>(</b>	ØD	Ød	Ød1	Q	L	M	ар	kg
HFMDM	025R-2-M12-LN10	2	25	23	12.5	35	59	M12	1.5	0.10
	025R-3-M12-LN10	3	25	23	12.5	35	59	M12	1.5	0.10
	026R-3-M12-LN10	3	26	23	12.5	35	59	M12	1.5	0.10
	030R-4-M16-LN10	4	30	29	17.0	40	67	M16	1.5	0.17
	032R-3-M16-LN10	3	32	29	17.0	40	67	M16	1.5	0.19
	032R-4-M16-LN10	4	32	29	17.0	40	67	M16	1.5	0.19
	033R-4-M16-LN10	4	33	29	17.0	40	67	M16	1.5	0.19
	035R-3-M16-LN10	3	35	29	17.0	40	67	M16	1.5	0.20
	035R-4-M16-LN10	4	35	29	17.0	40	67	M16	1.5	0.20
	040R-4-M16-LN10	4	40	29	17.0	40	67	M16	1.5	0.22
	040R-5-M16-LN10	5	40	29	17.0	40	67	M16	1.5	0.22
	042R-4-M16-LN10	4	42	29	17.0	40	67	M16	1.5	0.25
	042R-5-M16-LN10	5	42	29	17.0	40	67	M16	1.5	0.25

#### Available inserts

LNMX-ML LNMX-MF LNMX-MM

					_	_			_			_							
		Cer	met						C	oate	d						Unco	ated	
D	esignation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	된	page
LNMX	100412R-ML													•	•	•			
	100412R-MF									•	•			•	•	•			E12
	100412R-MM									•	•				•	•			

#### Available adaptor

	Designation	Available adaptor
<b>HFMDM</b>	025RM12-LN10	MAT-M12
	026RM12-LN10	IVIAT-IVITZ
	030R M16-LN10	MAT-M16
	032R M16-LN10	IVIA I - IVI I O

	Designation	Available adaptor
HFMDM	033R-□-M16-LN10	
	035R-□-M16-LN10	MAT-M16
	040R-□-M16-LN10	IVIAT-IVITO
	042R M16-LN10	

Designation : HFMDM035R- - M16-LN10 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

### мЕ


#### Stable machining, high efficiency milling tools for small diameter machining



- Increase productivity through improved insert shape and size, high feed per tooth, and many cutting-edges, for small diameter machining
- Stable tool life through the combination of the reinforced toughness on corner and suitable grades of high hardness in the area of high speed and high hardness

#### Code system

Shank



Modular



· Modular adapter



#### Features

- · Apply helix cutting-edge on insert, low cutting load and reinforce toughness on corner
- Increased rigidity with double relief angle (11, 13), prevent interference with high feed
- To apply the negative axial rake angle when set up the holder, increased chipping resistance
- Tool life is increased with suitable C/B and grade for every material



- · Holder setup
- To set up the negative axial rake angle, increased chipping resistance
- · No. of tooth
- Increased tool life with increased flutes
- HRM(D) Ø20 (2 flutes) → HFM Ø20 (5 flutes)



- · Relief angle
- 11, 13 double relief angle increase rigidity and prevent interference
- Major cutting-edge
- Improved sharpness of principle edge
- Improved toughness of corner edge





### **Technical Information for HFM**

#### Features of chip breaker

In	sert	Cutting-edge	Uses	Features
MF	0		Light cutting Titanium & Inconel machining	Low cutting resistance C/B, suitable for light cutting
None C/B			Super hard material machining	High toughness shape, suitable for hard die steel cutting

#### Application area





#### Recommended cutting condition

※ Recommended chip breaker: ●1st ○2nd


|--|--|

			Workpi	ece		НВ			Cutting c	onditions			nip aker
	Workpied	ce	KOR (KS)	USA (AISI)	GER (DIN)	(HRC)	Grades	vc (m/min)	fz (mm/t)	ap (mm)	ae	MF	None C/B
	Mild s	teel	SM20C	1020	C22	120~180	PC5400 (PC5300)	100~220	0.5~1.0	~0.5	0.7D~0.1D	•	-
	Carbon	steel	SM45C	1045	C45	200	PC5400 (PC5300)	100~200	0.5~1.0	~0.5	0.7D~0.1D	•	-
	Alloy	steel	SCM440	4140	41CrMo4	270(28)	PC5300	100~200	0.5~1.0	~0.5	0.7D~0.1D	•	-
			KP4M	P20 (Improved)	1.2738 (Improved)	300(32)	PC5300 (PC2510)	<b>1</b> 00~180	0.5~0.9	~0.4	0.7D~0.1D	•	0
			NIMAX	P21 (Improved)	-	370(40)	PC5300 (PC2510)		0.5~0.9	~0.4	0.7D~0.1D	•	0
P	Pre-hard stee		CENA1	P21 (Improved)	-	370(40)	PC5300 (PC2510)	<b>100~180</b>	0.5~0.9	~0.4	0.7D~0.1D	•	0
			NAK80	P21	_	400(43)	PC5300	100~160	0.5~0.7	~0.4	0.7D~0.1D	0	-
			147 (1100	(Improved)		400(40)		100~180	0.5~0.9	~0.4	0.7D~0.1D	-	•
			STAVAX	420	X30Cr13	510(52)	PC2510 (PC5300)		0.3~0.6	~0.4	0.7D~0.1D	•	-
	Alloy	tool	STD11 STD61	D2 H13	X155CrVMo12-1 X40CrMoV5-1	- (40~50)	PC2510 ne (PC2505)	80~130	0.3~0.55	~0.3	0.7D~0.1D	-	•
	ste	el	STD11 (Cold forging)	D2	X155CrVMo12-1	630(60)	PC2505	30~75	0.3~0.5	~0.2	0.7D~0.1D	-	•
M	Stainles	s steel	STS316	316	X5CrNiMo17-12-2	Under 270	PC5400 (PC5300)	70~150	0.5~0.7	~0.5	0.7D~0.1D	•	-
K	Gray cas Ductile ca		GCD450	65-45-12	GGG40.3	Tensile Strength Over 450Mpa	PC5300	130~220	0.6~0.8	~0.5	0.7D~0.1D	•	-
		Fe series	Incoloy901	N09901	- (WS 2.4662)	- (25~35)	PC5300 (PC5400)	30~100	0.3~0.5	~0.3	0.4D~0.7D	•	0
S		Ni or Co series	Inconel718	N07718	NiCr19FeNbMo (WS 2.4668)	- (35~45)	PC5300 (PC5400)	20~50	0.3~0.6	~0.3	0.4D~0.7D	•	0
	Titani	ium	Ti-6Al-4V	R56400	TiAl6V4	- (40~45)	PC5300	30~50	0.4~1.0	~0.3	0.7D~0.1D	•	-


#### Performance evaluation

#### High speed machining

- Workpiece STD11 (HRC40~45)
- Insert LPM(E)W0402□□R
- **Recommended grade** PC2505 (1st), PC2510 (2nd)




- Workpiece
  - STD11(Over HRC60)
- Insert LPM(E)W0402□□R
- Recommended grade PC2505 (1st), PC2510 (2nd)



#### High feed machining


- Workpiece KP4M (HRC32), NAK80 (HRC43)
- Insert

  LPMT0402□□R-MF
- Recommended grade PC5300 (1st), PC2510 (2nd)



- Workpiece Ti-6AL-4V (HRC40~45)
- Insert

  LPMT0402□□R-MF
- Recommended grade
  PC5300 (1st), PC5400 (2nd)



#### Machining example

#### Alloy tool steel [X155CrVMo12-1 (DIN)/D2 (AISI)/STD11 (KS), HRC40~45]

- Workpiece Mold
- Cutting vc (m/min) = 80, fz (mm/t) = 0.5 conditions ap (mm) = 0.3, ae (mm) = 10

dry

■ Tools Insert LPMW040210R (PC2510)

Holder HFMS1016HR-4S16





HFM



Competitor

- Chip removal rate Q (cm³/min): 4.8
- · Cutting time (min): 25

#### Alloy tool steel [X155CrVMo12-1 (DIN)/D2 (AISI)/STD11 (KS), HRC60]

- Workpiece Mold
- Cutting vc (m/min) = 75, fz (mm/t) = 0.4 conditions ap (mm) = 0.15, ae (mm) = 5

dry

■ Tools Insert LPMW040210R (PC2505)

Holder HFMS1010HR-2S10







Competitor

- Chip removal rate Q (cm3/min): 1.4
- Cutting time (min): 7.85

#### ${\sf HRSA} \ [{\sf TiAl6V4} \ ({\sf DIN})/{\sf R56400} \ ({\sf AISI})/{\sf Ti-6AI-4V} \ ({\sf KS}), \ {\sf HRC48}]$

■ Workpiece Aviation parts

■ Cutting vc (m/min) = 50, fz (mm/t) = 1.2 conditions ap (mm) = 0.3, ae (mm) = 10

wet

■ Tools Insert LPMT040210R-MF (PC5300)

Holder HFMS1016HR-4S16





HFM




- Chip removal rate Q (cm<sup>3</sup>/min): 7.2
- Cutting time (min): 10.05

### E

#### Ramping and helical cutting

#### Ramping




 $Lmin = \frac{ap}{\tan \alpha^{\circ}} (mm$ 


\* Lmin: Min. inclination cutting length

 $\alpha^{\circ} \colon$  Max. ramping angle

ap: Depth of cut

#### Helical cutting





- ØD = Tool dia. (mm)
- $\emptyset$ d = Tool path (mm) =  $\emptyset$ DHmin, Max  $\emptyset$ D
- ØDHmin (Min diameter, mm) =  $ØD \times 2 5.4$
- ØDHmax (Max diameter, mm) = ØD×2 2


(mm)

			Ramp	ina		Helical cutting	
Designation	Tool dia. ØD	Depth of cut ap	Max ramping angle a (°)	Lmin	Max diameter ØDHMax	Min diameter ØDHMin	Max pitch dmax
HFMS1010HR	10	0.4~0.5	3.5	7	18	15	0.4
HFMS1011HR	11	0.4~0.5	3.1	8	20	17	0.4
HFMS1012HR	12	0.4~0.5	2.7	9	22	19	0.4
HFMS1013HR	13	0.4~0.5	2.4	10	24	21	0.4
HFMS1014HR	14	0.4~0.5	2.2	11	26	23	0.4
HFMS1015HR	15	0.4~0.5	2.0	12	28	25	0.4
HFMS1016HR	16	0.4~0.5	1.8	13	30	27	0.4
HFMS1017HR	17	0.4~0.5	1.7	14	32	29	0.4
HFMS1018HR	18	0.4~0.5	1.6	15	34	31	0.4
HFMS1019HR	19	0.4~0.5	1.5	16	36	33	0.4
HFMS1020HR	20	0.4~0.5	1.4	17	38	35	0.4
HFMS1021HR	21	0.4~0.5	1.3	18	40	37	0.4
HFMM1025HR	25	0.4~0.5	1.1	22	48	45	0.4
HFMM1026HR	26	0.4~0.5	1.0	23	50	47	0.4
HFMM1030HR	30	0.4~0.5	0.9	27	58	55	0.4
HFMM1032HR	32	0.4~0.5	0.8	29	62	59	0.4
HFMM1033HR	33	0.4~0.5	0.8	30	64	61	0.4


- Adjust feed to under 70% of recommended cutting condition when ramping & helical cutting
- In helical ramping, max. cutting depth per 1 helical revolution of cutter should not exceed max. cutting depth as per insert size
- In ramping, max. cutting depth per 1 ramping process of cutter should not exceed max. depth of cut as per used insert size

#### Corner R programming

(mm)




Insert	Corner R	Cutting c	onditions	Over Cut	Uncut
ilisert	programming	Nose R	Мах. ар	Over Cut	Officut
LPMT040210R-MF	R1.0 (Standard)			0	0.17
LPMW040210R	R1.5	1.0	0.4	0.10	0.08
LPEW040210R	R2.0			0.31	0
LPMT040220R-MF	R1.0			0	0.41
LPMW040220R	R1.5	2.0	0.5	0	0.2
LPEW040220R	R2.0 (Standard)			0	0



 ${\mbox{\ensuremath{\bullet}}}$  To prevent overcut, you will need to complete a CNC program considering the above overcut

### HFMS1000 @



















• AR: -4° • RR: -14°~-7°

(mm)

	Designation	(a)	ØD	Ød	Q	L	ар	√ kg \
HFMS	1008HR-1S10	1	8	10	20	80	0.4~0.5	0.03
	1008HR-1M10	1	8	10	25	100	0.4~0.5	0.03
	1008HR-1L10	1	8	10	35	120	0.4~0.5	0.03
	1010HR-2S08	2	10	8	20	80	0.4~0.5	0.03
	1010HR-2M08	2	10	8	25	100	0.4~0.5	0.04
	1010HR-2L08	2	10	8	35	120	0.4~0.5	0.04
	1010HR-2S10	2	10	10	20	80	0.4~0.5	0.04
	1010HR-2M10	2	10	10	25	105	0.4~0.5	0.05
	1010HR-2L10	2	10	10	35	120	0.4~0.5	0.06
	1011HR-2S10	2	11	10	20	80	0.4~0.5	0.04
	1011HR-2M10	2	11	10	25	105	0.4~0.5	0.06
	1011HR-2L10	2	11	10	35	120	0.4~0.5	0.07
	1012HR-3S10	3	12	10	20	80	0.4~0.5	0.05
	1012HR-3M10	3	12	10	25	105	0.4~0.5	0.06
	1012HR-3L10	3	12	10	35	120	0.4~0.5	0.07
	1012HR-3S12	3	12	12	20	80	0.4~0.5	0.06
	1012HR-3M12	3	12	12	25	105	0.4~0.5	0.08
	1012HR-3L12	3	12	12	35	120	0.4~0.5	0.09
	1013HR-3S12	3	13	12	20	80	0.4~0.5	0.06
	1013HR-3M12	3	13	12	25	105	0.4~0.5	0.09
	1013HR-3L12	3	13	12	40	120	0.4~0.5	0.10
	1014HR-3S12	3	14	12	20	80	0.4~0.5	0.07
	1014HR-3M12	3	14	12	25	105	0.4~0.5	0.09
	1014HR-3L12	3	14	12	40	120	0.4~0.5	0.10

#### Available inserts




		Cei	rmet						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LPMT	040210R-MF									•	•				•	•				
	040220R-MF									•	•				•	•				
LPMW	040210R								•	•					•					E12
	040220R								•	•					•					E13
LPEW	040210R								•	•					•					
	040220R								•	•					•					





### HFMS1000 @

















• AR: -4° • RR: -6°~-3°

(mm)

	Designation	©	ØD	Ød	Q	L	ар	kg
HFMS	1015HR-4S12	4	15	12	20	80	0.4~0.5	0.07
	1015HR-4M12	4	15	12	25	105	0.4~0.5	0.09
	1015HR-4L12	4	15	12	40	120	0.4~0.5	0.11
	1016HR-4S16	4	16	16	20	80	0.4~0.5	0.11
	1016HR-4M16	4	16	16	25	105	0.4~0.5	0.14
	1016HR-4L16	4	16	16	40	120	0.4~0.5	0.16
	1017HR-4S16	4	17	16	20	80	0.4~0.5	0.11
	1017HR-4M16	4	17	16	25	105	0.4~0.5	0.15
	1017HR-4L16	4	17	16	40	120	0.4~0.5	0.17
	1018HR-4S16	4	18	16	20	80	0.4~0.5	0.11
	1018HR-4M16	4	18	16	25	105	0.4~0.5	0.15
	1018HR-4L16	4	18	16	40	120	0.4~0.5	0.17
	1019HR-4S16	4	19	16	20	80	0.4~0.5	0.12
	1019HR-4M16	4	19	16	25	105	0.4~0.5	0.16
	1019HR-4L16	4	19	16	40	120	0.4~0.5	0.18
	1020HR-4S20	4	20	20	20	80	0.4~0.5	0.17
	1020HR-4M20	4	20	20	25	105	0.4~0.5	0.22
	1020HR-4L20	4	20	20	40	120	0.4~0.5	0.26
	1020HR-5S20	5	20	20	20	80	0.4~0.5	0.17
	1020HR-5M20	5	20	20	25	105	0.4~0.5	0.23
	1020HR-5L20	5	20	20	40	120	0.4~0.5	0.27
	1021HR-5S20	5	21	20	20	80	0.4~0.5	0.17
	1021HR-5M20	5	21	20	25	105	0.4~0.5	0.23
	1021HR-5L20	5	21	20	40	120	0.4~0.5	0.27

#### Available inserts




		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LPMT	040210R-MF									•	•				•	•				
	040220R-MF									•	•				•	•				
LPMW	040210R								•	•					•					E12
	040220R								•	•					•					E13
LPEW	040210R								•	•					•					
	040220R								•	•					•					

Specification			
	Screw	Wrench	
Ø15~Ø21	FTKA01842	TW06S-A	



### HFMM new



















(mm)

D	esignation	0	ØD	Ød	Ød <sub>1</sub>	Q	L	М	ар	kg
HFMM	1008HR-M06	1	8	9.5	6.5	17	32	M06	0.4~0.5	0.01
	1010HR-M06	2	10	9.5	6.5	17	32	M06	0.4~0.5	0.01
	1011HR-M06	2	11	9.5	6.5	17	32	M06	0.4~0.5	0.01
	1012HR-M06	3	12	11	6.5	19	34	M6B	0.4~0.5	0.01
	1013HR-M06	3	13	11	6.5	19	34	M6B	0.4~0.5	0.01
	1016HR-M08	4	16	14.5	8.5	22	39	M08	0.4~0.5	0.03
	1017HR-M08	4	17	14.5	8.5	22	39	M08	0.4~0.5	0.03
	1020HR-M10	5	20	18	10.5	25	46	M10	0.4~0.5	0.06
	1021HR-M10	5	21	18	10.5	25	46	M10	0.4~0.5	0.06
	1025HR-M12	6	25	23	12.5	27	51	M12	0.4~0.5	0.11
	1026HR-M12	6	26	23	12.5	27	51	M12	0.4~0.5	0.11
	1030HR-M16	7	30	29	17	30	60	M16	0.4~0.5	0.17
	1032HR-M16	8	32	29	17	30	60	M16	0.4~0.5	0.18
	1033HR-M16	8	33	29	17	30	60	M16	0.4~0.5	0.18

#### Available inserts



						_														
			met	Coated								Uncoated								
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LPMT	040210R-MF									•	•				•	•				
	040220R-MF									•	•				•	•				
LPMW	040210R								•	•					•					E12
	040220R								•	•					•					E13
LPEW	040210R								•	•					•					
	040220R								•	•					•					

#### Available adaptor

	Designation	Available adaptor		
HFMM	1008HR-M06			
	1010HR-M06	MAT-M06		
	1011HR-M06	IVIA I-IVIOO		
	1012HR-M06			
	1013HR-M06			
	1016HR-M08	MAT-M08		
	1017HR-M08	IVIA I -IVIU8		

	Designation	Available adaptor
HFMM	1020HR-M10	MAT-M10
	1021HR-M10	IVIAT-IVITO
	1025HR-M12	MAT-M12
	1026HR-M12	IVIAT-IVITZ
	1030HR-M16	
	1032HR-M16	MAT-M16
	1033HR-M16	

Designation : HFMM1008HR-M06 Modular head threading measure size (M06)

П

Adaptor spec.: MAT-M06-020-S10S Adaptor threading measure (M06)

#### Parts

Specification	Screw	Wrench
Ø8~Ø10 Ø11~Ø33	FTKA01840 FTKA01842	TW06S-A



### Е


#### **Technical Information for HRMDouble**

HRMD is more economical due to the use of 6 cutting-edges compared to HRM tool with a 3-edge positive insert

### **HRMDouble**

- HRMD is more economical due to the use of 6 cutting-edges compared to HRM tool with a 3-edge positive insert
- High-rake angle cutting-edge and chip breaker reduces cutting load
- Negative geometry has been designed for rigidity of cutting-edge and double-sided function
- Screw on system and stable support achieves strong clamping force
- Unique insert design for high feed and multifunctional machining
- HRMD insert with symmetrical cutting-edge is applicable for both R and L type machining

#### Features of insert



#### Nose-R

- Security of rigid edge in ramping pocket machining
- Round edge suitable for high feed rates insert geometry
- · Possible to use R/L type machining

#### **8** Minor cutting-edge

- Improvement of surface roughness in high feed machining
- Special design for decreasing thrust force
- Symmetrical insert design for R/L type tool

#### Clamping surface

- · Design for stable clamping
- · Prevention of friction by chip

#### Ohip breaker

- Reduction of cutting load due to High-rake angle
- Improvement of chip flow and evacuation in various applications
- Prevention of damage on clamping face of insert

#### Major cutting-edge

- · Symmetrical design insert for R/L type tool
- Superior cutting performance due to high rake angle cutting-edge
- · Low cutting resistance in high feed
- Special design for decreasing thrust force

#### Features of cutter



#### Inner coolant system

- Improvement of chip control and evacuation
- Longer tool life due to reduced cutting temperature

#### Simple screw on system


- · Strong clamping of screw on system
- Convenient clamping system
- Wide chip pocket for better chip evacuation


#### 3-surface constrained system

- Strong clamping system
- Stable clamping system against different cutting resistances in various machining applications


#### Code system

Cutter






#### · Modular head



#### Modular adaptor






# E Technical Information for HRMDouble

#### Corner R programming

Designation	Cutting of	condition	Approx. R (mm)			
	Max.ap (mm)	Max.fz (mm/t)	Input. R	Uncut		
WNMX060312ZNN-	1.0	1.2	1.8	0.4		
WNMX09T316ZNN-□□	1.5	2.0	2.5	0.6		
WNMX130520ZNN-□□	2.0	3.0	3.0	0.8		
<b>WNMX160720ZNN-</b> □□	2.5	3.5	3.5	1.2		


·Information for uncut part by using "Input.R" for CAM program




 $\cdot$  Uncut part can be changed by poor machine condition or weak clamp of workpiece, etc


#### Interference prevent system

Designation	ØD (mm)	Ød (mm)	t (mm)
HRMDS0617HR-2□16	17	16	1
HRMDS0618HR-2□16	18	16	2
HRMDS0621HR-2□20	21	20	1
HRMDS0626HR-3□25	26	25	1
HRMDS0633HR-4□32	33	32	1
HRMDS0926HR-2□25	26	25	1
HRMDS0933HR-3□32	33	32	1
HRMDS0935HR-4□32	35	32	3
HRMDS0940HR-4□32	40	32	8
HRMDS0950HR-5□32	50	32	18
HRMDS0950HR-5□40	50	40	10
HRMDS0950HR-5□42	50	42	8
HRMDS1333HR-3□32	33	32	1
HRMDS1335HR-4□32	35	32	3
HRMDS1340HR-4□30	40	30	8
HRMDS1350HR-4□32	50	32	18
HRMDS1350HR-4□40	50	40	10
HRMDS1350HR-4□42	50	42	8
HRMDS1363HR-5□32	63	32	31
HRMDS1363HR-5□40	63	40	23
HRMDS1363HR-5□42	63	42	21



#### Ramping & helical cutting technical data





 $<sup>\</sup>bullet \text{ The side clearance prevents to interference between tool and workpiece even in deep hole machining } \\$ 

$$Lmin = \frac{ap}{tan \, a^{\circ}} \, (mm)$$

 $\emptyset Dc = \emptyset Dh - \emptyset D$ 

ØDc = Tool pass of tool center

ØDh = Desirable hole diameter on workpiece

 $\emptyset D = Tool dia.$ 

• Adjust feed to under 70% of Recommended cutting condition when ramping & helical cutting


• In helical ramping, max. cutting depth per 1 helical revolution of cutter should not exceed max. cutting depth as per insert size

• in ramping, max. cutting depth for 1 ramping process should not exceed max. depth of cut as per used insert size

	To all dia CCD	Efficient cutting		Ramping		Helical r	amping
Designation	Tool dia. ØD (mm)	diameter ØDe (mm)	Max. ap (mm)	Max. angle α°	Cutting Length Lmin (mm)	Dh Min. Cutting diameter (mm)	Dh Max. Cutting diameter (mm)
HRMDS0616HR	16	9.5	1	4.8	11	23.8	29.6
HRMDS0617HR	17	10.5	1	4.1	13	25.8	31.6
HRMDS0618HR	18	11.5	1	3.5	16	27.8	33.6
HRMDS0620HR	20	13.5	1	2.5	22	31.8	37.6
HRMDS0621HR	21	14.5	1	2.2	26	33.8	39.6
HRMDS0625HR	25	18.5	1	1.3	44	41.8	47.6
HRMDS0626HR	26	19.5	1	1.2	47	43.8	49.6
HRMDS0632HR	32	25.5	1	0.6	95	55.8	61.6
HRMDS0633HR	33	26.5	1	0.5	114	57.8	63.6
HRMDS0925HR	25	15.4	1.5	5.4	15.8	37.6	46.8
HRMDS0926HR	26	16.4	1.5	5.0	17.0	39.6	48.8
HRMDS0930HR	30	20.4	1.5	3.9	22.0	47.6	56.8
HRMDS0932HR	32	22.3	1.5	3.5	24.5	51.6	60.8
HRMDS0933HR	33	23.3	1.5	3.3	25.8	53.6	62.8
HRMDS0935HR	35	25.4	1.5	3.0	28.3	57.6	66.8
HRMDS0940HR	40	30.2	1.5	2.5	34.5	67.6	76.8
HRMDS0950HR	50	40.2	1.5	1.8	47.0	87.6	96.8
HRMDS1332HR	32	19.3	2	5.7	20.0	47	60
HRMDS1333HR	33	20.3	2	5.4	21.3	49	62
HRMDS1335HR	35	22.3	2	4.8	24.0	53	66
HRMDS1340HR	40	27.2	2	3.7	30.7	63	76
HRMDS1350HR	50	37	2	2.6	44.0	83	96
HRMDS1363HR	63	50	2	1.9	61.3	109	122
HRMDCM09040HR	40	30.2	1.5	2.5	34.5	67.6	76.8
HRMDCM09050HR	50	40.2	1.5	1.8	47.0	87.6	96.8
HRMDCM09063HR	63	53.1	1.5	1.4	63.3	113.6	122.8
HRMDC(M)09080HR	80	70.1	1.5	1.0	84.5	147.6	156.8
HRMDC(M)09100HR	100	90	1.5	0.8	109.5	187.6	196.8
HRMDCM13050HR	50	37	2	2.6	44.0	83	96
HRMDCM13063HR	63	50	2	1.9	61.3	109	122
HRMDC(M)13080HR	80	66.9	2	1.4	84.0	143	156
HRMDC(M)13100HR	100	86.9	2	1.0	110.7	183	196
HRMDC(M)13125HR	125	111.9	2	0.8	144.0	233	246
HRMDC(M)16080HR	80	63.3	2.5	1.4	102	138	156
HRMDC(M)16100HR	100	83.3	2.5	1	143	178	196
HRMDC(M)16125HR	125	108.3	2.5	0.7	204	228	246
HRMDC(M)16160R	160	143.3	2.5	0.5	286	298	316
HRMDC(M)16200R	200	183.3	2.5	0.3	477	378	396
HRMDC(M)16250R	250	233.3	2.5	0.2	716	478	496
HRMDC(M)16315R	315	298.3	2.5	0.1	1432	608	626

#### Uses





### **Technical Information for HRMDouble**

#### Recommended cutting condition

ISO	Work	piece	Material	Grades	Cutting speed, vc (m/min)
		Low carbon steel	SUM22, C = 0.1~25	PC5300	280
		Low carbon steer	30IVI22, C = 0.1~25	PC5400	245
	Carbon steel	General carbon steel	C = 0.30~55	PC5300	255
	Carbon Steel	General carbon steel	C = 0.50~55	PC5400	220
		High carbon steel	C = 0.55~80	PC5300	240
		Tiigii carboii steel	0 = 0.55~60	PC5400	205
Р		_	SCM415(H), SCM420, SCM440	PC5300	195
	Low alloy steel		30W413(H), 30W420, 30W440	PC5400	170
	(Alloy constituent < 5%)	Hardened		PC5300	115
		rialderied		PC5400	100
		Annealed	SKD61	PC5300	150
	High alloy steel	Ailliealeu	SKD01	PC5400	130
	(Alloy constituent > 5%)	Hardened	SKH51, SKH55	PC5300	120
		rialdelled	3KH31, 3KH33	PC5400	105
		Ferritic / Martensitic	SUS410, SUS420, SUS430	PC5300	160
		remuc/iviantenside	303410, 303420, 303430	PC5400	135
М	Stainless steel	Austenitic	SUS303, SUS304, SUS316	PC5300	130
IVI	Stairness steel	Austernite	303303, 303304, 303310	PC5400	110
		Duplex (Austenitic / Ferrictic)	F51	PC5300	100
		Duplex (Austerlitic / Ferrictic)	F51	PC5400	85
		Low tensile	GC200, GC250	PC5300	170
	Gray cast iron	Low terisile	GC200, GC250	PC5400	150
	Gray Cast Iron	Hight tensile	GC300, GC350	PC5300	150
K		Hight tensile	GC300, GC330	PC5400	130
_ ^		Ferric	GCD400, GCD500	PC5300	170
	Ductile cast iron	Femic	GCD400, GCD300	PC5400	150
	Ductile cast iron	Pearlitic	GCD600, GCD700	PC5300	150
		Feamilic	GCD000, GCD700	PC5400	130
	Fe Base	_	Incoloy	PC5300	60
	re base	-	Incoloy	PC5400	50
	Ni Base	_	Inconel, Nimonic, Hastelloy	PC5300	55
	NI Dase		inconer, Minoriic, Hasterloy	PC5400	45
S	Co Base	_	Stelite	PC5300	25
- 0	OU Dase	_	Otelite	PC5400	20
			Pure Ti	PC5300	130
	Titanium alloys	_	I UIC II	PC5400	105
	Titaliiuiii alioys	_	Alloy(TiAl6V4)	PC5300	65
			Alloy(TIAIOV+)	PC5400	55

#### Machining example



#### SM45C (HRC22)

■ Cutting conditions  $vc = 283 \text{ m/min } (1,803^{-1})$ 

fz = 1.4 mm/toothvf = 10,097 mm/min  $ap = 0.8 \, mm$ 

ae = 35 mm Coolant: Dry, Machining: Copying Machine: Horizontal MCT Overhang of tool: 250 mm

■ Tools Insert WNMX130520ZNN-MM (PC3500) Holder HRMDCM13050HR-4

> 10% Increased productivity 80% Reduced tool cost

→ In comparing HRMD with our competitor using the same cutting conditions, the cutting speed of HRMD was higher with the same depth of cut (ap×ae), the cycle time was reduced by 40% and the tool life was increased to over 60%. HRMD is economically more efficient due to the use of 6 cutting-edges compared to EDNW type with positive insert



#### STS304

■ Cutting conditions  $vc = 130 \text{ m/min } (414^{-1})$ fz = 1.2 mm/toothvf = 2,981 mm/min ap = 1.0 mm, ae = 80 mm Coolant: Wet, Machining:

Facing and Slotting Machine: Vertical MCT Overhang of tool: 250 mm ■ Tools Insert WNMX130520ZNN-MM (PC3545) Holder HRMDCM13100HR-6

> 80% Increased productivity 25% Reduced tool cost


→ In comparing HRMD with our competitor using the same cutting conditions, the cutting speed of HRMD was higher with the same depth of cut (ap×ae), the cycle time was reduced by 80% and the tool life was same, but HRMD is economically more efficient due to the use of 6 cutting-edges compared to SDKN type with positive insert





## HRMDC(M)09















14° • AR: -7° • RR: -12°~-18°

(mm)

D	esignation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	O kg	Bolt
HRMDCM	09040HR-3	3	40	34	16	9	14	8.4	5.6	19	40	1.5	0.2	SB0825
	09040HR-4	4	40	34	16	9	14	8.4	5.6	19	40	1.5	0.2	300023
	09050HR-4	4	50	42	22	11	18	10.4	6.3	21	40	1.5	0.3	SB1025
	09050HR-5	5	50	42	22	11	18	10.4	6.3	21	40	1.5	0.3	361023
	09063HR-5	5	63	49	22	11	18	10.4	6.3	21	40	1.5	0.5	SB1025
	09063HR-6	6	63	49	22	11	18	10.4	6.3	21	40	1.5	0.5	361023
	09080HR-6	6	80	57	27	14	20	12.4	7	23	50	1.5	1.1	SB1230
	09080HR-7	7	80	57	27	14	20	12.4	7	23	50	1.5	1.1	361230
	09100HR-7	7	100	67	32	18	26	14.4	8	25	50	1.5	1.7	SB1630
	09100HR-8	8	100	67	32	18	26	14.4	8	25	50	1.5	1.7	301030
HRMDC	09080HR-6	6	80	57	25.4	14	20	9.5	6	24	50	1.5	1.1	SB1230
	09080HR-7	7	80	57	25.4	14	20	9.5	6	24	50	1.5	1.1	301230
	09080HR-31.75-6	6	80	67	31.75	18	26	12.7	8	32	63	1.5	1.5	SB1630
	09080HR-31.75-7	7	80	67	31.75	18	26	12.7	8	32	63	1.5	1.5	361630
	09100HR-7	7	100	67	31.75	18	26	12.7	8	32	63	1.5	2.1	SB1630
	09100HR-8	8	100	67	31.75	18	26	12.7	8	32	63	1.5	2.1	361630

#### Available inserts








new	new	

		Cer	met		Coated Uncoated														
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
WNMX	09T316ZNN-MF									•				•	•				
	09T316ZNN-ML													•	•				E30
	09T316ZNN-MM							•	•	•		•		•	•				

#### Available arbors

1	Designation	NC arbors						
HRMDCM	09040HR-	BT -FMC16-						
	09040⊓R-∐	SK□□-FMC16-□□						
	09050HR-	BT□□-FMC22-□□						
	09063HR-	SK□□-FMC22-□□						
	09080HR-	BT□□-FMC27-□□						
	09000⊓n-□	SK□□-FMC27-□□						
	09100HR-	BT□□-FMC32-□□						
	09100HH-	SK□□-FMC32-□□						
HRMDC	09080HR-	BT□□-FMA25.4-□□						
	09000HH-	SK□□-FMA25.4-□□						
	09080HR-31.75-	BT□□-FMA31.75-□□						
	09100HR-	SK□□-FMA31.75-□□						

#### Bolt



Designation		Dimensions (mm)											
Designation	M	а	b	L	pitch								
SB0825	M08	13	8	25	1.25								
SB1025	M10	16	10	25	1.5								
SB1230	M12	18	12	30	1.75								
SB1630	M16	24	16	30	2.0								

Specification				
	Screw	Wrench		
Ø40~Ø100	FTKA0307	TW09S		

## **E** HRMDouble

## HRMDC(M)13




















(mm)

															(/
D	esignation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	E	F	ар	kg	Bolt
HRMDCM	13050HR-3	3	50	42	22	11	17	-	10.4	6.3	21	40	2	0.3	SB1025
	13050HR-4	4	50	42	22	11	17	-	10.4	6.3	21	40	2	0.3	SB1025
	13063HR-4	4	63	49	22	11	18	-	10.4	6.3	21	40	2	0.5	SB1025
	13063HR-5	5	63	49	22	11	18	-	10.4	6.3	21	40	2	0.5	361023
	13080HR-5	5	80	57	27	14	20	-	12.4	7	23	50	2	1	SB1230
	13080HR-6	6	80	57	27	14	20	-	12.4	7	23	50	2	1	361230
	13100HR-6	6	100	67	32	18	26	-	14.4	8	25	50	2	1.6	SB1630
	13100HR-7	7	100	67	32	18	26	-	14.4	8	25	50	2	1.6	361030
	13125HR-7	7	125	87	40	22	32	52	16.4	9	29	63	2	3.2	SB2040
	13125HR-8	8	125	87	40	22	32	52	16.4	9	29	63	2	3.2	MBA-M20
HRMDC	13080HR-5	5	80	57	25.4	14	20	-	9.5	6	24	50	2	1	SB1230
	13080HR-6	6	80	57	25.4	14	20	-	9.5	6	24	50	2	1	361230
	13080HR-31.75-5	5	80	67	31.75	18	26	-	12.7	8	32	63	2	1.4	SB1630
	13080HR-31.75-6	6	80	67	31.75	18	26	-	12.7	8	32	63	2	1.4	361030
	13100HR-6	6	100	67	31.75	18	26	-	12.7	8	32	63	2	2.1	SB1630
	13100HR-7	7	100	67	31.75	18	26	-	12.7	8	32	63	2	2.1	361030
	13125HR-7	7	125	87	38.1	22	32	52	15.9	10	35	63	2	3.3	SB2040
	13125HR-8	8	125	87	38.1	22	32	52	15.9	10	35	63	2	3.3	MBA-M20

#### Available inserts

WNMX-MF

WNMX-ML

WNMX-MM








		Cer	met	Coated Uncoated															
Designation			CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
WNMX	130520ZNN-MF													•	•				
	130520ZNN-ML													•	•				E30
	130520ZNN-MM							•		•		•	•	•					

#### Available arbors

	Designation	NC arbors
HRMDCM	400F0UD □	BT -FMC22-
	13050HR-□	SK□□-FMC22-□□
	13063HR-	BT□□-FMC22-□□
	13080HR-	SK□□-FMC27-□□
	13100HR-□	BT□□-FMC32-□□
	13100HR-	SK□□-FMC32-□□
	13125HR-□	BT□□-FMC40-□□
	13123NN	SK□□-FMC40-□□
HRMDC	13080HR-	BT□□-FMA25.4-□□
	13080HR-31.75-	SK□□-FMA25.4-□□
	13100HR-	BT□□-FMA31.75-□□
	13100Hr-	SK□□-FMA31.75-□□
	13125HR-□	BT□□-FMA38.1-□□
	13123NN*	SK□□-FMA38.1-□□

#### Bolt






Designation			Dime	nsions	(mm)			F:
Designation	М	а	b	b1	С	L	pitch	Fig.
SB1025	M10	16	10	-	-	25	1.5	1
SB1230	M12	18	12	-	-	30	1.75	1
SB1630	M16	24	16	-	-	30	2.0	1
SB2040	M20	30	20	-	-	40	2.5	1
MBA-M20	M20	50	14	20	27	30	2.5	2

Specification	6)		
	Screw	Wrench	
Ø50~Ø125	FTKA0412B	TW15S	

















																(mm)
Desig	gnation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	Е	F	ар	kg	Bolt	Fig.
HRMDC	16080HR-4	4	80	65	25.4 (27)	14	20	-	9.5 (12.4)	6 (7)	25 (23)	50	2.5	0.99	SB1230	_
(HRMDCM)	16080HR-5	5	80	65	25.4 (27)	14	20	-	9.5 (12.4)	6 (7)	25 (23)	50	2.5	0.91	301230	'
	16100HR-5	5	100	85	31.75 (32)	18	26	-	12.7 (14.4)	8	33 (25)	63 (50)	2.5	1.68	SB1630	4
	16100HR-6	6	100	85	31.75 (32)	18	26	-	12.7 (14.4)	8	33 (25)	63 (50)	2.5	1.64	301030	'
	16125HR-6	6	125	100	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	36 (29)	63	2.5	3.23	SB2040	4
	16125HR-7	7	125	100	38.1 (40)	22	32	52	15.9 (16.4)	10 (9)	36 (29)	63	2.5	3.24	MBA-M20	'
	16160R-7	7	160	107	50.8 (40)	-	90	-	19 (16.4)	11 (9)	38 (32)	63	2.5	3.73	MBA-M24	2
	16160R-8	8	160	107	50.8 (40)	-	90	-	19 (16.4)	11 (9)	38 (32)	63	2.5	3.77	IVIDA-IVIZ4	
	16200R-8	8	200	145	47.625 (60)	-	132	-	25.4 (25.7)	14	38	63	2.5	6.48		3
	16200R-10	10	200	145	47.625 (60)	-	132	-	25.4 (25.7)	14	38	63	2.5	6.61	-	3
	16250R-10	10	250	190	47.625 (60)	-	190	-	25.4 (25.7)	14	38	63	2.5	11.01		3
	16250R-12	12	250	190	47.625 (60)	-	190	-	25.4 (25.7)	14	38	63	2.5	11.04	-	3
	16315R-12	12	315	250	47.625 (60)	-	238	-	25.4 (25.7)	14	38	63	2.5	18.34		4
	16315R-14	14	315	250	47.625 (60)	-	238	-	25.4 (25.7)	14	38	63	2.5	18.35	-	4

#### Available inserts

( )Metric size



WNMX-MF



WNMX-ML




WNMX-MM

			Cer	met						Coa	ated						Ur	ncoat	ed	
	De	signation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	HOT	page
WI	XMX	160720ZNN-MF													•	•				
		160720ZNN-ML													•					E30
		160720ZNN-MM																		

#### Available arbors

Desig	nation	HRMDC	HRMDCM
HRMDC (HRMDCM)	16080HR-4 16080HR-5	BT□□-FMA25.4-□□	BT -FMC27-
(	16100HR-5 16100HR-6	BT□□-FMA31.75-□□	BT -FMC32-
	16125HR-6 16125HR-7	BT FMA38.1	BT -FMB40-
	16160R-7 16160R-8	BT -FMA50.8-	BT -FMC40-
	16200R-8 16200R-10 16250R-10 16250R-12 16315R-12 16315R-14	BT FMA47.625-	BT -FMB60-

#### Bolt




Designation			Dime	nsions	(mm)			Fi.e.
Designation	М	а	b	b1	С	L	pitch	Fig.
SB1025	M10	16	10	-	-	25	1.5	1
SB1230	M12	18	12	-	-	30	1.75	1
SB1630	M16	24	16	-	-	30	2.0	1
SB2040	M20	30	20	-	-	40	2.5	1
MBA-M20	M20	50	14	20	27	30	2.5	2
MBA-M24	M24	65	14	24	37	36	3.0	2

## E HRMDouble

## HRMDS06 new


















Designation ØD Ød Q L kg ар **HRMDS** 0616HR-2S16 2 16 16 30 110 1.0 0.15 0616HR-2M16 2 16 16 70 150 1.0 0.20 0616HR-2L16 2 16 16 100 200 1.0 0.26 0617HR-2S16 2 17 16 20 110 1.0 0.15 0617HR-2M16 2 17 16 20 150 1.0 0.21 0617HR-2L16 2 17 16 20 200 1.0 0.28 0618HR-2S16 2 18 16 20 110 1.0 0.15 0618HR-2M16 0.21 2 18 16 20 150 1.0 0618HR-2L16 20 200 0.28 2 18 16 1.0 0620HR-2S20 2 20 20 50 130 0.28 1.0 0620HR-2M20 2 20 20 100 180 1.0 0.38 0620HR-2L20 2 20 20 130 250 1.0 0.53 21 20 20 0.29 0621HR-2S20 2 130 1.0 0621HR-2M20 2 20 20 180 1.0 0.40 21 0621HR-2L20 2 21 20 20 250 1.0 0.57 0625HR-3S25 3 25 25 60 140 1.0 0.44 0625HR-3M25 3 25 25 80 180 1.0 0.57 0625HR-3L25 3 25 25 120 250 1.0 0.80 0626HR-3S25 3 26 25 30 140 1.0 0.46 0626HR-3M25 3 26 25 30 180 1.0 0.60 30 0626HR-3L25 3 26 25 250 1.0 0.84 70 0632HR-4S32 4 32 32 150 1.0 0.82 0632HR-4M32 32 100 1.0 1.10 4 32 200 0632HR-4L32 4 32 180 300 1.0 1.66 32 0633HR-4S32 4 33 32 40 200 1.0 1.14 0633HR-4M32 4 33 32 40 250 1.0 1.43

#### Available inserts

0633HR-4L32

4

WNMX-ML WNMX-MM WNMX-MF

32

40

300

1.0

33



		Cer	met	Coated Uncoated									ed						
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 1	page
WNMX	060312ZNN-MF													•	•				
	060312ZNN-ML													•	•				E30
	060312ZNN-MM							•	•	•				•	•				


#### Parts

Screw Wrench  Ø16~Ø33 ETNA02506 TW07S	Specification			
Ø16~Ø33 ETNA02506 TW07S		Screw	Wrench	
	Ø16~Ø33	ETNA02506	TW07S	

1.73

(mm)

















• AR: -7° • RR: -17°~-25°


(mm)

De	esignation	©	ØD	Ød	Q	L	ар	\(\rightarrow\) \(\left(\kg\)\)
HRMDS	0925HR-2S25	2	25	25	60	140	1.5	0.5
	0925HR-2M25	2	25	25	120	200	1.5	0.6
	0925HR-2L25	2	25	25	180	300	1.5	1
	0926HR-2S25	2	26	25	60	140	1.5	0.5
	0926HR-2M25	2	26	25	60	200	1.5	0.7
	0926HR-2L25	2	26	25	60	300	1.5	1
	0930HR-3S32	3	30	32	70	150	1.5	0.8
	0930HR-3M32	3	30	32	120	200	1.5	1
	0930HR-3L32	3	30	32	180	300	1.5	1.5
	0932HR-3S32	3	32	32	70	150	1.5	0.8
	0932HR-3M32	3	32	32	120	200	1.5	1.1
	0932HR-3L32	3	32	32	180	300	1.5	1.7
	0933HR-3S32	3	33	32	70	150	1.5	0.8
	0933HR-3M32	3	33	32	70	200	1.5	1.1
	0933HR-3L32	3	33	32	70	300	1.5	1.7
	0935HR-4S32	4	35	32	50	150	1.5	0.9
	0935HR-4M32	4	35	32	50	200	1.5	1.1
	0935HR-4L32	4	35	32	50	300	1.5	1.7
	0940HR-4S32	4	40	32	50	150	1.5	0.9
	0940HR-4M32	4	40	32	50	250	1.5	1.5
	0940HR-4L32	4	40	32	50	300	1.5	1.8
	0940HR-4S40	4	40	40	60	150	1.5	1.3

#### Available inserts




		met	Coated										Uncoated						
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
WNMX	09T316ZNN-MF									•				•	•				
	09T316ZNN-ML													•	•				E30
	09T316ZNN-MM							•	•	•		•		•	•				





















• AR: -7° • RR: -17°~-25°

(mm)

D	esignation	©	ØD	Ød	Q	L	ар	kg
HRMDS	0940HR-4M40	4	40	40	130	250	1.5	2.2
	0940HR-4L40	4	40	40	180	300	1.5	2.7
	0940HR-4S42	4	40	42	60	150	1.5	1.4
	0940HR-4M42	4	40	42	130	250	1.5	2.3
	0940HR-4L42	4	40	42	180	300	1.5	2.8
	0950HR-4S32	4	50	32	40	150	1.5	1.1
	0950HR-4M32	4	50	32	40	250	1.5	1.6
	0950HR-4L32	4	50	32	40	300	1.5	2
	0950HR-4S40	4	50	40	40	150	1.5	1.4
	0950HR-4M40	4	50	40	40	250	1.5	2.4
	0950HR-4L40	4	50	40	40	300	1.5	2.9
	0950HR-4S42	4	50	42	40	150	1.5	1.6
	0950HR-4M42	4	50	42	40	250	1.5	2.6
	0950HR-4L42	4	50	42	40	300	1.5	3.1
	0950HR-5S32	5	50	32	40	150	1.5	1.1
	0950HR-5M32	5	50	32	40	250	1.5	1.6
	0950HR-5L32	5	50	32	40	300	1.5	2
	0950HR-5S40	5	50	40	40	150	1.5	1.4
	0950HR-5M40	5	50	40	40	250	1.5	2.4
	0950HR-5L40	5	50	40	40	300	1.5	2.9
	0950HR-5S42	5	50	42	40	150	1.5	1.6
	0950HR-5M42	5	50	42	40	250	1.5	2.6
	0950HR-5L42	5	50	42	40	300	1.5	3.1


#### Available inserts

WNMX-ML WNMX-MM WNMX-MF

		Cer	met						Coa	ated						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
WNMX	09T316ZNN-MF									•				•	•				
	09T316ZNN-ML													•	•				E30
	09T316ZNN-MM							•	•	•		•		•	•				

Specification			
	Screw	Wrench	
Ø40~Ø50	FTKA0307	TW09S	

















• AR: -7°

• AR: -7°
• RR: -14°~-16°

(mm)

De	esignation	©	ØD	Ød	Q	L	ар	O kg
HRMDS	1332HR-2S32	2	32	32	70	150	2	0.8
	1332HR-2M32	2	32	32	120	200	2	1
	1332HR-2L32	2	32	32	180	300	2	1.6
	1333HR-2S32	2	33	32	70	150	2	0.8
	1333HR-2M32	2	33	32	70	200	2	1.1
	1333HR-2L32	2	33	32	70	300	2	1.7
	1335HR-2S32	2	35	32	50	150	2	0.8
	1335HR-2M32	2	35	32	50	200	2	1.1
	1335HR-2L32	2	35	32	50	300	2	1.7
	1340HR-3S32	3	40	32	50	150	2	0.8
	1340HR-3M32	3	40	32	50	250	2	1.4
	1340HR-3L32	3	40	32	50	300	2	1.7
	1340HR-3S40	3	40	40	60	150	2	1.2
	1340HR-3M40	3	40	40	130	250	2	2.1
	1340HR-3L40	3	40	40	180	300	2	2.6
	1340HR-3S42	3	40	42	60	150	2	1.4
	1340HR-3M42	3	40	42	130	250	2	2.3
	1340HR-3L42	3	40	42	180	300	2	2.7
	1350HR-3S32	3	50	32	50	150	2	1.1
	1350HR-3M32	3	50	32	50	250	2	1.7
	1350HR-3L32	3	50	32	50	300	2	2
	1350HR-3S40	3	50	40	50	150	2	1.5
	1350HR-3M40	3	50	40	50	250	2	2.4
	1350HR-3L40	3	50	40	50	300	2	2.9
	1350HR-3S42	3	50	42	50	150	2	1.6
	1350HR-3M42	3	50	42	50	250	2	2.6
	1350HR-3L42	3	50	42	50	300	2	3.1

#### Available inserts

WNMX-MF WNMX-ML WNMX-MM









		Cer	met						Coa	ated						Ur	icoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
WNMX	130520ZNN-MF													•	•				
	130520ZNN-ML													•	•				E30
	130520ZNN-MM							•	•	•		•	•	•	•				

Wrench
TW15S





















• AR: -7° • RR: -14°~-16°

(mm)

Designation   OD   Od   Q			ı						(11111)
1350HR-4M32	De	esignation	<b>©</b>	ØD	Ød	Q	L	ар	kg
1350HR-4L32	HRMDS	1350HR-4S32	4	50	32	50	150	2	1.1
1350HR-4S40         4         50         40         50         150         2         1.5           1350HR-4M40         4         50         40         50         250         2         2.4           1350HR-4L40         4         50         40         50         300         2         2.9           1350HR-4S42         4         50         42         50         150         2         1.6           1350HR-4M42         4         50         42         50         250         2         2.6           1350HR-4L42         4         50         42         50         300         2         3.1           1363HR-4L32         4         63         32         50         150         2         1.4           1363HR-4M32         4         63         32         50         250         2         2.1           1363HR-4M32         4         63         32         50         300         2         2.4           1363HR-4M40         4         63         40         50         150         2         1.8           1363HR-4M40         4         63         40         50         300         2		1350HR-4M32	4	50	32	50	250	2	1.7
1350HR-4M40		1350HR-4L32	4	50	32	50	300	2	2
1350HR-4L40         4         50         40         50         300         2         2.9           1350HR-4S42         4         50         42         50         150         2         1.6           1350HR-4M42         4         50         42         50         250         2         2.6           1350HR-4L42         4         50         42         50         300         2         3.1           1363HR-4S32         4         63         32         50         150         2         1.4           1363HR-4M32         4         63         32         50         250         2         2.1           1363HR-4L32         4         63         32         50         300         2         2.4           1363HR-4S40         4         63         40         50         150         2         1.8           1363HR-4W40         4         63         40         50         250         2         2.8           1363HR-4L40         4         63         42         50         300         2         3.2           1363HR-4S42         4         63         42         50         250         2		1350HR-4S40	4	50	40	50	150	2	1.5
1350HR-4S42		1350HR-4M40	4	50	40	50	250	2	2.4
1350HR-4M42		1350HR-4L40	4	50	40	50	300	2	2.9
1350HR-4L42       4       50       42       50       300       2       3.1         1363HR-4S32       4       63       32       50       150       2       1.4         1363HR-4M32       4       63       32       50       250       2       2.1         1363HR-4L32       4       63       32       50       300       2       2.4         1363HR-4S40       4       63       40       50       150       2       1.8         1363HR-4M40       4       63       40       50       250       2       2.8         1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       300       2       3.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5M92       5       63       32       50       300       2		1350HR-4S42	4	50	42	50	150	2	1.6
1363HR-4S32       4       63       32       50       150       2       1.4         1363HR-4M32       4       63       32       50       250       2       2.1         1363HR-4L32       4       63       32       50       300       2       2.4         1363HR-4S40       4       63       40       50       150       2       1.8         1363HR-4M40       4       63       40       50       250       2       2.8         1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       300       2       3.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5S40       5       63       32       50       300       2       2.3         1363HR-5M40       5       63       40       50       300       2		1350HR-4M42	4	50	42	50	250	2	2.6
1363HR-4M32       4       63       32       50       250       2       2.1         1363HR-4L32       4       63       32       50       300       2       2.4         1363HR-4S40       4       63       40       50       150       2       1.8         1363HR-4M40       4       63       40       50       250       2       2.8         1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       300       2		1350HR-4L42	4	50	42	50	300	2	3.1
1363HR-4L32       4       63       32       50       300       2       2.4         1363HR-4S40       4       63       40       50       150       2       1.8         1363HR-4M40       4       63       40       50       250       2       2.8         1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5L40       5       63       40       50       300       2       2.8         1363HR-5S42       5       63       40       50       300       2		1363HR-4S32	4	63	32	50	150	2	1.4
1363HR-4S40       4       63       40       50       150       2       1.8         1363HR-4M40       4       63       40       50       250       2       2.8         1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5H40       5       63       40       50       250       2       2.8         1363HR-5S42       5       63       42       50       300       2       3.2         1363HR-5S42       5       63       40       50       300       2		1363HR-4M32	4	63	32	50	250	2	2.1
1363HR-4M40       4       63       40       50       250       2       2.8         1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2		1363HR-4L32	4	63	32	50	300	2	2.4
1363HR-4L40       4       63       40       50       300       2       3.2         1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3.2		1363HR-4S40	4	63	40	50	150	2	1.8
1363HR-4S42       4       63       42       50       150       2       1.9         1363HR-4M42       4       63       42       50       250       2       3         1363HR-4L42       4       63       42       50       300       2       3.5         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-4M40	4	63	40	50	250	2	2.8
1363HR-4M42       4       63       42       50       250       2       3         1363HR-4L42       4       63       42       50       300       2       3.5         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-4L40	4	63	40	50	300	2	3.2
1363HR-4L42       4       63       42       50       300       2       3.5         1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-4S42	4	63	42	50	150	2	1.9
1363HR-5S32       5       63       32       50       150       2       1.5         1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-4M42	4	63	42	50	250	2	3
1363HR-5M32       5       63       32       50       250       2       2         1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-4L42	4	63	42	50	300	2	3.5
1363HR-5L32       5       63       32       50       300       2       2.3         1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-5S32	5	63	32	50	150	2	1.5
1363HR-5S40       5       63       40       50       150       2       1.8         1363HR-5M40       5       63       40       50       250       2       2.8         1363HR-5L40       5       63       40       50       300       2       3.2         1363HR-5S42       5       63       42       50       150       2       1.9         1363HR-5M42       5       63       42       50       250       2       3		1363HR-5M32	5	63	32	50	250	2	2
1363HR-5M40     5     63     40     50     250     2     2.8       1363HR-5L40     5     63     40     50     300     2     3.2       1363HR-5S42     5     63     42     50     150     2     1.9       1363HR-5M42     5     63     42     50     250     2     3		1363HR-5L32	5	63	32	50	300	2	2.3
1363HR-5L40     5     63     40     50     300     2     3.2       1363HR-5S42     5     63     42     50     150     2     1.9       1363HR-5M42     5     63     42     50     250     2     3		1363HR-5S40	5	63	40	50	150	2	1.8
1363HR-5S42     5     63     42     50     150     2     1.9       1363HR-5M42     5     63     42     50     250     2     3		1363HR-5M40	5	63	40	50	250	2	2.8
<b>1363HR-5M42</b> 5 63 42 50 250 2 3			-	63	40	50	300	2	3.2
			-						
<b>1363HR-5L42</b> 5 63 42 50 300 2 3.5			-				250		
		1363HR-5L42	5	63	42	50	300	2	3.5

#### Available inserts


WNMX-MF WNMX-ML WNMX-MM

		Cer	met						Coa	ted						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
WNMX	130520ZNN-MF													•	•				
	130520ZNN-ML													•	•				E30
	130520ZNN-MM							•	•	•		•	•	•	•				

Specification			
	Screw	Wrench	
Ø50~Ø63	FTKA0412B	TW15S	

## HRMDM06 @W















14° · AF

• AR: -7° • RR: -18°~-25°

(mm)

Des	signation	©	ØD	Ød	Ød <sub>1</sub>	Q	L	М	ар	kg \
HRMDM	0616HR-M08	2	16	14.5	8.5	25	42	M08	1.0	0.03
	0617HR-M08	2	17	14.5	8.5	25	42	M08	1.0	0.03
	0618HR-M08	2	18	14.5	8.5	25	42	M08	1.0	0.03
	0620HR-M10	2	20	18	10.5	30	51	M10	1.0	0.06
	0621HR-M10	2	21	18	10.5	30	51	M10	1.0	0.07
	0625HR-M12	3	25	23	12.5	35	59	M12	1.0	0.10
	0626HR-M12	3	26	23	12.5	35	59	M12	1.0	0.11
	0632HR-M16	4	32	29	17	40	67	M16	1.0	0.21
	0633HR-M16	4	33	29	17	40	67	M16	1.0	0.22

#### Available inserts



		Cer	met						Coa	ated						Ur	icoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
WNMX	060312ZNN-MF													•	•				
	060312ZNN-ML													•	•				E30
	060312ZNN-MM							•	•	•		•	•	•	•				

#### Available adaptor

Des	signation	Available adaptor
HRMDM	0616HR-M08	
	0617HR-M08	MAT- M08
	0618HR-M08	
	0620HR-M10	MAT- M10
	0621HR-M10	IVIAT-IVITU

Des	signation	Available adaptor
HRMDM	0625HR-M12	MAT- M12
	0626HR-M12	IVIAT- IVITZ
	0632HR-M16	MAT- M16
	0633HR-M16	IVIAT- IVITO


Designation : HRMDM0625HR-M12 Modular head threading measure size (M12)

Ш

Adaptor spec.: MAT-M12-030-S25S Adaptor threading measure (M12)

#### Parts

Arench
W07S






297

## HRMDM09

















(mm)

Des	signation	<b>(</b>	ØD	Ød	ød1	Q	L	M	ар	(kg)
HRMDM	0925HR-M12	2	25	23	12.5	35	59	M12	1.5	0.10
	0926HR-M12	2	26	23	12.5	35	59	M12	1.5	0.11
	0930HR-M16	3	30	29	17	40	67	M16	1.5	0.19
	0932HR-M16	3	32	29	17	40	67	M16	1.5	0.20
	0933HR-M16	3	33	29	17	40	67	M16	1.5	0.21
	0935HR-M16		35	29	17	40	67	M16	1.5	0.22
	0940HR-M16	4	40	29	17	40	67	M16	1.5	0.25

#### Available inserts

WNMX-MF	WNMX-ML	WNMX-MM
new	(ew)	

		Cer	met		Coated											Uncoated			
Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
WNMX	09T316ZNN-MF									•				•	•				
	09T316ZNN-ML													•	•				E30
	09T316ZNN-MM							•		•		•		•	•				

#### Available adaptor


	Designation	Available adaptor
HRMDM	0925HR-M12	MAT- M12
	0926HR-M12	MAI- WIZ
	0930HR-M16	
	0932HR-M16	
	0933HR-M16	MAT- M16
	0935HR-M16	
	0940HR-M16	

Designation: HRMDM0932HR-M16 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

## HRMDM13















• AR: -7° • RR: -18°~-25°

(mm)

Des	signation	©	ØD	Ød	ød1	Q	L	М	ар	kg
HRMDM	1332HR-M16	2	32	29	17	40	67	M16	2	0.20
	1333HR-M16	2	33	29	17	40	67	M16	2	0.20
	1335HR-M16	2	35	29	17	40	67	M16	2	0.22
	1340HR-M16	3	40	29	17	45	72	M16	2	0.26

#### Available inserts



		Cer	met	Coated											Uncoated				
Designation		CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	E H	page
WNMX	130520ZNN-MF													•	•				
	130520ZNN-ML													•	•				E30
	130520ZNN-MM							•	•	•		•	•	•	•				

#### Available adaptor

	Designation	Available adaptor
HRMDM	1332HR-M16	
	1333HR-M16	MATINAC
	1335HR-M16	MAT-M16
	1340HR-M16	


Designation : HRMDM1332HR-M16 Modular head threading measure size (M16)

- 11

Adaptor spec.: MAT-M16-120-S32T Adaptor threading measure (M16)

#### Parts

Screw Wrench	Specification
A0412B TW15S	Ø32~Ø40






299



## HRMC(M)13

















(mm)

Desiç	gnation	<b>(</b> )	ØD	ØD <sub>2</sub>	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	а	b	E	F	ар	kg	Bolt
HRMC	13050HR-3	3	50	47	22.225 (22)	11	16.4	8.0 (10.4)	5 (6.3)	20 (21)	50	2.0	0.4	SB1035
(HRMCM)	13050HR-4	4	50	47	22.225 (22)	11	16.4	8.0 (10.4)	5 (6.3)	20 (21)	50	2.0	0.4	SB1035
	13063HR-4	4	63	60	22.225 (22)	11	17	8.0 (10.4)	5 (6.3)	20 (21)	50	2.0	0.7	SB1035
	13080HR-5	5	80	76	31.75 (27)	18 (13)	26 (20)	12.7 (12.4)	8 (7)	32 (23)	70	2.0	1.6	SB16(12)45

( )Metric size

#### Available inserts

WDKT-MH




	Cerme		Coated Uncoated										ted				
Designation	CN2500	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	191	page
WDKT 130520ZDSR-MH						•	•	•	•	•		•	•				E29

#### Available arbors

Desig	nation	HRMDC	HRMDCM
HRMC	13050HR-3		DTCC FM000 CC
(HRMCM)	13050HR-4	BT□□-FMA22.225-□□	BT□□-FMC22-□□ SK□□-FMC22-□□
	13063HR-4		OKEET MOZZ EE
	13080HR-5	BT - FMA31.75- SK - FMA31.75-	BT -FMC27- SK -FMC27-

#### Bolt




Designation			Dime	nsions	(mm)			F:
Designation	M	а	b	b <sub>1</sub>	С	L	pitch	Fig.
SB1035	M10	16	10	-	-	35	1.5	1
SB1245	M12	18	12	-	-	45	1.75	1
SB1645	M16	24	16	-	-	45	2.0	1
SB2040	M20	30	20	-	-	40	2.5	1
MBA-M20	M20	50	14	20	27	30	2.5	2
MBA-M24	M24	65	14	24	37	36	3.0	2

Specification		2			San Cr	
	Screw	Clamp	Clamp screw	C-ring	Wrench	
Ø50~Ø80	FTGA0513-P	CHH4.5R1	CTX04513H	CR03	TW20-100	

## HRMC(M)15

















(mm)

Desig	ınation	0	ØD	ØD	Ød	Ød1	Ød2	а	b	E	F	ар	kg	Bolt
HRMC	15063HR-3	3	63	60	22.225 (22)	11	17	8.0 (10.4)	5 (6.3)	20 (21)	50	2.5	0.7	SB1035
(HRMCM)	15080HR-4	4	80	76	31.75 (27)	18 (13)	26 (20)	12.7 (12.4)	8 (7)	32 (23)	70	2.5	1.7	SB16(12)45
	15100HR-5	5	100	96	31.75 (32)	18	26	12.7 (14.4)	8 (8)	32 (26)	70	2.5	2.8	SB1645
	15100HR-6	6	100	96	31.75 (32)	18	26	12.7 (14.4)	8 (8)	32 (26)	70	2.5	3.2	SB1645
	15125HR-6	6	125	98	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	2.5	3.3	SB2040
	15160R-7	7	160	100	50.8 (40)	-	72	19.0 (16.4)	11 (9)	38 (35)	63	2.5	4.3	MBA-M24(M20)

( )Metric size

#### Available inserts







		Cer	met						Coa	ated						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
WDKT	150625ZDSR-MH									•	•	•		•	•				E29

#### Available arbors

Desig	gnation	HRMDC	HRMDCM
HRMC (HRMCM)	15063HR-3	BT□□-FMA22.225-□□	BT -FMC22- SK -FMC22-
	15080HR-4	BT□□-FMA31.75-□□	BT -FMC27- SK -FMC27-
	15100HR-5 15100HR-6	SK FMA31.75-	BT -FMC32- SK -FMC32-
	15125HR-6	BTFMA38.1 SKFMA38.1	BT -FMB40- BT -FMC40-
	15160R-7	BT□□-FMA50.8-□□	SK□□-FMC40-□□


#### Bolt






Designation			Dime	nsions	(mm)			F:
Designation	M	а	b	b <sub>1</sub>	С	L	pitch	Fig.
SB1035	M10	16	10	-	-	35	1.5	1
SB1245	M12	18	12	-	-	45	1.75	1
SB1645	M16	24	16	-	-	45	2.0	1
SB2040	M20	30	20	-	-	40	2.5	1
MBA-M20	M20	50	14	20	27	30	2.5	2
MBA-M24	M24	65	14	24	37	36	3.0	2

Specification		2			- Sanda
	Screw	Clamp	Clamp screw	C-ring	Wrench
Ø63~Ø160	FTGA0513-P	CHH5.5R1	CTX0515	CR04	TW20-100








## HRMS08/10

















(mm)

	Designation	©	ØD	Ød	Q	L	ар	kg
HRMS	0820HR-2S20	2	20	20	50	130	1.0	0.3
	0820HR-2M20	2	20	20	100	180	1.0	0.4
	0820HR-2L20	2	20	20	130	250	1.0	0.5
	0821HR-2S20	2	21	20	50	130	1.0	0.3
	0821HR-2M20	2	21	20	50	180	1.0	0.4
	0821HR-2L20	2	21	20	50	250	1.0	0.5
HRMS	1025HR-2S25	2	25	25	60	140	1.5	0.4
	1025HR-2M25	2	25	25	120	200	1.5	0.6
	1025HR-2L25	2	25	25	180	300	1.5	0.9
	1026HR-2S25	2	26	25	60	140	1.5	0.4
	1026HR-2M25	2	26	25	60	200	1.5	0.6
	1026HR-2L25	2	26	25	60	300	1.5	1.0
	1030HR-2S32	2	30	32	70	150	1.5	0.8
	1030HR-2M32	2	30	32	120	200	1.5	1.0
	1030HR-2L32	2	30	32	180	300	1.5	1.5

#### Available inserts

WDKT-MH




			Cer	met						Coa	ited						Ur	icoat	ed	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
08 type	WDKT	080316ZDSR-MH							•	•	•	•	•		•	•				F00
10 type	WDKT	10T320ZDSR-MH								•	•	•	•		•	•				E29

Specification		2				
	Screw	Clamp	Clamp screw	C-ring	Wrench	
Ø20~Ø21 (08 type)	FTNA0306	-	-	-	TW09P	
Ø25~Ø30 (10 type)	FTKA0408	CHH3.5R1	CTX03510	CR03	TW15S	



## HRMS13















AA • AR: 7

• AR: 7° • RR: -11°~-5°

(mm)

	Designation	$\odot$	ØD	Ød	Q	L	ар	kg
HRMS	1332HR-2S32	2	32	32	70	150	2.0	0.8
	1332HR-2M32	2	32	32	120	200	2.0	1.0
	1332HR-2L32	2	32	32	180	300	2.0	1.6
	1333HR-2S32	2	33	32	70	150	2.0	0.8
	1333HR-2M32	2	33	32	70	200	2.0	1.1
	1333HR-2L32	2	33	32	70	300	2.0	1.7
	1335HR-2S32	2	35	32	50	150	2.0	0.8
	1335HR-2M32	2	35	32	50	200	2.0	1.1
	1335HR-2L32	2	35	32	50	300	2.0	1.7
	1340HR-3S32	3	40	32	50	150	2.0	0.8
	1340HR-3M32	3	40	32	50	250	2.0	1.4
	1340HR-3L32	3	40	32	50	300	2.0	1.7
	1340HR-3S40	3	40	40	60	150	2.0	1.2
	1340HR-3M40	3	40	40	130	250	2.0	2.1
	1340HR-3L40	3	40	40	180	300	2.0	2.6
	1340HR-3S42	3	40	42	60	150	2.0	1.4
	1340HR-3M42	3	40	42	130	250	2.0	2.3
	1340HR-3L42	3	40	42	180	300	2.0	2.7


#### Available inserts

WDKT-MH



		Cei	rmet						Coa	ited						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
WDKT	130520ZDSR-MH							•	•		•	•		•	•				E29

Specification		(C)			Manak	
	Screw	Clamp	Clamp screw	C-ring	Wrench	
Ø32,33,35	FTGA0510-P	CHH4.5R1	CTX04513H	CR03	TW20	
Ø40	FTGA0512-P	CHH4.5R1	CTX04513H	CR03	TW20	








## HRMS15

















(mm)

	Designation	<b>(</b>	ØD	Ød	Q	L	ар	kg
HRMS	1550HR-3S32	3	50	32	50	150	2.5	1.0
	1550HR-3M32	3	50	32	50	250	2.5	1.6
	1550HR-3L32	3	50	32	50	300	2.5	1.9
	1550HR-3S40	3	50	40	50	150	2.5	1.4
	1550HR-3M40	3	50	40	50	250	2.5	2.3
	1550HR-3L40	3	50	40	50	300	2.5	2.8
	1550HR-3S42	3	50	42	50	150	2.5	1.5
	1550HR-3M42	3	50	42	50	250	2.5	2.5
	1550HR-3L42	3	50	42	50	300	2.5	3.0
	1563HR-4S32	4	63	32	50	150	2.5	1.3
	1563HR-4M32	4	63	32	50	250	2.5	1.9
	1563HR-4L32	4	63	32	50	300	2.5	2.2
	1563HR-4S40	4	63	40	50	150	2.5	1.7
	1563HR-4M40	4	63	40	50	250	2.5	2.6
	1563HR-4L40	4	63	40	50	300	2.5	3.1
	1563HR-4S42	4	63	42	50	150	2.5	1.8
	1563HR-4M42	4	63	42	50	250	2.5	2.8
	1563HR-4L42	4	63	42	50	300	2.5	3.3

#### Available inserts

WDKT-MH




	Cerme								Coa	ated						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	면	page
WDKT	150625ZDSR-MH									•	•	•		•	•				E29

Specification		2			No.	
	Screw	Clamp	Clamp screw	C-ring	Wrench	
Ø50~Ø63	FTGA0513-P	CHH5.5R1	CTX0515	CR04	TW20	

## HRMM08

















• AR: 7° • RR: -11°~-5°

(mm)

	Designation	0	ØD	Ød	ød1	Q	L	М	ар	
HRMM	0820HR-M10	2	20	18	10.5	30	51	M10	1	0.06
	0821HR-M10	2	21	18	10.5	30	51	M10	1	0.06
	0825HR-M12	3	25	23	12.5	35	59	M12	1	0.11
	0826HR-M12	3	26	23	12.5	35	59	M12	1	0.11
	0828HR-M12	3	28	23	12.5	35	59	M12	1	0.12
	0832HR-M16	4	32	29	17	40	67	M16	1	0.21
	0833HR-M16	4	33	29	17	40	67	M16	1	0.21
	0835HR-M16	4	35	29	17	40	67	M16	1	0.23
	0840HR-M16	5	40	29	17	40	67	M16	1	0.25

#### Available inserts

WDKT-MH



		Cer	met						Coa	ated						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
WDKT	WDKT 080316ZDSR-MH							•	•	•	•	•		•	•				E29


#### Available adaptor

	Designation	Available adaptor
HRMM	0820HR-M10	MAT MAO
	0821HR-M10	MAT-M10
	0825HR-M12	
	0826HR-M12	MAT-M12
	0828HR-M12	
	0832HR-M16	
	0833HR-M16	MAT MIC
	0835HR-M16 0840HR-M16	MAT-M16

Designation : HRMM0820HR-M10 Modular head threading measure size (M10)

Adaptor spec.: MAT-M10-030-S20S Adaptor threading measure (M10)

Specification						anor)	
	Screw	Clamp	Clamp screw	C-ring	Wrench	Wrench	
Ø20~Ø40	FTNA0306	-	-	-	-	-	








## HRMM10/13

















(mm)

	Designation	©	ØD	Ød	ød1	Q	L	M	ар	kg
HRMM	1025HR-M12	2	25	23	12.5	35	59	M12	1.5	0.1
	1026HR-M12	2	26	23	12.5	35	59	M12	1.5	0.1
	1030HR-M16	2	30	29	17	40	67	M16	1.5	0.2
	1032HR-M16	3	32	29	17	45	72	M16	1.5	0.26
	1035HR-M16	3	35	29	17	45	72	M16	1.5	0.23
	1040HR-M16	4	40	29	17	45	72	M16	1.5	0.27
HRMM	1332HR-M16	2	32	29	17	40	67	M16	2	0.17
	1333HR-M16	2	33	29	17	40	67	M16	2	0.17
	1335HR-M16	2	35	29	17	40	67	M16	2	0.19
	1340HR-M16	3	40	29	17	45	72	M16	2	0.24

#### Available inserts





			Cer	met						Coa	ited						Ur	ncoat	ed	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
10 type	WDKT	10T320ZDSR-MH								•	•	•	•		•	•				F00
13 type	WDKT	130520ZDSR-MH							•	•	•	•	•		•	•				E29

#### Available adaptor

	Designation	Available adaptor
HRMM	1025HR-M12	MAT-M12
	1026HR-M12	IVIAT-IVITZ
	1030HR-M16	
	1032HR-M16	MAT M4C
	1035HR-M16	MAT-M16
	1040HR-M16	
	1332HR-M16	
	1333HR-M16	MAT M40
	1335HR-M16	MAT-M16
	1340HR-M16	


Designation: HRMM1030HR-M16 Modular head threading measure size (M16)

Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M10)

Specification				7		ARCY	
	Screw	Clamp	Clamp screw	C-ring	Wrench	Wrench	
Ø25~Ø40 (10 type)	FTKA0408	CHH3.5R1	CTX03510	CR03	TW15S	-	
Ø32, 33, 35 (13 type)	FTGA0510-P	CHH4.5R1	CTX04513H	CR03	-	TW20	
Ø40 (13 type)	FTGA0512-P	CHH5.5R1	CTX04513H	CR03	-	TW20	

## THE

















(mm)

	Decimation	ØD	Ød	0			No. of	kg	Available	e inserts
	Designation	טט	νū	¥		ар	flute	/ kg \	Lower cutting-edge	External cutting-edge
THE	25R	25	25	55	120	25	2	0.4	APLT070304R 1z	SPMT060304 4z
	32R	32	32	70	145	40	2	0.5	ADLT150308R 1z	SDMT090308-MM 5z
	40R	40	42	88	175	54	2	1.3	ZPMT1504PPSR-MM 1z	SPMT120408-MM 5z
	50R		42	85	175	54	4	1.4	ZPMT1504PPSR-MM 2z	SPMT120408-MM 10z

#### Available inserts

	ADLT			APLT	•		SPMT	-ММ		S	PMT		S	DMT-N	ИM		ZPMT	-ММ		
	(5)								)					0			P			
		Cer	met						(	coate	d						Ur	icoat	ed	
	Designation	CN2500	CN30	NCM325	NCM335	NC5330	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
SPMT	060304			•																
SDMT	090308-MM										•				•					E04
SPMT	120408-MM										•				•					E05
APLT	070304R														•					E20 E27
ADLT	150308R			•											•					E33
ZPMT	1504PPSR-MM										•				•					

#### Recommended cutting condition

#### Grooving

Workpiece	Cutting (	Grades	
workpiece	vc (m/min)	fz (mm/t)	Grades
Р	90~140	0.05~0.2	PC5300
M	50~90	0.05~0.2	PC5300
K	70~120	0.05~0.25	PC5300

#### · Side cutting

Workpiece	Cutting C	Condition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Grades
Р	150 ~240	0.05~0.2	PC5300
M	90~150	0.05~0.2	PC5300
K	120~200	0.10~0.25	PC5300


Specification	Screw	Wrench	Wrench	
Ø25	ETNA02506	TW07P	-	
Ø32	ETNA0408	-	TW15S	
Ø40	ETNA0511	-	TW20S	
Ø50	ETNA0511	-	TW20S	

## **Technical Information for TP2P**


This milling tool series with its tangential clamping system increases stable machining and productivity, while improving perpendicularity

## Tangen-Pro TP2P 🚭

- Clamping stability gained through tangential clamping system and wedge-shaped inserts
- Excellent surface finish nearly perfect perpendicularity, and highly even flank surface compared to competitors' designs
- Improved productivity due to High-rake angles and sharp cutting-edges which lead to lower cutting resistance
   → Ideally suited for high speed and high feed machining



#### Features of insert




- Wedge type clamping area
- Clamping in wedge form on seats
   → Creates strong clamping force
- 4 High-rake angle chip breaker
- · High-rake angle applied
- Produces smooth chip flow
   → Extended insert life
- Convex projection
- · Improved chip evacuation
- Enhances rigidity

- Side hole (tangential type)
- · Higher clamping stability
- 1 High-rake angle cutting-edges
- Improves cutting performance while reducing cutting load
- 6 2-level flank relief surface
- 1st reverse positive relief surface enhances rigidity
- 2nd negative relief surface enables stable clamping
- → Improved chipping resistance and surface finish

#### Features of cutter

- Tangential clamping system, wedge-shaped inserts and wide seat area
- → Higher clamping stability
- → Lower vibrations and cutting resistance during machining
- Optimized H/D design with curved surface for smooth chip flow
  - → Excellent chip evacuation in ramping or deep shouldering



#### Application guideline for grade

10	/orkpiece		P	K	N
VV	rorkpiece	Carbon steel	Alloy steel	Cast iron	Aluminum
	High speed cutting	PC5300	PC5300	PC6510	H01
Grades	General cutting	PC5400	PC5300	PC6510	H01
	Interrupted cutting	PC5400	PC5400	PC5300	H01



#### Features of chip breaker

In	sert	Cutting-edge	Uses	Features
MA			Aluminum	Exclusive sharp cutting edge for aluminum machining ensures good chip flow due to surface buffing treatment and high welding resistance.
ML		Light cutting		Chip breaker design for low cutting resistance that provides excellent tool life and quality surface finishes in light cutting and hard-to-cut materials
ММ	MM General cutting		General cutting	Universal design for general shoulder milling operations, highly suitable in most applications

#### Recommended cutting condition

#### · LNKT08

	Workpiece	Grades	vc (m/min)	fz (mm/t)	Max. ap (mm)	Applicable insert
P	Chaol	PC5300	150~240	0.25~0.05	8.0	LNKT0804□□PNR-MM
	P Steel	PC5400	130~210	0.25~0.05	8.0	LINK I 0004 FIND-IVIIVI
K	Coot ivon	PC6510	100~250	0.25~0.05	8.0	LNKT0804∏PNR-ML
I.	Cast iron PC5300		100~200	0.25~0.05	8.0	LINK I 0804
N	Aluminum	H01	500~1000 0.25~0.05		8.0	LNKT0804□□PNR-MA

<sup>\*</sup> The above data refer to general cutting conditions and can be adjustable to the speed of 300m/min and the feed per tooth of 0.5 mm/t depending on user environment.

#### · LNKT14

	Workpiece	Grades	vc (m/min)	fz (mm/t)	Max. ap (mm)	Applicable insert
D	Steel	PC5300	150~240	0.25~0.05	12.7	LNKT1406□□PNR-MM
	PC540		130~210	210 0.25~0.05 12		LINK I 1400   FINE-IVIIVI
K	Cast iron	PC6510	100~250	0.25~0.05	12.7	LNKT1406□□PNR-ML
, K	Cast from	PC5300	100~200	0.25~0.05	12.7	LINKT 1406 PINA-WIL
N	Aluminum	H01	500~1000	0.25~0.05	12.7	LNKT1406□□PNR-MA

<sup>\*</sup> The above data refer to general cutting conditions and can be adjustable to the speed of 300m/min and the feed per tooth of 0.5 mm/t depending on user environment.


#### · LNKT17


	Workpiece	Grades	vc (m/min)	fz (mm/t)	Max. ap (mm)	Applicable insert
В	Ctool	PC5300	150~240	0.25~0.05	16.5	LNKT1707□□PNR-MM
	P Steel PC:		130~210	~210 0.25~0.05 16.5		
1/	Coativon	PC6510	100~250	0.25~0.05	16.5	- LNKT1707∏PNR-ML
K	Cast iron	PC5300	100~200	0.25~0.05	8.0	LINKTT/U/ PNR-ML
N	Aluminum	H01	500~1000	0.25~0.05	16.5	LNKT1707□□PNR-MA

<sup>\*</sup> The above data refer to general cutting conditions and can be adjustable to the speed of 300m/min and the feed per tooth of 0.5 mm/t depending on user environment.

#### Application area


▶ Higher speed and feed machining than competitor's increases machinability.





## **TP2PC(M)-LN08**























														(mm)
	Designation	0	ØD	ØD2	Ød	Ød1	Ød2	Ød3	а	b	Е	F	ар	kg
TP2PCM	040R-16-6-LN08	6	40	35	16	9	14	-	8.4	5.6	16	40	8.0	0.19
	040R-16-7-LN08	7	40	35	16	9	14	-	8.4	5.6	16	40	8.0	0.19
	050R-22-7-LN08	7	50	41	22	11	18	-	10.4	6.3	20	40	8.0	0.31
	050R-22-10-LN08	10	50	41	22	11	18	-	10.4	6.3	20	40	8.0	0.31
	063R-22-10-LN08	10	63	49	22	11	18	-	10.4	6.3	20	40	8.0	0.49
	063R-22-11-LN08	11	63	49	22	11	18	-	10.4	6.3	20	40	8.0	0.49

#### Available inserts







									_			-								
		Cer	rmet						C	coate	d						Ur	ncoat	ed	
	Designation			NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNKT	080404PNR-MA																			
	080408PNR-MA																			
	080412PNR-MA																			
	080416PNR-MA																			
	080404PNR-ML																			
	080408PNR-ML																			E11
	080412PNR-ML																			E11
	080416PNR-ML																			
	080404PNR-MM																			
	080408PNR-MM																			
	080412PNR-MM																			
	080416PNR-MM																			


#### Available arbors

	Designation	Available arbors
TP2PCM	040R-16-6-LN08	BT□□-FMC16-□□
	040R-16-7-LN08	DI LL-FMICIO-LL
	050R-22-7-LN08	
	050R-22-10-LN08	BT□□-FMC22-□□
	063R-22-10-LN08	DI
	063R-22-11-I N08	

Specification	
Screw	Wrench
Ø40~Ø63 FTKA02565	TW07S

## **TP2PC(M)-LN14**





















• AR: -6° • RR: -22°~-12°

/ <b></b>
mm

														(mm)
	Designation	(i)	ØD	ØD2	Ød	Ød1	Ød2	Ø <b>d</b> 3	а	b	E	F	ар	kg
TP2PCM	040R-16-4-LN14	4	40	35	16	9	14	-	8.4	5.6	19	40	12.7	0.19
	040R-16-5-LN14	5	40	35	16	9	14	-	8.4	5.6	19	40	12.7	0.19
	050R-22-5-LN14	5	50	42	22	11	18	-	10.4	6.3	20	40	12.7	0.29
	050R-22-6-LN14	6	50	42	22	11	18	-	10.4	6.3	20	40	12.7	0.29
	063R-22-6-LN14	6	63	49	22	11	18	-	10.4	6.3	20	40	12.7	0.49
	063R-22-8-LN14	8	63	49	22	11	18	-	10.4	6.3	20	40	12.7	0.49
	080R-27-7-LN14	7	80	57	27	14	20	35	12.4	7	23	50	12.7	0.94
	080R-27-10-LN14	10	80	57	27	14	20	35	12.4	7	23	50	12.7	0.94
	100R-32-8-LN14	8	100	70	32	18	28	45	14.4	8	28	63	12.7	1.73
	100R-32-13-LN14	13	100	70	32	18	28	45	14.4	8	28	63	12.7	1.73
	125R-40-9-LN14	9	125	90	40	22	32	54	16.4	9	30	63	12.7	2.98
	125R-40-17-LN14	17	125	90	40	22	32	54	16.4	9	30	63	12.7	3.04
TP2PC	080R-25.4-7-LN14	7	80	57	25.4	14	25	38	9.5	6	25	50	12.7	0.95
	080R-25.4-10-LN14	10	80	57	25.4	14	25	38	9.5	6	25	50	12.7	0.96
	100R-31.75-8-LN14	8	100	70	31.75	18	28	45	12.7	8	32	63	12.7	1.76
	100R-31.75-13-LN14	13	100	70	31.75	18	28	45	12.7	8	32	63	12.7	1.81
	125R-38.1-9-LN14	9	125	90	38.1	22	32	54	15.9	10	35	63	12.7	2.99
	125R-38.1-17-LN14	17	125	90	38.1	22	32	54	15.9	10	35	63	12.7	3.07

#### Available inserts







								•														
		Cermet			Coa	ated			Unco	oated				Cermet		(	Coat	ed			Uncoate	d
	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535		PC3700	PC6510 PC9530	PC9540 PC5300	PC5400 ST30A		page		Designation	CN2500 CN30	NC5330 NCM325	NCM545	PC2505 PC2510	PC3700	PC9530	PC5300	ST30A HOT	page
LNKT	140604PNR-MA											LNKT	140612PNR-ML									
	140608PNR-MA												140616PNR-ML									
	140612PNR-MA										E11		140604PNR-MM									F44
	140616PNR-MA										EII		140608PNR-MM									E11
	140604PNR-ML												140612PNR-MM									
	140608PNR-ML												140616PNR-MM									

#### Available arbors


	Designation	Available arbors
TP2PCM	040R-16-4-LN14	BT -FMC16-
	040R-16-5-LN14	BILL-FINCTO-LL
	050R-22-5-LN14	
	050R-22-6-LN14	BT -FMC22-
	063R-22-6-LN14	BILL-FIVICZZ-LL
	063R-22-8-LN14	
	080R-27-7-LN14	BT -FMC27-
	080R-27-10-I N14	DILL-FIVICZ/-LL

	Designation	Available arbors				
TP2PCM	100R-32-8-LN14	BT -FMC32-				
	100R-32-13-LN14	BILL-FIVIC32-LL				
	125R-40-9-LN14	BT -FMC40-				
	125R-40-17-LN14	BIFIVIC40				
TP2PC	080R-25.4-7-LN14	BT -FMA25.4-				
	080R-25.4-10-LN14	DIFIVIA25.4				
	100R-31.75-8-LN14	BT□□-FMA31.75-□□				
	100R-31.75-13-LN14	DILL-FIVIAS1./5-LL				
	125R-38.1-9-LN14	BT -FMA38.1-				
	125R-38.1-17-LN14	BILL-FIVIA38.1-LL				

Specification			
	Screw	Wrench	
Ø40 ~ Ø125	FTKA03510	TW15S	

## **TP2PC(M)-LN17**





















														(mm)
	Designation	0	ØD	ØD2	Ød	Ød1	Ød2	Ø <b>d</b> 3	а	b	Е	F	ар	kg
TP2PCM	040R-16-3-LN17	3	40	35	16	9	14	-	8.4	5.6	16	40	16.5	0.17
	040R-16-4-LN17	4	40	35	16	9	14	-	8.4	5.6	16	40	16.5	0.17
	050R-22-4-LN17	4	50	41	22	11	18	-	10.4	6.3	20	40	16.5	0.27
	050R-22-5-LN17	5	50	41	22	11	18	-	10.4	6.3	20	40	16.5	0.26
	063R-22-6-LN17	6	63	49	22	11	18	-	10.4	6.3	20	40	16.5	0.46
	063R-22-7-LN17	7	63	49	22	11	18	-	10.4	6.3	20	40	16.5	0.47
	080R-27-7-LN17	7	80	57	27	14	20	35	12.4	7	23	50	16.5	0.89
	080R-27-8-LN17	8	80	57	27	14	20	35	12.4	7	23	50	16.5	0.91
	100R-32-8-LN17	8	100	67	32	18	28	45	14.4	8	25	63	16.5	1.68
	100R-32-9-LN17	9	100	67	32	18	28	45	14.4	8	25	63	16.5	1.75
	125R-40-10-LN17	10	125	90	40	22	32	52	16.4	10	30	63	16.5	2.88
	125R-40-11-LN17	11	125	90	40	22	32	52	16.4	10	30	63	16.5	2.88
TP2PC	080R-25.4-7-LN17	7	80	57	25.4	14	20	35	9.5	6	25	50	16.5	0.92
	080R-25.4-8-LN17	8	80	57	25.4	14	20	35	9.5	6	25	50	16.5	0.93
	100R-31.75-8-LN17	8	100	67	31.75	18	28	45	12.7	8	32	63	16.5	1.73
	100R-31.75-9-LN17	9	100	67	31.75	18	28	45	12.7	8	32	63	16.5	1.73
	125R-38.1-10-LN17	10	125	90	38.1	22	32	52	15.9	9	35	63	16.5	3.06
	125R-38.1-11-LN17	11	125	90	38.1	22	32	52	15.9	9	35	63	16.5	2.91

#### Available inserts

LNKT-MA

LNKT-ML

LNKT-MM







							•													
		Cermet		Co	ated			Uncoated							Coate	d			Uncoated	
	Designation	CN2500 CN30	NC5330 NCM325 NCM335	22 22	PC2510 PC3700	PC9530	PC5300 PC5400	ST30A H01	page		Designation		NC5330 NCM325	NCM535 NCM535	PC2505 PC2510	PC6510	PC9530 PC9540	PC5300 PC5400	ST30A H01	page
LNKT	170704PNR-MA									LNKT	170716PNR-ML									
	170708PNR-MA										170720PNR-ML									
	170712PNR-MA										170704PNR-MM									
	170716PNR-MA								E11		170708PNR-MM							• •		E11
	170720PNR-MA																			LII
	170704PNR-ML										170712PNR-MM									
	170708PNR-ML						• •		1		170716PNR-MM									
	170712PNR-ML										170720PNR-MM									

#### Available arbors

	Designation	Available arbors
TP2PCM	040R-16-3-LN17	BT□□-FMC16-□□
	040R-16-4-LN17	BILL-FINICIO-LL
	050R-22-4-LN17	
	050R-22-5-LN17	BT□□-FMC22-□□
	063R-22-6-LN17	DILL-FIVICZZ-LL
	063R-22-7-LN17	
	080R-27-7-LN17	BT□□-FMC27-□□
	080R-27-8-LN17	


	Designation	Available arbors
TP2PCM	100R-32-8-LN17	BT□□-FMC32-□□
	100R-32-9-LN17	
	125R-40-10-LN17	BT□□-FMC40-□□
	125R-40-11-LN17	B11 WC40
TP2PC	080R-25.4-7-LN17	BT□□-FMA25.4-□□
	080R-25.4-8-LN17	BILL-FIVIA25.4-LL
	100R-31.75-8-LN17	BT□□-FMA31.75-□□
	100R-31.75-9-LN17	B11 WA31.75
	125R-38.1-10-LN17	BT□□-FMA38.1-□□
125R-38.1-11-LN17		

Screw	Wrench	
FTKA0412B	TW15S	
	Screw	Screw Wrench



## TP2PS-LN08



















(mm)

	Designation	0	ØD	Ød	Q	L	ар	(kg)
TP2PS	020R-2W20-120-LN08	2	20	20	30	120	8.0	0.25
	020R-3W20-120-LN08	3	20	20	30	120	8.0	0.25
	025R-3W25-120-LN08	3	25	25	30	120	8.0	0.39
	025R-4W25-120-LN08	4	25	25	30	120	8.0	0.39

#### Available inserts

LNKT-MA LNKT-ML LNKT-MM


			met		Coated Uncoated										ed					
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
LNKT	080404PNR-MA																			
	080408PNR-MA																			
	080404PNR-ML																			E11
	080408PNR-ML																			EII
	080404PNR-MM																			
	080408PNR-MM																			

Specification		
	Screw	Wrench
Ø16~Ø25	FTKA02565S	TW07S



## TP2PS-LN14





















• AR: -6° • RR: -21°~-18°

(mm)

	Designation	©	ØD	Ød	Q	L	ар	O kg
TP2PS	025R-2W25-130-LN14	2	25	25	40	130	12.7	0.41
	032R-3W32-130-LN14	3	32	32	40	130	12.7	0.69
	040R-3W32-130-LN14	3	40	32	40	130	12.7	0.75
	040R-4W32-130-LN14	4	40	32	40	130	12.7	0.76
	050R-4W32-130-LN14	4	50	32	40	130	12.7	0.85
	050R-5W32-130-LN14	5	50	32	40	130	12.7	0.84


#### Available inserts

			met		Coated Uncoated										ed					
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H0.1	page
LNKT	140608PNR-MA																			
	140608PNR-ML																			E11
	140608PNR-MM																			



## TP2PS-LN17





















• AR: -6° • RR: -26°~-18°

(mm)

	Designation	©	ØD	Ød	Q	L	ар	kg
TP2PS	032R-2W32-130-LN17	2	32	32	40	130	16.5	0.68
	032R-3W32-130-LN17	3	32	32	40	130	16.5	0.67
	040R-3W32-130-LN17	3	40	32	40	130	16.5	0.73
	040R-4W32-130-LN17	4	40	32	40	130	16.5	0.73
	050R-4W32-130-LN17	4	50	32	40	130	16.5	0.83
	050R-5W32-130-LN17	5	50	32	40	130	16.5	0.83

#### Available inserts

LNKT-MA LNKT-ML LNKT-MM

					-															
		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LNKT	170704PNR-MA																			
	170708PNR-MA																			
	170712PNR-MA																			
	170716PNR-MA																			
	170720PNR-MA																			
	170704PNR-ML																			
	170708PNR-ML											•			•	•				
	170712PNR-ML																			E11
	170716PNR-ML																			
	170720PNR-ML																			
	170704PNR-MM																			
	170708PNR-MM														•	•				
	170712PNR-MM																			
	170716PNR-MM																			
	170720PNR-MM																			

#### Parts

 Specification
 Wrench

 Screw
 Wrench

 Ø32~Ø50
 FTKA0412B
 TW15S



#### Longer tool life guaranteed thanks to the excellent cutting performance of our grades


## **Laser Mill**

- Long tool life has been achieved due to the excellent cutting performance of the insert grade
- Optimum machining of molds has been achieved with the MQL available system
- Easy clamping with simple screw on system
- Various holder line up: steel shank, carbide shank, modular type
- · High accuracy indexable endmills for mold finishing


**MQL System** 

- · Environmental friendly system
- · Decreased coolant cost
- · Lubrication of cutting-edge
- · Improved chip control property
- · Increased tool life & improved surface quality

#### Clamping system



- High precision (ground internal diameter) Run-out: 0.02 mm Accuracy of 'R part: below 0.01
- Through coolant system



#### Features



- · Six types of inserts are available with one holder
- · Single screw for clamping of insert: Easy clamping system
- · Various types of holders (Steel shank, Carbide shank, Modular type)
- · MQL applicable- environmentally responsible with longer tool life & improved surface quality.

#### LBS, LR Order-made items

## LBH-Ball

- · Helical cutting-edge
- Suitable for harder material with high feed

#### **LRH-Corner radius**



- · Helical cutting-edge
- · Variety of nose-R

#### LFH-High feed



- · Helical cutting-edge
- · Suitable for high feed

#### LCF-Chamfer



- Straight cutting-edge
- · Center drilling and chamfering

#### LBS-Ball type



- Straight cutting-edge
- Suitable for precise

steel



- · Straight cutting-edge
- · Variety of nose-R

#### Features of Laser Mill grades

#### PC2005

- · Extremely high hardness grade
- · The harmony between improved blade design and strong chip breaker
- · Optimized for machining heat-treated steel and high hardness steel


#### PC2010

- · High wear resistance and excellent toughness
- · The harmony between excellent thermal shock resistance and strong cutting-edges.
- Optimized for machining tool steel and pre-hardened steel

#### PC2015

- · High welding resistance and excellent toughness
- The harmony between tough grade and excellent cutting-edge design
- · Optimized for machining carbon steel

#### Application guideline per workpiece




steel



#### **Technical Information for Laser Mill**

#### Features of KF/KH chip breaker

- KF: Exclusive chip breaker for stable machining of carbon steel with its characteristics of high wear resistance at center part and improved blade design
- KH: Stronger insert with the combination of rake angle and relief angle that are ideal for machining high hardness workpiece



#### Recommended cutting condition

	Woi	Od	Chip	Recommended cutting conditions						
	ISO	Material	HB (HRC)	Grades	breaker	vc (m/min)	fz (mm/t)	ap (mm)	ae (mm)	
K	Gray cast iron	Gray cast iron         GC250         180 (8)         PC2015			130~210	0.2~0.5	0.07D	0.07D		
, r	Ductile cast iron	GCD600	250 (24)	PC2010	KF	130~210	0.2~0.5	0.07D	0.07D	
	Carbon steel	S20C~S50C	150	PC2005		170~250	0.2~0.5	0.07D	0.07D	
	Alloy steel	SCM21~SCM5H	270 (28)			130~210	0.1~0.3	0.7D	0.7D	
	Pre-	KP4M	300 (32)	DC0010				0.5D		
		NIMAX	370 (40)	PC2010	KII	100~160	0.1~0.3			
Р	hardened	CENA1	370 (40)	PC2015 PC210F	KH				0.5D	
Р	steel	NAK80	400 (43)	P0210F						
		STAVAX	510 (52)							
	High speed tool steel	SKH51~SKH59	550 (55)	DCCCC		80~130	0.1~0.2	0.3D	0.3D	
	Allow to all ato al	STD61 (Hot forging)	COO (CO)	PC2005 PC2010	KH	70.400	0.1.00	0.00	0.00	
	Alloy tool steel	STD11 (Cold forging)	630 (60)	FG2010		70~120	0.1~0.2	0.3D	0.3D	


Overhang	vc (m/min)	fz (mm/t)
Under 3D	100%	100%
3D~5D	70%	70%
5D~8D	60%	60%
8D~10D	50%	50%



## ιЕ


#### Cutting speed calculation formulas

Practical cutting speed	RPM
$VCe = \frac{\pi \times De \times n}{1000} (m/min)$	$n = \frac{\text{vce} \times 1000}{\pi \times \text{De}} \text{ (min}^{-1}\text{)}$
Feed per tooth	Feed per minute
$fz = \frac{vf}{z \times n} \text{ (mm/t)}$	$vf = fz \times z \times n \text{ (mm/min)}$
Chip removal amount	Power requirement
$Q = \frac{ap \times ae \times vf}{1000} \text{ (cm}^3/\text{min)}$	$Pkw = \frac{Q \times kc}{60 \times 102 \times \eta} (kW)$ $Php = \frac{Pc}{0.75} (hp)$



vc = Cutting speed (m/min)	Pkw = Power requirement (kW)			
vce = Practical cutting speed (m/min)	Php = Horsepower requirement (hp)			
<b>n</b> = Revolution per minute (min <sup>-1</sup> )	Q = Chip removal amount (cm³/min)			
D = Cutting diameter (mm)	ap = Depth of cut (mm)			
De = Actual diameter (mm)	ae = Width of cut (mm)			
vf = Feed per minute (mm/min)	kc = Specific cutting resistance (kg/mm²)			
fz = Feed per tooth (mm/t)	η = Mechanical efficiency (%)			
z = Number of tooth				

#### Practical cutting speed calculation formulas




- 2.  $\theta^\circ$ Using: Calculating cutting speed at P point (Cutting speed according to depth of cut when ramping)
- : Practical cutting speed  $vce = \frac{\pi \text{ Dsin } \theta \times n}{1000} \text{ (m/min)}$   $\theta = cost \left( \frac{D - 2ap}{1000} \right) + (900 \text{ cm}^2)$

Formula

- 3. In case of using ap: Calculating cutting speed at Q point
- : Pratical cutting speed  $vce = \frac{2\pi n \sqrt{ap (D - ap)}}{1000}$


Formula



#### Theoretical surface roughness

h (surface roughness) (μm)										
ae (mm) R (mm)	0.1	0.2	0.3	0.4	0.5	0.6	0.7	8.0	0.9	1.0
5	0.3	1.0	2.3	4.0	6.3	9.0	12.3	16.0	20.3	25.0
6	0.2	0.8	1.9	3.3	5.2	7.5	10.2	13.3	16.9	20.8
8	0.2	0.6	1.4	2.5	3.9	5.6	7.7	10.0	12.7	15.6
10	0.1	0.5	1.1	2.0	3.1	4.5	6.1	8.0	10.1	12.5
12.5	0.1	0.4	0.9	1.6	2.5	3.6	4.9	6.4	8.1	10.0
15	0.1	0.3	0.8	1.3	2.1	3.0	4.1	5.3	6.8	8.3
16	0.1	0.3	0.7	1.3	2.0	2.8	3.8	5.0	6.3	7.8

Formula of surface roughness: h (surface finish) =  $\frac{(ae)^2}{8R} \times 1000 \; (\mu m)$ 



#### Actual diameter data

ap ØD	Ø08	Ø10	Ø12	Ø16	Ø20	Ø25	Ø30	Ø32
0.1	1.8	2.0	2.2	2.5	2.8	3.2	3.5	3.6
0.2	2.5	2.8	3.1	3.6	4.0	4.5	4.9	5.0
0.3	3.0	3.4	3.7	4.3	4.9	5.4	6.0	6.2
0.5	3.9	4.4	4.8	5.6	6.2	7.0	7.7	7.9
1.0	5.3	6.0	6.6	7.7	8.7	9.8	10.8	11.1
1.5	6.2	7.1	7.9	9.3	10.5	11.9	13.1	13.5
2.0	6.9	8.0	8.9	10.6	12.0	13.6	15.0	15.5
2.5	7.4	8.7	9.7	11.6	13.2	15.0	16.6	17.2
3.0	7.7	9.2	10.4	12.5	14.3	16.2	18.0	18.7
3.5	7.9	9.5	10.9	13.2	15.2	17.3	19.3	20.0
4.0	8.0	9.8	11.3	13.9	16.0	18.3	20.4	21.2
5.0			11.8	14.8	17.3	20.0	22.4	23.2
6.0			12.0	15.5	18.3	21.4	24.0	25.0
7.0				15.9	19.1	22.4	25.4	26.5
8.0				16.0	19.6	23.3	26.5	27.7
10.0		•		•	20.0	24.5	28.3	29.7

#### **Technical Information for Laser Mill**

#### Performance evaluation

# PC2005 tool life test

# ■ Cutting conditions vc = 140 m/min fz = 0.15 mm/t ap = 1.2 mm ae = 1.2 mm Coolant (Air)

■ Tools Insert LBH120-KH (PC2005)

#### Chip removal rate (Q) = 1.6 cm<sup>3</sup>/min 2400 Chip removal volume (cm3) 2100 108 min machining Otot = 1736 cm³ 1800 1500 87 min machining 1200 Qtot = 1389 cm<sup>3</sup> 900 600 22 min machining 300 $Q_{tot} = 347 \text{ cm}^3$ 80 100 120 140 Cutting time (min)

Competitor A

PC2005







#### PC2010 tool life test

#### Pre-hardened steel (X40CrMnNiMo8-6-4)


Competitor B

High hardness heat-treated steel (X100CrMoV5 1, heat-treated HRC60)



#### ■ Cutting conditions vc = 276 m/min fz = 0.15 mm/t ap = 0.3 mm ae = 1.2 mm Wet

■ Tools Insert LBH120-KH (PC2010)









#### PC2015 tool life test


#### Carbon steel (C45)



#### ■ Cutting conditions

vc = 250 m/min fz = 0.35 mm/t ap = 0.3 mm ae = 0.3 mm Coolant (MQL)

■ Tools Insert LBH120 (PC2015)











#### Available inserts

	LBH (B	all type)	LRH (Corner	radius type)	LFH (High feed type)	LCF (Chamfer type)	LBS (Ball type)	LR (Corner	radius type)
Holders		d t		d	* d	d 900	r		d
	R accuracy ±0.005		Corner R ±0.015				R accuracy ±0.005	Corner F	R ±0.015
LBE080	LBH080 LBH080-KF LBH080-KH	LBH090 LBH090-KF LBH090-KH					LBS080 LBS090		
LBE100 LRE100	LBH100 LBH100-KF LBH100-KH	LBH110 LBH110-KF LBH110-KH	LRH100-R05 LRH100-R10 LRH100-R20	LRH110-R05	LFH100		LBS100 LBS110	LR100-R05 LR100-R10	LR100-R20 LR110-R05
LBE120 LRE120	LBH120 LBH120-KF LBH120-KH	LBH130 LBH130-KF LBH130-KH	LRH120-R05 LRH120-R10 LRH120-R20	LRH130-R05	LFH120		LBS120 LBS130	LR120-R05 LR120-R10	LR120-R20 LR130-R05
LBE160 LRE160	LBH160 LBH160-KF LBH160-KH	LBH170 LBH170-KF LBH170-KH	LRH160-R05 LRH160-R10 LRH160-R20 LRH160-R30	LRH170-R05	LFH160	LCF160-D90	LBS160 LBS170	LR160-R05 LR160-R10 LR160-R20	LR160-R30 LR170-R05
LBE200 LRE200	LBH200 LBH200-KF LBH200-KH	LBH210 LBH210-KF LBH210-KH	LRH200-R05 LRH200-R10 LRH200-R20 LRH200-R30	LRH210-R05	LFH200	LCF200-D90	LBS200 LBS210	LR200-R05 LR200-R10 LR200-R20	LR200-R30 LR210-R05
LBE250 LRE250	LBH250 LBH250-KF LBH250-KH	LBH260 LBH260-KF LBH260-KH	LRH250-R05 LRH250-R10 LRH250-R20 LRH250-R30	LRH260-R05	LFH250	LCF250-D90	LBS250 LBS260	LR250-R05 LR250-R10 LR250-R20	LR250-R30 LR260-R05
LBE300 LRE300	LBH300 LBH300-KF LBH300-KH		LRH300-R10 LRH300-R20 LRH300-R30	LRH310-R05	LFH300		LBS300 LBS310	LR300-R10 LR300-R20	LR300-R30 LR310-R05
LBE320 LRE320	LBH320 LBH320-KF LBH320-KH		LRH320-R10 LRH320-R20 LRH320-R30	LRH330-R20	LFH320		LBS320	LR320-R10 LR320-R20	LR320-R30

<sup>→</sup> Available inserts E08~E10

 $<sup>^{\</sup>star}$  LBH for general cutting, LBH-KF for carbon steel, and LBH-KH for high hardened steel.

## **Technical Information for GBE**

#### Long tool life due to high hardness grade

## **GBE**

- Indexable ball nose endmill for molds in medium & roughing applications
- Long tool life with high hardness grade
- Helical high accuracy cutting-edge
- Optimized mold machining process with our internal coolant system
- · Able to adjust to medium processing in middle & big roughing mold process
- Wide variety of holders in normal & long style holders

#### Code system

Flank support





- · High accuracy machining & large depth of cut applications
- Run-out: within 0.05 mm
- R accuracy: within 0.05 mm
- Various diameters (Ø16, Ø18, Ø20, Ø22, Ø25, Ø26, Ø28, Ø30, Ø32, Ø40, Ø50)
- · Minimal cutting resistance due to Helical cutting-edge
- · Anti-rotation of insert due to concave bottom & stable setting by flank support
- · Long tool life & better processing due to 2 cutting inserts
- · Better tool life with new grade




- Various diameters (Ø16, Ø18, Ø20, Ø22, Ø25, Ø26, Ø28, Ø30, Ø32, Ø40, Ø50)
- · Improved chip treatment with internal coolant (cutting-edge portion)
- · Long tool life & better processing
- · Easy insert setting with projection part to prevent vibration during processing

Concave bottom

# ΕE

#### How to set insert





Insert

- 1. Set the insert onto the holder projection seat
- 2. Push the insert into the pocket as shown by red arrows and screw down with wrench

**Parts** 

## Performance evaluation





## Cutting condition

Class.	Cutting speed (vc)	Feed (fz)	Depth of cut (ap)	Depth of cut (ae)	Workpiece	Etc.
Condition 1	150 m/min	0.15 mm/t	5 mm	8 mm	STD61 (HRC50)	Dest
Condition 2	100 m/min	0.1 mm/t	8 mm	8 mm	SCM440 (HRC20)	Dry

## Inserts/parts

Туре				9			No Markor
5.		<b>-</b>		Sc	rew	Wre	ench
Dia.	Internal I/S	External I/S	External main I/S	Int./Ext. type	Ext. main type	Int./Ext. type	Ext. main type
Ø16	ZPET080M-MM	ZPET080S-MM	-	FTKA02555S	-	TW08S	-
Ø18	ZPET090M-MM	ZPET090S-MM	-	FTKA0307	-	TW09S	-
Ø20	ZPET100M-MM	ZPET100S-MM	SPMT060304	FTKA0307	ETNA02506	TW09S	TW07P
Ø22	ZPET110M-MM	ZPET110S-MM	SPMT060304	FTKA0408	ETNA02506	TW15S	TW07P
Ø25	ZPET125M-MM	ZPET125S-MM	SPMT060304	FTKA0409	ETNA02506	TW15S	TW07P
Ø26	ZPET130M-MM	ZPET130S-MM	SDMT090308-MM	FTKA0409	ETNA0408	TW15S	TW15S
Ø28	ZPET140M-MM	ZPET140S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20	TW15S
Ø30	ZPET150M-MM	ZPET150S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20-100	TW15S
Ø32	ZPET160M-MM	ZPET160S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20-100	TW15S
Ø40	ZPET200M-MM	ZPET200S-MM	SPMT120408-MM	FTGA0614	ETNA0511	TW20-100	TW20S
Ø50	ZPET250M-MM	ZPET250S-MM	SPMT120408-MM	FTGA0818	ETNA0511	TW25S	TW20S




# E Technical Information for GBE

## Recommended cutting condition

Workpiece	Machining type	Hardness (HRC)	vc (m/min)	fz (mm/t)	ap (mm)	ae (mm)
Carbon, Alloy steel	Flank Groove Deep flank	Under 25	160~250 120~200 160~250	0.1~0.5 0.1~0.5 0.1~0.5	0.3~0.5D 0.3~0.5D 1.0~1.5D	0.2~0.3D - 0.1~0.2D
Carbon, Alloy steel	Flank Groove Deep flank	Under 45	120~200 120~160 120~200	0.1~0.5 0.1~0.5 0.1~0.5	0.3~0.5D 0.3~0.5D 1.0~1.5D	0.2~0.3D - 0.1~0.2D
Mold Alloy steel	Flank Groove Deep flank	30~40	120~200 120~160 120~200	0.1~0.3 0.1~0.3 0.1~0.3	0.3~0.5D 0.3~0.5D 1.0~1.5D	0.2~0.3D - 0.1~0.2D
Cast iron (GC, GCD)	Flank Groove Deep flank	20~30	150~300 150~300 150~300	0.2~0.7 0.2~0.7 0.2~0.7	0.3~0.5D 0.3~0.5D 1.0~1.5D	0.2~0.3D - 0.1~0.2D
Heat-treated steel	Flank Groove Deep flank	50~60	40~100 40~100 40~100	0.1~0.3 0.1~0.3 0.1~0.3	0.3~0.5D 0.3~0.5D 1.0~1.5D	0.2~0.3D - 0.1~0.2D

## Line-up for indexable ball endmill



	Application									
Туре	Quality	Machining Efficiency	Machining Dia. Equivalence	Economical	Flank Machining with Long Edge					
Laser Mill	•	0	•	0	0					
GBE	•	•	•	•	•					
BRE	0	•	•	•	•					

•: Very Good ⊕: Good ∘: Normal


## Test result for wear resistance

	Cutting condition			Wear resi	stance photos	
	■ Workpiece			GBE	Com.A	Com.B
	KP4M (HRC33), Dry ■ Condition vc = 280 m/min	Top	Internal			7
0	fz = 0.25  mm/t $ap = 5 \sim 10 \text{ mm}$ $ae = 5 \sim 10 \text{ mm}$		External			
Cutting time	vf = 1,486 mm/min n = 2,971 rpm ■ Tool Holder GBE300-S32	Flank	Internal	West Control		
: 4 Pass	Insert ZPET150M-MM (PC3700) ZPET150S-MM (PC3700)	ᇤ	External	A PROPERTY OF	YEAR	4
	■ Workpiece			GBE	Com.A	Com.B
	STD11 (HRC20), Dry ■ Condition vc = 250 m/min	Top	Internal			
	tz = 0.2 mm/t ap = 5 mm ae = 5 mm	ř	External	Contraction of the Contraction o		
	vf = 1,062 mm/min n = 2,653 rpm ■ <b>Tool</b>	~	Internal		Service of	
Cutting time : 4 Pass	Holder GBE300-S32 Insert ZPET150M-MM (PC3700) ZPET150S-MM (PC3700)	Flank	External	The second second		SAME L


### Better tool life with its anti-breakage special surface treatment

## BRE

- Cutting performance: Good chip control & Superior cutting performance with optimal cutting-edge line
- High rigidity body: Better tool life and special surface treatment to strengthen the holder Easy to set and good durability with TCRX screw Good chip control with our 3D flute design & improved external quality
- Insert: Grade available for high speed & feed applications due to it's high wear and breakage resistance providing a stable cutting performance with high cutting-edge toughness and a chip breaker featuring a high rake angle



### BRE machining type for roughing & Recommended cutting condition




Workpiece	Machining type	Cutting speed (m/min)	Feed (mm/t)	Grades
	1	120~220	0.1~0.4	NCM325
Carbon/alloy steel	2	120~220	0.2~0.4	NCM325
	3	100~180	0.1~0.3	NCM325
	1	100~200	0.1~0.4	NCM325
Alloy steel	2	100~200	0.2~0.4	NCM325
	3	80~160	0.1~0.3	NCM325
	1	80~150	0.1~0.3	NCM325
Tool steel	2	80~150	0.15~0.35	NCM325
	3	60~120	0.1~0.3	NCM325
High bandmans material	1	60~120	0.1~0.3	NCM325
High hardness material	2	60~120	0.1~0.3	NCM325
(HRC35~45)	3	50~80	0.1~0.2	NCM325
	1	100~180	0.2~0.5	NCM325
Cast iron	2	100~180	0.2~0.5	NCM325
	3	80~160	0.15~0.4	NCM325



## LBE08/10/12/16/20/25/30/32

Straight type

## Carbide Shank (Ball type)



|--|--|

(mm)

				Dimensions			Par	s	Available	(11111)
	Designation	ØD	Ød	Ød1	Q	L	Clamp screw	Wrench	inserts (Ø)	Fig.
LBE	080080S-S08C	8, 9	8	7.5	80	136	FTNDOOFOOF	TMD070	0.0	
	080100S-S08C	8, 9	8	7.5	100	156	ETND02506F	TWP07S	8, 9	1
	080020S-S08C-130	8, 9	8	7.5	20	130	ETNDOOFOCE	TMDOZO	0.0	0
	080020S-S08C-150	8, 9	8	7.5	20	150	ETND02506F	TWP07S	8, 9	2
	100080S-S10C	10, 11	10	9.5	80	136	ETND0307F	TWP08S	10 11	
	100120S-S10C	10, 11	10	9.5	120	176	ETND0307F	100000	10, 11	1
	100023S-S10C-130	10, 11	10	9.5	23	130	ETND0307F	TWP08S	10 11	2
	100023S-S10C-170	10, 11	10	9.5	23	170	ETND0307F	100000	10, 11	2
	120100S-S12C	12, 13	12	11.5	100	156	ETND03509	TWP10S	12, 13	1
	120150S-S12C	12, 13	12	11.5	150	206	ETND03509	1005	12, 13	'
	120025S-S12C-150	12, 13	12	11.5	25	150	ETND03509	TWP10S	12, 13	2
	120025S-S12C-200	12, 13	12	11.5	25	200	E1ND03509	TWP105	12, 13	
	160100S-S16C	16, 17	16	15.5	100	160	ETND0413	TWP15S	16, 17	1
	160150S-S16C	16, 17	16	15.5	150	210	ETND0413	100-100	10, 17	ı
	160030S-S16C-160	16, 17	16	15.5	30	160	ETND0413	TWP15S	16, 17	2
	160030S-S16C-210	16, 17	16	15.5	30	210	ETND0413		10, 17	2
	200120S-S20C	20, 21	20	19.5	120	190	ETKD0516	TWP20	20, 21	1
	200170S-S20C	20, 21	20	19.5	170	240	EINDUSIO			<u>'</u>
	200035S-S20C-190	20, 21	20	19.5	35	190	ETKD0516	TWP20	20, 21	2
	200035S-S20C-240	20, 21	20	19.5	35	240	ETKD0510	T VVP20	20, 21	
	250140S-S25C	25, 26	25	24.5	140	220	ETKD0620	TWP25	25, 26	1
	250170S-S25C	25, 26	25	24.5	170	250	ETKD0020	TVVFZS	25, 20	'
	250040S-S25C-220	25, 26	25	24.5	40	220	ETKD0620	TWP25	25, 26	2
	250040S-S25C-250	25, 26	25	24.5	40	250	LTRD0020	1 7 7 2 3	23, 20	
	300140S-S32C	30, 31	32	29.5	140	230	ETGD0825	TWP40	30, 31	1
	300170S-S32C	30, 31	32	29.5	170	260	LTGD0023	1 7 7 40	30, 31	
	300050S-S32C-230	30, 31	32	29.5	50	230	ETGD0825	TWP40	30, 31	2
	300050S-S32C-260	30, 31	32	29.5	50	260	LIGDUOZJ	1 7 7 1 40	30, 31	
	320140S-S32C	32	32	31.5	140	230	ETGD0825	TWP40	32 33	1
	320170S-S32C	32	32	31.5	170	260	LIGDUOZJ	1 00 740	32, 33	1
	320050S-S32C-230	32	32	31.5	50	230	ETGD0825	TWP40	32, 33	2
	320050S-S32C-260	32	32	31.5	50	260	LIGDUOZJ	1 7 7 40	32, 33	


→ Available inserts E08~E10

## LBE08/10/12/16/20/25/30/32

**Taper type** 

## Steel Shank (Ball type)



















(mm)

	Desimolism			Dimensions			Par	ts	Available
	Designation	ØD	Ød	Ød1	Q	L	Clamp screw	Wrench	inserts (Ø)
LBE	080035T-S12	8, 9	12	7.5	35	91			
	080055T-S12	8, 9	12	7.5	55	111	ETND02506F	TWP07S	8, 9
	080075T-S12	8, 9	12	7.5	75	131			
	100035T-S12	10, 11	12	9.5	35	91			
	100055T-S12	10, 11	12	9.5	55	111	ETND0307F	TWP08S	10, 11
-	100075T-S12	10, 11	12	9.5	75	131			
	120055T-S12	12, 13	12	10.4	55	111	ETNIDOGEGO	TWP10S	10.10
	120085T-S16	12, 13	16	11.5	85	145	ETND03509		12, 13
	160065T-S16	16, 17	16	14	65	125	ETND0413	TWP15S	10 17
	160100T-S20	16, 17	20	15.5	100	170	ETND0413		16, 17
	200075T-S20	20, 21	20	17.5	75	145	ETKD0516	TMDOO	20. 21
	200115T-S25	20, 21	25	19.5	115	195	EINDUSIO	TWP20	20, 21
	250090T-S25	25, 26	25	22	90	170	ETKDOCOO	TWDOE	05.00
	250135T-S32	25, 26	32	24.5	135	225	ETKD0620	TWP25	25, 26
	300105T-S32	30, 31	32	29.5	105	195	ETGD0825	TWP40	20.24
	300160T-S32	30, 31	32	29.5	160	250	E1GD0825	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	30, 31
	320105T-S32	32	32	29	105	195	ETCDOOGE	TWP40	20.22
	320160T-S32	32	32	29	160	250	ETGD0825		32, 33


<sup>→</sup> Available inserts E08~E10

## LBE12/16/20/25/30/32

Straight type

## Steel Shank (Ball type)






















(mm)

									(11111)
	Designation			Dimensions	Part	Available			
	Designation	ØD	Ød	Ød <sub>1</sub>	Q	L	Clamp screw	Wrench	inserts (Ø)
LBE	120035S-S12	12, 13	12	11.5	35	91	ETND03509	TWP10S	12, 13
	160035S-S16	16, 17	16	15.5	35	95	ETND0413	TWP15S	16, 17
	200040S-S20	20, 21	20	19.5	40	110	ETKD0516	TWP20	20, 21
	250045S-S25	25, 26	25	24.5	40	125	ETKD0620	TWP25	25, 26
	300055S-S32	30, 31	32	29.5	55	145	ETGD0825	TWP40	30, 31
	320055S-S32	32	32	31.5	55	145	ETGD0825	TWP40	32, 33






## LRE10/12/16/20/25/30/32

Straight type

## Carbide Shank (Corner R type)





(mm)


	Danismatian			Dimensions	3		Par	ts	Available	F:
	Designation	ØD	Ød	Ød1	Q	L	Clamp screw	Wrench	inserts (Ø)	Fig.
LRE	100080S-S10C	10, 11	10	9.5	80	136	ETND0007E	TWP08S	10 11	1
	100120S-S10C	10, 11	10	9.5	120	176	ETND0307F	100000	10, 11	ı
	100023S-S10C-130	10, 11	10	9.5	23	130	ETND0307F	TWP08S	10, 11	2
	100023S-S10C-170	10, 11	10	9.5	23	170	ETND0307F	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10, 11	2
	120100S-S12C	12, 13	12	11.5	100	156	ETND03509	TWP10S	10.10	1
	120150S-S12C	12, 13	12	11.5	150	206	E1ND03509	TWF 103	12, 13	ı
	120025S-S12C-150	12, 13	12	11.5	25	150	ETND03509	TWP10S	12, 13	2
	120025S-S12C-200	12, 13	12	11.5	25	200	E1ND03509	TWP10S	12, 13	
	160100S-S16C	16, 17	16	15.5	100	160	ETND0413	TWD450	10.17	1
	160150S-S16C	16, 17	16	15.5	150	210	EINDU413	TWP15S	16, 17	<u>'</u>
	160030S-S16C-160	16, 17	16	15.5	30	160	ETND0413	TWP15S	10.17	2
	160030S-S16C-210	16, 17	16	15.5	30	210	EINDU413	1 WF 133	16, 17	2
	200120S-S20C	20, 21	20	19.5	120	190	ETKD0516	TWDOO	00.04	
	200170S-S20C	20, 21	20	19.5	170	240		TWP20	20, 21	1
	200035S-S20C-190	20, 21	20	19.5	35	190	ETI/DOE10	TWP20	20, 21	2
	200035S-S20C-240	20, 21	20	19.5	35	240	ETKD0516			
	250140S-S25C	25, 26	25	24.5	140	220	ETI/Docoo	TWDOE	05.00	4
	250170S-S25C	25, 26	25	24.5	170	250	ETKD0620	TWP25	25, 26	1
	250040S-S25C-220	25, 26	25	24.5	40	220	ETKD0620	TWP25	05.00	0
	250040S-S25C-250	25, 26	25	24.5	40	250	ETKD0620	TWP25	25, 26	2
	300140S-S32C	30, 31	32	29.5	140	230	FTODOOG	TWD 40	00.04	
	300170S-S32C	30, 31	32	29.5	170	260	ETGD0825	TWP40	30, 31	1
	300050S-S32C-230	30, 31	32	29.5	50	230	ETCDOOG	TWD40	00.01	0
	300050S-S32C-260	30, 31	32	29.5	50	260	ETGD0825	TWP40	30, 31	2
	320140S-S32C	32	32	31.5	140	230	ETCDOOG	TWD40	00.00	4
	320170S-S32C	32	32	31.5	170	260	ETGD0825	TWP40	32, 33	1
	320050S-S32C-230	32	32	31.5	50	230	ETCDOOG	TWP40	00.00	
	320050S-S32C-260	32	32	31.5	50	260	ETGD0825		32, 33	2

Available inserts E08~E10

LRE10/12

## Steel Shank (Corner R type)



















(mm)

Straight type


	Designation			Dimensions	Parts	Available			
	Designation		Ød	Ød1	Q	L	Clamp screw	Wrench	inserts (Ø)
LRE	100025T-S12	10, 11	12	9.5	25	111	ETND0307F	TWP08S	10.11
	100050T-S12	10, 11	12	9.5	50	150	ETND0307F		10,11
	120060T-S16	12, 13	16	11.5	60	160	ETND03509	TWP10S	12,13

<sup>→</sup> Available inserts E08~E10

## LRE12/16/25/30/32

**Steel Shank (Corner R type)** 



















(mm)


	Danismatian			Dimensions			Par	ts	Available
	Designation	ØD	Ød	Ød1	Q	L	Clamp screw	Wrench	inserts (Ø)
LRE	120030S-S12	12, 13	12	11.5	30	111	ETND03509	TWP10S	12, 13
	160050S-S16	16, 17	16	15.5	50	131	ETND0413	TWP15S	16 17
	160060S-S16	16, 17	16	15.5	60	160	ETND0413	1007155	16, 17
	200060S-S20	20, 21	20	19.5	60	145	ETKD0516	TWP20	20, 21
	200080S-S20	20, 21	20	19.5	80	180	EINDUSTO		20, 21
	250070S-S25	25, 26	25	24.5	70	145	ETKD0620		05.06
	250100S-S25	25, 26	25	24.5	100	225	ETKD0620		25, 26
	300070S-S32	30, 31	32	29.5	70	160	ETGD0825	TWP40	30. 31
	300100S-S32	30, 31	32	29.5	100	225	E1GD0625	1 44 740	30, 31
	320080S-S32	32	32	31.5	80	160	ETGD0825	TWP40	20.00
	320100S-S32	32	32	31.5	100	225	E1GD0825	1 00 1 40	32, 33


<sup>→</sup> Available inserts E08~E10



## LBE-MHD






















- 1	ľ	γ	٦	ì	Υ	٦

	Decimation			Dimer	nsions			Parts		Available
	Designation	M	ØD	L	Q	Ød	Ød <sub>1</sub>	Clamp screw	Wrench	inserts (Ø)
LBE	100-MHD-M06	M06	10, 11	40	25	9.5	6.5	ETND0307F	TWP08S	10, 11
	120-MHD-M06	M06	12, 13	40	25	11	6.5	ETND03509	TWP10S	12, 13
	160-MHD-M08	M08	16, 17	47	30	14.5	8.5	ETND0413	TWP15S	16, 17
	200-MHD-M10	M10	20, 21	56	35	18	10.5	ETKD0516	TWP20	20, 21
	250-MHD-M12	M12	25, 26	69	45	22.5	12.5	ETKD0620	TWP25	25, 26
	300-MHD-M16	M16	30, 31	77	50	28	17	ETGD0825	TWP40	30, 31
	320-MHD-M16	M16	32	77	50	29	17	ETGD0825	TWP40	32, 33

→ Available inserts E08~E10 → Available adaptors E401~E402

Designation: LBE320-MHD-M16 Modular head threading measure size (M16) Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)

## **BFE**





(mm)

	Designation	ØD	Ød	Q	L	ар	kg	Fig.	Available inserts
BFE	16-S	16	16	36	140	8.0	0.2	1	
	16-M	16	20	65	170	8.0	0.3	2	RC16
	16-L	16	25	65	200	8.0	0.5	2	
	20-S	20	20	45	160	10.0	0.4	1	
	20-M	20	25	80	200	10.0	0.6	2	RC20
	20-L	20	25	80	250	10.0	0.8	2	
	25-S	25	25	45	160	12.5	0.7	1	
	25-M	25	32	90	210	12.5	1.1	2	RC25
	25-L	25	32	90	300	12.5	1.7	2	
	30-S	30	32	65	175	15.0	0.9	2	
	30-M	30	32	100	250	15.0	1.4	2	RC30
	30-L	30	32	100	350	15.0	2.0	2	1
	32-S	32	32	56	175	16.0	0.9	1	
	32-M	32	32	100	250	16.0	1.4	1	RC32
	32-L	32	32	100	350	16.0	2.0	1	

## Available inserts



		Coated	
[	Designation	PC210F	page
RC	16	•	
	20	•	
	25	•	E16
	30		
	32	•	


## Recommended cutting condition

	Workniego	Cutting of	condition
	Workpiece	vc (m/min)	fz (mm/t)
P	General steel (SS41, SM25C) Over HB180	150 ~ 250	0.10 ~ 0.30
	Alloy steel (SM55C, SCM) Under HB300	100 ~ 200	0.10 ~ 0.20
К	Cast iron Under HB300	100 ~ 200	0.10 ~ 0.30

Specification	Screw	Clamp	Clamp screw	Stopper Ring	Wrench	
Ø16	FTGA0513	CBH4.5R1	CTX04513	ER03	TW20	
Ø20	FTGA0517	CBH4.5R2	CTX04513	ER03	TW20	
Ø25	FTGA0621	CBH5R1	CTX0517	ER04	TW20	
Ø30, 32	FTGA0826	CBH6R1	CTX0621	ER05	TW25	

# **E** GBE (Single-edge)

# **GBE** (Single-edge)






(mm)

			Di	mensio	ns		Available	e inserts	Pa	ırts	
Des	signation	αD	~-	0			Internal	Fortermel	Screw	Wrench	Fig.
		ØD	Ød	Q	L	ар	Internal	External	Int./Ext. type	Ext. main type	
GBE	160-S20	16	20	50	130	15	ZPET080M-MM	ZPET080S-MM	FTKA02555S	TW08S	
	160-L20	16	20	90	200	15	ZPET080M-MM	ZPET080S-MM	FTKA02555S	TW08S	
	180-S20	18	20	60	130	17	ZPET090M-MM	ZPET090S-MM	FTKA0307	TW09S	
	180-L20	18	20	80	200	17	ZPET090M-MM	ZPET090S-MM	FTKA0307	TW09S	
	200-S25	20	25	60	140	18	ZPET100M-MM	ZPET100S-MM	FTKA0307	TW09S	
	200-L25	20	25	80	250	18	ZPET100M-MM	ZPET100S-MM	FTKA0307	TW09S	
	220-S25	22	25	70	140	21	ZPET110M-MM	ZPET110S-MM	FTKA0408	TW15S	] ,
	220-L25	22	25	100	250	21	ZPET110M-MM	ZPET110S-MM	FTKA0408	TW15S	'
	250-S32	25	32	70	150	23	ZPET125M-MM	ZPET125S-MM	FTKA0409	TW15S	
	250-L32	25	32	100	300	23	ZPET125M-MM	ZPET125S-MM	FTKA0409	TW15S	
	260-S32	26	32	70	150	24.5	ZPET130M-MM	ZPET130S-MM	FTKA0409	TW15S	
	260-L32	26	32	100	300	24.5	ZPET130M-MM	ZPET130S-MM	FTKA0409	TW15S	
	280-S32	28	32	70	150	26	ZPET140M-MM	ZPET140S-MM	FTGA0511-P	TW20	
	280-L32	28	32	120	300	26	ZPET140M-MM	ZPET140S-MM	FTGA0511-P	TW20	
	300-S32	30	32	70	160	27	ZPET150M-MM	ZPET150S-MM	FTGA0511-P	TW20-100	
	300-L32	30	32	120	350	27	ZPET150M-MM	ZPET150S-MM	FTGA0511-P	TW20-100	
	320-S32	32	32	70	160	28	ZPET160M-MM	ZPET160S-MM	FTGA0511-P	TW20-100	2
	320-L32	32	32	120	350	28	ZPET160M-MM	ZPET160S-MM	FTGA0511-P	TW20-100	
	400-S42	40	42	100	200	37	ZPET200M-MM	ZPET200S-MM	FTGA0614	TW20-100	
	400-L42	40	42	150	350	37	ZPET200M-MM	ZPET200S-MM	FTGA0614	TW20-100	
	500-S42	50	42	100	200	47	ZPET250M-MM	ZPET250S-MM	FTGA0818	TW25-100	3
	500-L42	50	42	100	350	47	ZPET250M-MM	ZPET250S-MM	FTGA0818	TW25-100	٥

→ Available inserts E33

# GBE-M (Multi-edge)





(mm


			Dim	nensi	ons			Available insei	ts		Parts	3		
Des	signation	ØD	Ød	Q			Internal	External	Ext. main	Scr	'ew	Wre	nch	Fig.
		טש	Øα	¥	L	ар	internal	External	EXI. IIIaili	Int./Ext. type	Ext. main type	Int./Ext. type	Ext. main type	
GBE	200M-S25	20	25	70	150	28	ZPET100M-MM	ZPET100S-MM	SPMT060304	FTKA0307	ETNA02506	TW09S	TW07P	
	200M-L25	20	25	70	250	28	ZPET100M-MM	ZPET100S-MM	SPMT060304	FTKA0307	ETNA02506	TW09S	TW07P	
	220M-S25	22	25	80	150	31	ZPET110M-MM	ZPET110S-MM	SPMT060304	FTKA0408	ETNA02506	TW15S	TW07P	
	220M-L25	22	25	80	250	31	ZPET110M-MM	ZPET110S-MM	SPMT060304	FTKA0408	ETNA02506	TW15S	TW07P	
	250M-S32	25	32	80	180	33	ZPET125M-MM	ZPET125S-MM	SPMT060304	FTKA0409	ETNA02506	TW15S	TW07P	
	250M-L32	25	32	80	300	33	ZPET125M-MM	ZPET125S-MM	SPMT060304	FTKA0409	ETNA02506	TW15S	TW07P	
	260M-S32	26	32	80	180	39	ZPET130M-MM	ZPET130S-MM	SDMT090308-MM	FTKA0409	ETNA0408	TW15S	TW15S	'
	260M-L32	26	32	80	300	39	ZPET130M-MM	ZPET130S-MM	SDMT090308-MM	FTKA0409	ETNA0408	TW15S	TW15S	
	280M-S32	28	32	80	180	41	ZPET140M-MM	ZPET140S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20	TW15S	
	280M-L32	28	32	80	300	41	ZPET140M-MM	ZPET140S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20	TW15S	
	300M-S32	30	32	100	200	41	ZPET150M-MM	ZPET150S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20-100	TW15S	
	300M-L32	30	32	100	350	41	ZPET150M-MM	ZPET150S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20-100	TW15S	
	320M-S32	32	32	100	200	42	ZPET160M-MM	ZPET160S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20-100	TW15S	
	320M-L32	32	32	100	350	42	ZPET160M-MM	ZPET160S-MM	SDMT090308-MM	FTGA0511-P	ETNA0408	TW20-100	TW15S	2
	400M-S42	40	42	100	200	56	ZPET200M-MM	ZPET200S-MM	SPMT120408-MM	FTGA0614	ETNA0511	TW20-100	TW20S	
	400M-L42	40	42	100	350	56	ZPET200M-MM	ZPET200S-MM	SPMT120408-MM	FTGA0614	ETNA0511	TW20-100	TW20S	
	500M-S42	50	42	100	200	67	ZPET250M-MM	ZPET250S-MM	SPMT120408-MM	FTGA0818	ETNA0511	TW25-100	TW20S	3
	500M-L42	50	42	100	350	67	ZPET250M-MM	ZPET250S-MM	SPMT120408-MM	FTGA0818	ETNA0511	TW25-100	TW20S	3

Available inserts E20, E27, E33



## **GBEM**



















(mm)

				D	Available inserts					
Designation		ØD	Ød	Ød <sub>1</sub>	Q	L	M	ар	Internal	External
GBEM	160-M08	16	15	8.5	30	47	M08	15	ZPET080M-MM	ZPET080S-MM
	200-M10	20	18.6	10.5	35	56	M10	18	ZPET100M-MM	ZPET100S-MM
	250-M12	25	23.2	12.5	45	69	M12	23	ZPET125M-MM	ZPET125S-MM
	300-M16	30	27.8	17	50	77	M16	27	ZPET150M-MM	ZPET150S-MM
	320-M16	32	29.8	17	50	77	M16	28	ZPET160M-MM	ZPET160S-MM

#### Available inserts



			Coa	ated						Coa	ated		
D	Designation		PC2510	PC3700	PC5300	page	Designation		NCM325	PC2510	PC3700	PC5300	page
SPMT	060304	•				E27	ZPET	080S-MM					
	120408-MM			•	•	E27		090S-MM					
SDMT	090308-MM			•	•	E20	]	100S-MM		•	•	•	
ZPET	080M-MM						1	110S-MM					
	090M-MM							125S-MM		•	•	•	
	100M-MM		•	•	•			130S-MM					E33
	110M-MM							140S-MM					
	125M-MM		•	•	•			150S-MM			•	•	
	130M-MM					E33		160S-MM		•	•	•	
	140M-MM							200S-MM			•		1
	150M-MM			•	•			250S-MM					
	160M-MM		•	•	•								
	200M-MM			•									
	250M-MM												

#### Parts

Specification	©) Sc	rew	Wrench			
	Int./Ext. type	Ext. main type	Int./Ext. type	Ext. main type		
Ø16	FTKA02555S	-	TW08S	-		
Ø18, Ø20	FTKA0307	ETNA02506	TW09S	TW07P		
Ø22						
Ø25	FTKA0409	ETNA02506	TW15S	TW07P		
Ø30	FTGA0511-P	ETNA0408	TW20-100	TW15S		
Ø32	FTGA0511-P	ETNA0408	TW20-100	TW15S		

Designation: GBEM320-M16 Modular head threading measure size (M16)


Adaptor spec.: MAT-M16-035-S32S Adaptor threading measure (M16)






## **BRE**











(mm)

Da	-!		D	imensior	าร		Available	inserts	Part	ts		Tim.
De	signation	ØD	Ød	Q	L	ар	Internal	External	Screw	Wrench	kg	Fig.
BRE	20R-S	20	20	50	125	20					0.25	4
	20R-M	20	20	75	150	20	ZDMT080310R-MM	SPMT060304	ETNA02506	TW07P	0.31	'
	20R-L	20	25	100	200	20	ZDIVITUOUSTUR-IVIIVI	3FW1000304	ETNAU2506	10077	0.57	2
	20R-SL	20	25	65	125	20					0.33	3
	25R-S 25R-M 25R-L	25	25	70	150	23					0.47	4
		25	25	95	175	23	7DMT110010 FD MM	SPMT060304	ETNA02506	TW07P	0.56	'
		25	32	100	200	23	ZDMT110312.5R-MM	SPINI 1000304	ETNAU2506	TWU/P	0.92	2
	25R-SL	25	25	75	135	23					0.41	3
	25R-SL 32R-S 32R-M 32R-L 32R-SL	32	32	85	175	31					0.87	
		32	32	100	200	31	7DMT100410D MM	CDMT000000 MM	ETNIA0400	TM4FC	1.02	1
		32	32	150	250	31	ZDMT130416R-MM	SDMT090308-MM	ETNA0408	TW15S	1.3	
		32	32	75	150	31					0.71	3

#### Available inserts

SPMT

ZDMT-R-MM




				Coated			
	Designation	NCM325	PC3700	PC5300	PC5400	PC6510	page
SPMT	060304	•					E27
ZDMT	080310R-MM		•	•			
	110312.5R-MM			•			E33
	130416R-MM		•	•			


Specification				
	Screw	Wrench	Wrench	
Ø20~Ø25	ETNA02506	-	TW07P	
Ø32	ETNA0408	TW15S	-	



## **BRE**











(mm)

	)!ti		D	imensio	ns		Available	inserts	Pa	rts		Fin.
	Designation	ØD	Ød	Q	L	ар	Main	Ext. main	Screw	Wrench	kg	Fig
BRE	40R-S	40	42	85	175	41					1.37	
	40R-S-40	40	40	85	175	41					1.35	
	40R-M	40	42	100	200	41					1.62	
	40R-M-40	40	40	100	200	41	ZPMT160520R-MM	SPMT120408-MM	ETNA0511	TW20-100	1.6	1
	40R-L	40	42	150	250	41	ZPIVIT 100520H-IVIIVI	SPMT120508-MMN	ETINAUSTI	1 4420-100	2.1	
	40R-L-40	40	40	150	250	41					2	
	40R-SL	40	42	80	160	41					1.21	3
	40R-SL-40	40	40	80	160	41					1.2	3
	50R-S	50	42	100	200	45					2.02	
	50R-S-40	50	40	100	200	45					1.93	1
	50R-L	50	42	100	300	45	ZPMT160525R-MM	SPMT120408-MM	ETNA0511	TW20-100	3.1	'
	50R-L-40	50	40	100	300	45	ZPIVIT 100525R-IVIIVI	SPMT120508-MMN	ETINAUSTI	1 4420-100	2.92	
	50R-SL	50	42	100	250	45					2.56	3
	50R-SL-40	50	40	100	250	45					2.5	3
	63R-S	63	42	100	200	52					2.41	
	63R-S-40	63	40	100	200	52					2.4	1
	63R-L	63	42	100	300	52	ZPMT160531.5R-MM	SPMT120408-MM	ETNA0511	TW20-100	3.5	] '
	63R-L-40	63	40	100	300	52	ZFIVITIOUSST.SH-IVIIVI	SPMT120508-MMN	ETNAUSTI	1 4420-100	3.3	
	63R-SL	63	42	100	250	52					2.95	3
	63R-SL-40	63	40	100	250	52					2.9	3
	40XR-SC40	40	40	110	200	54	ZPMT1609	SOOD MM	ETNA0511	TW20-100	1.43	4
	40XR-LC40	40	40	150	250	54	ZFIVIT 1003	JZUI 141VIIVI	LINAUSII	1 4420-100	1.89	4
	40XR-SC40 40XR-LC40 50XR-SC50.8	50	50.8	110	200	57	ZPMT160	525R-MM	ETNA0511	TW20-100	2.34	4
	50XR-LC50.8	50	50.8	150	250	57	ZPMT160	525R-MR	LICOAMI	1 4420-100	3.06	4

## Available inserts

SDMT-MM	SPMT-MM	ZPMT-R-MM	ZPMT-R-MR

				Coated			
	Designation	NCM325	PC3700	PC5300	PC5400	PC6510	page
SDMT	090308-MM		•	•			E20
SPMT	120408-MM		•	•			E27
	120508-MMN						E21
ZPMT	160520R-MM		•	•			
	160525R-MM		•	•			F00
	160525R-MR						E33
	160531.5R-MM			•			

Specification			
	Screw	Wrench	
Ø40~Ø63	ETNA0511	TW20-100	




#### Multifunctional milling tool for mold making

## **HAVE**


- Tools for Z-axis feed plunge machining to cut faster and more effectively in vertical machining
- Able to utilize the full diameter of the tools, thanks to the position and design of the inserts

## Maximum step in vertical machining

1											
						Diameter					
ae	16	17	20	21	25	26	32	33	35	40	50
					ma	x step (n	nm)				
1	7.7	8	8.7	8.9	9.7	10	11.1	11.3	11.6	12.4	14
2	10.5	10.9	12	12.3	13.5	13.8	15.4	15.7	16.2	17.4	19.5
3	12.4	12.9	14.2	14.6	16.2	16.6	18.6	18.9	19.5	21	23.7
4	13.8	14.4	16	16.4	18.3	18.7	21.1	21.5	22.2	24	27.1
5	14.8	15.4	17.3	17.8	20	20.4	23.2	23.6	24.4	26.4	30
6	15.4	16.2	18.3	18.9	21.3	21.9	24.9	25.4	26.3	28.5	32.4
7	15.8	16.7	19	19.7	22.4	23	26.4	26.9	28	30.3	34.6
8	16	16.9	19.5	20.3	23.3	24	27.7	28.2	29.3	32	36.6
9	15.8	16.9	19.9	20.7	24	24.7	28.7	29.3	30.5	33.4	38.4
10	15.4	16.7	20	20.9	24.4	25.2	29.6	30.3	31.6	34.6	40
11	14.8	16.2	19.9	20.9	24.8	25.6	30.3	31.1	32.4	35.7	41.4
12	13.8	15.4	19.5	20.7	24.9	25.9	30.9	31.7	33.2	36.6	42.7
13	12.4	14.4	19	20.3	24.9	26	31.4	32.2	33.8	37.4	43.8
14	10.5	12.9	18.3	19.7	24.8	25.9	31.7	32.6	34.2	38.1	44.9
15	7.7	10.9	17.3	18.9	24.4	25.6	31.9	32.8	34.6	38.7	45.8
16	-	8	16	17.8	24	25.2	32	32.9	34.8	39.1	46.6
17	-	-	14.2	16.4	23.3	24.7	31.9	32.9	34.9	39.5	47.3
18	-	-	12	14.6	22.4	24	31.7	32.8	34.9	39.7	48
19	-	-	8.7	12.3	21.3	23	31.4	32.6	34.8	39.9	48.5
20	-	-	-	8.9	20	21.9	30.9	32.2	34.6	40	48.9
21	-	-	-	-	18.3	20.4	30.3	31.7	34.2	39.9	49.3
22	-	-	-	-	16.2	18.7	29.6	31.1	33.8	39.7	49.6
23	-	-	-	-	13.5	16.6	28.7	30.3	33.2	39.5	49.8
24	-	-	-	-	9.7	13.8	27.7	29.3	32.4	39.1	49.9
25	-	-	-	-	-	10	26.4	28.2	31.6	38.7	50



## Programming in vertical cutting



Vertical machining route Rapid feed

Angle between tool and workpiece  $(\beta \ge 1^\circ)$ 

- Reduce 30% of feed till 3 mm machining
- · Have the tool be away from the workpiece more than 1° (b) after finishing the machining or when moving the tool to the next step.

## Cutting condition

	<b>5</b>			Cutting condition	Ø16	5, 17	Ø20	, 21	Ø25	, 26	Ø32	, 33	Ø	35	Ø	10	Ø!	50
	Designation	Hardness	Grades	vc (m/min)		Step (mm)					Feed (mm/rev)						Feed (mm/rev)	
P	Mild steel, Low Carbon steel (SS400)	Under 200HB	PC3700	200 (150~250)	0.03	0.20	0.04	0.30	0.05	0.30	0.05	0.30	0.06	0.30	0.06	0.30	0.07	0.30
	Carbon steel, Alloy steel (SM50C, SCM440)	Under 100HRC	PC3700	180 (120~220)	0.03	0.20	0.04	0.30	0.05	0.30	0.05	0.30	0.05	0.30	0.06	0.30	0.06	0.30
M	Stainless steel (STS)	Under 270HB	PC5300	160 (120~200)	0.03	0.15	0.04	0.25	0.05	0.25	0.05	0.25	0.05	0.25	0.06	0.25	0.06	0.25
K	Cast iron (GC, GCD)	350N/mm <sup>2</sup>	PC5300	200 (150~250)	0.04	0.40	0.05	0.50	0.06	0.50	0.06	0.50	0.06	0.50	0.07	0.50	0.07	0.50
н	Hardened steel	40~55HRC	PC5300	80 (50~120)	0.03	0.15	0.03	0.25	0.04	0.25	0.04	0.25	0.04	0.25	0.04	0.25	0.05	0.25

<sup>\*</sup> Please note - Step machining is required for aspect ratio under 0.5D or initial drilling



## **Technical Information for HAVE**

# Direction $Lmin = \frac{ap}{tan a} (mm)$ $\alpha \le 3^{\circ}$

# ØDc = ØDh-ØD ØDc = Tool pass of tool center ØDh = Desirable hole diameter on workpiece ØD = Tool diameter

2. Helical cutting

## Cutting condition for ramping and helical operation

				Cutting Speed		Ø16	, 17			Ø20	), 21			Ø25	, 26			Ø32	2, 33			Ø	35			Ø	40			Ø5	50	
[	Designation	Hardness	Grades	vc (m/min)	ØDh (mm)	ap (mm/t)	fz (mm/t)	max pitch (mm)	ØDh (mm)	ap (mm/t)	fz (mm/t)	max pitch (mm)	ØDh (mm)	ap (mm/t)	fz (mm/t)	max pitch (mm)	ØDh (mm)	ap (mm/t)	fz (mm/t)	max pitch (mm)	ØDh (mm)	ap (mm/t)	fz (mm/t)	max pitch (mm)	ØDh (mm)	ap (mm/t)	fz (mm/t)	max pitch (mm)	ØDh (mm)	ap (mm/t) (	fz (mm/t)	max pitch (mm)
	Mild steel, Low Carbon steel (SS400)	≤200HB	PC3700	200 (150~250)	19 ~30	0.5D ~1D	0.15 ~0.12 <i>-</i>	0.35 ~1.61	23 ~28	0.5D ~1D	0.18 ~0.12	0.35 ~2.07	29 ~47	0.5D ~1D	0.2 ~0.15	0.46 ~2.53	37 ~60	0.5D ~1D	0.25 ~0.2	0.58 ~3.23	41 ~65	0.5D ~1D	0.28 ~0.2	0.69 ~3.46	47 ~75	0.5D ~1D	0.3 ~0.2	0.81 ~4.03	58 ~95		0.35 ~0.25	0.92 ~5.18
	Carbon steel, Alloy Steel (SM50C,SCM440)	≤100HB	PC3700	180 (120~220)	19 ~30	0.5D ~1D		0.26 ~1.23	23 ~28	0.5D ~1D		0.26 ~1.58	29 ~47	0.5D ~1D	0.18 ~0.12	0.35 ~1.93	37 ~60	0.5D ~1D	0.2 ~0.15	0.44 ~2.46	41 ~65	0.5D ~1D	0.22 ~0.17	0.53 ~2.63	47 ~75	0.5D ~1D	0.25 ~0.2	0.61 ~3.07	58 ~95		0.28 ~0.25	
N	Stainless steel (STS)	≤270HB	PC5300	160 (120~200)	19 ~30	0.2D ~0.5D		0.18 ~0.84	23 ~28	0.2D ~0.5D		0.18 ~1.09	29 ~47	0.2D ~0.5D	0.18 ~0.12	0.24 ~1.33	37 ~60	0.2D ~0.5D	0.2 ~0.15	0.24 ~1.33	41 ~65	0.2D ~0.5D	0.22 ~0.17	0.36 ~1.81	47 ~75	0.2D ~0.5D	0.25 ~0.2	0.42 ~2.11	58 ~95	0.2D ~0.5D	58 ~95	0.48 ~2.71
K	Cast iron (GC, GCD)	≤ 350N/mm <sup>2</sup>	PC5300	200 (150~250)	19 ~30	0.7D ~1D		0.43	23 ~28	0.7D ~1D	0.2 ~0.12	0.42 ~2.57	29 ~47	0.7D ~1D	0.2 ~0.15	0.57 ~3.14	37 ~60	0.7D ~1D	0.25 ~0.2	0.71 ~3.99	41 ~65	0.7D ~1D	0.28 ~0.2	0.86 ~4.28	47 ~75	0.7D ~1D	0.3 ~0.2	1.0 ~4.99	58 ~95		0.35 ~0.25	1.14 ~6.42
Н	Hardened steel	40~55HrC	PC5300	80 (50~120)	19 ~30	0.2D ~0.5D	0.1 ~0.05 /	0.18 ~0.84	23 ~28	0.2D ~0.5D	0.12 ~0.07	0.18 ~1.09	29 ~47	0.2D ~0.5D	0.13 ~0.1	0.24 ~1.33	37 ~60	0.2D ~0.5D	0.15 ~0.12	0.30 ~1.69	41 ~65	0.2D ~0.5D	0.17 ~0.13	0.36 ~1.81	47 ~75	0.2D ~0.5D	0.18 ~0.15	0.42 ~2.11	58 ~95	0.2D ~0.5D		0.48 ~2.71

## Recommended cutting condition in shouldering


				Cutting Speed	Q	ð16, 1	7	Q	ð20, 2	1	Ç	ð25, 2	6	Ç	<b>332, 3</b>	3		Ø35			Ø40			Ø50	
[	Designation	Hardness	Grades	vc (m/min)	max ap (mm)	max ae (mm)	max fz (mm/t)		max ae (mm)	max fz (mm/t)		max ae (mm)	max fz (mm/t)			max fz (mm/t)		max ae (mm)	max fz (mm/t)	max ap (mm)	max ae (mm)	max fz (mm/t)	max ap (mm)	max ae (mm)	max fz (mm/t)
	Mild steel, Low Carbon steel (SS400)	≤ 200HB	PC3700	200 (150~250)	17	8	0.25	22	10	0.3	27	13	0.35	35	16	0.4	40	18	0.45	44	20	0.5	55	25	0.6
	Carbon steel, Alloy Steel (SM50C,SCM440)	≤100HB	PC3700	180 (120~220)	17	8	0.2	22	10	0.25	27	13	0.3	35	16	0.35	40	18	0.4	44	20	0.4	55	25	0.5
N	Stainless steel (STS)	≤ 270HB	PC5300	160 (120~200)	17	8	0.2	22	10	0.25	27	13	0.3	35	16	0.35	40	18	0.4	44	20	0.4	55	25	0.5
K	Cast iron (GC, GCD)	≤ 350N/mm <sup>2</sup>	PC5300	200 (150~250)	17	8	0.25	22	10	0.3	27	13	0.35	35	16	0.4	40	18	0.45	44	20	0.5	55	25	0.6
Н	Hardened steel	40~55HrC	PC5300	80 (50~120)	17	5	0.15	22	6	0.2	27	7	0.22	35	8	0.25	40	9	0.3	44	10	0.3	55	14	0.35


## Recommended cutting condition in grooving

					5		•	,	9									
				Cutting Speed	Ø16	, 17	Ø20	), 21	Ø25	5, 26	Ø32	2, 33	Ø	35	Ø	40	Ø	50
[	Designation	Hardness	Grades	vc (m/min)	max ap (mm)	max fz (mm/t)	max ap (mm)	max fz (mm/t)	max ap (mm)	max fz (mm/t)	max ap (mm)	max fz (mm/t)	max ap (mm)	max fz (mm/t)	max ap (mm)	max fz (mm/t)	max ap (mm)	max fz (mm/t)
	Mild steel, Low Carbon steel (SS400)	≤ 200HB	PC3700	200 (150~250)	17	0.15	22	0.18	27	0.2	35	0.25	40	0.27	44	0.3	55	0.35
۲	Carbon steel, Alloy Steel (SM50C,SCM440)	≤100HB	PC3700	180 (120~220)	17	0.15	22	0.15	27	0.18	35	0.2	40	0.22	44	0.25	55	0.3
N	Stainless steel (STS)	≤ 270HB	PC5300	160 (120~200)	17	0.15	22	0.15	27	0.18	35	0.2	40	0.22	44	0.25	55	0.3
K	Cast iron (GC, GCD)	≤ 350N/mm <sup>2</sup>	PC5300	200 (150~250)	17	0.15	22	0.18	27	0.2	35	0.25	40	0.27	44	0.3	55	0.35
Н	Hardened steel	40~55HRC	PC5300	80 (50~120)	12	0.1	14	0.12	17	0.15	22	0.15	25	0.18	28	0.18	35	0.22

## **HAVE** (Multi-edge)



































- (	r	Υ	٦	r	Υ
١.					۰

										(mm)	
ı	Designation	©	ØD	Ød	Q	L	ар	Available inserts	kg	Fig.	
HAVE	0816HR-S16M	4	16	16	30	120	17.6		0.15	-1	
	0816HR-L16M	4	16	16	30	200	17.6	XPMT0802ER-MM	0.26	'	
	0817HR-S16M	4	17	16	30	120	17.6	AFIVITUOUZEN-IVIIVI	0.18	2	
	0817HR-L16M	4	17	16	30	200	17.6		0.27	2	
	1020HR-S20M	4	20	20	35	130	22		0.26	1	
	1020HR-L20M	4	20	20	35	210	22	XPMT1003ER-MM	0.44	'	
	1021HR-S20M	4	21	20	35	130	22	AFIVIT TOUSEN-IVIIVI	0.26	2	
	1021HR-L20M	4	21	20	35	210	22		0.45	2	
	1325HR-S25M	4	25	25	45	140	27		0.41	1	
	1325HR-L25M	4	25	25	45	220	27	XPMT13T3ER-MM	0.71	'	
	1326HR-S25M	4	26	25	45	140	27		0.45	2	
	1326HR-L25M	4	26	25	45	220	27		0.68		
	1632HR-S32M	4	32	32	50	150	35.2		0.72		
	1632HR-L32M	4	32	32	50	250	35.2	XPMT1604ER-MM	1.32	'	
	1633HR-S32M	4	33	32	50	150	35.2	XI WIT 1004LI I-WW	0.76	2	
	1633HR-L32M	4	33	32	50	250	35.2		1.27		
	1835HR-S32M	4	35	32	50	150	40	XPMT1805ER-MM	0.75	4	
	1835HR-L32M	4	35	32	50	230	40	AFIVIT TOUSEN-IVIIVI	1.23	'	
	2040HR-S32M	4	40	32	55	160	44	XPMT2006ER-MM	0.74	2	
	2040HR-L32M	4	40	32	55	240	44	AT IVITZOUDER-IVIIVI	1.35	1 2	
	2550HR-S42M	4	50	42	70	170	55	XPMT2507ER-MM	1.53	2	
	2550HR-L42M	4	50	42	70	250	55	AFIVITZOU/EN-IVIIVI	2.60	2	

## Available inserts

XPMT-MM




		Cer	rmet Coated Uncoa						ncoat	ed										
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 194	page
XPMT	0802ER-MM														•					
	1003ER-MM										•				•					
	13T3ER-MM														•					
	1604ER-MM														•					E32
	1805ER-MM														•					
	2006ER-MM														•					
	2507ER-MM														•					

Specification		
	Screw	Wrench
Ø16~Ø17	FTNA0204	TW06S
Ø20~Ø21	FTNA02205	1 00000
Ø25~Ø26	FTKA0307	TW09S
Ø32~Ø33	FTKA0408	TW15S
Ø35	F1NAU4U8	1 1 1 1 2 2
Ø40	FTGA0511-P	TW20S
Ø50	FTNA0615	1 00205

# E HAVE (Single-edge)

## **HAVE** (Single-edge)



	Designation	©	ØD	Ød	Q	L	ар	Available inserts	kg	Fig.	
HAVE	0816HR-S16	2	16	16	30	120	7.5		0.16	1	
	0816HR-L16	2	16	16	30	200	7.5	XPMT0802ER-MM	0.27	!	
	0817HR-S16	2	17	16	30	120	7.5	AFIVITUOUZEN-IVIIVI	0.16	2	
	0817HR-L16	2	17	16	30	200	7.5		0.27	2	
1020HR-S20	2	20	20	35	130	9.5		0.28	4		
	1020HR-L20	2	20	20	35	210	9.5	XPMT1003ER-MM	0.46	!	
	1021HR-S20	2	21	20	35	130	9.5	APIVIT TOUSEN-IVIIVI	0.28	2	
	1021HR-L20	2	21	20	35	210	9.5		0.46	2	
	1325HR-S25	2	25	25	45	140	12		0.44	1	
	1325HR-L25	2	25	25	45	220	12	XPMT13T3ER-MM	0.76	'	
	1326HR-S25	2	26	25	45	140	12		0.47	2	
	1326HR-L25	2	26	25	45	220	12		0.76		
	1632HR-S32	2	32	32	50	150	15.4		0.77	4	
	1632HR-L32	2	32	32	50	250	15.4	XPMT1604ER-MM	1.36	'	
	1633HR-S32	2	33	32	50	150	15.4	AFIVIT 1004EN-IVIIVI	0.81	2	
	1633HR-L32	2	33	32	50	250	15.4		1.41		
	1835HR-S32	2	35	32	50	150	16.7	XPMT1805ER-MM	0.81	1	
	1835HR-L32 2040HR-S32	2	35	32	50	230	16.7	AFIVIT TOUSER-IVIIVI	1.28	'	
		2	40	32	55	160	19.3	XPMT2006ER-MM	0.95	2	
	2040HR-L32	2	40	32	55	240	19.3	AT IVITZOUDER-IVIIVI	1.45		
	2550HR-S42	2	50	42	70	170	24	XPMT2507ER-MM	1.68	2	
	2550HR-L42	2	50	42	70	250	24	AFIVITZ307ER-IVIVI	2.54		

## Available inserts

XPMT-M	IM
0	1

		Cer	met	Coated								Uncoated								
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 194	page
XPMT	0802ER-MM														•					
	1003ER-MM										•				•					
	13T3ER-MM																			
	1604ER-MM																			E32
	1805ER-MM														•					
	2006ER-MM														•					
	2507ER-MM														•					

## Parts

Specification		
	Screw	Wrench
Ø16~Ø17	FTNA0204	TW06S
Ø20~Ø21	FTNA02205	1 77003
Ø25~Ø26	FTKA0307	TW09S
Ø32~Ø33	FTKA0408	TW15S
Ø35	FINAU4U8	1 10 100
Ø40	FTGA0511-P	TWOOL
Ø50	FTNA0615	TW20S


(mm)

Guarantee strong constrain force by 2-side constraint

# **BT/HSK Tooling System**

### Code system

· Single, Multi-edge



#### Modular




## **DBT** system

#### Feature of (D)BT arbor

- · Guaranteed strong force by 2-side constraint
- · Guarantee strengthen cutting at high speed
- · Guaranteed superior surface roughness

## **DBT** (Constrain, increased surface roughness)

2-side constraint (Taper, 1-side)






**DBT Workpiece**  $Ra = 0.3 \mu m$ 

1-side constraint (Taper)

вт





BT Workpiece Ra = 0.5µm

## **HSK** system

#### Feature of HSK arbor

- · Guaranteed strong constrain force by 2-side constraint
- · Guaranteed strengthened cutting at high speeds
- · Guaranteed superior surface roughness
- · Guaranteed repeatability at axle direction and repeated direction

## HSK tolerance comparison

Arbor type	Max. tolerance	Min. tolerance	Available facility
HSK-T	0.075	0.035	Multi-tasking machine
HSK-A	0.33	0.08 (General)	MCT


#### HSK A: HSK T key tolerance comparison





## **BT30 AM1000HS**



















(mm)

ı	Designation	0	ØD	ØD2	ØD3	Q1	Q2	L	ар
BT30	AM1010HS-2	2	10	46	41	35	83	112	5.6
	AM1012HS-2	2	12	46	41	35	83	112	5.6
	AM1012HS-3	3	12	46	41	35	83	112	5.6
	AM1016HS-3	3	16	46	41	35	83	112	5.6
	AM1016HS-4	4	16	46	41	35	83	112	5.6
	AM1020HS-4	4	20	46	41	45	98	127	5.6
	AM1020HS-5	5	20	46	41	45	98	127	5.6

## Available inserts

APMT-MA

Al	-MII-MM	
	-	
- 4		
- 4		

		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0602PDFR-MA																	•	
	060208PDFR-MA																		
	060202PDSR-MM			•							•				•	•			
	0602PDSR-MM			•					•	•	•	•	•		•	•			E06
	060208PDSR-MM			•							•				•	•			
	060212R-MM			•											•	•			
	060216R-MM														•	•			


Specification	<b>6</b>		
	Screw	Wrench	Wrench
Ø10~Ø20	FTKA01842	-	TW06S-A





## **BT40 AM1500HS**



















• AR: 7.5°~13° • RR: -28°~-7°

(mm)


	Designation	©	ØD	ØD <sub>2</sub>	Ø <b>D</b> 3	Q1	<b>Q</b> 2	L	ар
BT40	AM15016HS-2	2	16	63	50	45	83	117	9
	AM15016HS-2L	2	16	63	50	35	118	152	9
	AM15020HS-2	2	20	63	50	60	98	132	9
	AM15020HS-3	3	20	63	50	60	98	132	9
	AM15020HS-2L	2	20	63	50	50	118	152	9
	AM15025HS-3	3	25	63	50	75	113	147	9
	AM15025HS-4	4	25	63	50	75	113	147	9
	AM15025HS-3L	3	25	63	50	65	133	167	9
	AM15032HS-4	4	32	63	50	80	113	147	9
	AM15032HS-5	5	32	63	50	80	113	147	9
	AM15032HS-4L	4	32	63	50	70	133	167	9
	AM15040HS-5	5	40	63	50	60	98	132	9
	AM15040HS-6	6	40	63	50	60	98	132	9
	AM15040HS-5L	5	40	63	50	50	118	152	9

## Available inserts



		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			


Specification	67		
	Screw	Wrench	Wrench
Ø16~Ø40	FTKA02565S	TW08S	-





## **BT40 AM2000HS**

















90° • AR: 7°~10° • RR: -20°~-7°

(mm)

ı	Designation	0	ØD	ØD2	ØD3	Q1	Q2	L	ар
BT40	AM2016HS-2	2	16	63	50	45	83	117	11
	AM2016HS-2L	2	16	63	50	35	118	152	11
	AM2020HS-2	2	20	63	50	60	98	132	11
	AM2020HS-2L	2	20	63	50	50	118	152	11
	AM2025HS-3	3	25	63	50	75	113	147	11
	AM2025HS-3L	3	25	63	50	65	133	167	11
	AM2032HS-4	4	32	63	50	80	113	147	11
	AM2032HS-4L	4	32	63	50	70	133	167	11
	AM2040HS-5	5	40	63	50	60	98	132	11
	AM2040HS-5L	5	40	63	50	50	118	152	11
	AM2050HS-6	6	50	63	50	60	98	132	11
	AM2050HS-6L	6	50	63	50	50	118	152	11

#### Available inserts

		API	MT-M	Α	A	APMT-	ML		APM <sup>°</sup>	T-MM		AP	МТ-М	F	-	APMT-	MN			
			6	new	•	6	nev	9	4			•			4	9	ne	W		
			Cer	met						C	oate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H04	page
APMT	11T3PDFR-MA																		•	
AF IVI I	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML															•	•			
	11T3PDSR-MM				•	•		•		•	•	•	•	•		•	•			
	11T3PDSR-MF				•							•	•			•	•			
	11T308PDSR-MM				•							•		•	•	•	•			E06
	11T312PDSR-MM				•							•		•		•	•			
	11T316R-MM				•							•				•	•			
	11T318R-MM																			
	11T324R-MM				•							•				•	•			
	11T3PDSR-MN2															•				
	11T3PDSR-MN3															•				

<sup>\*\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \*\* Please use the cutters with even teeth.


Specification	Screw	Wrench	
Ø16~Ø50	FTKA02565S	TW08S	





## **BT50 AM3000HS**



















• AR: 7°~10° • RR: -20°~-7°

(mm)


С	Designation	0	ØD	ØD2	ØD3	Q1	Q2	L	ар
BT50	AM3025HS-2	2	25	100	80	65	113	158	16
	AM3025HS-2L	2	25	100	80	55	123	168	16
	AM3032HS-3	3	32	100	80	70	113	158	16
	AM3032HS-3L	3	32	100	80	60	123	168	16
	AM3040HS-4	4	40	100	80	50	98	143	16
	AM3040HS-4L	4	40	100	80	40	108	153	16
	AM3050HS-5	5	50	100	80	50	98	143	16
	AM3050HS-5L	5	50	100	80	40	108	153	16

#### Available inserts

		APN	/IT-M	A	P	PMT-	ML		APM.	T-MM		AP	MT-M	F	P	APMT-	MN			
		0		new	•	6	nev	9	4			1					ne	<b>9</b>		
			Cer	met						С	oate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	亨	page
APMT	1604PDFR-MA																		•	
	160404PDFR-MA																			
	1604PDER-ML															•	•			
	160404PDER-ML															•	•			
	1604PDSR-MM				•	•		•		•	•		•	•	•	•	•			
	1604PDSR-MF				•							•	•			•	•			
	160410PDSR-MM															•	•			E06
	160416PDSR-MM				•							•				•	•			
	160424R-MM				•							•				•	•			
	160430R-MM											•				•	•			
	160432R-MM				•							•				•	•			
	1604PDSR-MN3															•				
	1604PDSR-MN4															•				


<sup>\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \* Please use the cutters with even teeth.

<b>J</b> Turto			
Specification	<b>6</b>		
	Screw	Wrench	
<u>Ø25</u> <u>Ø32</u> ~Ø50	FTKA0408 FTKA0410	TW15S	



## **BT50 AM4000HS**

















• AR: 7°~10° • RR: -20°~-7°

(mm)

	Designation	©	ØD	ØD2	ØD3	Q1	Q2	L	ар
BT50	AM4020HS-1	1	20	100	80	50	98	143	17
	AM4025HS-2	2	25	100	80	65	113	158	17
	AM4032HS-3	3	32	100	80	70	113	158	17
	AM4032HS-3L	3	32	100	80	60	123	168	17
	AM4040HS-4	4	40	100	80	50	98	143	17
	AM4040HS-4L	4	40	100	80	40	108	153	17
	AM4050HS-5	5	50	100	80	50	98	143	17
	AM4050HS-5L	5	50	100	80	40	108	153	17

#### Available inserts

		AP	MT-M	Α	A	PMT-	ML		APM	T-MM		AP	MT-M	F	Α	PMT-	MN			
		4	Cermet		•	6	nev		-			•			4		nev	7		
			Cer	met						С	oate	d						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	문	page
APMT	1806PDFR-MA																		•	
	180604PDFR-MA																		•	
	180612PDFR-MA																		•	
	180616PDFR-MA																			
	180620PDFR-MA																			
	180624PDFR-MA																			
	180630R-MA																			
	1806PDER-ML															•	•			
	180604PDER-ML															•	•			
	180612PDER-ML															•	•			
	180616PDER-ML																			
	180620PDER-ML															•	•			E06
	180624PDER-ML															•	•			LUU
	180630R-ML															•	•			
	1806PDSR-MM									•	•	•	•	•		•	•			
	1806PDSR-MF				•								•			•	•			
	180612PDSR-MM				•							•				•	•			
	180616PDSR-MM				•											•	•			
	180620PDSR-MM																			
	180624PDSR-MM				•											•	•			
	180630R-MM															•	•			
	180632R-MM				•											•	•			
	1806PDSR-MN3															•				
	1806PDSR-MN4															•				


\*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 

\*\* Please use the cutters with even teeth.



## BT30/40 AM1000













• AR: -12.5°~13° • RR: -17°~-6°

(mm)

	Designation	0	ØD	ØD2	ØD3	Q2	L	No. of flute	ар
BT30	AM1016015-2	6	16	46	41	30	62	2	15.5
	AM1020020-3	12	20	46	41	32	64	3	20.5
	AM1025025-4	20	25	46	41	39	71	4	25.5
BT40	AM1016015-2	6	16	63	50	30	67	2	15.5
	AM1020020-3	12	20	63	50	32	69	3	20.5
	AM1025025-4	20	25	63	50	39	76	4	25.5

#### Available inserts




		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	F01	page
APMT	0602PDFR-MA																	•	
	060208PDFR-MA																		
	060202PDSR-MM			•							•				•	•			
	0602PDSR-MM			•					•	•	•	•	•		•	•			E06
	060208PDSR-MM			•							•				•	•			
	060212R-MM			•											•	•			
	060216R-MM														•	•			

## Parts


Specification	6		
	Screw	Wrench	Wrench
Ø16~Ø25	FTKA01842	-	TW06S-A

Available inserts E06



## BT30/40 AM1500













• AR: -12.5°~13° • RR: -17°~-6°

(mm)

	Designation	©	ØD	ØD2	ØD3	Q2	L	No. of flute	ар
BT30	AM15020026-1	3	20	46	41	42	74	1	26.5
	AM15025035-2	8	25	46	41	50	62	2	35
	AM15032044-2	10	32	46	41	60	92	2	44
BT40	AM15020026-1	3	20	63	50	42	79	1	26.5
	AM15025035-2	8	25	63	50	50	87	2	35
	AM15032044-2	10	32	63	50	60	97	2	44


#### Available inserts

				AF	PMT-M	ΙΑ		APMT	-ML		APM	T-MM							
					0	new	4	6	ne	9	-		•						
		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	НО1	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

#### Parts

Specification	67		
	Screw	Wrench	Wrench
Ø20~Ø32	FTKA02565S	TW08S	-


Available inserts E06





## BT30/40 AM2000













(mm)

ı	Designation	<b>(</b>	ØD	ØD2	ØD3	Q2	L	No. of flute	ар
BT30	AM2020029-1	3	20	46	41	45	77	1	29.4
	AM2025038-2	8	25	46	45	55	87	2	38.9
	AM2032048-2	10	32	46	45	65	97	2	48.5
	AM2040058-2	14	40	46	45	75	107	2	58
	AM2050039-4	16	50	46	45	58	90	4	39
	AM2063039-4	16	63	46	45	58	90	4	39
	AM2080039-5	20	80	46	45	63	95	5	39
	AM2100039-6	24	100	46	45	63	95	6	39
BT40	AM2020029-1	3	20	63	50	45	82	1	29.4
	AM2025038-2	8	25	63	50	55	92	2	38.9
	AM2032048-2	10	32	63	50	65	102	2	48.5
	AM2040058-2	14	40	63	50	75	112	2	58
	AM2050039-4	16	50	63	50	58	95	4	39
	AM2063039-4	16	63	63	50	58	95	4	39
	AM2080039-5	20	80	63	50	63	100	5	39
	AM2100039-6	24	100	63	50	63	100	6	39

#### Available inserts


		APN	PMT-MA		ļ	APMT-	ML		APM'	T-MM		AP	MT-M	F	I	APMT-	MN			
		-		new	(	6	nev		4						4		ne	<b>»</b>		
			Cer	met						C	oate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML															•	•			
	11T3PDSR-MM				•	•		•		•	•	•	•	•		•	•			
	11T3PDSR-MF				•							•	•			•	•			
	11T308PDSR-MM													•						E06
	11T312PDSR-MM													•		•	•			
	11T316R-MM															•	•			
	11T318R-MM																			
	11T324R-MM															•	•			
	11T3PDSR-MN3															•				
	11T3PDSR-MN4															•				

- \* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers.
- \* Please use the cutters with even teeth.

#### Parts

Specification	Screw	Wrench
Ø20~Ø100	FTKA02565S	TW08S


Available inserts E06





## **BT50 AM3000**













• AR: 13°~15° • RR: -11°~-4°

(mm)


	Designation	©	ØD	ØD <sub>2</sub>	ØD3	Q2	L	No. of flute	ар
BT50	AM3050043-2	6	50	100	80	72	120	2	43
	AM3063057-4	16	63	100	80	86	134	4	57
	AM3080071-4	20	80	100	80	100	148	4	71
	AM3100071-6	30	100	100	80	100	148	6	71

#### Available inserts

		-	APMT-	MA		APM	T-ML		AP	мт-мі	VI	A	APMT-	MN					
		4	5	T.	<b>.</b>	4		ew	•			4		nev	9				
		Cer	rmet						C	oate	d						Unc	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	문	page
APMT	1604PDFR-MA																	•	
	160404PDFR-MA																		
	1604PDER-ML														•	•			
	160404PDER-ML																		
	1604PDSR-MM			•					•			•	•	•					
	1604PDSR-MF			•							•	•			•	•			
	160410PDSR-MM														•	•			E06
	160416PDSR-MM			•							•				•	•			
	160424R-MM																		
	160430R-MM										•				•	•			
	160432R-MM										•				•	•			
	1604PDSR-MN3														•				
	1604PDSR-MN4														•				

- \*\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers.
- \* Please use the cutters with even teeth.

## Caution when clamping the inserts



#### Parts


Milling

Specification		
	Screw	Wrench
Ø50~Ø100	FTKA0410	TW15S

Available inserts E06

## **BT50 AM4000**













(mm)

	Designation	<b></b>	ØD	ØD2	ØD3	<b>Q2</b>	L	No. of flute	ар
BT50	AM4040046-2	6	40	100	80	75	123	2	46
	AM4050061-2	8	50	100	80	95	143	2	61
	AM4063061-4	16	63	100	80	90	138	4	61
	AM4080076-4	20	80	100	90	105	153	4	76
	AM4100076-6	30	100	100	80	105	153	6	76

#### Available inserts

		AP	МТ-М	Α	ļ	РМТ-	ML		APM	Т-ММ		AP	мт-м	F	ı	APMT-	MN			
			0	new	(	6	ne	9	-			•			4		ne	<b>y</b>		
			Cer	met						(	coate	d						Unco	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	윤	page
APMT	1806PDFR-MA																		•	
	180604PDFR-MA																		-	
	180612PDFR-MA 180616PDFR-MA																			
	180620PDFR-MA																			
	180624PDFR-MA																		•	
	180630R-MA																			
	1806PDER-ML															•	•			
	180604PDER-ML															•				
	180612PDER-ML															•				
	180616PDER-ML															•	•			
	180620PDER-ML															•	•			E06
	180624PDER-ML															•	•			200
	180630R-ML																•			

\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers.

•

\* Please use the cutters with even teeth.

1806PDSR-MM

1806PDSR-MF

180612PDSR-MM

180616PDSR-MM 180620PDSR-MM 180624PDSR-MM 180630R-MM 180632R-MM

1806PDSR-MN3 1806PDSR-MN4

#### Parts

Specification	Screw	Wrench
Ø40~Ø100	FTKA0410	TW15S

Available inserts E06


## Caution when clamping the inserts

•

•


•

•





## **BT50 HAT4000**



(mm)

										(
De	esignation		-	ØD	Q1	Q2	L	No. of flute	ар	Application
		SPMT	ZPMT					nute		
BT50-	HAT4050094-2F	10	1	50	32	119	160	2	94	
(Set)	HAT4050104-2F	11	1	50	32	129	170	2	104	HAT4050032-2F
	HAT4050114-2F	12	1	50	32	139	180	2	114	
	HAT4063094-4F	20	2	63	32	119	160	4	94	
	HAT4063104-4F	22	2	63	32	129	170	4	104	HAT4063032-4F
	HAT4063114-4F	24	2	63	32	139	180	4	114	
	HAT4080094-4F	20	2	80	33	119	160	4	94	
	HAT4080104-4F	22	2	80	33	129	170	4	104	HAT4080033-4F
	HAT4080114-4F	24	2	80	33	139	180	4	114	
(Front Piece)	HAT4050032-2F	3	1	50	32	-	-	2	-	
	HAT4063032-4F	6	2	63	32	-	-	4	-	-
	HAT4080033-4F	6	2	80	33	-	-	4	-	

#### Available inserts

SPMT-MMN ZPMT-MMN





		Cer	met						С	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H0.1	page
SPMT	120508-MMN																		E27
ZPMT	1505PPSR-MMN																		E33

## Set specification

Set Designation	Designation	Front Piece	Clamping Bolt
HAT4050094-2F HAT4050104-2F HAT4050114-2F	HAT4050062-2F HAT4050072-2F HAT4050082-2F	HAT4050032-2F	HSB1255
HAT4063094-4F HAT4063104-4F HAT4063114-4F	HAT4063062-4F HAT4063072-4F HAT4063082-4F	HAT4063032-4F	HSB1670
HAT4080094-4F HAT4080104-4F HAT4080114-4F	HAT4080061-4F HAT4080071-4F HAT4080081-4F	HAT4080033-4F	HSB1682


Specification	6		
	Screw	Wrench	
Ø50~Ø80	ETNA0511	TW20	





## **HSK63A AM1000HS**



















• AR: 7.5°~13° • RR: -28°~-7°


Des	signation	0	ØD	ØD <sub>2</sub>	Ø <b>D</b> 3	Q1	Q2	L	ар
HSK63A	AM1010HS-2	2	10	63	53	35	83	116	5.6
	AM1012HS-2	2	12	63	53	35	83	116	5.6
	AM1012HS-3	3	12	63	53	35	83	116	5.6
	AM1016HS-3	3	16	63	53	35	83	116	5.6
	AM1016HS-4	4	16	63	53	35	83	116	5.6
	AM1020HS-4	4	20	63	53	45	98	131	5.6
	AM1020HS-5	5	20	63	53	45	98	131	5.6

## Available inserts

APMT-MM


						_													
		Cei	rmet						C	oate	d						Unc	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H0.1	page
APMT	0602PDFR-MA																	•	
	060208PDFR-MA																		
	060202PDSR-MM			•							•				•	•			
	0602PDSR-MM			•					•	•	•	•	•		•	•			E06
	060208PDSR-MM			•							•				•	•			
	060212R-MM			•											•	•			
	060216R-MM														•	•			

o i di to			
Specification	61		
	Screw	Wrench	Wrench
Ø10~Ø20	FTKA01842	-	TW06S-A



## **HSK63A AM1500HS**

















• AR: 7.5°~13° • RR: -28°~-7°

(mm)

D	esignation	<b>(</b>	ØD	ØD2	ØD3	Q1	<b>Q2</b>	L	ар
ISK63A	AM15016HS-2	2	16	63	53	45	83	116	9
	AM15016HS-2L	2	16	63	53	35	118	151	9
	AM15020HS-2	2	20	63	53	60	98	131	9
	AM15020HS-3	3	20	63	53	60	98	131	9
	AM15020HS-2L	2	20	63	53	50	118	151	9
	AM15025HS-3	3	25	63	53	75	113	146	9
	AM15025HS-4	4	25	63	53	75	113	146	9
	AM15025HS-3L	3	25	63	53	65	133	166	9
	AM15032HS-4	4	32	63	53	80	113	146	9
	AM15032HS-5	5	32	63	53	80	113	146	9
	AM15032HS-4L	4	32	63	53	70	133	166	9
	AM15040HS-5	5	40	63	53	60	98	131	9
	AM15040HS-6	6	40	63	53	60	98	131	9
	AM15040HS-5L	5	40	63	53	50	118	151	9

## Available inserts


APMT-MA APMT-MM

		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			F00
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

Specification	6				
	Screw	Wrench	Wrench		
Ø16~Ø40	FTKA02565S	TW08S	-		

## **HSK63A AM2000HS**



















• AR: 7°~10° • RR: -20°~-7°

(mm)

De	esignation	0	ØD	ØD2	ØD3	Q1	Q2	L	ар
HSK63A	AM2016HS-2	2	16	63	53	45	83	116	11
	AM2016HS-2L	2	16	63	53	35	118	151	11
	AM2020HS-2	2	20	63	53	60	98	131	11
	AM2020HS-2L	2	20	63	53	50	118	151	11
	AM2025HS-3	3	25	63	53	75	113	146	11
	AM2025HS-3L	3	25	63	53	65	133	166	11
	AM2032HS-4	4	32	63	53	80	113	146	11
	AM2032HS-4L	4	32	63	53	70	133	166	11
	AM2040HS-5	5	40	63	53	60	98	131	11
	AM2040HS-5L	5	40	63	53	50	118	151	11
	AM2050HS-6	6	50	63	53	60	98	131	11
	AM2050HS-6L	6	50	63	53	50	118	151	11


## Available inserts

		AP	мт-м	Α	A	PMT-	ML		APM'	Т-ММ		AP	МТ-М	F	-	APMT-	-MN			
			Correct		(	6	nev	0	-		0		9		4		ne	<b>V</b>		
			Cer	met						C	oate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML															•	•			
	11T3PDSR-MM				•	•		•		•			•	•		•	•			
	11T3PDSR-MF				•							•	•			•	•			
	11T308PDSR-MM				•							•		•	•	•	•			E06
	11T312PDSR-MM				•							•		•		•	•			
	11T316R-MM				•							•				•	•			
	11T318R-MM																			
	11T324R-MM				•							•				•	•			
	11T3PDSR-MN2															•				
	11T3PDSR-MN3															•				

<sup>\*\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 

\*\* Please use the cutters with even teeth.


Faits			
Specification	67		
	Screw	Wrench	
Ø16~Ø50	FTKA02565S	TW08S	





## **HSK63A AM3000HS**

















• AR: 7°~10° • RR: -20°~-7°

(mm)

De	esignation	0	ØD	ØD2	ØD3	Q1	Q2	L	ар
HSK63A	AM3025HS-2	2	25	63	53	65	113	146	16
	AM3025HS-2L	2	25	63	53	55	123	156	16
	AM3032HS-3	3	32	63	53	70	113	146	16
	AM3032HS-3L	3	32	63	53	60	123	156	16
	AM3040HS-4	4	40	63	53	50	98	131	16
	AM3040HS-4L	4	40	63	53	40	108	141	16
	AM3050HS-5	5	50	63	53	50	98	131	16
	AM3050HS-5L	5	50	63	53	40	108	141	16

#### Available inserts

		APN	MT-M	A	4	APMT-	ML		APM.	T-MM		AP	MT-M	F	F	APMT-	MN								
		0	Cermet			new		new		•	6	nev		-			1	9		4		net	N)		
			Cer	met						C	oate	d						Unc	oated						
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H0.1	page					
APMT	1604PDFR-MA																		•						
	160404PDFR-MA																								
	1604PDER-ML															•	•								
	160404PDER-ML															•	•								
	1604PDSR-MM				•	•		•		•	•	•	•	•	•	•	•								
	1604PDSR-MF				•							•	•			•	•								
	160410PDSR-MM															•	•			E06					
	160416PDSR-MM				•							•				•	•								
	160424R-MM				•							•				•	•								
	160430R-MM											•				•	•								
	160432R-MM				•							•				•	•								
	1604PDSR-MN3															•									
	1604PDSR-MN4															•									

<sup>\*\*</sup> Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. 


\*\* Please use the cutters with even teeth.

Specification	Screw	Wrench
<u>Ø25</u> <u>Ø32</u> ~Ø50	FTKA0408 FTKA0410	TW15S



## **HSK63A AM4000HS**



















(mm)


De	signation	0	ØD	ØD2	ØD3	Q1	Q2	L	ар
HSK63A	AM4020HS-1	1	20	63	53	50	98	131	17
	AM4025HS-2	2	25	63	53	65	113	146	17
	AM4032HS-3	3	32	63	53	70	113	146	17
	AM4032HS-3L	3	32	63	53	60	123	156	17
	AM4040HS-4	4	40	63	53	50	98	131	17
	AM4040HS-4L	4	40	63	53	40	108	141	17
	AM4050HS-5	5	50	63	53	50	98	131	17
	AM4050HS-5L	5	50	63	53	40	108	141	17

#### Available inserts



								4			4				4				
		Cer	met						C	Coate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	H01	page
APMT	1806PDFR-MA																	•	
	180604PDFR-MA																	•	
	180612PDFR-MA																	•	
	180616PDFR-MA																	•	
	180620PDFR-MA																	•	
	180624PDFR-MA																	•	
	180630R-MA																	•	
	1806PDER-ML														•				
	180604PDER-ML														•				
	180612PDER-ML														•	•			
	180616PDER-ML														•	•			
	180620PDER-ML														•	•			E06
	180624PDER-ML														•	•			LUU
	180630R-ML														•				
	1806PDSR-MM			•					•	•	•	•	•	•	•	•			
	1806PDSR-MF			•															
	180612PDSR-MM			•							•				•	•			
	180616PDSR-MM														•				
	180620PDSR-MM																		
	180624PDSR-MM															•			
	180630R-MM														•	•			
	180632R-MM			•											•	•			
	1806PDSR-MN3																		
	1806PDSR-MN4														•				


\* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers. \* Please use the cutters with even teeth.





## **HSK63A AM1000**













(mm)

Designation		0	ØD	ØD2	ØD3	Q2	L	No. of flute	ар
HSK63A	AM1016015-2	6	16	63	53	30	66	2	15.5
	AM1020020-3	12	20	63	53	32	68	3	20.5
	AM1025025-4	20	25	63	53	39	75	4	25.5

#### Available inserts


APMT-MA APMT-MM Coated Uncoated

Designation		CN30	NC5330	NCM325	NCM335	NCM5	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
02PDFR-MA																	•	
0208PDFR-MA																		
0202PDSR-MM			•							•				•	•			
02PDSR-MM			•					•	•	•	•	•		•	•			E06
0208PDSR-MM			•							•				•	•			
0212R-MM			•											•	•			
0216R-MM														•	•			
0	208PDFR-MA 202PDSR-MM 2PDSR-MM 208PDSR-MM 212R-MM	208PDFR-MA 202PDSR-MM 2PDSR-MM 208PDSR-MM 212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 208PDSR-MM 212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 0 208PDSR-MM 0 212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 0 208PDSR-MM 0 212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 0 208PDSR-MM 0 212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 0 208PDSR-MM 0 212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 0208PDSR-MM 0212R-MM	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM  208PDSR-MM  212R-MM  4  4  4  4  4  4  4  4  4  4  4  4	2PDFR-MA 208PDFR-MA 202PDSR-MM 2PDSR-MM 0 208PDSR-MM 0 212R-MM 0	2PDFR-MA 208PDFR-MA 202PDSR-MM  2PDSR-MM  208PDSR-MM  212R-MM  4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	2PDFR-MA 208PDFR-MA 202PDSR-MM  2PDSR-MM  208PDSR-MM  208PDSR-MM  212R-MM  •	2PDFR-MA 208PDFR-MA 202PDSR-MM  2PDSR-MM  208PDSR-MM  212R-MM  4  4  4  4  5  6  6  6  6  7  7  8  8  8  8  8  8  8  8  8  8  8	2PDFR-MA         208PDFR-MA         202PDSR-MM       •         2PDSR-MM       •       •         208PDSR-MM       •       •         212R-MM       •       •	2PDFR-MA         208PDFR-MA         202PDSR-MM       • • • • • •         2PDSR-MM       • • • • • • •         208PDSR-MM       • • • • • • •         212R-MM       • • • • • • • •	2PDFR-MA         208PDFR-MA         202PDSR-MM         2PDSR-MM         208PDSR-MM         08PDSR-MM         0      <	2PDFR-MA         208PDFR-MA         202PDSR-MM         2PDSR-MM         008PDSR-MM         008PDSR-MM	2PDFR-MA         •           208PDFR-MA         •           202PDSR-MM         •         •         •           2PDSR-MM         •         •         •         •         •           208PDSR-MM         •

#### Parts



→ Available inserts E06








# **HSK63A AM1500**














(mm)


De	esignation	0	ØD	ØD2	ØD3	Q2	L	No. of flute	ар
HSK63A	AM15020026-1	3	20	63	53	42	78	1	26.5
	AM15025035-2	8	25	63	53	50	86	2	35
	AM15032044-2	10	32	63	53	60	96	2	44

### Available inserts




		Cer	met						C	oate	d						Unco	oated	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
APMT	0903PDFR-MA																	•	
	090308PDFR-MA																		
	0903PDER-ML														•	•			
	090308PDER-ML														•	•			
	0903PDSR-MM			•					•	•	•	•			•	•			E06
	090308PDSR-MM			•							•				•	•			
	090312R-MM										•				•	•			
	090316R-MM			•							•				•	•			
	090320R-MM										•				•	•			

# Caution when clamping the inserts




Specification	67		
	Screw	Wrench	Wrench
Ø20~Ø32	FTKA02565S	TW08S	-



# **HSK63A AM2000**













• AR: -12.5°~13° • RR: -17°~-6°


(mm)

De	signation	0	ØD	ØD2	ØD3	<b>Q2</b>	L	No. of flute	ар
HSK63A	AM2020029-1	3	20	63	53	45	81	1	29.4
	AM2025038-2	8	25	63	53	55	91	2	38.9
	AM2032048-2	10	32	63	53	65	101	2	48.5
	AM2040058-2	14	40	63	53	75	111	2	58
	AM2050039-4	16	50	63	53	58	94	4	39
	AM2063039-4	16	63	63	53	58	94	4	39
	AM2080039-5	20	80	63	53	63	99	5	39
	AM2100039-6	24	100	63	53	63	99	6	39

### Available inserts

		API	MT-M	Α	A	PMT-	ML		APM <sup>*</sup>	T-MM		AP	MT-M	F	A	PMT-	MN			
			6	new	(	6	nev		-		0	•			4		nev	9		
			Cer	met						C	oate	d						Unc	oated	
	Designation		CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	된	page
APMT	11T3PDFR-MA																		•	
	11T308PDFR-MA																			
	11T3PDER-ML															•	•			
	11T308PDER-ML															•	•			
	11T3PDSR-MM				•			•		•	•	•	•	•		•	•			
	11T3PDSR-MF				•							•	•			•	•			
	11T308PDSR-MM				•							•		•	•	•	•			E06
	11T312PDSR-MM				•							•		•		•	•			
	11T316R-MM				•							•				•	•			
	11T318R-MM																			
	11T324R-MM				•							•				•	•			
	11T3PDSR-MN3															•				
	11T3PDSR-MN4																			

- \* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers.
- \* Please use the cutters with even teeth.




### Parts

Specification	Screw	Wrench
Ø20~Ø100	FTKA02565S	TW08S

Available inserts E06

# **HSK100A AM3000**














(mm)


Des	ignation	0	ØD	ØD2	Ø <b>D</b> 3	Q2	L	No. of flute	ар
HSK100A	AM3050043-2	6	50	100	88	72	111	2	43
	AM3063057-4	16	63	100	88	86	125	4	57
	AM3080071-4	20	80	100	88	100	139	4	71
	AM3100071-6	30	100	100	88	100	139	6	71

# Available inserts


		APM	IT-MA		APMT	-ML		APN	IT-MM		AP	MT-M	F	Α	PMT-	MN			
		3	new	•	6	ne	w 	-		,		6		4		nev	9		
		(	Cermet						C	oate	d						Unc	oated	
	Designation		CN2500	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	G10	문	page
APMT	1604PDFR-MA																	•	
	160404PDFR-MA																		
	1604PDER-ML															•			
	160404PDER-ML																		
	1604PDSR-MM				•														
	1604PDSR-MF			•															
	160410PDSR-MM																		E06
	160416PDSR-MM			•															
	160424R-MM			•															
	160430R-MM										•				•	•			
	160432R-MM										•				•	•			
	1604PDSR-MN3																		
	1604PDSR-MN4																		

- \* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers.
- \* Please use the cutters with even teeth.

# Caution when clamping the inserts




Specification	Screw	Wrench
Ø50~Ø100	FTKA0410	TW15S





# **HSK100A AM4000**













• AR: -13°~15° • RR: -11°~-4°

(mm)


Des	signation	0	ØD	ØD2	ØD3	Q2	L	No. of flute	ар
HSK100A	AM4040046-2	6	40	100	88	75	114	2	46
	AM4050061-2	8	50	100	88	95	134	2	61
	AM4063061-4	16	63	100	88	90	129	4	61
	AM4080076-4	20	80	100	88	105	144	4	76
	AM4100076-6	30	100	100	88	105	144	6	76

# Available inserts

			APMT-I	/ΙΑ		ΑP	MT-ML		APN	IT-MM	APMT-MF	-	APMT-N	N						
			6	nev	9	4		new	4	-		4		new						
	Cermet			Coat	ed			Uncoated				Cerme			Coa	ated			Uncoated	
Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535 NCM545	PC2505 PC2010	PC3700	PC9530	PC9540 PC5300 PC5400	G10 H01	page		Designation	CN2500 CN30	NC5330 NCM325	NCM535 NCM545	PC2505	PC2510	PC6510 PC9530	PC9540 PC5300	G10 H01	page
APMT 1806PDFR-MA								•		APMT	180624PDER-ML				П			• •		
180604PDFR-MA								•			180630R-ML							• •		
180612PDFR-MA								•			1806PDSR-MM		•		• (	•	• •	• • •		1
180616PDFR-MA								•			1806PDSR-MF		•				•	•		
180620PDFR-MA								•			180612PDSR-MM		•			•		• •		
180624PDFR-MA								•	E06		180616PDSR-MM		•					• •		E06
180630R-MA								•	E00		180620PDSR-MM									E00
1806PDER-ML							• •				180624PDSR-MM		•					•		1
180604PDER-ML							• •		1		180630R-MM							• •		1
180612PDER-ML							• •				180632R-MM		•					• •		
180616PDER-ML							• •		1		1806PDSR-MN3							•		
180620PDER-ML							• •		1		1806PDSR-MN4							•		1

- \* Please purchase 2 types of APMT-MN (nick type) inserts with different chip breakers.

# Caution when clamping the inserts



### Parts

Milling


Specification	Screw	Wrench
Ø40~Ø100	FTKA0410	TW15S

Available inserts E06



# HSK-XD19



















• AR: 9°~13° • RR: -11°~-13°

(mm)

	Designation	0	ØD	Ød <sub>1</sub>	Q <sub>1</sub>	Q <sub>2</sub>	L	ар	kg
HSK63A-	PAV032R-3-100-XD19-A,B	3	32	63	60	74	100	17	0.97
	PAV050R-3-100-XD19-A,B	3	50	63	72	74	100	17	1.37

 $<sup>\</sup>times$  Type A uses Insert Nose R 0.4~3.2, and Type B uses Nose R 4.0~5.0


# Available inserts


# **XDET-MA**



		Cermet	Coated		Uncoate	d				Coated	Uncoated	
	Designation	CN2500 CN30	NC5330 NCM325 NCM325 NCM535 NCM545 NCM545 PC5700 PC6510 PC9530 PC9530	PD1005 PD1010	두	page		Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC3700 PC6510 PC9530 PC9540 PC5300 PC5300 PC5300	5	page
XDET	190504PEFR-MA				• •	)	XDET	190524PEFR-MA			• •	
	190508PEFR-MA				• •			190530PEFR-MA			• •	
	190512PEFR-MA				• •	E31		190532PEFR-MA			• •	E31
	190516PEFR-MA				• •		1	190540PEFR-MA			• •	•
	190520PEFR-MA				• •			190550PEFR-MA			• •	]

Specification		
	Screw	Wrench
Ø32~Ø50	PTKA0408-A	TW15S





 $<sup>\</sup>times$  When using a spindle at high speed, please check the balance of tool and use it after replacing with the new screw.


# Technical Information for O-ring Cutter

# High productivity with optimized grade for high speed machining


# **O-ring Cutter**

- Optimized for grooving the seat of an O-ring in a plastic mold
- Guarantees superior surface roughness compared to HSS and brazed tool
- High productivity with optimized grade for high speed machining
- Reduced time for regrinding and tool alignment
- Special types are available for quotation

# Code system



# Grooving and assembly of O-ring



O-ring size	ØD	(ØD <sub>1</sub> )	h ± 0.05		
P08	11.0	5.8			
P09	12.0	6.8	1.40		
P10	13.0	7.8			
P11	15.0	8.5			
P12	16.0	9.5			
P14	18.0	11.5			
P15	19.0	12.5			
P16	20.0	13.5	1.80		
P18	22.0	15.5			
P20	24.0	17.5			
P21	25.0	18.5			
P22	26.0	19.5			
P24	30.0	20.6	2.70		
P25	31.0	21.6	2.10		

O-ring size	ØD	(ØD <sub>1</sub> )	h ± 0.05
P26	32.0	22.6	
P28	34.0	24.6	
P29	35.0	25.6	
P30	36.0	26.6	
P31	37.0	27.6	0.70
P32	38.0	28.6	2.70
P34	40.0	30.6	
P35	41.0	31.6	
P38	44.0	34.6	
G40	46.0	36.6	
G25	30.0	21.8	
G30	35.0	26.8	2.40
G35	40.0	31.8	2.40
G40	45.0	36.8	

(mm)

# Recommended cutting condition

		vc (m/min)
Workpiece	fz (mm/t)	Coating
		PC3500
Stainless Steel (STS304)	0.03~0.12	60~130
Carbon Steel (SM□□C)	0.05~0.15	80~150
Alloy Steel (SCM)	0.05~0.15	80~150
Hardened Steel (STD, NAK)	0.03~0.12	60~130

### Machining Example






Milling

# **ORC**





(mm)

D	Designation	0	ØD	Ød1	Ød	Q	L	Available inserts	O-Ring size
ORC -	P08	1	11.0	5.7	16	30	150	ORG265	P08
	P09	1	12.0	6.7	16	30	150	ORG265	P09
	P10	1	13.0	7.7	16	30	150	ORG265	P10
	P11	1	15.0	8.5	16	30	150	ORG325	P11
	P12	2	16.0	9.5	16	30	200	ORG325	P12
	P14	2	18.0	11.5	20	30	200	ORG325	P14
	P15	2	19.0	12.5	20	30	200	ORG325	P15
	P16	2	20.0	13.5	20	30	200	ORG325	P16
	P18	2	22.0	15.5	20	30	200	ORG325	P18
	P20	2	24.0	17.5	25	30	200	ORG325	P20
	P21	2	25.0	18.5	25	30	200	ORG325	P21
	P22	2	26.0	19.5	25	30	200	ORG325	P22
	P24	2	30.0	20.6	32	40	250	ORG470	P24
	P25	2	31.0	21.6	32	40	250	ORG470	P25
	P26	2	32.0	22.6	32	40	250	ORG470	P26
	P28	2	34.0	24.6	32	40	250	ORG470	P28
	P29	2	35.0	25.6	32	40	250	ORG470	P29
	P30	2	36.0	26.6	32	40	250	ORG470	P30
	P31	2	37.0	27.6	32	40	250	ORG470	P31
	P32	2	38.0	28.6	32	40	250	ORG470	P32
	P34	2	40.0	30.6	42	40	250	ORG470	P34
	P35	2	41.0	31.6	42	40	250	ORG470	P35
	P38	2	44.0	34.6	42	40	250	ORG470	P38
	P40	2	46.0	36.6	42	40	250	ORG470	P40
ORC -	G25	2	30.0	21.9	32	40	250	ORG405	G25
	G30	2	35.0	26.9	32	40	250	ORG405	G30
	G35	2	40.0	31.9	42	40	250	ORG405	G35
	G40	2	45.0	36.9	42	40	250	ORG405	G40


# Available inserts

ORG



									_												
		Cer	rmet	t				Coated						Uncoated							
Cutter Designation	De	esignation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
ORC-P08~P10	ORG	265																			
ORC-P11~P22		325										•									E15
ORC-P24~P40		470										•									E15
ORC-G25~G40		405																			

Specification	Screw	Wrench	
Ø11~Ø26	FTKA0307	TW09S	
Ø30~Ø46	FTGA03508	TW15S	
Ø30~Ø45	FIGAUSSUS	100100	



# E Technical Information for Chamfer Tool

# All applications for chamfers

# **Chamfer Tool**


- All chamfer applications
- Chamfer angles 15°, 30°, 45°, 60° for a variety of customer's needs
- The long cutting-edge provides a wide chamfering range





**Back & Front Chamfer Tools** 


# Code system



# Recommended cutting condition


Workniego	Grades	ØD (Ø	5~Ø20)	ØD (Ø25~Ø35)			
Workpiece	Grades	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)		
	PC3700	160~270		160~270			
P	PC5300	190~310	0.05~0.25	190~310	0.05~0.25		
	ST30A	60~100		60~100			
М	PC5300	100~160	0.05~0.20	100~160	0.10.0.20		
IVI	PC5400	70~120	0.05~0.20	70~120	0.10~0.30		
V	PC5300	110~180	0.10, 0.20	110~180	0.20, 0.50		
K	G10	50~90	0.10~0.30	50~90	0.30~0.50		

# Application example




# Multi-functional Chamfer Tool

# Code system



# Application area and recommended cutting condition



Warknings	Hardness (HpC)	Centering	Grooving	Chamfering		
Workpiece	Hardness (HRC)	vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	
Mild steel, Carbon steel, Alloy steel	Under HRC 30	80~200	0.01~0.04	100~250	0.04~0.06	
High Carbon steel, Alloy steel	H <sub>R</sub> C 30, 40	150~250	0.02~0.06	150~300	0.05~0.10	
Aluminum, Copper	-	150~300	0.04~0.08	150~350	0.05~0.10	
Cast iron	-	80~150	0.02~0.06	100~250	0.05~0.10	
Stainless steel	-	60~120	0.01~0.03	60~150	0.03~0.06	
HRSA		60~80	0.01~0.03	60~100	0.03~0.06	

Note) Please keep fz. backtouch & chipping one caused by wrong fz

# Machining example











# **Solid Chamfer Tool**

# Code system




### Features





- For internal chamfering up to 0.5 mm
- · Can be applied to side milling and easy to regrinding

## **CCT (Centering & Chamfering Tool)**




- Chipping resistance realizes machining in high speed due to double point angle
- · Lowers cutting load due to web thinning


# CET/CCT Application example

Туре	Centering	Hole Chamfering	Chamfering (External)	Chamfering (Internal)	Side milling	Slot milling
Applications (CET)						
60°	×	•	•	●~▲	•	×
90°	<b>A</b>	•	•	•	•	●~▲
120°	•	•	•	•	•	•
Applications (CCT)						
60°	•	•	●~▲	<b>▲</b> ~×	×	×
90°	•	•	●~▲	<b>▲</b> ~×	×	×
120°	•	•	•	•	×	•

# **CE** (Back & Front)









(mm)

	Decimation	(a)	αD	αD.	αч		Eia	Aveilable incorte	α° (Cham	fer angle)	Machining range	Hees
	Designation		ØD	ØD1	Ød	ар	Fig.	Available inserts	Front	Back	(Min~Max)	Uses
CE	15-1125R-S20	2	25	30.5	20	9.5	1		15°	-	Ø25~Ø30	Front chamfering
	30-1125R-S20	2	25	35.5	20	8.5	1		30°	60°	Ø25~Ø35	Front, Back chamfering
	45-1107R-S20	1	7	21.9	20	7.0	1	SPMT110408-KC	45°	-	Ø7~Ø21	Front chamfering
	45-1119R-S20	2	19	33.9	20	7.0	1	3FWITI10400-KC	45°	45°	Ø19~Ø33	Front, Back chamfering
	45-1125R-S20	3	25	39.9	20	7.0	1		45°	45°	Ø25~Ø39	Front, Back chamfering
	60-1125R-S32	3	25	43.3	32	5.0	1		60°	30°	Ø25~Ø42	Front, Back chamfering
	45-1207R-S32	1	7	23.3	32	7.8	2		45°	-	Ø7~Ø22	Front chamfering
	45-1220R-S32	2	20	37.3	32	7.8	2	SPMN120308	45°	-	Ø21~Ø36	Front chamfering
	45-1225R-S32	2	25	42.3	32	7.8	2	3F WIN 120306	45°	-	Ø26~Ø41	Front chamfering
	45-1235R-S32	2	35	52.3	32	7.8	2		45°	-	Ø36~Ø51	Front chamfering

# Available inserts






		Cer	rmet						C	oate	d						Uı	ncoat	ted	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	F01	page
SPMT	110408-KC										•						•	•		E27
SPMN	120308																•			E21

Specification						
	Screw	Clamp	C-Ring	Wrench	Wrench	
Ø7~Ø25 (1100 type)	FTKA0408	-	-	TW15S	-	
Ø7~Ø35 (1200 type)	CHX0617L	CH6R2	CR05	-	HW30L	

# E Chamfer Tools

# **CE** (Long chamfer)







• AR: -5°~1° • RR: 0°

(mm)

	Designation	0	ØD	ØD <sub>1</sub>	Ød	ар	α° (Chamfer angle)	Machining range (Min~Max)	Uses
CE	30-3105R-S32	1	5	35	32	26	30°	Ø5~Ø35	Front Chamfering
	45-3105R-S32	2	5	48	32	21	45°	Ø5~Ø48	Front Chamfering
	60-3105R-S32	2	5	57	32	15	60°	Ø5~Ø57	Front Chamfering

# Available inserts

XCET-KC





		Cer	met						C	oate	d						Uı	ncoat	ed	
D	esignation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
XCET	310404ER-KC										•						•	•		E31

Screw Wrench
crew Wrench

# **CE** (Multi-functional)















(mm)

	Designation	ØD	Ød	Q	L	ар	Fig.	Available Inserts	Machining range (Min~Max)	Uses
CE	45-1600R-S12	21.2	12	40	90	10	2	TWX16R-KC	Ø0 ~ Ø20	
	45-1600R-S20	21.2	20	50	110	10	1	TWX16R-KC	Ø0 ~ Ø20	
	45-1600R-L20	21.2	20	60	200	10	1	TWX16R-KC	Ø0 ~ Ø20	Centering
	45-2200R-S12	28.8	12	40	90	14	2	TWX22R-KC	Ø0 ~ Ø27	Grooving Chamfering
	45-2200R-S25	28.8	25	50	110	14	1	TWX22R-KC	Ø0 ~ Ø27	o
	45-2200R-L25	28.8	25	60	200	14	1	TWX22R-KC	Ø0 ~ Ø27	

# Available inserts

TWX-KC




									C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	Н	page
TWX	16R-KC										•				•					F00
	22R-KC										•									E29

# E Solid Chamfer Tool

# **CET**






(mm)

Desig	nation	ØD	Ød	Q	L	$\theta$ °
CET060 -	030	3	3	5.5	50	
	040	4	4	7	50	
	060	6	6	10	60	
	080	8	8	13	70	60°
	100	10	10	16	70	
	120	12	12	18	80	
	160	16	16	24	100	
CET090 -	030	3	3	5.5	50	
	040	4	4	7	50	
	060	6	6	10	60	
	080	8	8	13	70	90°
	100	10	10	16	70	
	120	12	12	18	80	
	160	16	16	24	100	
CET120 -	030	3	3	5.5	50	
	040	4	4	7	50	
	060	6	6	10	60	
	080	8	8	13	70	120°
	100	10	10	16	70	
	120	12	12	18	80	
	160	16	16	24	100	

# CCT




(mm)

Design	nation	$ \emptyset D = \emptyset d $	ØD1	L	$\theta^{f o}$	Fig.
CCT060 -	030	3	1.0	40		
	040	4	1.5	40		
	060	6	2.0	50		
	080	8	2.5	60		1
	100	10	3.0	70		
	120	12	4.0	80		
	160	16	5.0	100		
CCT060T -	030	3	1.0	40		
	040	4	1.5	40		
	060	6	2.0	50	60°	
	080	8	2.5	60		
	100	10	3.0	70		
	120	12	4.0	80		
	160	16	5.0	100		2
CT060T -	030L	3	1.0	100		
	040L	4	1.5	100		
	060L	6	2.0	100		
	080L	8	2.5	120		
	100L	10	3.0	120		
	120L	12	4.0	150		
CT090 -	030	3	1.0	40		
	040	4	1.5	40		
	060	6	2.0	50		
	080	8	2.5	60		1
	100	10	3.0	70		
CTOOOT	120	12	4.0	80		
	160	16	5.0	100		
CT090T -	030	3	1.0	40		
	040	4	1.5	40		
	060	6	2.0	50	000	
	080	8	2.5	60	90°	
	100	10	3.0	70		
	120	12	4.0	80		
	160	16	5.0	100		2
CT090T -	030L	3	1.0	100		-
7C10301 -	040L	4	1.5	100		
	060L	6	2.0	100		
	080L	8	2.5	120		
	100L	10	3.0	120		
	120L	12	4.0	150		
CCT120 -	030	3	1.0	40		
O 1 120 -	040	4	1.5	40		
	060	6	2.0	50		
	080	8	2.5	60		1
	100	o 10	3.0	70		'
	120	12	4.0	80		
	160	16	5.0	100		
CT120T	030	3	1.0	40		-
CT120T -						
	040 060	6	1.5 2.0	40 50		
	080		2.5	60	120°	
	100	8 10	3.0	70		
	100	12		70		
	120	16	4.0	80		
	160	16	5.0	100		2
CT120T -	030L	3	1.0	100		
	040L	4	1.5	100		
	060L	6	2.0	100		
	080L	8	2.5	120		
	100L	10	3.0	120		
	120L	12	4.0	150		

# E T-Cutter

# **TFE**









(mm)

1	Designation	©	ØD	Ød	Ød1	Q	L	ар	Available inserts
TFE	2125R/L	2	21	25	10.5	20	109	9	CPMT06
	2525R/L	2	25	25	12.5	21	112	11	CPMT08
	3232R/L	2	32	32	16.5	26	120	14	CPMT09
	4032R/L	2	40	32	20.5	32	130	18	CPMH12
	5032R/L	4	50	32	26.5	38	140	22	CPMH12

# Available inserts

СРМТ СРМН Uncoated Cermet Coated PC2510 PC3700 Designation page 을 달 CPMT 060204-MM 080308-MM E08 09T308-MM СРМН 120408-MM

# Parts

Specification				
	Screw	Wrench		
Ø21	FTNA02555	TW08S		
Ø25	FTNA0306	TW09S		
Ø32	FTNA0407	TW15S		
Ø40	DTMAGERIA	TMACO		
Ø50	PTMA0511A	TW15S		

Assembling





# Inserts feature a buffed top surface ensuring better chip control and reducing built-up edge

# **Pro-A Mill**

- Buffed top face of insert ensures good chip control and reduces built-up edge
- Small size modular type for aluminum machining
- Various line up of modular system for aluminum machining
- For shouldering, curved surface and ramping
- High rake angle chip breaker ensures excellent surface roughness, improved cooling effects, and chip control by through coolant system, even in deep pocket machining

### Uses









Copying

Shouldering

Ramping Through coolant

### Pro-A Mill series

Туре			Through coolant system		
Application of small-sized Aluminum machining	Pro-A 2000			<ul> <li>Modular: Ø12~Ø42</li> <li>Shank: Ø12~Ø42</li> <li>Insert: VDKT11T210N-MA</li> <li>VDKT11T220N-MA</li> </ul>	0
General application of Aluminum machining	Pro-A 4000			• cutter: Ø40~Ø100 • Shank: Ø32~Ø40 • Insert: VCKT220530N-MA	0

# Recommended cutting condition

Work	rpiece	Cutting speed vc (m/min)			
Alumainuma allau	Rm < 280 MPa	1000			
Aluminum alloy	Rm > 280 MPa	800			
Copper alloy	Long chip	250			
Thermo plastic	-	300			
Aluminum alloy	Si < 12%	800			
Copper alloy	Short chip	400			
Magnesium alloy	-	400			
Duroplastics	-	150			




# Technical Information for Pro-A Mill


# Pro-A Mill ramping & helical cutting technical data


1. Ramping

2. Blind hole helical cutting

3. Thru hole helical cutting







(mm)

		Ram	ping	Blind hole helical cutting				Thru hole helical cutting	
Designation	ØD	a°	Lmin	ØDHmin	dmax	ØDHmax	dmax	ØDHmin	dmax
PAS2012HR	12	11.9	38	21	4.4	23	4.8	19	4.0
PAS2016HR	16	12.5	36	29	6.4	31	6.9	27	6.0
PAS2020HR	20	9.7	47	37	6.3	39	6.7	35	6.0
PAS2025HR	25	7.6	60	47	6.3	49	6.5	45	6.0
PAS2032HR	32	5.8	79	61	6.2	63	6.4	59	6.0
PAS2042HR	42	4.3	105	81	6.2	83	6.3	79	6.0
PAS4032HR	32	24.4	22	54	15.0	59	26.8	40	15.0
PAS4040HR	40	18.4	30	70	15.0	75	25.0	56	15.0
PAS4050HR	50	14.0	40	90	15.0	95	23.8	76	15.0
PAS4063HR	63	10.7	53	116	15.0	121	22.8	102	15.0
PAC(M)4080HR	80	8.1	70	150	15.0	155	22.1	136	15.0
PAC(M)4100HR	100	6.3	90	190	15.0	195	21.7	176	15.0

<sup>•</sup> Lmin: When ap = 8 mm

 $Lmin = \frac{ap}{\tan \alpha^{\circ}} (mm)$ 

α°: Max. rampig angle ap: Depth of cut

<sup>·</sup> Lmin: Minimum inclination cutting length





## Features a strong clamping provided by the concave grooves on the back surface of the inserts

# **Pro-X Mill**


- Inserts feature a buffed top surface ensuring a smoother chip evacuation and reducing built-up edge
- High rake angle of insert provides good surface finish and low cutting load
- Specially designed for high speed machining of aluminum
- Suitable for square shouldering and curved surface machining


# Clamping system for high speed





# Centrifugal force as per RPM







# Max. RPM as per cutting diameter

Cutting diameter	500	0 type	6000 type			
ØD (mm)	n (min <sup>-1</sup> )	vc (m/min)	n (min <sup>-1</sup> )	vc (m/min)		
20	14,000	879	-	-		
25	28,000	2,199	15,000	1,178		
32	25,000	2,513	23,000	2,312		
40	22,000	2,764	20,000	2,513		
50	20,000	3,141	18,000	2,827		
63	18,000	3,562	16,000	3,166		
80	16,000	4,021	14,000	3,518		
100	14,000	4,398	13,000	4,084		
125	13,000	5,105	11,000	4,319		

<sup>※</sup> In case of actual machining accidental breakage of insert or tool could happen even under the written RPM special cover or door is necessary to prevent damage from broken insert or broken tool

## Recommended cutting condition

Work	piece	Cutting Speed vc (m/min)	Feed fz (mm/t)	
Aluminum alloy	Rm280 < MPa Rm280 > MPa	1200 1000	0.30 0.25	
Copper alloy Thermo plastic	Long chipping -	400 350	0.20 0.15	
Aluminum alloy	Si < 12% Si ≥ 12%	1000 300	0.25 0.23	
Copper alloy	Short chipping	500	0.20	
Magnesium alloy	-	450	0.20	
Duroplastics	-	200	0.15	


# **Technical Information for Pro-X Mill**


# Pro-X Mill ramping & helical cutting technical data


1. Ramping

2. Blind hole helical cutting

3. Thru hole helical cutting







(mm)


		Ramping			Blind hole H	lelical cutting		Thru hole Helical cutting	
Designation	ØD	a°	Lmin	ØDHmin	dmax	ØDHmax	dmax	ØDHmin	dmax
PAXS5020HR	20	8.4	68	32	4.7	34	5.0	27	4.0
PAXS5025HR	25	13.2	43	42	9.9	44	10.4	34	8.0
PAXS5032HR	32	9.5	60	56	9.3	58	9.7	48	8.0
PAXS5040HR	40	7.1	80	72	9.0	74	9.3	64	8.0
PAXCM5050HR	50	5.4	105	92	8.8	94	9.0	84	8.0
PAXCM5063HR	63	4.2	138	118	8.6	120	8.7	110	8.0
PAXC(M)5080HR	80	3.2	180	152	8.4	154	8.6	144	8.0
PAXC(M)5100HR	100	2.5	230	192	8.3	194	8.4	184	8.0
PAXC(M)5125HR	125	2.0	293	242	8.3	244	8.3	234	8.0
PAXS6025HR	25	9.0	63	42	6.6	44	6.9	38	6.0
PAXS6032HR	32	6.6	87	56	6.5	58	6.7	52	6.0
PAXS6040HR	40	12.1	47	72	15.4	74	15.9	56	12.0
PAXCM6050HR	50	9.0	63	92	14.5	94	14.8	76	12.0
PAXCM6063HR	63	6.7	85	118	13.9	120	14.1	102	12.0
PAXC(M)6080HR	80	5.0	113	152	13.4	154	13.6	136	12.0
PAXC(M)6100HR	100	3.9	147	192	13.1	194	13.2	176	12.0
PAXC(M)6125HR	125	3.0	188	242	12.8	244	13.0	226	12.0

<sup>•</sup> Lmin: When ap = 10mm

 $\alpha^{\circ} :$  Max. rampig angle ap: Depth of cut

 $Lmin = \frac{ap}{tan \alpha^{\circ}} (mm)$ 

# Plunging, slotting, drilling technical data



- 1. When drilling, grooving machining sequence is  $\textcircled{1} \to \textcircled{2} \to \textcircled{3} \to \textcircled{4}$
- When drilling, grooving, decrease the feed and cutting speed 30%~50% from the recommended data

### · Cutting condition for drilling

Holder	ap (mm)					
noidei	5000 type	6000 type				
Ø20	8	-				
Ø25	4	11				
Ø32	4	6				
Ø40~125	4	6				

Insert	ap (mm)
XETK19	4
XETK25	6

# Uses





Copying Helical cutting



Slotting & Ramping Shouldering



<sup>•</sup> Lmin: Minimum inclination cutting length

## New indexable milling tool for the machining of high quality workpieces

# **Pro-L Mill**

- Improved perpendicularity and lower cutting resistance due to the combined design of the clearance face and high helix edge of these inserts
- Productivity increase due to more than half as much of depth of cut comparing to existing product
- · Strong clamping design by adaption of double screw on system
- Improved chip flow due to helical type design of chip pocket and application of coolant system

### Uses











Facing


Slotting Shoulderina

Ramping


Helical cutting

### Code system

### · Cutter



### Shank



### Features

Strong clamping by 2 screw on system



Enhanced chip flow and increased tool life by inner coolant system

Set of various Nose-R

Improved perpendicularity and decreased cutting resistance due to application of high helix

### Features of chip breakers

I	Insert	Cutting-edge	Uses	Features	
MA	MA A		Al	Edge optimized for aluminum machining and buffed finish ensuring an excellent machining quality	
ML	50		Hard-to-cut material	Design of low cutting resistance chip breaker ensures excellent machining quality for light cutting and hard-to-cut material	

# **Technical Information for Pro-L Mill**

# Selection of grades and chip breaker

Category	M (Stainless steel)	N (Aluminum alloy)	S (HRSA)		
Grades	PC5300/PC5400	H01	PC5300/PC5400		
MA	-	0	-		
ML	0	-	0		

# Application examples

### Al6061 (HRC30)


### ■ Cutting condition


vc = 500 m/min, fz = 0.2 mm/t,  $ap = 30\sim60$  mm,  $ae = 1\sim5$  mm (finishing: 1 mm, roughing: 5 mm), z = 3




# Pro-L Mill ramping & helical cutting technical data









3. Thru hole helical cutting

(mm)

		Ran	ping		Blind hole h	elical cutting		Thru hole he	elical cutting
Designation	ØD	a°	Lmin	ØDHmin	dmax	ØDHmax	dmax	ØDHmin	dmax
PALS032HR-2S20	32	3.37	170	60	3.5	62	3.6	55	3.2
PALS032HR-2S25	32	3.37	170	60	3.5	62	3.6	55	3.2
PALS032HR-2S32	32	3.37	170	60	3.5	62	3.6	55	3.2
PALS040HR-2S32	40	2.12	270	76	2.8	78	2.9	71	2.6
PALS040HR-2S40	40	2.12	270	76	2.8	78	2.9	71	2.6
PALS040HR-2S42	40	2.12	270	76	2.8	78	2.9	71	2.6
PALS040HR-3S32	40	2.12	270	76	2.8	78	2.9	71	2.6
PALS040HR-3S40	40	2.12	270	76	2.8	78	2.9	71	2.6
PALS040HR-3S42	40	2.12	270	76	2.8	78	2.9	71	2.6
PALS050HR-3S32	50	2.08	275	96	3.5	98	3.6	91	3.3
PALS050HR-3S40	50	2.08	275	96	3.5	98	3.6	91	3.3
PALS050HR-3S42	50	2.08	275	96	3.5	98	3.6	91	3.3
PALS063HR-4S32	63	1.76	325	122	3.8	124	3.8	117	3.6
PALS063HR-4S40	63	1.76	325	122	3.8	124	3.8	117	3.6
PALS063HR-4S42	63	1.76	325	122	3.8	124	3.8	117	3.6
PALS063HM-4S32	63	1.76	325	122	3.8	124	3.8	117	3.6
PALS063HM-4S40	63	1.76	325	122	3.8	124	3.8	117	3.6
PALS063HM-4S42	63	1.76	325	122	3.8	124	3.8	117	3.6
PALCM063HR	63	1.76	325	122	3.8	124	3.8	117	3.6

<sup>•</sup> Lmin: When ap = 10 mm

 $\alpha^{\circ}\,$  : Max. rampig angle

ap : Depth of cut



<sup>•</sup> Lmin: Minimum inclination cutting length




# Deep cutting milling tools to maximize productivity in aluminum machining

# **Pro-XL Mill**

- **Productivity** Cutting time is shortened by finishing the process with a single pass of deep shouldering in aluminum machining
- High quality Shouldering within a single pass enables walls with perfect perpendicularity
- Clamping stability Two-Screw On system secures clamping stability

## Features of Pro-XL Mill





Improved chip flow and inhibited built-up edges thanks to mirror-like finishing of inserts

- 4 times shorter cutting time
- · Satisfactory surface finish of side faces with no need for further processing

# Application examples

### AI7075

### ■ Cutting condition

vc = 500 m/min, fz = 0.25 mm/t ap = 56 mm, ae = 1 mmz = 2



### ■ Tools

Insert LDET650550PPFR-MA

Grades H01

Holder BT50-PXL04090HR-2F (ØD = 40 mm)



# **Technical Information for Pro-V Mill**


### The Premium High-Speed Milling Tool for Aluminum

# Pro-V Mill new


- Enhanced productivity- Increased productivity due to high speed capability
- Improved surface finish- Excellent surface finish and perpendicularity with high-precision products
- Excellent clamping stability- Satisfactory clamping force of inserts by the use of the key shape

## Code system


### Cutter



### Shank



### Tooling System






### Cutter Features

- The combined clamping system of the key to key slot structure and simple screw-on type ensures strong clamping force
- Stable machining / prevention of insert breakage
- · Avoiding uplifting problems of insert due to axial acute-angle clamping of cutters
- Reduced vibrations and excellent surface finish



### Insert Features



# Features of chip breaker


In	sert	Cutting-edge	Uses	Features
MA		120	For non-ferrous metals	Ensuring satisfactory machining quality with the application of mirror-like cutting edges optimized for aluminum machining


# Recommended cutting condition

		Workpiece	Grade	vc (m/min)	Max. ap (mm)
			H01	1,300 (500 - 2,200)	
N	A l	Si $\leq$ 5% (Si Lower than 5%)	H05	1,000 (300 - 1,700)	47
N	Aluminum		PD1005	1,500 (500 - 3,000)	17
		Si ≤ 10% (Si Lower than 10%)	PD1010	1,200 (300 - 2,200)	

<sup>\*</sup> The recommended cutting conditions above are a general guideline. Their details may vary depending on the machining method of users and other conditions.

# Application area







# Pro-V Mill ramping & helical cutting technical data


### 1. Ramping

### 2. Blind hole helical cutting

### 3. Thru hole helical cutting







(mm)

	Ran	nping		Blind hole h	elical cutting		Thru hole helical cutting			
ØD	α°	Lmin	ØDHmin	dmax	ØDHmax	dmax	ØDHmin	dmax		
25	15.0	59	41	13.0	44	15.5	27	2.0		
32	10.0	99	55	11.0	58	12.5	41	4.5		
40	7.0	142.5	71	10.5	74	11.5	57	6.0		
50	5.0	200	91	10.0	94	10.5	77	6.5		
63	3.5	286	117	9.2	120	9.5	103	7.0		
80	2.6	385	151	9.0	154	9.5	137	7.3		
100	2.0	501	191	9.0	194	9.0	177	7.6		
125	1.5	668	241	8.5	244	8.5	227	7.5		

When ramping and helical milling, table feed, vf (mm/min) should be lower than 70% of the recommended cutting conditions.

- When helical milling, Max. pitch, DHmax should be lower than max. depth of cut, ap.
- When ramping, the depth of cut should be lower than max. depth of cut, ap.

• Lmin: Minimum inclination cutting length

 $\alpha^{\circ}\,$  : Max. rampig angle

ap : Depth of cut




Milling

<sup>•</sup> Lmin: ap/tan( $\alpha^{\circ}$ ) (mm)

# PAC(M)2000/4000





















• AR: 0° • RR: -3°

(mm)

D	Designation	<b>(a)</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg
PACM	2040HR	3	40	34	16	9	14	8.4	5.6	18	40	8.7	0.2
	2050HR	4	50	42	22	11	18	10.4	6.3	22	50	8.7	0.4
	2063HR	5	63	49	22	11	18	10.4	6.3	22	50	8.7	0.6
	2080HR	5	80	57	27	14	20	12.4	7.0	25	50	8.7	0.9
	2100HR	6	100	67	32	18	26	14.4	8.0	30	63	8.7	1.9
	4040HR	3	40	32	16	9	11.5	8.4	5.6	20	55	15	0.2
	4050HR	3	50	40	22	11	18	10.4	6.3	20	55	15	0.3
	4063HR	4	63	50	22	11	18	10.4	6.3	20	60	15	0.6
	4080HR	4	80	60	27	14	20	12.4	7.0	25	60	15	1.0
	4100HR	5	100	80	32	18	26	14.4	8.0	26	60	15	1.6
PAC	2080HR	5	80	57	25.4	14	20	9.5	6.0	25	50	8.7	0.9
	2100HR	6	100	67	31.75	-	44	12.7	8.0	37	63	8.7	1.9
	4080HR	4	80	60	25.4	14	20	9.5	6.0	25	60	15	1.0
	4100HR	5	100	80	31.75	-	44	12.7	8.0	37	60	15	1.6

# Available inserts

# VCKT-MA



			Cer	met						C	oate	d						Ur	icoat	ed	
Туре		Designation	CN30		NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	년 194	page
2000 type	VDKT	11T210N-MA																		•	E29
4000 type	VCKT	220530N-MA																		•	E29

# Available arbors


Des	signation	Ød	NC arbors
PAC	2040HR	16	BT□□-FMC16-□□
(PACM)	2050HR	22	BT□□-FMC22-□□
	2063HR	22	BT□□-FMC22-□□
	2080HR	25.4	BT□□-FMC25.4-□□
	2000HK	27	BT□□-FMC27-□□
	2100HR	31.75	BT□□-FMC31.75-□□
	2100AR	32	BT - FMC32-

Des	signation	Ød	NC arbors
PAC	4040HR	16	BT□□-FMC16-□□
(PACM)	4050HR	22	BT□□-FMC22-□□
	4063HR	22	BT□□-FMC22-□□
	4080HR	25.4	BT□□-FMC25.4-□□
	4000Hh	27	BT□□-FMC27-□□
	4100HR	31.75	BT□□-FMC31.75-□□
	4100NN	32	BT□□-FMC32-□□

Specification	Screw	Wrench	Arbor Bolt
Ø40~Ø100 (2000 type)	ETNA02506	TW07S	
Ø40~Ø100 (4000 type)	FTNC04509(Ø40)	TW20S	PHMA0834(Ø40)
940~9100 (4000 type)	FTNC04511 FTNC04511		FNWA0634(040)

# PAS2000/4000























(mm)

								(11111)
	Designation	©	ØD	Ød	Q	L	ар	kg
PAS	2012HR	1	12	16	25	85	8	0.1
	2016HR	2	16	16	25	90	8	0.11
	* 2016HR-R2.0	2	16	16	25	90	6	0.11
	2020HR	2	20	20	30	100	8	0.2
	* 2020HR-R2.0	2	20	20	30	100	6	0.2
	2025HR	3	25	25	35	115	8	0.36
	2032HR	4	32	32	40	125	8	0.66
	2042HR	5	42	32	42	130	8	0.84
PAS	4032HR	2	32	32	50	125	15	0.6
	4040HR	3	40	32	50	140	15	8.0
	4040HR-S40	3	40	40	60	150	15	1.2
	4040HR-S42	3	40	42	60	150	15	1.2

Holders marked with an asterisk (\*) are only for VDKT11T220N-MA.

### ♠ Available inserts

Available iliserts			
	VDKT-MA	VCKT-MA	

			Cer	met						C	oate	d						Ur	coat	ed	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H0.1	page
2000 tune	VDKT	11T210N-MA																		•	
2000 type		11T220N-MA																			E29
4000 type	VCKT	220530N-MA																		•	

# Parts

Milling


Specification			
	Screw	Wrench	
Ø40 Ø40 (0000 to as a)	ETNA02505*	TM070	
Ø12~Ø42 (2000 type)	ETNA02506	TW07S	
Ø32~Ø40 (4000 type)	FTNC04509	TW20S	





# **PAM2000**





















(mm)

	Designation	<b>©</b>	ØD	Ød	Ød <sub>1</sub>	Q	L	М	ар	kg
PAM	2012HR-M06	1	12	11.0	6.5	33	48	M06	8	0.02
	2016HR-M08	2	16	14.5	8.5	36	53	M08	8	0.04
	2020HR-M10	2	20	18.0	10.5	36	57	M10	8	0.06
	2025HR-M12	3	25	22.5	12.5	41	65	M12	8	0.1
	2032HR-M16	4	32	28.5	17.0	45	72	M16	8	0.18
	2042HR-M16	5	42	28.5	17.0	45	72	M16	8	0.27

# Available inserts

VDKT-MA



		Ce	rmet						(	oate	d						ıU	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
VDKT	11T210N-MA																		•	E29

# Available adaptors


	Designation	Available adaptors
PAM	2012HR-M06	MAT-M06
	2016HR-M08	MAT-M08
	2020HR-M10	MAT-M10
	2025HR-M12	MAT-M12
	2032HR-M16	MAT-M16
	2042HR-M16	MAT-M16

Designation: PAM2012HR-M06 Modular head threading measure size (M06)

П

Adaptor spec.: MAT-M06-030-S20S Adaptor threading measure (M06)


Specification		
	Screw	Wrench
Ø12~Ø42	ETNA02505*	TW07S
Ø12~Ø42	ETNA02506	10075





# **PAXC(M)5000**





















• AR: 8°~17.5° • RR: -9.5°~-5°

(ı	"	''

Des	signation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	Max rpm	ар	kg
PAXCM	5040HR-A,B	3	40	34	16	9	14	8.4	5.6	19	40	25,800	17	0.15
	5050HR-A,B	4	50	42	22	11	18	10.4	6.3	21	50	23,000	17	0.3
	5063HR-A,B	5 (4)	63	49	22	11	18	10.4	6.3	21	50	20,500	17	0.56
PAXC	5080HR-A,B	5	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	24 (23)	50	18,200	17	1.0
(PAXCM)	5100HR-A,B	6	100	67	31.75 (32)	18	26	12.7 (14.4)	8 (8)	32 (26)	63	16,300	17	2.3
	5125HR-A,B	7	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	14,600	17	3.2

<sup>•</sup> A type: Insert NoseR 0.4~3.2, B type: Insert NoseR 4.0~5.0

( )Metric size

# Available inserts







																100															
		Cermet				Coa	itec	k			l	Unc	coate	d				C	ermet				Co	oate	d				Und	coated	
	Designation	CN2500 CN30	NC5330 NCM535	NCM545	PC2510	PC3700	PC9530	PC9540	PC5300		PUIUIU	S130A	윤		page	D	esignation	CNIDEOO	CN30	NC5330 NCM535	NCM545	PC2505	PC3700	PC6510	PC9530	PC5300	PC5400	PD1010	ST30A	3 5 5 5 5 5 5 5 5 5 7 7 7 7 7 7 7 7 7 7	page
<b>XEKT</b>	19M504FR-MA									•			•	•		XEKT	19M504ER-W	IL													
	19M508FR-MA									•			•	•			19M508ER-W	IL													
	19M512FR-MA									•			•	•			19M512ER-N	IL													
	19M516FR-MA									(			•	•			19M516ER-N	IL													1
	19M518FR-MA														E04		19M518ER-N	IL													F04
	19M520FR-MA									•			•	•	E31		19M520ER-N	IL													E31
	19M530FR-MA									(			•	•			19M530ER-N	IL													
	19M532FR-MA									•			•	•			19M532ER-N	IL													1
	19M540FR-MA									•			•	•			19M540ER-N	IL													1
	19M550FR-MA									•			•	•			19M550ER-N	IL													


# Available arbors

	Designation	Ød	Available arbors
PAXCM	5040HR-A,B	16	BT□□-FMC16-□□
	5050HR-A,B	00	DTCC FMC00 CC
	5063HR-A,B	22	BT□□-FMC22-□□
PAXC	COCOLID A D	25.4	BT□□-FMA25.4-□□
PAXCM)	5080HR-A,B	27	BT□□-FMC27-□□
	5100HR-A,B	31.75	BT□□-FMA31.75-□□
	SIUURR-A,D	32	BT□□-FMC32-□□
	E10EUD A D	38.1	BT□□-FMA38.1-□□
	5125HR-A,B	40	BT□□-FMC40-□□

Specification		
	Screw	Wrench
Ø40~Ø125	PTKA0408	TW15S

# **PAXC(M)6000**



















AA • AR: 8°~17.5° • RR: -9.5°~-5°

														(mm)
Des	signation	<b>(</b>	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	Max rpm	ар	kg
PAXCM	6050HR-A,B	2	50	42	16	9	14	8.4	5.6	18	50	23,000	23	0.32
	6063HR-A,B	3	63	49	22	11	18	10.4	6.3	21	50	20,500	23	0.53
PAXC	6080HR-A,B	4	80	57	25.4 (27)	14	20	9.5 (12.4)	6 (7)	25 (23)	50	18,200	23	0.73
(PAXCM)	6100HR-A,B	5	100	67	31.75 (32)	18	26	12.7 (14.4)	8 (8)	32.5 (26)	63	16,300	23	1.7
	6125HR-A,B	6	125	87	38.1 (40)	22	32	15.9 (16.4)	10 (9)	35 (29)	63	14,600	23	3.06

<sup>•</sup> A type: Insert NoseR 0.4~3.2, B type: Insert NoseR 4.0~5.0

( )Metric size

### Available inserts



												_				-													
		Cermet			(	Coa	ited				U	Jnc	oate	ed				Cermet					ate					oated	
	Designation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC2505	PC3700	PC6510	PC9530 PC9540	PC5300	ST30A	G-10 G-10	윤	H05	page	С	esignation	CN2500 CN30	NC5330	NCM335	NCM535	PC2505	PC2510	PC6510	PC9530 PC9540	PC5300	ST30A	F F S F S	page
XEK													•			XEKT	250604ER-ML												
	250608FR-MA												•	•			250608ER-ML												
	250612FR-MA									П		Т	•	•			250612ER-ML												
	250616FR-MA																250616ER-ML												
	250620FR-MA												•	•	E31		250620ER-ML												E31
	250630FR-MA																250630ER-ML												
	250632FR-MA												•	•			250632ER-ML												
	250640FR-MA																250640ER-ML												
	250650FR-MA												•	•			250650ER-ML												

# Available arbors


	Designation	Ød	Available arbors
PAXCM	6050HR-A,B	16	BT□□-FMC16-□□
	6063HR-A,B	22	BT□□-FMC22-□□
PAXC	COOOLD A D	25.4	BT□□-FMA25.4-□□
(PAXCM)	6080HR-A,B	27	BT□□-FMC27-□□
	6100HR-A,B	31.75	BT□□-FMA31.75-□□
	0100NR-A,D	32	BT□□-FMC32-□□
	C40ELID A D	38.1	BT□□-FMA38.1-□□
	6125HR-A,B	40	BT□□-FMC40-□□

Specification		
	Screw	Wrench
Ø50~Ø125	FTGA0513-P	TW20-100



# **PAXS5000**



















• AR: 5°~10° • RR: -14°~-5°

(mm)

									(11111)
	Designation	©	ØD	Ød	Q	L	Max <b>rpm</b>	ар	\(\rightarrow\) kg
PAXS	5020HR-A,B	1	20	20	60	130	15,000	17	0.24
	5025HR-A,B	2	25	25	60	140	32,600	17	0.4
	5025HR-A,B-L200	2	25	25	60	200	32,600	17	0.63
	5032HR-A,B	2	32	32	70	150	28,800	17	0.74
	5032HR-A,B-L220	2	32	32	70	220	28,800	17	1.2
	5040HR-A,B-S32	3	40	32	70	160	25,800	17	1.0
	5040HR-A,B-L220	3	40	32	70	220	25,800	17	1.4
	5040HR-A,B-S40	3	40	40	70	160	25,800	17	1.3
	5040HR-A,B-S42	3	40	42	70	160	25,800	17	1.4

<sup>•</sup> A type: Insert NoseR 0.4~3.2, B type: Insert NoseR 4.0~5.0


# Available inserts

									XEKT-	-MA	4	XE	KT-ML											
								4		-		1	new											
		Cermet		Co	ated			Uı	ncoate	d				Cerme			С	oate	d			Und	coated	
D	esignation	CN2500 CN30	NC5330 NCM535 NCM545 NCM545 PC2505	PC2510 PC3700	PC6510 PC9530	PC9540 PC5300	PD2000	ST30A	등 단 단 단 단 단		page	D	esignation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC2510	PC6510	PC9540	PC5400	PD2000 PD1010	ST30A	동동	page
XEKT	19M504FR-MA						• •		•	•		XEKT	19M504ER-ML											
	19M508FR-MA						•		•				19M508ER-ML											
	19M512FR-MA						•		•				19M512ER-ML											
	19M516FR-MA						•		•				19M516ER-ML											
	19M518FR-MA										E31		19M518ER-ML											E31
	19M520FR-MA						•		•		ESI		19M520ER-ML											ESI
	19M530FR-MA						•		•				19M530ER-ML											
	19M532FR-MA						• •		•				19M532ER-ML											
	19M540FR-MA						• •		•				19M540ER-ML											
	19M550FR-MA												10M550ER-MI											1

Specification		
pecification	Screw	Wrench
Ø20	PTKA0407	
Ø25~Ø40	PTKA0408	TW15S

# **PAXS6000**





















• AR: 5°~10° • RR: -14°~-5°

œ \	
42	

						. •			(mm)
	Designation	<b>©</b>	ØD	Ød	Q	L	Max rpm	ар	(kg)
PAXS	6025HR-A,B	1	25	25	60	140	32,600	23	0.42
	6025HR-A,B-L200	1	25	25	60	200	32,600	23	0.63
	6032HR-A,B	1	32	32	70	150	28,800	23	0.72
	6032HR-A,B-L220	1	32	32	70	220	28,800	23	1.14
	6040HR-A,B-S32	2	40	32	70	160	25,800	23	0.88
	6040HR-A,B-L220	2	40	32	70	220	25,800	23	1.23
	6040HR-A,B-S40	2	40	40	70	160	25,800	23	1.2
	6040HR-A,B-S42	2	40	42	70	160	25,800	23	1.3

<sup>•</sup> A type: Insert NoseR 0.4~3.2, B type: Insert NoseR 4.0~5.0

# Available inserts


		XEKT-MA	XEKT-MI	-
				new
Comment	Oneted	Unanahad		

	Cermet Coated		U	Jnc	oate	d				Cerme	t			С	oate	ed				Unco	oated									
D	esignation	CN2500 CN30	NC5330 NCM325	NCM335 NCM535	NCM545	PC2505	PC3700	PC6510	PC9540	PC5300	ST30A	610	6 등	일 일	page			CN2500 CN30	NC5330	NCM325 NCM335	NCM535	NCM545	PC2510	PC3700	PC9530	PC9540	PC5400	ST30A G10	155 155	page
<b>XEKT</b>	250604FR-MA												•	•		XEKT 250604ER-ML														
	250608FR-MA												•	•			250608ER-ML													
	250612FR-MA												•	•			250612ER-ML													
	250616FR-MA																250616ER-ML													
	250620FR-MA												•	•	E31		250620ER-ML													E31
	250630FR-MA																250630ER-ML													
	250632FR-MA												•	•			250632ER-ML													
	250640FR-MA																250640ER-ML													
	250650FR-MA												•	•			250650ER-ML													

Specification		P
	Screw	Wrench
Ø25~Ø32	FTGA0510-P	TW20-100
Ø40	FTGA0513-P	17920-100

# **PAXM5000**























• RR: -7°~-5°

(ı	ı	Ш	1	IJ	

	Designation	<b>(</b>	ØD	Ød	Ød <sub>1</sub>	Q	L	M	ар	kg
PAXM	5025HR-A,B-M12	2	25	23	12.5	55	79	M12	17	0.12
	5032HR-A,B-M16	2	32	29	17.0	55	82	M16	17	0.2
	5040HR-A,B-M16	3	40	29	17.0	55	82	M16	17	0.4

<sup>•</sup> A type: Insert NoseR 0.4~3.2, B type: Insert NoseR 4.0~5.0

# Available inserts



Cernet Coated Uncoated Cern																															
		Cermet			C	oat	ted				U	nco	ated			Cermet				Co	ate	d			Uı	ncoat	ed				
D	esignation	CN2500 CN30	NC5330 NCM535	NCM545 PC2505	PC2510	PC6510	PC9530	PC9540 PC5300	PC5400	PD2000	ST30A	G10	돋	pa	ige	D	esigna	ation	CN2500 CN30	NC5330	NCM545	PC2505	PC3700	PC6510	PC9540	PC5300	PD2000	ST30A	55 55 54	H22	page
XEKT	19M504FR-MA						П			•			•			XEKT	19M5	04ER-ML								П					
	19M508FR-MA									• •			•				19M5	08ER-ML													
	19M512FR-MA									• •			• •				19M5	12ER-ML													
	19M516FR-MA									•			• •				19M5	16ER-ML													
	19M518FR-MA						П							Ī _,			19M5	18ER-ML								П					F04
	19M520FR-MA						П			• •			• •	E:	31		19M5	20ER-ML													E31
	19M530FR-MA									•			• •				19M5	30ER-ML													
	19M532FR-MA									• •			•				19M5	32ER-ML													
	19M540FR-MA									• •			• •				19M5	40ER-ML													
	19M550FR-MA									• •			• •				19M5	50ER-ML													

# Available adaptor

	Designation	Available adaptor
PAXM	5025HR-A,B-M12	MAT-M12
	5032HR-A,B-M16	MAT M4C
	5040HR-A.B-M16	MAT-M16


Designation: PAXM5025HR-M12 Modular head threading measure size (M12)

Adaptor spec.: MAT-M12-030-S25S Adaptor threading measure (M12)

Specification			
	Screw	Wrench	
Ø25~Ø40	PTKA0408	TW15S	

# HSK63A/100A PAX5000





















(mm)

	Designation	<b>©</b>	ØD	ØD1	Q 1	Q 2	L	ар	kg
HSK63A	PAX5032HR-A, B	2	32	53	58	137	163	17	1.14
HSK100A	PAXCM5080HR-A, B	5	80	-	-	66	95	17	4
	PAXCM5100HR-A, B	6	100	-	-	66	95	17	4.6

<sup>•</sup> A type: Insert NoseR 0.4~3.2, B type: Insert NoseR 4.0~5.0

# Available inserts



	Cermet			(	Coa	ted				U	nco	oateo	d				Cermet				Co	ate	t			Unc	oated	
Designation	CN2500 CN30	NC5330 NCM535	NCM545	PC2510	PC3700	PC9530	PC9540	PC5400	PD2000	ST30A	G10			age	D	esignation	CN2500 CN30	NC5330 NCM535	NCM545	PC2505	PC3700	PC6510	PC9540	PC5300 PC5400	PD2000	ST30A G10	된 당 당	page
XEKT 19M504FR-MA									•			•			XEKT	19M504ER-ML												
19M508FR-MA									•			•				19M508ER-ML												
19M512FR-MA									•			•				19M512ER-ML												
19M516FR-MA									•			•				19M516ER-ML												1
19M518FR-MA													١.	E31		19M518ER-ML												F04
19M520FR-MA									• •			•		E31		19M520ER-ML												E31
19M530FR-MA									•			•				19M530ER-ML												1
19M532FR-MA									•			•				19M532ER-ML												1
19M540FR-MA									•			•				19M540ER-ML												1
19M550FR-MA									• •			•				19M550ER-ML												1


Screw Wrench

<sup>•</sup> For the maximum rake angle and the rpm limit, please refer to technical information on pp. E377~E378.

# Pro-L Mill

# **PALCM**















• AR: 16° • RR: -8°

(mm)

Designation	0	ØD	ØD2	Ød	Ød1	Ød2	а	b	E	F	ар	kg
PALCM 063HR	4	63	50	22	11	21	10	6.3	20	70	34	0.57

# Available inserts

LXET-MA LXET-ML

		Cer	met													Ur	icoat	ed		
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LXET	340504PEFR-63-MA																			
	3405PEFR-63-MA																		•	
	340512PEFR-63-MA																			
	340516PEFR-63-MA																			E13
	340504PEER-63-ML																			EIS
	3405PEER-63-ML																			
	340512PEER-63-ML																			
	340516PEER-63-ML																			

# Available arbors


	Designation	Ød	Available arbors
PALCM	063HR	22	BT□□-FMC22-□□

Specification		San Constitution of the Co	
	Screw	Wrench	
Ø63	FTGA0511-P	TW20-100	



## PALS (Single-edge)















90°

• AR: 12°~16° • RR: -5°~-9°

(mm)

ı	Designation	©	ØD	Ød	Q	L	ар	kg
PALS	032HR-2S20	2	32	20	50	140	25	0.36
	032HR-2S25	2	32	25	50	140	25	0.48
	032HR-2S32	2	32	32	50	140	25	0.71
	040HR-2S32	2	40	32	50	140	25	0.85
	040HR-2S40	2	40	40	50	140	25	1.16
	040HR-2S42	2	40	42	50	140	25	1.26
	040HR-3S32	3	40	32	50	140	25	0.80
	040HR-3S40	3	40	40	50	140	25	1.10
	040HR-3S42	3	40	42	50	140	25	1.20

### Available inserts

LXET-MA

LXET-ML




			Cer	met						C	Coate	d						Un	coat	ed	
Туре	ı	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
	LXET	250404PEFR-32-MA																			
		2504PEFR-32-MA																		•	
		250412PEFR-32-MA																			
Ø32		250416PEFR-32-MA																			
<i>1</i> 032		250404PEER-32-ML																			
		2504PEER-32-ML																			
		250412PEER-32-ML																			
		250416PEER-32-ML																			E13
	LXET	250404PEFR-40-MA																			E13
		2504PEFR-40-MA																			
		250412PEFR-40-MA																			
Ø40		250416PEFR-40-MA																			
940		250404PEER-40-ML																			
		2504PEER-40-ML																			
		250412PEER-40-ML																			
		250416PEER-40-ML																			

Specification			
	Screw	Wrench	
Ø32	FTKA0408	TW15S	
Ø40	FTKA0410	TW15S	

## PALS (Single-edge)















• AR: 12°~16° • RR: -5°~-9°

(mm)

								()
	Designation	©	ØD	Ød	Q	L	ар	
PALS	050HR-3S32	3	50	32	70	160	34	1.10
	050HR-3S40	3	50	40	70	160	34	1.40
	050HR-3S42	3	50	42	70	160	34	1.50
	063HR-4S32	4	63	32	70	160	34	1.60
	063HR-4S40	4	63	40	70	160	34	1.92
	063HR-4S42	4	63	42	70	160	34	2.00

### Available inserts

LXET-MA

LXET-ML






			Cer	met						C	Coate	d						Ur	icoat	ed	
Туре		Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	H01	page
	LXET	340504PEFR-50-MA																		•	
		3405PEFR-50-MA																		•	
		340512PEFR-50-MA																			
Ø50		340516PEFR-50-MA																			
Ø50		340504PEER-50-ML																			
		3405PEER-50-ML														•					
		340512PEER-50-ML																			
		340516PEER-50-ML																			E13
	LXET	340504PEFR-63-MA																			E13
		3405PEFR-63-MA																		•	
		340512PEFR-63-MA																			
Ø63		340516PEFR-63-MA																			
<i>1</i> 003		340504PEER-63-ML																			
		3405PEER-63-ML																			
		340512PEER-63-ML																			
		340516PEER-63-ML																			

Specification	Screw	Wrench	
Ø50	FTGA0510-P	TW20-100	
Ø63	FTGA0511-P	TW20-100	

## PALS (Multi-edge)















90° • RR: -8°

(mm)


	Designation	©	Ød	Ød <sub>1</sub>	Q	L	ар	kg
PALS	063HM-4S32	12	63	32	130	220	96	1.60
	063HM-4S40	12	63	40	130	220	96	1.92
	063HM-4S42	12	63	42	130	220	96	2.00

### Available inserts



		Cer	met							oate							Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LXET	340504PEFR-63-MA																			
	3405PEFR-63-MA																		•	
	340512PEFR-63-MA																			
	340516PEFR-63-MA																			E13
	340504PEER-63-ML																			EIS
	3405PEER-63-ML																			
	340512PEER-63-ML																			
	340516PEER-63-ML																			

Specification	<b>O</b> MMM	Senor)
	Screw	Wrench
Ø63	FTGA0511-P	TW20-100































• AR: 5°~17.5° • RR: -14°~-5°

(mm)

	Designation	0	ØD	ØD1	ØD2	l1	l2	L	ар	kg	Fig.
HSK63A	PXL04090HR-2F	2	40	48	63	85	90	116	57	1.13	1
HSK100A	PXL04090HR-3F	3	40	70	100	90	100	129	57	2.74	1
	PXL08090HR-5F	5	80	77	100	-	90	119	57	4.29	1
BT50	PXL04090HR-2F	2	40	48	100	85	90	128	57	4.13	2

### Available inserts

LDET-MA




		Cer	met						C	oate	d						Ur	ncoat	ed	
	Designation	CN2500	CN30	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	ST30A	G10	된	page
LDET	650540PPFR-MA																			F10
	650550PPFR-MA																			E10

Specification		South of the second
	Screw	Wrench
Ø40~80	FTGA0511-P	TW20-100

























(mm)

	Designation	0	ØD	ØD <sub>2</sub>	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	Ød3	а	b	E	F	ар	∑ kg \
PAVCM	040R-16-3-XD19-A,B	3	40	34	16	9	13.5	-	8.4	5.6	16	45	17	0.17
	050R-22-4-XD19-A,B	4	50	42	22	11	18	-	10.4	6.3	21	50	17	0.35
	063R-22-5-XD19-A,B	5	63	42	22	11	18	-	10.4	6.3	21	50	17	0.53
	080R-27-5-XD19-A,B	5	80	60	27	14	20	-	12.4	7.0	24	50	17	0.88
	100R-32-6-XD19-A,B	6	100	70	32	18	26	42	14.4	8.0	25	63	17	1.72
	125R-40-7-XD19-A,B	7	125	90	40	22	32	52	16.4	9.0	29	63	17	2.82

<sup>•</sup> Type A uses Insert Nose R 0.4~3.2, and Type B uses Nose R 4.0~5.0

### Available inserts

### XDET-MA



		Cermet	Coated		Uncoated				Cermet	Coated	Uncoated	
	Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC3700 PC6510 PC9530	PC5400 PD1005 PD1010	된 당 당	page		Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC3700 PC6510 PC9530 PC9540 PC5300 PC5300 PC5300	5	page
XDET	190504PEFR-MA				• •		XDET	190524PEFR-MA			• •	
	190508PEFR-MA				• •			190530PEFR-MA			• •	
	190512PEFR-MA				• •	E31		190532PEFR-MA			• •	E31
	190516PEFR-MA				• •			190540PEFR-MA			• •	1
	190520PEFR-MA				• •	1		190550PEFR-MA			• •	1

### Available arbors

	Designation	Available arbors
PAVCM	040R-16-3-XD19	BT□□-FMC16-□□
	050R-22-4-XD19	BT□□-FMC22-□□
	063R-22-5-XD19	BT□□-FMC22-□□
	080R-27-5-XD19	BT□□-FMC27-□□
	100R-32-6-XD19	BT□□-FMC32-□□
	125R-40-7-XD19	BT□□-FMC40-□□


Specification	
Screw	Wrench
Ø40~Ø125 PTKA0408-A	TW15S

<sup>•</sup> When using a spindle at high speed, please check the balance of tool and use it after replacing with the new screw.

## Pro-V Mill

## PAVS-XD19 @





















(mm)

	Designation	©	ØD	Ød	Q	L	ар	
PAVS	025R-2C25-140-XD19-A,B	2	25	25	60	140	17	0.40
	032R-2C32-150-XD19-A,B	2	32	32	70	150	17	0.76
	032R-2C32-200-XD19-A,B	2	32	32	70	200	17	1.06
	040R-3C40-200-XD19-A,B	3	40	40	70	200	17	1.71

- Type A uses Insert Nose R 0.4~3.2, and Type B uses Nose R 4.0~5.0
- When using a spindle at high speed, please check the balance of tool and use it after replacing with the new screw.

### Available inserts

### XDET-MA



		Cermet	Coated	Uncoated				Cermet	Coated	Uncoated	
	Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC3700 PC5510 PC9530 PC9540 PC5400 PC5400 PC5400 PC5400	192	page		Designation	CN2500 CN30	NC5330 NCM325 NCM335 NCM535 NCM545 PC3700 PC6510 PC9530 PC9540 PC5300 PC5300	H55 H55	page
XDET	190504PEFR-MA			• •		XDET	190524PEFR-MA			• •	
	190508PEFR-MA			• •			190530PEFR-MA			• •	
	190512PEFR-MA			• •	E31		190532PEFR-MA			• •	E31
	190516PEFR-MA			• •			190540PEFR-MA			• •	
	190520PEFR-MA			• •			190550PEFR-MA			• •	

Specification		
	Screw	Wrench
Ø25~Ø40	PTKA0408-A	TW15S

## MAT (Steel shank type)







Fig. 1



		I						(11111)
	Designation	ØD	Ød	Ød <sub>1</sub>	Q	L	M	Fig.
MAT-	M06-020-S10S	9.5	10	6.5	20	70	M06	1
	M6B-020-S12S	11.0	12	6.5	20	76	M06	1
	M6B-040-S12S	11.0	12	6.5	40	96	M06	1
	M08-020-S16S	14.5	16	8.5	20	80	M08	1
	M10-030-S20S	18.0	20	10.5	30	100	M10	1
	M12-030-S25S	22.5	25	12.5	29	110	M12	1
	M16-035-S32S	28.5	32	17.0	35	125	M16	1
	M06-040-S12T	9.5	12	6.5	40	96	M06	2
	M06-065-S16T	9.5	16	6.5	65	125	M06	2
	M6B-065-S16T	11.0	16	6.5	65	125	M06	2
	M6B-080-S16T	11.0	16	6.5	80	140	M06	2
	M08-040-S16T	14.5	16	8.5	40	100	M08	2
	M08-065-S16T	14.5	16	8.5	65	125	M08	2
	M08-080-S20T	14.5	20	8.5	80	150	M08	2
	M08-110-S25T	14.5	25	8.5	110	190	M08	2
	M10-050-S20T	18.0	20	10.5	50	120	M10	2
	M10-070-S20T	18.0	20	10.5	70	140	M10	2
	M10-090-S25T	18.0	25	10.5	90	170	M10	2
	M10-110-S25T	18.0	25	10.5	110	190	M10	2
	M10-130-S32T	18.0	32	10.5	130	220	M10	2
	M12-050-S25T	22.5	25	12.5	50	130	M12	2
	M12-070-S25T	22.5	25	12.5	70	150	M12	2
	M12-090-S25T	22.5	25	12.5	90	170	M12	2
	M12-110-S32T	22.5	32	12.5	110	200	M12	2
	M12-175-S40T	22.5	40	12.5	175	300	M12	2
	M16-055-S32T	28.5	32	17.0	55	145	M16	2
	M16-080-S32T	28.5	32	17.0	80	170	M16	2
	M16-120-S32T	28.5	32	17.0	120	210	M16	2
	M16-175-S40T	28.5	40	17.0	175	300	M16	2

<sup>•</sup> S: straight neck adaptor • T: taper neck adaptor





<sup>3</sup> Applicable modular E45, E46 (FMRM, LBE, PAM, AMM, RM4PM, HFMM, RM4ZM, HRMM, PAXM)



## MAT-C (Carbide shank type)








								(mm
	Designation	ØD	Ød	Ød1	Q	L	M	Fig.
MAT-	M06-030-S10S-C-80	9.5	10	6.5	30	80	M06	1
	M06-050-S10S-C-100	9.5	10	6.5	50	100	M06	1
	M06-080-S10S-C-130	9.5	10	6.5	80	130	M06	1
	M6B-030-S12S-C-80	11.0	12	6.5	30	80	M06	1
	M6B-050-S12S-C-100	11.0	12	6.5	50	100	M06	1
	M6B-080-S12S-C-130	11.0	12	6.5	80	130	M06	1
	M08-080-S16S-C	14.5	16	8.5	80	150	M08	1
	M08-110-S16S-C	14.5	16	8.5	110	180	M08	1
	M08-150-S16S-C	14.5	16	8.5	150	250	M08	1
	M08-010-S16S-C-150	14.5	16	8.5	10	150	M08	2
	M08-010-S16S-C-180	14.5	16	8.5	10	180	M08	2
	M08-010-S16S-C-250	14.5	16	8.5	10	250	M08	2
	M10-090-S20S-C	18.0	20	10.5	90	170	M10	1
	M10-110-S20S-C	18.0	20	10.5	110	200	M10	1
	M10-175-S20S-C	18.0	20	10.5	175	300	M10	1
	M10-010-S20S-C-170	18.0	20	10.5	10	170	M10	2
	M10-010-S20S-C-200	18.0	20	10.5	10	200	M10	2
	M10-010-S20S-C-300	18.0	20	10.5	10	300	M10	2
	M12-090-S25S-C	22.5	25	12.5	90	170	M12	1
	M12-110-S25S-C	22.5	25	12.5	110	200	M12	1
	M12-175-S25S-C	22.5	25	12.5	175	300	M12	1
	M12-015-S25S-C-170	22.5	25	12.5	15	170	M12	2
	M12-015-S25S-C-200	22.5	25	12.5	15	200	M12	2
	M12-015-S25S-C-300	22.5	25	12.5	15	300	M12	2
	M16-090-S32S-C	28.5	32	17.0	90	180	M16	1
	M16-120-S32S-C	28.5	32	17.0	120	210	M16	1
	M16-175-S32S-C	28.5	32	17.0	175	300	M16	1
	M16-020-S32S-C-180	28.5	32	17.0	20	180	M16	2
	M16-020-S32S-C-210	28.5	32	17.0	20	210	M16	2
	M16-020-S32S-C-300	28.5	32	17.0	20	300	M16	2



## BT30/BT40/BT50






_										
L	Designation	ØD	ØD1	ØD2	ØD3	Ød1	Q1	Q2	L	М
BT30-	MAT-M06-053	11.0	11.7	13.0	30	6.5	5	21	53	M06*1.0
	MAT-M08-057	14.5	15.7	17.5	35	8.5	7	25	57	M08*1.25
	MAT-M10-062	18.0	19.7	24.0	38	10.5	7	30	62	M10*1.5
	MAT-M12-067	23.0	24.7	27.5	41	12.5	10	35	67	M12*1.75
	MAT-M16-067	29.0	31.7	33.5	41	17.0	10	35	67	M16*2.0
BT40-	MAT-M06-062	11.0	11.7	14.0	40	6.5	5	25	62	M06*1.0
	MAT-M06-077	11.0	11.7	14.0	40	6.5	5	40	77	M06*1.0
	MAT-M06-092	11.0	11.7	14.0	40	6.5	5	55	92	M06*1.0
	MAT-M08-067	14.5	15.7	19.0	44	8.5	7	30	67	M08*1.25
	MAT-M08-082	14.5	15.7	19.0	44	8.5	7	45	82	M08*1.25
	MAT-M08-097	14.5	15.7	19.0	44	8.5	7	60	97	M08*1.25
	MAT-M10-072	18.0	19.7	23.0	50	10.5	10	35	72	M10*1.5
	MAT-M10-087	18.0	19.7	23.0	50	10.5	10	50	87	M10*1.5
	MAT-M10-102	18.0	19.7	23.0	50	10.5	10	65	102	M10*1.5
	MAT-M12-077	23.0	24.7	30.0	55	12.5	10	40	77	M12*1.75
	MAT-M12-092	23.0	24.7	30.0	55	12.5	13	55	92	M12*1.75
	MAT-M12-107	23.0	24.7	30.0	55	12.5	13	70	107	M12*1.75
	MAT-M16-077	29.0	31.7	37.0	55	17.0	13	40	77	M16*2.0
	MAT-M16-092	29.0	31.7	37.0	55	17.0	13	55	92	M16*2.0
	MAT-M16-107	29.0	31.7	37.0	55	17.0	13	70	107	M16*2.0
BT50-	MAT-M06-083	11.0	11.7	15.0	40	6.5	5	35	83	M06*1.0
	MAT-M06-098	11.0	11.7	15.0	40	6.5	5	50	98	M06*1.0
	MAT-M06-113	11.0	11.7	15.0	40	6.5	5	65	113	M06*1.0
	MAT-M08-088	14.5	15.7	20.0	45	8.5	7	40	88	M08*1.25
	MAT-M08-103	14.5	15.7	20.0	45	8.5	7	55	103	M08*1.25
	MAT-M08-118	14.5	15.7	20.0	45	8.5	7	70	118	M08*1.25
	MAT-M10-093	18.0	19.7	25.0	55	10.5	10	45	93	M10*1.5
	MAT-M10-113	18.0	19.7	25.0	55	10.5	10	65	113	M10*1.5
	MAT-M10-128	18.0	19.7	25.0	55	10.5	10	80	128	M10*1.5
	MAT-M12-103	23.0	24.7	33.0	65	12.5	10	55	103	M12*1.75
	MAT-M12-118	23.0	24.7	33.0	65	12.5	13	70	118	M12*1.75
	MAT-M12-133	23.0	24.7	33.0	65	12.5	13	85	133	M12*1.75
	MAT-M16-103	29.0	31.7	41.0	85	17.0	13	55	103	M16*2.0
	MAT-M16-118	29.0	31.7	41.0	85	17.0	13	70	118	M16*2.0
	MAT-M16-133	29.0	31.7	41.0	85	17.0	13	85	133	M16*2.0

<sup>◆</sup> Applicable modular E45, E46

## HSK63A/HSK100A






(mm)


										(111111)
Des	signation	ØD	ØD1	ØD2	Ø <b>D</b> 3	Ød1	Q1	<b>Q2</b>	L	М
HSK63A-	MAT-M06-061	11.0	11.7	27.0	40	6.5	5	25	61	M06*1.0
	MAT-M06-076	11.0	11.7	27.0	40	6.5	5	40	76	M06*1.0
	MAT-M06-091	11.0	11.7	27.0	40	6.5	5	55	91	M06*1.0
	MAT-M08-066	14.5	15.7	30.5	44	8.5	7	30	66	M08*1.25
	MAT-M08-081	14.5	15.7	30.5	44	8.5	7	45	81	M08*1.25
	MAT-M08-096	14.5	15.7	30.5	44	8.5	7	60	96	M08*1.25
	MAT-M10-071	18.0	19.7	34.0	50	10.5	10	35	71	M10*1.5
	MAT-M10-086	18.0	19.7	34.0	50	10.5	10	50	86	M10*1.5
	MAT-M10-101	18.0	19.7	34.0	50	10.5	10	65	101	M10*1.5
	MAT-M12-076	23.0	24.7	36.5	55	12.5	10	40	76	M12*1.75
	MAT-M12-091	23.0	24.7	36.5	55	12.5	13	55	91	M12*1.75
	MAT-M12-106	23.0	24.7	36.5	55	12.5	13	70	106	M12*1.75
	MAT-M16-076	29.0	31.7	38.5	55	17.0	13	40	76	M16*2.0
	MAT-M16-091	29.0	31.7	38.5	55	17.0	13	55	91	M16*2.0
	MAT-M16-106	29.0	31.7	38.5	55	17.0	13	70	106	M16*2.0
HSK100A-	MAT-M06-074	11.0	11.7	15.0	40	6.5	5	35	74	M06*1.0
	MAT-M06-089	11.0	11.7	15.0	40	6.5	5	50	89	M06*1.0
	MAT-M06-104	11.0	11.7	15.0	40	6.5	5	65	104	M06*1.0
	MAT-M08-079	14.5	15.7	20.0	45	8.5	7	40	79	M08*1.25
	MAT-M08-094	14.5	15.7	20.0	45	8.5	7	55	94	M08*1.25
	MAT-M08-109	14.5	15.7	20.0	45	8.5	7	70	109	M08*1.25
	MAT-M10-084	18.0	19.7	25.0	55	10.5	10	45	84	M10*1.5
	MAT-M10-104	18.0	19.7	25.0	55	10.5	10	65	104	M10*1.5
	MAT-M10-119	18.0	19.7	25.0	55	10.5	10	80	119	M10*1.5
	MAT-M12-094	23.0	24.7	33.0	65	12.5	10	55	94	M12*1.75
	MAT-M12-109	23.0	24.7	33.0	65	12.5	13	70	109	M12*1.75
	MAT-M12-124	23.0	24.7	33.0	65	12.5	13	85	124	M12*1.75
	MAT-M16-094	29.0	31.7	41.0	85	17.0	13	55	94	M16*2.0
	MAT-M16-109	29.0	31.7	41.0	85	17.0	13	70	109	M16*2.0
	MAT-M16-124	29.0	31.7	41.0	85	17.0	13	85	124	M16*2.0

Applicable modular E45, E46

### Adjusting side cutter




### Tangential type (High rigidity)



- · Medium/Roughing
- Excellent performance at medium to roughing range (14~30 mm) table operation due to the strong rigidity of the cutter
- Good performance in heavy interruption and deep depth of cut application

### Radial type (Low cutting load)




- · Medium/Finishing
- Suitable for small width cutting operation (12~24 mm)
- 3 dimensional chip breaker provides smooth cutting operation
- Several chip breakers as per applications are available (MF, MM, FA)
- · Economical insert using 4 cutting-edges per insert

### Insert features

- Precise adjustable side cutter can control the width of the cutter by 5 µm unit
- Since the width of the cutter is adjustable up to ±1.5 mm, single cutter can cover various cutting width
- · Specially designed clamping system of the locator provides excellent rigidity by using elastic deformation of the locator
- Tangential type clamping system of insert provides enough strength can withstand large width cutting operations
- · 3-dimensional chip breaker of insert provides smooth cutting with low cutting load at medium to finishing range

### Operating manual



### · How to assemble the adjusting side cutter

- 1. Clamp wedge slightly on locator-wedge pocket by using wedge screw
- 2. Put (a) locator on (b) locator-wedge pocket along with the (b) key-way
- 3. Tighten the 6 taper screw little bit to set proper position of locator
- 4. Tighten the ② wedge screw tightly by using 70~80N.m torque
- 5. After, put the 4 insert on insert pocket of 9 locator, clamp it with 4 insert screw by using 40~50N.m torque

### · How to adjust Run-out & cutting width

- 1. Settle the adjusting side cutter after cleaning to the jig for measurement
- 2. Un-screw the **②** Wedge screw first, then tighten **①** wedge slightly again by using 8N.m torque
- 3. Adjusting the height of cutting-edge by using a dial gauge to set the width of the cutter
- 4. Tighten the ② wedge screw tightly by using 70~80N.m torque
- 5. To finish the setting, tighten the 6 taper screw for strong clamp



## **Tangential type**

### Cutting width per insert & type of cutter







Dool		Coa	ated	Cutting width for	Cutting width for			
Desi	gnation	NCM535	PC6510	half side cutter (ap)	full side cutter (ap)	L	d	t
CNHQ1005	- C0.5			9.0	) 14~18			
	- R0.5			9.0	14~10	10	10	5.4
	- C1.0			8.5	14~17	10		5.4
	- R1.0			0.5	14~17			
CNHQ1305	- C0.5			12	18~21/21~24			
	- R0.5			12	10/421/21/424			
	- C1.0			11.5	18~21/21~23	12.7	10	5.4
	- R1.0			11.5	10~21/21~25	12.7	10	5.4
	- C1.5			11	18~21/21~22			
	- R1.5			11	10~21/21~22			
CNHQ1606	- C0.5			15	24~27/27~30			
	- R0.5			13	24~21121~00			
	- C1.0			14.5	24~27/27~29			
	- R1.0			14.5	24~21121~29	16	12	6.4
	- C1.5			14	24~27/27~28	10	12	6.4
	- R1.5			14	24~21121~20			
	- C2.0			13.5	24~27			
	- R2.0			13.5	24~21			

<sup>→</sup> Applicable cutter E407, E408 → Available arbors and bolt E426~E428

### Recommended cutting condition

ISO	Grades	vc (m/min)	fz (mm/t)
D	NCM535	190~310	0.10~0.30
P	PC3700	160~270	0.10~0.30
NA.	PC5300	90~150	0.10~0.30
M	NCM335	180~290	0.10~0.30
K	PC6510	140~230	0.10~0.30

## Radial type

### Cutting width per insert & type of cutter











							С	oate	ed						Unc	oated	Cutting width for	Cutting width for		
D	esignation	NC5330	NCM325	NCM335	NCM535	NCM545	PC2505	PC2510	PC3700	PC6510	PC9530	PC9540	PC5300	PC5400	H01	H05	half side cutter (ap)	full side cutter (ap)	d	t
SDXT	09M405R-MA														•	•				
	09M405L-MA																			
	09M405R-MF																8	12~14	9.525	4
	09M405L-MF																0	14~16	9.525	4
	09M405R-MM		•							•	•		•	•						
	09M405L-MM									•										
	130508R-MA														•	•				
	130508L-MA																	16~18		
	130508R-MF		•							•	•		•	•			10.5	18~20	13.5	5.56
	130508L-MF																10.5	20~22	13.3	5.50
	130508R-MM		•							•	•		•	•				22~24		
	130508L-MM																			


### Recommended cutting condition


ISO	Grades	vc (m/min)	fz (mm/t)
	NCM325	190~310	0.08~0.30
Р	NCM335	180~290	0.08~0.25
	PC3700	160~270	0.10~0.25
М	PC9530	90~150	0.10.005
IVI	PC5300	90~150	0.10~0.25
V	PC8110	140~230	0.10~0.25
K	PC6510	140~230	0.10~0.25

<sup>→</sup> Applicable cutter E409, E410 → Available arbors and bolt E426~E428

<sup>:</sup> Stock item

## Tangential type (Full side cutter)





• TAFCP(M) • TAFCB(M)

																			(mm)
Deci	gnation	Ød	F	ØD2	а	b	T-MAX	Dec	ignation	Ød	E	ØD2	а	b	Е	T-MAX	Di	mensio	ns
Desi	griation	να		XID2	a	D	I-IVIAA	Des	ignation	, Su		XID2	a			I-IVIAA	ØD	W	No. of tooth
<b>TAFCP</b>	1001418	31.75 (32)	14	48	7.92 (8)	35.2	24	TAFCB	1001418R/L	31.75 (32)	50	54	12.7 (14	.4) 8	28	21	100	14-18	6
(M)	1251418	38.1 (40)	14	56	9.52 (10)	42.3	32	(M)	1251418R/L	38.1 (40)	60	70	15.9 (16	5.4) 10	30	25	125	14-18	8
	1601418	38.1 (40)	14	56	9.52 (10)	42.3	50		1601418R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	43	160	14-18	10
	2001418	50.8 (50)	14	72	12.7 (12)	55.8	61		2001418R/L	50.8 (40)	65	90	19.0 (16	.4) 11	30	53	200	14-18	12
	2501418	50.8 (50)	14	72	12.7 (12)	55.8	86		2501418R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	58	250	14-18	16
	3151418	50.8 (50)	14	72	12.7 (12)	55.8	118		3151418R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	90	315	14-18	20
TAFCP	1001821	31.75 (32)	18	48	7.92 (8)	35.2	24	TAFCB	1001821R/L	31.75 (32)	50	50	12.7 (14	.4) 8	28	21	100	18-21	6
(M)	1251821	38.1 (40)	18	56	9.52 (10)	42.3	32	(M)	1251821R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	25	125	18-21	8
	1601821	38.1 (40)	18	56	9.52 (10)	42.3	50		1601821R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	43	160	18-21	10
	2001821	50.8 (50)	18	72	12.7 (12)	55.8	61		2001821R/L	50.8 (40)	65	90	19.0 (16	6.4) 11	30	53	200	18-21	12
	2501821	50.8 (50)	18	72	12.7 (12)	55.8	86		2501821R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	58	250	18-21	16
	3151821	50.8 (50)	18	72	12.7 (12)	55.8	118		3151821R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	90	315	18-21	20
TAFCP	1002124	31.75 (32)	21	48	7.92 (8)	35.2	24	TAFCB	1002124R/L	31.75 (32)	50	54	12.7 (14	.4) 8	28	21	100	21-24	6
(M)	1252124	38.1 (40)	21	56	9.52 (10)	42.3	32	(M)	1252124R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	25	125	21-24	8
	1602124	38.1 (40)	21	56	9.52 (10)	42.3	50		1602124R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	43	160	21-24	10
	2002124	50.8 (50)	21	72	12.7 (12)	55.8	61		2002124R/L	50.8 (40)	65	90	19.0 (16	5.4) 11	30	53	200	21-24	12
	2502124	50.8 (50)	21	72	12.7 (12)	55.8	86		2502124R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	58	250	21-24	16
	3152124	50.8 (50)	21	72	12.7 (12)	55.8	118		3152124R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	90	315	21-24	20
TAFCP	1252427	38.1 (40)	24	56	9.52 (10)	42.3	32	TAFCB	1252427R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	25	125	24-27	8
(M)	1602427	38.1 (40)	24	56	9.52 (10)	42.3	50	(M)	1602427R/L	38.1 (40)	60	70	15.9 (16	.4) 10	30	43	160	24-27	10
	2002427	50.8 (50)	24	72	12.7 (12)	55.8	61		2002427R/L	50.8 (40)	65	90	19.0 (16	5.4) 11	30	53	200	24-27	12
	2502427	50.8 (50)	24	72	12.7 (12)	55.8	86		2502427R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	58	250	24-27	16
	3152427	50.8 (50)	24	72	12.7 (12)	55.8	118		3152427R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	90	315	24-27	20
TAFCP	1252730	38.1 (40)	27	56	9.52 (10)	42.3	32	TAFCB	1252730R/L	38.1 (40)	60	70	15.9 (16	5.4) 10	30	25	125	27-30	8
(M)	1602730	38.1 (40)	27	56	9.52 (10)	42.3	50	(M)	1602730R/L	38.1 (40)	60	70	15.9 (16	5.4) 10	30	43	160	27-30	10
	2002730	50.8 (50)	27	72	12.7 (12)	55.8	61		2002730R/L	50.8 (40)	65	90	19.0 (16	5.4) 11	30	53	200	27-30	12
	2502730	50.8 (50)	27	72	12.7 (12)	55.8	86		2502730R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	58	250	27-30	16
	3152730	50.8 (50)	27	72	12.7 (12)	55.8	118		3152730R/L	47.625 (60)	65	130	25.4 (25	.7) 14	38	90	315	27-30	20
		•																	

Available inserts and Recommended cutting condition
E406 • The ap (Maximum width of cutter) size written above is the number when using insert having corner size C0.5 or R0.5
( )Metric size


### Parts


o i aito									
Specification								**CONCOL	
Edge width TAFCP(B)	Insert	Locator	Wedge	Insert screw	Wedge screw	Locator screw	Insert wrench	Wedge Wrench	Locator Wrench
□□□1418R/L	CNHQ1005-□□□	LSA-CH10R/L	WSA10N	FTKA0410	DHA0617	SHGA0411	TW15S	HW30	-
□□□1821R/L	CNHQ1305-□□□	LSA-CH13R/L	WSA13N	FTKA0410	DHA0821F	SHGA0411	TW15S	HW40	HW30L
□□□2124R/L	CNHQ1305-□□□	LSA-CH13R/L	WSA13N	FTKA0410	DHA0821F	SHGA0411	TW15S	HW40	HW30L
□□□2427R/L	CNHQ1606-□□□	LSA-CH16R/L	WSA13N	FTGA0513-P	DHA0821F	SHGA0411	TW20S	HW40	HW30L
□□□2730R/L	CNHQ1606-□□□	LSA-CH16R/L	WSA13N	FTGA0513-P	DHA0821F	SHGA0411	TW20S	HW40	HW30L

• Note) The Wedge screw for 1001821, 1002124 cutter is DHA0818F



## Tangential type (Half side cutter)





CP(M) • TAHCB(M)

(mm)


Dani	lawatian	αų	_	αD.		- TMAX	Decima	ation.	α4	_	αD-			<b>L</b>	_	TMAY		Dime	ension	ıs
Desi	ignation	Ød	E	ØD2	2 a	o T-MA)	Design	iation	Ød	F	ØD2	а		b	E	T-MAX	ØD	W	W <sub>1</sub>	No. of tooth
TAHCP	10014R/L	31.75 (32)	14	48	7.92 (8) 3	5.2 24	TAHCB 1	0014R/L	31.75 (32)	50	54	12.7 (	14.4)	8	28	21	100	9	13.25	6
(M)	12514R/L	38.1 (40)	14	56	9.52 (10) 42	2.3 32	(M) 1:	2514R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	25	125	9	13.25	8
	16014R/L	38.1 (40)	14	56	9.52 (10) 42	2.3 50	10	6014R/L	38.1 (40)	60	70	15.9 ( <sup>-</sup>	16.4)	10	30	43	160	9	13.25	10
	20014R/L	50.8 (50)	14	72	12.7 (12) 5	5.8 61	20	0014R/L	50.8 (40)	65	90	19.0 (	16.4)	11	30	53	200	9	13.25	12
	25014R/L	50.8 (50)	14	72	12.7 (12) 5	5.8 86	2	5014R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	58	250	9	13.25	16
	31514R/L	50.8 (50)	14	72	12.7 (12) 5	5.8 118	3	1514R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	90	315	9	13.25	20
<b>TAHCP</b>	10018R/L	31.75 (32)	18	48	7.92 (8) 3	5.2 24	TAHCB 1	0018R/L	31.75 (32)	50	50	12.7 (	14.4)	8	28	21	100	12	16.75	6
(M)	12518R/L	38.1 (40)	18	56	9.52 (10) 42	2.3 32	(M) 1:	2518R/L	38.1 (40)	60	70	15.9 ( <sup>-</sup>	16.4)	10	30	25	125	12	16.75	8
	16018R/L	38.1 (40)	18	56	9.52 (10) 42	2.3 50	10	6018R/L	38.1 (40)	60	70	15.9 (°	16.4)	10	30	43	160	12	16.75	10
	20018R/L	50.8 (50)	18	72	12.7 (12) 5	5.8 61	20	0018R/L	50.8 (40)	65	90	19.0 (	16.4)	11	30	53	200	12	16.75	12
	25018R/L	50.8 (50)	18	72	12.7 (12) 5	5.8 86	2	5018R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	58	250	12	16.75	16
	31518R/L	50.8 (50)	18	72	12.7 (12) 5	5.8 118	3	1518R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	90	315	12	16.75	20
	10021R/L	31.75 (32)	21	48	7.92 (8) 3	5.2 24	TAHCB 1	0021R/L	31.75 (32)	50	54	12.7 (	14.4)	8	28	21	100	12	19.75	6
(M)	12521R/L	38.1 (40)	21	56	9.52 (10) 42	2.3 32	(M) 1:	2521R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	25	125	12	19.75	8
	16021R/L	38.1 (40)	21	56	9.52 (10) 42	2.3 50	10	6021R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	43	160	12	19.75	10
	20021R/L	50.8 (50)	21	72	12.7 (12) 5	5.8 61	20	0021R/L	50.8 (40)	65	90	19.0 (	16.4)	11	30	53	200	12	19.75	12
	25021R/L	50.8 (50)	21	72	12.7 (12) 5	5.8 86	2	5021R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	58	250	12	19.75	16
	31521R/L	50.8 (50)	21	72	12.7 (12) 5	5.8 118	3	1521R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	90	315	12	19.75	20
TAHCP	12524R/L	38.1 (40)	24	56	9.52 (10) 42	2.3 32	TAHCB 1	2524R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	25	125	15	22.75	8
(M)	16024R/L	38.1 (40)	24	56	9.52 (10) 42	2.3 50	(M) 1	6024R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	43	160	15	22.75	10
	20024R/L	50.8 (50)	24	72	12.7 (12) 5	5.8 61	20	0024R/L	50.8 (40)	65	90	19.0 (	16.4)	11	30	53	200	15	22.75	12
	25024R/L	50.8 (50)	24	72	12.7 (12) 5	5.8 86	2	5024R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	58	250	15	22.75	16
	31524R/L	50.8 (50)	24	72	12.7 (12) 5	5.8 118	3	1524R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	90	315	15	22.75	20
TAHCP	12527R/L	38.1 (40)	27	56	9.52 (10) 42	2.3 32	TAHCB 1	2527R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	25	125	15	25.75	8
(M)	16027R/L	38.1 (40)	27	56	9.52 (10) 42	2.3 50	-	6027R/L	38.1 (40)	60	70	15.9 (	16.4)	10	30	43	160	15	25.75	10
	20027R/L	50.8 (50)	27	72	12.7 (12) 5	5.8 61	20	0027R/L	50.8 (40)	65	90	19.0 (	16.4)	11	30	53	200	15	25.75	12
	25027R/L	50.8 (50)	27	72	12.7 (12) 5	5.8 86	2	5027R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	58	250	15	25.75	16
	31527R/L	50.8 (50)	27	72	12.7 (12) 5	5.8 118	3	1527R/L	47.625 (60)	65	130	25.4 (2	25.7)	14	38	90	315	15	25.75	20


Available inserts and Recommended cutting condition
 E406 • The ap (Maximum width of cutter) size written above is the number when using insert having corner size C0.5 or R0.5
 ( )Metric size

Specification								Season Season	
Edge width TAHCP(B)	1 1 1	Locator	Wedge	Insert screw	Wedge screw	Locator screw	Insert wrench	Wedge Wrench	Locator Wrench
□□□1418R/L	CNHQ1005-□□□	LSA-CH10R/L	WSA10N	FTKA0410	DHA0617	SHGA0411	TW15S	HW30	-
□□□1821R/L	CNHQ1305-□□□	LSA-CH13R/L	WSA13N	FTKA0410	DHA0821F	SHGA0411	TW15S	HW40	HW30L
□□□2124R/L	CNHQ1305-	LSA-CH13R/L	WSA13N	FTKA0410	DHA0821F	SHGA0411	TW15S	HW40	HW30L
□□□2427R/L	CNHQ1606-	LSA-CH16R/L	WSA13N	FTGA0513-P	DHA0821F	SHGA0411	TW20S	HW40	HW30L
□□□2730R/L	CNHQ1606-	LSA-CH16R/L	WSA13N	FTGA0513-P	DHA0821F	SHGA0411	TW20S	HW40	HW30L



### Radial type (Full side cutter)





· RAFCP(M) • RAFCB(M)

(mm)

																			(11111)
Desi	gnation	Ød	Е	ØD2	a	b	T-MAX	Des	ignation	Ød	F	ØD2	а	b	Ε	T-MAX		mensio	
																	ØD	W	No. of tooth
	1001214	. ,			7.92 (8)				1001214R/L	` ,	50		2.7 (14.4)		28	21	100	12-14	6
(M)	1251214	38.1 (40)			9.52 (10)			(M)	1251214R/L	` '	60		5.9 (16.4)			25	125	12-14	8
	1601214	38.1 (40)			9.52 (10)				1601214R/L	. ,	60		5.9 (16.4)			43	160	12-14	10
	2001214	50.8 (50)	12	72	12.7 (12)	55.8	61		2001214R/L	50.8 (40)	65	90 1	9.0 (16.4)	11	30	53	200	12-14	12
	2501214	50.8 (50)	12	72	12.7 (12)	55.8	86		2501214R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	58	250	12-14	16
	3151214	50.8 (50)	12	72	12.7 (12)	55.8	118		3151214R/L	47.625 (60)	65		. ,		38	90	315	12-14	20
	1001416	31.75 (32)	14	48	7.92 (8)	35.2	24		1001416R/L	31.75 (32)	50	50 1	2.7 (14.4)	8	28	21	100	14-16	6
(M)	1251416	38.1 (40)	14	56	9.52 (10)	42.3	32	(M)	1251416R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	25	125	14-16	8
	1601416	38.1 (40)	14	56	9.52 (10)	42.3	50		1601416R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	43	160	14-16	10
	2001416	50.8 (50)	14	72	12.7 (12)	55.8	61		2001416R/L	50.8 (40)	65	90 1	9.0 (16.4)	11	30	53	200	14-16	12
	2501416	50.8 (50)	14	72	12.7 (12)	55.8	86		2501416R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	58	250	14-16	16
	3151416	50.8 (50)	14	72	12.7 (12)	55.8	118		3151416R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	90	315	14-16	20
RAFCP	1251618	38.1 (40)	16	56	9.52 (10)	42.3	32	RAFCB	1251618R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	25	125	16-18	8
(M)	1601618	38.1 (40)	16	56	9.52 (10)	42.3	50	(M)	1601618R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	43	160	16-18	10
	2001618	50.8 (50)	16	72	12.7 (12)	55.8	61		2001618R/L	50.8 (40)	65	90 1	9.0 (16.4)	11	30	53	200	16-18	12
	2501618	50.8 (50)	16	72	12.7 (12)	55.8	86		2501618R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	58	250	16-18	16
	3151618	50.8 (50)	16	72	12.7 (12)	55.8	118		3151618R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	90	315	16-18	20
RAFCP	1251820	38.1 (40)	18	56	9.52 (10)	42.3	32	RAFCB	1251820R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	25	125	18-20	8
(M)	1601820	38.1 (40)	18	56	9.52 (10)	42.3	50	(M)	1601820R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	43	160	18-20	10
	2001820	50.8 (50)	18	72	12.7 (12)	55.8	61		2001820R/L	50.8 (40)	65	90 1	9.0 (16.4)	11	30	53	200	18-20	12
	2501820	50.8 (50)	18	72	12.7 (12)	55.8	86		2501820R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	58	250	18-20	16
	3151820	50.8 (50)	18	72	12.7 (12)	55.8	118		3151820R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	90	315	18-20	20
RAFCP	1252022	38.1 (40)	20	56	9.52 (10)	42.3	32	RAFCB	1252022R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	25	125	20-22	8
(M)	1602022	38.1 (40)	20	56	9.52 (10)	42.3	50	(M)	1602022R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	43	160	20-22	10
	2002022	50.8 (50)	20	72	12.7 (12)	55.8	61		2002022R/L	50.8 (40)	65	90 1	9.0 (16.4)	11	30	53	200	20-22	12
	2502022	50.8 (50)	20	72	12.7 (12)	55.8	86		2502022R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	58	250	20-22	16
	3152022	50.8 (50)	20	72	12.7 (12)	55.8	118		3152022R/L	47.625 (60)			5.4 (25.7)			90	315	20-22	20
RAFCP	1252224	38.1 (40)	22	56	9.52 (10)	42.3	32	RAFCB	1252224R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	25	125	22-24	8
(M)	1602224	38.1(40)	22	56	9.52 (10)	42.3	50	(M)	1602224R/L	38.1 (40)	60	70 1	5.9 (16.4)	10	30	43	160	22-24	10
	2002224	50.8 (50)	22		12.7 (12)			1	2002224R/L	` '	65		9.0 (16.4)			53	200	22-24	12
	2502224	50.8 (50)	22	72	12.7 (12)	55.8	86		2502224R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	58	250	22-24	16
	3152224	50.8 (50)		72	12.7 (12)	55.8	118		3152224R/L	47.625 (60)	65	130 2	5.4 (25.7)	14	38	90	315	22-24	20

Available inserts and Recommended cutting condition
E406 • The ap (Maximum width of cutter) size written above is the number when using insert having corner size C0.5 or R0.5 ( )Metric size

### Parts

□□**2224R/L** SDXT13050□R/L

LSD13R/L

Specification  $\bigcirc$ WSA10N Edge width RAFCP(B) Wedge Wedge screw Wedge, locator wrench Insert screw Locator screw Insert wrench □□□1214R/L SDXT09M40□R/L WSD09N FTGA03508 DHA0617 HW30 LSD09R/L SHGA0409 **TW15S** □□□1416R/L SDXT09M40□R/L LSD09R/L WSD09N FTGA03508 DHA0617 SHGA0409 TW15S HW30 □□□1618R/L SDXT13050□R/L LSD13R/L WSA10N FTNC04509 DHA0617 SHGA0411 TW20S HW30 1820R/L SDXT13050□R/L LSD13R/L WSA10N FTNC04509 DHA0617 SHGA0411 TW20S HW30 SDXT13050□R/L HW30 2022R/L LSD13R/L WSA10N FTNC04509 DHA0617 SHGA0411 TW20S

FTNC04509

DHA0617


SHGA0411


TW20S

WSA10N

HW30

## Radial type (Half side cutter)





• RAHCB(M)

																				(mm)
Desi	gnation	Ød	F	ØD2	а	b	T-MAX	Designation	ion	Ød	F	ØD2	а	b	Е	T-MAX		Dimer	sions	3
Desi	griation	, ou		χυ.	a	, D	I-IVIAA	Designation	OII	юu	<u>'</u>	XD2	а	Ü		I-IVIAA	ØD	W	W <sub>1</sub>	No. of tooth
	10012R/L	31.75 (32)	12	48	7.92 (8	35.2	24	RAHCB 1001	12R/L	31.75 (32)	50	54 12	7 (14.4)	8	28	21	100	8	11.1	6
(M)	12512R/L	38.1 (40)	12	56	9.52 (10	) 42.3	32	(M) 1251	12R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	25	125	8	11.1	8
	16012R/L	38.1 (40)	12	56	9.52 (10	) 42.3	50	1601	12R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	43	160	8	11.1	10
	20012R/L	50.8 (50)	12	72	12.7 (12	2) 55.8	61	2001	12R/L	50.8 (40)	65	90 19	0 (16.4)	11	30	53	200	8	11.1	12
	25012R/L	50.8 (50)	12	72	12.7 (12	2) 55.8	86	2501	12R/L 4	47.625 (60)	65	130 25	4 (25.7)	14	38	58	250	8	11.1	16
	31512R/L	50.8 (50)	12	72	12.7 (12	2) 55.8	118	3151	12R/L 4	47.625 (60)	65	130 25	4 (25.7)	14	38	90	315	8	11.1	20
	10014R/L	31.75 (32)	14	48	7.92 (8	) 35.2	24	RAHCB 1001	14R/L	31.75 (32)	50	50 12	7 (14.4)	8	28	21	100	8	13.1	6
(M)	12514R/L	38.1 (40)	14	56	9.52 (10	) 42.3	32	(M) 1251	14R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	25	125	8	13.1	8
	16014R/L	38.1 (40)	14	56	9.52 (10	) 42.3	50	1601	14R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	43	160	8	13.1	10
	20014R/L	50.8 (50)	14	72	12.7 (12	2) 55.8	61	2001	14R/L	50.8 (40)	65	90 19	0 (16.4)	11	30	53	200	8	13.1	12
	25014R/L	50.8 (50)	14	72	12.7 (12	2) 55.8	86	2501	14R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	58	250	8	13.1	16
	31514R/L	50.8 (50)	14	72	12.7 (12	2) 55.8	118	3151	14R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	90	315	8	13.1	20
	12516R/L	38.1 (40)	16	56	9.52 (10	) 42.3	32	<b>RAHCB</b> 1251	16R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	25	125	10.5	15	8
(M)	16016R/L	38.1 (40)	16	56	9.52 (10	) 42.3	50	(M) 1601	16R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	43	160	10.5	15	10
	20016R/L	50.8 (50)	16	72	12.7 (12	2) 55.8	61	2001	16R/L	50.8 (40)	65	90 19	0 (16.4)	11	30	53	200	10.5	15	12
	25016R/L	50.8 (50)	16	72	12.7 (12	2) 55.8	86	2501	16R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	58	250	10.5	15	16
	31516R/L	50.8 (50)	16	72	12.7 (12	2) 55.8	118	3151	16R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	90	315	10.5	15	20
	12518R/L	38.1 (40)	18	56	9.52 (10	) 42.3	32	RAHCB 1251	18R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	25	125	10.5	17	8
(M)	16018R/L	38.1 (40)	18	56	9.52 (10	) 42.3	50	(M) 1601	18R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	43	160	10.5	17	10
	20018R/L	50.8 (50)	18	72	12.7 (12	2) 55.8	61	2001	18R/L	50.8 (40)	65	90 19	0 (16.4)	11	30	53	200	10.5	17	12
	25018R/L	50.8 (50)	18	72	12.7 (12	2) 55.8	86	2501	18R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	58	250	10.5	17	16
	31518R/L	50.8 (50)	18	72	12.7 (12	2) 55.8	118	3151	18R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	90	315	10.5	17	20
	12520R/L	38.1 (40)	20	56	9.52 (10	) 42.3	32	<b>RAHCB 1252</b>	20R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	25	125	10.5	19	8
(M)	16020R/L	38.1 (40)	20	56	9.52 (10	) 42.3	50	(M) 1602	20R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	43	160	10.5	19	10
	20020R/L	50.8 (50)	20	72	12.7 (12	2) 55.8	61	2002	20R/L	50.8 (40)	65	90 19	0 (16.4)	11	30	53	200	10.5	19	12
	25020R/L	50.8 (50)	20	72	12.7 (12	2) 55.8	86	2502	20R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	58	250	10.5	19	16
	31520R/L	50.8 (50)	20	72	12.7 (12	2) 55.8	118	3152	20R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	90	315	10.5	19	20
	12522R/L	38.1 (40)	22	56	9.52 (10	) 42.3	32	<b>RAHCB 1252</b>	22R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	25	125	10.5	21	8
(M)	16022R/L	38.1 (40)	22	56	9.52 (10	) 42.3	50	(M) 1602	22R/L	38.1 (40)	60	70 15	9 (16.4)	10	30	43	160	10.5	21	10
	20022R/L	50.8 (50)	22	72	12.7 (12	2) 55.8	61	2002	22R/L	50.8 (40)	65	90 19	0 (16.4)	11	30	53	200	10.5	21	12
	25022R/L	50.8 (50)	22	72	12.7 (12	2) 55.8	86	2502	22R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	58	250	10.5	21	16
	31522R/L	50.8 (50)	22	72	12.7 (12	2) 55.8	118	3152	22R/L	47.625 (60)	65	130 25	4 (25.7)	14	38	90	315	10.5	21	20


- → Available inserts and Recommended cutting condition E406
- The ap (Maximum width of cutter) size written above is the number when using insert having corner size R0.5. The ap is subject to change as per insert corner size
- The ap (Maximum width of cutter) size written above is the number when using SDXT09M405R-MM. The ap is subject to change as per insert corner size


( )Metric size

Specification				<b>6</b>				- Tonos
Edge width RAHCP(B)	Insert	Locator	WSD09N WSA10N Wedge	Insert screw	Wedge screw	Locator screw	Insert wrench	Wedge, locator wrench
□□□1214R/L	SDXT09M40□R/L	LSD09R/L	WSD09N	FTGA03508	DHA0617	SHGA0409	TW15S	HW30
□□□1416R/L	SDXT09M40□R/L	LSD09R/L	WSD09N	FTGA03508	DHA0617	SHGA0409	TW15S	HW30
□□□1618R/L	SDXT13050□R/L	LSD13R/L	WSA10N	FTNC04509	DHA0617	SHGA0411	TW20S	HW30
□□□1820R/L	SDXT13050□R/L	LSD13R/L	WSA10N	FTNC04509	DHA0617	SHGA0411	TW20S	HW30
□□□2022R/L	SDXT13050□R/L	LSD13R/L	WSA10N	FTNC04509	DHA0617	SHGA0411	TW20S	HW30
□□□2224R/L	SDXT13050□R/L	LSD13R/L	WSA10N	FTNC04509	DHA0617	SHGA0411	TW20S	HW30

SPP(M)










													(mm)
Desig	gnation	0	ØD	W	T-MAX	Ød	а	b	E	ØD2	Insert	Screw	Wrench
SPP	080-04	8	80	4	20	25.4 (27)	6.35 (7)	28.04 (29.8)	8	40	PNEJ1223N	PTMA0403F	TW15S
(SPPM)	080-05	8	80	5	20	25.4 (27)	6.35 (7)	28.04 (29.8)	8	40	PNEJ1230N	PTMA0404F	TW15S
(,	080-06	8	80	6	20	25.4 (27)	6.35 (7)	28.04 (29.8)	8	40	PNEJ1235N	PTMA0405F	TW15S
	100-04	10	100	4	24	31.75 (32)	7.94 (8)	35.18 (34.8)	8	47	PNEJ1223N	PTMA0403F	TW15S
	100-05	10	100	5	24	31.75 (32)	7.94 (8)	35.18 (34.8)	8	47	PNEJ1230N	PTMA0404F	TW15S
	100-06	10	100	6	25	31.75 (32)	7.94 (8)	35.18 (34.8)	8	47	PNEJ1235N	PTMA0405F	TW15S
	100-07	10	100	7	25	31.75 (32)	7.94 (8)	35.18 (34.8)	10	47	PNEJ1240N	PTMA0406F	TW15S
	100-08	10	100	8	25	31.75 (32)	7.94 (8)	35.18 (34.8)	10	47	PNEJ1245N	PTKA0407F	TW15S
	100-09	10	100	9	25	31.75 (32)	7.94 (8)	35.18 (34.8)	12	47	PNEJ1250N	PTKA0408F	TW15S
	100-10	10	100	10	25	31.75 (32)	7.94 (8)	35.18 (34.8)	12	47	PNEJ1255N	PTKA0409F	TW15S
	125-04	12	125	4	30	38.1 (40)	9.53 (10)	42.32 (43.5)	8	56	PNEJ1223N	PTMA0403F	TW15S
	125-05	12	125	5	32	38.1 (40)	9.53 (10)	42.32 (43.5)	8	56	PNEJ1230N	PTMA0404F	TW15S
	125-06	12	125	6	32	38.1 (40)	9.53 (10)	42.32 (43.5)	8	56	PNEJ1235N	PTMA0405F	TW15S
	125-07	12	125	7	32	38.1 (40)	9.53 (10)	42.32 (43.5)	10	56	PNEJ1240N	PTMA0406F	TW15S
	125-08	12	125	8	32	38.1 (40)	9.53 (10)	42.32 (43.5)	10	56	PNEJ1245N	PTKA0407F	TW15S
	125-09	12	125	9	32	38.1 (40)	9.53 (10)	42.32 (43.5)	12	56	PNEJ1250N	PTKA0408F	TW15S
	125-10	12	125	10	32	38.1 (40)	9.53 (10)	42.32 (43.5)	12	56	PNEJ1255N	PTKA0409F	TW15S
	160-04	16	160	4	45	38.1 (40)	9.53 (10)	42.32 (43.5)	8	66	PNEJ1223N	PTMA0403F	TW15S
	160-05	16	160	5	45	38.1 (40)	9.53 (10)	42.32 (43.5)	8	66	PNEJ1230N	PTMA0404F	TW15S
	160-06	16	160	6	45	38.1 (40)	9.53 (10)	42.32 (43.5)	8	66	PNEJ1235N	PTMA0405F	TW15S
	160-07	16	160	7	45	38.1 (40)	9.53 (10)	42.32 (43.5)	10	66	PNEJ1240N	PTMA0406F	TW15S
	160-08	16	160	8	45	38.1 (40)	9.53 (10)	42.32 (43.5)	10	66	PNEJ1245N	PTKA0407F	TW15S
	160-09	16	160	9	45	38.1 (40)	9.53 (10)	42.32 (43.5)	12	66	PNEJ1250N	PTKA0408F	TW15S
	160-10	16	160	10	45	38.1 (40)	9.53 (10)	42.32 (43.5)	12	66	PNEJ1255N	PTKA0409F	TW15S
	160-11	16	160	11	45	38.1 (40)	9.53 (10)	42.32 (43.5)	14	66	PNEJ1260N	PTKA0410F	TW15S
	160-12	16	160	12	45	38.1 (40)	9.53 (10)	42.32 (43.5)	14	66	PNEJ1265N	PTKA0411F	TW15S
	160-13	16	160	13	45	38.1 (40)	9.53 (10)	42.32 (43.5)	16	66	PNEJ1270N	PTKA0412F	TW15S
	160-14	16	160	14	45	38.1 (40)	9.53 (10)	42.32 (43.5)	16	66	PNEJ1275N	PTKA0413F	TW15S
	200-06	18	200	6	60	50.8 (50)	12.7 (12)	55.83 (53.5)	8	70	PNEJ1235N	PTMA0405F	TW15S
	200-07	18	200	7	60	50.8 (50)	12.7 (12)	55.83 (53.5)	10	70	PNEJ1240N	PTMA0406F	TW15S
	200-08	18	200	8	60	50.8 (50)	12.7 (12)	55.83 (53.5)	10	70	PNEJ1245N	PTKA0407F	TW15S
	200-09	18	200	9	60	50.8 (50)	12.7(12)	55.83 (53.5)	12	70	PNEJ1250N	PTKA0408F	TW15S
	200-10	18	200	10	60	50.8 (50)	12.7 (12)	55.83 (53.5)	12	70	PNEJ1255N	PTKA0409F	TW15S
	200-11	18	200	11	60	50.8 (50)	12.7 (12)	55.83 (53.5)	14	70	PNEJ1260N	PTKA0410F	TW15S
	200-12	18	200	12	60	50.8 (50)	12.7 (12)	55.83 (53.5)	14	70	PNEJ1265N	PTKA0411F	TW15S
	200-13	18	200	13	60	50.8 (50)	12.7 (12)	55.83 (53.5)	16	70	PNEJ1270N	PTKA0412F	TW15S
	200-14	18	200	14	60	50.8 (50)	12.7 (12)	55.83 (53.5)	16	70	PNEJ1275N	PTKA0413F	TW15S

### Available arbors

De	signation		NC arbors	
Бе	signation	BT30	BT40	BT50
SPP	080-04~06	BT30-SCA25.4-60	BT40-SCA25.4-75/120	BT50-SCA25.4-90/135
	100-04~10		BT40-SCA31.75-105	BT50-SCA31.75-90/135
	125-04~09			BT50-SCA38.1-90/135
	160-04~14			BT50-SCA38.1-90/135
	200-06~14		-	-
SPPN	1 080-04~06	-	BT40-SCA27-75/120	BT50-SCA27-90/135
	100-04~10		BT40-SCA32-105	BT50-SCA32-90/135
	125-04~09			BT50-SCA40-90/135
	160-04~14			BT50-SCA40-90/135
	200-06~14			-

### Recommended cutting condition


Workpiece	Cutting of	condition	Grades
workpiece	vc (m/min)	fz (mm/t)	Grades
Р	190~310	0.10~0.25	NCM325
	160~270	0.10~0.30	PC3700
	60~100	0.10~0.25	ST30A
М	90~150	0.10~0.25	PC9530
	80~150	0.10~0.30	ST30A
K	140~230	0.10~0.35	PC6510
	50~90	0.10~0.40	G10




→ Available inserts E16 → Available arbors and bolt E426~E428

( )Metric size









(mm)

														(mm)
Des	ignation	0	ØD	w	T-MAX	ØD2	Ød	а	b	F	E	Insert	Screw	Wrench
SPB	080-04R/L	8	80	4	18	40	25.4 (27)	9.5 (12.4)	6 (7)	50	25 (22)	PNEJ1223N	PTMA0403F	TW15S
(SPBM)	080-05R/L	8	80	5	18	40	25.4 (27)	9.5 (12.4)	6 (7)	50	25 (22)	PNEJ1230N	PTMA0404F	TW15S
	080-06R/L	8	80	6	18	40	25.4 (27)	9.5 (12.4)	6 (7)	50	25 (22)	PNEJ1235N	PTMA0405F	TW15S
	100-04R/L	10	100	4	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1223N	PTMA0403F	TW15S
	100-05R/L	10	100	5	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1230N	PTMA0404F	TW15S
	100-06R/L	10	100	6	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1235N	PTMA0405F	TW15S
	100-07R/L	10	100	7	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1240N	PTMA0406F	TW15S
	100-08R/L	10	100	8	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1245N	PTMA0407F	TW15S
	100-09R/L	10	100	9	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1250N	PTMA0408F	TW15S
	100-10R/L	10	100	10	21	54	31.75 (32)	12.7 (14.4)	8 (8)	50	32 (28)	PNEJ1255N	PTMA0409F	TW15S
	125-04R/L	12	125	4	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1223N	PTMA0403F	TW15S
	125-05R/L	12	125	5	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1230N	PTMA0404F	TW15S
	125-06R/L	12	125	6	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1235N	PTMA0405F	TW15S
	125-07R/L	12	125	7	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1240N	PTMA0406F	TW15S
	125-08R/L	12	125	8	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1245N	PTKA0407F	TW15S
	125-09R/L	12	125	9	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1250N	PTKA0408F	TW15S
	125-10R/L	12	125	10	25	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1255N	PTKA0409F	TW15S
	160-04R/L	16	160	4	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1223N	PTMA0403F	TW15S
	160-05R/L	16	160	5	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1230N	PTMA0404F	TW15S
	160-06R/L	16	160	6	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1235N	PTMA0405F	TW15S
	160-07R/L	16	160	7	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1240N	PTMA0406F	TW15S
	160-08R/L	16	160	8	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1245N	PTKA0407F	TW15S
	160-09R/L	16	160	9	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1250N	PTKA0408F	TW15S
	160-10R/L	16	160	10	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1255N	PTKA0409F	TW15S
	160-11R/L	16	160	11	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1260N	PTKA0410F	TW15S
	160-12R/L	16	160	12	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1265N	PTKA0411F	TW15S
	160-13R/L	16	160	13	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1270N	PTKA0412F	TW15S
	160-14R/L	16	160	14	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60 (50)	38 (30)	PNEJ1275N	PTKA0413F	TW15S
	200-06R/L	18	200	6	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1235N	PTMA0405F	TW15S
	200-07R/L	18	200	7	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1240N	PTMA0406F	TW15S
	200-08R/L	18	200	8	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1245N	PTKA0407F	TW15S
	200-09R/L	18	200	9	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1250N	PTKA0408F	TW15S
	200-10R/L	18	200	10	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1255N	PTKA0409F	TW15S
	200-11R/L	18	200	11 12	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1260N	PTKA0410F	TW15S
	200-12R/L	18	200		53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1265N	PTKA0411F	TW15S
	200-13R/L	18	200	13	53 53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1270N	PTKA0412F	TW15S
	200-14R/L	18	200	14	53	90	50.8 (40)	19 (16.4)	11 (9)	65	38 (30)	PNEJ1275N	PTKA0413F	TW15S

( )Metric size

### Notice (When mounting inserts)


- ▶ Insert chip breaker should face chip pocket of the cutter
- ▶ Fasten screw after insert contacts securely on its seat
- ▶ If there is a gap between insert and its seat after mounting it may cause tool troubles

### Recommended cutting condition

Workning	Cutting of	ondition	Grades
Workpiece	vc (m/min)	fz (mm/t)	Graues
P	190~310 160~270 60~100	0.10~0.25 0.10~0.30 0.10~0.25	NCM325 PC3700 ST30A
М	90~150 80~150	0.10~0.25 0.10~0.30	PC9530 ST30A
К	140~230	0.10~0.35 0.10~0.40	PC6510 G10



## **SPS**




(mm)

	Designation		ØD	W	T-MAX	Ød	<b>A</b> 1	Fig	Incort	Adapt	or	Wrench
	Designation		טש	VV	I-IVIAX	υa	A1	Fig.	Insert	WS	DF	wrench
SPS	050-0204-08R	4	50	2.2	11	8	1.8	2		WS2528-M4	-	
	063-0205-10R	5	63	2.2	15.5	10	1.8	3	SPFN	WS2532-M5	-	
	080-0207-22R/F	7	80	2.2	20 (17)	22	1.8	1	200	WS3240-M5	DF22-46	
	100-0209-22R/F	9	100	2.2	30 (27)	22	1.8	1		WS3240-M5	DF22-46	
	125-0211-32F 160-0214-32F	11	125	2.2	35	32	1.8	1	- ( )	-	DF32-55	
		14	160	2.2	52.5	32	1.8	3		-	DF32-55	
	063-0305-10R	5	63	3	15.5	10	2.55	1		WS2532-M5	-	
	080-0307-22R/F	7	80	3	20 (17)	22	2.55	1	SPFN 300	WS3240-M5	DF22-46	SW17P (separately ordered)
	100-0309-22R/F	9	100	3	30 (27)	22	2.55	1		WS3240-M5	DF22-46	
	125-0311-32F	11	125	3	35	32	2.55	1		-	DF32-55	
	160-0314-32F	14	160	3	52.5	32	2.55	1	( )	-	DF32-55	
	200-0318-40F	18	200	3	60	40	2.55	1		-	DF40-80	
	080-0406-22R/F	6	80	4	20 (17)	22	3.4	1		WS3240-M5	DF22-46	
	100-0408-22R/F 125-0410-32F 160-0413-32F	8	100	4	30 (27)	22	3.4	1	SPFN	WS3240-M5	DF22-46	
		10	125	4	35	32	3.4	1	400	-	DF32-55	
		13	160	4	52.5	32	3.4	1	( )	-	DF32-55	
	200-0417-40F	17	200	4	60	40	3.4	1		-	DF40-80	1


( )Metric size

### **♥** WS( )-( ) (Weldon Shank)



Designation	L	L <sub>1</sub>	D	<b>D</b> 1	<b>D</b> 2	d	Screw
WS2528-M4	110	85	25	28	18	8	PTKA0408
WS2532-M5	110	85	25	32	22	10	PTKA0515
WS3240-M5	120	90	32	40	32	22	PTKA0515

### DF( )-( ) (Drive Flange set)



Designation	D1	D <sub>2</sub>	d	d1	Α	Е	F
DF22-46	46	32	22	5	10	24.1	6
DF32-55	55	45	32	6	10	34.8	8
DF40-80	80	63	40	11	12	43.5	10
DF50-110	110	80	50	14	14	53.6	12

### Recommended cutting condition

Workpiece	Cutting of	Cutting condition							
workpiece	vc (m/min)	fz (mm/t)	Grades						
Р	160~270	0.13~0.25	PC3700						
M	90~150	0.10~0.22	PC5300						
K	110~180	0.10~0.25	PC6510						

→ Available inserts E26 → Available arbors and bolt E426~E428



### For slotting workpieces with corner radii of varying sizes and widths

## **Wind Mill**

- Optimal machining for slotting applications
- A unique recess design on the minor cutting-edge reduces cutting load and improves tool life
- Special clamping system prevents incorrect clamping and fracture

### Item description








WFSP(M) - Plane type


WFSB(M) - Boss type

### Code system

### · Insert



### Cutter




### Features


 Ideal geometry for superior surface roughness and extended tool life



Perpendicular slot



 Protruded part on tip seat prevents wrong clamping and fracture



• Workpieces with corner radii of varying size and width (R0.2~R2.0)

R0.2	R0.4	R0.6	R0.8	R1.0	R1.2	R1.4	R1.6	R1.8	R2.0

## **Technical Information for Wind Mill**

## E

### Application example

■ **Use** Carriers for Motor Vehicles

■Workpiece FCD500K

■ Cutting vc (m/min) = 200 conditions fz (mm/t) = 0.2

vf (mm/min) = 600 ap (mm) = 2~3

■Tool KSF140R-T14-HM-2

SNHT1205408R/L-WX (PC5300)


(ee) ssed full limproved improved

180

152

Wind Mill Competitor's

■ Test result



■Use

Lug for Vessel


■Workpiece Mild steel


■ Cutting vc (m/min) = 560 conditions fz (mm/t) = 0.09

fz (mm/t) = 0.09 vf (mm/min) = 750 ap (mm) = 6

■Tool WFSP178R/L-T06

SNHT1203508R/L-WX (PC5300)





### Recommended cutting condition

Workpiece	Cutting c	onditions	Cuadaa
workpiece	vc (m/min)	fz (mm/t)	Grades
Р	150~250	0.10~0.25	PC5300
M	120~200	0.10~0.30	PC5300
K	100~150	0.10~0.30	PC5300



### Available inserts


	Designation	Coated		Dimensi	ons (mm	1)		Configuration		
	Designation	PC5300	Ød	Ød <sub>1</sub>	t	W	Nose R			
SNHT	1102308R/L-WX	•	11.0	4	2.30	4.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6			
	110308R/L-WX	•	11.0	4	3.00	5.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6			
	1203508R/L-WX	•	12.7	5	3.54	6.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0			
	120408R/L-WX		12.7	5	4.00	7.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0			
	1204508R/L-WX	•	12.7	5	4.54	8.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0		_	
	120508R/L-WX	•	12.7	5	5.00	9.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0		<b>†</b> d₁	
	1205408R/L-WX	•	12.7	5	5.47	10.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0	d t		
	120608R/L-WX		12.7	5	6.00	11.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0		ļi	
	1206508R/L-WX		12.7	5	6.50	12.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0			
	120708R/L-WX		12.7	5	7.00	13.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0			
	1207508R/L-WX		12.7	5	7.50	14.0	0.2, 0.4, 0.6, 0.8, 1.0, 1.2, 1.4, 1.6, 2.0			


<sup>•</sup> Available cutter stock requires to be asked separately



## WFSB(M) (Boss type)










Fig. 1


Fig. 2



Des	ignation	0	ØD	w	Т-мах	ØD <sub>2</sub>	Ød	а	b	F	E	Insert	Screw	Wrench
WFSBM	080R/L-T04	8	80	4	17	40	22	10.4	6.3	50	21	SNHT11023R/L-WX	PTMA03503	TW09S
	080R/L-T05	8	80	5	17	40	22	10.4	6.3	50	21	SNHT1103R/L-WX	PTMA03504	TW09S
	080R/L-T06	8	80	6	17	40	22	10.4	6.3	50	21	SNHT12035R/L-WX	PTMA04045F	TW15S
WFSB	100R/L-T04	10	100	4	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT11023R/L-WX	PTMA03503	TW09S
(WFSBM)	100R/L-T05	10	100	5	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT1103R/L-WX	PTMA03504	TW09S
	100R/L-T06	10	100	6	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT12035R/L-WX	PTMA04045F	TW15S
	100R/L-T07	10	100	7	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT1204R/L-WX	PTMA0405F	TW15S
	100R/L-T08	10	100	8	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT12045R/L-WX	PTMA0406F	TW15S
	100R/L-T09	10	100	9	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT1205R/L-WX	PTMA0407F	TW15S
	100R/L-T10	10	100	10	21	50 (48)	25.4 (27)	9.5 (12.4)	6 (7)	50	25	SNHT12054R/L-WX	PTMA0408F	TW15S
	125R/L-T04	12	125	4	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT11023R/L-WX	PTMA03503	TW09S
	125R/L-T05	12	125	5	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT1103R/L-WX	PTMA03504	TW09S
	125R/L-T06	12	125	6	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT12035R/L-WX	PTMA04045F	TW15S
	125R/L-T07	12	125	7	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT1204R/L-WX	PTMA0405F	TW15S
	125R/L-T08	12	125	8	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT12045R/L-WX	PTMA0406F	TW15S
	125R/L-T09	12	125	9	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT1205R/L-WX	PTM A0407F	TW15S
	125R/L-T10	12	125	10	30	60 (58)	31.75 (32)	12.7 (14.4)	8	50	32 (30)	SNHT12054R/L-WX	PTMA0408F	TW15S
	160R/L-T04	16	160	4	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT11023R/L-WX	PTMA03503	TW09S
	160R/L-T05	16	160	5	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT1103R/L-WX	PTMA03504	TW09S
	160R/L-T06	16	160	6	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT12035R/L-WX	PTMA04045F	TW15S
	160R/L-T07	16	160	7	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT1204R/L-WX	PTMA0405F	TW15S
	160R/L-T08	16	160	8	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT12045R/L-WX	PTMA0406F	TW15S
	160R/L-T09	16	160	9	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT1205R/L-WX	PTMA0407F	TW15S
	160R/L-T10	16	160	10	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT12054R/L-WX	PTMA0408F	TW15S
	160R/L-T11	16	160	11	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT1206R/L-WX	PTKA0409F	TW15S
	160R/L-T12	16	160	12	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT12065R/L-WX	PTKA0410F	TW15S
	160R/L-T13	16	160	13	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT1207R/L-WX	PTKA0411F	TW15S
	160R/L-T14	16	160	14	43	70	38.1 (40)	15.9 (16.4)	10 (9)	60	38 (32)	SNHT12075R/L-WX	PTKA0412F	TW15S
	200R/L-T06	18	200	6	53	90	50.8 (40)	19.1 (16.4)	11 (9)	65	38 (32)	SNHT12035R/L-WX	PTMA04045F	TW15S
	200R/L-T07	18	200	7	53	90	50.8 (40)	19.1 (16.4)	11 (9)	65	38 (32)	SNHT1204R/L-WX	PTMA0405F	TW15S
	200R/L-T08	18	200	8	53	90	50.8 (40)	19.1 (16.4)	11 (9)	65	38 (32)	SNHT12045R/L-WX	PTMA0406F	TW15S
	200R/L-T09	18	200	9	53	90	50.8 (40)	19.1 (16.4)	11 (9)	65	38 (32)	SNHT1205R/L-WX	PTMA0407F	TW15S
	200R/L-T10	18	200	10	53	90	50.8 (40)	19.1 (16.4)		65	38 (32)	SNHT12054R/L-WX	PTMA0408F	TW15S
	200R/L-T11	18	200	11	53	90	50.8 (40)	19.1 (16.4)		65	38 (32)	SNHT1206R/L-WX	PTKA0409F	TW15S
	200R/L-T12	18	200	12	53	90	. ,	19.1 (16.4)	. ,	65	38 (32)	SNHT12065R/L-WX	PTKA0410F	TW15S
	200R/L-T13	18	200	13	53	90		19.1 (16.4)	11 (9)	65	38 (32)	SNHT1207R/L-WX	PTKA0411F	TW15S
	200R/L-T14	18	200	14	53	90		, ,	11 (9)	65	38 (32)	SNHT12075R/L-WX	PTKA0412F	TW15S
	250R/L-T06	20	250	6	. ,	100 (90)	. ,	19.1 (16.4)	. ,	65	38 (32)	SNHT12035R/L-WX	PTMA04045F	TW15S
	250R/L-T07	20	250	7	. ,	100 (90)	50.8 (40)	19.1 (16.4)	. ,	65	38 (32)	SNHT1204R/L-WX	PTMA0405F	TW15S
	250R/L-T08	20	250	8	. ,	100 (90)	50.8 (40)	19.1 (16.4)		65	38 (32)	SNHT12045R/L-WX	PTMA0406F	TW15S
	250R/L-T09	20	250	9	. ,	100 (90)	50.8 (40)	19.1 (16.4)		65	38 (32)	SNHT1205R/L-WX	PTMA0407F	TW15S
	250R/L-T10	20	250	10		100 (90)	50.8 (40)	19.1 (16.4)		65	38 (32)	SNHT12054R/L-WX	PTMA0408F	TW15S
	250R/L-T11	20	250	11	. ,	100 (90)	50.8 (40)	19.1 (16.4)		65	38 (32)	SNHT1206R/L-WX	PTKA0409F	TW15S
	250R/L-T12	20	250	12	_ ` '	100 (90)	50.8 (40)	19.1 (16.4)	11 (9)	65	38 (32)	SNHT12065R/L-WX	PTKA0410F	TW15S
	250R/L-T13	20	250	13		100 (90)	50.8 (40)		11 (9)	65	38 (32)	SNHT1207R/L-WX	PTKA0411F	TW15S
	250R/L-T14	20	250	14	73 (78)	100 (90)	50.8 (40)	19.1 (16.4)	11 (9)	65	38 (32)	SNHT12075R/L-WX	PTKA0412F	TW15S

## WFSP(M) (Plane type)







Desig	gnation	0	ØD	W	Т-мах	ØD <sub>2</sub>	Ød	а	b	Ε	Insert	Screw	Wrench
WFSP	080-T04	8	80	4	20	40	25.4 (27)	6.35 (7)	28 (29.8)	8	SNHT11023R/L-WX	PTMA03503	TW09S
(WFSBM)	080-T05	8	80	5	20	40	25.4 (27)	6.35 (7)	28 (29.8)	8	SNHT1103R/L-WX	PTMA03504	TW09S
	080-T06	8	80	6	20	40	25.4 (27)	6.35 (7)	28 (29.8)	8	SNHT12035R/L-WX	PTMA04045F	TW15S
	100-T04	10	100	4	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	8	SNHT11023R/L-WX	PTMA03503	TW09S
	100-T05	10	100	5	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	8	SNHT1103R/L-WX	PTMA03504	TW09S
	100-T06	10	100	6	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	8	SNHT12035R/L-WX	PTMA04045F	TW15S
	100-T07	10	100	7	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	10	SNHT1204R/L-WX	PTMA0405F	TW15S
	100-T08	10	100	8	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	10	SNHT12045R/L-WX	PTMA0406F	TW15S
	100-T09	10	100	9	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	12	SNHT1205R/L-WX	PTMA0407F	TW15S
	100-T10	10	100	10	24	47	31.75 (32)	7.92 (8)	35.2 (34.8)	12	SNHT12054R/L-WX	PTMA0408F	TW15S
	125-T04	12	125	4	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	8	SNHT11023R/L-WX	PTMA03503	TW09S
	125-T05	12	125	5	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	8	SNHT1103R/L-WX	PTMA03504	TW09S
	125-T06	12	125	6	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	8	SNHT12035R/L-WX	PTMA04045F	TW15S
	125-T07	12	125	7	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	10	SNHT1204R/L-WX	PTMA0405F	TW15S
	125-T08	12	125	8	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	10	SNHT12045R/L-WX	PTMA0406F	TW15S
	125-T09	12	125	9	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	12	SNHT1205R/L-WX	PTMA0407F	TW15S
	125-T10	12	125	10	32	56	38.1 (40)	9.52 (10)	42.3 (43.5)	12	SNHT12054R/L-WX	PTMA0408F	TW15S
	160-T04	16	160	4	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	8	SNHT11023R/L-WX	PTMA03503	TW09S
	160-T05	16	160	5	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	8	SNHT1103R/L-WX	PTMA03504	TW09S
	160-T06	16	160	6	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	8	SNHT12035R/L-WX	PTMA04045F	TW15S
	160-T07	16	160	7	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	10	SNHT1204R/L-WX	PTMA0405F	TW15S
	160-T08	16	160	8	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	10	SNHT12045R/L-WX	PTMA0406F	TW15S
	160-T09	16	160	9	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	12	SNHT1205R/L-WX	PTMA0407F	TW15S
	160-T10	16	160	10	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	12	SNHT12054R/L-WX	PTMA0408F	TW15S
	160-T11	16	160	11	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	14	SNHT1206R/L-WX	PTKA0409F	TW15S
	160-T12	16	160	12	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	14	SNHT12065R/L-WX	PTKA0410F	TW15S
	160-T13	16	160	13	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	16	SNHT1207R/L-WX	PTKA0411F	TW15S
	160-T14	16	160	14	45	66	38.1 (40)	9.52 (10)	42.3 (43.5)	16	SNHT12075R/L-WX	PTKA0412F	TW15S
	200-T06	18	200	6	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	8	SNHT12035R/L-WX	PTMA04045F	TW15S
	200-T07	18	200	7	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	10	SNHT1204R/L-WX	PTMA0405F	TW15S
	200-T08	18	200	8	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	10	SNHT12045R/L-WX	PTMA0406F	TW15S
	200-T09	18	200	9	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	12	SNHT1205R/L-WX	PTMA0407F	TW15S
	200-T10	18	200	10	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	12	SNHT12054R/L-WX	PTMA0408F	TW15S
	200-T11	18	200	11	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	14	SNHT1206R/L-WX	PTKA0409F	TW15S
	200-T12	18	200	12	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	14	SNHT12065R/L-WX	PTKA0410F	TW15S
	200-T13	18	200	13	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	16	SNHT1207R/L-WX	PTKA0411F	TW15S
	200-T14	18	200	14	60	70	50.8 (50)	12.7 (12)	55.8 (53.5)	16	SNHT12075R/L-WX	PTKA0412F	TW15S
	250-T06	20	250	6	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	8	SNHT12035R/L-WX	PTMA04045F	TW15S
	250-T07	20	250	7	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	10	SNHT1204R/L-WX	PTMA0405F	TW15S
	250-T08	20	250	8	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	10	SNHT12045R/L-WX	PTMA0406F	TW15S
	250-T09	20	250	9	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	12	SNHT1205R/L-WX	PTMA0407F	TW15S
	250-T10	20	250	10	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	12	SNHT12054R/L-WX	PTMA0408F	TW15S
	250-T11	20	250	11	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	14	SNHT1206R/L-WX	PTKA0409F	TW15S
	250-T12	20	250	12	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	14	SNHT12065R/L-WX	PTKA0410F	TW15S
	250-T13	20	250	13	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	16	SNHT1207R/L-WX	PTKA0411F	TW15S
	250-T14	20	250	14	88	70	50.8 (50)	12.7 (12)	55.8 (53.5)	16	SNHT12075R/L-WX	PTKA0412F	TW15S



### **Technical Information for High feed Cutter**

### High feed cutter with extra pitch for cast iron and light alloy steels

## **High feed Cutter**

- High feed cutter employs extra pitch for cast iron and light alloy steels
- Quick change type for reduction of cutter change time
- Cutting-edge chatter is controlled
- Quick change type for cutter size under ø160, 2 piece types for cutter size over ø200

### Guide of insert setting


· Special equipment has to be used to get precise run out with high feed cutter.

# Adaptor type

- Mainly under ø160 diameter is used in 1 piece type
- Available for fixed size of cutter and assembling & checking can be done at the same time

# Roller type

- Mainly over ø200 diameter is used in 2 piece type
- Due to 3 adjustable guide rollers, variety size of cutter can be assembled




- Suitable for small size cutter due to the simple structure
- It is unnecessary to unclamp the cutter from the machine, it's possible to reassemble the cutter as it mounted on the machine
- You should make plate by yourself

### · Guide of insert setting in adaptor/roller type

- 1. Clean the cutter and equipment
- 2. Pointer should be assembled with same height with cutter
- 3. Move to each insert on tip seat to end of pointer and tighten (torque 2 N.m) wedge
- 4. Exchange pointer to dial gauge
- 5. Measure the run-out totally
- 6. When a insert over run-out, loosen wedge and adjust run-out. (for roughing  $10\sim20~\mu$ , for finishing  $5\sim10~\mu$ )
- 7. Tighten (torque 7-8 N.m) wedge
- 8. Measure the final run-out by dial gauge

Note: When you clamp wedge too tightly, run-out will get worse due to cutter distortion. When you clamp the wedge, use torque wrench to set precisely.

### Adaptor (Ø200~Ø450)



De	esignation	ØD	Ød	Ød <sub>1</sub>	Ød <sub>2</sub>	Ød₃	Ød4	Ød₅	øс	ØC <sub>1</sub>	ØC <sub>2</sub>	N	Cutter
APR	200	180	47.625	26	18	-	-	80	120	101.6	-	4	Ø200
	250	230	47.625	26	18	-	-	120	170	101.6	-	4	Ø250
	315	295	47.625	26	18	32	22	180	230	101.6	177.8	6	Ø315
	355	335	63.50	26	18	32	22	220	270	101.6	177.8	6	Ø355
	400	370	63.50	26	18	32	22	250	300	101.6	177.8	8	Ø400
	450	420	63.50	26	18	32	22	300	350	101.6	177.8	8	Ø450



## Technical Information for High feed Cutter



### High feed cutters type and features

Designation	Cutter diameter	Workpiece, Application range	Min. surface roughness	Approach angle and Max. cutting depth is for 5000 type	Axial rake angle	Radial rake angle	Available insert
ANH4000 ANH5000	Ø100~Ø450	Cast iron Roughing	25Z	45	-5°	-6°	SNCN1204ENN SNCN1504ENN
CDH4000 CDH5000	Ø100~Ø450	Cast iron Roughing Finishing	18Z	000 000 000 000 000 000	+10°	+5°	SDCN42R SDCN53R
DEH5000	Ø100~Ø450	Al alloy Roughing	20Z	30°, 20°, 20°, 20°, 20°, 20°, 20°, 20°, 2	+14°	+6°	HECN090408FN
DPH5000	Ø100~Ø450	Cast iron Roughing Finishing	12Z	30, 20, 20, 20, 20, 20, 20, 20, 20, 20, 2	<b>+</b> 5°	-3°	HPEN090408 HPEN090408-WC
PNH4000 PNH5000	Ø125~Ø450	Cast iron Finishing	12 <b>Z</b>	0.5	-5°	-6°	SNEF435 SNEF535
PPH4000	Ø125~Ø450	Cast iron Finishing	12Z	0.5	<b>+</b> 5°	-5°	SPEN120416-WC

### Recommended cutting condition

Worksiana	Cutting of	condition	Grades	Remark	
Workpiece	vc (m/min)	fz (mm/t)	Grades	nemark	
Cast iron	100~230 0.05~0.20		PC6510	PVD Coated	
Cast iron	80~150	0.05~0.20	H01, G10	Uncoated	
Aleller	400	0.10~0.30	PC6510	PVD Coated	
Al alloy	400	0.05~0.20	H01, G10	Uncoated	

### Special Korloy cutter for cast iron roughing


## **Cube Mill**

- · Special Korloy cutter for cast iron roughing
- 8-corner using insert (maximum 16-corner available with 2 cutter, R/L cutter)
- Excellent cutting performance with positive rake angle made by 3-dimensional chip breaker
- Excellent tool life by a wide combination of grade varieties and chip breakers to match most working conditions
- 2 different type of inserts (chamfer/nose R) are available with 1 type cutter




Roughing for cast iron

### Code system



<sup>\*</sup> Cube Mill and Cube Mill Couple are available by order made.

### Insert (R/L type)



### Cutter body

	Normal	Quick change
Cutter diameter (Ø)	Ø80~315 mm	Ø200~450 mm
ulamotor (2)	3 1/4~12 1/2 Inch	8~18 Inch
	AA: 88°, 85°, 75°, 65°,	45°

### Cutter





Screw on clamping system

### Parts







Wrench

Screw

FTGA0417CBM ETGA0520CBM

TW15-100 TW20-100



Milling


### Ideal combination of aluminum body with cast iron high feed cutter

## **Couple Mill**


- Ideal combination of Aluminum body with cast iron high feed cutter
- Since the weight of the cutter has been reduced 50% vs. a steel cutter, it is very easy to handle and very effective in preventing loading accidents
- Applicable for Cube Mill, Storm Mill

### Code system


### · Cube-couple



### · Storm-couple








### Cutter body

	Quick change			
Cutter diameter (Ø)	Metric	Ø355~450 mm		
	Inch	14 1/4~18 Inch		

Car age	a. with	Screw	Wrench	Wrench	Bolt for body	Bolt for key	Key for body	
Cube-Couple	3000 type	FTGA0417CBM	TW15-100		BHA0616	MHBO410	DN4040 DDV	
4000 type		ETGA0520CBM	TW20-100	· •	BHA0620	IVINDU410	PN1019-DRV	
Storm-Couple	3000 type	FTNA0513	-	TW15S	-	-	-	

## E Technical Information for Couple Mill

### Application range of high feed cutters for cast iron



### Recommended cutting condition

Cube Mill		Gray ca	st iron	Ductile cast iron		
		vc (m/min)	fz (mm/t)	vc (m/min)	fz (mm/t)	
PVD	PC6510	150~300	0.08~0.18	100~200	0.08~0.18	
Uncoated	G10	90~120	0.05~0.18	60~130	0.05~0.18	

### Available arbors and adaptors

Designation			Available arbors and adaptors	
	Designation	Arbors	General arbor	Adaptor
CBMQ	3080R/L-00Z	BT□□-FMA25.4-□□	NT*□□(M/U)-FMA25.4-25	
(CBMF)	3100R/L-00Z	BT□□-FMA31.75-□□	NT*□□(M/U)-FMA31.75-□□	
(CBME)	3125R/L-00Z	BT□□-FMA38.1-□□	NT*□□(M/U)-FMA38.1-□□	
CBMC)	3160R/L-00Z	BT□□-FMA50.8-□□	NT*□□(M/U)-FMA50.8-□□	
CBMA)	3200R/L-00Z	BT□□-FMA47.625-□□	NT*□□(M/U)-FMA47.625-25, KCP-8***	
	3250R/L-00Z	BT□□-FMA47.625-□□	KNT*□□(M/U)-FMA47.625-25, KCP-8***	
	3315R/L-00Z		KCP-8*** (Centering Plug)	
	3200R/L2-00Z			APR200
	3250R/L2-00Z			APR250
	3315R/L2-00Z			APR315
	3355R/L2-00Z			APR355
	3400R/L2-00Z			APR400
	3450R/L2-00Z			APR450
SQN	3080R/L-00Z	BT□□-FMA25.4-□□	NT*□□(M/U)-FMA25.4-25	
SFN)	3100R/L-00Z	BT□□-FMA31.75-□□	NT*□□(M/U)-FMA31.75-□□	
SEN)	3125R/L-00Z	BT□□-FMA38.1-□□	NT*□□(M/U)-FMA38.1-□□	
SAN)	3160R/L-00Z	BT□□-FMA50.8-□□	NT*□□(M/U)-FMA50.8-□□	
	3200R/L-00Z	BT□□-FMA47.625-□□	NT*□□(M/U)-FMA47.625-25, KCP-8***	
	3250R/L-00Z	BT□□-FMA47.625-□□	NT*□□(M/U)-FMA47.625-25, KCP-8***	
	3315R/L-00Z		KCP-8*** (Centering Plug)	
	3200R/L2-00Z			APR200
	3250R/L2-00Z			APR250
	3315R/L2-00Z			APR315
	3355R/L2-00Z			APR355
	3400R/L2-00Z			APR400
	3450R/L2-00Z			APR450



## Optimal cutter for steel and cast iron machining with easily adjustable run-out

## **Shave Mill**

- Adjustable Range (Adjustable range: 0.1 mm, Adjustable allowance: within 2 μm)
- Wiper crown type 8-cornered insert reduces machining cost and realizes excellent surface roughness
- Grades with high toughness and wear resistance ensures long tool life
- The cBN grade achieves superior surface finish

### Code system

· Insert




■ cBN

SNEU1204-TBW


T: Nagaland B: cBN

W: Wiper

### Cutter



### Features






## 3-face constrained clamping

### Adjustment

- Adjustable range: 0.1 mm
- Adjustability: below 2 μ
- Operation: easy and simple

### **Technical Information for Shave Mill**

### Features of insert






### Recommended cutting condition

Workpiece		Grades						
workpiece	vc (m/min)	fz (mm/t)	mm/t) ap (mm)					
Р	160~270	0.05~0.2	~0.5	PC3700				
К	140~230 600~1000	0.05~0.3 0.05~0.2	~0.5 ~0.5	PC6510 DBN920				

### Application example

■Workpiece Cylinder head (facing) **■**Cutting vc = 200, fz = 0.15, ap = 0.5, dryconditions ■ Tools Cutter SVMM4250R Insert PC6510 SNEU120420-MF

■ Workpiece FC25 (HB250) Cylinder head (facing) **■**Cutting vc = 700, fz = 0.1, ap = 0.5, dryconditions ■ Tools Cutter SVMM4160R



### · Results

	Tool life	Surface finish	Machinability
Shave Mill	250 pcs	$Rz = 3\mu$	High
Competitor	180 pcs	Rz = 3.5μ	Normal

Insert DBN920 SNEU1204-cBN

· KORLOY's Shave Mills ensure twice the machinability, adjustability, and surface roughness than competitor's, along with twice the tool life.


Better tool life with special grade which has both toughness and wear resistance

## **Shave Mill-Ultra**


- Superior surface roughness for this Finishing cutter when applied to heavy work pieces
- Easy to handle and good rigidity with simple screw on system
- Superior surface finishes due to the wiper crown cutting-edge
- Better tool life with special grade which has both toughness and wear resistance
- Two different types: economical normal type and adjustable run-out type 'B'

### Code system


· Insert



Cutter




### Features









· Range: 1.0 mm **Adjustable Range** · Allowance: Within 2 µ


### Recommended cutting condition


Mouleniaga		Cutting condition	Tooth	Grades		
Workpiece	vc (m/min)	fz (mm/t)	ap (mm)	100111	Grades	
	160~270	0.05~0.20	~0.50	Full use	D00700	
P	160~270	2~5	~0.03	1 use	PC3700	
	140~230	0.05~0.20	~0.50	Full use	DOCE40	
k	140~230	2~5	~0.03	1 use	PC6510	



## Inch

### Actual designations of milling cutter






Ø177.8

ØD

### Inch type


	Dimensions (mm)								Fig	Available arbors
ØD	Ød	а	b	E	F	ØD1	Ød1	Ød2	Fig.	Available arbors
40	16	8.4	5.6	18	40	34	9	14	1	FMC16, SMA16
50	22	10.4	6.3	20	40	42	11	18	1	FMC22
63	22	10.4	6.3	20	40	49	11	18	1	FMC22
80	25.4	9.5	6	25	50	57	14	20	1	FMA25.4
100	31.75	12.7	8	32	50	67	-	45	2	FMA31.75, SMB31.75
125	38.1	15.9	10	38	63	87	-	56	2	FMA38.1
160	50.8	19	11	38	63	107	-	-	2	FMA50.8
200	47.625	25.4	14	38	63	130	-	-	3	FMA47.625
250	47.625	25.4	14	38	63	180	-	-	3	FMA47.625
315	47.625	25.4	14	38	63	240	-	-	4	-

### Wrench bolt



Designation	ØD	S	K	L	M	Cutter size
SB0825	13	6	8	25	M08×1.25	Ø40
SB1025	16	8	10	25	M10×1.50	Ø50, Ø63
SB1035	16	8	10	35	M10×1.50	Ø50, Ø63 (HRM)
SB1230	18	10	12	30	M12×1.75	Ø80
SB1630	24	14	16	30	M16×2.0	Ø100
SB1645	24	14	16	45	M16×2.0	Ø80, Ø100 (HRM)
SB2040	30	17	20	40	M20×2.5	Ø125

### Clamp bolt





Designation		D	Cutter size				
Designation	D	L	K	S	h	d	Cutter size
M8×1.25	20	20	7	6	-	-	Ø40
M10×1.5	28	24	9	8	-	-	Ø50, Ø63
M12×1.75	33	28	10	10	2	23	Ø80
M16×2	40	32	10	14	5	23	Ø100
M20×2.5	50	40	14	17	5	27	Ø125
M24×3	64	46	14	19	9	37	Ø160



## **Metric - ISO6462, DIN138**

### Clamping part of milling cutter






ØD

### Metric type


		Fig.	Available arbors							
ØD	Ød	а	b	Е	F	ØD1	Ød1	Ød2	rig.	Available arbors
40	16	8.4	5.6	18	40	34	9	14	1	FMC16, SMA16
50	22	10.4	6.3	20	40	42	11	18	1	FMC22
63	22	10.4	6.3	20	40	49	11	18	1	FMC22
80	27	12.4	7	22	50	57	14	20	1	FMC27
100	32	14.4	8	28	50	67	-	45	2	FMC32
125	40	16.4	9	32	63	87	-	56	2	FMB40
160	40	16.4	9	32	63	107	-	-	2	FMB40
200	60	25.7	14	38	63	130	-	-	3	FMB60
250	60	25.7	14	38	63	180	-	-	3	FMB60
315	60	25.7	14	38	63	240	-	-	4	-

### Wrench bolt



Designation	ØD	S	K	L	M	Cutter size
SB0825	13	6	8	25	M08 × 1.25	Ø40
SB1025	16	8	10	25	M10 × 1.50	Ø50, Ø63
SB1035	16	8	10	35	M10 × 1.50	Ø50, Ø63 (HRM)
SB1230	18	10	12	30	M12 × 1.75	Ø80
SB1245	18	10	12	45	M12 × 1.75	Ø80 (HRM)
SB1630	24	14	16	30	M16 × 2.0	Ø100
SB1645	24	14	16	45	M16 × 2.0	Ø100 (HRM)
SB2040	30	17	20	40	M20 × 2.5	Ø125

### Clamp bolt




Decimation		D	Cutter size				
Designation	D	L	K	S	h	d	Cutter size
M12 × 1.75	33	28	10	10	2	23	Ø80
M16 × 2	40	32	10	14	5	23	Ø100
M20 × 2.5	50	40	14	17	5	27	Ø125, Ø160



## E Actual Designations of Milling Cutter and Arbor

## Clamping part of milling cutter (Oil-hole)

### Clamping part of milling cutter




### Inch type

		Available aubore							
ØD	Ød	а	b	E	F	ØD1	Ød1	Ød2	Available arbors
40	16	8.4	5.6	19	40	34	9	14	FMC16, SMA16
50	22	10.4	6.3	21	40	42	11	18	FMC22
63	22	10.4	6.3	21	40	49	11	18	FMC22
80	25.4	9.5	6	24	50	57	14	20	FMA25.4, FMB25.4
100	31.75	12.7	8	32	63	67	18	26	FMA31.75, SMB31.75
125	38.1	15.9	10	35	63	87	22	32	FMA38.1, FMB38.1, FMC38.1

### Metric type

		Available arbors										
ØD	Ød	а	b	E	F	ØD1	Ød1	Ød2	Available arbors			
40	16	8.4	5.6	19	40	34	9	14	FMC16, SMA16			
50	22	10.4	6.3	21	40	42	11	18	FMC22			
63	22	10.4	6.3	21	40	49	11	18	FMC22			
80	27	12.4	7.0	23	50	57	14	20	FMC27			
100	32	14.4	8.0	25	50	67	18	26	FMC32			
125	40	16.4	9.0	29	63	87	22	32	FMB40/FMC40			

### Wrench bolt



Designation	ØD	S	К	L	М	Cutter size
CB0825	13	6	8	25	M08×1.25	Ø40
CB1025	16	8	10	25	M10×1.50	Ø50, Ø63
CB1035	16	8	10	35	M10×1.50	Ø50, Ø63 (HRM)
CB1230	18	10	12	30	M12×1.75	Ø80
CB1245	18	10	12	45	M12×1.75	Ø80 (HRM)
CB1630	24	14	16	30	M16×2.0	Ø100
CB1645	24	14	16	45	M16×2.0	Ø100 (HRM)
CB2040	30	17	20	40	M20×2.5	Ø125



### Gear cutter applicable example

### Applicable example-external tooth gear

### Finishing: M20



- Cutter Dia: Ø400
  - Tooth No: 20 tooth
- External tooth gear: Formal cutter for gear processing which can be expected to KS 4 level accuracy
- Cutter can simultaneously chamfer while milling



M20XZ130-EX

### Semi-finishing



- Cutter Dia: Ø280
- Tooth No: 48 tooth
- Designed for processing of external gear involute curve line shape
- Possible to work for gear root portion R with optimal insert R design



M20-M22-ROU

### Roughing



- Cutter Dia: Ø560
- Tooth No: 140 tooth
- High feed rate with low cutting resistance due to V shape insert setting design







LNE333-02

-02-1 LNE434-02-1

1 KEL1906-C0.6-MF

### Applicable example-internal tooth gear

### Finishing: M16



■ Cutter Dia: Ø400

accuracy

- Tooth No: 20 tooth
- Internal tooth gear: Formal cutter for gear processing which can be expected to KS 4 level
- Cutter can simultaneously chamfer while milling



M16XZ130

### Semi-finishing



- Cutter Dia: Ø280
- Tooth No: 48 tooth
- The semi-finishing cutter was designed for processing of external gear involute curb line shape.



M16-M18-ROU



LNE433-R60

### Roughing



- Cutter Dia: Ø560
- Tooth No: 40 tooth
- Possible to use for gear processing of all module due to step type of insert setting design



KEL1906-C0.6-MF



IF LNE434-02-1

### Gear cutter machining example



- Machine
- Gleason-PFAUTER CNC Hobbing Machine (Power: 52kW)
- Cutting condition
- vc = 119.98 m/min (n = 86.8 rpm) fz = 0.518 mm/t (vf = 450 mm/min) ae = 36 mmDry
- Tools
  M16-PT-RACK-KOR03 (Ø440xW90)
- Semi-finishing cutter (low cut, low resistance)






- Machine
  - KARATS (30kw)
- Cutting condition
- vc = 150 m/min, n = 119 rpm fz = 0.09 mm/t, vf = 81.6 mm/min ae = 45 mm
- Dry
- Tools
- M24 Semi-finishing External type Applicable Insert M40-ROU (Main), KEL150708-MX (Flank)


## **E** Gear Cutter Table

Туре	Cutter shape	Cutting-edge shape	Туре	Feature
Roughing				Working for big sized gear tooth     Low cutting resistance with step type insert setting
Roug			V shape type	Low cutting resistance with V shape cutting insert setting     Optimal cutting-edge line setting according to Rach type & cutting-edge shape
			Low cutting resistance type	4-Corner insert on Root portion     3D chip breaker shape on flank     Optimal cutting-edge line setting for low cutting resistance
Semi-finishing			External gear high rigidity type	Optimal R type insert setting on Root portion Superior Semi-finishing cutting with high rigidity shape of cutter & insert
			Internal gear high rigidity type	Exclusive semi-finishing Internal Gear insert     Optimal cutting-edge line setting with Internal tooth shape
			External gear	Concave shape of cutting-edge line according to external gear type  Optimal cutting insert setting design according to a customer conditions
Finishing			Internal gear	2-corner insert setting on right & left side and chamfering insert setting     Adjustable chamfering cartridge use for chamfering control
			2 STEP type	Exclusive insert for machining the root part     4-cornered insert

# **Gear Roughing Cutter (Step type)**









(mm)

m	©	ØD	Ad	Ød	ØD1	а	е	F
	96	450	90	100	180	25	14	140
30	108	500	90	100	180	25	14	140
	120	560	90	120	220	40	32	160
	112	450	105	100	180	25	14	140
40	126	500	105	100	180	25	14	140
	140	560	105	120	220	40	32	160
50	160	560	119	120	220	40	32	160

### Available inserts

(mm)


				Coa	ited		Unco	ated		Dime	nsion	IS		
Picture		Designation	NC5330	PC9530	PC3500	PC5300	H04	G10	ı	d	t	<b>d</b> 1	С	Configuration
	LNE	434-02-1			0	0			19.05	14.29	6.35	5.4	0.6	
Reinforced cutting-edge														C C
	KEL	1906-C0.6-MF			0	0			19.05	14.29	6.35	5.4	0.6	
		190610-MR			0	0			19.05	14.29	6.35	5.4	-	d
Low cutting resistance														


©: 1 st Rec o: 2 nd Rec



# **Gear Roughing Cutter (V shape type)**









								(mm)
m	Туре	©	ØD	Ød	ØD1	а	е	F
20	rack	48	280	80	135	25	18	95
22	rack	48	280	80	135	25	18	95
24	rack	48	320	80	145	25	18	105
26	rack	60	320	80	145	25	18	105
28	rack	96	400	100	180	25	24	130
30	rack	96	400	100	180	25	24	130
32	rack	96	400	100	180	25	24	130
34	rack	112	400	100	180	25	24	130
36	rack	112	450	100	180	25	24	130
38	rack	112	450	100	180	25	24	130
40	rack	128	450	100	180	25	24	160
42	rack	128	450	100	180	25	24	160
44	rack	128	560	120	220	32	32	160
46	rack	144	560	120	220	32	32	160
48	rack	144	560	120	220	32	32	160
50	rack	144	560	120	220	32	32	160


### Available inserts


(mm

															()
				Coa	ated		Unco	oated		Dime	ensior	าร			
Picture		esignation	NC5330	PC9530	PC3500	PC5300	된	G10	ı	d	t	d <sub>1</sub>	С	Configura	tion
Reinforced cutting-edge	LNE	434-02-1			0	©		-	19.05	14.29	6.35	5.4	0.6		
Low cutting	LNE	1906-C0.6-MF 190610-MR			0	0			19.05 19.05	14.29 14.29		5.4	0.6	-	. dı
Reinforced cutting-edge	KEL	333-02-1			0	0			14.3	12.7	6.35	5.8	0.8	d d	<u>t</u>
1	CNHQ	1005-C0.5							10	10	5.4	-	-	80 1	t

**Gear Semi-finishing Cutter** (Low cutting resistance type)










								(mm)
m	No.of teeth	<b>(</b>	ØD	Ød	ØD1	а	е	F
6	30, 60, 120	18	250	60	100	25	18	70
8	30, 60, 120	18	250	60	100	25	18	80
10	30, 60, 120	24	250	60	100	25	18	80
12	30, 60, 120	24	250	60	100	25	18	90
14	30, 60, 120	24	280	80	135	25	24	95
16	30, 60, 120	32	280	80	135	25	24	100
18	30, 60, 120	32	320	80	145	25	24	105
20	30, 60, 120	64	400	100	180	25	24	110
22	30, 60, 120	64	400	100	180	25	24	110
24	30, 60, 120	64	400	100	180	25	24	120

### Available inserts

(mm)

				Coa	ited		Unco	pated		Diı	nensio	ns			(11111)
Picture	De	esignation	NC5330	PC9530	PC3500	PC5300	된	G10	ı	d	t	<b>d</b> 1	С	Configur	ation
		M6-2ST			0	0			19.05	11.6	3.8	4.4	2.25		
6		M8-2ST			0	0			19.05	11.6	4	4.4	3		
		M10-2ST			0	0			19.05	11.6	4.76	4.4	3.75		R
		M12-2ST			0	0			19.05	14.3	6.35	5.5	4.5		$\sum$
6		M14-2ST			0	0			25.4	14.3	6.35	5.5	5.25		dı
		M16-2ST			0	0			31.8	14.3	7.14	5.5	6		——————————————————————————————————————
		M18-2ST			0	0			31.8	14.3	7.14	5.5	6.75		
0		M20-2ST			0	0			31.8	14.3	9.52	5.5	7.5	d	
		M22-2ST			0	0			31.8	14.3	9.52	5.5	8.25		
		M24-2ST			0	0			31.8	14.3	9.52	5.5	9		
	KEC	120606-MX			0	0			12	12.7	6.35	4.5	-		
		150708-MX			0	0			15.15	15	7.6	5.8	-		
														800	d t




©: 1<sup>st</sup> Rec ○: 2 <sup>nd</sup> Rec



# Gear Semi-finishing Cutter (High rigid edge type, External gear)







								(mm)
m	No.of teeth	<b>(</b>	ØD	Ød	ØD1	а	е	F
12	30, 60, 120	24	250	60	100	25	14	70
14	30, 60, 120	36	250	60	100	25	14	80
16	30, 60, 120	36	250	60	100	25	14	80
18	30, 60, 120	36	250	60	100	25	14	90
20	30, 60, 120	48	280	80	135	25	18	95
22	30, 60, 120	48	280	80	135	25	18	100
24	30, 60, 120	48	320	80	145	25	18	105
26	30, 60, 120	72	400	100	180	25	24	110
28	30, 60, 120	72	400	100	180	25	24	110
30	30, 60, 120	72	400	100	180	25	24	120
32	30, 60, 120	84	400	100	180	25	24	130
34	30, 60, 120	84	400	100	180	25	24	130

### Available inserts

(mm)

			Coa	ited		Uncoa	ated			Dimer	sions				(****)
Picture	Designation	NC5330	PC9530	PC3500	PC5300	된	G10	ı	d	t	d <sub>1</sub>	R	С	Configura	ation
	M8-ROU			0	0			15.875	11	4.76	4.6	4.6	-		
	M12-M14-ROU			0	0			19.05	14.29	6.35	5.4	5.4	-		
	M16-M18-ROU			0	0			19.05	14.29	7	5.4	5.4	-		
	M20-M22-ROU			0	0			19.05	14.29	7.94	5.4	5.4	-		R
	M40-ROU			0	0			25.4	14.29	9.52	5.4	5.4	-	1	
														d	-t-
	LNE 434-02-1			0	0			19.05	14.29	6.35	5.4	-	0.6		
6															C C
	KEL 1906-C0.6-MF			0	0			19.05	14.29	6.35	5.4	-	0.6		
6	190610-MR			0	0			19.05	14.29	6.35	5.4		-	1	+
														<u>d</u>	<del>  -   -  </del>





<sup>\*</sup>The above specification is subject to change according to customer related condition & Korloy technical condition

## **Gear Semi-finishing Cutter** (High rigid edge type, Internal gear)









(mm	

m	No.of teeth	<b>(</b>	ØD	Ød	ØD1	а	е	F
12	30, 60, 120	24	250	60	100	25	14	70
14	30, 60, 120	36	250	60	100	25	14	80
16	30, 60, 120	36	250	60	100	25	14	80
18	30, 60, 120	36	250	60	100	25	14	90
20	30, 60, 120	48	280	80	135	25	18	95
22	30, 60, 120	48	280	80	135	25	18	100
24	30, 60, 120	48	320	80	145	25	18	105
26	30, 60, 120	72	400	100	180	25	24	110
28	30, 60, 120	72	400	100	180	25	24	110
30	30, 60, 120	72	400	100	180	25	24	120
32	30, 60, 120	84	400	100	180	25	24	130
34	30, 60, 120	84	400	100	180	25	24	130

### Available inserts

				Coa	ted		Unco	oated		Di	imensior	าร			
Picture		Designation	NC5330	PC9530	PC3500	PC5300	H01	G10	I	d	t	d <sub>1</sub>	С	Configura	ation
		M8-ROU			0	0			15.875	11	4.76	4.6	2		
		M12-M14-ROU			0	0			19.05	14.29	6.35	5.4	3		
		M16-M18-ROU			0	0			19.05	14.29	7	5.4	5		
		M20-M22-ROU			0	0			19.05	14.29	7.94	5.4	7		R
6		M40-ROU			0	0			25.4	14.29	9.52	5.4	10		
															_t_
	LNE	433-R80			0	0			19.05	14.29	5.56	5.4	2.5		
6														d	R80 du

<sup>\*</sup> The above specification is subject to change according to customer related condition & Korloy technical condition


⊚: 1st Rec o: 2 nd Rec




# **Gear Finishing Cutter** (1 Step type, External gear)









m	©	ØD	Ød	ØD <sub>1</sub>	а	F
6	20	400	80	155	25	90
8	20	400	80	155	25	90
10	20	400	80	155	25	90
12	20	400	80	155	25	90
14	20	400	80	155	25	90
16	20	400	80	155	25	90
18	20	400	80	155	25	90
20	20	400	80	155	25	90
22	20	400	80	155	25	90
24	20	400	80	155	25	90

### Available inserts


mm)


				Coa	ited		Unco	oated		Di	mensio	าร			
Picture	Des	signation	NC5330	PC9530	PC3500	PC5300	H01	G10	ı	d	t	d <sub>1</sub>	R	Configura	ation
		M6			0	0			19	14.3	5	5.5	2.25		
		M8			0	0			27	14.3	5.4	5.5	3		
		M10			0	0			29	14.3	6.35	5.5	3.75		R
		M12			0	0			33	14.3	6.35	5.5	4.5	<b> </b>	
66		M14			0	0			39	14.3	6.35	5.5	5.25	│ <del> </del> -�+.	<del>-</del> d
		M16			0	0			43	14.3	7.94	5.5	6		<u> </u>
		M18			0	0			50	14.3	7.94	5.5	6.75		
		M20			0	0			54	14.3	9.53	5.5	7.5	d d	+
		M22			0	0			57	14.3	9.53	5.5	8.25	<del>  • • •  </del>	<del></del>
		M24			0	0			64	14.3	9.53	5.5	9		
	SNEQ	1507-C0.8			0	0			15.875	15.875	7.94	-	-		
6														d	d



# Gear Finishing Cutter (1 Step type, Internal gear)









(mm)

m	<b>©</b>	ØD	Ød	ØD <sub>1</sub>	a	F
6	20	400	80	155	25	90
8	20	400	80	155	25	90
10	20	400	80	155	25	90
12	20	400	80	155	25	90
14	20	400	80	155	25	90
16	20	400	80	155	25	90
18	20	400	80	155	25	90
20	20	400	80	155	25	90
22	20	400	80	155	25	90
24	20	400	80	155	25	90

### Available inserts

(mm)

				Coa	ated		Unco	ated		Di	mensior	าร			
Picture	Desi	ignation	NC5330	PC9530	PC3500	PC5300	H01	G10	I	d	t	d <sub>1</sub>	R	Configura	ation
		M6			0	0			19	14.3	5	5.5	2.25		
		M8			0	0			27	14.3	5.4	5.5	3		
		M10			0	0			29	14.3	6.35	5.5	3.75		R
		M12			0	0			33	14.3	6.35	5.5	4.5		
6		M14			0	0			39	14.3	6.35	5.5	5.25		
		M16			0	0			43	14.3	7.94	5.5	6	<del>       </del>	d1
		M18			0	0			50	14.3	7.94	5.5	6.75		
		M20			0	0			54	14.3	9.53	5.5	7.5	d	+
		M22			0	0			57	14.3	9.53	5.5	8.25		<del></del>
		M24			0	0			64	14.3	9.53	5.5	9		
	SNEQ	1507-C0.8			0	0			15.875	15.875	7.94	-	-		
5														d d	dt

<sup>\*\*</sup> The above specification is subject to change according to customer related condition & Korloy technical condition


⊚: 1 st Rec o: 2 nd Rec






# Gear Finishing Cutter (2 Step type, Internal/Externa gear)









						(mm)
m	©	ØD	Ød	ØD <sub>1</sub>	a	F
6	24	400	80	155	25	90
8	24	400	80	155	25	90
10	24	400	80	155	25	90
12	24	400	80	155	25	90
14	24	400	80	155	25	90
16	24	400	80	155	25	90
18	24	400	80	155	25	90
20	24	400	80	155	25	90
22	24	400	80	155	25	90
24	24	400	80	155	25	90

### Available inserts


(mm)


				Coa	ated		Unco	ated		Di	imension	ıs			
Picture	Desi	ignation	NC5330	PC9530	PC3500	PC5300	H01	G10	ı	d	t	d <sub>1</sub>	R	Configura	tion
		M6		0		0			19	14.3	5	5.5	2.25		
		M8		0		0			27	14.3	5.4	5.5	3		
		M10		0		0			29	14.3	6.35	5.5	3.75		R
		M12		0		0			33	14.3	6.35	5.5	4.5		
6		M14		0		0			39	14.3	6.35	5.5	5.25		
		M16		0		0			43	14.3	7.94	5.5	6		
		M18		0		0			50	14.3	7.94	5.5	6.75		
		M20		0		0			54	14.3	9.53	5.5	7.5	_ d _	t
		M22		0		0			57	14.3	9.53	5.5	8.25		H <del>air</del>
		M24		0		0			64	14.3	9.53	5.5	9		
	SNEQ	1507-C0.8		0		0			15.875	15.875	7.94	-	-		
6														d d	- di
		M6-2ST							19.05	11.6	3.8	4.4	2.25		
		M8-2ST							19.05	11.6	4	4.4	3		
		M10-2ST							19.05	11.6	4.76	4.4	3.75		R
		M12-2ST							19.05	14.3	6.35	5.5	4.5	1	
6		M14-2ST							25.4	14.3	6.35	5.5	5.25		dı.
(1)		M16-2ST							31.8	14.3	7.14	5.5	6		
		M18-2ST							31.8	14.3	7.14	5.5	6.75	d	_t_
		M20-2ST							31.8	14.3	9.52	5.5	7.5	<del>  -  </del>	
		M22-2ST							31.8	14.3	9.52	5.5	8.25		
		M24-2ST							31.8	14.3	9.52	5.5	9		



<sup>\*</sup>The above specification is subject to change according to customer related condition & Korloy technical condition

### • Gear cutter order form






Cutter type
Roughing       Semi-finishing       Finishing         Step       Low cutting resistance       1 Step         V shape       High rigid edge       2 Step
■ Stock for finishing (one side) (mm):
■ Outside diameter ØD (mm):
■ Bore diameter Ød (mm):
■ Hub diameter Ød1 (mm):
■ Cutter width W (mm):
■ Radial keyway w1 (mm):
■ Radial keyway w₂ (mm):
Axial keyway t1 (mm):
Axial keyway t2 (mm):

### Involute gear data

☐ External gear ☐ Internal gear	□ Rack gear
■ Module M:	■ Root diameter df (mm):
■ No.of teeth Z (mm):	■ Root radius ρfp (mm)
■ Pressure angle α (°):	■ Base tangent length Wk (mm)
■ Helix angle β (°):	■ No. of measuring teeth K:
■ Addendum modification coefficient x:	■ Dimensions/Dimension over balls M <sub>d</sub> (mm):
■ Tip diameter da (mm):	■ Ball diameter D <sub>M</sub> (mm):
	■ Gear quality (DIN, JIS):




## **Indexable HOB**



(mm)

Gear module	ØD	ØDh	Ød	No.Segm. (Pitch)	Le	Segment insert	Total insert	γ (Lead Ang.)
	180	125	40	6	(113)	15	90	2.084
6	210	125	50	6	(113)	17	102	1.763
	240	160	60	6	(113)	19	114	1.528
	180	125	40	6	(132)	15	90	2.469
7	210	125	50	6	(132)	17	102	2.084
	240	160	60	6	(132)	19	114	1.803
	210	125	50	6	(151)	17	102	2.413
8	240	160	60	6	(151)	19	114	2.084
	270	180	80	6	(151)	21	126	1.834
	210	125	50	6	(169)	17	102	2.751
9	240	160	60	6	(169)	19	114	2.372
	270	180	80	6	(169)	21	126	2.084
	210	125	50	6	(189)	17	102	3.099
10	240	160	60	6	(189)	19	114	2.666
	270	180	80	6	(189)	21	126	2.339
	240	140	60	6	(226)	18	108	3.276
12	270	180	80	6	(226)	22	132	2.866
	350	215	80	6	(226)	26	156	2.149
	270	180	80	6	(264)	22	132	3.415
14	350	215	80	6	(264)	26	156	2.547
40	270	160	80	6	(302)	22	132	3.989
16	350	215	80	6	(302)	26	156	2.959
10	270	145	80	5	(283)	22	110	4.589
18	350	215	80	5	(283)	26	130	3.383
	350	215	80	5	(314)	26	130	3.823
20	450	265	100	5	(314)	34	170	2.866


### **○** Indexable HOB



### Tool SPEC.


- Outside diameter ØD (mm):
- Bore diameter Ød (mm):
- Hub diameter ØDh (mm):
- Hob length L (mm):
- Cutting length Le (mm):
- Spiral direction RH/LH:
- Quality class acc. to DIN 3968:

### Profile of hob [Module m6~]



- Module M:
- ■Addendum hkw (mm):
- Tooth thickness Sw (mm):
- Tooth depth hg (mm):

### Profile of roughing hob [Module m8~]



- Pressure angle  $\alpha_w$  (mm):
- Protuberance amount Ppr (mm):
- Protuberance angle α<sub>pr</sub> (mm):
- Tip radius 'h (mm):

# **DRILL**

Korloy drills provide a total solution for hole making, based on tooling know-how as well as extensive research and development for our tools.



#### **Technical Information for Drills**

F02 KORLOY DrillsF03 Available Insert

#### **Indexable Drills**

F75 Technical Information for WPDC

F78 Center Drill F79 WPDC

### **Indexable Drills**

F05 Technical Information for King Drill
F11 King Drill

F20 Technical information of King Drill (for through coolant system with a lathe)

F21 King Drill
(for through coolant system with a lathe)

F24 Technical Information for King Drill (for large diameter drilling)

**F25** King Drill (for large diameter drilling)

F26 Technical Information for KED Plus Drill
F29 KED Plus Drill

F37 Technical Information for TPDC Plus Drill

F47 TPDC Plus Drill

F54 Technical Information for TPDB Plus Drill

F57 TPDB Plus Drill

**F63** Technical Information for TPDB-F

F66 TPDB-F

F68 Technical Information for TPDB-H

F71 TPDB-H

#### Reamer

F82 Technical Information for Indexable ReamerF86 Indexable Reamer

# F KORLOY Drills

Туре	Designat	ion	Shape	Drills dia.	Aspect ratio	Page
	King Drill	K□D	Available insert: SP□T, XO□T	Ø12.0~Ø60.5	2D~5D	F11~F19
	King Drill HP	K□DHP	Available insert: SP□T, XO□T	Ø12.0~Ø60.5	2D~4D	F21~F23
	King Drill (for large diameter drilling)	K□D	Available insert: SPDT, XODT	Ø61.0~Ø100.0	2D~4D	F25
	KED Plus Drill @	E□D	Available insert: SP□T, XO□T	Ø12.0~Ø60.5	2D~5D	F29~F36
Indexable	TPDC Plus Drill	TPDX	Available insert: TPDDDDDXP	Ø8.0~Ø11.9	3D~8D	F50
Drills	II DOT IUS DIIII	TPDC	Available insert: TPDDDDDCD	Ø12.0~Ø30.9	1.5D~12D	F51~F53
		TPDB-P	Available insert: TPDDDB	Ø10.0~Ø32.9	3D~12D	F58~F62
	TPDB Plus Drill @	TPDB-F	Available insert: TPD□□□B-F	Ø14.0~Ø30.9	1.5D	F67
		TPDB-H	Available insert: TPD□□□B-H	Ø14.0~Ø30.9	3D~8D	F72~F74
	Indexable Drills & Drill with center	WPDC	Available insert: WC□T	Ø25.0~Ø80.0	5D~8D	F79~F81
Reamer	Indexable Reamer	IRT	Available Insert: RI	Ø10.0~Ø31.0	3D~5D	F86
		IRB	Available Insert: RI	Ø10.0~Ø31.0	3D~5D	F87

### Available insert

					Co	ated				Uncoated		Dime	nsions	(mm)			
Picture	Designation	NC5330	NCM535	PC3700	PC6510	PC9530	PC9540	PC5335	PC5300	H01	I	d	t	r	d1	Configuration	Page
	040204-PD	•	•	•	•		•		•		4.7	-	2.4	0.4	2.3		
	050204-PD	•	•	•	•		•		•		5.1	-	2.4	0.4	2.3		
[ Peripheral ]	060205-PD	•	•	•	•		•		•		6.2	-	2.5	0.5	2.5		
SPMT-PD	07T208-PD	•	•	•	•		•		•		7.5	-	2.8	0.7	2.8	_ <u>r</u>	
SPW1-PD	090308-PD	•	•	•	•		•		•		9.2	-	3.3	0.8	3.4		F11~
	11T308-PD	•	•	•	•		•		•		11.0	-	4.0	0.8	4.0	d1	F36
	130410-PD	•	•	•	•		•		•		13.0		4.5	1.0	4.5	t	
Universal	15M510-PD	•	•	•	•		•		•		15.2		5.0	1.0	5.5	<del>  • • • • • • • • • • • • • • • • • •</del>	
	180510-PD	•	•	•	•		•		•		18.2		5.5	1.0	6.0		
	10001012		_		_				_								
	040204-PD						•		•		4.3	4.9	2.4	0.4	2.3		
	050204-PD						•		•		4.8	5.4	2.4	0.4	2.3		
[ Central ]	060204-PD						•		•		5.8	6.6	2.5	0.4	2.5		
	07T205-PD						•		•		6.9	7.8	2.8	0.4	2.8		
KOMT-PD	071205-PD 090305-PD						•		•		8.4	9.6	3.3	0.5	3.4		
									_							d1	F11~
	11T306-PD						•		•		10.0	11.4	4.0	0.6	4.0	l t	F36
	130406-PD						•		•		11.9	13.6	4.5	0.6	4.5		
Universal	15M508-PD						•		•		13.9	15.9	5.0	0.8	5.5		
	180508-PD						•		•		16.5	18.9	5.5	0.8	6.0		
	060205-LD							•			6.2	-	2.5	0.5	2.5		
[ Peripheral ]	07T208-LD							•			7.5	-	2.8	0.7	2.8		
[1 01.01.01.01.1]	090308-LD							•			9.2	-	3.3	0.8	3.4		
SPMT-LD	11T308-LD							•			11.0	-	4.0	8.0	4.0		
	130410-LD							•			13.0	-	4.5	1.0	4.5	dı	F11~
	15M510-LD							•			15.2	-	5.0	1.0	5.5		F36
	180510-LD							•			18.2	-	5.5	1.0	6.0		
Mild steel	000004 L D										5.0		0.5				
	060204-LD							•			5.8	6.6	2.5	0.4	2.5		
[ Central ]	07T205-LD							•			6.9	7.8	2.8	0.5	2.8		
	090305-LD							•			8.4	9.6	3.3	0.5	3.4	r	
XOMT-LD	11T306-LD							•			10.0	11.4	4.0	0.6	4.0		
	130406-LD							•			11.9	13.6	4.5	0.6	4.5	dı dı	F11~
	15M508-LD							•			13.9	15.9	5.0	0.8	5.5		F36
	180508-LD							•			16.5	18.9	5.5	0.8	6.0	-  -   -    -  -  -  -  -  -  -  -  -	
Mild steel																	
	040204-ND									•	4.7	-	2.4	0.4	2.3		
[ Peripheral ]	050204-ND									•	5.1	-	2.4	0.4	2.3		
[1 cripileral]	060205-ND									•	6.2	-	2.5	0.5	2.5		
SPET-ND	07T208-ND									•	7.5	-	2.8	0.7	2.8		
	090308-ND									•	9.2	-	3.3	0.8	3.4	Ødı	F11~
	11T308-ND									•	11.0	-	4.0	0.8	4.0		F36
	130410-ND									•	13.0	-	4.5	1.0	4.5	-   -      -	
A		1												1.0	5.5		
Al	15M510-ND									•	15.2	-	5.0	1.0	5.5		
Al	15M510-ND 180510-ND									•	15.2	-	5.5	1.0	6.0		

# Available Insert

### Available insert


					Coa	ited				Uncoated		Dime	nsions	(mm)			
Picture	Designation	NC5330	NCM535	PC3700	PC6510	PC9530	PC9540	PC5335	PC5300	H01	ı	d	t	r	d1	Configuration	Page
	040204-ND									•	4.3	4.9	2.4	0.4	2.3		
	050204-ND									•	4.8	5.4	2.4	0.4	2.3	-	
[ Central ]	060204-ND									•	5.8	6.6	2.5	0.4	2.5	-	
XOET-ND	07T205-ND									•	6.9	7.8	2.8	0.5	2.8		
AOL I-ND	090305-ND									•	8.4	9.6	3.3	0.5	3.4	d	F11~
	11T306-ND									•	10.0	11.4	4.0	0.6	4.0		F36
	130406-ND									•	11.9	13.6	4.5	0.6	4.5		
Al	15M508-ND									•	13.9	15.9	5.0	0.8	5.5		
	180508-ND									•	16.5	18.9	5.5	8.0	6.0		
	07T207-RD								•		6.9	7.8	2.8	0.7	2.8		
[ Central ]	090308-RD								•		8.4	9.6	3.3	0.8	3.4		
Lociniai	11T309-RD								•		10.0	11.4	4.0	0.9	4.0		
XOMT-RD	130410-RD								•		11.9	13.6	4.5	1.0	4.5		
new	15M511-RD								•		13.9	15.9	5.0	1.1	5.5	d dı	F11~
	180512-RD								•		16.5	18.9	5.5	1.2	6.0		F36
Rein fored cutting-edge																	
	030208-C20N							•			3.8	5.56	2.38	0.8	2.8		
	040208-C20N							•			4.3	6.35	2.38	0.8	3.0		
WCMT-	050308-C20N		•					•			5.4	7.94	3.18	0.8	3.4		
C20N	06T308-C20N		•					•			6.5	9.525	3.97	0.8	3.7	<u> </u>	
	080408-C20N							•			8.7	12.7	4.76	0.8	4.3		_
	080412-C20N		•					•			8.7	12.7	4.76	1.2	4.3	80 7	
	030204-C21N							•			3.8	5.56	2.38	0.4	2.55		
	040204-C21N							•			4.3	6.35	2.38	0.4	2.8	-	
	040208-C21N							•			4.3		2.38	0.8	2.8	-	
WCMT-	050308-C21N							•			5.4		3.18	0.8	3.4		
C21N	06T308-C21N							•			6.5	9.525		0.8	4.4	d d	E70
	080408-C21N							•			8.7		4.76	0.8	5.5	80 7	F79~ F81

•: Stock Item

### Optimized insert design for maximum drilling efficiency


## King Drill

### Code system



#### Features

- Optimized design of inserts for maximum drilling efficiency
- Excellent cutting performance and chip control due to the optimized geometry and chip breaker of both inserts, central & peripheral
- · Different inserts, optimized for the central and peripheral insert locations in order to maximize cutting tool life



### Features of chip breaker

Chip breaker	Р	D	L	D	N	D	RD
Features	- Universal - At medium speed	and medium feed	Superior chip of machining mile stainless steel     Light cutting (a speed and low	d steel and	Sharp cutting ealuminum mace     Insert surface I high quality res     E Class tolerar	hining ouffed for sult	Improved chipping resistance     Excellent performance in case of frequent fracture and chipping on the cutting edge
Insert	Peripheral insert	Central insert	Peripheral insert	Central insert	Peripheral insert	Central insert	Central insert
Shape						9	
Grades for workpiece	NC5330: P, M, K PC3700: P PC5300: P, M, K, S PC6510: K PC9540: P, M, S	PC5300: P, M, K, S PC9540: P, M, S	PC533	35: P, M	НО	1: N	PC5300: P, M, K, S

### Technical Information for King Drill

### Application examples

■ Use Track link bush

■ Workpiece SM45C

■ **Cutting** vc (m/min) = 120, fn (mm/rev) = 0.1

conditions Through coolant system

■ Tools Inserts SPMT07T208-PD (PC3700)


XOMT07T205-PD (PC5300)

Holder K5D20025-07

■ Machine Drilling machine

0





• Superior surface finish and chip evacuation

■ Use Track link bush

■ Workpiece SCM415H

■ Cutting Competitor: vc (m/min) = 125, fn (mm/rev) = 0.1 conditions King Drill: vc (m/min) = 140, fn (mm/rev) = 0.12

■ Tools Inserts SPMT090308-PD (PC3700)

XOMT090305-PD (PC5300)

Holder K3D27032-09

■ Machine MCT



#### ■ Test result



 Increased productivity due to higher capabilities for cutting conditions compared to the competitor


### Recommended cutting condition


				Insert	İ			Asp	ect ratio (L	(D) = 2D, 3D	), 4D		
	ISO	Maukaiaaa	Hardness	Chip	Gra	ade	vc (m/min)		Feed ra	te (mm/rev)	per drill d	ia. (mm)	
	150	Workpiece	(HB)	breaker	Central	Peripheral		Ø12~Ø16	Ø17~Ø23	Ø24~Ø29	Ø30~Ø42	Ø43~Ø60	Ø61~Ø100
				LD	PC5335	PC5335	120 (60~170)						
		Low carbon steel	80~180	PD/	PC5300	PC3700	150 (120~180)	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08
	Carbon steel			RD	FC3300	NC5330	180 (140~220)						
		High carbon	180~280	PD	PC5300	PC3700	120 (90~150)	0.04~0.10	0.04~0.12	0.05~0.16	0.06~0.16	0.06~0.18	0.06~0.18
		steel	100~200	רט	FC3300	NC5330	150 (110~190)	0.04~0.06	0.04~0.07	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08
P				LD	PC5335	PC5335	120 (60~160)	0.06~0.10	0.06~0.10	0.06~0.12	0.06~0.14	0.06~0.14	0.06~0.14
		Low alloy steel	140~260	PD	PC5300	PC3700	150 (120~170)	0.06~0.12	0.06~0.12	0.06~0.14	0.06~0.16	0.06~0.16	0.06~0.16
	Alloy	0.00		עץ	FC3300	NC5330	180 (140~210)	0.06~0.08	0.06~0.08	0.06~0.10	0.06~0.12	0.06~0.12	0.06~0.12
	steel	Low alloy heattreated steel	200~400	PD	PC5300	PC5300	100 (50~150)	0.04~0.10	0.06~0.10	0.06~0.12	0.06~0.14	0.06~0.14	0.06~0.14
	High alloy st	High alloy steel	260~320	PD	PC5300	PC3700	100 (50~160)	0.05~0.11	0.05~0.11	0.05~0.13	0.05~0.15	0.05~0.15	0.05~0.15
	<u> </u>	High alloy heattreated steel	300~450	PD	PC5300	PC5300	70 (30~120)	0.04~0.08	0.06~0.08	0.06~0.10	0.06~0.12	0.06~0.12	0.06~0.12
				LD	PC5335	PC5335	120 (80~140)	0.04~0.07	0.04~0.07	0.04~0.07	0.04~0.08	0.04~0.08	0.04~0.08
M	Stainless steel	Stainless steel	135-275	PD	PC5300	PC5300	130 (100~160)	0.04~0.07	0.04~0.07	0.04~0.07	0.04~0.08	0.04~0.08	0.04~0.08
				רם	PC9540	PC9540	90 (60~120)	0.04~0.07	0.04~0.07	0.04~0.07	0.04~0.08	0.04~0.08	0.04~0.08
K	Cast iron	Gray cast iron	150~230	PD	PC5300	PC6510	190 (150~250)	0.04~0.12	0.05~0.14	0.06~0.18	0.10~0.22	0.10~0.26	0.10~0.26
	Cast Iron	Ductile cast iron	150~230	PD	PC5300	PC6510	130 (100~160)	0.04~0.07	0.04~0.08	0.04~0.10	0.05~0.12	0.05~0.12	0.05~0.12
		Nii haat vaaistina allav	130~400	PD	PC5300	PC5300	50 (30~100)	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10
	Heat	Ni-heat resisting alloy	130~400	רם	PC9540	PC9540	40 (20~80)	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10
S	resisting	Ti heat registing allow	130~400	LD	PC5335	PC5335	60 (40~80)	0.04~0.08	0.04~0.10	0.06~0.12	0.06~0.14	0.06~0.16	0.06~0.16
	alloy	Ti-heat resisting alloy	130~400	PD	PC5300	PC5300	60 (40~80)	0.04~0.08	0.04~0.10	0.06~0.12	0.06~0.14	0.06~0.16	0.06~0.16
	High hardened stee	High hardened steel	over 400	PD	PC5300	PC5300	40 (20~80)	0.04~0.05	0.04~0.06	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08
, .	Ali maini	Aluminium	30~150	ND	H01	H01	300 (250~400)	0.05~0.14	0.06~0.16	0.10~0.20	0.10~0.22	0.12~0.25	0.12~0.25
N	Aluminium	Alloyed copper	150-160	ND	H01	H01	250 (200~300)	0.05~0.14	0.06~0.16	0.10~0.20	0.10~0.22	0.12~0.25	0.12~0.25

- The Max. feed of 5D holders is 70%~80% of the max. conditions of 2D/3D/4D holders
- $\cdot$  In interrupted machining part, reduce 30 $\sim$ 50% of feed from the above machining around interrupted part


### Required cutting power

- The graphs below show the cutting force required in drilling
- · Machining with the King Drill and a machine with high rigidity and power
- Workpiece SCM440 (240HB)
- Cutting vc (m/min) = 100, Through coolant system conditions






fn (mm/rev) = 0.13




### Cutting oil quantity

- Workpiece SCM440 (240HB)
- Cutting vc (m/min) = 100, Through coolant system conditions
- The data of the graph above could be changed depending on workpiece and cutting condition



### Drill tolerance and hole tolerance







(mm)

Dr	ill dia.	Ø12~Ø29	Ø30~Ø45	Ø46~Ø60.5
2D~3D	Drill tolerance (ØD)	0~-0.15	0~-0.15	0~-0.15
20~30	Hole tolerance	+0.2~-0.1	+0.25~-0.1	+0.28~-0.1
4D~5D	Drill tolerance (ØD)	0~-0.15	0~-0.15	0~-0.15
40~50	Hole tolerance	+0.25~-0.05	+0.3~-0.05	+0.33~-0.05

### Notice for setting the drill in the lathe








- Set the peripheral insert parallel to the X axis. (based on the side lock)
- If the machined core is 0.5 mm after machining 5 mm, that is the proper setting
- \*\* Please make sure that the location of the side lock could be different depending on manufacturers of machine



### **Technical Information for King Drill**

### Range of adjusting machining diameter in the lathe

- In machining in the lathe, the King Drill can extend and reduce the machining diameter by adjusting the x-axis. Please refer to the table showing the range of adjusting drilling diameter below
- The more the drilling diameter is extended or reduced, the more the drill loses drilling balance. In this case, reduce the feed or cutting speed in machining
- · Reducing the machining diameter excessively could damage the holder



(mm)

Drill dia. (Ø)	Range of adjusting diameter (Ø)	Drill dia. (Ø)	Range of adjusting diameter (Ø)	Drill dia. (Ø)	Range of adjusting diameter (Ø)	Drill dia. (Ø)	Range of adjusting diameter (Ø)
12.0	11.7~12.4	24.5	23.9~25.1	37.0	36.3~37.7	49.5	48.7~50.2
12.5	12.2~12.9	25.0	24.4~25.6	37.5	36.8~38.2	50.0	49.2~50.7
13.0	12.7~13.4	25.5	24.9~26.1	38.0	37.3~38.7	50.5	49.7~51.2
13.5	13.2~13.9	26.0	25.4~26.6	38.5	37.8~39.2	51.0	50.2~51.7
14.0	13.6~14.5	26.5	25.9~27.1	39.0	38.3~39.7	51.5	50.7~52.2
14.5	14.1~15.0	27.0	26.4~27.6	39.5	38.8~40.2	52.0	51.2~52.7
15.0	14.6~15.5	27.5	26.9~28.1	40.0	39.3~40.7	52.5	51.7~53.2
15.5	15.1~16.0	27.8	27.4~28.6	40.5	39.8~41.2	53.0	52.2~53.7
16.0	15.6~16.5	28.5	27.9~29.1	41.0	40.3~41.7	53.5	52.7~54.2
16.5	16.0~17.0	29.0	28.4~29.6	41.5	40.8~42.2	54.0	53.2~54.7
17.0	16.5~17.5	29.5	28.9~30.1	42.0	41.3~42.7	54.5	53.7~55.2
17.5	17.0~18.0	30.0	29.3~30.7	42.5	41.8~43.2	55.0	54.2~55.7
18.0	17.5~18.5	30.5	29.8~31.2	43.0	42.2~43.7	55.5	54.7~56.2
18.5	18.0~19.0	31.0	30.3~31.7	43.5	42.7~44.2	56.0	55.2~56.7
19.0	18.5~19.5	31.5	30.8~32.2	44.0	43.2~44.7	56.5	55.7~57.2
19.5	19.0~20.0	32.0	31.3~32.7	44.5	43.7~45.2	57.0	56.2~57.7
20.0	19.4~20.6	32.5	31.8~33.2	45.0	44.2~45.7	57.5	56.7~58.2
20.5	19.9~21.1	33.0	32.3~33.7	45.5	44.7~46.2	58.0	57.2~58.7
21.0	20.4~21.6	33.5	32.8~34.2	46.0	45.2~46.7	58.5	57.7~59.2
21.5	20.9~22.1	34.0	33.3~34.7	46.5	45.7~47.2	59.0	58.2~59.7
22.0	21.4~22.6	34.5	33.8~35.2	47.0	46.2~47.7	59.5	58.7~60.2
22.5	21.9~23.1	35.0	34.3~35.7	47.5	46.7~48.2	60.0	59.2~60.7
23.0	22.4~23.6	35.5	34.8~36.2	48.0	47.2~48.7	60.5	59.7~61.2
23.5	22.9~24.1	36.0	35.3~36.7	48.5	47.7~49.2		
24.0	23.4~24.6	36.5	35.8~37.2	49.0	48.2~49.7		

### Insert and parts

Drill dia. (mm)	Peripheral insert	Central insert	Screw	Wrench	Torque (N·m)
Ø12.0~Ø13.5	SP□T040204-□□	XO□T040204-□□	FTNA0204	TW06P	0.4
Ø13.6~Ø16.0	SP□T050204-□□	XO□T050204-□□	FTNA0204	TW06P	0.4
Ø16.1~Ø19.5	SP□T060205-□□	XO□T060204-□□	FTKA02206S	TW07P	0.8
Ø19.6~Ø23.5	SP□T07T208-□□	XO□T07T205-□□	FTKA02565	TW07S	0.8
Ø23.6~Ø29.5	SP□T090308-□□	XO□T090305-□□	FTKA0307	TW09S	1.2
Ø29.6~Ø35.5	SP□T11T308-□□	XO□T11T306-□□	FTKA03508	TW15S	3
Ø35.6~Ø42.5	SP□T130410-□□	XO□T130406-□□	FTKA0410	TW15S	3
Ø42.6~Ø50.5	SP□T15M510-□□	XO□T15M508-□□	FTNC04511	TW20S	5
Ø50.6~Ø60.5	SP□T180510-□□	XO□T180508-□□	FTNA0511	TW20-100	5

<sup>•</sup> In clamping an insert, please clean the tip seat and apply CASMOLY1000 on the screw


<sup>•</sup> Please make sure to use a Korloy-produced wrench and screw only



### Sking Drill - for machining a tap foundation hole

• There are two types of specifications of tap, metric and inch. The King Drill is available for machining both thru tap and blind tap







(mm)


Tap type	Thread	ØD	Designation	Reference
	M14 x 2.0	12.0	K3D12020-04	F13
	M16 x 2.0	14.0	K3D14020-05	F13
	M18 x 2.5	15.5	K3D15520-05	F13
	M20 x 2.5	17.5	K3D17525-06	F13
	M22 x 2.5	19.5	K3D19525-06	F13
Mertic	M24 x 3.0	21.0	K3D21025-07	F13
Wertic	M27 x 3.0	24.0	K3D24032-09	F13
	M30 x 3.5	26.5	K3D26532-09	F13
	M33 x 4.0	29.0	K3D29032-09	F13
	M36 x 4.0	32.0	K3D30032-11	F14
	M39 x 4.0	35.0	K3D35032-11	F14
	M42 x 4.5	37.5	K3D37540-13	F14
	9/16-12 UNC	12.2	K3D12220-04	F13
	5/8-11 UNC	13.5	K3D13520-04	F13
	3/4-10 UNC	16.5	K3D16525-06	F13
Inch	7/8-9 UNC	19.5	K3D19525-06	F13
	9/16-18 UNF	12.9	K3D12920-04	F13
	5/8-18 UNF	14.5	K3D14520-05	F13
	3/4-16 UNF	17.5	K3D17525-06	F13


### **Technical Information for King Drill**


### Special drill order form
























#### ■ Note

- · Currently using tool:
- · Current cutting condition
- RPM or vc (m/min):
- vf (mm/min) or fn (mm/rev):
- Depth of cut (mm):

- Standard of measuring tool life:
- · Currently using machine
  - Machining center:
  - General lathe:
  - CNC lathe:

King Drill (2D)







										1)
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Screw	Wrench
2D	12020-04	12.0	20	25	27	50	91			
	12520-04	12.5	20	25	27	50	91	SP□T040204-□□	ETNIA 000 4	TIMOOD
	13020-04	13.0	20	25	29	50	93	XO□T040204-□□	FTNA0204	TW06P
	13520-04	13.5	20	25	29	50	93			
	14020-05	14.0	20	25	31	50	96			
	14520-05	14.5	20	25	31	50	96	0007070004		
	15020-05	15.0	20	25	33	50	99	SP□T050204-□□	FTNA0204	TW06P
	15520-05	15.5	20	25	33	50	99	XO□T050204-□□		
	16020-05	16.0	20	25	35	50	101	-		
	16525-06	16.5	25	34	35	56	107			
	17025-06	17.0	25	34	37	56	109			
	17525-06	17.5	25	34	37	56	109			
	18025-06	18.0	25	34	39	56	112	SP□T060205-□□	FTKA02206S	TW07P
	18525-06	18.5	25	34	39	56	112	XO□T060204-□□	. 110.022000	. ****/
	19025-06	19.0	25	34	41	56	114			
	19525-06	19.5	25	34	41	56	114			
	20025-07	20.0	25	34	43	56	118			
	20525-07	20.5	25	34	43	56	118			
	21025-07	21.0	25	34	45	56	120			
	21525-07	21.0	25	34	45	56	120	   SP□T07T208-□□	FTKA02565	TW07S
	22025-07		25		45		120			
	22525-07	22.0	25	34	47	56	122	XO□T07T205-□□		
		22.5		34		56				
	23025-07	23.0	25	34	49	56	126			
	23525-07	23.5	25	34	49	56	126			
	24032-09	24.0	32	44	51	60	133			
	24532-09	24.5	32	44	51	60	133			
	25032-09	25.0	32	44	53	60	135			
	25532-09	25.5	32	44	53	60	135			
	26032-09	26.0	32	44	55	60	137	000700000		
	26532-09	26.5	32	44	55	60	137	SP□T090308-□□	FTKA0307	TW09S
	27032-09	27.0	32	44	57	60	140	XO□T090305-□□		
	27532-09	27.5	32	44	57	60	140			
	28032-09	28.0	32	44	59	60	143			
	28532-09	28.5	32	44	59	60	143			
	29032-09	29.0	32	44	61	60	145			
	29532-09	29.5	32	44	61	60	145			
	30032-11	30.0	32	44	63	60	150			
	30532-11	30.5	32	44	63	60	150			
	31032-11	31.0	32	44	65	60	152			
	31532-11	31.5	32	44	65	60	152			
	32032-11	32.0	32	44	67	60	154			
	32532-11	32.5	32	44	67	60	154	SP□T11T308-□□	FTKA03508	TW15S
	33032-11	33.0	32	44	69	60		XO□T11T306-□□	1 11/403300	144132
	33532-11	33.5	32	44	69	60	157			
	34032-11	34.0	32	44	71	60	159			
	34532-11	34.5	32	44	71	60	159	1		
	35032-11	35.0	32	44	73	60	161	1		
	35532-11	35.5	32	44	73	60	161	1		


<sup>◆</sup> Applicable inserts F03~04

# King Drill

King Drill (2D)










<sup>→</sup> Applicable inserts F03~04

King Drill (3D)









										(r
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Screw	Wrench
3D	12020-04*	12.0	20	25	39	50	103			
	12220-04	12.2	20	25	39	50	103			
	12520-04	12.5	20	25	39	50	103	SP□T040204-□□	ETNIA 0004	TW06P
	12920-04	12.9	20	25	42	50	106	XO□T040204-□□	FTNA0204	
	13020-04	13.0	20	25	42	50	106			
	13520-04	13.5	20	25	42	50	106			
	14020-05*	14.0	20	25	45	50	110			
	14520-05	14.5	20	25	45	50	110	CD TOFO004		
	15020-05	15.0	20	25	48	50	114	SP□T050204-□□ XO□T050204-□□	FTNA0204	TW06P
	15520-05*	15.5	20	25	48	50	114	XO_1030204		
	16020-05	16.0	20	25	51	50	117			
	16525-06	16.5	25	34	51	56	123			
	17025-06	17.0	25	34	54	56	126			
	17525-06*	17.5	25	34	54	56	126			
	18025-06	18.0	25	34	57	56	130	SP_T060205	FTKA02206S	TW07P
	18525-06	18.5	25	34	57	56	130	XO□T060204-□□		
	19025-06	19.0	25	34	60	56	133	-		
	19525-06*	19.5	25	34	60	56	133			
	20025-07	20.0	25	34	63	56	138			
	20525-07	20.5	25	34	63	56	138			TM070
	21025-07*	21.0	25	34	66	56	141			
	21525-07	21.5	25	34	66	56	141	SP□T07T208-□□	FTKAOOEGE	
	22025-07	22.0	25	34	69	56	144	XO□T07T205-□□	FTKA02565	TW07S
	22525-07	22.5	25	34	69	56	144			
	23025-07	23	25	34	72	56	149	-		
	23525-07	23.5	25	34	72	56	149			
	24032-09*	24.0	32	44	75	60	157			
	24532-09	24.5	32	44	75	60	157	1		
	25032-09	25.0	32	44	78	60	160			
	25532-09	25.5	32	44	78	60	160	1		
	26032-09	26.0	32	44	81	60	163			
	26532-09*	26.5	32	44	81	60	163	SP□T090308-□□	ETK A0007	T\4/000
	27032-09	27.0	32	44	84	60	167	XO□T090305-□□	FTKA0307	TW09S
	27532-09	27.5	32	44	84	60	167			
	28032-09	28.0	32	44	87	60	171			
	28532-09	28.5	32	44	87	60	171	-		
	29032-09*	29.0	32	44	90	60	174			
	29532-09	29.5	32	44	90	60	174	1		


<sup>→</sup> Applicable inserts F03~04

# F King Drill

King Drill (3D)







(mm)



Screw Wrench Designation ØD Ød<sub>1</sub>  $Ød_2$ Q1 Q2 L Insert K<sub>3</sub>D 30032-11 \* 30.0 30.5 30532-11 31032-11 31.0 31532-11 31.5 32032-11 32.0 32532-11 32.5 SP□T11T308-□□ FTKA03508 TW15S 33032-11 33.0 XO□T11T306-□□ 33532-11 33.5 34032-11 34.0 34532-11 34.5 35032-11\* 35.0 35532-11 35.5 36040-13 36.0 36.5 36540-13 37040-13 37.0 37540-13 37.5 38040-13 38.0 38540-13 38.5 39040-13 39.0 SP T130410-FTKA0410 TW15S 39540-13 39.5 XO□T130406-□□ 40040-13 40.0 40540-13 40.5 41040-13 41.0 41540-13 41.5 42040-13 42.0 42540-13 42.5 43040-15 43.0 43540-15 43.5 44040-15 44.0 44540-15 44.5 45040-15 45.0 45540-15 45.5 46.0 46040-15 SP□T15M510-□□ 46540-15 46.5 FTNC04511 TW20S XO□T15M508-□□ 47040-15 47.0 47540-15 47.5 48.0 48040-15 48540-15 48.5 

49040-15

49540-15

50040-15

50540-15

49.0

49.5


50.0

50.5

King Drill (3D)










										(mm)
	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q <sub>2</sub>	L	Insert	Screw	Wrench
K3D	51040-18	51.0	40	68	159	70	269			
	51540-18	51.5	40	68	159	70	269			
	52040-18	52.0	40	68	162	70	272			
	52540-18	52.5	40	68	162	70	272			
	53040-18	53.0	40	68	165	70	275			
	53540-18	53.5	40	68	165	70	275			
	54040-18	54.0	40	68	168	70	278			
	54540-18	54.5	40	68	168	70	278			
	55040-18	55.0	40	68	171	70	281			
	55540-18	55.5	40	68	171	70	281	SP□T180510-□□	FTNA0511	TW20-100
	56040-18	56.0	40	68	174	70	286	XO□T180508-□□	TINAOSII	14420-100
	56540-18	56.5	40	68	174	70	286			
	57040-18	57.0	40	68	178	70	290			
	57540-18	57.5	40	68	178	70	290			
	58040-18	58.0	40	68	182	70	294			
	58540-18	58.5	40	68	182	70	294			
	59040-18	59.0	40	68	186	70	298			
	59540-18	59.5	40	68	186	70	298			
	60040-18	60.0	40	68	190	70	302			
	60540-18	60.5	40	68	190	70	302			


<sup>◆</sup> Applicable inserts F03~04

# King Drill




									_	
	Designation	ØD	Ød <sub>1</sub>		Q 1	Q <sub>2</sub>	L	Insert	Screw	Wrench
ŀD	12020-04	12.0	20	25	51	50	115			
	12520-04	12.5	20	25	51	50	115	SP□T040204-□□	ETNIA 000 4	TMOOD
	13020-04	13.0	20	25	55	50	119	XO□T040204-□□	FTNA0204	TW06P
	13520-04	13.5	20	25	55	50	119			
	14020-05	14.0	20	25	59	50	124			
	14520-05	14.5	20	25	59	50	124	OD TO 50004 \( \tau \)	FTNA0204	TW06P
	15020-05	15.0	20	25	63	50	129	SP□T050204-□□		
	15520-05	15.5	20	25	63	50	129	XO□T050204-□□		
	16020-05	16.0	20	25	67	50	133			
	16525-06	16.5	25	34	67	56	139			
	17025-06	17.0	25	34	71	56	143			
	17525-06	17.5	25	34	71	56	143	000700005		
	18025-06	18.0	25	34	75	56	148	SP□T060205-□□	FTKA02206S	TW07P
	18525-06	18.5	25	34	75	56	148	XO□T060204-□□		
	19025-06	19.0	25	34	79	56	152			
	19525-06	19.5	25	34	79	56	152			
	20025-07	20.0	25	34	83	56	158			
	20525-07	20.5	25	34	83	56	158			
	21025-07	21.0	25	34	87	56	162			
	21525-07	21.5	25	34	87	56	162	SP□T07T208-□□		TW07S
	22025-07	22.0	25	34	91	56	166	XO□T07T205-□□	FTKA02565	
	22525-07	22.5	25	34	91	56	166	XOLIO71200 LL		
	23025-07	23.0	25	34	95	56	172			
	23525-07	23.5	25	34	95	56	172			
	24032-09	24.0	32	44	99	60	181			
	24532-09	24.5	32	44	99	60	181			
	25032-09	25.0	32	44	103	60	185			
	25532-09	25.5	32	44	103	60	185			
	26032-09	26.0	32	44	107	60	189			
	26532-09	26.5	32	44	107	60	189	SP□T090308-□□		
	27032-09	27.0	32	44	111	60	194	XO□T090305-□□	FTKA0307	TW09S
	27532-09	27.5	32	44	111	60	194	XOL 1090303-LL		
	28032-09	28.0	32	44	115	60	199			
	28532-09	28.5	32	44	115	60	199			
	29032-09	29.0	32	44	119	60	203			
	29532-09	29.5	32	44	119	60	203			
	30032-11	30.0	32	44	123	60	210			
	30532-11	30.5	32	44	123	60	210			
	31032-11	31.0	32	44	127	60	214			
	31532-11	31.5	32	44	127	60	214			
	32032-11	32.0	32	44	131	60	218			
	32532-11	32.5	32	44	131	60	218	SP□T11T308-□□		
	33032-11	33.0	32	44	135	60	223		FTKA03508	TW15S
	33532-11							XO□T11T306-□□		
		33.5	32	44	135	60	223			
	34032-11	34.0	32	44	139	60	227			
	34532-11	34.5	32	44	139	60	227			
	35032-11 35532-11	35.0 35.5	32 32	44	143	60 60	231			

(mm)



									Screw	Wrench
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q 1	Q <sub>2</sub>	L	Insert		P
K4D	36040-13	36.0	40	48	148	70	248		-	
	36540-13	36.5	40	48	148	70	248			
	37040-13	37.0	40	48	152	70	252			
	37540-13	37.5	40	48	152	70	252			
	38040-13	38.0	40	48	156	70	257			
	38540-13	38.5	40	48	156	70	257			
	39040-13	39.0	40	48	160	70	261	SP□T130410-□□	FTKA0410	TW15S
	39540-13	39.5	40	48	160	70	261	XO□T130406-□□	FINAU410	100100
	40040-13	40.0	40	48	164	70	266			
	40540-13	40.5	40	48	164	70	266			
	41040-13	41.0	40	48	168	70	270			
	41540-13	41.5	40	48	168	70	270			
	42040-13	42.0	40	48	172	70	275			
	42540-13	42.5	40	48	172	70	275			
	43040-15	43.0	40	58	177	70	282			
	43540-15	43.5	40	58	177	70	282			
	44040-15	44.0	40	58	181	70	286			
	44540-15	44.5	40	58	181	70	286			
	45040-15	45.0	40	58	185	70	291			
	45540-15	45.5	40	58	185	70	291			
	46040-15	46.0	40	58	189	70	295			
	46540-15	46.5	40	58	189	70	295	SP□T15M510-□□	FTNC04511	TW20S
	47040-15	47.0	40	58	193	70	300	XO□T15M508-□□	FINGU4511	1 W 203
	47540-15	47.5	40	58	193	70	300			
	48040-15	48.0	40	58	197	70	304			
	48540-15	48.5	40	58	197	70	304			
	49040-15	49.0	40	58	201	70	308			
	49540-15	49.5	40	58	201	70	308			
	50040-15	50.0	40	58	205	70	312			
	50540-15	50.5	40	58	205	70	312			
	51040-18	51.0	40	68	210	70	320			
	51540-18	51.5	40	68	210	70	320			
	52040-18	52.0	40	68	214	70	324			
	52540-18	52.5	40	68	214	70	324			
	53040-18	53.0	40	68	218	70	328			
	53540-18	53.5	40	68	218	70	328			
	54040-18	54.0	40	68	222	70	332			
	54540-18	54.5	40	68	222	70	332			
	55040-18	55.0	40	68	226	70	336			
	55540-18	55.5	40	68	226	70	336	SP□T180510-□□	FTNA0511	TW20-100
	56040-18	56.0	40	68	230	70	342	XO□T180508-□□		20 100
	56540-18	56.5	40	68	230	70	342			
	57040-18	57.0	40	68	235	70	347			
	57540-18	57.5	40	68	235	70	347			
	58040-18	58.0	40	68	240	70	352			
	58540-18	58.5	40	68	240	70	352			
	59040-18	59.0	40	68	245	70	357			
	59540-18	59.5	40	68	245	70	357			
	60040-18	60.0	40	68	250	70	362			
	60540-18	60.5	40	68	250	70	362			


# **F** King Drill



									Screw	Wrench
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Sciew	A
5D	12020-04	12.0	20	25	63	50	127			
	12520-04	12.5	20	25	63	50	127	SP□T040204-□□	FTNA0204	TW06P
	13020-04	13.0	20	25	68	50	132	XO□T040204-□□	F1NA0204	
	13520-04	13.5	20	25	68	50	132			
	14020-05	14.0	20	25	73	50	138			
	14520-05	14.5	20	25	73	50	138	SP□T050204-□□		
	15020-05	15.0	20	25	78	50	144		FTNA0204	TW06F
	15520-05	15.5	20	25	78	50	144	XO\ \text{T050204-\ \text{\pi}\		
	16020-05	16.0	20	25	83	50	149			
	16525-06	16.5	25	34	83	56	155			
	17025-06	17.0	25	34	88	56	160			
	17525-06	17.5	25	34	88	56	160	SP□T060205-□□		
	18025-06	18.0	25	34	93	56	166	XO□T060204-□□	FTKA02206S	TW07F
	18525-06	18.5	25	34	93	56	166	XU_1060204		
	19025-06	19.0	25	34	98	56	171			
	19525-06	19.5	25	34	98	56	171			
	20025-07	20.0	25	34	103	56	178			
	20525-07	20.5	25	34	103	56	178			TW07S
	21025-07	21.0	25	34	108	56	183		FTKA02565	
	21525-07	21.5	25	34	108	56	183	SP□T07T208-□□		
	22025-07	22.0	25	34	113	56	188	XO□T07T205-□□	1 1KA02505	
	22525-07	22.5	25	34	113	56	188			
	23025-07	23.0	25	34	118	56	195			
	23525-07	23.5	25	34	118	56	195			
	24032-09	24.0	32	44	123	60	205			
	24532-09	24.5	32	44	123	60	205			
	25032-09	25.0	32	44	128	60	210			
	25532-09	25.5	32	44	128	60	210			
	26032-09	26.0	32	44	133	60	215			
	26532-09	26.5	32	44	133	60	215	SP□T090308-□□	FTKA0307	TW095
	27032-09	27.0	32	44	138	60	221	XO□T090305-□□	1 110 10007	111000
	27532-09	27.5	32	44	138	60	221			
	28032-09	28.0	32	44	143	60	227			
	28532-09	28.5	32	44	143	60	227			
	29032-09	29.0	32	44	148	60	232			
	29532-09	29.5	32	44	148	60	232			
	30032-11	30.0	32	44	153	60	240			
	30532-11	30.5	32	44	153	60	240			
	31032-11	31.0	32	44	158	60	245			
	31532-11	31.5	32	44	158	60	245			
	32032-11	32.0	32	44	163	60	250			
	32532-11	32.5		SP□T11T308-□□	FTKA03508	TW158				
	33032-11	33.0	32	44	168	8 60 256 XO□T11T306-□□				
	33532-11	33.5	32	44	168	60	256			
	34032-11	34.0	32	44	173	60	261			
	34532-11	34.5	32	44	173	60	261			
	35032-11	35.0	32	44	178	60	266	_		
	35532-11	35.5	32	44	178	60	266			

<sup>●</sup> Applicable inserts F03~04

(mm)



	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Screw	Wrench
K5D	36040-13	36.0	40	48	184	70	284			·
	36540-13	36.5	40	48	184	70	284			
	37040-13	37.0	40	48	189	70	289	1		
	37540-13	37.5	40	48	189	70	289	-		
	38040-13	38.0	40	48	194	70	295			
	38540-13	38.5	40	48	194	70	295			
	39040-13	39.0	40	48	199	70	300	SP□T130410-□□	ETI(A0440	TM450
	39540-13	39.5	40	48	199	70	300	XO□T130406-□□	FTKA0410	TW15S
	40040-13	40.0	40	48	204	70	306			
	40540-13	40.5	40	48	204	70	306			
	41040-13	41.0	40	48	209	70	311			
	41540-13	41.5	40	48	209	70	311			
	42040-13	42.0	40	48	214	70	317			
	42540-13	42.5	40	48	214	70	317			
	43040-15	43.0	40	58	220	70	325			
	43540-15	43.5	40	58	221	70	326			
	44040-15	44.0	40	58	225	70	330			
	44540-15	44.5	40	58	225	70	330			
	45040-15	45.0	40	58	230	70	336			
	45540-15	45.5	40	58	230	70	336			
	46040-15	46.0	40	58	235	70	341			
	46540-15	46.5	40	58	235	70	341	SP□T15M510-□□	ETNICOAEAA	TWOOO
	47040-15	47.0	40	58	240	70	347	XO□T15M508-□□	FTNC04511	TW20S
	47540-15	47.5	40	58	240	70	347			
	48040-15	48.0	40	58	245	70	352			
	48540-15	48.5	40	58	245	70	352			
	49040-15	49.0	40	58	250	70	357			
	49540-15	49.5	40	58	250	70	357			
	50040-15	50.0	40	58	255	70	362			
	50540-15	50.5	40	58	255	70	362			
	51040-18	51.0	40	68	261	70	371			
	51540-18	51.5	40	68	261	70	371			
	52040-18	52.0	40	68	266	70	376			
	52540-18	52.5	40	68	266	70	376			
	53040-18	53.0	40	68	271	70	381			
	53540-18	53.5	40	68	271	70	381			
	54040-18	54.0	40	68	276	70	386			
	54540-18	54.5	40	68	276	70	386			
	55040-18	55.0	40	68	281	70	391			
	55540-18	55.5	40	68	281	70	391	SP□T180510-□□	FTNA0511	TW20-100
	56040-18	56.0	40	68	286	70	398	XO□T180508-□□	FIICUAVII	1 VVZU-100
	56540-18	56.5	40	68	286	70	398			
	57040-18	57.0	40	68	292	70	404			
	57540-18	57.5	40	68	292	70	404			
	58040-18	58.0	40	68	298	70	410			
	58540-18	58.5	40	68	298	70	410			
	59040-18	59.0	40	68	304	70	416			
	59540-18	59.5	40	68	304	70	416			
	60040-18	60.0	40	68	310	70	422			
	60540-18	60.5	40	68	310	70	422			




### Technical Inforamation for King Drill (For through coolant system with a lathe)

Drill with through coolant system for general lathe and CNC lathe without through coolant system


## **King Drill** (For through coolant system with a lathe)

- Through coolant system with drill holder, plug, oil-hole hose and oil-hole pump
- PT TAP in the plug is combined to PT TAP connected to oil hose
- Available to use the drill without a plug in milling machine



(mm)

Tap type	Diameter	Shank dia.	Мхр	Plug
K□D120~16020HP-□□	Ø12.0~Ø16.0	Ø20	M12x1.5	PLG12PT18
K□D161~23525HP-□□	Ø16.1~Ø23.5	Ø25	M16x1.5	PLG16PT18
K□D236~35532HP-□□	Ø23.6~Ø35.5	Ø32	M20x2.0	PLG20PT14
K□D356~60940HP-□□	Ø35.6~Ø60.5	Ø40	M27x2.0	PLG27PT38



· Plug is assembled

Plug type	Мхр	PT tap	А
PLG12PT18	M12 x 1.5	1/8	16
PLG16PT18	M16 x 1.5	1/8	19
PLG20PT14	M20 x 2.0	1/4	26
PLG27PT38	M27 x 2.0	3/8	35




# King Drill (2D)

### For through coolant system with a lathe









										(mm)
	Desiagnation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Screw	Wrench
K2D	13020HP-04 13520HP-04	13.0 13.5	20 20	25 25	29 29	50 50	93 93	SP□T040204-□□ XO□T040204-□□	FTNA0204	TW06P
	14020HP-05	14.0	20	25	31	50	96	SP□T050204-□□	FTNA0204 TV	
	15020HP-05 16020HP-05	15.0 16.0	20	25 25	33 35	50 50	99	XO□T050204-□□		TW06P
	17025HP-06 18025HP-06	17.0 18.0	25 25	34 34	37 39	56 56	109 112	SP_T060205-□□ XO_T060204-□□	FTKA02206S FTKA02565	TW07P
	19025HP-06	19.0	25	34	41	56	114			
	20025HP-07 21025HP-07	20.0	25 25	34	43 45	56 56	118 120	SP□T07T208-□□		TW07S
	22025HP-07 23025HP-07	22.0	25 25	34 34	47 49	56 56	122 126	XO□T07T205-□□		
	24032HP-09	24.0	32	44	51	60	133			
	25032HP-09 26032HP-09	25.0 26.0	32 32	44	53 55	60	135 137	SP□T090308-□□	FTI/40007	TMOO
	27032HP-09 28032HP-09	27.0	32 32	44	57 59	60	140 143	XO□T090305-□□	FTKA0307	TW09S
	29032HP-09	28.0	32	44	61	60	143			


<sup>◆</sup> Applicable inserts F03~04

# F

# King Drill (3D)

### For through coolant system with a lathe





										(mm)
	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Screw	Wrench
K3D	13020HP-04	13.0	20	25	42	50	106	SP□T040204-□□	FTNA0204	
	13520HP-04	13.5	20	25	42	50	106	XO□T040204-□□		TW06P
	14020HP-05	14.0	20	25	45	50	110			
	14520HP-05	14.5	20	25	45	50	110	SP□T050204-□□		
	15020HP-05	15.0	20	25	48	50	114	XO T050204-	FTNA0204	TW06P
	15520HP-05	15.5	20	25	48	50	114			
	16020HP-05	16.0	20	25	51	50	117			
	16525HP-06	16.5	25	34	51	56	123			
	17025HP-06	17.0	25	34	54	56	126		FTKA02206S	TW07P
	17525HP-06	17.5	25	34	54	56	126	SB TOGOSOF D		
	18025HP-06	18.0	25	34	57	56	130	SP T060205- XO T060204- S		
	18525HP-06	18.5	25	34	57	56	130			
	19025HP-06	19.0	25	34	60	56	133			
	19525HP-06	19.5	25	34	60	56	133			
	20025HP-07	20.0	25	34	63	56	138	SP_T07T208	FTKA02565	
	20525HP-07	20.5	25	34	63	56	138			
	21025HP-07	21.0	25	34	66	56	141			
	21525HP-07	21.5	25	34	66	56	141			TW07S
	22025HP-07	22.0	25	34	69	56	144	XO□T07T205-□□		10075
	22525HP-07	22.5	25	34	69	56	144			
	23025HP-07	23.0	25	34	72	56	149			
	23525HP-07	23.5	25	34	72	56	149			
	24032HP-09	24.0	32	44	75	60	157			
	24532HP-09	24.5	32	44	75	60	157			
	25032HP-09	25.0	32	44	78	60	160			
	25532HP-09	25.5	32	44	78	60	160			
	26032HP-09	26.0	32	44	81	60	163			
	26532HP-09	26.5	32	44	81	60	163	SP□T090308-□□	FTKA0307	TW09S
	27032HP-09	27.0	32	44	84	60	167	XO□T090305-□□	1 TRAUGUT	
	27532HP-09	27.5	32	44	84	60	167			
	28032HP-09	28.0	32	44	87	60	171			
	28532HP-09	28.5	32	44	87	60	171			
	29032HP-09	29.0	32	44	90	60	174			
	29532HP-09	29.5	32	44	90	60	174			

<sup>→</sup> Applicable inserts F03~04




# King Drill (4D)

### For through coolant system with a lathe









										(mi
	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	Insert	Screw	Wrench
K4D	13020HP-04 13520HP-04	13.0 13.5	20 20	25 25	55 55	50 50	119 119	SP□T040204-□□ XO□T040204-□□	FTNA0204	TW06P
	14020HP-05 15020HP-05	14.0 15.0	20	25 25	59 63	50 50	124 129	SP\\_T050204-\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\		TW06P
	16020HP-05	16.0	20	25	67	50	133			
	17025HP-06 18025HP-06	17.0 18.0	25 25	34 34	71 75	56 56	143 148			TW07P
	19025HP-06 20025HP-07	19.0	25 25	34	79 83	56 56	152 158	SP□T07T208-□□ XO□T07T205-□□	FTKA02565	TW07S
	21025HP-07 22025HP-07	21.0 22.0	25 25	34 34	87 91	56 56	162 166			
	23025HP-07 24032HP-09	23.0	25 32	34 44	95 99	56 60	172 181			
	25032HP-09	25.0	32	44	103	60	185			
	26032HP-09 27032HP-09	26.0 27.0	32 32	44	107 111	60	189 194	SP   T090308-	FTKA0307	TW09S
	28032HP-09 29032HP-09	28.0 29.0	32 32	44	115 119	60 60	199 203			

<sup>→</sup> Applicable inserts F03~04




### Technical Information for King Drill (For large diameter drilling)

High rigidity drill produces cost efficiency due to cartridge replacement


# **King Drill** (For large diameter drilling)

- Cartridge type for Ø61~Ø100 drilling
- Peripheral cartridge can adjust the drilling diameter within 5 mm
- Easy to adjust drilling diameter with adjusting bolt

### Structure of King Drill (for large diameter) parts



### Adjustment of drill diameter






Adjustment	Adjusting washer								
Ø (mm)	Designation	Width (mm)							
1	WA0305	0.5							
2	WA0310	1.0							
3	WA0305 + WA0310	1.5							
4	WA0310 x 2	2.0							
5	WA0305 + WA0310 x 2	2.5							

<sup>\*</sup> Adjusting washer adjusts the drilling diameter within 5 mm

# **King Drill**





								1			(mm)
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q <sub>1</sub>	Q <sub>2</sub>	L	Carti	ridge	Screw	Wrench
	Designation	90	Øu₁	Øu₂	¥.1	W 2	_	Internal	External		P
K2D	616550-11	61~65	50	80	130	80	255	KDC6165C	KDC6165P	FTKA03508	TW15S
	657050-13	65~70	50	88	140	80	265	KDC6570C	KDC6570P	FTKA0410	TW15S
	707550-13	70~75	50	88	150	80	275	KDC7075C	KDC7075P	FTKA0410	TW15S
	758050-13	75~80	50	88	160	80	285	KDC7580C	KDC7580P	FTKA0410	TW15S
	808550-15	80~85	50	88	170	80	295	KDC8085C	KDC8085P	FTNC04511	TW20S
	859050-15	85~90	50	95	180	80	305	KDC8590C	KDC8590P	FTNC04511	TW20S
	909550-15	90~95	50	95	190	80	315	KDC9095C	KDC9095P	FTNC04511	TW20S
	9510050-18	95~100	50	95	200	80	325	KDC95100C	KDC95100P	FTNA0511	TW20-100
K3D	616550-11	61~65	50	80	195	80	320	KDC6165C	KDC6165P	FTKA03508	TW15S
	657050-13	65~70	50	88	210	80	335	KDC6570C	KDC6570P	FTKA0410	TW15S
	707550-13	70~75	50	88	225	80	350	KDC7075C	KDC7075P	FTKA0410	TW15S
	758050-13	75~80	50	88	240	80	365	KDC7580C	KDC7580P	FTKA0410	TW15S
	808550-15	80~85	50	88	255	80	380	KDC8085C	KDC8085P	FTNC04511	TW20S
	859050-15	85~90	50	95	270	80	395	KDC8590C	KDC8590P	FTNC04511	TW20S
	909550-15	90~95	50	95	285	80	410	KDC9095C	KDC9095P	FTNC04511	TW20S
	9510050-18	95~100	50	95	300	80	425	KDC95100C	KDC95100P	FTNA0511	TW20-100
K4D	616550-11	61~65	50	80	260	80	385	KDC6165C	KDC6165P	FTKA03508	TW15S
	657050-13	65~70	50	88	280	80	405	KDC6570C	KDC6570P	FTKA0410	TW15S
	707550-13	70~75	50	88	300	80	425	KDC7075C	KDC7075P	FTKA0410	TW15S
	758050-13	75~80	50	88	320	80	445	KDC7580C	KDC7580P	FTKA0410	TW15S
	808550-15	80~85	50	88	340	80	465	KDC8085C	KDC8085P	FTNC04511	TW20S
	859050-15	85~90	50	95	360	80	485	KDC8590C	KDC8590P	FTNC04511	TW20S
	909550-15	90~95	50	95	380	80	505	KDC9095C	KDC9095P	FTNC04511	TW20S
	9510050-18	95~100	50	95	400	80	525	KDC95100C	KDC95100P	FTNA0511	TW20-100

<sup>◆</sup> Applicable inserts F03~04

#### Parts

Carti	ridge	Range		Ins	ert		Screw	Wrench
Internal	External	(Ø)	Designation	Quantity	Designation	Quantity	Screw	wrench
KDC6165C	KDC6165P	61~65	XO□T11T306-□□	2	SP□T11T308-□□	2	FTKA03508	TW15S
KDC6570C	KDC6570P	65~70	XO□T130406-□□	2	SP□T130410-□□	2	FTKA0410	TW15S
KDC7075C	KDC7075P	70~75	XO□T130406-□□	2	SP□T130410-□□	2	FTKA0410	TW15S
KDC7580C	KDC7580P	75~80	XO□T130406-□□	2	SP□T130410-□□	2	FTKA0410	TW15S
KDC8085C	KDC8085P	80~85	XO□T15M508-□□	2	SP□T15M510-□□	2	FTNC04511	TW20S
KDC8590C	KDC8590P	85~90	XO□T15M508-□□	2	SP□T15M510-□□	2	FTNC04511	TW20S
KDC9095C	KDC9095P	90~95	XO□T15M508-□□	2	SP□T15M510-□□	2	FTNC04511	TW20S
KDC95100C	KDC95100P	95~100	XO□T180508-□□	2	SP□T180510-□□	2	FTNA0511	TW20-100



### **Technical Information for KED Plus Drill**

KORLOY indexable new generation economical drill

### **KED Plus Drill**


- Economical drill with good chip control due to optimal chip flute enlarging the space for chip flow
- Stable machining due to optimal shape and cutting edge arrangement of central and peripheral inserts

#### Code system



#### Features

- Excellent chip control for suitable cutting range with small diameters (Ø12-Ø23.5) due to the cutting fluid system and chip flute
- Excellent surface finish for suitable cutting range with medium to large diameters (Ø24-Ø60.5) due to widened chip pockets even in deep drilling
- · Increased the rigidity of drill body and improved chip evacuation due to optimalized shape of flute







#### Features of chip breaker

- · Optimized design of inserts for maximum drilling efficiency
  - Excellent cutting performance and chip control due to the optimized geometry and chip breaker of both inserts: central and peripheral
  - A set of differently shaped central and peripheral inserts optimizing the insert locations in order to maximize cutting tool life

Chip breaker	Р	D	L	D	N	D	RD
Features	- Universal - At medium speed a	and medium feed	Superior chip of machining mild stainless steel     Light cutting (a speed and low	t low~medium	Sharp cutting ealuminum mack     Insert surface bigh quality res     E Class Toleral	hining ouffed for sult	Improved chipping resistance     Excellent performance in case of frequent fracture and chipping on the cutting edge
Insert	Peripheral insert	Central insert	Peripheral insert	Central insert	Peripheral insert	Central insert	Central insert
Shape						9	
Grades for workpiece	NC5330: P, M, K PC3700: P PC5300: P, M, K, S PC6510: K PC9540: P, M, S	PC5300: P, M, K, S PC9540: P, M, S	PC533	35: P, M	H0	1: N	PC5300: P, M, K, S

# Technical Information for KED Plus Drill


#### Required cutting power


■ Workpiece SCM440 (240HB)


Cutting vc (m/min) = 100, Through coolant system conditions












\* Cutting force shown as the above is base on drilling in facilities with enough rigidity and power


#### Cutting oil quantity

- Workpiece SCM440 (240HB)
- Cutting vc (m/min) = 100, Through coolant system conditions
- The data of the graph above could be changed depending on workpiece and cutting condition



#### Drill tolerance and hole tolerance





(mm)

Dri	I dia.	Ø12~Ø29	Ø30~Ø45	Ø46~Ø60.5
2D~3D	Drill tolerance (ØD)	0~-0.15	0~-0.15	0~-0.15
20~30	Hole tolerance	+0.2~-0.1	+0.25~-0.1	+0.28~-0.1
4D~5D	Drill tolerance (ØD)	0~-0.15	0~-0.15	0~-0.15
40~30	Hole tolerance	+0.25~-0.05	+0.3~-0.05	+0.33~-0.05

### **Technical Information for KED Plus Drill**

#### Application examples

■ Workpiece Carbon steel (SM440)

Cutting vc (m/min) = 150, fn (mm/rev) = 0.1 conditions ap (mm) = 80 (through hole), wet

■ Tools Inserts SPMT060205-PD (PC3700)

XOMT060205-PD (PC5300)

Holder E4D-18025-06-P

(Drill dia. = Ø18 mm)







KED Plus Drill Competitor

■ Workpiece Stainless steel (STS316)

Cutting vc (m/min) = 120, fn (mm/rev) = 0.06

conditions ap (mm) = 42, wet

■ Tools Inserts SPMT060205-PD (PC3700)


XOMT060204-PD (PC3500)

Holder E3D-18025-06-P

(Drill dia. = Ø18 mm)



#### ■ Test result



#### Recommended cutting condition


		Workpiece			Insert				Aspect ra	atio (L/D) = 2	D, 3D, 4D	
	ISO	Wayloniaaa	Hardness	Chip	Gra	ade	vc (m/min)		Feed rate (m	m/rev) per d	rill dia. (mm)	)
	150	Workpiece	(HB)	breaker	Central	Peripheral		Ø12~Ø16	Ø17~Ø23	Ø24~Ø29	Ø30~Ø42	Ø43~Ø60
				LD	PC5335	PC5335	120 (60~170)					
		Low carbon steel	80~180	PD/	PC5300	PC3500	150 (120~180)	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08	0.04~0.08
	Carbon steel			RD	FC3300	NC5330	180 (140~220)					
		High carbon	180~280	PD	PC5300	PC3500	120 (90~150)	0.04~0.10	0.04~0.12	0.05~0.16	0.06~0.16	0.06~0.18
		steel	100~200	רט	FC3300	NC5330	150 (110~190)	0.04~0.06	0.04~0.07	0.04~0.08	0.04~0.08	0.04~0.08
P				LD	PC5335	PC5335	120 (60~160)	0.06~0.10	0.06~0.10	0.06~0.12	0.06~0.14	0.06~0.14
		Low alloy steel	140~260	PD	PC5300	PC3500	150 (120~170)	0.06~0.12	0.06~0.12	0.06~0.14	0.06~0.16	0.06~0.16
	Alloy	0.00.		רט	FC3300	NC5330	180 (140~210)	0.06~0.08	0.06~0.08	0.06~0.10	0.06~0.12	0.06~0.12
	steel	Low alloy heattreated steel	200~400	PD	PC5300	PC5300	100 (50~150)	0.04~0.10	0.06~0.10	0.06~0.12	0.06~0.14	0.06~0.14
		High alloy steel	260~320	PD	PC5300	PC3500	100 (50~160)	0.05~0.11	0.05~0.11	0.05~0.13	0.05~0.15	0.05~0.15
		High alloy heattreated steel	300~450	PD	PC5300	PC5300	70 (30~120)	0.04~0.08	0.06~0.08	0.06~0.10	0.06~0.12	0.06~0.12
				LD	PD5335	PC5335	120 (80~140)	0.04~0.07	0.04~0.07	0.04~0.07	0.04~0.08	0.04~0.08
M	Stainless steel	Stainless steel	135~275	PD	PC5300	PC5300	130 (100~160)	0.04~0.07	0.04~0.07	0.04~0.07	0.04~0.08	0.04~0.08
				10	PC9540	PC9540	90 (60~120)	0.04~0.07	0.04~0.07	0.04~0.07	0.04~0.08	0.04~0.08
K	Cast iron	Gray cast iron	150~230	PD	PC5300	PC6510	190 (150~250)	0.04~0.12	0.05~0.14	0.06~0.18	0.10~0.22	0.10~0.26
K	Cast IIOII	Ductile cast iron	150~230	PD	PC5300	PC6510	130 (100~160)	0.04~0.07	0.04~0.08	0.04~0.10	0.05~0.12	0.05~0.12
		Ni-heat resisting alloy	130~400	PD	PC5300	PC5300	50 (30~100)	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10
	Heat	INFREALTESISTING ANDY	130~400	רט	PC9540	PC9540	40 (20~80)	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10	0.04~0.10
S	resisting	Ti-heat resisting alloy	130~400	LD	PC5335	PC5335	60 (40~80)	0.04~0.08	0.04~0.10	0.06~0.12	0.06~0.14	0.06~0.16
	alloy	11-fleat fesisting alloy	130~400	PD	PC5300	PC5300	60 (40~80)	0.04~0.08	0.04~0.10	0.06~0.12	0.06~0.14	0.06~0.16
		High hardened steel	over 400	PD	PC5300	PC5300	40 (20~80)	0.04~0.05	0.04~0.06	0.04~0.08	0.04~0.08	0.04~0.08
N	Non-ferrous	Aluminium	30~150	ND	H01	H01	300 (250~400)	0.05~0.14	0.06~0.16	0.10~0.20	0.10~0.22	0.12~0.25
IN	metal	Alloyed copper	150-160	ND	H01	H01	250 (200~300)	0.05~0.14	0.06~0.16	0.10~0.20	0.10~0.22	0.12~0.25

- The Max. feed of 5D holders is 70%~80% of the max. conditions of 2D/3D/4D holders
- $\bullet$  In interrupted machining part, reduce 30~50% of feed from the above machining around interrupted part

## **KED Plus Drill (2D)**








										Screw	Wrench
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q <sub>1</sub>	Q 2	L	PT	Insert		P
E2D-	12020-04-P	12.0	20	25	27	50	91				
	12520-04-P	12.5	20	25	27	50	91		SP□T040204-□□		
	13020-04-P	13.0	20	25	29	50	93		XO□T040204-□□		
	13520-04-P	13.5	20	25	29	50	93				
	14020-05-P	14.0	20	25	31	50	96			FTNA0204	TW06P
	14520-05-P	14.5	20	25	31	50	96		SP□T050204-□□		
	15020-05-P	15.0	20	25	33	50	99		XO\\[\tau\)50204-\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\		
	15520-05-P	15.5	20	25	33	50	99		XO_1030204		
	16020-05-P	16.0	20	25	35	50	101				
	16525-06-P	16.5	25	34	35	56	107				
	17025-06-P	17.0	25	34	37	56	109				
	17525-06-P	17.5	25	34	37	56	109	1/8	SP□T060205-□□		
	18025-06-P	18.0	25	34	39	56	112	176	XO T060204-	FTKA02206S	TW07P
	18525-06-P	18.5	25	34	39	56	112		XO_1000204		
	19025-06-P	19.0	25	34	41	56	114				
	19525-06-P	19.5	25	34	41	56	114				
	20025-07-P	20.0	25	34	43	56	118				
	20525-07-P	20.5	25	34	43	56	118				
	21025-07-P	21.0	25	34	45	56	120				
	21525-07-P	21.5	25	34	45	56	120		SP□T07T208-□□	ETKAOOEGE	TW070
	22025-07-P	22.0	25	34	47	56	122		XO□T07T205-□□	FTKA02565	TW07S
	22525-07-P	22.5	25	34	47	56	122				
	23025-07-P	23.0	25	34	49	56	126				
	23525-07-P	23.5	25	34	49	56	126				
	24032-09-P	24.0	32	44	51	60	133				
	24532-09-P	24.5	32	44	51	60	133				
	25032-09-P	25.0	32	44	53	60	135				
	25532-09-P	25.5	32	44	53	60	135				
	26032-09-P	26.0	32	44	55	60	137				
	26532-09-P	26.5	32	44	55	60	137		SP□T090308-□□	FTKA0307	TW09S
	27032-09-P	27.0	32	44	57	60	140		XO□T090305-□□	1 110 10007	144000
	27532-09-P	27.5	32	44	57	60	140				
	28032-09-P	28.0	32	44	59	60	143				
	28532-09-P	28.5	32	44	59	60	143				
	29032-09-P	29.0	32	44	61	60	145				
	29532-09-P	29.5	32	44	61	60	145	1/4			
	30032-11-P	30.0	32	44	63	60	150	,,,,			
	30532-11-P	30.5	32	44	63	60	150				
	31032-11-P	31.0	32	44	65	60	152				
	31532-11-P	31.5	32	44	65	60	152				
	32032-11-P	32.0	32	44	67	60	154				
	32532-11-P	32.5	32	44	67	60	154		SP□T11T308-□□	FTKA03508	TW15S
	33032-11-P	33.0	32	44	69	60	157		XO□T11T306-□□		
	33532-11-P	33.5	32	44	69	60	157				
	34032-11-P	34.0	32	44	71	60	159				
	34532-11-P	34.5	32	44	71	60	159				
	35032-11-P	35.0	32	44	73	60	161				
	35532-11-P	35.5	32	44	73	60	161				

## **KED Plus Drill (2D)**






(mm)


	Designation	αD	αd	αd	0	0		PT	Innert	Screw	Wrench
	Designation	ØD	Ød₁	Ød₂	Q 1	Q 2	L	PI	Insert		
E2D-	36040-13-P	36.0	40	48	76	70	176				
	36540-13-P	36.5	40	48	76	70	176				
	37040-13-P	37.0	40	48	78	70	178				
	37540-13-P	37.5	40	48	78	70	178				
	38040-13-P	38.0	40	48	80	70	181				
	38540-13-P	38.5	40	48	80	70	181				
	39040-13-P	39.0	40	48	82	70	183		SP□T130410-□□	FTKA0410	TW15S
	39540-13-P	39.5	40	48	82	70	183		XO□T130406-□□	1 110.0410	144150
	40040-13-P	40.0	40	48	84	70	186				
	40540-13-P	40.5	40	48	84	70	186				
	41040-13-P	41.0	40	48	86	70	188				
	41540-13-P	41.5	40	48	86	70	188				
	42040-13-P	42.0	40	48	88	70	191				
	42540-13-P	42.5	40	48	88	70	191				
	43040-15-P	43.0	40	58	91	70	196				
	43540-15-P	43.5	40	58	91	70	196				
	44040-15-P	44.0	40	58	93	70	198				
	44540-15-P	44.5	40	58	93	70	198				
	45040-15-P	45.0	40	58	95	70	201				
	45540-15-P	45.5	40	58	95	70	201				
	46040-15-P	46.0	40	58	97	70	203				
	46540-15-P	46.5	40	58	97	70	203		SP□T15M510-□□	ETNO04544	TMOOO
	47040-15-P	47.0	40	58	99	70	206		XO□T15M508-□□	FTNC04511	TW20S
	47540-15-P	47.5	40	58	99	70	206				
	48040-15-P	48.0	40	58	101	70	208	.,,			
	48540-15-P	48.5	40	58	101	70	208	1/4			
	49040-15-P	49.0	40	58	103	70	210				
	49540-15-P	49.5	40	58	103	70	210				
	50040-15-P	50.0	40	58	105	70	212				
	50540-15-P	50.5	40	58	105	70	212				
	51040-18-P	51.0	40	68	108	70	218				
	51540-18-P	51.5	40	68	108	70	218				
	52040-18-P	52.0	40	68	110	70	220				
	52540-18-P	52.5	40	68	110	70	220				
	53040-18-P	53.0	40	68	112	70	222				
	53540-18-P	53.5	40	68	112	70	222				
	54040-18-P	54.0	40	68	114	70	224				
	54540-18-P	54.5	40	68	114	70	224				
	55040-18-P	55.0	40	68	116	70	226				
	55540-18-P	55.5	40	68	116	70	226		SP□T180510-□□	ETNIAGE11	TW00 100
	56040-18-P	56.0	40	68	118	70	230	1	XO□T180508-□□	FTNA0511	TW20-100
	56540-18-P	56.5	40	68	118	70	230				
	57040-18-P	57.0	40	68	121	70	233				
	57540-18-P	57.5	40	68	121	70	233				
	58040-18-P	58.0	40	68	124	70	236	]			
	58540-18-P	58.5	40	68	124	70	236				
	59040-18-P	59.0	40	68	127	70	239	]			
	59540-18-P	59.5	40	68	127	70	239	1			
	60040-18-P	60.0	40	68	130	70	242	1			
	60540-18-P	60.5	40	68	130	70	242	1			

## **KED Plus Drill (3D)**



	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	PT	Insert	Screw	Wrench
3D-	12020-04-P	12.0	20	25	39	50	103				
_	12520-04-P	12.5	20	25	39	50	103		SP□T040204-□□		
	13020-04-P	13.0	20	25	42	50	106		XO□T040204-□□		
	13520-04-P	13.5	20	25	42	50	106				TW06P
	14020-05-P	14.0	20	25	45	50	110			FTNA0204	
	14520-05-P	14.5	20	25	45	50	110				
	15020-05-P	15.0	20	25	48	50	114		SP□T050204-□□		
	15520-05-P	15.5	20	25	48	50	114		XO□T050204-□□		
	16020-05-P	16.0	20	25	51	50	117				
	16525-06-P	16.5	25	34	51	56	123				
	17025-06-P	17.0	25	34	54	56	126				
	17525-06-P	17.5	25	34	54	56	126				
	18025-06-P	18.0	25	34	57	56	130	1/8	SP□T060205-□□	FTKA02206S	TW07P
	18525-06-P	18.5	25	34	57	56	130		XO□T060204-□□		
	19025-06-P	19.0	25	34	60	56	133				
	19525-06-P	19.5	25	34	60	56	133				TW07S
	20025-07-P	20.0	25	34	63	56	138				
	20525-07-P	20.5	25	34	63	56	138				
	21025-07-P	21.0	25	34	66	56	141				
	21525-07-P	21.5	25	34	66	56	141		SP□T07T208-□□		
	22025-07-P	22.0	25	34	69	56	144		XO□T07T205-□□	FTKA02565	
	22525-07-P	22.5	25	34	69	56	144				
	23025-07-P	23.0	25	34	72	56	149				
	23525-07-P	23.5	25	34	72	56	149				
	24032-09-P	24.0	32	44	75	60	157				
	24532-09-P	24.5	32	44	75	60	157				
	25032-09-P	25.0	32	44	78	60	160				
	25532-09-P	25.5	32	44	78	60	160				
	26032-09-P	26.0	32	44	81	60	163				
	26532-09-P	26.5	32	44	81	60	163		SP□T090308-□□		
	27032-09-P	27.0	32	44	84	60	167		XO□T090305-□□	FTKA0307	TW09S
	27532-09-P	27.5	32	44	84	60	167				
	28032-09-P	28.0	32	44	87	60	171				
	28532-09-P	28.5	32	44	87	60	171				
	29032-09-P	29.0	32	44	90	60	174				
	29532-09-P	29.5	32	44	90	60	174				
	30032-11-P	30.0	32	44	93	60	180	1/4			
	30532-11-P	30.5	32	44	93	60	180				
	31032-11-P	31.0	32	44	96	60	183				
	31532-11-P	31.5	32	44	96	60	183				
	32032-11-P	32.0	32	44	99	60	186				
	32532-11-P	32.5	32	44	99	60	186		SP□T11T308-□□		
	33032-11-P	33.0	32	44	102	60	190		XO□T11T306-□□	FTKA03508	TW15S
	33532-11-P	33.5	32	44	102	60	190				
	34032-11-P	34.0	32	44	105	60	193				
	34532-11-P	34.5	32	44	105	60	193				
	35032-11-P	35.0	32	44	108	60	196				
	35532-11-P	35.5	32	44	108	60	196				


# **KED Plus Drill (3D)**



	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	PT	Insert	Screw	Wrench
BD-	36040-13-P	36.0	40	48	112	70	212				
	36540-13-P	36.5	40	48	112	70	212				
	37040-13-P	37.0	40	48	115	70	215				
	37540-13-P	37.5	40	48	115	70	215				
	38040-13-P	38.0	40	48	118	70	219				
	38540-13-P	38.5	40	48	118	70	219				
	39040-13-P	39.0	40	48	121	70	222		SP□T130410-□□	FTKA0410	TW15S
	39540-13-P	39.5	40	48	121	70	222		XO□T130406-□□	1 11XA0410	1 1 1 1 3 3
	40040-13-P	40.0	40	48	124	70	226				
	40540-13-P	40.5	40	48	124	70	226				
	41040-13-P	41.0	40	48	127	70	229				
	41540-13-P	41.5	40	48	127	70	229				
	42040-13-P	42.0	40	48	130	70	233				
	42540-13-P	42.5	40	48	130	70	233				
	43040-15-P	43.0	40	58	134	70	239				
	43540-15-P	43.5	40	58	134	70	239				
	44040-15-P	44.0	40	58	137	70	242				
	44540-15-P	44.5	40	58	137	70	242				
	45040-15-P	45.0	40	58	140	70	246				
	45540-15-P	45.5	40	58	140	70	246				TW20S
	46040-15-P	46.0	40	58	143	70	249				
	46540-15-P	46.5	40	58	143	70	249		SP□T15M510-□□	FTNC04511	
	47040-15-P	47.0	40	58	146	70	253		XO□T15M508-□□	1111004311	
	47540-15-P	47.5	40	58	146	70	253				
	48040-15-P	48.0	40	58	149	70	256	1/4			
	48540-15-P	48.5	40	58	149	70	256	17-7			
	49040-15-P	49.0	40	58	152	70	259				
	49540-15-P	49.5	40	58	152	70	259				
	50040-15-P	50.0	40	58	155	70	262				
	50540-15-P	50.5	40	58	155	70	262				
	51040-18-P	51.0	40	68	159	70	269				
	51540-18-P	51.5	40	68	159	70	269				
	52040-18-P	52.0	40	68	162	70	272				
	52540-18-P	52.5	40	68	162	70	272				
	53040-18-P	53.0	40	68	165	70	275				
	53540-18-P	53.5	40	68	165	70	275				
	54040-18-P	54.0	40	68	168	70	278				
	54540-18-P	54.5	40	68	168	70	278				
	55040-18-P	55.0	40	68	171	70	281		0007100710		
	55540-18-P	55.5	40	68	171	70	281		SP_T180510	FTNA0511	TW20-10
	56040-18-P	56.0	40	68	174	70	286		XO□T180508-□□		
	56540-18-P	56.5	40	68	174	70	286				
	57040-18-P	57.0	40	68	178	70	290				
	57540-18-P	57.5	40	68	178	70	290				
	58040-18-P	58.0	40	68	182	70	294				
	58540-18-P	58.5	40	68	182	70	294	4			
	59040-18-P	59.0	40	68	186	70	298				
	59540-18-P	59.5	40	68	186	70	298				
	60040-18-P	60.0	40	68	190	70	302				
	60540-18-P	60.5	40	68	190	70	302				


<sup>◆</sup> Applicable inserts F03~04

## **KED Plus Drill (4D)**



											(mı
	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	PT	Insert	Screw	Wrench
E4D-	12020-04-P	12.0	20	25	51	50	115				
	12520-04-P	12.5	20	25	51	50	115		SP□T040204-□□		
	13020-04-P	13.0	20	25	55	50	119		XO□T040204-□□		
	13520-04-P	13.5	20	25	55	50	119				TW06P
	14020-05-P	14.0	20	25	59	50	124			FTNA0204	
	14520-05-P	14.5	20	25	59	50	124		0007050004		
	15020-05-P	15.0	20	25	63	50	129		SP T050204-		
	15520-05-P	15.5	20	25	63	50	129		XO□T050204-□□		
	16020-05-P	16.0	20	25	67	50	133				
	16525-06-P	16.5	25	34	67	56	139				
	17025-06-P	17.0	25	34	71	56	143				
	17525-06-P	17.5	25	34	71	56	143				
	18025-06-P	18.0	25	34	75	56	148	1/8	SP□T060205-□□	FTKA02206S	TW07P
	18525-06-P	18.5	25	34	75	56	148		XO□T060204-□□		
	19025-06-P	19.0	25	34	79	56	152				
	19525-06-P	19.5	25	34	79	56	152				
	20025-07-P	20.0	25	34	83	56	158				
	20525-07-P	20.5	25	34	83	56	158				
	21025-07-P	21.0	25	34	87	56	162				
	21525-07-P	21.5	25	34	87	56	162		SP□T07T208-□□ XO□T07T205-□□		TW07S
	22025-07-P	22.0	25	34	91	56	166			FTKA02565	
	22525-07-P	22.5	25	34	91	56	166		X0_10/1200		
	23025-07-P	23.0	25	34	95	56	172				
	23525-07-P	23.5	25	34	95	56	172				
	24032-09-P	24.0	32	44	99	60	181				
	24532-09-P	24.0	32	44	99	60	181				
	25032-09-P			44	103	60					
	25532-09-P	25.0 25.5	32	44	103		185 185				
				44	103	60	189				
	26032-09-P	26.0	32						OD   T000000		
	26532-09-P	26.5	32	44	107	60	189		SP_T090308-	FTKA0307	TW09S
	27032-09-P	27.0	32	44	111	60	194		XO□T090305-□□		
	27532-09-P	27.5	32	44	111	60	194				
	28032-09-P	28.0	32	44	115	60	199				
	28532-09-P	28.5	32	44	115	60	199				
	29032-09-P	29.0	32	44	119	60	203				
	29532-09-P	29.5	32	44	119	60	203	1/4			
	30032-11-P	30.0	32	44	123	60	210				
	30532-11-P	30.5	32	44	123	60	210				
	31032-11-P	31.0	32	44	127	60	214				
	31532-11-P	31.5	32	44	127	60	214				
	32032-11-P	32.0	32	44	131	60	218				
	32532-11-P	32.5	32	44	131	60	218		SP□T11T308-□□	FTKA03508	TW15S
	33032-11-P	33.0	32	44	135	60	223		XO□T11T306-□□	1110.0000	1.77100
	33532-11-P	33.5	32	44	135	60	223				
	34032-11-P	34.0	32	44	139	60	227				
	34532-11-P	34.5	32	44	139	60	227				
	35032-11-P	35.0	32	44	143	60	231				
	35532-11-P	35.5	32	44	143	60	231				


## **KED Plus Drill (4D)**



											(1
	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	PT	Insert	Screw	Wrench
4D-	36040-13-P	36.0	40	48	148	70	248				
	36540-13-P	36.5	40	48	148	70	248				
	37040-13-P	37.0	40	48	152	70	252				
	37540-13-P	37.5	40	48	152	70	252				
	38040-13-P	38.0	40	48	156	70	257				
	38540-13-P	38.5	40	48	156	70	257				
	39040-13-P	39.0	40	48	160	70	261		SP□T130410-□□	ETI/A0440	TW15S
	39540-13-P	39.5	40	48	160	70	261		XO□T130406-□□	FTKA0410	1 W 133
	40040-13-P	40.0	40	48	164	70	266				
	40540-13-P	40.5	40	48	164	70	266				
	41040-13-P	41.0	40	48	168	70	270				
	41540-13-P	41.5	40	48	168	70	270				
	42040-13-P	42.0	40	48	172	70	275				
	42540-13-P	42.5	40	48	172	70	275				
	43040-15-P	43.0	40	58	177	70	282				
	43540-15-P	43.5	40	58	177	70	282				
	44040-15-P	44.0	40	58	181	70	286				
	44540-15-P	44.5	40	58	181	70	286				
	45040-15-P	45.0	40	58	185	70	291				
	45540-15-P	45.5	40	58	185	70	291				TW20S
	46040-15-P	46.0	40	58	189	70	295				
	46540-15-P	46.5	40	58	189	70	295		SP□T15M510-□□	=======================================	
	47040-15-P	47.0	40	58	193	70	300		XO□T15M508-□□	FTNC04511	
	47540-15-P	47.5	40	58	193	70	300				
	48040-15-P	48.0	40	58	197	70	304				
	48540-15-P	48.5	40	58	197	70	304	1/4			
	49040-15-P	49.0	40	58	201	70	308				
	49540-15-P	49.5	40	58	201	70	308				
	50040-15-P	50.0	40	58	205	70	312				
	50540-15-P	50.5	40	58	205	70	312				
	51040-18-P	51.0	40	68	210	70	320				
	51540-18-P	51.5	40	68	210	70	320				
	52040-18-P	52.0	40	68	214	70	324				
	52540-18-P	52.5	40	68	214	70	324				
	53040-18-P	53.0	40	68	218	70	328				
	53540-18-P	53.5	40	68	218	70	328				
	54040-18-P	54.0	40	68	222	70	332				
	54540-18-P	54.5	40	68	222	70	332				
	55040-18-P	55.0	40	68	226	70	336				
	55540-18-P	55.5	40	68	226	70	336		SP□T180510-□□	ETNIAGE	TM00 400
	56040-18-P	56.0	40	68	230	70	342		XO□T180508-□□	FTNA0511	TW20-100
	56540-18-P	56.5	40	68	230	70	342				
	57040-18-P	57.0	40	68	235	70	347				
	57540-18-P	57.5	40	68	235	70	347				
	58040-18-P	58.0	40	68	240	70	352				
	58540-18-P	58.5	40	68	240	70	352				
	59040-18-P	59.0	40	68	245	70	357				
	59540-18-P	59.5	40	68	245	70	357				
	60040-18-P	60.0	40	68	250	70	362				
	60540-18-P	60.5	40	68	250	70	362				


<sup>◆</sup> Applicable inserts F03~04

## **KED Plus Drill (5D)**



	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	PT	Insert	Screw	Wrench
	10000 04 B	100		05			407				
5D-	12020-04-P	12.0	20	25	63	50	127				
	12520-04-P	12.5	20	25	63	50	127		SP_T040204		
	13020-04-P	13.0	20	25	68	50	132		XO□T040204-□□		
	13520-04-P	13.5	20	25	68	50	132			ETNA0004	TWOCD
	14020-05-P	14.0	20	25	73	50	138			FTNA0204	TW06P
	14520-05-P 15020-05-P	14.5	20	25 25	73 78	50 50	138		SP□T050204-□□		
	15520-05-P	15.5	20	25	78	50	144		XO□T050204-□□		
	16020-05-P	16.0	20	25	83	50	149				
	16525-06-P	16.5	25	34	83	56	155				
	17025-06-P	17.0	25	34	88	56	160				
	17525-06-P	17.5	25	34	88	56	160				
	18025-06-P	18.0	25	34	93	56	166	1/8	SP□T060205-□□	FTKA02206S	TW07P
	18525-06-P	18.5	25	34	93	56	166		XO□T060204-□□	1 110 1022000	111071
	19025-06-P	19.0	25	34	98	56	171				
	19525-06-P	19.5	25	34	98	56	171				
	20025-07-P	20.0	25	34	103	56	178				
	20525-07-P	20.5	25	34	103	56	178			FTKA02565	
	21025-07-P	21.0	25	34	108	56	183				
	21525-07-P	21.5	25	34	108	56	183		SP T07T208-		
	22025-07-P	22.0	25	34	113	56	188				TW07S
	22525-07-P	22.5	25	34	113	56	188				
	23025-07-P	23.0	25	34	118	56	195				
	23525-07-P	23.5	25	34	118	56	195				
	24032-09-P	24.0	32	44	123	60	205				
	24532-09-P	24.5	32	44	123	60	205				
	25032-09-P	25.0	32	44	128	60	210				
	25532-09-P	25.5	32	44	128	60	210				
	26032-09-P	26.0	32	44	133	60	215				
	26532-09-P	26.5	32	44	133	60	215		SP□T090308-□□	FTKA0307	TW09S
	27032-09-P	27.0	32	44	138	60	221		XO□T090305-□□	1 110,0007	1 44030
	27532-09-P	27.5	32	44	138	60	221				
	28032-09-P	28.0	32	44	143	60	227				
	28532-09-P	28.5	32	44	143	60	227				
	29032-09-P	29.0	32	44	148	60	232				
	29532-09-P	29.5	32	44	148	60	232	1/4			
	30032-11-P	30.0	32	44	153	60	240				
	30532-11-P	30.5	32	44	153	60	240				
	31032-11-P	31.0	32	44	158	60	245				
	31532-11-P	31.5	32	44	158	60	245				
	32032-11-P	32.0	32	44	163	60	250		0007117		
	32532-11-P		60	250		SP_T11T308-	FTKA03508	TW15S			
	33032-11-P	33.0	32	44	168	60	256		XO□T11T306-□□		
	33532-11-P	33.5	32	44	168	60	256				
	34032-11-P	34.0	32	44	173	60	261				
	34532-11-P	34.5	32	44	173	60	261				
	35032-11-P	35.0	32	44	178	60	266				
	35532-11-P	35.5	32	44	178	60	266				

# **KED Plus Drill (5D)**



	Designation	ØD	Ød <sub>1</sub>	Ød <sub>2</sub>	Q 1	Q 2	L	PT	Insert	Screw	Wrench
D-	36040-13-P	36.0	40	48	184	70	284				
	36540-13-P	36.5	40	48	184	70	284				
	37040-13-P	37.0	40	48	189	70	289				
	37540-13-P	37.5	40	48	189	70	289				
	38040-13-P	38.0	40	48	194	70	295				
	38540-13-P	38.5	40	48	194	70	295				
	39040-13-P	39.0	40	48	199	70	300		SP□T130410-□□	FTKA0410	TW15S
	39540-13-P	39.5	40	48	199	70	300		XO□T130406-□□	1 11XA0410	1 1 1 1 3 3
	40040-13-P	40.0	40	48	204	70	306				
	40540-13-P	40.5	40	48	204	70	306				
	41040-13-P	41.0	40	48	209	70	311				
	41540-13-P	41.5	40	48	209	70	311				
	42040-13-P	42.0	40	48	214	70	317				
	42540-13-P	42.5	40	48	214	70	317				
	43040-15-P	43.0	40	58	220	70	325				
	43540-15-P	43.5	40	58	221	70	326				
	44040-15-P	44.0	40	58	225	70	330				
	44540-15-P	44.5	40	58	225	70	330				
	45040-15-P	45.0	40	58	230	70	336			FTNC04511	TW20S
	45540-15-P	45.5	40	58	230	70	336				
	46040-15-P	46.0	40	58	235	70	341				
	46540-15-P	46.5	40	58	235	70	341		SP□T15M510-□□		
	47040-15-P	47.0	40	58	240	70	347		XO□T15M508-□□		
	47540-15-P	47.5	40	58	240	70	347				
	48040-15-P	48.0	40	58	245	70	352	1/4			
	48540-15-P	48.5	40	58	245	70	352	17-7			
	49040-15-P	49.0	40	58	250	70	357				
	49540-15-P	49.5	40	58	250	70	357				
	50040-15-P	50.0	40	58	255	70	362				
	50540-15-P	50.5	40	58	255	70	362				
	51040-18-P	51.0	40	68	261	70	371				
	51540-18-P	51.5	40	68	261	70	371				
	52040-18-P	52.0	40	68	266	70	376				
	52540-18-P	52.5	40	68	266	70	376				
	53040-18-P	53.0	40	68	271	70	381				
	53540-18-P	53.5	40	68	271	70	381				
	54040-18-P	54.0	40	68	276	70	386				
	54540-18-P	54.5	40	68	276	70	386				
	55040-18-P	55.0	40	68	281	70	391		0007400710		
	55540-18-P	55.5	40	68	281	70	391		SP_T180510-	FTNA0511	TW20-10
	56040-18-P	56.0	40	68	286	70	398		XO□T180508-□□		
	56540-18-P	56.5	40	68	286	70	398				
	57040-18-P	57.0	40	68	292	70	404				
	57540-18-P	57.5	40	68	292	70	404				
	58040-18-P	58.0	40	68	298	70	410				
	58540-18-P	58.5	40	68	298	70	410				
	59040-18-P	59.0	40	68	304	70	416				
	59540-18-P	59.5	40	68	304	70	416				
	60040-18-P	60.0	40	68	310	70	422				
	60540-18-P	60.5	40	68	310	70	422				

<sup>◆</sup> Applicable inserts F03~04



High quality and high feed top solid indexable drill


### **TPDC Plus Drill**

### (TPDC-XP, CP, CM, CN, CP-FC)


- The optimal tool shape for drilling realizing high precision and high feed machining as of carbide solid drill performance level
- Usable for various machining through enlarged line-up by workpieces, depth of cuts and workpiece shapes

#### Code system

Insert




Holder




#### Features


- · One step clamp system Increased stability and shortened setting time
- · High helix angle and flute polishing Reduced cutting load and enhanced chip evacuation
- Various applications from enlarged line-up by depth of cuts and shapes of workpiece



### **Technical Information for TPDC Plus Drill**

#### Application range





#### Run-out

#### **Durability evaluation**


■ Workpiece Alloy steel (SCM440, HRC22)

vc (m/min) = 90, fn (mm/rev) = 0.25 Cutting conditions ap (mm) = 60, wet (10bar)

Insert TPD1500CP(PC5335) ■ Tools Holder TPDC5D-15020-75

(Drill dia. = Ø15 mm)

### Clamping repeatability evaluation



Excellent clamping system keeping the run-out, lower than 6 µm after clamping 150 times repeatedly

#### Performance evaluation


#### **Precision**

■ Workpiece Carbon steel (SM45C, HRC19)

vc (m/min) = 60, fn (mm/rev) = 0.2Cutting conditions ap (mm) = 150, wet (20bar)


TPD1500CP (PC5335) ■ Tools Holder TPDC12D-15020-170

(Drill dia. = Ø15 mm)



60

vc (m/min)



High precision in deep hole-making


■ Workpiece Carbon steel (SM45C, HRC18)

Cutting vc (m/min) = 60~100conditions fn (mm/rev) = 0.2~0.3

ap (mm) = 50, wet (20 bar)

TPD2000CP-FC (PC5335) ■ Tools Insert Holder

TPDC3D-20025-60




**TPDC-CP-FC** Hole — Competitor diameter (mm) Ø20.030 Ø20.025 Ø20.020 Ø20.015 Ø20.010 Ø20.005 Ø20.000 Ø19 995 Drilling part End Beginning End Beginning Middle End Beainnina Middle Middle 0.25 0.20 0.25 0.25 0.30 0.30 fn (mm/rev)

80

100

High precision and excellent centering due to profiled cutting edge

#### Performance evaluation



■ Workpiece Carbon steel (SM45C, HRC18)

Cutting vc (m/min) = 100 conditions fn (mm/rev) = 0.25


ap (mm) = 50, wet (10bar)

TPD2000CP-FC (PC5335) ■ Tools

> TPDC3D-20025-60 Holder

(Drill dia. = Ø20 mm)

Low and stable cutting load due to profiled-cutting edge



#### Application examples

Part of machine ■ Use

Alloy steel (SCM440, HRC22) ■ Workpiece


vc (m/min) = 100 Cutting conditions fn (mm/rev) = 0.3

ap (mm) = 90, wet

TPD1900CP (PC5335) ■ Tools Insert

Holder TPDC5D-19025-95

(Drill dia.(mm) =  $\emptyset$ 19.0)





Competitor



· Lubricative multi-layer coating prevents chipping on cutting edges

■ Use Part of machine

■ Workpiece Carbon steel (SM45C, HRC40)

Cutting vc (m/min) = 60 conditions fn (mm/rev) = 0.15ap (mm) = 65, wet

■ Tools Insert TPD1800CP(PC5335)

> Holder TPDC5D-18025-90

(Drill dia.(mm) = Ø18.0)





· Lubricative multi-layer coating enhances wear resistance

### F

### **Technical Information for TPDC Plus Drill**

#### Application examples

■ Use Tube sheet

■ Workpiece Carbon steel (S235JR, HRC18)


■ Cutting vc (m/min) = 85 conditions n (rpm) = 1381

fn (mm/rev) = 0.27


ap (mm) = 12mm x 3Passes, wet

■ Tools Insert TPD1960CP (PC330P)

Holder TPDC3D-19025-57



#### ■ Test result



 Optimized cutting edge enhances wear resistance due to stable cutting load and lubricated multi-layer coating

■ Use Turret flange

■ Workpiece Alloy steel (SCM440, HRC22)

■ Cutting vc (m/min) = 82 conditions n (rpm) = 2000


fn (mm/rev) = 0.2ap (mm) = 95, wet

■ Tools Insert TPD1300CP (PC5335)

Holder TPDC8D-13016-104



#### ■ Test result



• Lubricated multi-layer coating improving chipping resistance prevents chipping on the cutting edge

#### Insert features

Shape	Application	Drill dia. (mm)	Features
XP new	P	Ø8.00~Ø11.99	High durability due to the strong clamping system  Excellent quality of machining and stable machining from high clamping force  Enhanced performance by high lubricated grade
СР	PK	Ø12.00~Ø30.99	High quality machining due to excellent centering: Good roundness and surface finish     Excellent chip control from exclusive edge design: Stable machining by good chip forming and chip evacuation
CM new	M	Ø12.00~Ø30.99	Ensuring strength of point and cutting edge: Stable machinability     Increased stability of machining due to low cutting load     Applied grade with high built up edge resistance and chipping resistance
CN (18W)	N	Ø12.00~Ø30.99	Cutting edge with low cutting load: Excellent chip evacuation from increased surface finish of insert by special after treatment  Long tool life due to ultra-fine substrate application
CP-FC (C	P	Ø12.00~Ø30.99	Cutting edge shape with excellent centering: Stable machinability from low cutting load     Available in various machining applications: Flat surface, angled surface, curved surface drilling, plunging and boring     Reduced cycle time by simplified tools: Endmill+drill machining → TPDC-CP-FC insert

#### How to clamp insert

#### Using the improved wrench

· Using the insert with slot on the top (Use the improved inserts only)



Clean the mounting seat with air or cloth

2 Put an insert on the holder

3 Put the wrench in the slot parallel







Clamped state

#### Using the existing wrench

• Using any inserts (Use both existing inserts and improved inserts)





2 Put an insert on the holder

3 A part of wrench and B part of insert must beparallel to each other before clamp the insert Turn the wrench clockwise to finish clamping

Use only the improved wrench later



Clamped state

Drills



### **Technical Information for TPDC Plus Drill**

### **○** Recommended cutting conditions (TPDC-XP)

#### • 3D Drilling

		Warknings				Aspect ratio (L/D) = 3D		
		Workpiece		Grade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)		
	ISO	Workpiece	НВ		(11211111)	Ø8.00~Ø9.99	Ø10.00~Ø11.99	
P	Carbon steel	Low carbon steel	80~120	PC325U	110 (80~140)	0.12~0.22	0.15, 0.29	
ľ	Carbon Steer	High carbon steel	180~280	PC325U	90 (70~110)	0.12~0.22	0.15~0.28	
		Low alloy steel	140~260	PC325U	90 (70~110)	0.12~0.20	0.14~0.25	
P	Alloy steel	Low alloy heat-treated steel	200~400	PC325U	70 (50~90)	0.12~0.20	0.14~0.25	
ľ	Alloy Steel	High alloy steel	260~320	PC325U	70 (50~90)	0.10~0.15	0.12~0.18	
		High alloy heat-treated steel	300~450	PC325U	60 (40~80)	0.10~0.15	0.12~0.16	
K	Cast iron	Gray cast iron	150~230	PC325U	125 (90~160)	0.15~0.30	0.20~0.35	
	Cast IIOII	Ductile cast iron	160~260	PC325U	110 (80~140)	0.15~0.50	0.20~0.33	

 $<sup>\,\,</sup>$ % In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part

#### • 5D Drilling

		Worknings				Aspect ratio (L/D) = 5D  Feed rate (mm/rev) per drill dia. (mm)		
		Workpiece		Grade	vc (m/min)			
	ISO	Workpiece	НВ		(110/11111)	Ø8.00~Ø9.99	Ø10.00~Ø11.99	
P	Corbon stool	Low carbon steel	80~120	PC325U	110 (80~140)	0.12~0.22	0.45, 0.00	
	Carbon steel	High carbon steel	180~280	PC325U	90 (70~110)	0.12~0.22	0.15~0.28	
		Low alloy steel	140~260	PC325U	90 (70~110)	0.40, 0.00	0.14~0.25	
P	Alloy steel	Low alloy heat-treated steel	200~400	PC325U	70 (50~90)	0.12~0.20		
	Alloy Steel	High alloy steel	260~320	PC325U	70 (50~90)		0.40.040	
		High alloy heat-treated steel	300~450	PC325U	60 (40~80)	0.10~0.15	0.12~0.18	
К	On at large	Gray cast iron	150~230	PC325U	125 (90~160)	0.15~0.30	0.20~0.35	
TA.	Cast iron	Ductile cast iron	ctile cast iron 160~260		110 (80~140)	0.15~0.30	0.20~0.35	

 $<sup>\,\,</sup>$ % In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part

#### 8D Drilling

		Moulmine				Aspect ratio (L/D) = 8D		
		Workpiece		Grade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)		
	ISO	Workpiece	НВ		(11211111)	Ø8.00-Ø9.99	Ø10.00-Ø11.99	
P	Onub - 11 - 11 - 1	Low carbon steel	80~120	PC325U	100 (70~130)	0.10~0.20	0.12~0.25	
	Carbon steel	High carbon steel	180~280	PC325U	80 (60~100)	0.10~0.20		
		Low alloy steel	140~260	PC325U	80 (60~100)	0.10, 0.10	0.12~0.20	
P	Alley steel	Low alloy heat-treated steel	200~400	PC325U	60 (40~80)	0.10~0.18	0.12~0.20	
	Alloy steel	High alloy steel	260~320	PC325U	60 (40~80)	0.00.040		
		High alloy heat-treated steel	300~450	PC325U	50 (30~70)	0.09~0.13	0.10~0.16	
K	Coativen	Gray cast iron	150~230	PC325U	115 (80~150)	0.10.0.07	0.17~0.32	
	Cast iron	Ductile cast iron	160~260	PC325U	100 (70~130)	0.12~0.27		

<sup>\*</sup> In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part

<sup>\*</sup> In case of 8D drilling, please use a Pilot Dirll



### **②** Recommended cutting conditions (TPDC-CP/CM/CN)

#### • 1.5D/3D Drilling

		Wastraiaaa					Asp	Aspect ratio (L/D) = 1.5D, 3D			
		Workpiece		Insert	Grade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)				
	ISO	Workpiece	НВ			(111/111111)	Ø12.00~Ø17.99	Ø18.00~Ø25.99	Ø26.00~Ø30.99		
	Carbon steel	Low carbon steel	80~120	СР	PC5335 PC330P	120 (90~140)	0.25~0.35	0.30~0.40	0.35~0.45		
	Carbon steer	High carbon steel	180~280	СР	PC5335 PC330P	110 (80~130)	0.25~0.35	0.30~0.40	0.30~0.45		
P		Low alloy steel	140~260	СР	PC5335 PC5300	120 (90~140)	0.28~0.40	0.33~0.43	0.38~0.48		
	Alloy stool	Low alloy heat-treated steel	200~400	СР	PC5335 PC5300	80 (60~100)	0.28~0.40	0.33~0.43	0.30~0.48		
	Alloy steel	High alloy steel	260~320	СР	PC5335 PC5300	75 (60~90)	0.20~0.35	0.22~0.40	0.25~0.45		
		High alloy heat-treated steel	300~450	СР	PC5335 PC5300	65 (50~80)	0.20~0.35	0.22~0.40	0.22~0.45		
М	Stainless	Austenitic	135~275	СМ	PC330N	65 (50~80)	0.05~0.15	0.10~0.20	0.15~0.25		
141	steel	Ferritic, martensitic	135~275	СМ	PC330N	75 (60~90)	0.10~0.20	0.15~0.30	0.20~0.35		
K	Cast iron	Gray cast iron	150~230	СР	PC5335 PC5300	130 (90~140)	0.35~0.45	0.40~0.50	0.45~0.55		
K	Cast Iron	Ductile cast iron	160~260	СР	PC5335 PC5300	120 (80~130)	0.30~0.40	0.30~0.45	0.40~0.50		
N	Non-ferrous	Aluminum	30~150	CN	H01	200 (120~220)	0.35~0.45	0.40~0.50	0.45~0.55		
N	metal	Copper alloy	150~160	CN	H01	200 (120~220)	0.35~0.45	0.40~0.50	0.45~0.55		

 $<sup>\,\,^{\</sup>times}$  In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part

#### • 5D Drilling

		Wasteniaga					Aspect ratio (L/D) = 5D			
		Workpiece		Insert	Grade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)			
	ISO	Workpiece	НВ			()	Ø12.00-Ø17.99	Ø18.00-Ø25.99	Ø26.00-Ø30.99	
	Carbon steel	Low carbon steel	80~120	СР	PC5335 PC330P	110 (80~140)	0.15~0.30	0.20~0.35	0.25~0.40	
	Carbon steer	High carbon steel	180~280	СР	PC5335 PC330P	100 (70~130)	0.15~0.30	0.20~0.35	0.25~0.40	
P		Low alloy steel	140~260	СР	PC5335 PC5300	110 (80~140)	0.18~0.35	0.23~0.38	0.28~0.43	
	Alloy steel	Low alloy heat-treated steel	200~400	СР	PC5335 PC5300	75 (50~100)	0.18~0.35	0.23~0.38	0.28~0.43	
	Alloy Steel	High alloy steel	260~320	СР	PC5335 PC5300	70 (50~90)	0.18~0.30	0.20~0.35	0.25~0.40	
		High alloy heat-treated steel	300~450	СР	PC5335 PC5300	60 (40~80)	0.18~0.30	0.20~0.35	0.22~0.40	
м	Stainless	Austenitic	135~275	СМ	PC330N	60 (40~80)	0.05~0.15	0.10~0.20	0.15~0.25	
	steel	Ferritic, martensitic	135~275	СМ	PC330N	70 (50~90)	0.10~0.20	0.15~0.30	0.20~0.35	
K		Gray cast iron	150~230	СР	PC5335 PC5300	120 (80~140)	0.25~0.40	0.30~0.45	0.35~0.50	
-	Cast iron	Ductile cast iron	160~260	СР	PC5335 PC5300	110 (70~130)	0.20~0.35	0.25~0.40	0.30~0.45	
N	Non-ferrous metal	Aluminum	30~150	CN	H01	200 (90~220)	0.35~0.45	0.40~0.50	0.45~0.55	
N		Copper alloy	150~160	CN	H01	200 (90~220)	0.35~0.45	0.40~0.50	0.45~0.55	

 $<sup>\,\,^{\</sup>times}$  In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part

<sup>\*</sup> In stainless steel machining, start with low feed machining then, gradually get the cutting conditions higher and set the optimal cutting conditions

<sup>\*</sup> In stainless steel machining, start with low feed machining then, gradually get the cutting conditions higher and set the optimal cutting conditions



### **Technical Information for TPDC Plus Drill**

#### 8D Drilling

		Workpiece					A	spect ratio (L/D) = 8	BD		
		Workpiece		Insert	Graade	vc (m/min)	Feed rat	Feed rate (mm/rev) per drill dia. (mm)			
	ISO	Workpiece	НВ			(11211111)	Ø12.00-Ø17.99	Ø18.00~Ø25.99	Ø26.00-Ø30.99		
	Carbon steel	Low carbon steel	80~120	CP	PC5335 PC330P	100 (70~130)	0.12~0.25	0.17~0.30	0.22~0.35		
	Carbon steel	High carbon steel	180~280	CP	PC5335 PC330P	90 (60~120)	0.12~0.25	0.17~0.30	0.22~0.35		
P		Low alloy steel	140~260	CP	PC5335 PC5300	100 (70~130)	0.15~0.30	0.20~0.33	0.25~0.38		
	Alloy steel	Low alloy heat-treated steel	200~400	CP	PC5335 PC5300	65 (40~90)	0.15~0.30	0.20~0.33	0.25~0.38		
		High alloy steel	260~320	CP	PC5335 PC5300	60 (40~80)	0.15~0.25	0.17~0.30	0.22~0.35		
		High alloy heat-treated steel	300~450	СР	PC5335 PC5300	50 (30~70)	0.15~0.25	0.17~0.30	0.22~0.35		
М	Stainless	Austenitic	135~275	СМ	PC330N	50 (30~70)	0.05~0.10	0.05~0.15	0.10~0.20		
	steel	Ferritic, martensitic	135~275	CM	PC330N	60 (40~80)	0.05~0.15	0.10~0.25	0.15~0.30		
K		Gray cast iron	150~230	СР	PC5335 PC5300	110 (70 ~130)	0.22~0.35	0.27~0.40	0.32~0.45		
K	Cast iron	Ductile cast iron	160~260	СР	PC5335 PC5300	100 (60~120)	0.17~0.30	0.22~0.35	0.27~0.40		
N	Non-ferrous metal	Aluminum	30~150	CN	H01	190 (80~200)	0.30~0.40	0.35~0.45	0.40~0.50		
- 14		Copper alloy	150~160	CN	H01	190 (80~200)	0.30~0.40	0.35~0.45	0.40~0.50		

#### • 10D/12D Drilling

		Worknings					Aspe	ect ratio (L/D) = 10D	, 12D	
		Workpiece		Insert	Grade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)			
	ISO	Workpiece	НВ			()	Ø12.00~Ø17.99	Ø18.00~Ø25.99	Ø26.00~Ø30.99	
	Carbon steel	Low carbon steel	80~120	СР	PC5335 PC330P	90 (60~120)	0.10~0.20	0.15~0.25	0.20~0.30	
	Carbon Steel	High carbon steel	180~280	СР	PC5335 PC330P	80 (50~110)	0.10~0.20	0.15~0.25	0.20~0.30	
P		Low alloy steel	140~260	СР	PC5335 PC5300	90 (60~120)	0.13~0.25	0.18~0.28	0.23~0.33	
	Alloy steel	Low alloy heat-treated steel	200~400	СР	PC5335 PC5300	55 (40~80)	0.13~0.30	0.18~0.28	0.23~0.33	
		High alloy steel	260~320	СР	PC5335 PC5300	50 (40~70)	0.13~0.25	0.15~0.25	0.20~0.30	
		High alloy heat-treated steel	300~450	СР	PC5335 PC5300	40 (30~60)	0.13~0.25	0.15~0.25	0.20~0.30	
М	Stainless	Austenitic	135~275	СМ	PC330N	50 (30~60)	0.05~0.10	0.05~0.15	0.10~0.20	
141	steel	Ferritic, martensitic	135~275	СМ	PC330N	60 (40~70)	0.05~0.15	0.10~0.25	0.15~0.30	
K	Continue	Gray cast iron	150~230	СР	PC5335 PC5300	100 (60~120)	0.20~0.30	0.25~0.35	0.30~0.40	
T.	Cast iron	Ductile cast iron	160~260	СР	PC5335 PC5300	90 (50~110)	0.15~0.25	0.20~0.30	0.25~0.35	
N	Non-ferrous metal	Aluminum	30~150	CN	H01	180 (70~190)	0.28~0.35	0.33~0.40	0.38~0.45	
N		Copper alloy	150~160	CN	H01	180 (70~190)	0.28~0.35	0.33~0.40	0.38~0.45	

<sup>\*</sup> In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part

 <sup>\*\*</sup> In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part
 \*\* In stainless steel machining, start with low feed machining then, gradually get the cutting conditions higher and set the optimal cutting conditions

<sup>\*</sup> In case of 10D and 12D, apply the recommended cutting conditions in the other side

<sup>\*</sup> In stainless steel machining, start with low feed machining then, gradually get the cutting conditions higher and set the optimal cutting conditions



#### Recommended cutting conditions (TPDC-CP-FC)

		Workpiece				Aspect ratio (L/D) = 1.5D, 3D, 5D)			
				Graade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)			
	ISO Workpiece HB		НВ		()	Ø12.00-Ø17.99	Ø18.00-Ø25.99	Ø26.00-Ø30.99	
	Carbon steel	Low carbon steel (SM10C, SM20C etc)	80~120	PC5335	90 (70~110)	0.18~0.28	0.2~0.3	0.23~0.33	
P		High carbon steel (SM45C, SM50C etc)	180~280		80 (60~100)	0.18~0.28	0.2~0.3	0.23~0.33	
	Alloy steel	Low alloy steel (SCM420, SCM440 etc)	140~260		90 (70~110)	0.18~0.28	0.2~0.3	0.23~0.33	
	Alloy Steel	High alloy steel (SCM435, SCM445 etc)	260~320		70 (50~90)	0.18~0.28	0.2~0.3	0.23~0.33	

Machining	Flat surface drilling	Angled surface drilling	Curved surface drilling	Plunging	Boring
Pic.					
1.5D/3D	0	0	0	0	0
5D	0	X	X	X	X

<sup>\*</sup> Please refer to the precaution in drilling in case of angled surface drilling, curved surface drilling, plunging and boring

#### ● How to drill a deep hole (10D/12D)

Using a pilot drill (recommended)

#### 1. Drilling a pilot hole (with a pilot drill)



• Drill a 0.5D pilot hole in 70% lower cutting speed with 1.5D drill or 3D drill


#### 2. Start drilling



· Start drilling in recommended cutting conditions after replacing the drill

#### · Without pilot drill

#### 1. Drilling a pilot hole (without a pilot drill)



• After drill 0.5D with 70% lower cutting speed, stop drilling for 2-3 seconds putting the drill in the hole

#### 2. Stop drilling



· Stop supplying the coolant and take out the drill from the hole. Then, stop drilling for 2-3 seconds

#### 3. Ready to drill



• After putting the drill in the hole to 2-3 mm upper than the bottom of the pilot hole, start supplying the coolant. Then, be ready to start drilling

#### 4. Stop drilling



· Start drilling in recommended cutting conditions

### **Technical Information for TPDC Plus Drill**

#### Precaution in drilling

#### · TPDC-CP/CM/CN

#### Angled surface drilling



- The approach angle between drill and the workpiece at the beginning and the end should be less than 6°
- Reduce the feed (fn) to 30-50% than general cutting conditions at the beginning and the end of angled surface

#### Stacked plates drilling



- Gap between the plates could make wrong chip evacuation causing fracture of the drill
- Place stacked plates without any gap between each

#### **Plunging**



 Irregular cutting resistance in plunging could cause fracture and deformation of the drill

#### **Boring**



 Boring is not recommended due to wear and chipping in the corner of the insert


#### · TPDC-CP-FC

#### Angled surface drilling




• Reduce the feed (fn) to 30% than general cutting conditions at the beginning and the end of angled surface (Recommended only in case of  $\theta$  is less than 10°)

#### **Curved surface drilling**



 Reduce the feed (fn) to 30% than general cutting conditions at the beginning of curved surface (In case, θ is over 30°, reduce it to 50%)

#### **Plunging**



- Reduce the depth of cut (ae) to shorter than 1/2 of drill diameter
- In case, the depth of cut is longe than drill diameter, plunge with divided depth of cut


#### Boring



- Reduce the feed (fn) to 30% than general cutting conditions at the beginning of boring
- Start with 2 mm stepping before boring to prevent long chip

#### Check point in drilling

- · Condition of the clamped workpiece
- · Revolution of the main axis of the machine
- · Condition of the holder
- Run-out of the clamped drill (Max. 0.03 mm)
- Condition of supplying coolant (pressure, flow, concentration)
- · Chip evacuation




Setting of the horizontal equipment



Setting of the vertical equipment

#### Supply of coolant

- · Supply enough coolant to the beginning of the hole
- · Minimum pressure of oil coolant: 5 bar
- Minimum flow of coolant: 5 l/min








#### Available insert









Drill dia.	P type (XP)	Coated	Ualdan	Wyonob		
ØD (mm)	TPDC-XP	PC325U	Holder	Wrench		
8.0	TPD0800XP	•				
8.1	TPD0810XP	•				
8.2	TPD0820XP	•	TPDX□D-08012-□			
8.3	TPD0830XP	•				
8.4	TPD0840XP	•				
8.5	TPD0850XP	•				
8.6	TPD0860XP	•				
8.7	TPD0870XP	•	TPDX□D-08512-□			
8.8	TPD0880XP	•				
8.9	TPD0890XP	•				
9.0	TPD0900XP	•				
9.1	TPD0910XP	•				
9.2	TPD0920XP	•	TPDX□D-09012-□			
9.3	TPD0930XP	•				
9.4	TPD0940XP	•				
9.5	TPD0950XP	•				
9.6	TPD0960XP	•				
9.7	TPD0970XP	•	TPDX□D-09512-□			
9.8	TPD0980XP	•				
9.9	TPD0990XP	•	TDDV/DD 40040 D	TPDC -W0811		
10.0	TPD1000XP	•		200011		
10.1	TPD1010XP	•				
10.2	TPD1020XP	•	TPDX□D-10016-□			
10.3	TPD1030XP	•				
10.4	TPD1040XP	•				
10.5	TPD1050XP	•				
10.6	TPD1060XP	•				
10.7	TPD1070XP	•	TPDX□D-10516-□			
10.8	TPD1080XP	•				
10.9	TPD1090XP	•				
11.0	TPD1100XP	•				
11.1	TPD1110XP	•				
11.2	TPD1120XP	•	TPDX□D-11016-□			
11.3	TPD1130XP	•				
11.4	TPD1140XP	•		-		
11.5	TPD1150XP	•				
11.6	TPD1160XP	•	TDDV \( \tau \)			
11.7	TPD1170XP	•	TPDX□D-11516-□			
11.8	TPD1180XP	•				
11.9	TPD1190XP	•				

\* We can provide if you order exact machining specification

•: Stock Item

### Parts (applicable wrench)

Picture	Designation	Drill diameter ØD (mm)	Torque (N·m)
	TPDC-W0811	8.00-11.99	0.7-1.5

### F TPDC Plus Drill


#### Available insert











		P type (	CP)		M type (CM)		N type (CN)			
Drill dia.			Coated			Coated		Uncoated	Holder	Wrench
ØD(mm)	TPDC-CP	PC5335	PC5300	PC330P	TPDC-CM	PC330N	TPDC-CN	H01		
12.0	TPD1200CP	•			TPD1200CM	•	TPD1200CN		TDD0	
12.2	TPD1220CP	•			TPD1220CM	•	TPD1220CN		TPDC□D-12016-□	
12.5	TPD1250CP	•			TPD1250CM	•	TPD1250CN		TDD0 D 40540 D	
12.6	TPD1260CP	•			TPD1260CM	•	TPD1260CN		TPDC□D-12516-□	
13.0	TPD1300CP	•			TPD1300CM	•	TPD1300CN		TPDC D-13016-	
13.5	TPD1350CP	•			TPD1350CM	•	TPD1350CN		TPDC□D-13516-□	
14.0	TPD1400CP	•			TPD1400CM	•	TPD1400CN		TPDC□D-14016-□	
14.2	TPD1420CP	•			TPD1420CM	•	TPD1420CN			TPDC-
14.3	TPD1430CP	•			TPD1430CM	•	TPD1430CN			W1216
14.5	TPD1450CP	•			TPD1450CM	•	TPD1450CN		TPDC D-14516-	VVIZIO
15.0	TPD1500CP	•			TPD1500CM	•	TPD1500CN			
15.2	TPD1520CP	•			TPD1520CM	•	TPD1520CN		TPDC□D-15020-□	
15.5	TPD1550CP	•			TPD1550CM	•	TPD1550CN			
16.0	TPD1600CP	•			TPD1600CM	•	TPD1600CN			
16.3	TPD1630CP	•			TPD1630CM	•	TPD1630CN			
16.5	TPD1650CP	•			TPD1650CM	•	TPD1650CN		TPDC □ D-16020- □	
16.7	TPD1670CP	•			TPD1670CM	•	TPD1670CN			
16.9	TPD1690CP	•			TPD1690CM	•	TPD1690CN			
17.0	TPD1700CP	•			TPD1700CM	•	TPD1700CN			
17.5	TPD1750CP	•			TPD1750CM	•	TPD1750CN		TPDC□D-17020-□	_
17.7	TPD1770CP	•			TPD1770CM	•	TPD1770CN		TPDC□D-18025-□	
18.0	TPD1800CP	•			TPD1800CM	•	TPD1800CN			
18.1	TPD1810CP	•			TPD1810CM	•	TPD1810CN			
18.5	TPD1850CP	•			TPD1850CM	•	TPD1850CN			
18.6	TPD1860CP	•			TPD1860CM	•	TPD1860CN			
18.7	TPD1870CP	•			TPD1870CM	•	TPD1870CN			TPDC- W1721
19.0	TPD1900CP	•			TPD1900CM	•	TPD1900CN			
19.2	TPD1920CP	•			TPD1920CM		TPD1920CN			
19.3	TPD1930CP	•			TPD1930CM	•	TPD1930CN		TPDC□D-19025-□	
19.5	TPD1950CP	•			TPD1950CM	•	TPD1950CN			
19.7	TPD1970CP	•			TPD1970CM	•	TPD1970CN			
20.0	TPD2000CP	•			TPD2000CM	•	TPD2000CN		TPDC D-20025-	
20.5	TPD2050CP	•			TPD2050CM	•	TPD2050CN			
21.0	TPD2100CP	•			TPD2100CM	•	TPD2100CN		TPDC □ D-21025- □	
21.5	TPD2150CP	•			TPD2150CM	•	TPD2150CN			
22.0	TPD2200CP	•			TPD2200CM	•	TPD2200CN			
22.5	TPD2250CP	•			TPD2250CM	•	TPD2250CN		TPDC □ D-22025- □	
22.6	TPD2260CP	•			TPD2260CM	•	TPD2260CN			
22.7	TPD2270CP	•			TPD2270CM	•	TPD2270CN			
23.0	TPD2300CP	•			TPD2300CM	•	TPD2300CN		TPDC □ D-23025- □	
23.5	TPD2350CP				TPD2350CM		TPD2350CN			TPDC-
24.0	TPD2400CP				TPD2400CM		TPD2400CN		TPDC □ D-24032- □	W2225
24.5	TPD2450CP				TPD2450CM		TPD2450CN			-
25.0	TPD2500CP				TPD2500CM		TPD2500CN			
25.3	TPD2530CP				TPD2530CM		TPD2530CN		TPDC□D-25032-□	
25.5	TPD2550CP				TPD2550CM		TPD2550CN		1FDC_D-23032	
25.8	TPD2580CP TPD2590CP				TPD2580CM		TPD2580CN			
25.9 26.0	TPD2590CP				TPD2590CM		TPD2590CN		_	
26.5	TPD2650CP				TPD2600CM TPD2650CM		TPD2600CN TPD2650CN		TPDC □ D-26032- □	
27.0	TPD2650CP				TPD2650CM		TPD2700CN			-
27.5	TPD2750CP				TPD2750CM		TPD2700CN		TPDC□D-27032-□	
28.0	TPD2750CP				TPD2750CM		TPD2750CN		_	TPDC-
28.5	TPD2850CP				TPD2850CM		TPD2850CN		TPDC□D-28032-□	TPDC- W2630
29.0	TPD2900CP				TPD2900CM		TPD2900CN		_	
29.5	TPD2950CP				TPD2950CM		TPD2950CN		TPDC □ D-29032- □	
	1 2 2 2 3 3 0 6 2	_			I PDZ 930CIVI	_	I FDZ93UCN		11 DO D-58095-	
30.0	TPD3000CP	•			TPD3000CM	•	TPD3000CN		TPDC□D-30032-□	

imes We can provide if you order exact machining specification Ex)  $ilde{ ilde{Q}}15.9$  and carbon steel machining o TPDC1590CP/PC330P

### Parts (applicable wrench)


Picture		Designation	Drill diameter ØD (mm)	Torque (N·m)
	TPDC-	W1216	12.00-16.99	2.0-3.0
		W1721	17.00-21.99	2.0-4.0
- 1		W2225	22.00-25.99	3.0-4.0
		W2630	26.00-30.99	4.0-5.0

<sup>:</sup> Stock Item

#### Available insert



FC



Daill alla	FC type (CP-FC)			Chamf	er (mm)	
Drill dia. ØD(mm)	TDD0 0D F0	Coated	Holder	_		Wrench
(וווווו)	TPDC-CP-FC	PC5335		а	b	
12.0	TPD1200CP-FC		TPDC□D-12016-□			
12.2	TPD1220CP-FC		1FDC D-12010-			
12.5	TPD1250CP-FC		TPDC□D-12516-□			
12.6	TPD1260CP-FC					
13.0	TPD1300CP-FC		TPDC □ D-13016- □			
13.5	TPD1350CP-FC		TPDC□D-13516-□			
14.0	TPD1400CP-FC		TDD 0 0 0 1 10 10 0			TDDO MAGA
14.2	TPD1420CP-FC		TPDC□D-14016-□	0.38	0.38 0.45	TPDC-W1216
14.3	TPD1430CP-FC		TDD0000 14540 0	_		
14.5	TPD1450CP-FC		TPDC□D-14516-□	_		
15.0 15.5	TPD1500CP-FC TPD1550CP-FC		TPDC □ D-15020- □			
16.0	TPD1550CP-FC					
16.3	TPD1630CP-FC					
16.5	TPD1650CP-FC		TPDC □ D-16020- □			
16.7	TPD1670CP-FC					
17.0	TPD1070CP-FC					
17.5	TPD1750CP-FC		TPDC□D-17020-□			
17.7	TPD1770CP-FC		11 0000 17020			
18.0	TPD1800CP-FC					
18.1	TPD1810CP-FC					
18.5	TPD1850CP-FC		TPDC □ D-18025- □			
18.6	TPD1860CP-FC					
18.7	TPD1870CP-FC					TDD 0 144.704
19.0	TPD1900CP-FC		TDDC D 10005 D			TPDC-W1721
19.2	TPD1920CP-FC					
19.5	TPD1950CP-FC		TPDC□D-19025-□			
19.7	TPD1970CP-FC					
20.0	TPD2000CP-FC		TPDC□D-20025-□			
20.5	TPD2050CP-FC		TFDC_D-20025			
21.0	TPD2100CP-FC		TPDC□D-21025-□	0.46	0.55	
21.5	TPD2150CP-FC					
22.0	TPD2200CP-FC					
22.5	TPD2250CP-FC		TPDC □ D-22025- □			
22.6	TPD2260CP-FC					
22.7	TPD2270CP-FC					
23.0	TPD2300CP-FC		TPDC □ D-23025- □			
23.5	TPD2350CP-FC TPD2400CP-FC			_		TPDC-W2225
24.0	TPD2400CP-FC		TPDC □ D-24032- □			1FDG-W2223
25.0	TPD2450CP-FC			$\dashv$		
25.3	TPD2530CP-FC					
25.5	TPD2550CP-FC		TPDC□D-25032-□			
25.8	TPD2580CP-FC		50-5 20002			
25.9	TPD2590CP-FC					
26.0	TPD2600CP-FC		TDD0\\\\D\\\00000\\\\\\\\\\\\\\\\\\\\\\			
26.5	TPD2650CP-FC		TPDC□D-26032-□			
27.0	TPD2700CP-FC		TBDC D 07000 D			
27.5	TPD2750CP-FC		TPDC□D-27032-□			
28.0	TPD2800CP-FC		TPDC□D-28032-□	0.54	0.65	TPDC-W2630
28.5	TPD2850CP-FC		1FDC_D-20032	0.54	0.65	1700-772030
29.0	TPD2900CP-FC		TPDC□D-29032-□			
29.5	TPD2950CP-FC		1 F DO D-23032-			
30.0	TPD3000CP-FC		TPDC□D-30032-□			
30.5	TPD3050CP-FC		11 00 0-00002-			

 $<sup>\</sup>hbox{$\times$ We can provide if you order exact machining specification } \hbox{$Ex$) $\varnothing$15.9 and carbon steel machining $\rightarrow$ TPDC1590CP-FC/PC5335 } \\$ 

 $\bullet \colon \mathsf{Stock} \mathsf{\ Item}$ 

### Parts (applicable wrench)

Picture		Designation	Drill diameter ØD (mm)	Torque (N·m)
	TPDC-	W1216	12.00-16.99	2.0-3.0
		W1721	17.00-21.99	2.0-4.0
- 1		W2225	22.00-25.99	3.0-4.0
		W2630	26.00-30.99	4.0-5.0


\* TPDC-CP-FC insert: impossible to be reground

# F TPDC Plus Drill

## **TPDX (3D/5D/8D)**







(mm)

	Designation	ØD	Ød	Ød₁	Q 1	Q 2	L	Insert
TPDX	3D-08012-24	8.0-8.4	12	16	24	45	82.2	TPD0800XP-0849XP
	3D-08512-26	8.5-8.9	12	16	26	45	84.1	TPD0850XP-0899XP
	3D-09012-27	9.0-9.4	12	16	27	45	85.9	TPD0900XP-0949XP
	3D-09512-29	9.5-9.9	12	16	29	45	87.7	TPD0950XP-0999XP
	3D-10016-30	10.0-10.4	16	20	30	48	94.6	TPD1000XP-1049XP
	3D-10516-32	10.5-10.9	16	20	32	48	96.5	TPD1050XP-1099XP
	3D-11016-33	11.0-11.4	16	20	33	48	98.2	TPD1100XP-1149XP
	3D-11516-35	11.5-11.9	16	20	35	48	100.1	TPD1150XP-1199XP
ГРОХ	5D-08012-40	8.0-8.4	12	16	40	45	98.2	TPD0800XP-0849XP
	5D-08512-43	8.5-8.9	12	16	43	45	101.1	TPD0850XP-0899XP
	5D-09012-45	9.0-9.4	12	16	45	45	103.9	TPD0900XP-0949XP
	5D-09512-48	9.5-9.9	12	16	48	45	106.7	TPD0950XP-0999XP
	5D-10016-50	10.0-10.4	16	20	50	48	114.6	TPD1000XP-1049XP
	5D-10516-53	10.5-10.9	16	20	53	48	117.5	TPD1050XP-1099XP
	5D-11016-55	11.0-11.4	16	20	55	48	120.2	TPD1100XP-1149XP
	5D-11516-58	11.5-11.9	16	20	58	48	123.1	TPD1150XP-1199XP
TPDX	8D-08012-64	8.0-8.4	12	16	64	45	122.2	TPD0800XP-0849XP
	8D-08512-68	8.5-8.9	12	16	68	45	126.6	TPD0850XP-0899XP
	8D-09012-72	9.0-9.4	12	16	72	45	130.9	TPD0900XP-0949XP
	8D-09512-76	9.5-9.9	12	16	76	45	135.2	TPD0950XP-0999XP
	8D-10016-80	10.0-10.4	16	20	80	48	144.6	TPD1000XP-1049XP
	8D-10516-84	10.5-10.9	16	20	84	48	149.0	TPD1050XP-1099XP
	8D-11016-88	11.0-11.4	16	20	88	48	153.2	TPD1100XP-1149XP
	8D-11516-92	11.5-11.9	16	20	92	48	157.6	TPD1150XP-1199XP


<sup>→</sup> Applicable inserts F47


imes We can provide if you order exact machining specification. Ex)  $ilde{ ilde{Q}}$ 10 and 60 mm depth of cut o TPDX6D-10016-60

# **TPDC (1.5D/3D)**









		I							(mm)
	Designation	ØD	Ød	Ød₁	Q 1	Q 2	L	Insert	Fig.
TPDC	1.5D-12016-18	12.0~12.4	16	20	18	48	85	TPD1200C□-1249C□	1
	1.5D-12516-19	12.5~12.9	16	20	19	48	86	TPD1250C□-1299C□	1
	1.5D-13016-20	13.0~13.4	16	20	20	48	87	TPD1300C□-1349C□	1
	1.5D-13516-20	13.5~13.9	16	20	20	48	88	TPD1350C□-1399C□	1
	1.5D-14016-21	14.0~14.4	16	20	21	48	93	TPD1400C□-1449C□	1
	1.5D-14516-22	14.5~14.9	16	20	22	48	94	TPD1450C□-1499C□	1
	1.5D-15020-23	15.0~15.9	20	25	23	50	95	TPD1500C□-1599C□	2
	1.5D-16020-24	16.0~16.9	20	25	24	50	98	TPD1600C□-1699C□	2
	1.5D-17020-26	17.0~17.9	20	25	26	50	100	TPD1700C□-1799C□	2
	1.5D-18025-27	18.0~18.9	25	33	27	56	110	TPD1800C□-1899C□	2
	1.5D-19025-28	19.0~19.9	25	33	28	56	112	TPD1900C□-1999C□	2
	1.5D-20025-30	20.0~20.9	25	33	30	56	114	TPD2000C□-2099C□	2
	1.5D-21025-31	21.0~21.9	25	33	31	56	116	TPD2100C□-2199C□	2
	1.5D-22025-33	22.0~22.9	25	33	33	56	119	TPD2200C□-2299C□	2
	1.5D-23025-34	23.0~23.9	25	33	34	56	121	TPD2300C□-2399C□	2
	1.5D-24032-36	24.0~24.9	32	43	36	60	130	TPD2400C□-2499C□	2
	1.5D-25032-37	25.0~25.9	32	43	37	60	132	TPD2500C□-2599C□	2
	1.5D-26032-39	26.0~26.9	32	43	39	60	134	TPD2600C□-2699C□	2
	1.5D-27032-40	27.0~27.9	32	43	40	60	136	TPD2700C□-2799C□	2
	1.5D-28032-42	28.0~28.9	32	43	42	60	138	TPD2800C□-2899C□	2
	1.5D-29032-43	29.0~29.9	32	43	43	60	141	TPD2900C□-2999C□	2
	1.5D-30032-45	30.0~30.9	32	43	45	60	143	TPD3000C□-3099C□	2
TPDC	3D-12016-36	12.0~12.4	16	20	36	48	99	TPD1200C□-1249C□	1
	3D-12516-38	12.5~12.9	16	20	38	48	101	TPD1250C□-1299C□	1
	3D-13016-39	13.0~13.4	16	20	39	48	103	TPD1300C□-1349C□	1
	3D-13516-41	13.5~13.9	16	20	41	48	105	TPD1350C□-1399C□	1
	3D-14016-42	14.0~14.4	16	20	42	48	106	TPD1400C□-1449C□	1
	3D-14516-44	14.5~14.9	16	20	44	48	107	TPD1450C□-1499C□	1
	3D-15020-45	15.0~15.9	20	25	45	50	113	TPD1500C□-1599C□	2
	3D-16020-48	16.0~16.9	20	25	48	50	117	TPD1600C□-1699C□	2
	3D-17020-51	17.0~17.9	20	25	51	50	120	TPD1700C□-1799C□	2
	3D-18025-54	18.0~18.9	25	33	54	56	132	TPD1800C□-1899C□	2
	3D-19025-57	19.0~19.9	25	33	57	56	135	TPD1900C□-1999C□	2
	3D-20025-60	20.0~20.9	25	33	60	56	138	TPD2000C□-2099C□	2
	3D-21025-63	21.0~21.9	25	33	63	56	141	TPD2100C□-2199C□	2
	3D-22025-66	22.0~22.9	25	33	66	56	145	TPD2200C□-2299C□	2
	3D-23025-69	23.0~23.9	25	33	69	56	149	TPD2300C□-2399C□	2
	3D-24032-72	24.0~24.9	32	43	72	60	159	TPD2400C□-2499C□	2
	3D-25032-75	25.0~25.9	32	43	75	60	162	TPD2500C□-2599C□	2
	3D-26032-78	26.0~26.9	32	43	78	60	173	TPD2600C□-2699C□	2
	3D-27032-81	27.0~27.9	32	43	81	60	176	TPD2700C□-2799C□	2
	3D-28032-84	28.0~28.9	32	43	84	60	180	TPD2800C□-2899C□	2
	3D-29032-87	29.0~29.9	32	43	87	60	185	TPD2900C□-2999C□	2
	3D-30032-90	30.0~30.9	32	43	90	60	188	TPD3000C□-3099C□	2


<sup>●</sup> Applicable inserts F48~49


imes We can provide if you order exact machining specification. Ex) Ø15 and 60 mm depth of cut ightarrow TPDC4D-15020-60

## **TPDC (5D/8D)**









	Designation	ØD	Ød	Ød <sub>1</sub>	Q 1	Q 2	L	Insert	Fig.
TPDC	5D-12016-60	12.0~12.4	16	20	60	48	123	TPD1200C□-1249C□	1
	5D-12516-63	12.5~12.9	16	20	63	48	126	TPD1250C□-1299C□	1
	5D-13016-65	13.0~13.4	16	20	65	48	129	TPD1300C□-1349C□	1
	5D-13516-68	13.5~13.9	16	20	68	48	132	TPD1350C□-1399C□	1
	5D-14016-70	14.0~14.4	16	20	70	48	134	TPD1400C□-1449C□	1
	5D-14516-73	14.5~14.9	16	20	73	48	136	TPD1450C□-1499C□	1
	5D-15020-75	15.0~15.9	20	25	75	50	143	TPD1500C□-1599C□	2
	5D-16020-80	16.0~16.9	20	25	80	50	149	TPD1600C□-1699C□	2
	5D-17020-85	17.0~17.9	20	25	85	50	154	TPD1700C□-1799C□	2
	5D-18025-90	18.0~18.9	25	33	90	56	168	TPD1800C□-1899C□	2
	5D-19025-95	19.0~19.9	25	33	95	56	173	TPD1900C□-1999C□	2
	5D-20025-100	20.0~20.9	25	33	100	56	178	TPD2000C□-2099C□	2
	5D-21025-105	21.0~21.9	25	33	105	56	183	TPD2100C□-2199C□	2
	5D-22025-110	22.0~22.9	25	33	110	56	189	TPD2200C□-2299C□	2
	5D-23025-115	23.0~23.9	25	33	115	56	195	TPD2300C□-2399C□	2
	5D-24032-120	24.0~24.9	32	43	120	60	207	TPD2400C□-2499C□	2
	5D-25032-125	25.0~25.9	32	43	125	60	212	TPD2500C□-2599C□	2
	5D-26032-130	26.0~26.9	32	43	130	60	225	TPD2600C□-2699C□	2
	5D-27032-135	27.0~27.9	32	43	135	60	230	TPD2700C□-2799C□	2
	5D-28032-140	28.0~28.9	32	43	140	60	236	TPD2800C□-2899C□	2
	5D-29032-145	29.0~29.9	32	43	145	60	243	TPD2900C□-2999C□	2
	5D-30032-150	30.0~30.9	32	43	150	60	248	TPD3000C□-3099C□	2
TPDC	8D-12016-96	12.0~12.4	16	20	96	48	159	TPD1200C□-1249C□	1
	8D-12516-100	12.5~12.9	16	20	100	48	163	TPD1250C□-1299C□	1
	8D-13016-104	13.0~13.4	16	20	104	48	168	TPD1300C□-1349C□	1
	8D-13516-108	13.5~13.9	16	20	108	48	173	TPD1350C□-1399C□	1
	8D-14016-112	14.0~14.4	16	20	112	48	176	TPD1400C□-1449C□	1
	8D-14516-116	14.5~14.9	16	20	116	48	180	TPD1450C□-1499C□	1
	8D-15020-120	15.0~15.9	20	25	120	50	188	TPD1500C□-1599C□	2
	8D-16020-128	16.0~16.9	20	25	128	50	197	TPD1600C□-1699C□	2
	8D-17020-136	17.0~17.9	20	25	136	50	205	TPD1700C□-1799C□	2
	8D-18025-144	18.0~18.9	25	33	144	56	222	TPD1800C□-1899C□	2
	8D-19025-152	19.0~19.9	25	33	152	56	230	TPD1900C□-1999C□	2
	8D-20025-160	20.0~20.9	25	33	160	56	238	TPD2000C□-2099C□	2
	8D-21025-168	21.0~21.9	25	33	168	56	246	TPD2100C□-2199C□	2
	8D-22025-176	22.0~22.9	25	33	176	56	255	TPD2200C□-2299C□	2
	8D-23025-184	23.0~23.9	25	33	184	56	264	TPD2300C□-2399C□	2
	8D-24032-192	24.0~24.9	32	43	192	60	279	TPD2400C2499C	2
	8D-25032-200	25.0~25.9	32	43	200	60	287	TPD2500C□-2599C□	2
	8D-26032-208	26.0~26.9	32	43	208	60	303	TPD2600C2699C	2
	8D-27032-216	27.0~27.9	32	43	216	60	311	TPD2700C□-2799C□	2
	8D-28032-224	28.0~28.9	32	43	224	60	320	TPD2800C□-2899C□	2
	8D-29032-232	29.0~29.9	32	43	232	60	330	TPD2900C□-2999C□	2
	8D-30032-240	30.0~30.9	32	43	240	60	338	TPD3000C□-3099C□	2


<sup>◆</sup> Applicable inserts F48~49


 $<sup>\</sup>times$  We can provide if you order exact machining specification. Ex) Ø15 and 60 mm depth of cut  $\rightarrow$  TPDC4D-15020-60

## **TPDC (10D/12D)**









	Designation	ØD	Ød	Ød <sub>1</sub>	Q 1	Q 2	L	Insert	Fig.
PDC	10D-12016-120	12.0~12.4	16	20	120	48	183	TPD1200C□-1249C□	1
	10D-12516-125	12.5~12.9	16	20	125	48	188	TPD1250C□-1299C□	1
	10D-13016-130	13.0~13.4	16	20	130	48	194	TPD1300C□-1349C□	1
	10D-13516-135	13.5~13.9	16	20	135	48	199	TPD1350C□-1399C□	1
	10D-14016-140	14.0~14.4	16	20	140	48	204	TPD1400C□-1449C□	1
	10D-14516-145	14.5~14.9	16	20	145	48	208	TPD1450C□-1499C□	1
	10D-15020-150	15.0~15.9	20	25	150	50	218	TPD1500C□-1599C□	1
	10D-16020-160	16.0~16.9	20	25	160	50	229	TPD1600C□-1699C□	1
	10D-17020-170	17.0~17.9	20	25	170	50	239	TPD1700C□-1799C□	1
	10D-18025-180	18.0~18.9	25	33	180	56	258	TPD1800C□-1899C□	1
	10D-19025-190	19.0~19.9	25	33	190	56	268	TPD1900C□-1999C□	1
	10D-20025-200	20.0~20.9	25	33	200	56	278	TPD2000C□-2099C□	1
	10D-21025-210	21.0~21.9	25	33	210	56	288	TPD2100C□-2199C□	1
	10D-22025-220	22.0~22.9	25	33	220	56	299	TPD2200C□-2299C□	1
	10D-23025-230	23.0~23.9	25	33	230	56	310	TPD2300C□-2399C□	1
	10D-24032-240	24.0~24.9	32	43	240	60	327	TPD2400C□-2499C□	2
	10D-25032-250	25.0~25.9	32	43	250	60	337	TPD2500C□-2599C□	2
	10D-26032-260	26.0~26.9	32	43	260	60	355	TPD2600C□-2699C□	2
	10D-27032-270	27.0~27.9	32	43	270	60	365	TPD2700C□-2799C□	2
	10D-28032-280	28.0~28.9	32	43	280	60	376	TPD2800C□-2899C□	2
	10D-29032-290	29.0~29.9	32	43	290	60	388	TPD2900C□-2999C□	2
	10D-30032-300	30.0~30.9	32	43	300	60	398	TPD3000C□-3099C□	2
PDC	12D-12016-144	12.0~12.4	16	20	144	48	207	TPD1200C□-1249C□	1
	12D-12516-150	12.5~12.9	16	20	150	48	213	TPD1250C□-1299C□	1
	12D-13016-156	13.0~13.4	16	20	156	48	220	TPD1300C□-1349C□	1
	12D-13516-162	13.5~13.9	16	20	162	48	226	TPD1350C□-1399C□	1
	12D-14016-168	14.0~14.4	16	20	168	48	232	TPD1400C□-1449C□	1
	12D-14516-174	14.5~14.9	16	20	174	48	237	TPD1450C□-1499C□	1
	12D-15020-180	15.0~15.9	20	25	180	50	248	TPD1500C□-1599C□	1
	12D-16020-192	16.0~16.9	20	25	192	50	261	TPD1600C□-1699C□	1
	12D-17020-204	17.0~17.9	20	25	204	50	273	TPD1700C□-1799C□	1
	12D-18025-216	18.0~18.9	25	33	216	56	294	TPD1800C□-1899C□	1
	12D-19025-228	19.0~19.9	25	33	228	56	306	TPD1900C□-1999C□	1
	12D-20025-240	20.0~20.9	25	33	240	56	318	TPD2000C□-2099C□	1
	12D-21025-252	21.0~21.9	25	33	252	56	330	TPD2100C□-2199C□	1
	12D-22025-264	22.0~22.9	25	33	264	56	343	TPD2200C□-2299C□	1
	12D-23025-276	23.0~23.9	25	33	276	56	356	TPD2300C□-2399C□	1
	12D-24032-288	24.0~24.9	32	43	288	60	375	TPD2400C□-2499C□	2
	12D-25032-300	25.0~25.9	32	43	300	60	387	TPD2500C□-2599C□	2
	12D-26032-312	26.0~26.9	32	43	312	60	407	TPD2600C□-2699C□	2
	12D-27032-324	27.0~27.9	32	43	324	60	419	TPD2700C□-2799C□	2
	12D-28032-336	28.0~28.9	32	43	336	60	432	TPD2800C□-2899C□	2
	12D-29032-348	29.0~29.9	32	43	348	60	446	TPD2900C□-2999C□	2
	12D-30032-360	30.0~30.9	32	43	360	60	458	TPD3000C□-3099C□	2

Highly precise and efficient top solid indexable drill

### **TPDB Plus Drill**

### (TPDB Plus / TPDB-F <sup>™</sup>/ TPDB-H <sup>™</sup>)

- Highly precise clamping system Superior clamping precision with auto-centering system and highly precise grinding clamping parts
- Screw on clamping system Easy to replace inserts
- Sharp cutting edge Low cutting load and good chip control
- Holder with excellent durability Holder with high rigidity and excellent wear resistance due to special surface treatment
- Holder with excellent chip control Low cutting resistance and outstanding chip evaluation applying high helix angle

#### Code system


Insert



Holder





#### Features



# F

#### Application range





	Application range									
Tools	Drill Diameter (Ø)		Aspect ratio Tolerance of (L/D) drill dia.		Tolerance of Surface finish of hole (Ra)					
TPDB Plus	10~32,99 mm	3, 5, 8, 10, 12	h7	IT10	≤ 2.0 µm	P, K				


#### Performance evaluation

#### Run-out

■ Workpiece Alloy steel (SCM440)

Cutting vc (m/min) = 90, fn (mm/rev) = 0.25
 conditions ap (mm) = 120, wet (20 bar)

■ Tools Insert TPD250B (PC5300) Holder TPDB250-32-5-P




#### **Cutting load**

■ Workpiece Alloy steel (SCM440)

Cutting vc (m/min) = 120, fn (mm/rev) = 0.25
 conditions ap (mm) = 120, wet (20 bar)

■ Tools Insert TPD250B (PC5300)

Holder TPDB250-32-5-P




#### Outstanding roundness of hole


■ Workpiece Alloy steel (SCM440)

■ Cutting vc (m/min) = 90/120, fn (mm/rev) = 0.25/0.35 conditions ap (mm) = 120, wet (20 bar)

\_\_\_\_\_\_

■ Tools Insert TPD250B (PC5300) Holder TPDB250-32-5-P







### **Technical Information for TPDB Plus Drill**

### Recommended cutting conditions

		Workpiece				Aspect ratio (L/D) = 3D, 5D				
	workpiece			Grade	vc (m/min)	Feed rate (mm/rev) per drill dia. (mm)				
	ISO	Workpiece	НВ		(11211111)	Ø10~Ø16.9	Ø17~Ø26.9	Ø27~Ø32.9		
	O subserve a basel	Low carbon steel	80~120	PC5335 PC330P	110 (80~140)	0.15~0.30	0.20~0.35	0.25~0.40		
	Carbon steel	High carbon steel	180~280	PC5335 PC330P	100 (70~130)	0.15~0.30	0.20~0.35	0.25~0.40		
Р		Low alloy steel	140~260	PC5300	110 (80~140)	0.18~0.35	0.23~0.38	0.28~0.43		
	Alloy steel	Low alloy heat treated steel	200~400	PC5300	75 (50~100)	0.18~0.35	0.23~0.38	0.28~0.43		
	Alloy Steel	High alloy steel	50~260	PC5300	70 (50~90)	0.18~0.30	0.20~0.35	0.25~0.40		
		High alloy heat treated steel	220~450	PC5300	60 (40~80)	0.18~0.30	0.20~0.35	0.25~0.40		
	Onet incu	Gray cast iron	150~230	PC5300	110 (80~140)	0.18~0.35	0.20~0.40	0.25~0.45		
K	Cast iron	Ductile cast iron	160~260	PC5300	100 (70~130)	0.18~0.35	0.20~0.40	0.25~0.45		


<sup>\*\*</sup> In case of 8D, machine in 20-30% lower cutting conditions than the mentioned above, or machine the beginning of hole (1.5D) before drilling.


### Replacement of holders and screws

Worn part	How to check	Description
[Pic.1]	[Pic.2] Check the gap	<ul> <li>In case of drilling for a long time as shown in the [Pic.1] the 'A' part is torn and twisted due to torque</li> <li>As shown in the [Pic.2] check the gap between the insert and the tip seat turning the clamped insert from side to side. If there is a gap between them, replace the used holder to a new one</li> </ul>
[Pic.3]	[Pic.4] Check the moving	The insert could move up or down due to the load on the Z-axis in drilling over an extended period of time which causes wear on the 'B' part as shown the [Pic.3]  After clamping an insert, if the insert is moving or there is a gap between the insert and the tip seat as shown in the [Pic.4] replace the used holder to a new one
[Pic.5]	Check the moving	After an extended period of use, the screw can be worn as shown in the 'E' part of [Pic.5] which could decrease the clamping force of the insert. When the screw is worn, replace the old screw to a new one among the enclosed extras  Spreading the grease on the screw makes it last longer
<ul><li>[Pic.6]</li><li>① Check the 'C' and 'D' parts as shown in the [Pic.6]</li><li>② Check whether the chips ar getting longer or not.</li></ul>	D	Winding or jamming of long and tiny chips in drilling causes wear or scratch on the 'C' part as shown in the [Pic.6] due to chattering from machining in improper cutting conditions. In that case, reset the cutting conditions and check the Run-out before machining  The excessive wear of the part 'D' as shown in the [Pic.6] relating to chip curling might cause long chips

<sup>\*</sup> In interrupted machining, reduce the feed to 0.1-0.15 machining around the interrupted part.

### Available insert





(mm)

			Coated		~~		(mm)	
	Designation	PC5300	PC5335	PC330P	ØD	h	t	
TPD	100B	•			10.0	5.5	3.5	
	105B	•			10.5	5.5	3.5	
	110B	•	•		11.0	5.8	3.5	
	115B	•			11.5	5.8	3.5	
	120B	•	•		12.0	6.3	3.5	
	125B	•	•		12.5	6.3	3.5	
	130B	•			13.0	6.5	4.0	
	135B	•			13.5	6.5	4.0	
	140B	•	•		14.0	6.8	4.0	
	145B	•	•		14.5	6.8	4.0	
	150B	•	•		15.0	7.0	4.0	
	155 <b>B</b>	•	•		15.5	7.0	4.0	
	160B	•	•		16.0	7.7	5.5	
	165B	•			16.5	7.7	5.5	
	170B	•	•		17.0	7.9	5.5	
	175B	•	•		17.5	7.9	5.5	
	180B	•	•		18.0	8.1	6.0	
	185B	•	•		18.5	8.1	6.0	
	190B	•	•		19.0	8.3	6.0	
	195B	•			19.5	8.3	6.0	
	200B	•	•		20.0	9.7	6.5	
	205B	•			20.5	9.7	6.5	
	210B	•	•		21.0	9.4	6.5	
	215B	•	_		21.5	9.4	6.5	
	220B	•	•		22.0	9.6	7.0	
	225B	•	_		22.5	9.6	7.0	
	230B	•	•		23.0	9.8	7.0	
	235B	•	_		23.5	9.8	7.0	
	240B	•	•		24.0	10.7	7.5	
	245B	•			24.5	10.7	7.5	
	250B	•	•		25.0	10.9	7.5	
	255B	•			25.5	10.9	7.5	
	260B	•	•		26.0	11.0	8.5	
	265B	•			26.5	11.0	8.5	
	270B 275B	•			27.0	11.8 11.8	8.5	
	2/5B	_			27.5	11.8	8.5	
	280B 285B	•			28.0 28.5	12.6 12.6	9.5	
	200B	•			28.5	12.0	9.5	
	290B 295B				29.0 29.5	12.9 12.9	9.5 9.5	
	300B				30.0	13.0	10.0	
	305B				30.0	13.0	10.0	
	310B				31.0	13.0	10.0	
	315B				31.5	13.2	10.0	
	320B				32.0	13.4	10.0	
	325B				32.5	13.4	10.0	
	323B				3∠.5	13.4	10.0	

 $<sup>\,</sup>$  We can provide nonstock items with Ø10.00-Ø32.99

#### •: Stock Item

#### Parts


(mn

					(mm)
	Designation	Drill dia. (ØD)	Screw	Wrench	Torque (N·m)
TPD	100B~129B	10.0~12.9	FTNB0209-P	TW06P	0.4
	130B~149B	13.0~14.9	FTNB02512-P	TW07S	0.8
	150B~179B	15.0~17.9	FTNB02514-P	TW07S	0.8
	180B~199B	18.0~19.9	FTNB0316-P	TW09S	1.2
	200B~239B	20.0~23.9	FTNB0319	TW09S	1.2
	240B~259B	24.0~25.9	FTNB03522	TW15S	3.0
	260B~279B	26.0~27.9	FTNB03524	TW15S	3.0
	280B~299B	28.0~29.9	FTNB0426	TW15S	3.0
	300B~329B	30.0~32.9	FTNB0528	TW20-100	4.0

# F TPDB Plus Drill

# **TPDB-P (3D)**








(mm)

								(r
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q 1	Q 2	L	Insert
TPDB	100-16-3-P	10.0~10.4	16	20	30.0	48	96.6	TPD100B~104B
	105-16-3-P	10.5~10.9	16	20	31.5	48	97.6	TPD105B~109B
	110-16-3-P	11.0~11.4	16	20	33.0	48	99.7	TPD110B~114B
	115-16-3-P	11.5~11.9	16	20	34.5	48	100.7	TPD115B~119B
	120-16-3-P	12.0~12.4	16	20	36.0	48	104.1	TPD120B~124B
	125-16-3-P	12.5~12.9	16	20	37.5	48	106.2	TPD125B~129B
	130-16-3-P	13.0~13.4	16	20	39.0	48	109.3	TPD130B~134B
	135-16-3-P	13.5~13.9	16	20	40.5	48	111.4	TPD135B~139B
	140-16-3-P	14.0~14.4	16	20	42.0	48	113.5	TPD140B~144B
	145-16-3-P	14.5~14.9	16	20	43.5	48	116.6	TPD145B~149B
	150-20-3-P	15.0~15.4	20	25	45.0	50	120.7	TPD150B~154B
	155-20-3-P	15.5~15.9	20	25	46.5	50	122.7	TPD155B~159B
	160-20-3-P	16.0~16.4	20	25	48.0	50	124.9	TPD160B~164B
	165-20-3-P	16.5~16.9	20	25	49.5	50	126.9	TPD165B~169B
	170-20-3-P	17.0~17.4	20	25	51.0	50	130.1	TPD170B~174B
	175-20-3-P	17.5~17.9	20	25	52.5	50	132.1	TPD175B~179B
	180-25-3-P	18.0~18.4	25	33	54.0	56	140.2	TPD180B~184B
	185-25-3-P	18.5~18.9	25	33	55.5	56	142.2	TPD185B~189B
	190-25-3-P	19.0~19.4	25	33	57.0	56	145.3	TPD190B~194B
	195-25-3-P	19.5~19.9	25	33	58.5	56	147.3	TPD195B~199B
	200-25-3-P	20.0~20.4	25	33	60.0	56	149.5	TPD200B~204B
	205-25-3-P	20.5~20.9	25	33	61.5	56	151.5	TPD205B~209B
	210-25-3-P	21.0~21.4	25	33	63.0	60	154.7	TPD210B~214B
	215-25-3-P	21.5~21.9	25	33	64.5	60	156.7	TPD215B~219B
	220-25-3-P	22.0~22.4	25	33	66.0	60	158.9	TPD220B~224B
	225-25-3-P	22.5~22.9	25	33	67.5	60	160.9	TPD225B~229B
	230-25-3-P	23.0~23.4	25	33	69.0	60	164.1	TPD230B~234B
	235-25-3-P	23.5~23.9	25	33	70.5	60	166.1	TPD235B~239B
	240-32-3-P	24.0~24.4	32	43	72.0	60	172.3	TPD240B~244B
	245-32-3-P	24.5~24.9	32	43	73.5	60	174.3	TPD245B~249B
	250-32-3-P	25.0~25.4	32	43	75.0	60	177.5	TPD250B~254B
	255-32-3-P	25.5~25.9	32	43	76.5	60	179.5	TPD255B~259B
	260-32-3-P	26.0~26.9	32	43	78.0	60	181.7	TPD260B~269B
	270-32-3-P	27.0~27.9	32	43	81.0	60	186.9	TPD270B~279B
	280-32-3-P	28.0~28.9	32	43	84.0	60	191.0	TPD280B~289B
	290-32-3-P	29.0~29.9	32	43	87.0	60	196.2	TPD290B~299B
	300-32-3-P	30.0~30.9	32	43	90.0	60	199.4	TPD300B~309B
	310-32-3-P	31.0~31.9	32	43	93.0	60	204.6	TPD310B~319B
	320-32-3-P	32.0~32.9	32	43	96.0	60	206.8	TPD320B~329B

## **TPDB-P (5D)**








		I						(
	Designation	ØD	$ \emptyset d_1 $	$\emptyset d_2$	Q 1	Q <sub>2</sub>	L	Insert
PDB	100-16-5-P	10.0~10.4	16	20	50.0	48	116.1	TPD100B~104B
	105-16-5-P	10.5~10.9	16	20	52.5	48	118.9	TPD105B~109B
	110-16-5-P	11.0~11.4	16	20	55.0	48	121.7	TPD110B~114B
	115-16-5-P	11.5~11.9	16	20	57.5	48	124.5	TPD115B~119B
	120-16-5-P	12.0~12.4	16	20	60.0	48	128.1	TPD120B~124B
	125-16-5-P	12.5~12.9	16	20	62.5	48	131.2	TPD125B~129B
	130-16-5-P	13.0~13.4	16	20	65.0	48	135.3	TPD130B~134B
	135-16-5-P	13.5~13.9	16	20	67.5	48	138.4	TPD135B~139B
	140-16-5-P	14.0~14.4	16	20	70.0	48	141.5	TPD140B~144B
	145-16-5-P	14.5~14.9	16	20	72.5	48	145.6	TPD145B~149B
	150-20-5-P	15.0~15.4	20	25	75.0	50	150.7	TPD150B~154B
	155-20-5-P	15.5~15.9	20	25	77.5	50	153.7	TPD155B~159B
	160-20-5-P	16.0~16.4	20	25	80.0	50	156.9	TPD160B~164B
	165-20-5-P	16.5~16.9	20	25	82.5	50	159.9	TPD165B~169B
	170-20-5-P	17.0~17.4	20	25	85.0	50	164.1	TPD170B~174B
	175-20-5-P	17.5~17.9	20	25	87.5	50	167.1	TPD175B~179B
	180-25-5-P	18.0~18.4	25	33	90.0	56	176.2	TPD180B~184B
	185-25-5-P	18.5~18.9	25	33	92.5	56	179.2	TPD185B~189B
	190-25-5-P	19.0~19.4	25	33	95.0	56	183.3	TPD190B~194B
	195-25-5-P	19.5~19.9	25	33	97.5	56	186.3	TPD195B~199B
	200-25-5-P	20.0~20.4	25	33	100.0	56	189.5	TPD200B~204B
	205-25-5-P	20.5~20.9	25	33	102.5	56	192.5	TPD205B~209B
	210-25-5-P	21.0~21.4	25	33	105.0	60	196.7	TPD210B~214B
	215-25-5-P	21.5~21.9	25	33	107.5	60	199.7	TPD215B~219B
	220-25-5-P	22.0~22.4	25	33	110.0	60	202.9	TPD220B~224B
	225-25-5-P	22.5~22.9	25	33	112.5	60	205.9	TPD225B~229B
	230-25-5-P	23.0~23.4	25	33	115.0	60	210.1	TPD230B~234B
	235-25-5-P	23.5~23.9	25	33	117.5	60	213.1	TPD235B~239B
	240-32-5-P	24.0~24.4	32	43	120.0	60	220.3	TPD240B~244B
	245-32-5-P	24.5~24.9	32	43	122.5	60	223.3	TPD245B~249B
	250-32-5-P	25.0~25.4	32	43	125.0	60	227.5	TPD250B~254B
	255-32-5-P	25.5~25.9	32	43	127.5	60	230.5	TPD255B~259B
	260-32-5-P	26.0~26.9	32	43	130.0	60	233.7	TPD260B~269B
	270-32-5-P	27.0~27.9	32	43	135.0	60	240.9	TPD270B~279B
	280-32-5-P	28.0~28.9	32	43	140.0	60	247.0	TPD280B~289B
	290-32-5-P	29.0~29.9	32	43	145.0	60	254.2	TPD290B~299B
	300-32-5-P	30.0~30.9	32	43	150.0	60	259.4	TPD300B~309B
	310-32-5-P	31.0~31.9	32	43	155.0	60	266.6	TPD310B~319B
	320-32-5-P	32.0~32.9	32	43	160.0	60	270.8	TPD320B~329B

# F TPDB Plus Drill

# **TPDB-P (8D)**








	)							(mm)
	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q 1	Q 2	L	Insert
TPDB	100-16-8-P	10.0~10.4	16	20	80	48	146.1	TPD100B~104B
	105-16-8-P	10.5~10.9	16	20	84	48	150.4	TPD105B~109B
	110-16-8-P	11.0~11.4	16	20	88	48	154.7	TPD110B~114B
	115-16-8-P	11.5~11.9	16	20	92	48	159.0	TPD115B~119B
	120-16-8-P	12.0~12.4	16	20	96	48	164.1	TPD120B~124B
	125-16-8-P	12.5~12.9	16	20	100	48	168.7	TPD125B~129B
	130-16-8-P	13.0~13.4	16	20	104	48	174.3	TPD130B~134B
	135-16-8-P	13.5~13.9	16	20	108	48	178.9	TPD135B~139B
	140-16-8-P	14.0~14.4	16	20	112	48	183.5	TPD140B~144B
	145-16-8-P	14.5~14.9	16	20	116	48	189.1	TPD145B~149B
	150-20-8-P	15.0~15.4	20	25	120	50	195.7	TPD150B~154B
	155-20-8-P	15.5~15.9	20	25	124	50	200.2	TPD155B~159B
	160-20-8-P	16.0~16.4	20	25	128	50	204.9	TPD160B~164B
	165-20-8-P	16.5~16.9	20	25	132	50	209.4	TPD165B~169B
	170-20-8-P	17.0~17.4	20	25	136	50	215.1	TPD170B~174B
	175-20-8-P	17.5~17.9	20	25	140	50	219.6	TPD175B~179B
	180-25-8-P	18.0~18.4	25	33	144	56	230.2	TPD180B~184B
	185-25-8-P	18.5~18.9	25	33	148	56	234.7	TPD185B~189B
	190-25-8-P	19.0~19.4	25	33	152	56	240.3	TPD190B~194B
	195-25-8-P	19.5~19.9	25	33	156	56	244.8	TPD195B~199B
	200-25-8-P	20.0~20.4	25	33	160	56	249.5	TPD200B~204B
	205-25-8-P	20.5~20.9	25	33	164	56	254.0	TPD205B~209B
	210-25-8-P	21.0~21.4	25	33	168	60	259.7	TPD210B~214B
	215-25-8-P	21.5~21.9	25	33	172	60	264.2	TPD215B~219B
	220-25-8-P	22.0~22.4	25	33	176	60	268.9	TPD220B~224B
	225-25-8-P	22.5~22.9	25	33	180	60	273.4	TPD225B~229B
	230-25-8-P	23.0~23.4	25	33	184	60	279.1	TPD230B~234B
	235-25-8-P	23.5~23.9	25	33	188	60	283.6	TPD235B~239B
	240-32-8-P	24.0~24.4	32	43	192	60	292.3	TPD240B~244B
	245-32-8-P	24.5~24.9	32	43	196	60	296.8	TPD245B~249B
	250-32-8-P	25.0~25.4	32	43	200	60	302.5	TPD250B~254B
	255-32-8-P	25.5~25.9	32	43	204	60	307.0	TPD255B~259B
	260-32-8-P	26.0~26.9	32	43	208	60	311.7	TPD260B~269B
	270-32-8-P	27.0~27.9	32	43	216	60	321.9	TPD270B~279B
	280-32-8-P	28.0~28.9	32	43	224	60	331.0	TPD280B~289B
	290-32-8-P	29.0~29.9	32	43	232	60	341.2	TPD290B~299B
	300-32-8-P	30.0~30.9	32	43	240	60	349.4	TPD300B~309B
	310-32-8-P	31.0~31.9	32	43	248	60	359.6	TPD310B~319B
	320-32-8-P	32.0~32.9	32	43	256	60	366.8	TPD320B~329B

# TPDB Plus Drill

# **TPDB-P (10D)**








(mm)

	Designation	ØD	Ød <sub>1</sub>	$\emptyset d_2$	Q 1	Q 2	L	Insert
PDB	100-16-10-P	10.0~10.4	16	20	100	48	166.6	TPD100B~104B
	105-16-10-P	10.5~10.9	16	20	105	48	171.6	TPD105B~109B
	110-16-10-P	11.0~11.4	16	20	110	48	176.7	TPD110B~114B
	115-16-10-P	11.5~11.9	16	20	115	48	181.7	TPD115B~119B
	120-16-10-P	12.0~12.4	16	20	120	48	188.1	TPD120B~124B
	125-16-10-P	12.5~12.9	16	20	125	48	193.7	TPD125B~129B
	130-16-10-P	13.0~13.4	16	20	130	48	200.3	TPD130B~134B
	135-16-10-P	13.5~13.9	16	20	135	48	205.9	TPD135B~139B
	140-16-10-P	14.0~14.4	16	20	140	48	211.5	TPD140B~144B
	145-16-10-P	14.5~14.9	16	20	145	48	218.1	TPD145B~149B
	150-20-10-P	15.0~15.4	20	25	150	50	225.7	TPD150B~154B
	155-20-10-P	15.5~15.9	20	25	155	50	231.2	TPD155B~159B
	160-20-10-P	16.0~16.4	20	25	160	50	236.9	TPD160B~164B
	165-20-10-P	16.5~16.9	20	25	165	50	242.4	TPD165B~169B
	170-20-10-P	17.0~17.4	20	25	170	50	249.1	TPD170B~174B
	175-20-10-P	17.5~17.9	20	25	175	50	254.6	TPD175B~179B
	180-25-10-P	18.0~18.4	25	33	180	56	266.2	TPD180B~184B
	185-25-10-P	18.5~18.9	25	33	185	56	271.7	TPD185B~189B
	190-25-10-P	19.0~19.4	25	33	190	56	278.3	TPD190B~194B
	195-25-10-P	19.5~19.9	25	33	195	56	283.8	TPD195B~199B
	200-25-10-P	20.0~20.4	25	33	200	56	289.5	TPD200B~204B
	205-25-10-P	20.5~20.9	25	33	205	56	295.0	TPD205B~209B
	210-25-10-P	21.0~21.4	25	33	210	60	301.7	TPD210B~214B
	215-25-10-P	21.5~21.9	25	33	215	60	307.2	TPD215B~219B
	220-25-10-P	22.0~22.4	25	33	220	60	312.9	TPD220B~224B
	225-25-10-P	22.5~22.9	25	33	225	60	318.6	TPD225B~229B
	230-25-10-P	23.0~23.4	25	33	230	60	325.1	TPD230B~234B
	235-25-10-P	23.5~23.9	25	33	235	60	330.6	TPD235B~239B
	240-32-10-P	24.0~24.4	32	43	240	60	340.3	TPD240B~244B
	245-32-10-P	24.5~24.9	32	43	245	60	345.8	TPD245B~249B
	250-32-10-P	25.0~25.4	32	43	250	60	352.5	TPD250B~254B
	255-32-10-P	25.5~25.9	32	43	255	60	358.0	TPD255B~259B
	260-32-10-P	26.0~26.9	32	43	260	60	363.7	TPD260B~269B
	270-32-10-P	27.0~27.9	32	43	270	60	375.9	TPD270B~279B
	280-32-10-P	28.0~28.9	32	43	280	60	387.0	TPD280B~289B
	290-32-10-P	29.0~29.9	32	43	290	60	399.2	TPD290B~299B
	300-32-10-P	30.0~30.9	32	43	300	60	409.4	TPD300B~309B
	310-32-10-P	31.0~31.9	32	43	310	60	421.6	TPD310B~319B
	320-32-10-P	32.0~32.9	32	43	320	60	430.8	TPD320B~329B

# F TPDB Plus Drill

# **TPDB-P (12D)**





(mm)

	Designation	ØD	Ød₁	$\emptyset d_2$	Q 1	Q 2	L	Insert
PDB	100-16-12-P	10.0~10.4	16	20	120	48	186.6	TPD100B~104B
	105-16-12-P	10.5~10.9	16	20	126	48	192.6	TPD105B~109B
	110-16-12-P	11.0~11.4	16	20	132	48	198.7	TPD110B~114B
	115-16-12-P	11.5~11.9	16	20	138	48	204.7	TPD115B~119B
	120-16-12-P	12.0~12.4	16	20	144	48	212.1	TPD120B~124B
	125-16-12-P	12.5~12.9	16	20	150	48	218.7	TPD125B~129B
	130-16-12-P	13.0~13.4	16	20	156	48	226.3	TPD130B~134B
	135-16-12-P	13.5~13.9	16	20	162	48	232.9	TPD135B~139B
	140-16-12-P	14.0~14.4	16	20	168	48	239.5	TPD140B~144B
	145-16-12-P	14.5~14.9	16	20	174	48	247.1	TPD145B~149B
	150-20-12-P	15.0~15.4	20	25	180	50	255.7	TPD150B~154B
	155-20-12-P	15.5~15.9	20	25	186	50	262.2	TPD155B~159B
	160-20-12-P	16.0~16.4	20	25	192	50	268.9	TPD160B~164B
	165-20-12-P	16.5~16.9	20	25	198	50	275.4	TPD165B~169B
	170-20-12-P	17.0~17.4	20	25	204	50	283.1	TPD170B~174B
	175-20-12-P	17.5~17.9	20	25	210	50	289.6	TPD175B~179B
	180-25-12-P	18.0~18.4	25	33	216	56	302.2	TPD180B~184B
	185-25-12-P	18.5~18.9	25	33	222	56	308.7	TPD185B~189B
	190-25-12-P	19.0~19.4	25	33	228	56	316.3	TPD190B~194B
	195-25-12-P	19.5~19.9	25	33	234	56	322.8	TPD195B~199B
	200-25-12-P	20.0~20.4	25	33	240	56	329.5	TPD200B~204B
	205-25-12-P	20.5~20.9	25	33	246	56	336.0	TPD205B~209B
	210-25-12-P	21.0~21.4	25	33	252	60	343.7	TPD210B~214B
	215-25-12-P	21.5~21.9	25	33	258	60	350.2	TPD215B~219B
	220-25-12-P	22.0~22.4	25	33	264	60	356.9	TPD220B~224B
	225-25-12-P	22.5~22.9	25	33	270	60	363.6	TPD225B~229B
	230-25-12-P	23.0~23.4	25	33	276	60	371.1	TPD230B~234B
	235-25-12-P	23.5~23.9	25	33	282	60	377.6	TPD235B~239B
	240-32-12-P	24.0~24.4	32	43	288	60	388.3	TPD240B~244B
	245-32-12-P	24.5~24.9	32	43	294	60	394.8	TPD245B~249B
	250-32-12-P	25.0~25.4	32	43	300	60	402.5	TPD250B~254B
	255-32-12-P	25.5~25.9	32	43	306	60	409.0	TPD255B~259B
	260-32-12-P	26.0~26.9	32	43	312	60	415.7	TPD260B~269B
	270-32-12-P	27.0~27.9	32	43	324	60	429.9	TPD270B~279B
	280-32-12-P	28.0~28.9	32	43	336	60	443.0	TPD280B~289B
	290-32-12-P	29.0~29.9	32	43	348	60	457.2	TPD290B~299B
	300-32-12-P	30.0~30.9	32	43	360	60	469.4	TPD300B~309B
	310-32-12-P	31.0~31.9	32	43	372	60	483.6	TPD310B~319B
	320-32-12-P	32.0~32.9	32	43	384	60	494.8	TPD320B~329B

#### Cutting edge with 180° point angle - Flat bottom machining



- High precision clamping system High precision clamping due to high precise grinding and auto-centering
- Screw on clamping system Easy to replace insert
- Low cutting load cutting edge Low cutting load and excellent chip cpntrol
- High durability holder Improved wear resistance and durability with special surface treatment implementation
- Holder with good chip evacuation Good chip evacuation and reduced cutting load with high helix angle

#### Code system


#### · Insert



#### Holder




#### Features



## Technical Information for TPDB-F

#### Grade selection



#### PC5400

- PVD coating technology with high lubrication, built up edge resistance and chipping resistance
- Excellent chipping resistance due to high toughness coating with high adhesive strength
- Enhanced fracture resistance and stable machinability due to ultra-fine substrate with high toughness substrate


#### Performance evaluation


#### **Precision**

■ Workpiece Alloy steel (SCM440, HRC22)

■ Cutting conditions vc (m/min) = 70/90, fn (mm/rev) = 0.2/0.3, ap (mm) = 30, wet (20 bar)

■ Tools Insert TPD200B-F (PC5400) Holder TPDB200-25-1.5-F (Drill dia. = Ø20 mm)






Cutting edge with low cutting load enhances high precision

■ Workpiece Alloy steel (SCM440, HRC22), Angled surface 15°

■ Cutting conditions vc (m/min) = 70, fn (mm/rev) = 0.21, ap (mm) = 20, wet (20 bar)

■ Tools Insert TPD200B-F (PC5400) Holder TPDB200-25-1.5-F (Drill dia. = Ø20 mm)



Cutting edge with low cutting load enhances high precision

**Drills** 

### Recommended cutting condition (TPDB-F)


	Workpiece HB		Grade	vc	Aspect ratio (L/D) = 1.5D  Feed rate (mm/rev) per drill dia. (mm)		
			НВ	Grade	(m/min)	Ø14.0~Ø21.9	Ø22.0~Ø30.9
	Carbon	Low carbon steel (SM10C, SM20C etc)	80~120		80 (60~100)	0.2~0.3	0.22~0.32
P	steel	High carbon steel (SM45C, SM50C etc)	180~280	PC5400	70 (50~90)	0.2~0.3	0.22~0.32
	Alley steel	Low alloy steel (SCM420, SCM440 etc)	140~260		70 (50~90)	0.2~0.3	0.22~0.32
	Alloy steel	High alloy steel (SCM435, SCM445 etc)	260~320		60 (40~80)	0.2~0.3	0.22~0.32

Machining	Flat surface drilling	Angled surface drilling	Curved surface drilling	Plunging	Boring
Pic.					
1.5D	0	0	0	0	0

<sup>\*</sup> Please refer to the precaution in drilling in case of angled surface, curved surface drilling, plunging and boring


### Precaution in drilling

## Angled surface drilling



• Reduce the feed (fn) to 30% than general cutting conditions at the beginning and the end of angled surface (In case,  $\theta$  is over 30°, reduce it to 50%)

#### **Curved surface drilling**



• Reduce the feed (fn) to 30% than general cutting conditions at the beginning of curved surface (In case,  $\theta$  is over 30°, reduce it to 50%)

#### **Plunging**



- · Reduce the depth of cut (ae) to shorter than 1/2 of drill diameter
- In case, the depth of cut is longer than drill diameter, plunge with divided depth of cut








- Reduce the feed (fn) to 30% than general cutting conditions at the beginning of boring
- Start with 2 mm stepping before boring to prevent long chip

## F TPDB-F

### Available insert







		Coated					(mn
	Designation	PC5400	ØD	h	t	а	b
TPD	140B-F		14.0	8.75	4.0	0.065	0.055
	145B-F		14.5	8.75	4.0	0.065	0.055
	150B-F		15.0	9.25	4.0	0.065	0.055
	155B-F		15.5	9.25	4.0	0.065	0.055
	160B-F		16.0	10.25	5.5	0.065	0.055
	165B-F		16.5	10.25	5.5	0.065	0.055
	170B-F		17.0	10.75	5.5	0.065	0.055
	175B-F		17.5	10.75	5.5	0.065	0.055
	180B-F		18.0	11.75	6.0	0.065	0.055
	185B-F		18.5	11.75	6.0	0.065	0.055
	190B-F		19.0	12.25	6.0	0.065	0.055
	195B-F		19.5	12.25	6.0	0.065	0.055
	200B-F		20.0	12.75	6.5	0.065	0.055
	205B-F		20.5	12.75	6.5	0.065	0.055
	210B-F		21.0	13.25	6.5	0.065	0.055
	215B-F		21.5	13.25	6.5	0.065	0.055
	220B-F		22.0	13.75	7.0	0.065	0.055
	225B-F		22.5	13.75	7.0	0.065	0.055
	230B-F		23.0	14.25	7.0	0.065	0.055
	235B-F		23.5	14.25	7.0	0.065	0.055
	240B-F		24.0	14.75	7.5	0.065	0.055
	245B-F		24.5	14.75	7.5	0.065	0.055
	250B-F		25.0	15.25	7.5	0.065	0.055
	255B-F		25.5	15.25	7.5	0.065	0.055
	260B-F		26.0	15.75	8.5	0.065	0.055
	265B-F		26.5	15.75	8.5	0.065	0.055
	270B-F		27.0	16.75	8.5	0.065	0.055
	275B-F		27.5	16.75	8.5	0.065	0.055
	280B-F		28.0	17.75	9.5	0.065	0.055
	285B-F		28.5	17.75	9.5	0.065	0.055
	290B-F		29.0	18.25	9.5	0.065	0.055
	295B-F		29.5	18.25	9.5	0.065	0.055
	300B-F		30.0	18.75	10.0	0.065	0.055
	305B-F		30.5	18.75	10.0	0.065	0.055


\* We can provide nonstock items with Ø14.00-Ø30.99

### Parts

(mm)

Designation		Drill dia. (ØD)	Screw	Wrench	Torque (N·m)
TPD	140B-F~149B-F	14.0~14.9	FTNB02512-P	TW07S	0.8
	150B-F~179B-F	15.0~17.9	FTNB02514-P	TW07S	0.8
	180B-F~199B-F	18.0~19.9	FTNB0316-P	TW09S	1.2
	200B-F~239B-F	20.0~23.9	FTNB0319	TW09S	1.2
	240B-F~259B-F	24.0~25.9	FTNB03522	TW15S	3.0
	260B-F~279B-F	26.0~27.9	FTNB03524	TW15S	3.0
	280B-F~299B-F	28.0~29.9	FTNB0426	TW15S	3.0
	300B-F~309B-F	30.0~30.9	FTNB0528	TW20-100	4.0

# TPDB-F (1.5D)





	Designation	ØD	Ød₁	Ød <sub>2</sub>	Q <sub>1</sub>	Q <sub>2</sub>	L	(mn
	Designation	<b>0</b> 0	,Du <sub>1</sub>	, Du <sub>2</sub>	& 1	<b>%</b> 2		misert
ГРDВ	140-16-1.5-F	14.0~14.4	16	20	28	48	86.0	TPD140B-F~TPD144B-F
	145-16-1.5-F	14.5~14.9	16	20	29	48	87.0	TPD145B-F~TPD149B-F
	150-20-1.5-F	15.0~15.4	20	25	30	50	93.0	TPD150B-F~TPD154B-F
	155-20-1.5-F	15.5~15.9	20	25	31	50	94.0	TPD155B-F~TPD159B-F
	160-20-1.5-F	16.0~16.4	20	25	32	50	95.0	TPD160B-F~TPD164B-F
	165-20-1.5-F	16.5~16.9	20	25	33	50	96.0	TPD165B-F~TPD169B-F
	170-20-1.5-F	17.0~17.4	20	25	34	50	97.0	TPD170B-F~TPD174B-F
	175-20-1.5-F	17.5~17.9	20	25	35	50	98.0	TPD175B-F~TPD179B-F
	180-20-1.5-F	18.0~18.4	20	25	36	50	99.0	TPD180B-F~TPD184B-F
	185-20-1.5-F	18.5~18.9	20	25	37	50	100.0	TPD185B-F~TPD189B-F
	190-25-1.5-F	19.0~19.4	25	33	38	56	101.0	TPD190B-F~TPD194B-F
	195-25-1.5-F	19.5~19.9	25	33	39	56	102.0	TPD195B-F~TPD199B-F
	200-25-1.5-F	20.0~20.4	25	33	40	56	116.0	TPD200B-F~TPD204B-F
	205-25-1.5-F	20.5~20.9	25	33	41	56	117.0	TPD205B-F~TPD209B-F
	210-25-1.5-F	21.0~21.4	25	33	42	56	118.0	TPD210B-F~TPD214B-F
	215-25-1.5-F	21.5~21.9	25	33	43	56	119.0	TPD215B-F~TPD219B-F
	220-25-1.5-F	22.0~22.4	25	33	44	56	120.0	TPD220B-F~TPD224B-F
	225-25-1.5-F	22.5~22.9	25	33	45	56	121.0	TPD225B-F~TPD229B-F
	230-25-1.5-F	23.0~23.4	25	33	46	56	122.0	TPD230B-F~TPD234B-F
	235-25-1.5-F	23.5~23.9	25	33	47	56	123.0	TPD235B-F~TPD239B-F
	240-32-1.5-F	24.0~24.4	32	43	48	60	128.5	TPD240B-F~TPD244B-F
	245-32-1.5-F	24.5~24.9	32	43	49	60	129.5	TPD245B-F~TPD249B-F
	250-32-1.5-F	25.0~25.4	32	43	50	60	130.5	TPD250B-F~TPD254B-F
	255-32-1.5-F	25.5~25.9	32	43	51	60	131.5	TPD255B-F~TPD259B-F
	260-32-1.5-F	26.0~26.4	32	43	52	60	132.5	TPD260B-F~TPD264B-F
	265-32-1.5-F	26.5~26.9	32	43	53	60	133.5	TPD265B-F~TPD269B-F
	270-32-1.5-F	27.0~27.4	32	43	54	60	134.5	TPD270B-F~TPD274B-F
	275-32-1.5-F	27.5~27.9	32	43	55	60	135.5	TPD275B-F~TPD279B-F
	280-32-1.5-F	28.0~28.4	32	43	56	60	136.5	TPD280B-F~TPD284B-F
	285-32-1.5-F	28.5~28.9	32	43	57	60	137.5	TPD285B-F~TPD289B-F
	290-32-1.5-F	29.0~29.4	32	43	58	60	138.5	TPD290B-F~TPD294B-F
	295-32-1.5-F	29.5~29.9	32	43	59	60	139.5	TPD295B-F~TPD299B-F
	300-32-1.5-F	30.0~30.4	32	43	60	60	140.5	TPD300B-F~TPD304B-F
	305-32-1.5-F	30.5~30.9	32	43	61	60	141.5	TPD305B-F~TPD309B-F

<sup>→</sup> Applicable inserts F66

# Technical Information for TPDB-H


#### The exclusive top solid indexable drill for steel-frame structure, H-Beam



- High precision clamping system High precision clamping due highly precise grinding and auto-centering
- Screw on clamping system Easy to replace insert
- Edge design with excellent centering Low cutting load and good chip control
- High durability holder Improved wear resistance and durability with special surface treatment implementation
- Holder with good chip evacuation Good chip evacuation and reduced cutting load with high helix angle
- Optimally designed oil hole Long tool life

#### Code system


Insert




25: Ø25 mm

220: Ø22.0 mm

#### Features of insert



B: Blade type




3D, 4D, 8D \* For 8D

Flange shank (8F)

- Applied Double R point edge design is optimized for excellent centering and stable machinability
- Machinability and productivity are improved by minimizing both workpiece's bending and chipping at edge corner section

#### Features of holder








[ Competitor ]

■ Concentrated coolant injection on delicate cutting edge increases tool life

#### Grade selection



#### PC340Q 100V

- Application of high hardness lubricative PVD coating technology with excellent resistance on wear, welding, and chipping
- The special surface treatment improves chip evacuation and reduces wear on the rake surface and relief face
- High hardness ultra-fine substrate ensures high rigidity of cutting edge and good chipping resistance

#### Performance evaluation

#### Chip control

- Workpiece Carbon steel (SS275, SM355A)
- vc (m/min) = 80, fn (mm/rev) = 0.2 Cutting conditions ap (mm) = 30, wet
- TPD270B-H (PC340Q) ■ Tools Insert

Holder TPDB270-32-4-H (Drill dia. = Ø27 mm)





Good chip

**SM355A** 

#### Wear resistance

■ Workpiece Carbon steel (SS275)

Cutting vc (m/min) = 65, fn (mm/rev) = 0.25conditions ap (mm) = 30, wet

■ Tools Insert TPD220B-H (PC340Q) Holder TPDB220-25-4-H

(Drill dia. = Ø22 mm)

■ Workpiece Carbon steel (SM355A)


vc (m/min) = 70, fn (mm/rev) = 0.25Cutting conditions ap (mm) = 30, wet

TPD270B-H (PC340Q) ■ Tools Insert

Holder TPDB270-32-4-H (Drill dia. = Ø27 mm)




**SS275** 



**SM355A** 

#### ■ Test result



· Normal wear and still usable



## **Technical Information for TPDB-H**

### Workpiece and recommended cutting conditions

			Workpiece					L/D) = 3D, 4D
	ISO		Workpiece	Worpiece materials Grade		vc (m/min)	Ø14.0~Ø21.0	) per drill dia. (mm) Ø22.0~Ø30.0
		H-Beam						
P	Carbon	Angle	THE PARTY OF THE P	SS275 (SS400*)	DC2400	65 (60~75)	0.2~0.25	0.2~0.3
P	steel	Plate		SM355 (SM490*) SHN355 (SHN490*)	PC340Q			
		Plate (Stacked)	222			60 (55~65)	0.15~0.25	0.15~0.25

<sup>\*:</sup> old symbol

### Precaution in drilling

### Angled surface drilling

- The approach angle between drill and the workpiece at the beginning and the end should be less than 6°
- Reduce the feed (fn) to 30-50% than general cutting conditions at the beginning and the end of angled surface

#### Stacked plates drilling



- Gap between the plates could make wrong chip evacuation causing fracture of the drill
- Place stacked plates without any gap between each

#### Plunging



 Irregular cutting resistance in plunging could cause fracture and deformation of Boring





• Boring is not recommended due to wear and chipping in the corner of the insert



### Available insert







(mm)

	D. d	Coated	an an	L	(11111)
	Designation	PC5300	ØD	h	t
TPD	140B-H		14.0	10.0	4.0
	145B-H		14.5	10.0	4.0
	150B-H		15.0	10.5	4.0
	155B-H		15.5	10.5	4.0
	160B-H		16.0	11.5	5.5
	165B-H		16.5	11.5	5.5
	170B-H		17.0	12.0	5.5
	175B-H		17.5	12.0	5.5
	180B-H		18.0	13.0	6.0
	185B-H		18.5	13.0	6.0
	190B-H		19.0	13.5	6.0
	195B-H		19.5	13.5	6.0
	200B-H		20.0	14.5	6.5
	205B-H		20.5	14.5	6.5
	210B-H		21.0	15.0	6.5
	215B-H		21.5	15.0	6.5
	220B-H		22.0	15.5	7.0
	225B-H		22.5	15.5	7.0
	230B-H		23.0	16.0	7.0
	235B-H		23.5	16.0	7.0
	240B-H		24.0	16.5	7.5
	245B-H		24.5	16.5	7.5
	250B-H		25.0	17.0	7.5
	255B-H		25.5	17.0	7.5
	260B-H		26.0	17.5	8.5
	265B-H		26.5	17.5	8.5
	270B-H		27.0	18.5	8.5
	275B-H		27.5	18.5	8.5
	280B-H		28.0	19.5	9.5
	285B-H		28.5	19.5	9.5
	290B-H		29.0	20.0	9.5
	295B-H		29.5	20.0	9.5
	300B-H		30.0	20.5	10.0
	305B-H		30.5	20.5	10.0

 $\times$  We can provide nonstock items with Ø14.00-Ø30.99

•: Stock Item

### Parts


(mm)

					(11111)
	Designation	Drill dia. (ØD)	Screw	Wrench	Torque (N⋅m)
TPD	140B-H~149B-H	14.0~14.9	FTNB02512-P	TW07S	0.8
	150B-H~179B-H	15.0~17.9	FTNB02514-P	TW07S	0.8
	180B-H~199B-H	18.0~19.9	FTNB0316-P	TW09S	1.2
	200B-H~239B-H	20.0~23.9	FTNB0319	TW09S	1.2
	240B-H~259B-H	24.0~25.9	FTNB03522	TW15S	3.0
	260B-H~279B-H	26.0~27.9	FTNB03524	TW15S	3.0
	280B-H~299B-H	28.0~29.9	FTNB0426	TW15S	3.0
	300B-H~309B-H	30.0~30.9	FTNB0528	TW20-100	4.0

# F TPDB-H

# TPDB-H (3D)








	/						(mm)
	Designation	ØD	Ød	Q 1	<b>Q</b> 2	L	Insert
TPDB	140-16-3-H	14.0~14.4	16	42	48	98.8	TPD140B-144B-H
	145-16-3-H	14.5~14.9	16	43.5	48	100.8	TPD145B-149B-H
	150-20-3-H	15.0~15.4	20	45	50	104.4	TPD150B-154B-H
	155-20-3-H	15.5~15.9	20	46.5	50	106.4	TPD155B-159B-H
	160-20-3-H	16.0~16.4	20	48	50	108.0	TPD160B-164B-H
	165-20-3-H	16.5~16.9	20	49.5	50	110.0	TPD165B-169B-H
	170-20-3-H	17.0~17.4	20	51	50	111.5	TPD170B-174B-H
	175-20-3-H	17.5~17.9	20	52.5	50	113.5	TPD175B-179B-H
	180-20-3-H	18.0~18.4	20	54	50	115.1	TPD180B-184B-H
	185-20-3-H	18.5~18.9	20	55.5	50	117.1	TPD185B-189B-H
	190-20-3-H	19.0~19.4	20	57	50	118.7	TPD190B-194B-H
	195-20-3-H	19.5~19.9	20	58.5	50	120.7	TPD195B-199B-H
	200-25-3-H	20.0~20.4	25	60	56	128.3	TPD200B-204B-H
	205-25-3-H	20.5~20.9	25	61.5	56	130.3	TPD205B-209B-H
	210-25-3-H	21.0~21.4	25	63	56	131.9	TPD210B-214B-H
	215-25-3-H	21.5~21.9	25	64.5	56	133.9	TPD215B-219B-H
	220-25-3-H	22.0~22.4	25	66	56	135.5	TPD220B-224B-H
	225-25-3-H	22.5~22.9	25	67.5	56	137.5	TPD225B-229B-H
	230-25-3-H	23.0~23.4	25	69	56	139.1	TPD230B-234B-H
	235-25-3-H	23.5~23.9	25	70.5	56	141.1	TPD235B-239B-H
	240-32-3-H	24.0~24.4	32	72	60	146.8	TPD240B-244B-H
	245-32-3-H	24.5~24.9	32	73.5	60	148.8	TPD245B-249B-H
	250-32-3-H	25.0~25.4	32	75	60	150.3	TPD250B-254B-H
	255-32-3-H	25.5~25.9	32	76.5	60	152.3	TPD255B-259B-H
	260-32-3-H	26.0~26.4	32	78	60	153.8	TPD260B-264B-H
	265-32-3-H	26.5~26.9	32	79.5	60	155.8	TPD265B-269B-H
	270-32-3-H	27.0~27.4	32	81	60	157.5	TPD270B-274B-H
	275-32-3-H	27.5~27.9	32	82.5	60	159.5	TPD275B-279B-H
	280-32-3-H	28.0~28.4	32	84	60	161.0	TPD280B-284B-H
	285-32-3-H	28.5~28.9	32	85.5	60	163.0	TPD285B-289B-H
	290-32-3-H	29.0~29.4	32	87	60	164.6	TPD290B-294B-H
	295-32-3-H	29.5~29.9	32	88.5	60	166.6	TPD295B-299B-H
	300-32-3-H	30.0~30.9	32	90	60	168.2	TPD300B-309B-H

<sup>→</sup> Applicable inserts F71

# TPDB-H (4D)








	Designation	ØD	Ød	Q 1	Q 2	L	Insert
PDB	140-16-4-H	14.0~14.4	16	56	48	112.8	TPD140B-144B-H
	145-16-4-H	14.5~14.9	16	58	48	115.3	TPD145B-149B-H
	150-20-4-H	15.0~15.4	20	60	50	119.4	TPD150B-154B-H
	155-20-4-H	15.5~15.9	20	62	50	121.9	TPD155B-159B-H
	160-20-4-H	16.0~16.4	20	64	50	124.0	TPD160B-164B-H
	165-20-4-H	16.5~16.9	20	66	50	126.5	TPD165B-169B-H
	170-20-4-H	17.0~17.4	20	68	50	128.5	TPD170B-174B-H
	175-20-4-H	17.5~17.9	20	70	50	131.0	TPD175B-179B-H
	180-20-4-H	18.0~18.4	20	72	50	133.1	TPD180B-184B-H
	185-20-4-H	18.5~18.9	20	74	50	135.6	TPD185B-189B-H
	190-20-4-H	19.0~19.4	20	76	50	137.7	TPD190B-194B-H
	195-20-4-H	19.5~19.9	20	78	50	140.2	TPD195B-199B-H
	200-25-4-H	20.0~20.4	25	80	56	148.3	TPD200B-204B-H
	205-25-4-H	20.5~20.9	25	82	56	150.8	TPD205B-209B-H
	210-25-4-H	21.0~21.4	25	84	56	152.9	TPD210B-214B-H
	215-25-4-H	21.5~21.9	25	86	56	155.4	TPD215B-219B-H
	220-25-4-H	22.0~22.4	25	88	56	157.5	TPD220B-224B-H
	225-25-4-H	22.5~22.9	25	90	56	160.0	TPD225B-229B-H
	230-25-4-H	23.0~23.4	25	92	56	162.1	TPD230B-234B-H
	235-25-4-H	23.5~23.9	25	94	56	164.6	TPD235B-239B-H
	240-32-4-H	24.0~24.4	32	96	60	170.8	TPD240B-244B-H
	245-32-4-H	24.5~24.9	32	98	60	173.3	TPD245B-249B-H
	250-32-4-H	25.0~25.4	32	100	60	175.3	TPD250B-254B-H
	255-32-4-H	25.5~25.9	32	102	60	177.8	TPD255B-259B-H
	260-32-4-H	26.0~26.4	32	104	60	179.8	TPD260B-264B-H
	265-32-4-H	26.5~26.9	32	106	60	182.3	TPD265B-269B-H
	270-32-4-H	27.0~27.4	32	108	60	184.5	TPD270B-274B-H
	275-32-4-H	27.5~27.9	32	110	60	187.0	TPD275B-279B-H
	280-32-4-H	28.0~28.4	32	112	60	189.0	TPD280B-284B-H
	285-32-4-H	28.5~28.9	32	114	60	191.5	TPD285B-289B-H
	290-32-4-H	29.0~29.4	32	116	60	193.6	TPD290B-294B-H
	295-32-4-H	29.5~29.9	32	118	60	196.1	TPD295B-299B-H
	300-32-4-H	30.0~30.9	32	120	60	198.2	TPD300B-309B-H

Applicable inserts F71

## F TPDB-H

# **TPDB-H (8D)**



$\mathbf{A}$	

	)							(mm
	Designation	ØD	Ød	Q 1	Q 2	<b>Q</b> 3	L	Insert
TPDB	140-16-8F-H	14.0~14.4	16	50	112	48	176.3	TPD140B-144B-H
	145-16-8F-H	14.5~14.9	16	50	116	48	180.3	TPD145B-149B-H
	150-20-8F-H	15.0~15.4	20	50	120	50	187.4	TPD150B-154B-H
	155-20-8F-H	15.5~15.9	20	50	124	50	191.4	TPD155B-159B-H
	160-20-8F-H	16.0~16.4	20	50	128	50	196.5	TPD160B-164B-H
	165-20-8F-H	16.5~16.9	20	50	132	50	200.5	TPD165B-169B-H
	170-20-8F-H	17.0~17.4	20	50	136	50	205.5	TPD170B-174B-H
	175-20-8F-H	17.5~17.9	20	50	140	50	209.5	TPD175B-179B-H
	180-20-8F-H	18.0~18.4	20	50	144	50	215.6	TPD180B-184B-H
	185-20-8F-H	18.5~18.9	20	50	148	50	219.6	TPD185B-189B-H
	190-20-8F-H	19.0~19.4	20	50	152	50	223.7	TPD190B-194B-H
	195-20-8F-H	19.5~19.9	20	50	156	50	227.7	TPD195B-199B-H
	200-25-8F-H	20.0~20.4	25	50	160	56	237.8	TPD200B-204B-H
	205-25-8F-H	20.5~20.9	25	50	164	56	241.8	TPD205B-209B-H
	210-25-8F-H	21.0~21.4	25	50	168	56	245.9	TPD210B-214B-H
	215-25-8F-H	21.5~21.9	25	50	172	56	249.9	TPD215B-219B-H
	220-25-8F-H	22.0~22.4	25	50	176	56	254.0	TPD220B-224B-H
	225-25-8F-H	22.5~22.9	25	50	180	56	263.0	TPD225B-229B-H
	230-25-8F-H	23.0~23.4	25	50	184	56	267.1	TPD230B-234B-H
	235-25-8F-H	23.5~23.9	25	50	188	56	271.1	TPD235B-239B-H
	240-32-8F-H	24.0~24.4	32	50	192	60	279.3	TPD240B-244B-H
	245-32-8F-H	24.5~24.9	32	50	196	60	283.3	TPD245B-249B-H
	250-32-8F-H	25.0~25.4	32	50	200	60	287.3	TPD250B-254B-H
	255-32-8F-H	25.5~25.9	32	50	204	60	291.3	TPD255B-259B-H
	260-32-8F-H	26.0~26.4	32	50	208	60	295.3	TPD260B-264B-H
	265-32-8F-H	26.5~26.9	32	50	212	60	299.3	TPD265B-269B-H
	270-32-8F-H	27.0~27.4	32	50	216	60	303.5	TPD270B-274B-H
	275-32-8F-H	27.5~27.9	32	50	220	60	307.5	TPD275B-279B-H
	280-32-8F-H	28.0~28.4	32	50	224	60	313.5	TPD280B-284B-H
	285-32-8F-H	28.5~28.9	32	50	228	60	317.5	TPD285B-289B-H
	290-32-8F-H	29.0~29.4	32	50	232	60	322.6	TPD290B-294B-H
	295-32-8F-H	29.5~29.9	32	50	236	60	326.6	TPD295B-299B-H
	300-32-8F-H	30.0~30.9	32	50	240	60	330.7	TPD300B-309B-H

<sup>→</sup> Applicable inserts F71

 $<sup>\</sup>ensuremath{\text{\#}}$  The maximum length of flute could be  $\ensuremath{\text{\&}}_2$ 

#### Convenient and quickly adjustable drill height

## **WPDC**

## Indexable drill clamped with center drill

#### Code system


#### Holder



#### Cartridge



#### · Center drill




#### Grade



## F

## **Technical Information for WPDC**

### How to clamp the drills



Center Drill fixing bolt

Bolt for adjusting cone point

#### Feature of corn-point system

- · Convenient and quick adjustable heights when inserting the center drill
- In case the center drill brakes while in usage, it can be replaced with the bolt for adjusting cone point
- The bolt for adjusting cone point prevents chattering on the center drill


### Clamping

0	<b>2</b>	<b>©</b>	4	6
•				
Place a center drill	Clamp insert and cartridge	Adjust the center drill with the bolt for adjusting cone point	Clamp the center drill firmly with fixing bolt	Reassure the clamp with bolt for adjusting cone point

- \* Use safety covers for your safety when clamping the center drill and insert
- $\ensuremath{\mathrm{*}}$  When machining, be careful of the drill disk

### Length of the 'a' part of center drill


- The length of 'a' being too short can cause bad surface finish or high cutting load
- On the other hand, the length of 'a' being too long can make tool failure and chattering while drilling



Diameter (ØD)		Length of the 'a' part of center drill	
Diameter (ØD)	Steel	Alloy steel	Non-ferrous metal
25~30	1.2	1.0	1.5
31~40	1.5	1.3	1.8
41~50	1.8	1.5	2.2
51~59	2.2	1.8	2.5
60~75	2.5	2.0	2.8
76~80	3.0	2.5	3.5

#### Adjusting diameter of cartridge type drill

- 1) Disassemble a cartridge from the holder by loosening the bolt fixed for outer cartridge
- 2) Machine after calculating the hole size on the side of the outer cartridge
- 3) Trim the sharp part after machining
- 4) Clamp the bolt for fixing cartridge without any gap in between the holder and the machined outer cartridge



#### 1) Range of adjustable drill diameter

- ① Single cartridge type (Drill diameter Ø41~Ø59) ··· -1.0 mm
- ② Dual cartridge type (Drill diameter Ø60~Ø80) ··· -5.0 mm

## 2) Diameter of the standard drills is provided with maximum size of standards

Ex) WPDC6570-40-6.5 ··· Drill diameter 70.0 mm

Ex) How to adjust drill diameter to Ø66.0 machining with WPDC6570-40-8

 $\cdots$  To make the drill diameter of outer cartridge to Ø66.0, machine 2.0 mm (Ø70.0-Ø66.0 = 4  $\cdots$  4 ÷ 2 = 2 (radius))

### Recommended cutting condition

	w	orkpiece		Oblin				Aspe	ect ratio (L/I	D) = 5D, 6.5	2~0.16  0.12~0.16  0 2~0.16  0.12~0.16  0 2~0.18  0.12~0.18  0 0~0.16  0.10~0.16  0 2~0.14  0.12~0.14  0 4~0.22  0.14~0.22  0 4~0.22  0.14~0.22  0 4~0.22  0.14~0.22  0 4~0.18  0.14~0.18  0		
	VV	orkpiece		Chip breaker	Grade	vc (m/min)		Feed ra	te (mm/rev	) per drill di	a. (mm)		
	ISO	Workpiece	НВ	Di Ganoi		()	~Ø30	Ø31~Ø40	Ø41~Ø50	Ø51~Ø59	Ø60~Ø75	Ø76~Ø80	
	Carbon	Low carbon steel (~0.25%)	80~180	C21N	PC5335	190 (160~220)	0.07~0.11	0.08~0.12	0.10~0.14	0.12~0.16	0.12~0.16	0.12~0.16	
P	steel	High carbon steel (0.25%∼)	180~280	C21N	PC5335	140 (110~170)	0.07~0.11	0.08~0.12	0.10~0.14	0.12~0.16	0.12~0.16	0.12~0.16	
	Alloy	Low alloy steel	140~260	C21N	PC5335	130 (100~160)	0.08~0.12	0.08~0.12	0.10~0.14	0.12~0.18	0.12~0.18	0.12~0.18	
	steel	High alloy steel	50~260	C21N	PC5335	100 (70~130)	0.06~0.10	0.08~0.12	0.08~0.12	0.10~0.16	0.10~0.16	0.10~0.16	
M	Stainless steel	Stainless steel	135~275	C21N	PC5335	100 (70~130)	0.06~0.10	0.08~0.12	0.10~0.12	0.12~0.14	0.12~0.14	0.12~0.14	
		Gray cast iron	150~220	C21N	PC5335	160 (130~190)	0.09~0.15	0.10~0.16	0.12~0.2	0.14~0.22	0.14~0.22	0.14~0.22	
К	Cast iron	Ductile cast iron	200~300	C21N	PC5335	140 (170~110)	0.09~0.15	0.10~0.16	0.12~0.2	0.14~0.22	0.14~0.22	0.14~0.22	
		Malleable cast iron	130~230	C21N	PC5335	150 (180~120)	0.09~0.15	0.10~0.16	0.12~0.2	0.14~0.22	0.14~0.22	0.14~0.22	
N	Non-ferrous	Aluminum	30~150	C21N	PC5335	300 (250~350)	0.08~0.12	0.10~0.14	0.12~0.16	0.14~0.18	0.14~0.18	0.14~0.18	
IN	metal	Alloyed copper	150~160	C21N	PC5335	250 (200~300)	0.08~0.12	0.10~0.14	0.12~0.16	0.14~0.18	0.14~0.18	0.14~0.18	
S	Heat resistant alloy	Heat resistant alloy	130~400	C21N	PC5335	50 (70~30)	0.05~0.08	0.05~0.08	0.06~0.10	0.06~0.10	0.06~0.10	0.06~0.10	



### Parts of WPDC type indexable drills

		Ir	nsert			Center drill			Cartridge	
Designation	ØD		Screw	Wrench	Center drill	fixed bolt	cone point bolt			
20019.1.4.10.1		Insert		P				Inner	Outer	Fixed bolt
WPDC250-32-□	25	WC□T030204-C21N	FTKA02206	TW06S		KHA0508				
WPDC260~280-32-	26~28	WC□T040204-C21N	ETNIA02555	TW07S	CD0630	NI IA0300	KHC0510			
WPDC290~300-32-	29~30	WO_1040204-021N	1 114/10/2000	10075		KHA0510				
WPDC310~350-32-	31~35	WC□T050308-C21N	ETK A0307	TW09S	CD0835	KHA0610	KHC0610			
WPDC360~400-32-	36~40	WO_1030300-021N	1 110A0307	1 00095	CD0633	KHA0612	KIICOOTO			
WPDC410-40-□	41								CWP410P	
WPDC420-40-□	42								CWP420P	BHA0510
WPDC430-40-□	43					KHA0812		CWP4145C	CWP430P	
WPDC440-40-□	44								CWP440P	
WPDC450-40-□	45	 -WC□T06T308-C21N	FTKA03508	TW15S	CDH1035	CDH1035 KHC0812	KHC0812		CWP450P	
WPDC460-40-□	46	1001000 0211		100130	ODITIOOS			CWP460P		
WPDC470-40-□	47							CWP4650C	CWP470P	
WPDC480-40-□	48								CWP480P	BHA0512
WPDC490-40-□	49								CWP490P	
WPDC500-40-□	50								CWP500P	
WPDC510-40-□	51								CWP510P	
WPDC520-40-□	52								CWP520P	
WPDC530-40-□	53							CWP5155C	CWP530P	BHA0612
WPDC540-40-□	54								CWP540P	
WPDC550-40-□	55	WC□T080408-C21N	FTKA0411K	TW15S		KHA1015	KHC1016		CWP550P	
WPDC560-40-□	56				CDH1238				CWP560P	
WPDC570-40-□	57				ODITIZOO			CWP5659C	CWP570P	BHA0614
WPDC580-40-□	58							0111 00000	CWP580P	DI II/ (OO) 4
WPDC590-40-□	59								CWP590P	
WPDC6065-40-□	60~65							CWP6065C	CWP6065P	
WPDC6570-40-□	65~70	WC□T050308-C21N	FTKA0307	TW09S		KHA1020	KHA1020	CWP6570C	CWP6570P	P BHA0510
WPDC7075-40-□	70~75					KHA1020	131771020	CWP7075C	CWP7075P	
WPDC7580-40-□	75~80	WC□T06T308-C21N	FTKA03508	TW15S	CDH1645			CWP7580C	CWP7580T	BHA0612

<sup>→</sup> Applicable inserts F03~04

## **Center Drill**



(mm)


Designation	Grade	ØD	L	Oil-hole
CD 0630	PC40H	6	30	×
CD 0835	PC40H	8	35	×
CDH 1035	PC40H	10	35	0
CDH 1238	PC40H	12	38	0
CDH 1645	PC40H	16	45	0

<sup>•</sup> This is HSS with Tin coating

# WPDC (5D/6.5D/8D)

## Standard type





(mm)

	lacianation	αD	5	D	6.	5 <b>D</b>	8	D	Innaut	Contou duill
L	esignation	ØD	Q 1	L	Q 1	L	Q 1	L	Insert	Center drill
WPDC	250-32-	25	150	240	185	275	220	310	WC□T030204-C21N	
	260-32-	26	150	240	185	275	220	310		
	270-32-	27	150	240	185	275	220	310	WC□T040204-C21N	CD0630
	280-32-	28	150	240	185	275	220	310		CD0030
	290-32-	29	150	240	185	275	220	310		
	300-32-□	30	150	240	185	275	220	310		
	310-32-	31	175	265	218	308	260	350		
	320-32-	32	175	265	218	308	260	350		
	330-32-	33	175	265	218	308	260	350		
	340-32-□	34	175	265	218	308	260	350		
	350-32-	35	175	265	218	308	260	350	WC□T050308-C21N	CD0835
	360-32-□	36	200	290	250	340	300	390	VVC_1030306-C21N	CD0633
	370-32-□	37	200	290	250	340	300	390	0	
	380-32-□	38	200	290	250	340	300	390		
	390-32-	39	200	290	250	340	300	390		
	400-32-□	40	200	290	250	340	300	390		

<sup>◆</sup> Applicable inserts F04


 ${}^\star\!$  We can provide if you order exact diameter Ex) machining hole 32.5 mm ★ 6.5D ··· WPDC325-32-6.5

# F WPDC

# WPDC (5D/6.5D/8D)

### Single insert catridge type





(mm)

-	Na alamakian	ØD	5	D	6.	5D	8	D	lacout	Center	Cartı	ridge
L	Designation	טש	Q 1	L	Q 1	L	Q 1	L	Insert	drill	Inner	Outer
WPDC	410-40-	41	225	330	283	388	340	445				CWP410P
	420-40-□	42	225	330	283	388	340	445		CDH1035		CWP420P
	430-40-	43	225	330	283	388	340	445			CWP4145C	CWP430P
	440-40-	44	225	330	283	388	340	445				CWP440P
	450-40-	45	225	330	283	388	340	445	WC□T06T308-C21N			CWP450P
	460-40-	46	250	355	315	420	380	485	WC_1001300-C21N			CWP460P
	470-40-	47	250	355	315	420	380	485				CWP470P
	480-40-	48	250	355	315	420	380	485			CWP4650C	CWP480P
	490-40-	49	250	355	315	420	380	485				CWP490P
	500-40-□	50	250	355	315	420	380	485				CWP500P
	510-40-	51	275	380	348	453	420	525				CWP510P
	520-40-□	52	275	380	348	453	420	525				CWP520P
	530-40-	53	275	380	348	453	420	525			CWP5155C	CWP530P
	540-40-□	54	275	380	348	453	420	525				CWP540P
	550-40-	55	275	380	348	453	420	525	WC□T080408-C21N	CDH1238		CWP550P
	560-40-□	56	300	405	380	485	460	565				CWP560P
	570-40-□	57	300	405	380	485	460	565			CWP5659C	CWP570P
	580-40-□	58	300	405	380	485	460	565	1		C4412023C	CWP580P
	590-40-□	59	300	405	380	485	460	565				CWP590P


<sup>→</sup> Applicable inserts F04

 $^{\star}$  We can provide if you order exact diameter Ex) machining hole 47.5 mm  $^{\star}$  5D -> WPDC475-40-5

# WPDC (5D/6.5D/8D)

### Dual insert cartridge type





(mm)

D	a cianatian	ØD	5	D	6.	5D	8	D	Insert	Center	Cart	ridge
De	Designation		Q 1	L	Q 1	L	Q 1	L	ilisert	drill	Inner	Outer
WPDC	6065-40-	60~65	325	430	423	528	520	625			CWP6065C	CWP6065P
	6570-40-	65~70	350	455	455	560	560	665	WC□T050308-C21N	CDH1238	CWP6570C	CWP6570P
	7075-40-	70~75	375	480	488	593	600	705			CWP7075C	CWP7075P
	7580-40-	75~80	400	505	520	625	640	745	WC□T06T308-C21N	CDH1645	CWP7580C	CWP7580P

→ Applicable inserts F04

\* We can provide if you order exact diameter Ex) machining hole 70.5 mm \* 6.5D -> WPDC705-40-6.5

## F

### **Technical Information for Indexable Reamer**


#### Mass production and High performance

## **Indexable Reamer**

- Suitable for mass production and high performance
- Using PCD or coated insert for high speed machining
- Excellent high accuracy and adjustable machining hole
- Using accuracy chucking system (Hydraulic, rotating type arbor)
- Using inner coolant type machine to evacuate chips
- Using suitable holder and insert
- As insert setting, using setting fixture (KIRSD-210)

#### Code system

Insert



#### Holder



### Application






### **Technical Information for Indexable Reamer**

# F

#### How to set an insert




 Screw the wedge screw counter clockwise with the exclusive wrench




2. Screw the clamp screw

- ① Top side: counter clockwise
- 2 Lower side: clockwise



3. Remove the insert and clean the pocket



4. Put the insert up to the edge stopper and clamp the insert

- ① Top side: clockwise
- 2 Lower side: counterclockwise

#### Exclusive fixture

- Designation: KIRSD-210
- Maximum diameter of reamer:  $\emptyset$ 60 × 210 mm
- The fixture is also available for setting special reamer and mono tool
- Special reamers (out of maximum setting range) are available quotation



#### How to set an insert with fixture



1. Adjust the gauge to '0'



2. Rotate the reamer for the insert to touch the gauge



3. Set the back taper and adjust the insert height with screw the wedge screw

- ① Top side of insert: +0.015 $\sim$  +0.020 mm
- ② Bottom side of insert: +0.005~ +0.010 mm
- ③ Back taper: 0.010~0.015 mm

#### Back taper

- Ensures low cutting load and excellent surface finish with good chip evacuation
- Inaccurate back taper could cause unstable machining with wear of insert
- $\bullet$  The size of back taper of insert down side should be less to 0.010~0.015 mm than one of insert upper side

#### Insert setting with a micrometer





· Lathe with both centers or bench center are also available

**Notice:** The setting with a micrometer is not recommended due to chipping on the cutting edge



# F Technical Information for Indexable Reamer

## Recommended cutting condition


Maukoiaaa	Inser	t type	Feed rate (mm/rev)	С	utting speed vc (m/m	in)
Workpiece	Rake angle	Lead type	per drill dia. (mm)	Coated	Uncoated	Cermet
		А	0.1~0.4	60~80	40~60	
Carbon steel General steel	6	В	0.1~0.3	00.100	00.00	110~160
donoral otool		D	0.05~0.2	80~120	60~80	
		А	0.1~0.4	40~60	20~40	
Mild steel Alloy steel	6	В	0.1~0.3	80~120	60~80	110~160
7		D	0.05~0.2	80~120	60~80	
		А	0.1~0.4	20~60	20~40	20~60
High alloy steel Tool steel	6	В	0.1~0.3	40~80	40~60	40~80
		D	0.05~0.2	40~60	40~60	40~00
		А	0.1~0.3	40~60	20~40	40~60
Stainless steel	12	В	0.1~0.2	60~80	40~60	60~80
		D	0.05~0.2	60~80	40~60	60~80
		А	0.1~0.3	60~100	40~60	
Cast iron	0.6	В	0.1~0.25	00.100	00.00	
		D	0.05~0.2	80~120	60~80	
		В	0.1~0.3		160~200	
Alloyed aluminum	12	С	0.15~0.3		150~250	
		D	0.05~0.2		110~200	
Alloyed copper	0	В	0.1~0.2		00.100	
	0	D	0.05~0.2		80~100	
Non-ferrous alloy	0	В	0.1~0.3		10~70	

#### Parts

Reamer size	Clamp	Wedge	Clamp Screw	Wedge Screw	Clamp Wrench	Wedge Wrench	
10.0~11.9	CV 15	AW2430	DUAGGO	HSO306	HW15L	HW15L	
12.0~17.9	CV 16	AW2435	DHA0308	П5О306	HWISL	HWISL	
18.0~27.9	CV 17	AW3240	DHA0409	HS0406	HW20L	HW20L	
28.0~31.9	CV 22	AW3260	DHA0409	П30400	HWZUL	HW20L	

### Available insert







(mm)

	Decimation		Grade			Dimensions		I and home	Rake angle
	Designation	K10 (Uncoated)	BPK110 (TiAIN)	BPK210 (TiN)	L	W	S	Lead type	(α°)
RI	15-A06			0	15	3.0	1.5	Α	6°
	15-A12	0			15	3.0	1.5	Α	12°
	15-B06		0	0	15	3.0	1.5	В	6°
	15-B12		0		15	3.0	1.5	В	12°
	16-A06			0	16	3.5	1.5	Α	6°
	16-A12	0			16	3.5	1.5	А	12°
	16-B06		0	0	16	3.5	1.5	В	6°
	16-B12		0		16	3.5	1.5	В	12°
	17-A06			0	17	4.5	2.0	Α	6°
	17-A12	0			17	4.5	2.0	Α	12°
	17-B06		0	0	17	4.5	2.0	В	6°
	17-B12		0		17	4.5	2.0	В	12°
	22-A06			0	22	6.5	3.0	Α	6°
	22-A12	0			22	6.5	3.0	Α	12°
	22-B06		0	0	22	6.5	3.0	В	6°
	22-B12		0		22	6.5	3.0	В	12°

### Angle of chip breaker

Division	Division 00		12		
Shape	0.	6°	12°		
Application	For cast iron machining	For general machining	For stainless and aluminum machining		


### ● Insert lead type

Туре	Shape	Working condition	Туре	Shape	Working condition
A	15*	For excellent surface, low cutting condition	С	75*	For aluminum and copper alloy machining
В	30°	For general application, high cutting condition	D	30°	For blind hole machining, low feed

# Indexable Reamer

## IRT Throughout hole





	/n


	Designation	ØD	Q	Q1	<b>Q</b> 2	Qз	L	Ød	Insert
IRT	10.000-16125-15	10	15	30	75	45	125	16	RI 15
	11.000-16125-15	11	15	30	75	45	125	16	RI 15
	12.000-16135-16	12	16	30	85	45	135	16	RI 16
	13.000-16135-16	13	16	30	85	45	135	16	RI 16
	14.000-16135-16	14	16	30	85	45	135	16	RI 16
	15.000-16135-16	15	16	30	85	45	135	16	RI 16
	16.000-20155-16	16	16	30	100	50	155	20	RI 16
	17.000-20155-16	17	16	30	100	50	155	20	RI 16
	18.000-20155-17	18	17	30	100	50	155	20	RI 17
	19.000-20155-17	19	17	30	100	50	155	20	RI 17
	20.000-25165-17	20	17	30	110	56	165	25	RI 17
	21.000-25165-17	21	17	30	110	56	165	25	RI 17
	22.000-25165-17	22	17	30	110	56	165	25	RI 17
	23.000-25165-17	23	17	30	110	56	165	25	RI 17
	24.000-25165-17	24	17	30	110	56	165	25	RI 17
	25.000-25165-17	25	17	30	110	56	165	25	RI 17
	26.000-25165-17	26	17	30	110	56	165	25	RI 17
	27.000-25165-17	27	17	30	110	56	165	25	RI 17
	28.000-32165-22	28	22	30	110	56	165	32	RI 22
	29.000-32165-22	29	22	30	110	56	165	32	RI 22
	30.000-32165-22	30	22	30	110	56	165	32	RI 22
	31.000-32165-22	31	22	30	110	56	165	32	RI 22

<sup>→</sup> Applicable inserts F85



#### **IRB** Stuffed hole





(n	٦m

	Designation	ØD	Q	Q <sub>1</sub>	<b>Q</b> 2	Qз	L	Ød	Insert
IRB	10.000-16125-15	10	15	30	75	45	125	16	RI 15
	11.000-16125-15	11	15	30	75	45	125	16	RI 15
	12.000-16135-16	12	16	30	85	45	135	16	RI 16
	13.000-16135-16	13	16	30	85	45	135	16	RI 16
	14.000-16135-16	14	16	30	85	45	135	16	RI 16
	15.000-16135-16	15	16	30	85	45	135	16	RI 16
	16.000-20155-16	16	16	30	100	50	155	20	RI 16
	17.000-20155-16	17	16	30	100	50	155	20	RI 16
	18.000-20155-17	18	17	30	100	50	155	20	RI 17
	19.000-20155-17	19	17	30	100	50	155	20	RI 17
	20.000-25165-17	20	17	30	110	56	165	25	RI 17
	21.000-25165-17	21	17	30	110	56	165	25	RI 17
	22.000-25165-17	22	17	30	110	56	165	25	RI 17
	23.000-25165-17	23	17	30	110	56	165	25	RI 17
	24.000-25165-17	23	17	30	110	56	165	25 25	RI 17
	25.000-25165-17	25	17	30	110	56	165	25	RI 17
	26.000-25165-17	26	17	30	110	56	165	25	RI 17
	27.000-25165-17	27	17	30	110	56	165	25	RI 17
	28.000-32165-22	28	22	30	110	56	165	32	RI 22
	29.000-32165-22	29	22	30	110	56	165	32	RI 22
	30.000-32165-22	30	22	30	110	56	165	32	RI 22
	31.000-32165-22	31	22	30	110	56	165	32	RI 22

<sup>→</sup> Applicable inserts F85



### **Tooling System**

G02	Tooling System Index	G49	FMA
G04	DHE/S	G50	FMC
G07	DHE	G52	MD
G11	DHC/DHJ Collet	G54	EXT Bar
G12	DSC	G54	RDC Bar
G20	NPM	G55	FBH/B
G23	DCS/DC/TC	G62	DBCA
G24	Collet Chuck Series	G66	DBC
G25	SDC/P	G68	SMB
G30	DSK	G70	KMB
G32	GSK	G72	SMH
G34	GERC	G74	TBCA
G36	ER	G79	TBC
G37	ER/L	G82	FBC
G38	RTJW	G85	SAH
G40	NPU	G86	Angular Head
G41	DST	G94	DZC
G43	TER Tap Collet	G95	DCJ
G44	DTN	G96	DCL
G46	TCA Tap Adaptor	G97	DAMPHNG PRO
G47	SLA	G104	Others

# H Tooling System Index



**G54** 

**G55** 

**G54** 

G52

# Tooling System Index H



G99, 101

**G95** 

**G96** 

H100, 102, 103

## G DHE/S

#### Slim hydraulic expansion chuck

## DHE/S

- Optimized chuck for machining that requires high-quality surface roughness and accuracy
- Suitable for challenging mold and automotive parts machining that involves complicated shapes and a lot of interferences
- Ideal for metal impeller machining, which requires deep penetration
- Enables easy tool connection without any additional connecting device
- Easy to perform fine boring operations (0.02-0.2 mm)
- · Application scope: milling, drilling, reaming

#### Code system




#### Recommended Machining Works




- Optimized for machining that requires high precision
- · Enables challenging narrow and deep machining
- · Products that require fine boring operations

## Stable Clamping force




 Maintains high clamping force and good accuracy by holding the tool at two points

#### **Product Comparison**



- Length and thickness are the same as those of DSC/M Type (if the tool projection length is 40 mm, difference of  $\alpha$  = around 2°)
- Longer gauge line and higher rigidity (versus the DSC/M Type)
- · Ideal for mold machining due to its 3-degree taper shape


#### High-precision





## **BT-DHE/S**





(mm)

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	RPM	Run-out Based on 3D	\(\frac{\cappa_{kg}}{\kappa_{kg}}\)
BT30 -	DHE6S-115	6	16.8	50	115	50	25,000	5 µm	1.1
	DHE6S-180	6	16.8	50	180	115	25,000	8 <i>µm</i>	1.4
	DHE8S-115	8	18.8	50	115	50	25,000	5 µm	1.1
	DHE8S-180	8	18.8	50	180	115	25,000	8 µm	1.4
	DHE10S-120	10	20.8	50	120	55	25,000	5 µm	1.4
	DHE10S-180	10	20.8	50	180	115	25,000	8 <i>µm</i>	1.9
	DHE12S-130	12	22.8	50	130	65	25,000	5 µm	1.2
	DHE12S-180	12	22.8	50	180	115	25,000	8 µm	1.6
BT40 -	DHE6S-120	6	16.8	50	120	50	15,000	5 µm	1.7
	DHE6S-185	6	16.8	50	185	115	15,000	8 µm	2.0
	DHE8S-120	8	18.8	50	120	50	15,000	5 μm	2.0
	DHE8S-185	8	18.8	50	185	115	15,000	8 µm	2.0
	DHE10S-125	10	20.8	50	125	55	15,000	5 µm	1.6
	DHE10S-185	10	20.8	50	185	115	15,000	8 µm	2.0
	DHE12S-135	12	22.8	50	135	65	15,000	5 µm	1.8
	DHE12S-185	12	22.8	50	185	115	15,000	8 µm	2.2


<sup>●</sup> Spare Part G06

<sup>•</sup> Through coolant system installed



## **HSK-DHE/S**





(mm)

De	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	RPM	Run-out Based on 3D	\(\rightarrow\) \(\left(\kg\)\)
HSK63A -	DHE6S-120	6	16.8	50	120	50	10,000	5 μm	1.4
	DHE6S-185	6	16.8	50	185	115	10,000	8 <i>µm</i>	1.7
	DHE8S-120	8	18.8	50	120	50	10,000	5 μm	1.4
	DHE8S-185	8	18.8	50	185	115	10,000	8 <i>µm</i>	1.8
	DHE10S-125	10	20.8	50	125	55	10,000	5 µm	1.5
	DHE10S-185	10	20.8	50	185	115	10,000	8 <i>µm</i>	1.8
	DHE12S-135	12	22.8	50	135	65	10,000	5 µm	1.8
	DHE12S-185	12	22.8	50	185	115	10,000	8 <i>µm</i>	1.8

<sup>•</sup> Through coolant system installed

### Parts

Basic							
Divi	sion	Clamp bolt	Wrench	Division	Adjust screw		
Designation	Parts		1	Parts Designation			
ВТ30	DHE/S 6, 8, 10, 12	BTF1010	DHETW-5	DHE/S 6, 8, 10	DHE-M5 (ADJ)		
BT40/HSK63A	DHE/S 6, 8, 10, 12	BTF1010	DHETW-5	DHE/S 12	DHE-M10 (ADJ)		

#### Hydraulic expansion chuck

## DHE

- Ideal for mold making and machining automobile components & precise parts due to high precision machining
- Improved surface roughness due to vibration proof by hydraulic chamber
- Reduced replacement time and tiredness of worker with the use of T wrench for removal
- Applicable shank diameter: Ø6~32



#### Code system



#### Features


High accuracy provides long tool life due to reduced wear and hydraulic room enhances a surface roughness by lessening vibrations

- RUN OUT: under 5  $\mu m$
- $-L = 3 \times \emptyset D$
- Shank: Tolerance of ØD: h6



#### Internal sealing structure (Durability)

- Internal sealing system protects the chuck against dust, cutting oil, lubricant and chips getting into it
- Maintaining clamping force and accuracy for a long time



Shank	Grade	Max.rpm
BT50, HSK100A		8,000
BT40, HSK63A	G6.3	10,000
BT30, SK30		15,000



#### With simple t-wrench, very easy to change a tool

- Clamping structure for easy operation (Convenience)
- Decrease of worker's fatigue



#### Stable clamping


The clearance between holder and tool is fixed by hydraulic pressure



## G DHE

## **BT-DHE**






	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	н	Adjust screw		Fig.
BT30 -	DHE6-65	6	29	46	65	33	30~39.8	M5	0.7	1
	DHE8-65	8	31	46	65	33	30~39.8	M5	0.7	1
	DHE10-65	10	32	46	65	34	35~44.8	M5	0.7	1
	DHE12-70	12	35	46	70	34	41~50.8	M5	8.0	1
	DHE14-90	14	36	46	90	40	43~52.8	M5	1.0	1
	DHE16-90	16	40	46	90	45	46~55.8	M5	1.0	1
	DHE18-90	18	42	46	90	40	49~58.8	M5	1.1	1
	DHE20-90	20	44	46	90	45	49~58.8	M5	1.1	1
BT40 -	DHE6-90	6	29	50	90	40	30~39.8	M5	1.4	1
	DHE6-140	6	29	50	140	40	30~39.8	M5	2.2	1
	DHE8-90	8	31	50	90	40	30~39.8	M5	1.4	1
	DHE8-140	8	31	50	140	40	30~39.8	M5	2.2	1
	DHE10-90	10	33	50	90	40	35~44.8	M5	1.5	1
	DHE10-140	10	33	50	140	40	35~44.8	M5	2.2	1
	DHE12-90	12	35	50	90	40	41~50.8	M10	1.5	1
	DHE12-140	12	35	50	140	40	41~50.8	M10	2.3	1
	DHE14-90	14	36	50	90	40	43~52.8	M10	1.5	1
	DHE14-140	14	36	50	140	40	43~52.8	M10	2.2	1
	DHE16-90	16	40	50	90	45	46~55.8	M10	1.5	1
	DHE16-140	16	40	50	140	45	46~55.8	M10	2.2	1
	DHE18-90	18	42	50	90	45	49~58.8	M10	1.5	1
	DHE18-140	18	42	50	140	45	49~58.8	M10	2.2	1
	DHE20-90	20	44	50	90	47	49~58.8	M10	1.5	1
	DHE20-140	20	44	50	140	50	49~58.8	M10	2.3	1
	DHE25-90	25	50	70	90	35	58~67.8	M16	2.0	2
	DHE25-105	25	57	-	105	78	51~61	M16	2.0	4
	DHE25-140	25	57	-	140	113	51~61	M16	2.6	4
	DHE32-90	32	63	75	90	35	58~67.8	M16	2.3	2
	DHE32-105	32	57	61	105	45	55~65	M16	2.4	3
	DHE32-140	32	57	61	140	45	55~65	M16	3.0	3

<sup>●</sup> Spare Part G10 ● Applicable collet G11

<sup>•</sup> H: Insertion depth of tool (Min.~max.) • Through coolant system installed

# **BT-DHE**



	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	н	Adjust screw		Fig.
BT50 -	DHE6-90	6	29	50	90	34	30~39.8	M5	3.9	1
	DHE6-140	6	29	50	140	40	30~39.8	M5	4.4	1
	DHE8-90	8	31	50	90	34	30~39.8	M5	4.2	1
	DHE8-140	8	31	50	140	40	30~39.8	M5	4.6	1
	DHE10-90	10	33	50	90	34	35~44.8	M5	3.9	1
	DHE10-140	10	33	50	140	34	35~44.8	M5	4.5	1
	DHE12-90	12	35	50	90	34	41~50.8	M10	4.0	1
	DHE12-140	12	35	50	140	34	41~50.8	M10	4.6	1
	DHE14-90	14	36	50	90	34	43~52.8	M10	3.9	1
	DHE14-140	14	36	50	140	34	43~52.8	M10	4.5	1
	DHE16-90	16	40	50	90	34	46~55.8	M10	4.1	1
	DHE16-140	16	40	50	140	34	46~55.8	M10	4.7	1
	DHE18-90	18	42	50	90	40	49~58.8	M10	4.0	1
	DHE18-140	18	42	50	140	45	49~58.8	M10	4.5	1
	DHE20-90	20	44	50	90	34	49~58.8	M10	4.0	1
	DHE20-140	20	44	50	140	47	49~58.8	M10	4.5	1
	DHE25-90	25	66	-	90	52	58~67.8	M16	4.7	2
	DHE25-150	25	57	-	150	112	51~61	M16	4.5	3
	DHE32-90	32	72	-	90	52	58~67.8	M16	5.8	2

<sup>→</sup> Spare Part G10 → Applicable collet G11

 $<sup>\</sup>bullet \text{H: Insertion depth of tool (Min.$^{-}$max.)} \quad \bullet \text{Through coolant system installed}$ 



# **HSK-DHE**







Fig. 1



(mm)

De	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	н	Adjust Screw	RPM	O kg	Fig.
HSK63A -	DHE6-75	6	29	50	75	34	30~39.8	M5	10,000	1.0	1
	DHE8-75	8	31	50	75	34	30~39.8	M5	10,000	1.0	1
	DHE10-85	10	33	50	85	40	35~44.8	M5	10,000	1.2	1
	DHE12-90	12	35	50	90	40	41~50.8	M5	10,000	1.2	1
	DHE16-95	16	40	50	95	45	46~55.8	M10	10,000	1.3	1
	DHE20-100	20	44	50	100	50	49~58.8	M10	10,000	1.4	1
	DHE20-150	20	44	50	150	50	49~58.8	M10	10,000	2.2	1
	DHE25-110	25	50	70	110	48	56~67.8	M16	10,000	2.0	2
	DHE32-110	32	63	80	110	48	56~67.8	M16	10,000	2.0	2
HSK100A -	DHE20-105	20	44	50	105	50	49~58.8	M10	8,000	2.9	1
	DHE25-115	25	50	63	115	62	58~67.8	M16	8,000	3.2	1
	DHE32-115	32	63	75	115	62	58~67.8	M16	8,000	3.8	1


Applicable collet G11

	Basic										
Divi	sion	Clamp bolt	Wrench	Division	Adjust screw						
Designation	Parts		A	Parts Designation							
DT00/U0//F0	DHE 6, 8, 10, 12	BTF1010	DHETW-5	DUE 0 0 40	DUE ME (AD I)						
BT30 / HSK50	DHE 14, 16, 18, 20	BTF1010	DHETW-5	DHE 6, 8, 10	DHE-M5 (ADJ)						
BT40 / BT50 HSK63A / HSK100A	DHE 6, 8, 10, 12, 14, 16, 18, 20	BTF1010	DHETW-5	DHE 12, 14, 16, 18, 20	DHE-M10 (ADJ)						
	DHE 25, 32	BTF1212-1.5	DHETW-6	DHE 25, 32	DHE-M16 (ADJ)						

 $<sup>\</sup>bullet \text{H: Insertion depth of tool (Min.} \\ \neg \text{max.)} \quad \bullet \text{Through coolant system is optional}$ 

# DHC Collet General type





(mm)


Designation	ØD	ØD <sub>1</sub>	L
DHC12-3, 4, 5, 6, 8	3, 4, 5, 6, 8	12	47
DHC20-3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 14, 16	3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 14, 16	20	52
DHC32- 6, 8, 10, 12, 14, 16, 18, 19, 20, 25	6, 8, 10, 12, 14, 16, 18, 19, 20, 25	32	63

<sup>•</sup> Through coolant system not available

Accuracy type

# **DHC Collet**





(mm)


Designation	ØD	ØD <sub>1</sub>	L
DHC12-3(P), 4(P), 5(P), 6(P), 8(P)	3, 4, 5, 6, 8	12	47
DHC20-3(P), 4(P), 5(P), 6(P), 7(P), 8(P), 9(P), 10(P), 11(P), 12(P), 14(P), 16(P)	3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 14, 16	20	52
DHC32-6(P), 8(P), 10(P), 12(P), 14(P), 16(P), 18(P), 19(P), 20(P), 25(P)	6, 8, 10, 12, 14, 16, 18, 19, 20, 25	32	63

<sup>•</sup> Through coolant system installed

# **DHJ Collet**

Jet coolant





Designation	ØD	ØD	L
DHJ20-6, 8, 10, 12, 14, 16	6, 8, 10, 12, 14, 16	20	50


#### **Shrinking chuck**

## **DSC**

- Use of specially heat-treated steel
- High precision machining and clamping
- Increased precision and longer tool life due to minimized overhang when machining deep grooves
- Applicable shank diameter: Ø3~32



#### Code System




#### Mono curve type

- · Integral DSC with excellent precision and balancing
- · Long but stable holder design





#### High clamping force



- 30% stronger Clamping Force
- Run-Out (≤ 0.003 mm)

Collet chuck

• Higher Power transmission Clamping Force by Inner-Size

#### Shrinking chuck Fix the clearance between holder and tool by heat shrinking

Fix the tool by elasticity of collet

Elastic deformation Strong clamping

Thermal expansion ▶ Thermal shrinking Highly strong clamping

#### Slim type series




Used by combining with various holders such as hydraulic expansion chuck, milling chuck, and collet chuck

Used with high precision as integral types


Holder + collet connection shape Connecting the holder and collet by the bolt tightening method

## 2-pieces type

2Piece types enable various machining operations by collet replacement and provide convenience in tool management and use based on easy and fast assembly using tightening bolts.



#### Mono type




## Straight type

Figure	Accuracy	Туре
3° taper		Slim type Middle type 2-4.5t
Thickness t	3 x D Run-out 3 µm	Used by combining with various holders such as hydraulic expansion chuck, milling chuck, and collet chuck, etc.

# **BT-DSC**






(mm)

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	н	G	RPM	kg
BT30 -	DSC3-60	3	11	18.5	60	82	-	25,000	0.4
	DSC4-60	4	13	20.5	60	82	-	25,000	0.4
BT40 -	DSC6-90	6	21	27	90	36	M5	20,000	1.1
	DSC6-120	6	21	27	120	36	M5	20,000	1.2
	DSC6-160	6	21	27	160	36	M5	20,000	1.4
	DSC8-90	8	21	27	90	36	M5	20,000	1.1
	DSC8-120	8	21	27	120	36	M5	20,000	1.2
	DSC8-160	8	21	27	160	36	M5	20,000	1.4
	DSC10-90	10	24	32	90	42	M8	20,000	1.1
	DSC10-120	10	24	32	120	42	M8	20,000	1.3
	DSC10-160	10	24	32	160	42	M8	20,000	1.6
	DSC12-90	12	24	32	90	47	M8	20,000	1.1
	DSC12-120	12	24	32	120	47	M8	20,000	1.3
	DSC12-160	12	24	32	160	47	M8	20,000	1.6
	DSC16-90	16	27	34	90	50	M12	20,000	1.2
	DSC16-120	16	27	34	120	50	M12	20,000	1.3
	DSC16-160	16	27	34	160	50	M12	20,000	1.7
	DSC20-90	20	33	42	90	52	M12	20,000	1.3
	DSC20-120	20	33	42	120	52	M12	20,000	1.5
	DSC20-160	20	33	42	160	52	M12	20,000	2.0

<sup>→</sup> Adjust screw G19

# **BT-DSC/M**






(mm)

Mono Curve type

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	н	RPM	
BT30 -	DSC3M-75S	3	8	25	75	29.8	97	25,000	0.4
	DSC4M-75S	4	10	25	75	31.8	97	25,000	0.4
	DSC6M-75S	6	12	30	75	28.9	97	25,000	0.5
	DSC8M-75S	8	14	32	75	28.9	97	25,000	0.5
	DSC10M-75S	10	16	32	75	30.7	45	25,000	0.5
	DSC12M-75S	12	19	32	75	33.8	45	25,000	0.5

<sup>•</sup> H: Insertion depth of tool • Through coolant system installed

# BT-DSC/M Mono type



	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	М	Н	RPM	O kg	Fig.
BT40 -	DSC3M-95	3	8	26	95	42	128	20,000	1.1	1
	DSC4M-95	4	8	26	95	42	128	20,000	1.1	1
	DSC6M-95	6	10	26	95	42	128	20,000	1.0	1
	DSC6M-120	6	10	26	120	67	153	20,000	1.0	1
	DSC6M-160	6	10	36	160	97	193	20,000	1.2	1
	DSC8M-95	8	13	36	95	42	128	20,000	1.3	1
	DSC8M-120	8	13	36	120	67	153	20,000	1.3	1
	DSC8M-160	8	13	36	160	97	193	20,000	1.3	1
	DSC10M-95	10	16	36	95	42	128	20,000	1.1	1
	DSC10M-120	10	16	36	120	67	153	20,000	1.1	1
	DSC10M-160	10	16	36	160	97	193	20,000	1.3	1
	DSC12M-95	12	19	36	95	42	128	20,000	1.1	1
	DSC12M-120	12	19	36	120	67	153	20,000	1.2	1
	DSC12M-160	12	19	36	160	97	193	20,000	1.4	1
	DSC16M-95	16	24	50	95	42	47	20,000	1.3	2
	DSC16M-120	16	24	50	120	67	47	20,000	1.4	2
	DSC16M-160	16	24	50	160	97	47	20,000	1.7	2
	DSC20M-95	20	29	50	95	42	55	20,000	1.3	2
	DSC20M-120	20	29	50	120	67	55	20,000	1.5	2
	DSC20M-160	20	29	50	160	97	55	20,000	1.9	2
3T50 -	DSC6M-110	6	10	26	110	42	163	15,000	3.5	1
	DSC6M-160	6	10	36	160	97	213	15,000	3.6	1
	DSC8M-110	8	13	36	110	42	163	15,000	3.7	1
	DSC8M-160	8	13	36	160	97	213	15,000	3.7	1
	DSC10M-110	10	16	36	110	42	163	15,000	3.7	1
	DSC10M-160	10	16	36	160	97	213	15,000	3.7	1
	DSC12M-110	12	19	36	110	42	163	15,000	3.7	1
	DSC12M-160	12	19	50	160	97	213	15,000	4.0	1
	DSC16M-110	16	24	50	110	42	163	15,000	3.9	1
	DSC16M-160	16	24	50	160	97	213	15,000	4.1	1
	DSC20M-110	20	29	50	110	42	55	15,000	3.9	2
	DSC20M-160	20	29	50	160	97	55	15,000	4.2	2

Adjust screw G19


<sup>•</sup> H: Insertion depth of tool • Through coolant system installed



# **HSK-DSC/M**

#### Mono type





(mm)

D	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	M	н	RPM	
HSK63A -	DSC6M-95	6	10	26	95	42	73	20,000	0.7
	DSC8M-95	8	13	36	95	42	39	20,000	0.8
	DSC10M-120	10	16	36	120	67	45	20,000	0.8
	DSC12M-120	12	19	36	120	67	45	20,000	0.9
	DSC16M-120	16	24	50	120	67	47	20,000	1.1


• H: Insertion depth of tool • Not able to use the adjust screw

Through coolant system is optional

# ST-DSC/M

#### Straight Shank Shrinking Chuck





(mm)


	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	М	Н	\(\rightarrow\) \(\lambda\) kg\
ST16 -	DSC6M-115	6	10	16	115	50	95	0.1
	DSC6M-140	6	10	16	140	60	120	0.1
ST20 -	DSC6M-175	6	10	20	175	95	155	0.2
	DSC8M-145	8	13	20	145	70	125	0.2
	DSC10M-120	10	16	20	120	50	45	0.2
ST25 -	DSC8M-175	8	13	25	175	105	155	0.4
	DSC10M-145	10	16	25	145	75	45	0.4
	DSC10M-175	10	16	25	175	105	45	0.4
	DSC12M-120	12	19	25	120	50	45	0.3
	DSC12M-150	12	19	25	150	80	45	0.4
	DSC16M-175	16	24	25	175	50	47	0.5
ST32 -	DSC20M-175	20	29	32	175	50	55	0.8

•H: Insertion depth of tool •Not able to use the adjust screw •Through coolant system installed

# ST-DSC/S

#### Straight Shank Shrinking Chuck





(mm)

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	М	н
ST16 -	DSC6S-115	6	9	16	115	55	95
	DSC6S-140	6	9	16	140	70	120
	DSC8S-115	8	11	16	115	50	95
ST20 -	DSC6S-175	6	9	20	175	105	155
	DSC8S-175	8	11	20	175	85	155
	DSC10S-145	10	13	20	145	75	77
	DSC12S-120	12	15	20	120	50	52
ST32 -	DSC12S-315	12	15	32	315	185	295


• H: Insertion depth of tool • Not able to use the adjust screw

• Through coolant system installed

# **BT-DSC/S**

## Mono slim type






	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	M	н	RPM	\(\frac{\O}{kg}\)
BT30 -	DSC6S-60	6	9	20	60	22	82	25,000	0.4
	DSC6S-80	6	9	20	80	42	102	25,000	0.5
	DSC6S-120	6	9	25	120	67	142	25,000	0.5
BT40 -	DSC6S-95	6	9	26	95	42	128	20,000	1.0
	DSC6S-120	6	9	26	120	67	153	20,000	1.0
	DSC6S-160	6	9	36	160	97	193	20,000	1.2
	DSC8S-95	8	11	36	95	42	128	20,000	1.1
	DSC8S-120	8	11	36	120	67	153	20,000	1.1
	DSC8S-160	8	11	36	160	97	193	20,000	1.2
	DSC10S-95	10	13	36	95	42	128	20,000	1.0
	DSC10S-120	10	13	36	120	67	153	20,000	1.1
	DSC10S-160	10	13	36	160	97	193	20,000	1.2
	DSC12S-95	12	15	36	95	42	128	20,000	1.1
	DSC12S-120	12	15	36	120	67	153	20,000	1.1
	DSC12S-160	12	15	36	160	97	193	20,000	1.2
BT50 -	DSC6S-110	6	9	26	110	42	166	15,000	3.5
	DSC6S-160	6	9	36	160	97	216	15,000	3.6
	DSC8S-110	8	11	36	110	42	166	15,000	3.6
	DSC8S-160	8	11	36	160	97	216	15,000	3.6
	DSC10S-110	10	13	36	110	42	166	15,000	3.6
	DSC10S-160	10	13	36	160	97	216	15,000	3.6
	DSC12S-110	12	15	36	110	42	166	15,000	3.6
	DSC12S-160	12	15	36	160	97	216	15,000	3.7



CS/CM 2-pieces type





(mm)

	Designation	ØD	ØD <sub>1</sub>	L	М	н	kg
CS12	6-35	6	9	35	22	55	0.1
	6-80	6	9	80	67	100	0.2
	6-110	6	9	110	97	130	0.2
	8-35	8	11	35	22	55	0.1
	8-110	8	11	110	97	130	0.3
	10-35	10	13	35	22	45	0.1
	10-80	10	13	80	67	65	0.2
	10-110	10	13	110	97	65	0.3
	12-35	12	15	35	22	45	0.1
	12-55	12	15	55	42	49.5	0.2
	12-80	12	15	80	67	65	0.2
	12-110	12	15	110	97	65	0.3

•H: Insertion depth of tool •Not able to use the adjust screw •Through coolant system installed


(mm)

	Designation	ØD	ØD <sub>1</sub>	L	М	н	G	∑ kg \
CM12	6-35	6	12	35	22	55	M5	0.2
	6-80	6	12	80	67	100	M5	0.2
	8-35	8	14	35	22	55	M5	0.2
	8-55	8	14	55	42	75	M5	0.2
	8-80	8	14	80	67	100	M5	0.3
	10-35	10	16	35	22	45	M8	0.2
	10-55	10	16	55	42	45	M8	0.2
	10-80	10	16	80	67	45	M8	0.3
	12-35	12	20	35	22	45	M8	0.2
	12-55	12	20	55	42	45	M8	0.3
	12-80	12	20	80	52	55	M8	0.3

•H: Insertion depth of tool •Not able to use the adjust screw •Through coolant system installed

BT-SLK 2-pieces type





(mm)

	Designation	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	L <sub>2</sub>	
BT30 -	SLK12-35	38	-	35	13	-	0.4
S	SLK12-45F	41	-	45	18	-	1.0
	SLK12-75F	41	-	75	48	-	1.3
	SLK12-135F	41	-	135	108	-	2.1
BT50 -	SLK12-75	38	65	75	25	12	4.1
	SLK12-75F	41	65	75	25	12	4.1
	SLK12-105F	41	65	105	55	12	4.5
	SLK12-135F	41	65	135	85	12	5.3
	SLK12-225	38	65	225	150	37	6.2
	SLK12-315	38	90	315	150	127	11.5

• Through coolant system installed • PULL STUD BOLT is needed for BT30-SLK12-35

Basic											
	Туре	DSC6	DSC8	DSC10	DSC12	DSC14	DSC16	DSC18	DSC20	DSC25	DSC32
Adjust screw		M52	20C	M82	20C			M12	230C		



#### New power milling chuck

## **NPM**


- Strong clamping over 500kgf·m (on NPM42 basis)
- DUST BLOCK functions for blocking foreign substance
- Jet coolant available
- High precision within 15 μm at L/D = 3
- Boring range: Ø20~42



#### Code system



#### Improvement of durability by preventing minute dust, chips and coolant






**Needle Roller Bearing** 

#### Stable machining from heavy to fine


Perfect face contact and Powerful clamping force strengthen both Cutting force and Absorbtion of vibration.





# **BT-NPM**





(mm)

	Designation	ØD	ØD <sub>1</sub>	L	н	G	Collet	kg
BT30 -	NPM20-85	20	54	85	85	M16	DC20, DCS20, DCJ20	1.2
BT40 -	NPM20-85	20	54	85	85	M16	DC20, DCS20, DCJ20	2.6
	NPM20-100	20	54	100	85	M16	DC20, DCS20, DCJ20	2.3
	NPM25-85	25	61	85	85	M16	DC25	1.7
	NPM32-90	32	75	90	87	M16	DC32, DCS32, DCJ32	2.3
	NPM32-110	32	75	110	95	M16	DC32, DCS32, DCJ32	2.8
	NPM32-135	32	75	135	95	M16	DC32, DCS32, DCJ32	3.5
BT50 -	NPM20-95	20	54	95	85	M16	DC20, DCS20, DCJ20	4.3
	NPM20-125	20	54	125	85	M16	DC20, DCS20, DCJ20	4.7
	NPM20-165	20	54	165	85	M16	DC20, DCS20, DCJ20	5.2
	NPM32-110	32	75	110	105	M24	DC32, DCS32, DCJ32	5.0
	NPM32-135	32	75	135	105	M24	DC32, DCS32, DCJ32	5.7
	NPM32-165	32	75	165	105	M24	DC32, DCS32, DCJ32	6.9
	NPM42-110	42	90	110	125	M24	DC42, DCS42	5.4
	NPM42-135	42	90	135	125	M24	DC42, DCS42	6.5
	NPM42-165	42	90	165	125	M24	DC42, DCS42	7.9

Applicable collet G23

For separate purchase									
Division	Collet	Spanner	Through coolant system						
Parts Designation			Ô						
NPM20	DC20, DCS20, DCJ20	57-60	CTC20-□□						
NPM32	DC32, DCS32, DCJ20	75-79	CTC32-□□						
NPM42	DC42, DCS42	92-96	CTC42-□□						


<sup>•</sup> H: Insertion depth of tool • Through coolant system is optional

<sup>•</sup> In case of L  $\leq$  90, chucks with over 90mm are recommended for medium cutting by short cap



# **HSK-NPM**





(mm)

De	Designation		ØD <sub>1</sub>	L	L <sub>1</sub>	н	Collet	\(\frac{\O}{kg}\)
HSK63A -	NPM20-100	20	54	100	74	75	DC20, DSC20, DCJ20	2.5
	NPM32-120	32	75	120	84	90	DC32, DCS32, DCJ32	2.9
HSK100A -	NPM32-130	32	75	130	101	90	DC32, DCS32, DCJ32	4.0

● Spare Part G21, G22 ● Applicable collet G23


 $\bullet \text{H: Insertion depth of tool } \quad \bullet \text{Through coolant system is optional }$ 



Classification by shank							
HSK50	HSK50A-CNS						
HSK63	HSK63A-CNS						
HSK100	HSK100A-CNS						

DCS Straight Collet






(mm)

Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	
DCS20-6, 8, 10, 12, 16	6, 8, 10, 12, 16	20	26	55	0.2
DCS32-6, 8, 10, 12, 14, 16, 19, 20, 25	6, 8, 10, 12, 14, 16, 19, 20, 25	32	38	70	0.4
DCS42-6, 8, 10, 12, 16, 20, 25, 32	6, 8, 10, 12, 16, 20, 25, 32	42	48	75	0.7

DC Straight Collet






(mm)

Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	
DC20-6, 8, 10, 12, 14, 16	6, 8, 10, 12, 14, 16	20	26	53	0.1
DC25-6, 8, 10, 12, 16	6, 8, 10, 12, 16	25	29	61.5	0.2
DC32-6, 8, 10, 12, 14, 16, 19, 20, 25	6, 8, 10, 12, 14, 16, 19, 20, 25	32	38	64.5	0.2
DC42-6, 8, 10, 12, 16, 20, 25, 32	6, 8, 10, 12, 16, 20, 25, 32	42	48	73	0.5

Taper Collet





(mm


									(11111)
Designation	ØD	ØD <sub>1</sub>	L	MT No.	Designation	ØD	ØD <sub>1</sub>	L	MT No.
TC20-1	26	20	60	MT1	TC32-3	38	32	90	MT3
TC20-2	26	20	72	MT2	TC42-1	48	42	60	MT1
TC25-1	32	25	60	MT1	TC42-2	48	42	72	MT2
TC25-2	32	25	72	MT2	TC42-3	48	42	90	MT3
TC32-1	38	32	60	MT1	TC42-4	48	42	112.5	MT4
TC32-2	38	32	72	MT2					

# G Collet Chuck Series

#### **Collet chuck**

## SDC/P

- Improved precision (higher than conventional SDC)
- Simpler model number management than conventional SDC due to its organized gauge line
- Collet chuck suitable for multi-purpose machining with SWISSMADE sleeve nut adopted
- Boring range: Ø1~Ø25









Soft sleeve bearing RN Nut After


#### High speed collet chuck

# DSK

- Available for machining at max.15,000 RPM and balancing of G6.3
- Minimized tool vibration during operation by using collet 8°
- · Swiss made high precision nut enhances stability
- Tool clamping range: Ø2~25

Standard type & Precision type	Designation	Max chucking	Run-out
	HC6-Ød	6.0	
	HC10-Ød	10.0	Standard type
	HC13-Ød	13.0	5 µm ´
	HC16-Ød	16.0	Precision type
	HC20-Ød	20.0	3 µm
	HC25-Ød	25.0	






#### Great speed slim collet chuck

# **GSK**

- Available for machining at max.25,000 RPM and balancing of G6.3
- Increased productivity due to high speed machining
- Minimized tool vibration during operation by using collet 8°
- · Swiss made high precision nut enhances stability by pressing collet uniformly
- Tool clamping range: Ø2~25








Nut ideal for high speed rotation

Strong clamping by  $8^{\circ}$  collet and stable fixing with the use of planar part fixing




Chattering due to imbalance

Imbalance due to centrifugal force during high speed rotation



# BT-SDC/P



										(mm)
	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	Н	Collet	G	\(\sum_{kg}\)	Fig.
BT30 -	SDC7P-70	1.0~7.0	18	17	70	33	GERC11	M7	0.5	1
	SDC7P-100	1.0~7.0	18	17	100	33	GERC11	M7	0.5	1
	SDC10P-50	1.0~10.0	32	-	50	44.5	GERC16	M10	0.5	2
	SDC10P-70	1.0~10.0	32	31	70	44.5	GERC16	M10	0.6	1
	SDC10P-100	1.0~10.0	32	31	100	44.5	GERC16	M10	0.7	1
	SDC13P-50	1.0~13.0	35	-	50	49	GERC20	M7	0.5	2
	SDC13P-70	1.0~13.0	35	34	70	49	GERC20	M13	0.6	1
	SDC13P-100	1.0~13.0	35	34	100	49	GERC20	M13	0.8	1
	SDC16P-50	2.0~16.0	42	-	50	50	GERC25	M7	0.5	2
	SDC16P-70	2.0~16.0	42	41	70	50	GERC25	M18	0.7	1
	SDC16P-100	2.0~16.0	42	41	100	50	GERC25	M18	1.0	1
	SDC20P-60	2.0~20.0	50	-	60	60	GERC32	M7	0.6	2
	SDC20P-90	2.0~20.0	50	49	90	60	GERC32	M22	1.0	3
	SDC20P-120	2.0~20.0	50	49	120	60	GERC32	M22	1.4	3
BT40 -	SDC7P-70	1.0~7.0	18	17	70	33	GERC11	M7	0.9	1
	SDC7P-90	1.0~7.0	18	17	90	33	GERC11	M7	0.9	1
	SDC7P-130	1.0~7.0	18	17	130	33	GERC11	M7	1.0	1
	SDC10P-70	1.0~10.0	32	31	70	44.5	GERC16	M10	1.0	1
	SDC10P-90	1.0~10.0	32	31	90	44.5	GERC16	M10	1.2	1
	SDC10P-130	1.0~10.0	32	31	130	44.5	GERC16	M10	1.4	1
	SDC13P-70	1.0~13.0	35	34	70	49	GERC20	M13	1.1	1
	SDC13P-90	1.0~13.0	35	34	90	49	GERC20	M13	1.2	1
	SDC13P-130	1.0~13.0	35	34	130	49	GERC20	M13	1.4	1
	SDC13P-150	1.0~13.0	35	34	150	49	GERC20	M13	1.6	1
	SDC16P-70	2.0~16.0	42	41	70	50	GERC25	M18	1.1	1
	SDC16P-90	2.0~16.0	42	41	90	50	GERC25	M18	1.3	1
	SDC16P-130	2.0~16.0	42	41	130	50	GERC25	M18	1.7	1
	SDC20P-70	2.0~20.0	50	-	70	60	GERC32	M22	1.1	2
	SDC20P-90	2.0~20.0	50	49	90	60	GERC32	M22	1.4	1
	SDC20P-130	2.0~20.0	50	49	130	60	GERC32	M22	1.9	1
	SDC20P-150	2.0~20.0	50	49	150	60	GERC32	M22	2.2	1
	SDC26P-90	16.0~26.0	63	62	90	71	GERC40	M28	1.7	1


<sup>◆</sup> Spare Part G26 ◆ Applicable collet G33

 $<sup>\</sup>bullet \text{H: Insertion depth of tool} \qquad \bullet \text{Through coolant system is optional}$ • Collets in the right size are recommended for oil hole type



# BT-SDC/P





(mm)

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	н	Collet	G	kg	Fig.
BT50 -	SDC10P-100	1.0~10.0	32	31	100	44.5	GERC16	M10	3.7	1
	SDC10P-120	1.0~10.0	32	31	120	44.5	GERC16	M10	3.7	1
	SDC10P-160	1.0~10.0	32	31	160	44.5	GERC16	M10	3.8	1
	SDC13P-100	1.0~13.0	35	34	100	49	GERC20	M13	3.8	1
	SDC13P-130	1.0~13.0	35	34	130	49	GERC20	M13	3.8	1
	SDC13P-160	1.0~13.0	35	34	160	49	GERC20	M13	4.1	1
	SDC13P-180	1.0~13.0	35	34	180	49	GERC20	M13	4.2	1
	SDC16P-100	2.0~16.0	42	41	100	50	GERC25	M18	3.9	1
	SDC16P-160	2.0~16.0	42	41	160	50	GERC25	M18	4.3	1
	SDC20P-70	2.0~20.0	50	-	70	60	GERC32	M22	1.7	2
	SDC20P-100	2.0~20.0	50	49	100	60	GERC32	M22	4.0	1
	SDC20P-130	2.0~20.0	50	49	130	60	GERC32	M22	4.3	1
	SDC20P-160	2.0~20.0	50	49	160	60	GERC32	M22	4.7	1
	SDC20P-180	2.0~20.0	50	49	180	60	GERC32	M22	5.0	1
	SDC26P-160	16.0~26.0	63	62	160	71	GERC40	M28	5.5	1


<sup>⇒</sup> Spare Part G26 ⇒ Applicable collet G33

	Basic		For separate purchase				
Division	Sleeve bearing nut	Adjust screw	Spanner	Collet			
Parts  Designation	0;	•	P	<b>(</b>			
SDC7P	RN11	BN0716F	20-22	GERC/ER 11-ØD			
SDC10P	RN16	BN1025F	32-35	GERC/ER 16-ØD			
SDC13P	RN20	BN1325F	35-38	GERC/ER 20-ØD			
SDC16P	RN25	BN1830F	42-46	GERC/ER 25-ØD			
SDC20P	RN32	BN2230F	48-52	GERC/ER 32-ØD			
SDC26P	RN40	BN2838F	62-65	GERC/ER 40-ØD			

<sup>•</sup> H: Insertion depth of tool • Through coolant system is optional • Collets in the right size are recommended for oil hole type

# **HSK-SDC/P**





(mm)

De	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	н	Collet	G	
HSK63A -	SDC10P-100	1.0~10.0	32	31	100	44.5	GER16	M10	1.0
	SDC13P-100	1.0~13.0	35	34	100	49	GER20	M7	1.1
	SDC16P-100	1.0~16.0	42	41	100	50	GER25	M7	1.2
	SDC20P-110	1.0~20.0	50	49	110	60	GER32	M7	1.5
HSK100A -	SDC16P-110	1.0~16.0	42	41	110	50	GER25	M13	2.6
	SDC20P-120	2.0~20.0	50	49	120	60	GER32	M10	2.9

<sup>⇒</sup> Spare Part G26, G27 ⇒ Applicable collet G33

Division	For separate purchase
Internal coolant system	


Classification	on by shank
HSK50	HSK50A-CNS
HSK63	HSK63A-CNS
HSK100	HSK100A-CNS

<sup>•</sup> H: Insertion depth of tool • Through coolant system is optional • Collets in the right size are recommended for oil hole type

# G SDC/P

# S-SDC






	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	<b>L</b> 2	Н	Collet	G	∑ kg \
S16 -	SDC7-120M	1.0~7.0	19	16	120	-	-	33	GERC11	M7	0.1
	SDC7-120T	1.0~7.0	19	16	120	-	73	33	GERC11	M7	0.1
	SDC10-150T	1.0~10.0	28	16	150	46.5	83	34.5	GERC16	M10	0.2
S20 -	SDC10-150M	1.0~10.0	28	20	150	26.5	-	34.5	GERC16	M10	0.3
	SDC10-150T	1.0~10.0	28	20	150	26.5	83	34.5	GERC16	M10	0.3
	SDC13-150M	1.0~13.0	35	20	150	50	-	49	GERC20	M13	0.3
	SDC13-150T	1.0~13.0	35	20	150	50	83	49	GERC20	M13	0.3
S25 -	SDC10-150M	1.0~10.0	28	25	150	-	-	34.5	GERC16	M10	0.4
	SDC10-150T	1.0~10.0	28	25	150	-	83	34.5	GERC16	M10	0.4
	SDC13-150M	1.0~13.0	35	25	150	-	-	49	GERC20	M13	0.4
	SDC13-150T	1.0~13.0	35	25	150	-	83	49	GERC20	M13	0.4
S32 -	SDC13-150M	1.0~13.0	35	32	150	-	-	49	GERC20	M13	0.7
	SDC13-150T	1.0~13.0	35	32	150	-	83	49	GERC20	M13	0.7
	SDC20-165M	2.0~20.0	50	32	165	-	-	60	GERC32	M22	0.9
	SDC20-165T	2.0~20.0	50	32	165	-	83	60	GERC32	M22	0.9

Applicable collet G33

 $<sup>\</sup>bullet \text{H: Insertion depth of tool} \qquad \bullet \text{Through coolant system is optional}$ 

# S-SDC/S



										(mm)
	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	Н	Collet/Step	G	\(\frac{O}{kg}\)
S16 -	SDC7S-100M	1.0~7.0	16	16	100	21	33	GERC11/0.5	M7	0.1
	SDC7S-150M	1.0~7.0	16	16	150	21	33	GERC11/0.5	M7	0.1
	SDC10S-100M	1.0~10.0	22	16	100	50	44.5	GERC16/1.0	M10	0.1
	SDC10S-150M	1.0~10.0	22	16	150	50	44.5	GERC16/1.0	M10	0.1
S20 -	SDC7S-100M	1.0~7.0	16	20	100	30	35	GERC11/0.5	M7	0.1
	SDC7S-150M	1.0~7.0	16	20	150	80	35	GERC11/0.5	M7	0.2
	SDC10S-100M	1.0~10.0	22	20	100	50	44.5	GERC16/1.0	M10	0.1
	SDC10S-150M	1.0~10.0	22	20	150	50	44.5	GERC16/1.0	M10	0.2
	SDC10S-200M	1.0~10.0	22	20	200	50	44.5	GERC16/1.0	M10	0.3
	SDC13S-100M	1.0~13.0	28	20	100	50	49	GERC20/1.0	M13	0.1
	SDC13S-150M	1.0~13.0	28	20	150	50	49	GERC20/1.0	M13	0.2
S25 -	SDC7S-100M	1.0~7.0	16	25	100	30	33	GERC11/0.5	M7	0.2
	SDC7S-150M	1.0~7.0	16	25	150	80	33	GERC11/0.5	M7	0.2
	SDC10S-100M	1.0~10.0	22	25	100	30	44.5	GERC16/1.0	M10	0.2
	SDC10S-150M	1.0~10.0	22	25	150	80	44.5	GERC16/1.0	M10	0.3
	SDC13S-100M	1.0~13.0	28	25	100	50	49	GERC20/1.0	M13	0.2
	SDC13S-150M	1.0~13.0	28	25	150	50	49	GERC20/1.0	M13	0.4
	SDC16S-100M	1.0~16.0	35	25	100	50	50	GERC25/1.0	M18	0.3
	SDC16S-150M	1.0~16.0	35	25	150	50	50	GERC25/1.0	M18	0.4
	SDC16S-200M	1.0~16.0	35	25	200	50	50	GERC25/1.0	M18	0.6
S32 -	SDC16S-120M	1.0~16.0	35	32	120	50	50	GERC25/1.0	M18	0.5
	SDC16S-150M	1.0~16.0	35	32	150	50	50	GERC25/1.0	M18	0.6


Applicable collet G33

<sup>•</sup> H: Insertion depth of tool • Through coolant system is optional

# G DSK

# **BT-DSK**





	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	L <sub>2</sub>	н	Collet	G	RPM	O kg
BT30 -	DSK6-60	3.0~6.0	19.5	19.5	60	33	33	31	HC6	M8	15,000	0.4
	DSK6-90	3.0~6.0	19.5	32	90	56	65	31	HC6	M8	15,000	0.5
	DSK10-60	2.0~10.0	27.5	27.5	60	35	35	38	HC10	M12	15,000	0.5
	DSK10-90	2.0~10.0	27.5	27.5	90	65	65	38	HC10	M12	15,000	0.6
	DSK13-60	3.0~13.0	33	33	60	36	36	43	HC13	M12	15,000	0.5
	DSK16-60	3.0~16.0	40	40	60	37	37	52	HC16	M12	15,000	0.6
	DSK16-90	3.0~16.0	40	40	90	67	67	52	HC16	M18	15,000	0.8
	DSK25-90	16.0~25.0	55	55	90	67.5	67.5	63.5	HC25	M12	15,000	0.9
BT40 -	DSK6-90	3.0~6.0	19.5	32	90	51	61	31	HC6	M8	10,000	1.1
	DSK6-120	3.0~6.0	19.5	32	120	60	90	31	HC6	M8	10,000	1.1
	DSK6-150	3.0~6.0	19.5	25	150	60	120	31	HC6	M8	10,000	1.1
	DSK10-90	2.0~10.0	27.5	40	90	48	60	38	HC10	M12	10,000	1.2
	DSK10-120	2.0~10.0	27.5	40	120	73	90	38	HC10	M12	10,000	1.2
	DSK10-150	2.0~10.0	27.5	34.5	150	73	118	38	HC10	M12	10,000	1.4
	DSK13-90	3.0~13.0	33	33	90	59	59	43	HC13	M15	10,000	1.3
	DSK16-90	3.0~16.0	40	40	90	58	58	52	HC16	M18	10,000	1.3
	DSK16-120	3.0~16.0	40	40	120	88	88	52	HC16	M18	10,000	1.5
	DSK16-150	3.0~16.0	40	40	150	118	118	52	HC16	M18	10,000	1.9
	DSK20-90	4.0~20.0	48.5	48.5	90	60	60	60	HC20	M22	10,000	1.5
	DSK20-120	4.0~20.0	48.5	48.5	120	90	90	60	HC20	M22	10,000	1.8
	DSK25-90	16.0~25.0	55	55	90	61	61	63.5	HC25	M28	10,000	1.6
	DSK25-120	16.0~25.0	55	55	120	91	91	85	HC25	M28	10,000	2.0


<sup>◆</sup> Spare Part G31 ◆ Applicable collet G33

<sup>•</sup>H: Insertion depth of tool •Through coolant system is optional

<sup>•</sup> Coolant collets are recommended when using the coolant system

# **BT-DSK**





(mm)

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	L <sub>2</sub>	н	Collet	G	RPM	
BT50 -	DSK6-105	3.0~6.0	19.5	32	105	55	64	31	HC6	M8	8,000	3.6
	DSK6-135	3.0~6.0	19.5	32	135	60	92	31	HC6	M8	8,000	3.7
	DSK6-165	3.0~6.0	19.5	32	165	60	114	31	HC6	M8	8,000	4.1
	DSK10-105	2.0~10.0	27.5	27.5	105	57	57	38	HC10	M12	8,000	3.8
	DSK10-135	2.0~10.0	27.5	32	135	70	92	38	HC10	M12	8,000	3.9
	DSK10-165	2.0~10.0	27.5	36	165	75	114	38	HC10	M12	8,000	4.1
	DSK13-135	3.0~13.0	33	33	135	92	92	43	HC13	M15	8,000	3.8
	DSK16-105	3.0~16.0	40	40	105	62	62	52	HC16	M18	8,000	4.0
	DSK16-135	3.0~16.0	40	40	135	92	92	52	HC16	M18	8,000	4.2
	DSK16-165	3.0~16.0	40	50	165	40	122	52	HC16	M18	8,000	4.6
	DSK20-105	4.0~20.0	48	40	105	62	62	60	HC20	M22	8,000	4.2
	DSK20-135	4.0~20.0	48	40	135	92	92	60	HC20	M22	8,000	4.5
	DSK20-165	4.0~20.0	48	40	165	122	122	60	HC20	M22	8,000	4.9
	DSK25-105	16.0~25.0	55	55	105	62	62	63.5	HC25	M28	8,000	4.4
	DSK25-135	16.0~25.0	55	55	135	92	92	63.5	HC25	M28	8,000	4.5
	DSK25-165	16.0~25.0	55	55	165	122	122	63.5	HC25	M28	8,000	5.2

Applicable collet G33


		Basic		For separate purchase
Division	Nut	Spanner		
Parts Designation	0			
DSK6	DN6	BN0825F	DSK-6CE	DSS-6
DSK10	DN10	BN1225F	DSK-10CE	DSS-10
DSK13	DN13	BN1230 (BT30)/BN1524F (Others)	DSK-13CE	DSS-13
DSK16	DN16	BN1830F	DSK-16CE	DSS-16
DSK20	DN20	BN2230F	DSK-20CE	DSS-20
DSK25	DN25	BN2838F	DSK-25CE	DSS-25

<sup>•</sup> H: Insertion depth of tool • Through coolant system is optional • Coolant collets are recommended when using the coolant system

# G GSK

# **BT-GSK**





												(mm)
	Designation	ØD	Ø <b>D</b> 1	ØD <sub>2</sub>	L	L <sub>1</sub>	L <sub>2</sub>	Н	Collet / Step	G	RPM	O kg
BT30 -	GSK6-60	3.0~6.0	19.5	19.5	60	33	33	31	HC6/1.0	M8	25,000	0.4
	GSK6-90	3.0~6.0	19.5	32	90	56	65	31	HC6/1.0	M8	25,000	0.5
	GSK10-60	2.0~10.0	27	27	60	35	35	38	HC10/1.0	M12	25,000	0.5
	GSK10-90	2.0~10.0	27	27	90	65	65	38	HC10/1.0	M12	25,000	0.6
	GSK13-60	3.0~13.0	35	35	60	36	36	43	HC13/1.0	M12	25,000	0.6
	GSK16-60	3.0~16.0	40	40	60	37	37	52	HC16/1.0	M12	25,000	0.6
	GSK16-90	3.0~16.0	40	40	90	67	67	52	HC16/1.0	M18	25,000	0.8
	GSK25-90	16.0~25.0	55	55	90	67.5	67.5	63.5	HC25/1.0	M12	25,000	1.0
BT40 -	GSK6-90	3.0~6.0	19.5	32	90	51	61	31	HC6/1.0	M8	20,000	1.0
	GSK6-120	3.0~6.0	19.5	32	120	60	90	31	HC6/1.0	M8	20,000	1.2
	GSK6-150	3.0~6.0	19.5	25	150	60	120	31	HC6/1.0	M8	20,000	1.2
	GSK10-90	2.0~10.0	27	40	90	48	60	38	HC10/1.0	M12	20,000	1.1
	GSK10-120	2.0~10.0	27	40	120	73	90	38	HC10/1.0	M12	20,000	1.3
	GSK10-150	2.0~10.0	27	34.5	150	73	118	38	HC10/1.0	M12	20,000	1.4
	GSK13-90	3.0~13.0	35	35	90	59	59	43	HC13/1.0	M15	20,000	1.2
	GSK16-90	3.0~16.0	40	40	90	58	58	52	HC16/1.0	M18	20,000	1.3
	GSK16-120	3.0~16.0	40	40	120	88	88	52	HC16/1.0	M18	20,000	1.5
	GSK16-150	3.0~16.0	40	40	150	118	118	52	HC16/1.0	M18	20,000	1.8
	GSK20-90	4.0~20.0	48	48	90	60	60	60	HC20/1.0	M22	20,000	1.4
	GSK20-120	4.0~20.0	48	48	120	90	90	60	HC20/1.0	M22	20,000	1.8
	GSK25-90	16.0~25.0	55	55	90	61	61	63.5	HC25/1.0	M28	20,000	1.6
	GSK25-120	16.0~25.0	55	55	120	91	91	63.5	HC25/1.0	M28	20,000	2.0
BT50 -	GSK6-105	3.0~6.0	19.5	32	105	55	64	31	HC6	M8	15,000	3.6
	GSK6-135	3.0~6.0	19.5	32	135	60	92	31	HC6	M8	15,000	3.6
	GSK6-165	3.0~6.0	19.5	32	165	60	114	31	HC6	M8	15,000	3.9
	GSK10-105	2.0~10.0	27	27	105	57	57	38	HC10	M12	15,000	3.7
	GSK10-135	2.0~10.0	27	32	135	70	92	38	HC10	M12	15,000	3.7
	GSK10-165	2.0~10.0	27	36	165	75	114	38	HC10	M12	15,000	4.0
	GSK13-135	3.0~13.0	35	35	135	92	92	43	HC13	M15	15,000	3.9
	GSK16-105	3.0~16.0	40	40	105	62	62	52	HC16	M18	15,000	3.9
	GSK16-135	3.0~16.0	40	40	135	92	92	52	HC16	M18	15,000	4.1
	GSK16-165	3.0~16.0	40	50	165	40	122	52	HC16	M18	15,000	4.3
	GSK20-105	4.0~20.0	48	-	105	62	62	60	HC20	M22	15,000	4.1
	GSK20-135	4.0~20.0	48	-	135	92	92	60	HC20	M22	15,000	4.4
	GSK20-165	4.0~20.0	48	-	165	122	122	60	HC20	M22	15,000	4.9
	GSK25-105	16.0~25.0	55	55	105	62	62	63.5	HC25	M28	15,000	4.2
	GSK25-135	16.0~25.0	55	55	135	92	92	63.5	HC25	M28	15,000	4.6
	GSK25-165	16.0~25.0	55	55	165	122	122	63.5	HC25	M28	15,000	5.1


<sup>●</sup> Spare Part G33 ● Applicable collet G33

<sup>•</sup> H: Insertion depth of tool • Through coolant system is optional

<sup>•</sup> Coolant collets are recommended when using the coolant system

# **HSK-GSK**





(mm)

De	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	<b>L</b> 2	н	Collet / Step	G	RPM	O kg
HSK63A -	GSK6-100	3.0~6.0	19.5	32	100	51	61	35	HC6/0.5	M8	20,000	0.8
	GSK10-105	2.0~10.0	27	34.5	105	73	118	50	HC10/0.5	M12	20,000	0.9
	GSK16-120	3.0~16.0	40	40	120	58	58	60	HC16/0.5	M18	20,000	1.3
	GSK20-120	4.0~20.0	48	48	120	60	60	70	HC20/0.5	M22	20,000	1.6
HSK100A -	GSK6-120	3.0~6.0	19.5	32	120	55	64	35	HC6/0.5	M8	15,000	2.2
	GSK10-120	2.0~10.0	27	27	120	57	57	50	HC10/0.5	M12	15,000	2.3
	GSK16-140	3.0~16.0	40	40	140	62	62	60	HC16/0.5	M18	15,000	2.8
	GSK25-155	16.0~25.0	55	55	155	62	62	85	HC25/0.5	M28	15,000	3.6

• H: Insertion depth of tool


#### Parts

	Basic							
Division	Nut	Adjust screw	Extractor	Spanner				
Parts Designation	<b>6</b>							
GSK6	GN6	M820C	DSK-6CE	GSK-6				
GSK10	GN10	M1230C	DSK-10CE	GSK-10				
GSK13	GN13	BN1530F	DSK-13CE	GSK-13				
GSK16	GN16	BN1830F	DSK-16CE	GSK-16				
GSK20	GN20	BN2230F	DSK-20CE	GSK-20				
GSK25	GN25	BN2838F	DSK-25CE	GSK-25				

# **HC** Slim Collet

General & precision type





Designation	GD.		Ød	Distance	Tole	Tolerance		
	Designation	ØD	L	(Max.)	(mm)	Standard type	Precision type (P)	
HC6 -	Ød(P)	10.5	25.0	6.0	1.0			
HC10 -	Ød(P)	15.6	30.5	10.0	1.0		0	
HC13 -	Ød(P)	20.1	39.0	13.0	1.0	E		
HC16 -	Ød(P)	24.6	45.0	16.0	1.0	- 5 μm	3 μm	
HC20 -	Ød(P)	29.2	54.3	20.0	2.0	1		
HC25 -	Ød(P)	35.7	57.0	25.0	1.0			




#### **GERC Collet**



- · Corrosion resistant collet to micro unit
- High tech coating for long lasting precision
- Longer tool life and higher productivity




#### Code system



#### Special coating technology

Unlike GERC collets, Conventional non-coated collets have the following features:

Non-coated collets are affected by corrosion due to high humidity, cutting fluid, cleaner, salt, gas and many other factors, which in result deteriorates whole quality of machining



When a collet gets rusty, the tool life is shortened and precision considerably decreases. To prevent this problem, surface treatment by micro unit was applied to GERC collets for effective protection and long lasting precision






Two samples of collets after 4 months of use: Left: GERC collet, Right: Non-coated

#### GERC-HP

A precision type collet chuck is expensive than standard one, but still it has more advantages in long term cost and efficiency. Using GERC-HP can minimize pricy reworking due to smaller tolerance with maximum precision



# Degree of precision Finishing GERC-HP Medium cutting HPS roughingt Standard ER collet chuck Clamping force






# **GERC** Collet

## General/Precision/Water proof type





(mm)

Designation	ER size	ØD	ØD <sub>1</sub>		Min. pi of	Distance	Tolerance	
Designation	ER Size	(Max.)	וטש	L	water proof type	(mm)	Standard type	Precision type (HP)
GER11-Ød(HP)	11	7.0	11.5	18.0	-	0.5		
GER16-Ød(HP, C)	16	10.0	17.0	27.5	5.0	1.0		2 μm
GER20-Ød(HP, C)	20	13.0	21.0	31.5	6.0	1.0	E	
GER25-Ød(HP, C)	25	16.0	26.0	34.0	6.0	1.0	5 μm	
GER32-Ød(HP, C)	32	20.0	33.0	40.0	8.0	1.0		
GER40-Ød	40	26.0	41.0	46.0	10.0	1.0		

GERC Collet




Designation	ØD	Distance	Collet amount	Tolerance	O kg
GERC11 1.0-7.0 mm/0.5 mm	1.0-7.0	0.5	13 pcs	5 μm	0.1
GERC16 1.0-10.0 mm/1.0 mm	1.0-10.0	1.0	10 pcs	5 μm	0.2
GERC20 2.0-13.0 mm/1.0 mm	2.0-13.0	1.0	12 pcs	5 μm	0.5
GERC25 2.0-16.0 mm/1.0 mm	2.0-16.0	1.0	15 pcs	5 μm	1,1
GERC32 3.0-20.0 mm/1.0 mm	3.0-20.0	1.0	18 pcs	5 μm	2.6
GERC40 4.0-26.0 mm/1.0 mm	4.0-26.0	1.0	23 pcs	5 μm	5.8

# **ER** Collet

## General/Water proof type





(mm)

Designation	ER size	ØD (Max.)	ØD <sub>1</sub>	L	Min. pi of water proof type	Distance (mm)	Tolerance
ER11-Ød	11	7.0	11.5	18.0	-	0.5	
ER16-Ød(C)	16	10.0	17.0	27.5	5.0	1.0	
ER20-Ød(C)	20	13.0	21.0	31.5	6.0	1.0	10 μm
ER25-Ød(C)	25	16.0	26.0	34.0	6.0	1.0	
ER32-Ød(C)	32	20.0	33.0	40.0	8.0	1.0	

#### **ER** Collet General type



Designation	ØD	Distance	Collet amount	Tolerance
ER11(SET)	1.0-7.0	0.5	12 pcs	10 μm
ER16(SET)	1.0-10.0	1.0	10 pcs	10 μm
ER20(SET)	2.0-13.0	1.0	12 pcs	10 μm
ER25(SET)	2.0-16.0	1.0	15 pcs	10 μm
ER32(SET)	3.0-20.0	1.0	18 pcs	10 μm

#### Lock collet for ER collet chuck

# ER/L

- Designed to prevent the end mill from falling out
- Prevents tool fallout, slipping, or idle running
- Uses the Weldon flat (DIN 6535HB) end mill without any special endmill
- Useful for machining large-sized mold or difficult-to-cut materials

#### Structural Features


#### Designed to prevent fallout


- · Tool fallout is prevented by a key inserted in the collet
- · A key is inserted to prevent the tool from falling out

#### How to use

- · Assemble the collet with nut (same for general ER collet in use)
- · Assemble the end tool (in the direction of assembling notch with key)
- · Tighten the nut with the body







Clamp the nut after inserting no. ●into the collet chuck. After that, insert the end mill notch to be aligned with the part ▼ (steel ball position)

Note If an auto clamp device is used, skip step (Endmill rotation may cause injury)






After checking that the steel ball in the collet is caught in the notched part, completely clamp the nut by pulling the end mill in the axial direction (arrow direction)

# **ER/L** Collet







				()
Designation	ØD	ØD	Ø <b>D</b> 1	L
ER20-6L	20	6	20.7	31.5
ER20-8L	20	8	20.7	31.5
ER20-10L	20	10	20.7	31.5
ER20-12L	20	12	20.7	31.5
ER32-12L	32	12	32.7	40
ER32-16L	32	16	32.7	40
ER32-20L	32	20	32.7	40



# G RTJW

#### Jet coolant disk

# **RTJW**

- Provides a longer cutting tool service life by preventing chips from adhering to the tool
- Improveds chip breakability/breaking strong jet injection
- Reduces equipment non-operation time as nozzle position change is not necessary




#### Code system



#### Application

- With one waterproof type (RT, RUT) NUT, the inside jet coolant is simultaneously used
- Enables a fast change of the inside jet coolant only by disk replacement
- Strong jet injection with no scattering even in the high-speed rotation




RT NUT								
Туре	M	D	L					
RT16	M22x1.50	28.0	22.5					



RUT NUT									
Туре	M	D	L						
RUT20	M25x1.50	35.0	24.0						
RUT25	M32x1.50	42.0	25.0						
RUT32	M40x1.50	50.0	27.5						
RUT40	M50x1.50	63.0	30.5						




	Pocket machining	After	Remarks
Jet coolant	4		▶ The chips in the pocket completely are removed by a strong jet injection
Outside coolant	-	N. A.	<ul> <li>▶ The chips in the pocket are not removed</li> <li>▶ Chips are accumulated in the collet and nut</li> </ul>



#### Coolant method

According to use, inside coolant and jet coolant refueling can be used



#### Mixing prevention

Effective for vibration proof by preventing mixing of cutting chips by using RTJW

# **RTJW**





D	esignation	ER size	Inner diameter	D	esignation	ER size	Inner diameter
RTJW16 -	RTJW16-6	16	6	RTJW32 -	RTJW32-6	32	6
	RTJW16-7	16	7		RTJW32-7	32	7
	RTJW16-8	16	8		RTJW32-8	32	8
RTJW20 -	RTJW20-6	20	6		RTJW32-9	32	9
	RTJW20-7	20	7		RTJW32-10	32	10
	RTJW20-8	20	8		RTJW32-11	32	11
	RTJW20-9	20	9		RTJW32-12 RTJW32-13	32	12
	RTJW20-10	20	10			32	13
RTJW25 -	RTJW25-6	25	6		RTJW32-14	32	14
	RTJW25-7	25	7		RTJW32-15	32	15
	RTJW25-8	25	8		RTJW32-16	32	16
	RTJW25-9	25	9		RTJW32-17	32	17
	RTJW25-10	25	10		RTJW32-18	32	18
	RTJW25-11	25	11		RTJW32-20	32	20
	RTJW25-12	25	12	RTJW40 -	RTJW40-18	40	18
	RTJW25-13	25	13		RTJW40-19	40	19
	RTJW25-14	25	14		RTJW40-20	40	20
	RTJW25-15	25	15		RTJW40-21	40	21
	RTJW25-16	25	16		RTJW40-22	40	22
					RTJW40-24	40	24


<sup>◆</sup> Clamping items: G25~G27

<sup>•</sup> Less than Ø5 cannot be used for production



# **BT-NPU**






(mm)

	Designation	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	O kg
BT30 -	NPU8-97	1~ 8	38	97	8.5	0.8
	NPU13-125	1~13	50	125	12.5	1.4
BT40 -	NPU8-87	1~ 8	38	87	8.5	1.2
	NPU13-105	1~13	50	105	12.5	1.6
	NPU13-130	1~13	50	130	12.5	1.9
BT50 -	NPU13-130	1~13	50	130	12.5	4.5
	NPU13-190	1~13	50	190	12.5	5.3

<sup>•</sup> Through coolant system not available

# **HSK-NPU**





(mm)

Designation	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	L <sub>2</sub>	O kg
HSK63A - NPU13-175	1~13	50	175	149	12.5	2.4
HSK100A - NPU13-180	1~13	50	180	151	12.5	3.6

<sup>•</sup> Through coolant system not available

	For separate purchase		
Division	Chuck	Bolt	Spanner
Parts Designation		Contract of the Contract of th	
NPU8	NPU08	BX0620	NPU0836
NPU13	NPU13	BX0825	NPU1348

#### **High speed synchro tapping chuck**




- Tapping chuck for high speed machining
- Specially designed structure for absorbing thrust load and preventing damage on the tap
- Through coolant system available
- Applicable range: M1~M22




#### Code system





#### Excellent performance, precise machining





#### Comparison of thread figures






# G DST

# **BT-DST**






(mm)

	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	Collet	F-	F+	O kg
BT30 -	DST3-70	M1~M3	20	19	70	ER11	0.5	0.5	0.5
	DST10-100	M3~M10	40.4	28	100	TER16	0.5	0.5	0.8
BT40 -	DST3-70	M1~M3	20	19	70	ER11	0.5	0.5	1.0
	DST10-100	M3~M10	40.4	28	100	TER16	0.5	0.5	1.3
	DST22-110	M6~M22	60	49.5	110	TER32	0.7	0.7	1.7
BT50 -	DST10-110	M3~M10	60	49.5	110	TER16	0.5	0.5	3.8
	DST22-130	M6~M22	60	49.5	130	TER32	0.7	0.7	4.5

<sup>→</sup> Applicable collet G36, G43

# **HSK-DST**





D	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	Collet	F-	F+	O kg
HSK63A -	DST3-80	M1~M3	19	20	80	ER11	0.5	0.5	0.7
	DST10-100	M3~M10	28	40.4	100	TER16	0.5	0.5	0.9
	DST22 130	M6~M22	49.5	60	130	TER32	0.7	0.7	1.8


<sup>→</sup> Applicable collet G36, G43

<sup>•</sup> Through coolant system is optional

<sup>•</sup> Through coolant system is optional

**TER** Tap Collet





n

									(11111)
ı	Designation	Tapping Range	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	w	\(\rightarrow\) \(\lambda\) kg \(\rightarrow\)
TER16 -	4x3.2	M3	4	16.74	10.1	27.5	6.3	3.2	0.03
	5x4	M4	5	16.74	10.1	27.5	6.3	4	0.03
	5.5x4.5	M5	5.5	16.74	10.1	27.5	6.3	4.5	0.02
	6x4.5	M6,U1/4	6	16.74	10.1	27.5	6.3	4.5	0.02
	6.2x5	M7, M8	6.2	16.74	10.1	27.5	6.3	5	0.02
	7x5.5	M9, M10, U3/8	7	16.74	10.1	27.5	6.3	5.5	0.02
TER20 -	5x4	M4	5	20.74	13.2	31.5	7.2	4	0.05
	5.5x4.5	M5	5.5	20.74	13.2	31.5	7.2	4.5	0.05
	6x4.5	M6,U1/4	6	20.74	13.2	31.5	7.2	4.5	0.05
	6.2x5	M7, M8	6.2	20.74	13.2	31.5	7.2	5	0.04
	7x5.5	M9, M10, U3/8	7	20.74	13.2	31.5	7.2	5.5	0.05
	8x6	M11, U7/16, P1/8	8	20.74	-	-	-	6	0.04
	8.5x6.5	M12	8.5	20.74	13.2	31.5	7.2	6.5	0.04
TER25 -	5x4	M4	5	25.74	17.6	34	7.5	4	0.9
	5.5x4.5	M5	5.5	25.74	17.6	34	7.5	4.5	0.8
	6x4.5	M6	6	25.74	17.6	34	7.5	4.5	0.8
	6.2x5	M7, M8	6.2	25.74	17.6	34	7.5	5	0.1
	7x5.5	M9, M10, U3/8	7	25.74	17.6	34	7.5	5.5	0.8
	8.5x6.5	M12	8.5	25.74	17.6	34	7.5	6.5	0.8
ΓER32 -	6x4.5	M6,U1/4	6	32.74	23.1	40	8.2	4.5	0.2
	6.2x5	M7, M8	6.2	32.74	23.1	40	8.2	5	0.2
	7x5.5	M9, M10, U3/8	7	32.74	23.1	40	8.2	5.5	0.2
	8X6	M11, U7/16, P1/8	8	32.74	23.1	40	8.2	6	0.2
	8.5x6.5	M12	8.5	32.74	23.1	40	8.2	6.5	0.2
	10.5x8	M14, U9/16	10.5	32.74	23.1	40	8.2	8	0.2
	12.5x10	M16	12.5	32.74	23.1	40	8.2	10	0.2
	14x11	M18, P3/8	14	32.74	23.1	40	8.2	11	0.1
	15x12	M20	15	32.74	23.1	40	8.2	12	0.1
	17x13	M22, U7/8	17	32.74	23.1	40	8.2	13	0.1
	11x9	P1/4	11	32.74	23.1	40	8.2	9	0.2
	12x9	U5/8	12	32.74	23.1	40	8.2	9	0.2
	9x7	U1/2	9	32.74	23.1	40	8.2	7	0.2

 $\bullet$  Water proof tapping is possible with the use of RTJW and nuts (limited to the right sizes)



#### **Tapping holder**

## DTN

- Compact design and slim type
- Improvement of tapping force
- Tapping range: M3~M38




## Code system



## **ᢒ** Easy exchange of TCA (Tap adaptor)

Convenient one-touch exchange type for high precision and longer tool life Contraction of length is possible by axial floating way






## How to clamp TCA and a tap holder

Before installation	After installation	Disassembly
Insert TCA pushing the cover of tap holder     Clamp the TCA in the Key groove and firmly	The cover of tap holder is placed correctly	Seaparate the TCA pushing the cover of tap holder

# **BT-DTN**






(mm)

	Designation	Tapping range	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	Adaptor	F-	F+	
BT30 -	DTN12-85	M3~M12	32	39	85	60	TCA1-M	4	10	0.5
BT40 -	DTN12-90	M3~M12	32	39	90	65	TCA1-M	4	10	1.2
	DTN12-120	M3~M12	32	39	120	95	TCA1-M	4	10	1.5
	DTN22-130	M8~M24	50	56	130	96	TCA2-M	12.5	12.5	1.7
	DTN22-160	M8~M24	50	56	160	126	TCA2-M	12.5	12.5	2.2
BT50 -	DTN12-100	M3~M12	32	39	100	75	TCA1-M	4	10	3.9
	DTN12-130	M3~M12	32	39	130	105	TCA1-M	4	10	3.9
	DTN22-140	M8~M24	50	56	140	106	TCA2-M	12.5	12.5	4.3
	DTN22-170	M8~M24	50	56	170	136	TCA2-M	12.5	12.5	4.7
	DTN38-185	M16~M38	72	81	185	140	TCA3-M	20	20	5.7
	DTN38-215	M16~M38	72	81	215	170	TCA3-M	20	20	6.7

### S-DTN





	Designation	Tapping range	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	Lı	L <sub>2</sub>	F-	F+	Adaptor	O kg
S32 -	DTN12-90	M3-M12	32	32	39	170	90	65	4	10	TCA1	1.0
	DTN22-130	M8-M24	32	50	56	210	130	96	12.5	12.5	TCA2	1.8

<sup>→</sup> Tap Adapter (TCA) G46


<sup>•</sup> Through coolant system not available

<sup>•</sup> Through coolant system not available



# **TCA** Tap Adaptor






	Designation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	ØD <sub>3</sub>	L	L <sub>1</sub>	W	\(\rightarrow\) \(\left(\kg\)\)
TCA1 -	M3	4	19	18.5	32	26.5	24.5	3.2	0.2
	M4	5	19	18.5	32	26.5	24.5	4	0.2
	M5	5.5	19	18.5	32	26.5	24.5	4	0.2
	M6	6	19	18.5	32	26.5	24.5	4	0.2
	M8	6.2	19	18.5	32	26.5	24.5	5	0.2
	M10	7	19	18.5	32	26.5	24.5	5.5	0.2
	M11	8	19	18.5	32	26.5	24.5	6	0.2
	M12	8.5	19	18.5	32	26.5	24.5	6.5	0.2
TCA2 -	M8	6.2	31	29	50	34	30.5	5	0.5
	M10	7	31	29	50	34	30.5	5.5	0.5
	M12	8.5	31	29	50	34	30.5	6.5	0.5
	M14	10.5	31	29	50	34	30.5	8	0.5
	P(=1/4)	11	31	29	50	34	30.5	9	0.5
	M16	12.5	31	29	50	34	30.5	10	0.5
	M18	14	31	29	50	34	30.5	11	0.5
	M20	15	31	29	50	34	30.5	12	0.5
	M22	17	31	29	50	34	30.5	13	0.5
	P1/2	18	31	29	50	34	30.5	14	0.5
	M24	19	31	29	50	34	30.5	15	0.5
TCA3 -	M16	12.5	48	46	72	45	41	10	1.4
	M18	14	48	46	72	45	41	11	1.4
	M20	15	48	46	72	45	41	12	1.4
	M22	17	48	46	72	45	41	13	1.4
	M24	19	48	46	72	45	41	15	1.4
	M27	20	48	46	72	45	41	15	1.4
	M30	23	48	46	72	45	41	17	1.4
	M33	25	48	46	72	45	41	19	1.4
	M36	28	48	46	72	45	41	21	1.4

<sup>•</sup> Through coolant system not available

# **BT-SLA**





(mm)

	Designation	ØD	ØD <sub>1</sub>	L	н	H <sub>1</sub>	<b>H</b> <sub>2</sub>	М	G	∑ kg \
BT30 -	SLA16-90	16	40	90	72	25	20	M10	M12	0.9
	SLA20-90	20	50	90	72	25	20	M12	M12	1.2
	SLA25-90	25	50	90	72	25	20	M12	M12	1.1
BT40 -	SLA16-90	16	40	90	72	25	20	M10	M12	1.4
	SLA20-90	20	50	90	72	25	20	M12	M12	1.8
	SLA25-90	25	50	90	72	25	20	M12	M12	1.6
	SLA32-90	32	60	90	82	25	25	M14	M12	1.8
	SLA32-105	32	60	105	82	25	25	M14	M12	2.0
	SLA40-105	40	80	105	82	25	25	M16	M12	2.9
BT50 -	SLA20-105	20	50	105	72	25	20	M12	M12	4.4
	SLA25-105	25	50	105	72	25	20	M12	M12	4.3
	SLA32-105	32	60	105	82	25	25	M14	M12	4.5
	SLA40-105	40	90	105	82	25	20	M16	M12	6.1
	SLA42-105	42	90	105	80	25	25	M16	M12	5.9


	Ва	sic		For separa	te purchase		
Division	Set s	screw	Adjust screw	Wre	ench		
Parts							
Designation	BT type	HSK type		BT type	HSK type		
SLA16	BTF1010	BTF1414-1.5		LW-5	LW-6		
SLA20	BTF1212-1.5	BTF1616-1.5		LW-6	LW-8		
SLA25	BTF1212-1.5	BTF1818-1.5	M1230C	LW-6	LW-8		
SLA32	BTF1414-1.5	BTF2020-1.5	IVI1230C	LW-6	LW-10		
SLA40	<b>SLA40</b> BTF1624-1.5 BTF2			LW-8	LW-10		
<b>SLA42</b> BTF1624-1.5		BTF2020-1.5		LW-8	LW-10		

<sup>•</sup> H: Insertion depth of tool • Through coolant system installed



# **HSK-SLA**





(mm)

De	esignation	ØD	ØD <sub>1</sub>	L	н	H <sub>1</sub>	M	G	
HSK63A -	SLA20-100	20	52	100	51	25	M8	M12	1.6
	SLA25-105	25	65	105	59	25	M8	M12	2.1
	SLA32-105	32	72	105	63	30	M5	M12	2.3
HSK100A -	SLA20-105	20	52	105	51	25	M16	M12	3.1
	SLA25-110	25	65	110	59	25	M18	M12	3.8
	SLA32-125	32	72	125	63	30	M20	M12	4.4

• H: Insertion depth of tool • Through coolant system is optional

	Ва	sic		For separa	te purchase	
Division	Set s	screw	Adjust screw	Wre	ench	
Parts Designation						
Designation	BT type	HSK type		BT type	HSK type	
SLA20	BTF1212-1.5	BTF1616-1.5		LW-6	LW-8	
SLA25	BTF1212-1.5	BTF1818-1.5	M1230C	LW-6	LW-8	
SLA32	BTF1414-1.5	BTF2020-1.5		LW-6	LW-10	

Division	For separate purchase
Internal coolant system	

Classification by shank								
HSK50	HSK50A-CNS							
HSK63	HSK63A-CNS							
HSK100	HSK100A-CNS							

# **BT-FMA**






Fig. 3




Fig. 2






Fig. 4

(mm)


	Designation	Cutter dia.	ØD	ØD <sub>1</sub>	L	Н	W	K	G	O kg	Fig.
BT30 -	FMA25.4-45	80	25.4	50	45	22	9.5	5	M12	1.0	4
BT40 -	FMA25.4-45	80	25.4	50	45	22	9.5	5	M12	1.4	1
	FMA25.4-90	80	25.4	50	90	22	9.5	5	M12	2.2	1
	FMA31.75-45	100	31.75	60	45	30	12.7	7	M16	1.6	1
	FMA31.75-90	100	31.75	60	90	30	12.7	7	M16	2.5	1
	FMA38.1-60	125	38.1	80	60	34	15.87	9	M20	2.6	4
BT50 -	FMA25.4-45	80	25.4	50	45	22	9.5	5	M12	4.0	1
	FMA25.4-90	80	25.4	50	90	22	9.5	5	M12	4.7	1
	FMA25.4-150	80	25.4	50	150	22	9.5	5	M12	6.4	2
	FMA31.75-45	100	31.75	60	45	30	12.7	7	M16	4.1	1
	FMA31.75-75	100	31.75	60	75	30	12.7	7	M16	4.8	1
	FMA31.75-105	100	31.75	60	105	30	12.7	7	M16	5.6	2
	FMA38.1-45	125	38.1	80	45	34	15.87	9	M20	4.4	1
	FMA38.1-75	125	38.1	80	75	34	15.87	9	M20	5.6	1
	FMA50.8-45	160	50.8	100	45	36	19.05	10	M24	4.9	1
	FMA50.8-75	160	50.8	100	75	36	19.05	10	M24	6.8	1
	FMA47.625-75	200	47.625	128	75	38	25.4	12.5	-	8.3	3

<sup>•</sup>H: Insertion depth of tool •Through coolant system is optional •The weight above exclude the face cutter

	Basic									
Division	Key	Key bolt	Mount bolt	Clamp bolt	Wrench					
Parts Designation		Spine.	O.	C MIN						
FMA25.4	K9.5	BX0412	MBA-M12	BX1230	LW-10					
FMA31.75	K12.7	BX0515	MBA-M16	-	LW-14					
FMA38.1	K15.87	BX0616	MBA-M20	-	LW-17					
FMA50.8	K19.05	BX0820	MBA-M24	-	-					
FMA47.625	K25.4	BX1020	-	BX1645	-					



# **BT-FMC**




(mm)

	Designation	Cutter dia.	ØD	ØD <sub>1</sub>	L	Н	W	К	G	∑ kg \	Fig.
BT30 -	FMC16-45	40	16	38	45	17	8	5.0	M8	0.7	1
	FMC22-45	50/63	22	48	45	19	10	5.6	M10	0.8	2
	FMC27-50	80	27	60	50	21	12	6.3	M12	1.2	2
BT40 -	FMC16-60	40	16	38	60	17	8	5.0	M8	1.2	1
	FMC22-45	50/63	22	48	45	19	10	5.6	M10	1.2	1
	FMC22-90	50/63	22	48	90	19	10	5.6	M10	1.2	1
	FMC27-60	80	27	60	60	21	12	6.3	M12	1.8	1
	FMC27-90	80	27	60	90	21	12	6.3	M12	3.2	1
	FMC32-60	100	32	78	60	24	14	7.0	M16	2.3	2
	FMC40-50	125/160	40	89	50	27	15.87	8.0	M20	3.3	3
BT50 -	FMC16-60	40	16	38	60	17	8	5.0	M8	3.9	1
	FMC22-60	50/63	22	48	60	19	10	5.6	M10	4.1	1
	FMC27-40	80	27	60	40	21	12	6.3	M12	4.1	1
	FMC27-90	80	27	60	90	21	12	6.3	M12	5.5	1
	FMC27-150	80	27	60	150	21	12	6.3	M12	6.1	1
	FMC32-45	100	32	78	45	24	14	7.0	M16	4.2	1
	FMC32-75	100	32	78	75	24	14	7.0	M16	4.2	1
	FMC32-105	100	32	78	105	24	14	7.0	M16	4.2	1
	FMC40-50	125/160	40	89	50	27	15.87	8.0	M20	4.6	2

•H: Insertion depth of tool •Through coolant system is optional •The weight above exclude the face cutter

	For separate purchase							
Division	Key	Mount bolt	Mount bolt Key bolt Clamp bolt					
Parts Designation		Bu	September 1	Common Co				
FMC16	K8.0	-	BX0310	BX0830	LW-6			
FMC22	K10.0	-	BX0412	BX1030	LW-8			
FMC27	K12.0	MBA-M12	BX0616	BX1230	LW-10			
FMC32	K14.0	MBA-M16	BX0616	-	LW-14			
FMC40	K15.87	MBA-M20	BX0616	BX1030	LW-17			

# **HSK-FMC**



(mm)


De	esignation	Cutter dia.	ØD	ØD <sub>1</sub>	L	н	W	К	G	∑ kg \	Fig.
HSK50A -	FMC16-40	40	16	38	40	17	8	5	M8	0.4	1
	FMC22-50	50/63	22	48	50	19	10	5.6	M10	0.8	1
HSK63A -	FMC16-50	40	16	38	50	17	8	5.0	M8	0.9	1
	FMC22-50	50/63	22	48	50	19	10	5.6	M10	1.1	1
	FMC27-60	80	27	60	60	21	12	6.3	M12	1.4	1
	FMC32-60	100	32	78	60	24	14	7.0	M16	1.7	2
	FMC40-60	125/160	40	89	60	27	15.87	8.0	M20	2.5	3

•H: Insertion depth of tool •Through coolant system is optional •The weight above exclude the face cutter

	Basic							
Division	Key	Mount bolt	Key bolt	Clamp bolt	Wrench			
Parts Designation		Oh	September 1	Can.				
FMC16	K8.0	-	BX0310	BX0830	LW-6			
FMC22	K10.0	-	BX0412	BX1030	LW-8			
FMC27	K12.0	MBA-M12	BX0516	BX1230	LW-10			
FMC32	K14.0	MBA-M16	BX0616	-	LW-14			
FMC40	K15.87	MBA-M20	BX0616	BX1230	LW-17			

G MD

# BT-MD Modular Arbor




	,				
- (	1	Υ	٦		Υ
1	ı.	٠	٠	۰	٠

	Designation	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	G	\(\frac{O}{kg}\)	Fig.
BT30 -	MD19F-70	11	19	70	45	M5	0.5	1
	MD25F-90	14	25	90	63	M6	0.6	1
	MD32F-80	18	32	80	55	M8	0.7	1
	MD40F-45	22	40	45	22	M10	0.5	1
	MD40F-60	22	40	60	36	M10	0.7	1
	MD40F-80	22	40	80	56	M10	0.9	1
	MD50F-70	28	50	70	48	M12	0.9	1
BT40 -	MD19F-70	11	19	70	40	M5	1.0	1
	MD25F-95	14	25	95	63	M6	1.1	1
	MD25F-105R	14	25	105	40	M6	1.2	2
	MD32F-100	18	32	100	70	M8	1.2	1
	MD32F-115R	18	32	115	45	M8	1.5	2
	MD40F-60	22	40	60	31	M10	1.1	1
	MD40F-110R	22	40	110	60	M10	1.6	2
	MD40F-115	22	40	115	83	M10	1.6	1
	MD50F-105	28	50	105	73	M12	1.8	1
	MD63F-64	36	63	64	37	M16	1.5	1
	MD63F-110	36	63	110	83	M16	2.4	1
	MD63F-135	36	63	135	108	M16	3.0	1
	MD80F-100	45	80	100	73	M16	2.9	1
BT50 -	MD19F-85	11	19	85	44	M5	3.7	1
	MD25F-105	14	25	105	62	M6	3.8	1
	MD25F-120R	14	25	120	40	M6	3.8	2
	MD32F-110	18	32	110	67	M8	4.0	1
	MD32F-115R	18	32	115	45	M8	4.1	2
	MD32F-235R	18	32	235	115	M8	5.5	2
	MD40F-60	22	40	60	22	M10	3.7	1
	MD40F-195	22	40	195	152	M10	4.8	1
	MD40F-230R	22	40	230	180	M10	5.0	2
	MD50F-125	28	50	125	82	M12	4.6	1
	MD50F-225	28	50	225	182	M12	6.0	1
	MD50F-250R	28	50	250	81	M12	7.0	2
	MD63F-75	36	63	75	35	M16	4.2	1
	MD63F-130	36	63	130	87	M16	5.3	1
	MD63F-195	36	63	195	152	M16	6.8	1
	MD63F-230	36	63	230	187	M16	7.5	1
	MD80F-75	45	80	75	36	M16	4.3	1
	MD80F-110	45	80	110	69	M16	5.7	1
	MD80F-175	45	80	175	134	M16	8.0	1
	MD90F-75	45	90	75	34	M16	4.8	1
	MD90F-145	45	90	145	104	M16	7.4	1
	MD90F-195	45	90	195	154	M16	9.4	1

# HSK-MD Modular Arbor





(mm)

De	signation	ØD <sub>1</sub>	ØD <sub>2</sub>	L	L <sub>1</sub>	Н	М	
HSK 63A -	MD19F-60	11	19	60	31	15.5	M5	0.7
	MD25F-60	14	25	60	31	18.5	M6	0.7
	MD32F-65	18	32	65	36	23.5	M8	0.8
	MD40F-70	22	40	70	41	29	M10	0.9
	MD50F-85	28	50	85	58	36	M12	1.3
	MD63F-95	36	63	95	69	46	M16	1.7

<sup>•</sup> Through coolant system is optional

	Basic	For separate purchase
Division	Taper screw	Wrench
Parts Designation		
MD19F	BTT0506F	LW-2.5
MD25F	BTT0608F	LW-3
MD32F	BTT0810F	LW-4
MD40F	BTT1013F	LW-5
MD50F	BTT1215F	LW-6
MD63F	BTT1620F	LW-8
MD80F	BTT1626F	LW-8
MD90F	BTT1631F	LW-8


Division	For separate purchase
Internal coolant system	

Classification by shank					
HSK50	HSK50A-CNS				
HSK63	HSK63A-CNS				
HSK100	HSK100A-CNS				

# G EXT/RDC

### **EXT** Extension Bar






(mm)

De	esignation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	L	G	
EXT	1930F	11	19	11	30	M5	0.1
	1950F	11	19	11	50	M5	0.1
	2530F	14	25	14	30	M6	0.1
	2550F	14	25	14	50	M6	0.2
	3235F	18	32	18	35	M8	0.2
	3260F	18	32	18	60	M8	0.4
	4040F	22	40	22	40	M10	0.4
	4090F	22	40	22	90	M10	0.9
	5050F	28	50	28	50	M12	0.7
	50100F	28	50	28	100	M12	1.4
	6360F	36	63	36	60	M16	1.4
	63120F	36	63	36	120	M16	2.9
	8070F	45	80	45	70	M16	2.5
	80120F	45	80	45	120	M16	4.5
	9080F	45	90	45	80	M16	3.8
	90130F	45	90	45	130	M16	6.4

<sup>•</sup> Through coolant system installed

# **RDC** Reducer Bar





De	signation	ØD	ØD <sub>1</sub>	ØD <sub>2</sub>	ØD3	L	L <sub>1</sub>	G	O kg
RDC	3225F	18	32	14	25	30	9	M6	0.1
	4025F	22	40	14	25	30	9	M6	0.3
	4032F	22	40	18	32	30	9	M8	0.2
	5025F	28	50	14	25	30	9	M6	0.3
	5032F	28	50	18	32	40	9	M8	0.3
	5040F	28	50	22	40	40	10	M10	0.5
	6325F	36	63	14	25	30	9	M6	0.6
	6332F	36	63	18	32	40	9	M8	0.6
	6340F	36	63	22	40	40	10	M10	0.7
	6350F	36	63	28	50	45	10	M12	0.9
	8040F	45	80	22	40	40	10	M10	1.2
	8050F	45	80	28	50	45	10	M12	1.3
	8063F	45	80	36	63	50	13	M16	1.6

#### FBH back boring & balanced type

### FBH/B


- High speed boring and back boring capability
- High precision balancing: G2.5, Head: G6.3
- Min. adjustment range: 2 μm



### Code system



#### Back boring range calculation



- A: Boring range (Ø)
- B: FBH/B body size (Ø)
- C: Diameter for pass (Ø)

Designation	Min. diameter for pass (Ø)
FBH1920B	≥ Ø24
FBH2526B	≥ Ø30.5
FBH3233B	≥ Ø35
FBH4042B	≥ Ø44
FBH5053B	≥ Ø54
FBH6368B	≥ Ø71.5
FBH6398B	≥ Ø100
FBH8098B	≥ Ø100

	Α	Max. range of back boring (Ø)	A Max. value = (2 x C) - B
	В	B Max. FBH body size (Ø)	B Max. value = (2 x C) - A
ĺ	С	C Min. diameter for pass (Ø)	C Min. value = $(A + B)/2$

### Boring range adjustment method

#### Fine adjustment: 2 $\mu$ m Boring range


Adjusted location

Can be adjusted at a rate of 2  $\mu$ m by using the main scale and vernier scale



Adjusted location

#### Boring range



(mm)


Adjusted location

Designation		Boring range ØD		Backboring Range (Ø)					
Designation	Min	Max	L	Min	Max	L <sub>1</sub>	L <sub>2</sub>		
FBH1920B	20	26 (30)	35.3	29	30	13.1	18.6		
FBH2526B	26	34 (40)	40.9	36	40	15.1	21.9		
FBH3233B	33	43 (50)	40.9	38	46 (50)	13.1	24.9		
FBH4042B	42	54 (62)	50.4	48	54 (62)	15.2	31.4		
FBH5053B	53	70 (82)	58.4	58	70 (82)	15.7	38.4		
FBH6368B	68	100 (122)	80.6	78	100 (122)	27.4	48.6		
FBH6398B	98	150 (172)	100.6	106	150 (172)	47.4	48.6		
FBH8098B	98	150 (172)	100.6	106	150 (172)	47.4	48.6		



### BT-FBH/B

#### Micro Boring Balance type



	Designation		Boring I	range ØD	CD.	CD.				_0_	F:
Head	Bite	Arbor	Min	Max	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	L <sub>2</sub>	kg	Fig.
FBH1920B	FBB20N-□-□□	BT30-MD19F-70	20 (24)	26 (30)	19	11	105.2	35.2	45	0.2	1
FBH2526B	FBB26N-□-□□	BT30-MD25F-90	26 (32)	34 (40)	25	14	131	41	63	0.2	1
FBH3233B	FBB33N-□-□□	BT30-MD32F-80	33 (40)	43 (50)	32	18	121	41	55	0.3	1
FBH4042B	FBB42N-□-□□	BT30-MD40F-45	42 (50)	54 (62)	40	22	95.5	50.5	22	0.5	1
FBH4042B	FBB42N-□-□□	BT30-MD40F-60	42 (50)	54 (62)	40	22	110.5	50.5	36	0.5	1
FBH4042B	FBB42N-□-□□	BT30-MD40F-80	42 (50)	54 (62)	40	22	130.5	50.5	56	0.5	1
FBH5053B	FBB53N-□-□□	BT30-MD50F-70	53 (65)	70 (82)	50	28	128.4	58.5	48	0.8	1
FBH1920B	FBB20N-□-□□	BT40-MD19F-70	20 (24)	26 (30)	19	11	105.4	35.2	40	0.2	1
FBH2526B	FBB26N-□-□□	BT40-MD25F-95	26 (32)	34 (40)	25	14	135.9	41	63	0.2	1
FBH2526B	FBB26N-□-□□	BT40-MD25F-105R	26 (32)	34 (40)	25	14	146	41	40	0.2	2
FBH3233B	FBB33N-□-□□	BT40-MD32F-100	33 (40)	43 (50)	32	18	140.9	41	70	0.3	1
FBH3233B	FBB33N-□-□□	BT40-MD32F-115R	33 (40)	43 (50)	32	18	156	41	45	0.3	2
FBH4042B	FBB42N-□-□□	BT40-MD40F-60	42 (50)	54 (62)	40	22	165.5	50.5	31	0.5	1
FBH4042B	FBB42N-□-□□	BT40-MD40F-110R	42 (50)	54 (62)	40	22	160.5	50.5	60	0.5	2
FBH4042B	FBB42N-□-□□	BT40-MD40F-15	42 (50)	54 (62)	40	22	165.5	50.5	83	0.5	1
FBH5053B	FBB53N-□-□□	BT40-MD50F-105	53 (65)	70 (82)	50	28	163.4	58.5	73	0.8	1
FBH5053B	FBB53N-□-□□	BT40-MD63F-64	53 (65)	70 (82)	50	28	122.5	58.5	37	0.8	1
FBH6368B	FBB68N-□-□□	BT40-MD63F-110	68 (90)	100 (122)	63	36	190.6	80.6	83	2.1	1
FBH6398B	FBB68N-□-□□	BT40-MD63F-135	98 (120)	150 (172)	63	36	235.6	100.6	108	3.6	1
FBH8098B	FBB68N-□-□□	BT40-MD80F-100	98 (120)	150 (172)	80	45	200.6	100.6	73	4.8	1

<sup>●</sup> Spare Part G59 ● FBB Bite G61


<sup>\*</sup> FBB bites are divided into two sorts Normal type: FBB  $\square$  N, Scalable type: FBB  $\square$  N-1 There are also the other options for your insert type: FBB \\_N-\\_-C09 or T11

Bite	Applicable insert
FBB□□N, FBB□□N-1	TPGT, TPGW0802□□L
FBB□□N-□-C	CCMT, CCGT0602□□L
FBB□□N-□-C09	CCMT, CCGT09T3□□L
FBB□□N-□-T11	TPGT1103□□L

<sup>•</sup> Head: Basic, Bite/Arbor: For separate purchase • Through coolant system installed

### BT-FBH/B

### Micro Boring Balance type



	Designation		Boring I	range ØD	~D	CD.				_0_	<b>F:</b>
Head	Bite	Arbor	Min	Max	ØD	ØD <sub>1</sub>	L	L <sub>1</sub>	L <sub>2</sub>	kg	Fig.
FBH1920B	FBB20N-□-□□	BT50-MD19F-85	20 (24)	26 (30)	19	11	120.2	35.2	44	0.2	1
FBH2526B	FBB26N-□-□□	BT50-MD25F-105	26 (32)	34 (40)	25	14	146	41	62	0.2	1
FBH2526B	FBB26N-□-□□	BT50-MD25F-120R	26 (32)	34 (40)	25	14	161	41	40	0.2	2
FBH3233B	FBB33N-□-□□	BT50-MD32F-110	33 (40)	43 (50)	32	18	151	41	67	0.3	1
FBH3233B	FBB33N-□-□□	BT50-MD32F-115R	33 (40)	43 (50)	32	18	156	41	45	0.3	2
FBH3233B	FBB33N-□-□□	BT50-MD32F-235R	33 (40)	43 (50)	32	18	276	41	115	0.3	2
FBH4042B	FBB42N-□-□□	BT50-MD40F-60	42 (50)	54 (62)	32	18	110.5	50.5	22	0.5	1
FBH4042B	FBB42N-□-□□	BT50-MD40F-195	42 (50)	54 (62)	40	22	245.5	50.5	152	0.5	1
FBH4042B	FBB42N-□-□□	BT50-MD40F-230R	42 (50)	54 (62)	40	22	280.5	50.5	180	0.5	2
FBH5053B	FBB53N-□-□□	BT50-MD50F-125	53 (65)	70 (82)	40	22	183.5	58.5	82	8.0	1
FBH5053B	FBB53N-□-□□	BT50-MD50F-225	53 (65)	70 (82)	50	28	283.5	58.5	182	0.8	1
FBH5053B	FBB53N-□-□□	BT50-MD50F-205R	53 (65)	70 (82)	50	28	263.5	58.5	81	8.0	2
FBH6368B	FBB68N-□-□□	BT50-MD63F-75	68 (90)	100 (122)	63	36	145.6	80.6	35	2.1	1
FBH6368B	FBB68N-□-□□	BT50-MD63F-130	68 (90)	100 (122)	63	36	210.6	80.6	87	2.1	1
FBH6368B	FBB68N-□-□□	BT50-MD63F-195	68 (90)	100 (122)	63	36	275.6	80.6	152	2.1	1
FBH6368B	FBB68N-□-□□	BT50-MD63F-230	68 (90)	100 (122)	63	36	310.6	80.6	187	2.1	1
FBH6398B	FBB68N-□-□□	BT50-MD63F-75	98 (120)	150 (172)	63	36	175.6	100.6	35	3.6	1
FBH6398B	FBB68N-□-□□	BT50-MD63F-130	98 (120)	150 (172)	63	36	230.6	100.6	87	3.6	1
FBH6398B	FBB68N-□-□□	BT50-MD63F-95	98 (120)	150 (172)	63	36	295.6	100.6	152	3.6	1
FBH6398B	FBB68N-□-□□	BT50-MD63F-230	98 (120)	150 (172)	63	36	330.6	100.6	187	3.6	1
FBH8098B	FBB68N-□-□□	BT50-MD80F-75	98 (120)	150 (172)	80	45	175.6	100.6	36	4.8	1
FBH8098B	FBB68N-□-□□	BT50-MD80F-110	98 (120)	150 (172)	80	45	215.6	100.6	69	4.8	1
FBH8098B	FBB68N-□-□□	BT50-MD80F-175	98 (120)	150 (172)	80	45	275.6	100.6	134	4.8	1

<sup>◆</sup> Spare Part G59 ◆ FBB Bite G61

<sup>\*</sup> FBB bites are divided into two sorts Normal type: FBB \( \B\) \( N\), Scalable type: FBB \( \B\) \( N-1\)
There are also the other options for your insert type: FBB \( \B\) \( N-\Box\) -C09 or T11

Bite	Applicable insert
FBB□□N, FBB□□N-1	TPGT, TPGW0802□□L
FBB□□N-□-C	CCMT, CCGT0602□□L
FBB□□N-□-C09	CCMT, CCGT09T3□□L
FBB□□N-□-T11	TPGT1103□□L


<sup>•</sup> Head: Basic, Bite/Arbor: For separate purchase • Through coolant system installed




### **HSK-FBH/B**

#### Micro Boring Balance type








(mm)

	Designation		Boring ı	range ØD	ØD	ØD <sub>1</sub>		L <sub>1</sub>	L <sub>2</sub>	O kg
Head	Bite	Arbor	Min	Max	טט	וטש		Li	<b>L</b> 2	/ kg \
FBH1920B	FBB20N-□-□□	HSK63A-MD19F 60	20 (24)	26 (30)	19	11	95.2	35.2	31	0.2
FBH2526B	FBB26N-□-□□	HSK63A-MD25F 60	26 (32)	34 (40)	25	14	101	41	31	0.2
FBH3233B	FBB33N-□-□□	HSK63A-MD32F 65	33 (40)	43 (50)	32	18	106	41	36	0.3
FBH4042B	FBB42N-□-□□	HSK63A-MD40F 70	42 (50)	54 (62)	40	22	120.5	50.5	41	0.5
FBH5053B	FBB53N-□-□□	HSK63A-MD50F 85	53 (65)	70 (82)	50	28	143.5	58.5	58	0.9
FBH6368B	FBB68N-□-□□	HSK63A-MD63F 95	68 (90)	100 (122)	63	36	175.6	80.6	69	2.3
FBH6398B	FBB68N-□-□□	HSK63A-MD63F 95	98 (120)	150 (172)	63	36	195.6	100.6	69	3.8

<sup>◆</sup> Spare Part G59 ◆ FBB Bite G61

\* FBB bites are divided into two sorts Normal type: FBB \( \B\) N, Scalable type: FBB \( \B\) N-1 There are also the other options for your insert type: FBB \( \B\) N-\( \B\) -C09 or T11

Bite	Applicable insert
FBB□□N, FBB□□N-1	TPGT, TPGW0802□□L
FBB□□N-□-C	CCMT, CCGT0602□□L
FBB□□N-□-C09	CCMT, CCGT09T3□□L
FBB□□N-□-T11	TPGT1103□□L




Classification by shank						
HSK50	HSK50A-CNS					
HSK63	HSK63A-CNS					
HSK100	HSK100A-CNS					

<sup>•</sup> Head: Basic, Bite/Arbor: For separate purchase • Through coolant system is optional

### S-FBH/B

#### Micro Boring Balance type





(mm)

Designation	Boring r	ange ØD	ØD <sub>1</sub>		М	Main c	omponent		٩
Designation	Min	Max	וטש		IVI	Basic shank	Boring head	Bite	kg
S19W-FBH20B-120	20	26	19	192.35	120	S19W-MD19F-157	FBH1920B	FBB20N	0.6
S19W-FBH20B-140	20	26	19	212.35	140	S19W-MD19F-177	FBH1920B	FBB20N	0.7
S19W-FBH20B-160	20	26	19	232.35	160	S19W-MD19F-197	FBH1920B	FBB20N	0.8
S25W-FBH26B-150	26	34	25	238.35	150	S25W-MD25F-197.5	FBH2526B	FBB26N	1.4
S25W-FBH26B-175	26	34	25	263.35	175	S25W-MD25F-222.5	FBH2526B	FBB26N	1.6
S25W-FBH26B-200	26	34	25	288.35	200	S25W-MD25F-247.5	FBH2526B	FBB26N	1.8
S32W-FBH33B-180	33	43	32	279.9	180	S32W-MD32F-239	FBH3233B	FBB33N	2.7
S32W-FBH33B-240	33	43	32	339.9	240	S32W-MD32F-299	FBH3233B	FBB33N	3.4
S19-FBH20B-40	20	26	19	112.35	40	S19-MD19F-77	FBH1920B	FBB20N	0.2
S19-FBH20B-80	20	26	19	152.35	80	S19-MD19F-117	FBH1920B	FBB20N	0.2
S25-FBH26B-50	26	34	25	138.35	50	S25-MD25F-97.5	FBH2526B	FBB26N	0.4
S25-FBH26B-100	26	34	25	188.35	100	S25-MD25F-147.5	FBH2526B	FBB26N	0.6
S32-FBH33B-90	33	43	32	189.9	90	S32-MD32F-149	FBH3233B	FBB33N	1.1
S32-FBH33B-120	33	43	32	219.9	120	S32-MD32F-179	FBH3233B	FBB33N	1.2

<sup>◆</sup> Spare Part G59 ◆ FBB Bite G61

<sup>\*</sup> FBB bites are divided into two sorts Normal type: FBB \( \B\) \( N\), Scalable type: FBB \( \B\) \( N-1\)
There are also the other options for your insert type: FBB \( \B\) \( N-\Box\) -C09 or T11

Bite	Applicable insert
FBB□□N, FBB□□N-1	TPGT, TPGW0802□□L
FBB□□N-□-C	CCMT, CCGT0602□□L
FBB□□N-□-C09	CCMT, CCGT09T3□□L
FBB□□N-□-T11	TPGT1103□□L


Basic								
Type (FBH/B)	Lock screw	Clamp screw	Wrench					
		69	1					
FBH1920B	BTF0404	BXC0304	LW-2					
FBH2526B	BTF0505	BXC0405	LW-2.5					
FBH3233B	BTF0606	BXC0506	LW-3					
FBH4042B	BTF0808	BXC0610	LW-4					
FBH5053B	BTF0812	BXC0610	LW-4					
FBH6368B	BTF1016	BXC0810	LW-5					
FBH6398B	BTF1012	BXC0810	LW-5					
FBH8098B	BTF1014	BXC0810	LW-5					

 $<sup>\</sup>bullet \, S \square \square W \text{: Cemented carbide shank, } S \square \square \text{: steel shank} \quad \bullet \text{Through coolant system installed}$ 

G FBH/B

S-FBH Small Micro Boring





(mm)

Designation	Boring range Ø		αD.		М	Ι		9	
Designation	Min	Max	ØD <sub>1</sub>	L	IVI	Basic shank	Boring head	Bite	kg
S14W-FBH15-85	15	18	14	155	85	S14W-M6-123	FBH15	FBB15-C	0.3
S14W-FBH15-110	15	18	14	180	110	S14W-M6-148	FBH15	FBB15-C	0.3
S16W-FBH18-95	18	22	16	165	95	S16W-M8-128	FBH18	FBB15-C	0.4
S16W-FBH18-125	18	22	16	195	125	S16W-M8-158	FBH18	FBB15-C	0.5
S14-FBH15-40	15	18	14	110	40	S14-M6-78	FBH15	FBB15-C	0.1
S16-FBH18-45	18	22	16	115	45	S16-M8-78	FBH18	FBB15-C	0.1

<sup>●</sup> Spare Part G59, G60 ● FBB Bite G61

<sup>\*</sup> FBB bites are divided into two sorts Normal type: FBB \( \B\) \( N\), Scalable type: FBB \( \B\) \( N-1\)
There are also the other options for your insert type: FBB \( \B\) \( N-\Box\) -C09 or T11

Bite	Applicable insert
FBB□□N, FBB□□N-1	TPGT, TPGW0802□□L
FBB□□N-□-C	CCMT, CCGT0602□□L
FBB□□N-□-C09	CCMT, CCGT09T3□□L
FBB□□N-□-T11	TPGT1103□□L

	Basic									
Type (FBH)	Lock screw	FBB	Clamp screw							
September 1										
FBH15	BT02503	FBB15-C	BFTX02505N							
FBH18	BT02503	FBB15-C	BFTX02505N							

<sup>•</sup> S W: Cemented carbide shank, S : steel shank • Through coolant system installed

# FBB Bite

Designation	Boring range	Insert	Insert screw	Clamp bolt	
FBB15-C	Ø15~Ø18 mm	CCET0301-□□L	BFTX01604N	BFTX02505N	
FBB13-C	Ø18~Ø22 mm	CCET0301-□□L	BFTX01604N	BFTX02505N	
FBB20N	Ø20~Ø26 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0304	
FBB20N-C	Ø20~Ø26 mm	CCET0401□□L	FTNA0238	BXC0304	
FBB20N-1	Ø24~Ø30 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0304	
FBB20N-1-C	Ø24~Ø30 mm	CCET0401□□L	FTNA0238	BXC0304	
FBB26N	Ø26~Ø34 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0405	
FBB26N-C	Ø26~Ø34 mm	CCET0401□□L	FTNA0238	BXC0405	
FBB26N-1	Ø32~Ø40 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0405	
FBB26N-1-C	Ø32~Ø40 mm	CCET0401□□L	FTNA0238	BXC0405	
FBB33N	Ø33~Ø43 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0506	
FBB33N-C	Ø33~Ø43 mm	CCMT0602□□,CCGT0602□□	BFTX02506N	BXC0506	
FBB33N-1	Ø41~Ø50 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0506	
FBB33N-1-C	Ø41~Ø50 mm	CCMT0602□□,CCGT0602□□L	BFTX02506N	BXC0506	
FBB42N	Ø42~Ø54 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0610	
FBB42N-C	Ø42~Ø54 mm	CCMT0602□□CCGT0602□□L	BFTX02506N	BXC0610	
FBB42N-11	Ø42~Ø54 mm	TPGT1103□□L	BFTX0307A	BXC0610	
FBB42N-1	Ø50~Ø62 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0610	
FBB42N-1-C	Ø50~Ø62 mm	CCMT0602□□,CCGT0602□□L	BFTX02506N	BXC0610	
FBB42N-1-T11	Ø50~Ø62 mm	TPGT1103□□L	BFTX0307A	BXC0610	
FBB53N	Ø53~Ø70 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0610	
FBB53N-C	Ø53~Ø70 mm	CCMT0602□□,CCGT0602□□	BFTX02506N	BXC0610	
FBB53N-11	Ø53~Ø70 mm	TPGT1103□□L	BFTX0307A	BXC0610	
FBB53N-1	Ø65~Ø82 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0610	
FBB53N-1-C	Ø65~Ø82 mm	CCMT0602□□CCGT0602□□L	BFTX02506N	BXC0610	
FBB53N-1-C09	Ø65~Ø82 mm	CCMT09T3□□,CCGT09T3□□L	BFTX0409N	BXC0610	
FBB53N-1-T11	Ø65~Ø82 mm	TPGT1103□□L	BFTX0307A	BXC0610	
FBB68N	Ø68~Ø100 mm/Ø98~Ø150 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0810	
FBB68N-C	Ø68~Ø100 mm/Ø98~Ø150 mm	CCMT09T3□□,CCGT09T3□□L	BFTX0409N	BXC0810	
FBB68N-11	Ø68~Ø100 mm/Ø98~Ø150 mm	TPGT1103□□L	BFTX0307A	BXC0810	
FBB68N-1	Ø90~Ø122 mm/Ø120~Ø172 mm	TPGT0802□□L,TPGW0802□□	BFTX0204A	BXC0810	
FBB68N-1-C09	Ø90~Ø122 mm/Ø120~Ø172 mm	CCMT09T3□□,CCGT09T3□□L	BFTX0409N	BXC0810	
FBB68N-1-T11	Ø90~Ø122 mm/Ø120~Ø172 mm	TPGT1103□□L	BFTX0307A	BXC0810	



#### New balance cut tool



- Applied adjustment function simultaneously in Bi/Uni-direction of cartridge
- Improves the rigidity of cutting by applying cover for rotating type
- Increased machining area versus conventional own products
- Improved capacity to evacuate chips by unique design of helical type Head
- Boring range: Ø28~Ø136



#### Code system



#### Main features

#### **Helical Type**



- Improved capacity to discharge chips from clogged and deep holes
- · Minimized damage to tools and insert due to chip clogging

Extended head length	Deep hole machining implemented
Helical Type	Improved capacity to discharge chips from holes

#### Boring area optimization



- Max. diameter expanded owing to reinforced rigidity
- Boring range expanded per model no. versus conventional boring range of DINE

Coolant Hole (Direct spray to cutting edge)

- Improved capacity to discharge chips
- Improved capacity of machining

#### Effect of improved rigidity for cartridge by cover

Clamps the top of the cartridge stably, minimizing the vibration of tools and improving the roughness of the working surface







BT-DBC/A

Helical type







Desi	ignation	Boring r	ange ØD	~.	~.				0	(mm)
Head	Arbor	Min	Max	Ød	Ød <sub>1</sub>	L	L <sub>1</sub>	L <sub>2</sub>	kg	Fig.
DBCA2528S-H	BT30-MD25F-90	28	38	14	25	193	103	63	0.3	1
DBCA3238S-H	BT30-MD32F-80	38	54	18	32	190	110	55	0.5	1
DBCA5054S-H	BT30-MD50F-70	54	74	28	50	215	145	48	1.8	1
DBCA2528S-H	BT40-MD25F-95	28	38	14	25	198	103	63	0.3	1
DBCA2528S-H	BT40-MD25F-105R	28	38	14	25	208	103	40	0.3	2
DBCA3238S-H	BT40-MD32F-100	38	54	18	32	210	110	70	0.5	1
DBCA3238S-H	BT40-MD32F-115R	38	54	18	32	225	110	45	0.5	2
DBCA5054S-H	BT40-MD50F-105	54	74	28	50	250	145	73	1.8	1
DBCA6374S-H	BT40-MD63F-64	74	100	36	63	244	180	37	3.3	1
DBCA6374S-H	BT40-MD63F-110	74	100	36	63	290	180	83	3.3	1
DBCA6374S-H	BT40-MD63F-135	74	100	36	63	315	180	108	3.3	1
DBCA80100S-H	BT40-MD80F-100	100	136	45	80	315	215	73	7.3	1
DBCA2528S-H	BT50-MD25F-105	28	38	14	25	208	103	62	0.3	1
DBCA2528S-H	BT50-MD25F-120R	28	38	14	25	223	103	40	0.3	2
DBCA3238S-H	BT50-MD32F-110	38	54	18	32	220	110	67	0.5	1
DBCA3238S-H	BT50-MD32F-115R	38	54	18	32	225	110	45	0.5	2
DBCA3238S-H	BT50-MD32F-235R	38	54	18	32	345	110	115	0.5	2
DBCA5054S-H	BT50-MD50F-125	54	74	28	50	270	145	82	1.8	1
DBCA5054S-H	BT50-MD50F-225	54	74	28	50	370	145	182	1.8	1
DBCA5054S-H	BT50-MD50F-250R	54	74	28	50	395	145	81	1.8	2
DBCA6374S-H	BT50-MD63F-75	74	100	36	63	255	180	35	3.3	1
DBCA6374S-H	BT50-MD63F-130	74	100	36	63	280	180	87	3.3	1
DBCA6374S-H	BT50-MD63F-195	74	100	36	63	375	180	152	3.3	1
DBCA6374S-H	BT50-MD63F-230	74	100	36	63	410	180	187	3.3	1
DBCA80100S-H	BT50-MD80F-75	100	136	45	80	290	215	36	7.3	1
DBCA80100S-H	BT50-MD80F-110	100	136	45	80	325	215	69	7.3	1
DBCA80100S-H	BT50-MD80F-175	100	136	45	80	390	215	134	7.3	1

<sup>●</sup> Spare Part G67

<sup>•</sup> Head: Basic, Arbor: For separate purchase • Through coolant system installed

<sup>\*</sup> In the above table, the Arbor Model No. is an example model no. and able to adjust the depth of boring with a combination of MD arbors and extension bars. For more details, see the MD arbor page.



#### **BT-DBC/A** Straight type




Fig. 2

Des	signation	Boring r	ange ØD	~.	~ .				0	
Head	Arbor	Min	Max	Ød	Ød <sub>1</sub>	L	L <sub>1</sub>	L <sub>2</sub>	\(\sum_{\kg}\)	Fig.
DBCA2528S	BT30-MD25F-90	28	38	14	25	193	103	63	0.2	1
DBCA3238S	BT30-MD32F-80	38	54	18	32	190	110	55	0.4	1
DBCA5054S	BT30-MD50F-70	54	74	28	50	215	145	48	1.1	1
DBCA2528S	BT40-MD25F-95	28	38	14	25	198	103	63	0.2	1
DBCA2528S	BT40-MD25F-105R	28	38	14	25	208	103	40	0.2	2
DBCA3238S	BT40-MD32F-100	38	54	18	32	210	110	70	0.4	1
DBCA3238S	BT40-MD32F-115R	38	54	18	32	225	110	45	0.4	2
DBCA5054S	BT40-MD50F-105	54	74	28	50	205	145	73	1.1	1
DBCA6374S	BT40-MD63F-64	74	100	36	63	244	180	37	1.9	1
DBCA6374S	BT40-MD63F-135	74	100	36	63	315	180	83	1.9	1
DBCA6374S	BT40-MD80F-100	74	100	36	63	280	180	108	1.9	1
DBCA80100S	BT40-MD80F-100	100	136	45	80	315	215	73	3.7	1
DBCA2528S	BT50-MD25F-105	28	38	14	25	208	103	62	0.2	1
DBCA2528S	BT50-MD25F-120R	28	38	14	25	223	103	40	0.2	2
DBCA3238S	BT50-MD32F-110	38	54	18	32	220	110	67	0.4	1
DBCA3238S	BT50-MD32F-115R	38	54	18	32	225	110	45	0.4	2
DBCA3238S	BT50-MD32F-235R	38	54	18	32	345	110	115	0.4	2
DBCA5054S	BT50-MD50F-125	54	74	28	50	270	145	82	1.1	1
DBCA5054S	BT50-MD50F-225	54	74	28	50	370	145	182	1.1	1
DBCA5054S	BT50-MD50F-250R	54	74	28	50	395	145	81	1.1	2
DBCA6374S	BT50-MD63F-75	74	100	36	63	255	180	35	1.9	1
DBCA6374S	BT50-MD63F-130	74	100	36	63	310	180	87	1.9	1
DBCA6374S	BT50-MD63F-195	74	100	36	63	375	180	152	1.9	1
DBCA6374S	BT50-MD63F-230	74	100	36	63	410	180	187	1.9	1
DBCA80100S	BT50-MD80F-75	100	136	45	80	290	215	36	3.7	1
DBCA80100S	BT50-MD80F-110	100	136	45	80	325	215	69	3.7	1
DBCA80100S	BT50-MD80F-175	100	136	45	80	390	215	134	3.7	1

<sup>◆</sup> Spare Part G67


<sup>•</sup> Head: Basic, Arbor: For separate purchase • Through coolant system installed


<sup>\*</sup> In the above table, the Arbor Model No. is an example model no. and able to adjust the depth of boring with a combination of MD arbors and extension bars. For more details, see the MD arbor page.

### **HSK-DBC/A**

#### Helical type







(mm)

Designation		Boring range ØD		Ød	Ød <sub>1</sub>		L.	l.	
Head	Arbor	Min	Max	Øu	Øui	_	L1	L2	/ kg \
DBCA2528S-H	HSK63A-MD25F-60	38	54	14	25	163	103	31	0.3
DBCA3238S-H	HSK63A-MD32F-65	38	54	18	32	175	110	36	0.5
DBCA5054S-H	HSK63A-MD50F-85	54	74	28	50	230	145	58	1.8
DBCA6374S-H	HSK63A-MD63F-95	74	100	45	80	275	180	69	3.3


Spare Part G67


- Head: Basic, Arbor: For separate purchase Through coolant system is optional
- \* In the above table, the Arbor Model No. is an example model no. and able to adjust the depth of boring with a combination of MD arbors and extension bars. For more details, see the MD arbor page.

### **HSK-DBC/A**

#### Straight type







(mm)

De	Designation		Boring range ØD		Ød <sub>1</sub>		1.	La	<u>e</u>
Head	Arbor	Min	Max	Ød	<b>190</b> 1		Li	L2	kg
DBCA2528S	HSK63A-MD25F-60	38	54	14	25	122	62	31	0.3
DBCA3238S	HSK63A-MD32F-65	38	54	18	32	134.5	69.5	36	0.5
DBCA5054S	HSK63A-MD50F-85	54	74	28	50	179	94	58	1.8
DBCA6374S	HSK63A-MD63F-95	74	100	45	80	100	106.5	69	3.3

<sup>◆</sup> Spare Part G67


- Head: Basic, Arbor: For separate purchase Through coolant system is optional
- \* In the above table, the Arbor Model No. is an example model no. and able to adjust the depth of boring with a combination of MD arbors and extension bars. For more details, see the MD arbor page.

Designation	For separate purchase
Internal coolant system	

Classification by shank					
HSK50	HSK50A-CNS				
HSK63	HSK63A-CNS				
HSK100	HSK100A-CNS				

# G DBC

### **BT-DBC**



Designation											(mm)
Becator   Min   Max     DBC2528S   BT30-MD32F-80   35   14   25   150   60   63   0.3   1     DBC323SS   BT30-MD32F-80   35   46   18   32   145   65   55   0.4   1     DBC4046S   BT30-MD40F-46   46   58   22   40   115   70   22   0.6   1     DBC4046S   BT30-MD40F-80   46   58   22   40   140   70   56   0.6   1     DBC4046S   BT30-MD40F-80   46   58   22   40   140   70   56   0.6   1     DBC5058S   BT30-MD50F-70   58   74   28   50   150   80   48   1.1   1     DBC5252B   BT40-MD25F-95   28   35   14   25   155   60   63   0.3   1     DBC323SS   BT40-MD25F-105R   28   35   14   25   165   60   40   0.3   2     DBC323SS   BT40-MD32F-115R   35   46   18   32   180   65   45   0.4   2     DBC4046S   BT40-MD40F-60   46   58   22   40   130   70   31   0.6   1     DBC4046S   BT40-MD40F-110R   46   58   22   40   180   70   60   0.6   2     DBC4046S   BT40-MD40F-105   58   74   28   50   185   80   73   1.1   1     DBC6374S   BT40-MD63F-115   58   74   94   36   63   225   90   108   2.0   1     DBC6374S   BT40-MD63F-105   28   35   14   25   165   60   60   0.6   2     DBC6374S   BT40-MD63F-115   74   94   36   63   225   90   108   2.0   1     DBC6374S   BT40-MD63F-105   28   35   14   25   165   60   60   0.6   2     DBC6374S   BT40-MD63F-105   28   35   14   25   165   60   60   0.6   2     DBC6374S   BT40-MD63F-105   58   74   94   36   63   225   90   108   2.0   1     DBC6374S   BT40-MD63F-105   28   35   14   25   165   60   62   0.3   1     DBC6374S   BT40-MD63F-135   74   94   36   63   225   90   108   2.0   1     DBC6374S   BT50-MD25F-105   28   35   14   25   165   60   62   0.3   1     DBC6374S   BT50-MD36F-105   58   74   28   50   305   80   182   1.1   1     DBC6374S   BT50-MD36F-105   28   35   14   25   165   60   62   0.3   1     DBC6374S   BT50-MD36F-105   28   35   14   25   165   60   62   0.3   1     DBC6374S   BT50-MD36F-105   28   35   14   25   165   60   60   62   0.3   1     DBC6374S   BT50-MD36F-105   28   35   14   25   165   60   60   60   60   60   60   60	D	esignation	Boring r	ange ØD	Ød	Ød <sub>1</sub>	L	L <sub>1</sub>	L2	(kg)	Fig.
DBC3235S   BT30-MD32F-80   35   46   18   32   145   65   55   0.4   1	Head	Arbor	Min	Max						/ kg \	g.
DBC4046S   BT30-MD40F-45   46   58   22   40   115   70   22   0.6   1	DBC2528S	BT30-MD25F-90	28	35	14	25	150	60	63	0.3	1
DBC4046S   BT30-MD40F-60   46   58   22   40   130   70   36   0.6   1	DBC3235S	BT30-MD32F-80	35	46	18	32	145	65	55	0.4	1
DBC4046S   BT30-MD40F-80   46   58   22   40   140   70   56   0.6   1	DBC4046S	BT30-MD40F-45	46	58	22	40	115	70	22	0.6	1
DBC5058S   BT30-MD50F-70   58	DBC4046S	BT30-MD40F-60	46	58	22	40	130	70	36	0.6	1
DBC2528S         BT40-MD25F-95         28         35         14         25         155         60         63         0.3         1           DBC2528S         BT40-MD25F-10SR         28         35         14         25         165         60         40         0.3         2           DBC3235S         BT40-MD32F-11SR         35         46         18         32         180         65         45         0.4         2           DBC4046S         BT40-MD40F-60         46         58         22         40         130         70         31         0.6         1           DBC4046S         BT40-MD40F-110R         46         58         22         40         180         70         60         0.6         2           DBC4046S         BT40-MD40F-115         46         58         22         40         185         70         83         0.6         1           DBC6374S         BT40-MD63F-115         46         58         22         40         185         70         83         0.6         1           DBC6374S         BT40-MD63F-110         74         94         36         63         154         90         37         2.0	DBC4046S	BT30-MD40F-80	46	58	22	40	140	70	56	0.6	1
DBC2528S         BT40-MD25F-105R         28         35         14         25         165         60         40         0.3         2           DBC3235S         BT40-MD32F-110R         35         46         18         32         165         65         70         0.4         1           DBC3235S         BT40-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC4046S         BT40-MD40F-10R         46         58         22         40         130         70         31         0.6         1           DBC4046S         BT40-MD40F-115         46         58         22         40         180         70         60         0.6         2           DBC4046S         BT40-MD60F-105         58         74         28         50         185         80         73         1.1         1           DBC6374S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0	DBC5058S	BT30-MD50F-70	58	74	28	50	150	80	48	1.1	1
DBC3235S         BT40-MD32F-100         35         46         18         32         165         65         70         0.4         1           DBC3235S         BT40-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC4046S         BT40-MD40F-110R         46         58         22         40         180         70         60         0.6         1           DBC4046S         BT40-MD40F-115         46         58         22         40         180         70         60         0.6         2           DBC4046S         BT40-MD50F-105         58         74         28         50         185         80         73         1.1         1           DBC6374S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC2528S         BT50-MD25F-120R         28         35         14         25         165         60         62         0.3	DBC2528S	BT40-MD25F-95	28	35	14	25	155	60	63	0.3	1
DBC3235S         BT40-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC4046S         BT40-MD40F-60         46         58         22         40         130         70         31         0.6         1           DBC4046S         BT40-MD40F-110F         46         58         22         40         180         70         60         0.6         2           DBC4046S         BT40-MD40F-115         46         58         22         40         185         70         60         0.6         2           DBC6374S         BT40-MD63F-105         58         74         28         50         185         80         73         1.1         1           DBC6374S         BT40-MD63F-64         74         94         36         63         200         90         83         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC394S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5	DBC2528S	BT40-MD25F-105R	28	35	14	25	165	60	40	0.3	2
DBC4046S         BT40-MD40F-60         46         58         22         40         130         70         31         0.6         1           DBC4046S         BT40-MD40F-110R         46         58         22         40         180         70         60         0.6         2           DBC4046S         BT40-MD40F-115         46         58         22         40         185         70         83         0.6         1           DBC5058S         BT40-MD50F-105         58         74         28         50         185         80         73         1.1         1           DBC6374S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC6374S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC32528S         BT50-MD25F-105         28         35         14         25         165         60         62         0.3	DBC3235S	BT40-MD32F-100	35	46	18	32	165	65	70	0.4	1
DBC4046S         BT40-MD40F-110R         46         58         22         40         180         70         60         0.6         2           DBC4046S         BT40-MD40F-115         46         58         22         40         185         70         83         0.6         1           DBC6374S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-6110         74         94         36         63         200         90         83         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC8094S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-102         28         35         14         25         165         60         62         0.3         1           DBC3235S         BT50-MD32F-110         35         46         18         32         175         65         67         0.4	DBC3235S	BT40-MD32F-115R	35	46	18	32	180	65	45	0.4	2
DBC4046S         BT40-MD40F-115         46         58         22         40         185         70         83         0.6         1           DBC5058S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-64         74         94         36         63         200         90         37         2.0         1           DBC6374S         BT40-MD63F-110         74         94         36         63         200         90         83         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         200         90         83         2.0         1           DBC8094S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-105         28         35         14         25         185         60         62         0.3         1           DBC323SS         BT50-MD25F-120R         28         35         14         25         185         60         40         0.3	DBC4046S	BT40-MD40F-60	46	58	22	40	130	70	31	0.6	1
DBC5058S         BT40-MD50F-105         58         74         28         50         185         80         73         1.1         1           DBC6374S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-110         74         94         36         63         200         90         83         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC8094S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-105         28         35         14         25         165         60         62         0.3         1           DBC2528S         BT50-MD25F-120R         28         35         14         25         185         60         40         0.3         2           DBC3235S         BT50-MD32F-115R         35         46         18         32         180         65         45         0.4	DBC4046S	BT40-MD40F-110R	46	58	22	40	180	70	60	0.6	2
DBC6374S         BT40-MD63F-64         74         94         36         63         154         90         37         2.0         1           DBC6374S         BT40-MD63F-110         74         94         36         63         200         90         83         2.0         1           DBC6374S         BT40-MD80F-105         74         94         36         63         225         90         108         2.0         1           DBC8094S         BT40-MD80F-105         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-105         28         35         14         25         185         60         62         0.3         1           DBC2528S         BT50-MD25F-120R         28         35         14         25         185         60         40         0.3         2           DBC3235S         BT50-MD32F-110R         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-135R         35         46         18         32         180         65         45         0.4	DBC4046S	BT40-MD40F-115	46	58	22	40	185	70	83	0.6	1
DBC6374S         BT40-MD63F-110         74         94         36         63         200         90         83         2.0         1           DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC8094S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-105         28         35         14         25         185         60         62         0.3         1           DBC3235S         BT50-MD25F-110         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-15F         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD40F-23F         35         46         18         32         300         65         115         0.4	DBC5058S	BT40-MD50F-105	58	74	28	50	185	80	73	1.1	1
DBC6374S         BT40-MD63F-135         74         94         36         63         225         90         108         2.0         1           DBC8094S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-105         28         35         14         25         165         60         62         0.3         1           DBC2528S         BT50-MD32F-120R         28         35         14         25         185         60         40         0.3         2           DBC3235S         BT50-MD32F-110R         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-235R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-235R         35         46         18         32         180         65         45         0.4         2           DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6	DBC6374S	BT40-MD63F-64	74	94	36	63	154	90	37	2.0	1
DBC8094S         BT40-MD80F-100         94         120         45         80         200         100         73         3.5         1           DBC2528S         BT50-MD25F-105         28         35         14         25         165         60         62         0.3         1           DBC2528S         BT50-MD25F-120R         28         35         14         25         185         60         40         0.3         2           DBC3235S         BT50-MD32F-110         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-235R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-235R         35         46         18         32         300         65         115         0.4         2           DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6	DBC6374S	BT40-MD63F-110	74	94	36	63	200	90	83	2.0	1
DBC2528S         BT50-MD25F-105         28         35         14         25         165         60         62         0.3         1           DBC2528S         BT50-MD25F-120R         28         35         14         25         185         60         40         0.3         2           DBC3235S         BT50-MD32F-110R         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-235R         35         46         18         32         300         65         115         0.4         2           DBC3235S         BT50-MD40F-235R         35         46         18         32         300         65         115         0.4         2           DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6	DBC6374S	BT40-MD63F-135	74	94	36	63	225	90	108	2.0	1
DBC2528S         BT50-MD25F-120R         28         35         14         25         185         60         40         0.3         2           DBC3235S         BT50-MD32F-110         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-235R         35         46         18         32         300         65         115         0.4         2           DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6         1           DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-125         58         74         28         50         305         80         82         1.1	DBC8094S	BT40-MD80F-100	94	120	45	80	200	100	73	3.5	1
DBC3235S         BT50-MD32F-110         35         46         18         32         175         65         67         0.4         1           DBC3235S         BT50-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-235R         35         46         18         32         300         65         115         0.4         2           DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6         1           DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-125         58         74         28         50         205         80         82         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         305         80         81         1.1	DBC2528S	BT50-MD25F-105	28	35	14	25	165	60	62	0.3	1
DBC3235S         BT50-MD32F-115R         35         46         18         32         180         65         45         0.4         2           DBC3235S         BT50-MD32F-235R         35         46         18         32         300         65         115         0.4         2           DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6         1           DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-125         58         74         28         50         205         80         82         1.1         1           DBC5058S         BT50-MD50F-225         58         74         28         50         305         80         182         1.1         1           DBC5058S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0	DBC2528S	BT50-MD25F-120R	28	35	14	25	185	60	40	0.3	2
DBC3235S         BT50-MD32F-235R         35         46         18         32         300         65         115         0.4         2           DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6         1           DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-195         46         58         22         40         300         70         180         0.6         2           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-250F         58         74         28         50         305         80         82         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0	DBC3235S	BT50-MD32F-110	35	46	18	32	175	65	67	0.4	1
DBC4046S         BT50-MD40F-60         46         58         22         40         130         70         22         0.6         1           DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-125         58         74         28         50         205         80         82         1.1         1           DBC5058S         BT50-MD50F-225         58         74         28         50         305         80         182         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         285         90         152         2.0	DBC3235S	BT50-MD32F-115R	35	46	18	32	180	65	45	0.4	2
DBC4046S         BT50-MD40F-195         46         58         22         40         265         70         152         0.6         1           DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-125         58         74         28         50         205         80         82         1.1         1           DBC5058S         BT50-MD50F-225         58         74         28         50         305         80         182         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0	DBC3235S	BT50-MD32F-235R	35	46	18	32	300	65	115	0.4	2
DBC4046S         BT50-MD40F-230R         46         58         22         40         300         70         180         0.6         2           DBC5058S         BT50-MD50F-125         58         74         28         50         205         80         82         1.1         1           DBC5058S         BT50-MD50F-225         58         74         28         50         305         80         182         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0	DBC4046S	BT50-MD40F-60	46	58	22	40	130	70	22	0.6	1
DBC5058S         BT50-MD50F-125         58         74         28         50         205         80         82         1.1         1           DBC5058S         BT50-MD50F-225         58         74         28         50         305         80         182         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5	DBC4046S	BT50-MD40F-195	46	58	22	40	265	70	152	0.6	1
DBC5058S         BT50-MD50F-225         58         74         28         50         305         80         182         1.1         1           DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5	DBC4046S	BT50-MD40F-230R	46	58	22	40	300	70	180	0.6	2
DBC5058S         BT50-MD50F-250R         58         74         28         50         330         80         81         1.1         2           DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5	DBC5058S	BT50-MD50F-125	58	74	28	50	205	80	82	1.1	1
DBC6374S         BT50-MD63F-75         74         94         36         63         165         90         35         2.0         1           DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5         1	DBC5058S	BT50-MD50F-225	58	74	28	50	305	80	182	1.1	1
DBC6374S         BT50-MD63F-130         74         94         36         63         220         90         87         2.0         1           DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5         1	DBC5058S	BT50-MD50F-250R	58	74	28	50	330	80	81	1.1	2
DBC6374S         BT50-MD63F-195         74         94         36         63         285         90         152         2.0         1           DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5         1	DBC6374S	BT50-MD63F-75	74	94	36	63	165	90	35	2.0	1
DBC6374S         BT50-MD63F-230         74         94         36         80         320         90         187         2.0         1           DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5         1	DBC6374S	BT50-MD63F-130	74	94	36	63	220	90	87	2.0	1
DBC8094S         BT50-MD80F-75         94         120         36         80         175         100         36         3.5         1           DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5         1	DBC6374S	BT50-MD63F-195	74	94	36	63	285	90	152	2.0	1
DBC8094S         BT50-MD80F-110         94         120         45         80         210         100         69         3.5         1           DBC8094S         BT50-MD80F-175         94         120         45         80         275         100         134         4.5         1	DBC6374S	BT50-MD63F-230	74	94	36	80	320	90	187	2.0	1
<b>DBC8094S BT50-MD80F-175</b> 94 120 45 80 275 100 134 4.5 1	DBC8094S	BT50-MD80F-75	94	120	36	80	175	100	36	3.5	1
	DBC8094S	BT50-MD80F-110	94	120	45	80	210	100	69	3.5	1
<b>DBC120S BT50-MD80F-175</b> 120 175 45 80 275 100 134 4.1 1	DBC8094S	BT50-MD80F-175	94	120	45	80	275	100	134	4.5	1
	DBC120S	BT50-MD80F-175	120	175	45	80	275	100	134	4.1	1


<sup>◆</sup> Spare Part G67


<sup>•</sup> Head: Basic, Arbor: For separate purchase • Through coolant system installed

<sup>\*</sup> In the above table, the Arbor Model No. is an example model no. and able to adjust the depth of boring with a combination of MD arbors and extension bars. For more details, see the MD arbor page.

HSK-DBC Modular type







(mm)

С	Designation		ange ØD	Ød Ød1		L <sub>1</sub>	L <sub>2</sub>	و _	
Head	Arbor	Min	Max	Øu	Ø <b>u</b> 1		Li	<b>L</b> 2	kg
DBC2528S	HSK63A-MD25F-60	28	35	14	25	120	60	31	0.3
DBC3235S	HSK63A-MD32F-65	35	46	18	32	130	65	36	0.4
DBC4046S	HSK63A-MD40F-70	46	58	22	40	140	70	41	0.6
DBC5058S	HSK63A-MD50F-85	58	74	28	50	165	80	58	1.1
DBC6374S	HSK63A-MD63F-95	74	94	36	63	185	90	69	2.0

<sup>●</sup> Spare Part G67

#### Parts

#### • DBCA

	Basic												
Division	Head	Spring pin	Wrench bolt	Wrench	Cartridge	Set screw	Wrench	Clamp screw	Torx wrench				
Parts Designation			Simo		6			Change.	1				
DBCA2528S	DBCA2528	SP0308	BX0420	LW-3	BCC28-EC	BT0308	LW-1.5	BFTX02506N	TRX8				
DBCA3238S	DBCA3238	SP0410	BX0525	LW-4	BCC38-EC	BT0310	LW-1.5	BFTX02506M	TRX8				
DBCA5054S	DBCA5054	SP0616	BX0630	LW-5	BCC54-EC	BT0414	LW-2	BFTX0407N	TRX15				
DBCA6374S	DBCA6374	SP1018	BX0635	LW-5	BCC74-EC	BT0520	LW-2.5	BFTX0511N	TRX20				
DBCA80100S	DBCA80100	SP1020	BX0840	LW-6	BCC100-EC	BT0625	LW-3	BFTX0511N	TRX20				

#### • DBC

				Basic					
Division	Head	Spring pin	Wrench bolt	Wrench	Cartridge	Set screw	Wrench	Clamp screw	Torx wrench
Parts Designation			Simo		6			Dame.	-
DBC2528S	DBC2528	SP0308	BX0415	LW-3	BCC28	BT0306	LW-1.5	FTKA02565	TRX7
DBC3235S	DBC3235	SP0410	BX0515	LW-4	BCC35	BT0308	LVV-1.5		IHX/
DBC4046S	DBC4046	SP0516	BX0620	LW-5	BCC46	BT0410	LW-2	FTNA0408	TRX15
DBC5058S	DBC5058	SP0616	DXU02U	LVV-5	BCC58	BT0412	LVV-Z	FINAU4U8	IHAID
DBC6374S	DBC6374	SP1018	BX0830	LW-6	BCC74	BT0516	LW-2.5	DETVOE11N	TDV00
DBC8094S	DBC8094	SP1020	BX1035	LW-8	BCC94	BT0620	LW-3	BFTX0511N	TRX20
DBC120S	DBC120N	SP1020	BX0830	LW-6	BCC120	BT0830	LW-4	BFTX0511N	TRX20


<sup>•</sup> Head: Basic, Arbor: For separate purchase • Through coolant system is optional

<sup>\*</sup> In the above table, the Arbor Model No. is an example model no. and able to adjust the depth of boring with a combination of MD arbors and extension bars. For more details, see the MD arbor page.

G SMB

### **BT-SMB**

### **Small Micro Boring Bar**




(mm)

	Designation		Basing sange (CD		1.	1.		Fi <sub>m</sub>
Head	Arbor	Bite	Boring range ØD	L	L <sub>1</sub>	L <sub>2</sub>	kg	Fig.
SMB4022	BT30-MD40F-45	BB18-□(S)	Ø6.0~Ø34.0	107.5	22	62.5	0.6	1
SMB4022	BT30-MD40F-60	BB18-□(S)	Ø6.0~Ø34.0	122.5	36	62.5	0.6	1
SMB4022	BT30-MD40F-80	BB18-□(S)	Ø6.0~Ø34.0	142.5	56	62.5	0.6	1
SMB4022	BT40-MD40F-60	BB18-□(S)	Ø6.0~Ø34.0	122.5	31	62.5	0.6	1
SMB4022	BT40-MD40F-110R	BB18-□(S)	Ø6.0~Ø34.0	172.5	60	62.5	0.6	2
SMB4022	BT40-MD40F-115	BB18-□(S)	Ø6.0~Ø34.0	177.5	83	62.5	0.6	1
SMB4022	BT50-MD40F-60	BB18-□(S)	Ø6.0~Ø34.0	122.5	22	62.5	0.6	1
SMB4022	BT50-MD40F-195	BB18-□(S)	Ø6.0~Ø34.0	257.5	152	62.5	0.6	1
SMB4022	BT50-MD40F-230R	BB18-□(S)	Ø6.0~Ø34.0	292.5	180	62.5	0.6	2

<sup>\*</sup> Adjustment length: 7 mm

### **ᢒ** BB Bite (For SMB)



(mm)

	Desimation	Boring	range	α. <sub>1</sub>				<u> </u>	lucout	Incort course
	Designation	Min	Max	Ød	L <sub>1</sub>	L <sub>2</sub>	S	kg	Insert	Insert screw
ВВ	18-7(S)	7	27	18	30	30	3.5	0.1	TBGT0601□□L	BFTX0204A
	18-9(S)	9	29	18	30	40	4.5	0.1	TPGT0802□□L	BFTX0204A
	18-11(S)	11	31	18	30	45	5.5	0.1	TPGT1103□□L	BFTX0307A
	18-13(S)	13	33	18	40	45	6.5	0.1	TPGT1103□□L	BFTX0307A
	18-15(S)	15	35	18	40	50	7.5	0.2	TPGT1103□□L	BFTX0307A
	18-17(S)	17	37	18	40	50	8.5	0.2	TPGT1103□□L	BFTX0307A

	Ba	sic		For separate purchase			
Division	Boring head	Boring bite	Basic holder				
Parts Designation					1		
SMB	SMB4022	BTT1013F	LW-2.5	BB18	MD40F		


<sup>•</sup> Head: Basic, Arbor/Bite: For separate purchase • Through coolant system not available




### **HSK-SMB**

#### **Small Micro Boring Bar**








Head

(mm)

	Designation	Boring range ØD		L	La		
Head	Arbor	Bite	Borning range 90	_	Li	L2	<u>/ kg \</u>
SMB4022	SMB4022 HSK63A-MD40F - 70 BB18-□(S)		Ø6.0~Ø34.0	132.5	41	62.5	0.6

<sup>\*</sup> Adjustment length: 17 mm

### **ᢒ** BB Bite (For SMB)



(mm)

	Decimation	Boring	range	Ød	1.	1.	S	4	Insert	Insert screw
	Designation	Min	Max	Øα	L <sub>1</sub>	L <sub>2</sub>	3	kg	IIISCIT	insert screw
ВВ	18-7(S)	7	27	18	30	30	3.5	0.1	TBGT0601□□L	BFTX0204A
	18-9(S)	9	29	18	30	40	4.5	0.1	TPGT0802□□L	BFTX0204A
	18-11(S)	11	31	18	30	45	5.5	0.1	TPGT1103□□L	BFTX0307A
	18-13(S)	13	33	18	40	45	6.5	0.1	TPGT1103□□L	BFTX0307A
	18-15(S)	15	35	18	40	50	7.5	0.2	TPGT1103□□L	BFTX0307A
	18-17(S)	17	37	18	40	50	8.5	0.2	TPGT1103□□L	BFTX0307A


	Ba		For separate purchase			
Division	Boring head	Wrench	Boring bite	Basic holder		
Parts Designation					1	
SMB	SMB4022	BTT1013F	LW-2.5	BB18	MD40F	


<sup>•</sup> Head: Basic, Arbor/Bite: For separate purchase • Through coolant system not available

G KMB

### BT-KMB Micro Boring








(mm)

	Designation		Boring r	ange ØD		L	L <sub>2</sub>	\(\rightarrow\) \(\lambda\) kg \
Head	Arbor	Bite	Bite position	ØD	L	L <sub>1</sub>	L2	<u>/ kg \</u>
KMB6336	BT40-MD63F-64	BB18-□(S)	Center Hole	Ø8.0~Ø38.0	141	37	77	2.2
KMB6336	BT40-MD63F-110	BB18-□(S)	Center Hole	Ø8.0~Ø38.0	187	83	77	2.2
KMB6336	BT40-MD63F-135	BB18-□(S)	Eccentric Hole	Ø41.0~101.0	212	108	77	2.2
KMB6336	BT50-MD63F-75	BB18-□(S)	Eccentric Hole	Ø41.0~101.0	152	35	77	2.2
KMB6336	BT50-MD63F-135	BB18-□(S)	Side Hole	Max.Ø165.0	207	87	77	2.2
KMB6336	BT50-MD63F-195	BB18-□(S)	Side Hole	Max.Ø165.0	272	152	77	2.2

<sup>\*</sup> Adjustment length: 7 mm

### **ᢒ** BB Bite (For KMB)



(mm)


	Designation	Boring range (Center)			Qq	Ød L <sub>1</sub>		s	O kg \	Insert	Insert Screw	
	Designation	Cei	nter	Eccentric		Юu	Li	L2	3	/ kg \	ilisert	ilisert screw
ВВ	18-7(S)	7	40	27	91	18	30	30	3.5	0.1	TBGT0601□□L	BFTX0204A
	18-9(S)	9	42	29	93	18	30	40	4.5	0.1	TPGT0802□□L	BFTX0204A
	18-11(S)	11	44	31	95	18	30	45	5.5	0.1	TPGT1103□□L	BFTX0307A
	18-13(S)	13	46	33	97	18	40	45	6.5	0.1	TPGT1103□□L	BFTX0307A
	18-15(S)	15	48	35	99	18	40	50	7.5	0.2	TPGT1103□□L	BFTX0307A
	18-17(S)	17	50	37	101	18	40	50	8.5	0.2	TPGT1103□□L	BFTX0307A

	Ba	Basic									
Division	Boring head	Boring bite	Basic holder								
Parts Designation	9				W. Company						
KMB	KMB6336	BTT1620F	LW-4.0	BB18	MD63F						

<sup>•</sup> Head: Basic, Arbor/Bite: For separate purchase • Through coolant system not available

### HSK-KMB Micro Boring






(mm)

1DIV = Ø0.02mm

	Designation		Boring range ØD		1.		l.	٥
Head	Arbor	Bite	Bite position	ØD	_	Li	L2	<u>/ kg \</u>
KMB6336	HSK63A-MD63F-95	BB18-□(S)	Center Hole	Ø8.0~Ø38.0	172	69	77	2.2

<sup>\*</sup> Adjustment length: 7 mm

### **ᢒ** BB Bite (For KMB)



(mm)

	Designation		Boring range (Center)			Ød	1.	L <sub>2</sub>	S	O kg	Insert	Insert Screw
			nter	Eccentric		Юd	L <sub>1</sub>	L2	3	<u>/ kg \</u>	insert	insert Screw
ВВ	18-7(S)	7	40	27	91	18	30	30	3.5	0.1	TBGT0601□□L	BFTX0204A
	18-9(S)	9	42	29	93	18	30	40	4.5	0.1	TPGT0802□□L	BFTX0204A
	18-11(S)	11	44	31	95	18	30	45	5.5	0.1	TPGT1103□□L	BFTX0307A
	18-13(S)	13	46	33	97	18	40	45	6.5	0.1	TPGT1103□□L	BFTX0307A
	18-15(S)	15	48	35	99	18	40	50	7.5	0.2	TPGT1103□□L	BFTX0307A
	18-17(S)	17	50	37	101	18	40	50	8.5	0.2	TPGT1103□□L	BFTX0307A


	Ва	For separate purchase			
Division	Boring head	Taper screw	Wrench	Boring bite	Basic holder
Parts Designation	9				
KMB	KMB6336	BTT1620F	LW-4.0	BB18	MD63F

<sup>•</sup> Head: Basic, Arbor/Bite: For separate purchase • Through coolant system not available

G SMH

### **BT-SMH**

### **Small Micro Boring Bar (For High precision)**




(mm)

	Designation		Boring range ØD	L	L <sub>1</sub>	L <sub>2</sub>		Eia
Head	Arbor	Bite	Borning range ØD		Li	<b>L</b> 2	/ kg \	Fig.
SMH4022	BT30-MD40F-45	BB16-□(S)	Ø6.0~Ø34.0	94	22	49	0.6	1
SMH4022	BT30-MD40F-60	BB16-□(S)	Ø6.0~Ø34.0	109	36	49	0.6	1
SMH4022	BT30-MD40F-80	BB16-□(S)	Ø6.0~Ø34.0	129	56	49	0.6	1
SMH4022	BT40-MD40F-60	BB16-□(S)	Ø6.0~Ø34.0	109	31	49	0.6	1
SMH4022	BT40-MD40F-110R	BB16-□(S)	Ø6.0~Ø34.0	159	60	49	0.6	2
SMH4022	BT40-MD40F-115	BB16-□(S)	Ø6.0~Ø34.0	164	83	49	0.6	1
SMH4022	BT50-MD40F-60	BB16-□(S)	Ø6.0~Ø34.0	109	22	49	0.6	1
SMH4022	BT50-MD40F-195	BB16-□(S)	Ø6.0~Ø34.0	244	152	49	0.6	1
SMH4022	BT50-MD40F-230R	BB16-□(S)	Ø6.0~Ø34.0	279	180	49	0.6	2

<sup>\*</sup> Adjustment length: 7 mm

### **ᢒ** BB Bite (For SMH)



(mm)

	Designation		Boring range ØD		L <sub>1</sub>	1.	S	Insert	Insert Screw	Wrench
			Max	Ød		L2	3	ilisert	iliseit Sciew	Wielicii
ВВ	16-5(S)	5	19	16	34	20	2.75	WBGT0601□□L	BFTX0203A	TRX06
	16-7(S)	7	21	16	34	30	3.5	TBGT0601□□L	BFTX0204A	TRX06
	16-9(S)	9	23	16	34	40	4.5	TPGT0802□□L	BFTX0204A	TRX06
	16-11(S)	11	25	16	34	45	5.5	TPGT1103□□L	BFTX0307A	TRX10
	16-15(S)	15	29	16	34	50	7.5	TPGT1604□□L	BFTX0307A	TRX10
	16-19(S)	19	33	16	34	60	9.5	TPGT1604□□L	BFTX0410A	TRX15

	Ва	For separate purchase			
Division	Boring head	Taper screw	Wrench	Boring bite	Basic holder
Parts Designation					1
SMH	SMH4022	BTT1013F	LW-3.0	BB16	MD40F


<sup>•</sup> Head: Basic, Arbor/Bite: For separate purchase • Through coolant system not available



### **HSK-SMH**

### **Small Micro Boring Bar (For High precision)**






(mm)

Designation		Boring range ØD	1	1.		ب	
Head	Arbor	Bite	Borning range 90	L	Li	L2	<u>/ kg \</u>
SMH4022	HSK63-MD40F-70	BB16-□(S)	Ø6.0~Ø34.0	132.5	41	49	0.6

<sup>\*</sup> Adjustment length: 17 mm

### **ᢒ** BB Bite (For SMH)



(mm)

	Designation	Boring range ØD		Insert	Insert Screw	O kg
	Designation	Min	Max	IIISEIT	iliseit Sciew	<u>/ kg \</u>
ВВ	16-7(S)	8	28	TBGT0601□□L	BFTX0204A	0.1
	16-9(S)	10	30	TPGT0802□□L	BFTX0204A	0.1
	16-11(S)	12	32	TPGT1103□□L	BFTX0307A	0.1
	16-13(S)	14	34	TPGT1103□□L	BFTX0307A	0.1
	16-15(S)	16	36	TPGT1604□□L	BFTX0307A	0.2
	16-17(S)	18	38	TPGT1604□□L	BFTX0307A	0.2

	Ва		For separate purchase		
Division	Boring head	Taper screw	Wrench	Boring bite	Basic holder
Parts Designation					W. Commission
SMH	SMH4022	BTT1013F	LW-3.0	BB16	MD40F

<sup>•</sup> Head: Basic, Arbor/Bite: For separate purchase • Through coolant system not available

#### Wide diameter boring system

# TBCA new

- Convenience in use simultaneously (available both inside and outside)
- Broad boring diameter and range
- Rough/Finishing boring with replaceable cartridge and common rail
- Boring range for outer diameter: Ø0~Ø395
- Boring range for inner diameter: Ø130~Ø631




### Code system



#### Features

#### Reinforced rigidity

• 50% less moment strain (versus the conventional product of DINE)



#### Lightweight design(Head set)

• BCC (Cartridge) + DBR (Bridge) + DBB (Rail)



TBC130A	TBC175A	TBC220A	TBC265A
4.2 Kg	5.6 Kg	6.6 Kg	7.5 Kg
TBC310A	TBC385A	TBC460A	TBC535A
9.5 Kg	11.6Kg	14 Kg	16 Kg

#### Application








Single edge boring




Step boring



Outside boring

### Wide compatibility



Workpiece o	outer	dia.
. borin	ng	


	Images	List of clamping parts	Cutting type
Outer dia.		FBH3233B + FCE310 + FCB310	Finishing boring
boring		DBCA3235S + FCE310 + CB310	Rough boring
Inner dia. boring		DBS:::-:::::::::::::::::::::::::::::::::	Rough boring
		FCC310	Finishing boring
	8	BCC1354	Rough boring


• TBC310A in case

# **TBCA**

### Wide diameter boring system







(mm)

		Twin Edg	je Borin	g for Rou	ghing				
FMC Arbor	ے ا	0		Bor		ng range	ØD		
(Individual order)	/ kg \	TBC Head set (Rail + Cartridge (Main))	L	Inside Boring		Outside Boring			kg
				Min	Max	Min	Max	L <sub>1</sub>	
BT50-FMC40-50	4.6	TBC130A (DBR130 + BCC1348 + BCC1348)	108	130	180	0	35	65	3.8
BT50-FMC40-50	4.6	TBC175A (DBR175 + BCC1348 + BCC1348)	113	175	225	0	75	65	5.2
BT50-FMC40-50	4.6	TBC220A (DBR07015 + BCC1348 + BCC1348)	118	220	270	60	124	65	7.3
BT50-FMC40-50	4.6	TBC265A (DBR07015 + BCC1348 + BCC1348)	123	265	315	64	174	65	7.3
BT50-FMC40-50	4.6	TBC310A (DBR10015 + BCC1345 + BCC1345)	128	310	390	79	159	65	9.7
BT50-FMC40-50	4.6	TBC385A (DBR10015 + BCC1354 + BCC1345)	133	385	465	153	233	65	11.8
BT50-FMC40-50	4.6	TBC460A (DBR10015 + BCC1354 + BCC1345)	138	460	540	229	309	65	14.3
BT50-FMC40-50	4.6	TBC535A (DBR10015 + BCC1354 + BCC1345)	143	535	615	303	383	65	16.4

• TBC Head set: Basic, Arbor: For separate purchase • Through coolant system is optional


	Basic		For separate purchase			
Head set Bridge		Rail	Cartridge	Arbor	Pin	
•	Carlotte .			0	/	
TBC130A	DBB130	DBR130				
TBC175A	DBB175	DBR175	DCC1040C			
TBC220A	DBB220	DBR07015	BCC1348S			
TBC265A	DBB265	DBR07015		DT50 FM040 50	DNIAGOG	
TBC310A	DBB310	DBR10015		BT50-FMC40-50	PN1080	
TBC385A	DBB385	DBR10015	B0040540			
TBC460A	DBB460	DBR10015	BCC1354S			
TBC535A	DBB535	DBR10015				


G TBCA

# **TBCA**

### Wide diameter boring system







(mm)

		Single Edge Boring for Roughing											
FMC Arbor	O kg				Bori	ng range	ØD						
(Individual order)	/ kg \	TBC Head set (Rail + Cartridge (Separate sale))	L	Inside	Boring	Out	side Bor	kg					
		(Hall 1 Cartilage (Separate Sale))		Min	Max	Min	Max	L <sub>1</sub>					
BT50-FMC40-50	4.6	TBC130A (DBR130 + FCC130 + FCB130 + FBB33N)	101	130	180	37	37	72	4.4				
BT50-FMC40-50	4.6	TBC175A (DBR175 + FCC130 + FCB130 + FBB33N)	106	175	225	80	80	72	5.7				
BT50-FMC40-50	4.6	TBC220A (DBR07015 + FCC130 + FCB130 + FBB33N)	111	220	270	173	173	72	7.8				
BT50-FMC40-50	4.6	TBC265A (DBR07015 + FCC130 + FCB130 + FBB33N)	116	265	315	176	176	72	7.9				
BT50-FMC40-50	4.6	TBC310A (DBR10015 + FCC310 + FCB310 + BB33N)	121	310	390	155.5	155.5	72	10.1				
BT50-FMC40-50	4.6	TBC385A (DBR10015 + FCC310 + FCB310 + FBB33N)	126	385	465	229.5	229.5	72	12.2				
BT50-FMC40-50	4.6	TBC460A (DBR10015 + FCC310 + FCB310 + FBB33N)	131	460	540	305.5	305.5	72	14.7				
BT50-FMC40-50	4.6	TBC535A (DBR10015 + FCC310 + FCB310 + FBB33N)	136	535	615	379.5	379.5	72	16.7				

• TBC Head set/Rail: Basic, Arbor/Cartridge: For separate purchase • Through coolant system is optional


	Basic			Fe	or separate purcha	ise	
Head set	Bridge	Rail	Cartridge	Bite	Balance block	Arbor	Pin
***	California .	-		9	•	0	/
TBC130A	DBB130	DBR130			FORMO		
TBC175A	DBB175	DBR175	F00100				
TBC220A	DBB220	DBR07015	FCC130		FCB130		
TBC265A	DBB265	DBR07015		<b>EDD</b> 400		DT50 5140 40 50	DNIAGO
TBC310A	DBB310	DBR10015		FBB130△□□		BT50-FMC40-50	PN1080
TBC385A	DBB385	DBR10015	500040		FORMA		
TBC460A	DBB460	DBR10015	FCC310		FCB310		
TBC535A	DBB535	DBR10015					




# **TBCA**

### Wide diameter boring system







(mm)

		Step Boring for Roughing									
FMC Arbor	4			Boring ran			e ØD				
(Individual order)	/kg	☐ TBC Head set (Rail + Cartridge (Separate sale))	L	Inside Boring		Out	ıtside Boring		kg		
		(Hall + Gaithage (Geparate Sale))		Min	Max	Min	Max	L <sub>1</sub>			
BT50-FMC40-50	4.6	TBC130A (DBR130 + DBS25-□□CA + SCGCL16CA-12)	108	130	180	0	13.5	65	4.3		
BT50-FMC40-50	4.6	TBC175A (DBR175 + DBS25-□□CA + SCGCL16CA-12)	113	175	225	0	55	65	5.7		
BT50-FMC40-50	4.6	TBC220A (DBR07015 + DBS25-□□CA + SCGCL16CA-12)	118	220	270	64	128	65	7.8		
BT50-FMC40-50	4.6	TBC265A (DBR07015 + DBS25-□□CA + SCGCL16CA-12)	123	265	315	68	118	65	7.9		
BT50-FMC40-50	4.6	TBC310A (DBR10015 + DBS40-□□CA + SCGCL16CA-12)	128	310	390	109	159	65	10.2		
BT50-FMC40-50	4.6	TBC385A (DBR10015 + DBS40-□□CA + SCGCL16CA-12)	133	385	465	183	233	65	12.3		
BT50-FMC40-50	4.6	TBC460A (DBR10015 + DBS40-□□CA + SCGCL16CA-12)	138	460	540	259	309	65	14.8		
BT50-FMC40-50	4.6	TBC535A (DBR10015 + DBS40-□□CA + SCGCL16CA-12)	143	535	615	333	383	65	16.9		


• TBC Head set/Rail: Basic, Arbor/Cartridge: For separate purchase • Through coolant system is optional

	Ва	sic			Fo	r separate purch	ase	
Head set	Bridge	Rail	Cartridge	Arbor	Slide	Cartridge	Plate	Pin
•	The state of the s	-		0	•	1	10 to ca	/
TBC130A	DBB130	DBR130	BCC1348S					
TBC175A	DBB175	DBR175	BCC1348S		DBS25-16CA			
TBC220A	DBB220	DBR07015	BCC1348S		DBS25-20CA DBS25-25CA			
TBC265A	DBB265	DBR07015	BCC1348S	BT50-	22020 2007	100 0	ISO Cartridge	DNIAGOG
TBC310A	DBB310	DBR10015	BCC1354S	FMC40-50		ISO Cartridge	Plates	PN1080
TBC385A	DBB385	DBR10015	BCC1354S		DBS40-16CA			
TBC460A	DBB460	DBR10015	BCC1354S		DBS40-20CA DBS40-25CA			
TBC535A	DBB535	DBR10015	BCC1354S		220.32007			

# **TBCA**

### Wide diameter boring system





(mm)

		Step Boring for Roughing						
FMC Arbor	O kg			Boring rang		e ØD		
(Individual order)	/ kg \	TBC Head set (Rail + Cartridge (Separate sale))	L	Outside Boring			/ kg	
		(Hair Fourthage (Ocparate Sale))		Min	Max	L <sub>1</sub>		
BT50-FMC40-50	4.6	TBC130A (DBR130 + FCB130 + FCE130 + FBH3233B + FBB33N)	145	0	39	102	5.2	
BT50-FMC40-50	4.6	TBC175A (DBR175 + FCB130 + FCE130 + FBH3233B + FBB33N)	150	0	84	102	6.5	
BT50-FMC40-50	4.6	TBC220A (DBR07015 + FCB130 + FCE130 + FBH3233B + FBB33N)	155	26	180	102	8.7	
BT50-FMC40-50	4.6	TBC265A (DBR07015 + FCB130 + FCE130 + FBH3233B + FBB33N)	160	26	180	102	8.7	
BT50-FMC40-50	4.6	TBC310A (DBR10015 + FCB310 + FCE310 + FBH3233B + FBB33N)	165	16	170	102	11	
BT50-FMC40-50	4.6	TBC385A (DBR10015 + FCB310 + FCE310 + FBH3233B + FBB33N)	170	90	244	102	13.1	
BT50-FMC40-50	4.6	TBC460A (DBR10015 + FCB310 + FCE310 + FBH3233B + FBB33N)	175	166	318	102	15.6	
BT50-FMC40-50	4.6	TBC535A (DBR10015 + FCB310 + FCE310 + FBH3233B + FBB33N)	180	240	394	102	17.7	

• TBC Head set/Rail: Basic, Arbor/Cartridge: For separate purchase • Through coolant system is optional

	Basic			F	or separate purcha	se	
Head set	ead set Bridge		Arbor	Slide	В/В	B/B Head	
•	The state of the s	-	0	•	•	-	/
TBC130A	DBB130	DBR130					
TBC175A	DBB175	DBR175		505400	FCB130		
TBC220A	DBB220	DBR07015		FCE130			
TBC265A	DBB265	DBR07015	DT50 514040 50			EDI IOGGOD	
TBC310A	DBB310	DBR10015	BT50-FMC40-50			FBH3233B	PN1080
TBC385A	DBB385	DBR10015		505040	FORMA		
TBC460A	DBB460	DBR10015	1	FCE310	FCB310		
TBC535A	DBB535	DBR10015					

#### **Balance cut tool for Rough boring**

### **TBC**

- Wide boring range for big diameters: Ø130~Ø540 mm
- Stable structure against for cutting load Assembly by dove-tail structure
- Interconvert with FBC
  - Common boring head and rail adopted, different cartridge
- Light-weight (5%~20% reduced)
- Various cartridge approach angle: 15°, 45°



#### Code system

### TBC boring tool structure & features





Cartridge: BCC1348 Insert: CCMT1204 CNMG1204□□



Rail: TBR□□ Weight reduced and space for chip discharge secured by removing the side part

### Boring range


O I.	Dia (Ø)			1
Grade	Min	Max	Head set	Insert
TBC130	130	180	TBC130 (TBR130 + BCC1348 + BCC1348)	CCMT1204□□
TBC175	175	225	TBC175 (TBR175 + BCC1348 + BCC1348)	CCMT1204□□
TBC220	220	270	TBC220 (TBR220 + BCC1348 + BCC1348)	CCMT1204□□
TBC265	265	315	TBC265 (TBR265 + BCC1348 + BCC1348)	CCMT1204□□
TBC310	310	390	TBC310 (TBR310 + BCC1348 + BCC1348)	CCMT1204□□
TBC385	385	465	TBC385 (TBR310 + BCC1348 + BCC1348)	CCMT1204□□
TBC460	460	540	TBC460 (TBR460 + BCC1348 + BCC1348)	CCMT1204□□

# G TBC

# **BT-TBC**

### Balance cut tool for rough boring





5140 A I		Rough boring (TBC)								
FMC Arbor (Individual order)	kg	TBC Head set	L	Boring r	ange ØD	O kg				
(marriadar order)		(Rail + Cartridge)		Min	Max	/ kg \				
BT50-FMD50-85	5.9	TBC130 (TBR130 + BCC1348)	175	130	180	3.2				
BT50-FMD50-155	7.9	TBC130 (TBR130 + BCC1348)	245	130	180	3.2				
BT50-FMD50-205	9.7	TBC130 (TBR130 + BCC1348)	295	130	180	3.2				
BT50-FMD50-255	13.4	TBC130 (TBR130 + BCC1348)	345	130	180	3.2				
BT50-FMD50-85	5.9	TBC175 (TBR175 + BCC1348)	175	175	225	3.6				
BT50-FMD50-155	7.9	TBC175 (TBR175 + BCC1348)	245	175	225	3.6				
BT50-FMD50-205	9.7	TBC175 (TBR175 + BCC1348)	295	175	225	3.6				
BT50-FMD50-255	13.4	TBC175 (TBR175 + BCC1348)	345	175	225	3.6				
BT50-FMD50-85	5.9	TBC220 (TBR220 + BCC1348)	175	220	270	4				
BT50-FMD50-155	7.9	TBC220 (TBR220 + BCC1348)	245	220	270	4				
BT50-FMD50-205	9.7	TBC220 (TBR220 + BCC1348)	295	220	270	4				
BT50-FMD50-255	13.4	TBC220 (TBR220 + BCC1348)	345	220	270	4				
BT50-FMD50-85	5.9	TBC265 (TBR265 + BCC1348)	175	265	315	4.2				
BT50-FMD50-155	7.9	TBC265 (TBR265 + BCC1348)	245	265	315	4.2				
BT50-FMD50-205	9.7	TBC265 (TBR265 + BCC1348)	295	265	315	4.2				
BT50-FMD50-255	13.4	TBC265 (TBR265 + BCC1348)	345	265	315	4.2				
BT50-FMD50-85	5.9	TBC310 (TBR310 + BCC1354)	175	310	390	5.2				
BT50-FMD50-155	7.9	TBC310 (TBR310 + BCC1354)	245	310	390	5.2				
BT50-FMD50-205	9.7	TBC310 (TBR310 + BCC1354)	295	310	390	5.2				
BT50-FMD50-255	13.4	TBC310 (TBR310 + BCC1354)	345	310	390	5.2				
BT50-FMD50-85	5.9	TBC385 (TBR385 + BCC1354)	175	385	465	5.5				
BT50-FMD50-155	7.9	TBC385 (TBR385 + BCC1354)	245	385	465	5.5				
BT50-FMD50-205	9.7	TBC385 (TBR385 + BCC1354)	295	385	465	5.5				
BT50-FMD50-255	13.4	TBC385 (TBR385 + BCC1354)	345	385	465	5.5				
BT50-FMD50-85	5.9	TBC460 (TBR460 + BCC1354)	175	460	540	12.5				
BT50-FMD50-155	7.9	TBC460 (TBR460 + BCC1354)	245	460	540	12.5				
BT50-FMD50-205	9.7	TBC460 (TBR460 + BCC1354)	295	460	540	12.5				
BT50-FMD50-255	13.4	TBC460 (TBR460 + BCC1354)	345	460	540	12.5				


<sup>◆</sup> Spare Part G81

<sup>•</sup> TBC Head set: Basic, Arbor: For separate purchase • Through coolant system is not available

# **TBC Head Set**

### Balance cut tool for rough boring





(mm)

Head se	et (Main compo	nent)	Boring range ØD				For separate purchase
Designation	Rail	Cartridge	Min	Max			Insert
TBC130S	TBR130	BCC1348	130	180	90	3.5	CCMT1204□□
TBC175S	TBR175	BCC1348	175	225	90	3.9	CCMT1204□□
TBC220S	TBR220	BCC1348	220	270	90	4.3	CCMT1204□□
TBC265S	TBR265	BCC1348	265	315	90	4.5	CCMT1204□□
TBC310S	TBR310	BCC1354	310	390	90	5.5	CCMT1204□□
TBC385S	TBR385	BCC1354	385	465	90	5.8	CCMT1204□□
TBC460S	TBR460	BCC1354	460	540	90	12.8	CCMT1204□□

<sup>\*</sup> If CNMG1204 $\square$  insert is used, BCN1348, BCN1354 cartridges can be ordered.

			Bas	sic			
Division	Rail	Cartridge	Clamp bolt	Clamp bolt	Hexagonal wrench	Clamp screw	Torx wrench
Parts Head set			1500			Allen	^
TBC130S	TBR130			BT0645	LW-3 LW-4	BFTX0511N	TRX20
TBC175S	TBR175	BCC1348					
TBC220S	TBR220	(BCN1348)					
TBC265S	TBR265		BX0820				
TBC310S	TBR310				LW-6		
TBC385S	TBR385	BCC1354 (BCN1354)		BT0660			
TBC460S	TBR460	(50111004)					



#### Balance cut tool for fine boring


# **FBC**

- Broad boring diameter and range
  - Wide Boring Range: Ø130~Ø540 mm
- Structurally stable enough to resist cutting load
  - Provides strong cutting performance based on the precision grinding dovetail method
- Can perform rough boring operation by changing boring head cartridges
  - Compatible boring head and rail as they are in the same structure
- Various cartridge tip angles
  - cartridge fore end angles 15° and 45° selectable



### Code system

### ● FBC boring tool structure & features




#### Boring range

Decimation	Dia	ı (Ø)	Head set	Incort		
Designation	Min	Max	nead set	Insert		
FBC130	130	180	FBC130S (TBR130 + FCC130 + FCB130)			
FBC175	175	225	FBC175S (TBR175 + FCC130 + FCB130)			
FBC220	220	270	FBC220S (TBR220 + FCC130 + FCB130)	FBB130-C09 (CCMT09T3□□, CCGT09T3□□		
FBC265	265	315	FBC265S (TBR265 + FCC130 + FCB130)	FBB130-C12 (CCMT1204□□)		
FBC310	310	390	FBC310S (TBR310 + FCC310 + FCB310)	FBB130-T11 (TPMT1103, TPGT1103L)		
FBC385	385	465	FBC385S (TBR385 + FCC310 + FCB310)			
FBC460	460	540	FBC460S (TBR460 + FCC310 + FCB310)			

# **BT-FBC**

#### Balance cut tool for fine boring





(mm)

		Rough	boring (TBC)			
FMC Arbor (Individual order)	O kg	TBC Head set		Boring ra	inge (ØD)	
(marviddar order)		(Rail + Cartridge + Balance block)	L	Min	Max	kg \
BT50-FMD50-85	5.9	FBC130S (TBR130 + FCC130 + FCB130)	182	130	180	3.7
BT50-FMD50-155	7.9	FBC130S (TBR130 + FCC130 + FCB130)	252	130	180	3.7
BT50-FMD50-205	9.7	FBC130S (TBR130 + FCC130 + FCB130)	302	130	180	3.7
BT50-FMD50-255	13.4	FBC130S (TBR130 + FCC130 + FCB130)	352	130	180	3.7
BT50-FMD50-85	5.9	FBC175S (TBR175 + FCC130 + FCB130)	182	175	225	4.1
BT50-FMD50-155	7.9	FBC175S (TBR175 + FCC130 + FCB130)	252	175	225	4.1
BT50-FMD50-205	9.7	FBC175S (TBR175 + FCC130 + FCB130)	302	175	225	4.1
BT50-FMD50-255	13.4	FBC175S (TBR175 + FCC130 + FCB130)	352	175	225	4.1
BT50-FMD50-85	5.9	FBC220S (TBR220 + FCC130 + FCB130)	182	220	270	4.5
BT50-FMD50-155	7.9	FBC220S (TBR220 + FCC130 + FCB130)	252	220	270	4.5
BT50-FMD50-205	9.7	FBC220S (TBR220 + FCC130 + FCB130)	302	220	270	4.5
BT50-FMD50-255	13.4	FBC220S (TBR220 + FCC130 + FCB130)	352	220	270	4.5
BT50-FMD50-85	5.9	FBC265S (TBR265 + FCC130 + FCB130)	182	265	315	4.7
BT50-FMD50-155	7.9	FBC265S (TBR265 + FCC130 + FCB130)	252	265	315	4.7
BT50-FMD50-205	9.7	FBC265S (TBR265 + FCC130 + FCB130)	302	265	315	4.7
BT50-FMD50-255	13.4	FBC265S (TBR265 + FCC130 + FCB130)	352	265	315	4.7
BT50-FMD50-85	5.9	FBC310S (TBR310 + FCC310 + FCB310)	182	310	390	5.5
BT50-FMD50-155	7.9	FBC310S (TBR310 + FCC310 + FCB310)	252	310	390	5.5
BT50-FMD50-205	9.7	FBC310S (TBR310 + FCC310 + FCB310)	302	310	390	5.5
BT50-FMD50-255	13.4	FBC310S (TBR310 + FCC310 + FCB310)	352	310	390	5.5
BT50-FMD50-85	5.9	FBC385S (TBR385 + FCC310 + FCB310)	182	385	465	5.8
BT50-FMD50-155	7.9	FBC385S (TBR385 + FCC310 + FCB310)	252	385	465	5.8
BT50-FMD50-205	9.7	FBC385S (TBR385 + FCC310 + FCB310)	302	385	465	5.8
BT50-FMD50-255	13.4	FBC385S (TBR385 + FCC310 + FCB310)	352	385	465	5.8
BT50-FMD50-85	5.9	FBC460S (TBR460 + FCC310 + FCB310)	182	460	540	12.8
BT50-FMD50-155	7.9	FBC460S (TBR460 + FCC310 + FCB310)	252	460	540	12.8
BT50-FMD50-205	9.7	FBC460S (TBR460 + FCC310 + FCB310)	302	460	540	12.8
BT50-FMD50-255	13.4	FBC460S (TBR460 + FCC310 + FCB310)	352	460	540	12.8

<sup>◆</sup> Spare Part G84


<sup>•</sup> TBC Head set: Basic, Arbor: For separate purchase • Through coolant system not available

G FBC

# **FBC Head Set**

#### Balance cut tool for fine boring





(mm)

Н	lead set (Main	component)		Boring range ØD			۵	For separate purchase
Designation	Rail	Cartridge	Balance block	Min	Max	_	\(\int \kg\\)	Bite
TBC130S	TBR130	FCC130	FCB130	130	180	97	3.8	
TBC175S	TBR175	FCC130	FCB130	175	225	97	4.1	
TBC220S	TBR220	FCC130	FCB130	220	270	97	4.5	FBB130-C09
TBC265S	TBR265	FCC130	FCB130	265	315	97	4.6	FBB130-C12
TBC310S	TBR310	FCC310	FCB310	310	390	97	5.5	FBB130-T11
TBC385S	TBR385	FCC310	FCB310	385	465	97	5.8	
TBC460S	TBR460	FCC310	FCB310	460	540	97	12.8	

#### Parts

	Basic						For separate purchase
Division	Rail	Cartridge	Balance block	Clamp bolt	Clamp bolt	Hexagonal wrench	Bite
Parts Head set		4			Sharen.		9
FBC130S	TBR130				BT0645		FBB130-C09
FBC175S	TBR175	FCC130	FCB130				
FBC220S	TBR220	FCC130	FCB130	DTF0010	D10045		
FBC265S	TBR265			BTF0810 BTF0814		LW-3 LW-4	FBB130-C12
FBC310S	TBR310			D11 0014			FBB130-T11
FBC385S	TBR385	FCC310	FCB310		BT0660		
FBC460S	TBR460						

# **FBB Bite**



D	Designation Insert					
FBB130 -	C09	CCMT09T3□□, CCGT09T3□□				
	C12	CCMT1204□□				
	T11	TPMT1103□□, TPGT1103□□				

### **Slim Angular Head**

# **BT-SAH**


- Angular head for narrow inside boring (min. inner diameter of workpiece: Ø40, min. boring width: 32 mm)
- MAX 3,500 RPM, Spindle: applied rotation ratio = 1:1.37
- Boring range: Ø3, Ø4, Ø6



## **○** Code system




### Details



### Machining Features







Min.32mm gap (except tool projection)

Designation	L	L1	L2	L3	L4	A	Q	G	ØB	Rotation ratio (IN:OUT)	Rotation direction	MAX RPM	
BT50-SAH6-277	277	298	183.5	166.5	93.5	80 (110)	31.5	40	76	1:1.37	CW:CW	3,500	14

### Clamping Force

Division	Measurement	Ме	asured v	value (N-	·m)
Clamp torque	2	2.5	3	3.5	4
Clamping Force	Not measurable	5.5	6.5	7	7

<sup>\*</sup> The moderate clamp torque of collet is 3.5N-m.

#### Exclusive collet

-	Designation	Clamping range
	SAH6-C3	3
	SAH6-C4	4
	SAH6-C6	6

#### How to clamp



- 1. Couple the tool with SAH dedicated collet
- 2. Insert the coupled tool into SAH and fix it with a dedicated tightening jig
- 3. Turn the bolt using a hexagonal wrench

# **G** Angular head

#### **ANGULAR HEAD**

# **ANGULAR HEAD**

- Doubled effect by one equipment/Available for various angles
- Lighter aluminum body




#### Code system




### Name of angular head parts







#### Various applications



#### Components



#### MAH

#### **Universal type MAH (Reinforced series)**


- · Reinforced type Better performance by improving existing universal Angular head
  - Stability on large mold machining
  - Use 32mm Ball Endmill



#### **KHU**

#### Universal type KHU (Free angle)

- · Adjustable angle-type angular head that enables flexible machining
  - Wide vertical (0°~90°) and horizontal (0°~360°) machining angle range
  - To use Tap-exclusive collet, please contact us in advance
  - HSK and SK types are customizable



Be sure to give a slope to the cutting edge of a ball end mill when machining it as the ball end mill edge is worn out and the surface roughness of the workpiece becomes defective

#### **HRAG**

#### Attachment type HRAG (Reinforced type)

- · HRAG: The reinforced bracket enhanced durability upto 200%
  - Stablility on face milling machining
  - Enhances compatibility with the machining device due to easy bracket disassembly/ assembly even on the BT50 shank
  - Improves product life cycle



#### **KAG**

### Attachment type KAG

- Free 360° angle adjusting from side to side
  - Possible to use various tools of BT40 and BT30
  - HSK and SK type are order made
  - Coolant types are to be ordered separately



#### **KAH**

#### Modular type KAH (90° type)


- Adjustable angle-type angular head that enables flexible machining
  - Adjusting angle up to 360°
  - To use Tap-exclusive Collet, please contact us in advance
  - HSK and SK type are order made



#### **KAC**

#### Modular type KAC (45° type)

- Fixed angle type angular head that enables flexible machining
  - Adjusting angle up to 360°
  - To use Tap-exclusive Collet, please contact us in advance
  - 45-degree fixed type angular head
  - For BT40 types, please contact us separately




Be sure to give a slope to the cutting edge of a ball end mill when machining it as the ball end mill edge is worn out and the surface roughness of the workpiece becomes defective




# **G** Angular Head


## MHA for mold (0°~90°)\_Reinforced type

# **BT-MAH**









Shank size	M	A1	ØD
BT50	56.5	20°	Ø40

NO	Name
1	Inclination angle gradation (Axial positioning in 0°~90°)
2	Rotating angle graduation (Free radius position in 360°)
3	Head
4	Positioning pin part
5	Jaw key
6	Positioning ring
7	Positioning pin cover
8	Positioning pin


NO	Part name	Designation
1	Inclination angle gradation screw	BT1216
2	Head fixed bolts	BT0645
3	Rotating angle graduation screw	BT0640
4	Positioning ring set screw	MSST5-12
6	Tilt Axies fixing bolt	BH0616
6	Positioning pin height control bolt	BT0516
7	Positioning pin set screw	BT0512
8	Body position block set screw	BX0516

=	<b>=</b>	
	M	
Ľ		
_	ľ	

Designation	ØD	L	L1	L2	L3	С	C1	G	C2	Q	Q1	В	B1	Р	Α	Max RPM	Install tool	\(\sum_{kg}\)
BT50-MAH32-200	32	200	47	78	325	136	95	154	95	125	63	31	60	95	80	3,000	SIDE LOCK	19.6

## KHU (0°~90°)\_Collet type

# **BT-KHU**









Shank size	М	M1	Α	ØD
BT40	Max: 32 Min: 26	10	20°	Ø19.6

NO	Name
1	Inclination angle gradation (Axial positioning in 0°~90°)
2	Rotating angle graduation (Free radius position in 360°)
3	Head
4	Positioning pin part
5	Jaw key
6	Height control wrench hole


NO	Part name	Designation
1	Tilt Axies fixing bolt	BH0630
2	Bracket angle fixing bolt	BX0630
3	Position block fixing bolt	BX0512
4	Set screw	BT0404
6	Fixing bolts	BX05630

Designation	ØD	ØD1	L	L1	L2	L3	В	B1	E	F	С	Α	G	Q	Q1	Torque rate (IN:OUT)	Direction of rotation (IN:OUT)	Max RPM	Collet	O kg
BT40-KHU10-160	1.0~10.0	58	247	160	33	54	22	28	51	98	96	65	90	87	40	1:2	CW:CW	6,000	GER16	8.3
BT50-KHU10-180	1.0~10.0	84	267	180	33	54	22	28	53	103	114	80	90	87	40	1:2	CW:CW	6,000	GER16	11.5
BT50-KHU20-195	1.0~20.0	84	315	195	47	73	29	50	53	132	114	80	124	120	63	1:1	CW:CW	3,000	GER32	17.9

# G Angular Head


## HRAG (90° fixed)\_Reinforced type

# **BT-HRAG**









Shank size	M	A1	ØD		
BT50	56.5	20°	Ø40		

NO	Name
1	Rotating angle graduation (Free radius position in 360°)
2	Head
3	Positioning pin part
4	Jaw key
(5)	Positioning ring
6	Positioning pin cover
7	Positioning pin

NO	Part name	Designation
1	Head fixed bolts	BX0660
2	Positioning ring set screw	MSST5-12
3	Rotating angle graduation screw	BT0648
4	Positioning pin height control bolt	BT0516
6	Positioning pin set screw	BT0512
6	Body position block set screw	BX0516
7	BT/NT Bolt	

Designation	L	L1	L2	L3	L4	Q	Q1	Α	G	G1	Max RPM	Tool shank	O kg
BT50-HRAG40-230	230	56.5	145	46.5	276.5	89	101	80	93	136	3000	BT/NT40	18.2

## KAG (90° fixed type)

# **BT-KAG**









Shank size	M	M1	A1	ØD
BT40	Max: 32 Min: 26	10	20°	Ø19.6
BT50	Max: 35 Min: 29	15	20°	Ø28

NO	Name
1	Rotating angle graduation (Free radius position in 360°)
2	Head
3	Positioning pin part
4	Jaw key
5	Height control wrench hole


NO	Part name	Designation
1	Set screw	BT0404
2	Fixing bolts	BX50630
3	BT / NT Bolt	

Designation	L	L1	L2	L3	L4	L5	Q	Q1	Α	С	G	Torque rate (IN:OUT)	Direction of rotation (IN:OUT)	MAX RPM	Holder shank	\(\sum_{\kg}\)
BT40-KAG30-195	195	44	86	65	37.5	232.5	66	70	65	96	75	1:1	CW:CW	4,000	BT30/NT30	6.4
BT50-KAG40-230	230	57	88	85	46.5	276.5	89	94	80	114	93	1:1	CW:CW	3,000	BT40/NT40	15.8

# G Angular Head


## HRAG (90° fixed)\_Collet type

# **BT-KAH**









Shank size	M	M1	<b>A</b> 1	ØD
BT40	Max: 32 Min: 26	10	20°	Ø19.6
BT50	Max: 35 Min: 29	15	20°	Ø28

NO	Name
1	Head
2	Rotating angle graduation (Free radius position in 360°)
3	Positioning pin part
4	Jaw key
5	Height control wrench hole

NO	Part name	Designation
1	Head fixing bolts	BX0618
2	Set screw	BT0404
3	Fixing bolts	BX50630

Designation	ØD	L	L1	L2	L3	L4	L5	В	Α	Р	Q	G	G1	Torque rate (IN:OUT)	Max RPM	Collet	kg
BT40-KAH7-170	1.0~7.0	190	20	44	71	55	20	19	65	37	24.5	40	96	1:1	5,000	GER11	4.6
BT40-KAH10-195	1.0~10.0	220	25	44	71	80	25	28	65	46	32	58	96	1:1	5,000	GER16	5.8
BT40-KAH13-165	1.0~13.0	193	28	44	71	50	28	35	65	53	35	60	96	1:1	5,000	GER20	5.7
BT40-KAH20-180	2.0~20.0	218	38	44	71	65	38	50	65	71	49	76	96	1:1	3,500	GER32	6.7
BT50-KAH07-220	1.0~7.0	240	20	57	54	109	20	19	80	37	24.5	40	96	1:1	5,000	GER11	9.8
BT50-KAH10-215	1.0~10.0	240	25	57	54	104	25	28	80	46	32	58	96	1:1	5,000	GER16	10.7
BT50-KAH10-260	1.0~10.0	285	25	57	54	149	25	28	80	46	32	58	96	1:1	5,000	GER16	11.0
BT50-KAH13-260	1.0~13.0	288	28	57	54	149	28	35	80	53	35	60	96	1:1	5,000	GER20	11.2
BT50-KAH20-200	2.0~20.0	238	38	57	54	89	38	50	80	71	49	76	96	1:1	3,500	GER32	11.6
BT50-KAH20-240	2.0~20.0	278	38	57	54	129	38	20	80	71	49	76	96	1:1	3,500	GER32	12.4

## KAC (45° fixed)\_Collet type

# **BT-KAC**









Shank size	M	M1	<b>A1</b>	ØD
BT40	Max: 32 Min: 26	10	20°	Ø19.6
BT50	Max: 35 Min: 29	15	20°	Ø28

NO	Name
1	Head
2	Rotating angle graduation (Free radius position in 360°)
3	Positioning pin part
4	Jaw key
(5)	Height control wrench hole

NO	Part name	Designation
1	Head fixing bolts	BX0618
2	Set screw	BT0404
3	Fixing bolts	BXS0630

Designation	ØD	L	L1	L2	L3	В	G	G1	Р	Q	Α	Max RPM	Collet	() √kg
BT50-KAC10-240	1.0~10.0	240	57	54	129	28	60	96	25	54	80	5,000	GER16	9.7
BT50-KAC13-240	1.0~13.0	240	57	54	129	28	60	96	25	54	80	5,000	GER20	10.7
BT50-KAC20-250	2.0~20.0	240	57	54	139	50	72	96	30	60	80	3,500	GER32	11.7



#### Zero fit collet

# **DZC**

#### Correcting 10 - 20 $\mu m$ runout generated at tool tip to 0-2 $\mu m$


- Improves the runout and straightness of end tools
- Improves the surface roughness and quality of the machining area
- Improves the accuracy of boring hole dimension
- Improves the tool life of end tools




### Code system




#### Features









(mm)

Designation	ØD	ØD <sub>1</sub>	L
Designation	95	551	
DZC20-6	20	6	56.5
DZC20-8	20	8	56.5
DZC20-10	20	10	56.5
DZC20-12	20	12	56.5
DZC20-14	20	14	56.5
DZC20-16	20	16	56.5
DZC32-6	32	6	67.5
DZC32-8	32	8	67.5
DZC32-10	32	10	67.5
DZC32-12	32	12	67.5
DZC32-16	32	16	67.5
DZC32-20	32	20	67.5
DZC32-25	32	25	67.5

### Jetcoolant collet (for milling chuck)

# **DCJ**


- Ensures a longer service life of cutting tools by preventing chips from adhering to tools
- Improveds chip breakability/breaking strong jet injection
- Maintains the performance of the conventional milling chuck
- Enables a fast change of the inside jet coolant by collet replacement
- Available an ultrahigh-pressure inside coolant



Designation	Ø6	Ø8	Ø10	Ø12	Ø16	Ø20	Ø25	Ø32
NPM20	•	•	•	•	•			
NPM32	•	•	•	•	•	•	•	
NPM42	•	•	•	•	•	•	•	•

<sup>·</sup> Can be used for an ultrahigh-pressure inside coolant

#### **○** NPM + Jet coolant Collet



Increased tool service life

### Easy assembly



Can be used by only combining a collet with the conventional chuck (NPM)

### Coolant type

Jet coolant



· Inside coolant



### Coolant type

	Designation
	DCJ20-6
DCJ20	DCJ20-8
	DCJ20-10
	DCJ20-12
	DCJ20-16
	DCJ32-6
	DCJ32-8
	DCJ32-10
DCJ32	DCJ32-12
	DCJ32-16
	DCJ32-20
	DCJ32-25

### Chip evacuation








#### Lock collet for milling chuck

## DCL


Milling chuck equipped with anti-fallout feature to prevent poor milling when machining a workpiece and improve tool service life (with DINE's milling chuck)

- Prevents the tool from falling out due to coolant pressure and vibration
- Useful for working with difficult-to-cut materials that require high workload
- Fit for difficult-to-cut materials with ultralight weight and high hardness in aerospace and automobile industries

#### Features




- Designed especially for extreme machining with a lot of mechanical actions, prevents the tool from deviating or falling out
- · Weldon flat (DINE 6535HB) end mill used



 Closely adhered to the grooves of the milling chuck - No slip occurring even under high torque

### Detailed Specifications



(mm)

Designation	ØD	ØD <sub>1</sub>	L	Designation	ØD	ØD <sub>1</sub>	L
DCL20-6	6	20	53	DCL32-10	10	32	64.5
DCL20-8	8	20	53	DCL32-12	12	32	64.5
DCL20-10	10	20	53	DCL32-14	14	32	64.5
DCL20-12	12	20	53	DCL32-16	16	32	64.5
DCL20-14	14	20	53	DCL32-18	18	32	64.5
DCL20-16	16	20	53	DCL32-20	20	32	64.5
DCL32-6	6	32	64.5	DCL32-25	25	32	64.5
DCL32-8	8	32	64.5				

	Basic			Basic	
Division	Key	C-Grip	Division	Key	C-Grip
Parts Designation			Parts Designation		0
DCL20-6	DCL20-6K	DCL-CG20	DCL32-10	DCL32-10K	DCL-CG32
DCL20-8	DCL20-8K	DCL-CG20	DCL32-12	DCL32-12K	DCL-CG32
DCL20-10	DCL20-10K	DCL-CG20	DCL32-14	DCL32-14K	DCL-CG32
DCL20-12	DCL20-12K	DCL-CG20	DCL32-16	DCL32-16K	DCL-CG32
DCL20-14	DCL20-14K	DCL-CG20	DCL32-18	DCL32-18K	DCL-CG32
DCL20-16	DCL20-16K	DCL-CG20	DCL32-20	DCL32-20K	DCL-CG32
DCL32-6	DCL32-6K	DCL-CG32	DCL32-25	DCL32-25K	DCL-CG32
DCL32-8	DCL32-8K	DCL-CG32			




#### **KORLOY Anti-Vibration tool**

# **KORLOY DAMPING PRO**

- The application of a special design provides an excellent Anti-Vibration effect and is optimized for Overhang work
- Capable to elevate Feed comparing to standard arbor with stable machining
- Longer tool life and noise decrease
- Provides a solution for Mold, Deep Cavity machining, and Heavy-duty work

#### Code system



#### Features



- Anti-Vibration: Exclusively designed Anti-Vibration structure
- · Material: Special alloy steel
- Anti-Vibration body: Application of high density damper
- Overhang: Capable for 2D~5D
- · Coolant: Inner coolant is capable








ype HSK type SK

Various types and sizes are applicable


#### Comparison of vibration damping time

# Standard Arbor



Longer Vibration damping time/ Chattering is caused while Overhang work

#### **KORLOY DAMPIG PRO**



Short Vibration damping time/
Performance is 2~3 times better than standard arbor

# G

## **Technical Information for DAMPING PRO**

#### Performance evaluation

• Cutting condition: fz (mm/t) = 0.1 vc (m/min) = 100

......

• Cutter: AMC4063HS 6flute

 Arbor: BT50-FMC22-210 General arbor KDP-BT50-FMC22-210 Damping pro





• Cutter: FMRC3063HRD-H 6flute

• Arbor: BT50-FMC22-210 General arbor

KDP-BT50-FMC22-210 Damping pro

vc (m/min) = 100





#### Application examples

Mold machining	Side milling cutter machining	Facing for long depth	Deep-hole Boring machining
	THE		
Better productivity than general arbor	Excellent performance in the deep grooving	Better productivity and surface roughness than general arbor	Better surface roughness and machinability than general arbor

#### Side milling cutter machining example

- Faulty occurrence on size and surface roughness by the vibration, when use the general arbor
- Using DAMPING PRO, good size and surface roughness

#### Big size Crankshaft machining example

- General arbor: ap = 2 mm
- KORLOY DAMPING PRO: ap = 4mm available
- 2 times better productivity



# ■ General arbor Cutting condition:

vc (m/min) = 50fz (mm/t) = 0.1ae (mm) = 20

#### **DAMPING PRO**

Cutting condition: vc (m/min) = 100 fz (mm/t) = 0.1 ae (mm) = 20



# ■ General arbor Cutting condition: vc (m/min) = 100


vc (m/min) = 100fz (mm/t) = 0.15ap (mm) = 2

#### ■ DAMPING PRO

Cutting condition: vc (m/min) = 100 fz (mm/t) = 0.15 ap (mm) = 4

# **BT-FMA**





(mm)

De	signation	Cutter dia.	ØD	L	L <sub>1</sub>	øс	ØC <sub>2</sub>	Н	W	К	G	ØC <sub>1</sub>	Hı	O kg	Fig.	α°
KDP-BT40 -	FMA25.4-210	80	25.4	210	183	50	60	22	9.5	5	M12	33	10	5.42	2	1
	FMA25.4-260	80	25.4	260	233	50	60	22	9.5	5	M12	33	10	6.5	2	1.1
	FMA31.75-210	100	31.75	210	183	60	-	30	12.7	7	M16	40	10	5.94	1	-
	FMA31.75-260	100	31.75	260	233	60	-	30	12.7	7	M16	40	10	7.25	1	-
KDP-BT50 -	FMA25.4-210	80	25.4	210	172	50	78	22	9.5	5	M12	33	10	9.63	2	4
	FMA25.4-260	80	25.4	260	222	50	78	22	9.5	5	M12	33	10	11.8	2	3
	FMA31.75-210	100	31.75	210	172	60	85	30	12.7	7	M16	40	10	11.8	2	3
	FMA31.7 -260	100	31.75	260	222	60	85	30	12.7	7	M16	40	10	13.6	2	2.5

• The A type is for JIS B4113 Face milling

	Basic												
Division	Key	Clamp bolt	Wrench bolt	Wrench bolt	Wrench								
Parts Designation		84	Spine.	GM.									
FMA25.4	K9.5 (B)	MBA-M12	BX0412	BX1225	LW-10								
FMA31.75	K12.7 (D)	MBA-M16	BX0515	-	LW-14								

<sup>•</sup>The B type and C type are arbors for T-MAX Face Milling and shoulder cutter

<sup>•</sup> The weight (kg) shown in the chart does not include the weight of face cutter


<sup>•</sup> Key and screw are clamped

<sup>·</sup> Wrench is separately sold

# G DAMPING PRO

# **BT-FMC**





(mm)

De	signation	Cutter dia.	ØD	L	L <sub>1</sub>	øс	ØC <sub>2</sub>	н	W	K	G		Fig.	α°
KDP-BT40 -	FMC16-160	40	16	160	133	38	-	17	8	5	M8	2.45	1	-
	FMC22-210	50/63	22	210	183	48	4.95	19	10	5.6	M10	4.37	2	0.1
	FMC22-260	50/63	22	260	233	48	60	19	10	5.6	M10	6.3	2	1.5
	FMC27-210	80	27	210	183	60	-	21	12	6.3	M12	6	1	-
	FMC27-260	80	27	260	233	60	-	21	12	6.3	M12	7.25	1	-
KDP-BT50 -	FMC16-171	40	16	171	133	38	-	17	8	5	M8	5.1	1	-
	FMC22-210	50/63	22	210	172	48	49.5	19	10	5.6	M10	7.3	2	0.1
	FMC22-260	50/63	22	260	222	48	62	19	10	5.6	M10	10	2	1
	FMC27-210	80	27	210	172	60	78	21	12	6.3	M12	10.6	2	2.5
	FMC27-260	80	27	260	222	60	78	21	12	6.3	M12	12.6	2	2
	FMC27-320	80	27	320	282	60	78	21	12	6.3	M12	14.8	2	1
	FMC32-210	100	32	210	172	78	-	24	14	7	M16	11.7	1	-
	FMC32-260	100	32	260	222	78	-	24	14	7	M16	14.2	1	-
	FMC32-330	100	32	330	292	78	-	24	14	7	M16	16.6	1	-

 $\bullet\,\mbox{The A}$  type is for JIS B4113 Face milling


	Basic											
Division	Key	Clamp bolt	Wrench bolt	Wrench bolt	Wrench							
Parts Designation		84	Special Control of the Control of th	G/A								
FMC16	K8.0 (A)	-	BX0310	BX0820	LW-6							
FMC22	K10.0 (C)	-	BX0412	BX1030	LW-8							
FMC27	K12.0	MBA-M12	BX0616	-	LW-10							
FMC32	K14.0	MBA-M16	BX0820	-	LW-14							

<sup>•</sup> The B type and C type are arbors for T-MAX Face Milling and shoulder cutter

 $<sup>\</sup>bullet\,\mbox{The weight}$  (kg) shown in the chart does not include the weight of face cutter

 $<sup>{\</sup>bf \cdot}$  Key and screw are clamped

Wrench is separately sold



Desig	nation	Cutter dia.	ØD	L	L <sub>1</sub>	ØС	ØC <sub>2</sub>	Н	W	K	G	ØC <sub>1</sub>	H <sub>1</sub>	O ∠kg \	Fig.	α°
KDP-HSK63 -	FMA25.4-210	80	25.4	210	184	50	53	22	9.5	5	M12	33	10	4.55	3	0.1
	FMA25.4-260	80	25.4	260	234	50	53	22	9.5	5	M12	33	10	5.6	3	0.1
	FMA31.75-210	100	31.75	210	184	60	-	30	12.7	7	M16	40	10	5.52	2	-
	FMA31.75-260	100	31.75	260	234	60	-	30	12.7	7	M16	40	10	6.9	2	-
KDP-HSK100 -	FMA25.4-210	80	25.4	210	181	50	78	22	9.5	5	M12	33	10	8.32	3	4
	FMA25.4-260	80	25.4	260	231	50	78	22	9.5	5	M12	33	10	10.5	3	3
	FMA31.75-210	100	31.75	210	181	60	85	30	12.7	7	M16	40	10	10.9	3	3
	FMA31.75-260	100	31.75	260	231	60	85	30	12.7	7	M16	40	10	12.8	3	2.5

 $\bullet\,\mbox{The A}$  type is for JIS B4113 Face milling

	Basic											
Division	Key	Clamp bolt	Wrench bolt	Wrench bolt	Wrench							
Parts Designation		8	Spine .	Can								
FMA25.4	K9.5 (B)	MBA-M12	BX0412	BX1230	LW-10							
FMA31.75	K12.7 (D)	MBA-M16	BX0515	-	LW-14							


 $<sup>\</sup>bullet\,\mbox{The B}$  type and C type are arbors for T-MAX Face Milling and shoulder cutter

 $<sup>\</sup>bullet \, \mbox{The weight (kg)}$  shown in the chart does not include the weight of face cutter

<sup>•</sup> Key and screw are clamped

<sup>•</sup> Wrench is separately sold

# G DAMPING PRO



														()
Desig	nation	Cutter dia.	ØD	L	L <sub>1</sub>	ØС	ØC <sub>2</sub>	н	W	K	G	\(\int_{\kg}\)	Fig.	α°
KDP-HSK63 -	FMC16-160	40	16	160	134	38	-	17	8	5	M8	2.10	1	-
	FMC22-210	50/63	22	210	184	48	4.95	19	10	5.6	M10	3.82	1	0.1
	FMC22-260	50/63	22	260	234	48	62	19	10	5.6	M10	6.14	3	1.6
	FMC27-210	80	27	210	184	60	-	21	12	6.3	M12	5.53	2	-
	FMC27-260	80	27	260	234	60	-	21	12	6.3	M12	6.83	2	-
	FMC16-160	40	16	160	131	38	-	17	8	5	M8	3.45	1	-
	FMC22-210	50/63	22	210	181	48	49.5	19	10	5.6	M10	4.60	3	0.1
	FMC22-260	50/63	22	260	231	48	62	19	10	5.6	M10	8.10	3	1
	FMC27-210	80	27	210	181	60	78	21	12	6.3	M12	8.44	3	2.5
	FMC27-260	80	27	260	231	60	78	21	12	6.3	M12	10.40	3	2
	FMC27-320	80	27	320	291	60	78	21	12	6.3	M12	13.60	3	1
	FMC32-210	100	32	210	181	78	-	24	14	7	M16	10.20	1	-
	FMC32-260	100	32	260	231	78	-	24	14	7	M16	13.00	1	-
	FMC32-330	100	32	330	301	78	-	24	14	7	M16	15.43	1	-

• The A type is for JIS B4113 Face milling

 $\bullet\,\mbox{The B}$  type and C type are arbors for T-MAX Face Milling and shoulder cutter

• The weight (kg) shown in the chart does not include the weight of face cutter


Key and screw are clampedWrench is separately sold


	Basic							
Division	Key	Clamp bolt	Wrench bolt	Wrench bolt	Wrench			
Parts Designation	9	Oh.	Spen	GM.				
FMC16	K8.0 (A)	-	BX0310	BX0820	LW-6			
FMC22	K10.0 (C)	-	BX0412	BX1030	LW-8			
FMC27	K12.0	MBA-M12	BX0616	-	LW-10			
FMC32	K14.0	MBA-M16	BX0820	-	LW-14			

(mm)










100

330

310.9



De	signation	Cutter dia.	ØD	L	L <sub>1</sub>	ØС	ØC <sub>2</sub>	Н	W	K	G	O kg	Fig.	α°
KDP-SK40 -	FMC22-210	50/63	22	210	183.0	48	49.5	19	10	4.4	M10	4.4	3	0.1
	FMC22-260	50/63	22	260	233.0	48	60	19	10	5.6	M10	6.2	2	1.4
	FMC27-210	80	27	210	183.0	60	60	21	12	6.3	M12	5.9	1	-
	FMC27-260	80	27	260	233.0	60	60	21	12	6.3	M12	7.2	1	-
KDP-SK50 -	FMC22-210	50/63	22	210	190.9	48	49.5	19	10	5.6	M10	6.4	3	0.1
	FMC22-260	50/63	22	260	240.9	48	62	19	10	5.6	M10	9.1	3	1
	FMC27-210	80	27	210	190.9	60	78	21	12	6.3	M12	9.8	3	2.5
	FMC27-260	80	27	260	240.9	60	78	21	12	6.3	M12	12.4	3	1.8
	FMC27-320	80	27	320	300.9	60	78	21	12	6.3	M12	14.5	3	1.2
	FMC32-210	100	32	210	190.9	78	-	24	14	7	M16	11.5	1	-
	FMC32-260	100	32	260	240.9	78	-	24	14	7	M16	14	1	-

78

24

14

• The A type is for JIS B4113 Face milling

16.4

M16

#### Parts

FMC32-330

		Basic			For separate purchase
Division	Key	Clamp bolt	Wrench bolt	Wrench bolt	Wrench
Parts Designation		B.	Spirit .	Cha	
FMC16	K8.0 (A)	-	BX0310	BX0820	LW-6
FMC22	K10.0 (C)	-	BX0412	BX1030	LW-8
FMC27	K12.0	MBA-M12	BX0616	-	LW-10
FMC32	K14.0	MBA-M16	BX0820	-	LW-14

 $<sup>\</sup>bullet\,\mbox{The B}$  type and C type are arbors for T-MAX Face Milling and shoulder cutter


<sup>•</sup> The weight (kg) shown in the chart does not include the weight of face cutter

Key and screw are clampedWrench is separately sold



# **Pull Stud Bolt**






(mm)

Designation	ØD	ØС	ØC <sub>1</sub>	ØC <sub>2</sub>	Lı	L	θ	G	ØН
P20T-1	8.5	12	6	8.5	17.5	31.5	15°	M8	
P30T-1	12.5	16.5	7	11	23	43	45°	M12	
P30T-1(Ø2.5)	12.5	16.5	7	11	23	43	45°	M12	Ø2.5
P30T-2	12.5	16.5	7	11	23	43	30°	M12	
P30T-2(Ø2.5)	12.5	16.5	7	11	23	43	30°	M12	Ø2.5
P40T-1	17	23	10	15	35	60	45°	M16	
P40T-1(3)	17	23	10	15	35	60	45°	M16	Ø3
P40T-2	17	23	10	15	35	60	30°	M16	
PS40-3F	17	23	10	15	35	60	0°	M16	
PS-G51	17	22	12.45	18.8	19.11	44.11	45°	M16	Ø7
DIN69872-A40	17	23	14	19	26	54	15°	M16	Ø7
DIN69872-B40	17	23	14	19	26	54	15°	M16	
JISB6339-A40(PS-806)	17	23	14	19	29	54	15°	M16	Ø7
JISB6339-B40(PS-805)	17	23	14	19	29	54	15°	M16	
P50T-1	25	38	17	23	45	85	45°	M24	
P50T-1(7)	25	38	17	23	45	85	45°	M24	Ø7
P50T-2	25	38	17	23	45	85	30°	M24	
PS50-1F	25	38	17	23	45	85	0°	M24	
PS50-1FH	25	38	17	23	45	85	0°	M24	Ø8
PS-G41	25	37	20.83	28.96	25.2	65.2	45°	M24	Ø10
DIN69872-A50	25	36	21	28	34	74	15°	M24	Ø11.5
P50T-1HS	25	38	17	23	45	85	45°	M24	Ø5.7

# HT





(mm)

Designation	ØD	ØC	L
HT-100	32	68	100

Good for setting the Tool length at CNC machine
 No inturferance between height Touch setter and Tool makes safe work
 Location Accuracy: ±0.003 mm

# **PARTS**



#### **Parts**

H02 Shim H03 Cartridge H03 Chip Breaker H03 Chip Cover H03 Clamp H04 Coolant Bolt H04 Wrench Bolt H04 Lever H05 Locator H05 Nut H05 Pin H05 Screw H06 Shim Pin H07 Spring H07 Wrench H07 Stop Ring H07 Washer H07 Stopper H07 Nozzle

# H Parts

# Shim

			Dir	nensions
Geometry	Designation	а	b III	c d angle
	SC32	8.5	3.18	4.9
	SC32N	8.5	3.18	4.88
	SC42	12.5	3.18	6.9
a b	SC42N	11.6	3.18	6.5
80°	SC53	15.7	4.76	7.9
	SC53N	14.6	4.76	8.11
<del>/((†))/</del> a  + +	SC63	18.85	4.76	10
	SC63N	17.8	4.76	9.6
ı	SC83	24.4	4.76	12.8
	SC84N	24.2	6.35	13
⊬ a b	SC42B	12.5	3.18	6.9
80°	d †			
80° b	SC42CC	12.5	3.18	3.5
a	d 🛊			
<b>a</b> b.	SC32D	9.27	3.18	6.48
80°	SC43D	12.45	4.76	7.34
	SC53D	15.62	4.76	9.65
# + # a   +   +	d SC63D	18.8	4.76	11.25
	SC84D	25.08	6.35	14.85
<del></del>				
<b>/</b> ■a b	SC42S	11.5	3.18	6.4
80°	SC32S	8.3	3.18	5.4
a	d↓			
<b>/</b> ←a b	SC63V	18.35	4.76	5.5
80° -	SC83V	25.3	4.76	6.55
	SC84V	25.3	6.35	6.35
### a   F-F	d SC32V	9.12	3.18	3.4
	SC42V	12.6	3.18	4.5
	SC44V	12.6	6.35	4.5
	SC54V	15.75	6.35	5.5
. a . b	SS32V	9.12	3.18	3.4
90°	SS42V	12.6	3.18	4.5
	SS54V	15.75	6.35	5.5
	d SS64V	18.9	6.35	5.5
	SD317	9.35	2.7	5.2
a	SD317	8.5	3.18	4.88
Xx 101	SD32N	12.5	3.18	6.9
	SD42 SD42N	11.6	3.18	6.5
	SD42N SD43N	11.6	4.75	6.5
∕ a b	SD32D	9.2	3.18	5.8
/ \ \ \	SD43D	12.45	4.76	7.34
55°	d↓			
/\ a b	SD32S	8.5	3.18	5.4
a 55°	SD42S	11.5	3.18	6.4
<u> </u>	00001	0.10	0.40	0.4
a b	SD32V SD43V	9.12	3.18 4.76	3.4 4.5
555°	SD43V	12.6	6.35	4.5
a	d			

Geometry	Designation	а	Dii b	mensio	ns d	anala
► 80° . C.	SES33C	9.1	12	<b>c</b> 4.76	3.5	angle
a d	3E333C	3.1	12	4.70	0.0	
/ ьс.	SK33C	9.33	14.7	4.8	3.5	
55°	SK33CL	9.33	14.7	4.8	3.5	
b	SR10	8.4	3.18		4.7	
<del>-   -   -   -   -   -   -   -   -   -  </del>	SR12	10	3.18		4.7	
	SR16	13.55	4.76		6.9	
((+)) a + + d	SR20	17.1	4.85		7.9	
	SR25 SR32	22 27.8	6.35		9.6	
	SR42CC	12.575	3.18		3.5	
a	5114200	12.070	00			
b	SR10S	8.8	3.18		5.4	
	SR12S	10.55	3.18		5.4	
a						
	SS32	8.5	3.18		4.9	
	SS32N	8.5	3.18		4.88	
a b	SS42	12.5	3.18		6.9	
90°	SS42B SS42N	12.5 11.6	3.18		6.9	
	SS42N SS53	15.7	4.76		7.9	
	SS53N	14.6	4.76		8.11	
	SS63	18.85	4.76		10	
·	SS63N	17.8	4.76		9.6	
	SS84	24.4	6.35		12.8	
	SS84N	24.2	6.35		13	
a b	SS42CC	12.5	3.18		3.5	
a	SS32CC	9.3	3.18		3.5	
a 1 000 b	SS32D	9.27	3.18		5.77	
90°	SS43D	12.45	4.76		7.34	
a	SS53D SS63D	15.62 18.8	4.76 4.76		9.65	
	SS84D	25.15	6.35		14.43	
	55045	23.10	5.55		. 1. 10	
a b	SS32S	8.3	3.18		5.4	
	SS42S	11.5	3.18		6.4	
a						
a b	SS42SAF	11.2	3		5.5	
a						
60°, b	ST317	9.35	2.7		5	
	ST317B	9.35	2.7		5	
	ST317N	8.5	2.7		4.88	
a Hd	ST42N	12.5	3.18		6.9	
	ST42N ST53	11.6 15.7	4.76		7.9	
	3133	10.7	7.70		1.0	

## Shim

			Dimensions			
Geomet	ry	Designation	а	b	c d	angle
60°	b	ST32CC	9.35	3.18	3.5	49.0
		0.0200				
A						
(+) a	M al					
	<u> </u>					
.60°	_ b	ST32C1	9.13	3.18	4.95	
		ST42C1	12.3	3.18	4.95	
4 a	H-H d .					
60°	<u>► </u> b	ST32D	9.35	3.18	5.77	
$\wedge$		ST43D	12.52	4.76	7.34	
	<b>├</b> ┤	ST53D	15.7	4.76	9.65	
(+)\ a	+   <del> </del>   d	ST63D	18.87	4.76	11.25	)
				2.12		
60°	- b	ST32M	8.7	3.18	4.7	
Å		ST43M	12.5	4.76	6.3	
	$H_{-}$					
a	+ <u>+</u> + d ‡					
	h	ST32S	8.5	3.18	5.4	
60°	- b	31323	0.5	0.10	J. <del>T</del>	
$\wedge$						
	h—,					
a a	+++ d I					
60°	h	ST32V	9.12	3.18	3.4	
~ <del>~</del>	-  b	ST44V	12.6	6.35	4.5	
		01440	12.0	0.00		
		SV32D	9.2	3.18	5.8	
\	35°	SV43D	12.29	4.76	7.34	
	₹ <del>П</del>					
	¹↓ <u>†</u> ‡‡°•					
<b>∕</b> a	b	SV32D2	9.2	3.18	5.8	
	35°	SV32S	8.4	3.18	5.4	
(+) a	TT d					
	_ 🗷 🕂					
		01404=	0.07	c 7		
80°	<u>▶</u>   b	SW317	9.35	2.7	5	
$\times$		SW317N	8.5 12.5	2.7	4.88	
		SW42		3.18	6.9	
*!	<u> </u>	SW42N	11.6	3.18	6.5	
		SW32D	9.25	3.18	5.8	
80°	<u>-</u> b	SW43D	12.45	4.76	7.34	
		SW53D	15.62	4.76	9.65	
a a	- d	SW63D	18.8	4.76	11.25	
		SW84D	24.89	6.35	14.43	
80°	. b .	SW43M	12.5	4.76	6.2	
$\stackrel{\sim}{\triangleright}$	-	SW32M	8.52	3.18	5.2	
a a	T-I-d					
	<u> </u>					
、80°,	b	SW32V	9.12	3.18	3.4	
*		SW44V	12.6	6.35	4.5	
	_ \	SW54V	15.75	4.76	5.5	
( + ) a	H d					

## Cartridge

Geometry	Designation	Dimensions					
acometry		а	b	С	d	angle	
	LAPDR-AJ	M4×0.7	30	15	10		
b d c							

## Chip breaker

Geometry		Designation	Dimensions					
			а	b	С	d	angle	
a I <del>⊲ ►</del> I	b d	CB20	8.5	3.4	20			
c								

## • Chip cover

Geo	Geometry		Dimensions						
Geo			а	b	С	d	angle		
∳ p		CFMP3R14R1-A	10.5	20	1	(Ø4.3)			
□ <del>  ( )</del>	CFMP3R-A	8	18	1	(Ø4.3)				
*		CFMP4R-A	8	22	1	(Ø4.3)			

## Clamp

- Gramp						
Geometry	Designation			mensio		
domeny	Designation	а	b	С	d	angle
a b	CA05R	8.9	5.5	17.6	3.3	
	CA06R	12	7.2	20.6	5.3	
	CH5R3	7.85	7.2	14.8	3.1	
	CH6R4	12.02	9	23.97	3.75	
a b	CBH4.5R1	8	5.74	17.7	4	
	CBH4.5R2	9.5	6.4	18	4	
	CBH5R1	10	7.8	21.3	5	
	CBH6R1	12	9.3	26	6	
a b	CDH6N	9.5	10	18.6	6.1	
	CDH7N	7.9	11.4	14.7	4.7	
<del>(())</del>	CDH8N	10.9	16.9	22.4	6.1	
	CDH8N1	10.9	16.9	19.1	6.1	
a. V	CDH8N2	10.9	16.9	25.4	6.1	
<u>□</u>   ■	CDH8N3	12.5	19.8	25.4	9.2	
	ODCON	10.8	17	22.2	5	
a b	CDS8N	10.8	17	22.2	5	
	CGH5R1	19.5	9.5	28.8	2.5	
d-H-	CGH5R2	20.5	9.5	28.8	3.5	
	CGH5R3	22.5	9.5	28.8	5.5	

# H Parts

## Clamp

				Di	mensio	ns	
Geometry	<i>y</i>	Designation	а	b	С	d	angle
d		CGH6R1	22.3	11.9	23.2	2.5	
. 1	$\wedge$	CGH6R2	23.2	11.9	23.2	3.4	
	6-:-	CGH6R3	24.0	11.9	23.2	4.2	
+ (4)+	+++						
a	b						
a -	b	CHH3.5R1	7.5	6.7	13	2.45	
		CHH4.5R1	7.9	7.85	14.1	2.54	
	<u> </u>	CHH5.5R1	9.8	10	16.4	4	
d	J						
a	. b .	CH4R1	7.4	5	14.1	3.1	
		CH5R1	10.0	6.6	20.2	4.5	
	<b>17</b> 1						
d T							
a P	<del></del>	CH5R2	6.85	7	13.8	2	
	77	CH6R2	8.85	8.7	16.5	2	
	7-7-3	CH6R3	11.8	10	23	4.2	
\ /							
d T	VI.						
a		CMH5R1	18.5	7.9	16	6.26	
	T	CMH6R2	20.0	11	17.5	13.8	
		CMH6R6	18.5	7.9	16	6.26	
		CMH6R1	24	8.5	16.5	8.28	
	b						
<del>     </del>	<del> </del>						
		CMH6R3	20.0	11	17.51		
		CMH6L3	20.0	11	17.51		
a	p						
<del>&lt;                                    </del>	<del></del>						
a	d	CS5R1	6.8	7	14.5	2	
TA I		CS6R1	8.8	8.5	18.1	2.7	
<del>( ( ) )</del>		CS8R1	11.8	10	23	4.2	
d -     -	3						
d		CTH6L1	23.5	12	25.4	14.35	
	G.	CTH6R1	23.5	12	25.4	14.35	
		CTH6R2	21.78	12.9	31.22	17.33	
a b	<del>-   </del>						
b	, c , d ,	CVH3	21	11	5.8	7.7	
		CVH3V	29	14	7	8	
<del>                                      </del>		CVH4	25.5	14.5	6	7	
\		CVH5	30	17	7.5	9.5	
	$\Delta$	CVH6	33.5	18.5	8	10	
	h	CXH8N	10.1	10.0	17.5		
a -	<u> </u>	CVUQIA	10.1	10.0	17.5	-	
	Ш						

## ● Coolant bolt

Geometry	Designation		[	Dimen	sions		
Geometry	Designation	а	b	С	d	B(T)	á
B (a')	CBA063-3IN/MM	M10	Ø25	Ø16	37	8	(27)
a a	CBA063-4IN/MM	M10	Ø25	Ø16	42.5	8	(27)
	CBA080-IN/MM	M12	Ø28	Ø18	45.5	10	(32)
1	CBP063-IN/MM	M10	Ø22	Ø16	38.6	8	(27)
d d	CBP080-IN/MM	M12	Ø25	Ø18	48.6	10	(32)

### Coolant bolt

Geometry	Designation		- 1	Dimer	sions	3	
deometry	Designation	а	b	С	d	B(T)	á
	CBA100-IN/MM	M16	Ø54	Ø43	47	14	(32)
	CBA100-IN-25.4	M12	Ø44	Ø36	41.5	10	(25)
	CBA125-IN	M20	Ø65	Ø54	56	17	(38)
	CBA125-IN-25.4	M12	Ø44	Ø36	43.5	10	(25)
B (a')	CBA125-MM	M20	Ø65	Ø54	57	17	(35)
	CBA160-IN	M24	Ø83	Ø73	56	19	(38)
/	CBA160-MM	M20	Ø83	Ø73	53	17	(34)
	CBP100-IN	M16	Ø50	Ø43	48.6	14	(32)
	CBP100-IN-25.4	M12	Ø44	Ø36	46.5	10	(25)
~ ~	CBP100-MM-1	M16	Ø50	Ø43	48.6	14	(36)
	CBP125-IN	M20	Ø65	Ø54	56	17	(38)
	CBP125-IN-25.4	M12	Ø44	Ø36	55	10	(25)
	CBP125-MM	M20	Ø65	Ø54	57	17	(35)
	CBP125-MM-1	M20	Ø61	Ø54	65.6	14	(33)
	CBP160-IN	M24	Ø83	Ø73	56	19	(38)
	CBP160-MM	M20	Ø83	Ø73	53	17	(34)

### Wrench bolt

Geometry	Designation			Dimens	ions	
Geometry	Designation	Α	С	K	L	M
	SB0825	13	6	8	25	M08 × 1.25
	SB1025	16	8	10	25	M10 × 1.50
	SB1035	16	8	10	35	M10 × 1.50
(()) A] (()	SB1230	18	10	12	30	M12 × 1.75
K	SB1630	24	14	16	30	M16 × 2.0
C	SB1645	24	14	16	45	M6 × 2.0
	SB2040	30	17	20	40	M20 × 2.5
	CB1025	13	6	8	25	M08×1.25
	CB1025	16	8	10	25	M10×1.50
	CB1035	16	8	10	35	M10×1.50
	CB1230	18	10	12	30	M12×1.75
	CB1245	18	10	12	45	M12×1.75
K	CB1630	24	14	16	30	M16×2.0
С	CB1645	24	14	16	45	M16×2.0
	CB2040	30	17	20	40	M20×2.5

## Lever

G	o motru	De el mention		Dii	mensio	ns
G	eometry	Designation	а	b	С	d
a		LR10	3.4	10.8	11.7	3
		LR12	3.7	13.5	13.4	3.5
/ \ b	. / \	LR16	4.75	18.7	18.3	4.3
	d To	LR20	5.9	20.5	18.7	5.55
	C	LR25	7.35	24.25	23.7	6.2
	<del>-</del> -	LR32	8.45	29.7	26.95	7.9
a		LV2	2.6	7.75	6	2.1
		LV3B	3.1	10	9.5	3.7
ь	} [	LV4B	4.7	14.55	15.6	4.7
	d I	LV4BN	4.7	16	14.9	4.68
	C					
		LV3	3.7	10	12	3.6
		LV3N	3.75	10	12	3.55
		LV3AN	3.75	12.1	11.4	4.64
		LV3C	3.1	10	7.85	3.6
a   <del>**</del>		LV3CN	3.2	10	7.8	3.6
H		LV3DN	3.2	11.65	9.5	3.55
Н Ы	<i>J</i> \	LV4	4.7	14.55	14	4.7
	d to the same of t	LV4N	4.7	13.45	13.2	4.68
<del></del>	С	LV5	6	17.1	17	6
		LV5N	6	16.4	17.08	5.95
		LV5AN	6	18.82	17.3	5.95
		LV6N	7.5	20.5	21	7.6
		LV8N	8.6	25.5	25.4	8.6

### Lever

Geometry	Designation		Dii	mensio	ns
Geometry	Designation	а	b	С	d
a I <del>a</del>	LV4A	4.6	13.24	9.95	4.7
b d c	LV4AN	4.7	13.3	10	4.68

## Locator

G	eometry	Decimation		Di	mensio	ns	
- Ci	content y	Designation	а	b	С	d	
d	<u>a</u>	LFMP3R-A	M3.5	18.7	10.1	4.6	
		LFMP4R1-A	M4.5	24.3	13.8	6.2	
		LFMP4R-A	M4.5	26.3	13.8	6.2	
c -							
, d	a	LFMA3R-A	МЗ	18.5	9.5	4.8	
		LFMA4R-A	M3.5	26	13.1	7.3	
c	b						

## Nut

G	eometry	Daalamatian		D	imens	ions		
G	conieti y	Designation	а	b	С	d	B(T)	á
	-	N0407	M4 X 0.7	7.5	6	7	3	
В	d a a	N0508	M5 X 0.8	8.3	6.6	7	3	

## Pin

Geometry	Designation		Di	mensions	
deometry	Designation	а	b	С	
	PN0308	3.0	8		
	PN0310	3.0	10		
b	PN0312	3.0	12		
<del></del>	PN0314	0308 3.0 8 0310 3.0 10 0312 3.0 12 0314 3.0 14			
	PN0515	4.8	3.3	14.5	
a c					

### Screw

Geometry	Designation		Dir	nensi	ions		
deometry	Designation	а	b	С	d	02 02.5 6 4.0 6 4.0 5 5.0 5 5 7 2.5 8 2.5 7 3 3 4 4 4 2.5 6 3	á
<u>a</u>	AZ0508F	M5 X 0.5	13	8	9	Ø2	
	AZ0514	M5 X 0.8	14	7	9	Ø2.5	
B							
	BHA0510	M5 X 0.8	15	10	8.5	4.0	
	BHA0512	M5 X 0.8	17	12	8.5	4.0	
	BHA0612	M6 X 1.0	18	12	10	5.0	
В	BHA0614	M6 X 1.0	20	14	10	5.0	
b	BHA0616	M6 X 1.0	22	16	10	5	
	BHA0619-NYLOK	M6 X 1.0	25	19	10	5	
<b>* T</b>	CHX0407	M4 X 0.7	9.5	7.36	5.7	2.5	
	CHX0415	M4 X 0.7	17.5	15	5.4	2.5	
B	CHX0510	M5 X 0.8	13.1	10.1	7.7	3	
b _	CHX0518	M5 X 0.8	21.5	18	8	3	
	CHX0622	M6 X 1.0	26.5	22	10	4	
	CHX0513	M5 X 0.8	13	8	6.4	2.5	
	CHX0616	M6 x 1.0	16.2	10.1	8.5	3	
В с	CHX0617L	M6 x 1.0(인나사)	17.2	10.1	8.5	3	
b	CHX0621	M6 X 1.0	21	10.1	8.5	3	

### Screw

	I						
Geometry	Designation			mens			
,	200.9	а	b	С	d	B(T)	á
	CHX0625	1/4-20UNC	24.8	11	10	4	
<u> </u>	CTX03510	M3.5 X 0.6	10	4.7	5.3	15	
	CTX04513	M4.5 X 0.75	13.1	6.9	6.8	20	
	CTX04513H	M4.5 X 0.75	13.1	7.2	6.8	20	
B c b	CTX0515	M5 X 0.8	15	8	7	20	
-	CTX0517	M5 X 0.8	17.5	10	7	20	
	CTX0621	M6 X 1.0	21.2	12.4	9	25	
	DHA0514	M5 X 0.8	14.0	5.0	7.0	2.5	
		M6 x 1.0	17.0	7.0	7.5	3.0	
	DHA0617					3.0	
	DHA0620	M6 x 1.0	20.0	8.0	8.0		
	DHA0624	M6 x 1.0	24.0	12.0	8.5	3.0	
M	DHA0815	M8 X 1.25	15.5			4.0	
B c b d	DHA0818F	M8 X 1.0	18	8.5	5.5	4.0	
-	DHA0820	M8 X 1.25	20.0	8.0	9.0	4.0	
	DHA0821F	M8 X 1.0	21.0	8.5	8.5	4.0	
	DHA0825	M8 X 1.25	25.0	10.0	9.0	4.0	
	DHA0830	M8 X 1.25	30.0	11.5	11.5	4.0	
	ETGA0520CBM	M5 X 0.8	20		6.5	20	43°
	ETGD0825	M8 X 1.25	25.2		11.1	40	40°
	ETKA0523	M5 X 0.8	23		7.6	20	43°
	ETKA0625	M6 X 1.0	25.5		8.8	20	43°
	ETKD0516	M5 X 0.8	16.4		6.8	20	40°
		M6 X 1.0	20		8.3	25	40°
	ETKD0620					7	43°
	ETNA02506	M2.5 X 0.45			3.4		
	ETNA0408	M4 X 0.7	8.0		5.1	15	43°
	ETNA0412	M4 X 0.7	12		5.1	15	43°
	ETNA0511	M5 X 0.8	11.0		6.4	20	43°
	ETND02506F	M2.5 X 0.35			3.1	7	40°
	ETND0307F	M3 X 0.35	7.8		3.7	8	40°
	ETND03509	M3.5 X 0.6	9.6		4.7	10	40°
	FTGA03507	M3.5 X 0.6	7.0		5.3	15	60°
	FTGA03508	M3.5 X 0.6	8.0		5.3	15	60°
	FTGA03510	M3.5 X 0.6	10.0		5.3	15	60°
	FTGA03512	M3.5 X 0.6	12.0		5.0	15	60°
	FTGA0411F	M4 X 0.5	11.0		7.0	15	60°
	FTGA0417CBM	M4 X 0.7	17.0		5.5	15	62°
	FTGA0510-P	M5 X 0.8	10.0		7.0	20	63°
	FTGA0512-P	M5 X 0.8	12.0		7.0	20	63°
	FTGA0513	M5 X 0.8	13.2		7.0	20	61°
	FTGA0513-P	M5 X 0.8	13.0		7.0	20	63°
λ	FTGA0517	M5 X 0.8	17.0		7.5	20	61°
	FTGA0621	M6 X 1.0	21.5		9.0	20	61°
a' d	FTGA0826	M8 X 1.25	26.0		11.6	25	61°
	FTKA02206	M2.2 X 0.45			3.0	6	60°
<u></u>	FTKA02206S				3.05	7	60°
	FTKA02555	M2.5 X 0.45			3.5	7	60°
	FTKA02565	M2.5 X 0.45			3.5	7	60°
	FTKA02565S	M2.5 X 0.45			3.8	8	60°
	FTKA023033	M3 X 0.5	7.2		4.2	9	60°
	FTKA0357	M3.5 X 0.6	8.4		5.5	15	60°
	FTKA03510	M3.5 X 0.6	10.4		5.5	15	60°
					5.2	15	
	FTKA03511A	M3.5 X 0.6 M4 X 0.7	11.0 8.4		5.5	15	60°
	FTKA0408					15	
	FTKA0410	M4 X 0.7	10.0		5.5		60°
	FTKA0411K	M4 X 0.7	11.0		6.8	15	60°
	FTKA0412B	M4 X 0.7	12.5		5.5	15	60°
	FTKA0413	M4 X 0.7	13.0		5.5	15	60°
	FTNA01633	M1.6 X 0.35	3.3		2.6	6	60°
	FTNA0203	M2 X 0.4	3.0		2.7	6	60°
	FTNA02033	M2 X 0.4	3.3		2.7	6	60°
	FTNA0204	M2 X 0.4	4.3		2.7	6	60°
	FTNA02205	M2.2 X 0.45			3.0	6	60°
	FTNA0238	M2 X 0.4	3.8		3.0	6	60°
	FTNA0305	M3 X 0.5	5.2		4.2	9	60°
	FTNA0306	M3 X 0.5	6.2		4.2	9	60°
	FTNA0307	M3 X 0.5	7.2		4.2	9	60°
	FTNA0408	M4 X 0.7	8.5		5.5	15	60°
	FTNA0411	M4 X 0.7	11.0		5.5	15	60°
	FTNA0511	M5 X 0.8	11		7.0	20	63°
	FTNA0513	M5 X 0.8	13.0		7.0	20	60°
	FTNA0516	M5 X 0.8	16.0		7.0	20	60°
						P	arte

# H Parts

### Screw

	Dimensions								
Geometry	Designation	а				B(T)	á		
,	FTNB0411	M4 X 0.7	10.8	U		_ ,	<b>a</b> 60°		
	FTNC04509	M4.5 X 0.75	9.5		6.8		55°		
	FTNC04511	M4.5 X 0.75	11.5		6.8	20	55°		
a' d a									
<u>T</u> b									
	FTNB0209	2 X 0.4	9	2.5	2.7		60°		
	FTNB0209-P	2 X 0.4	9	2.5	2.7		60°		
	FTNB02512	2.5 X 0.45	12	3.5	3.5		60°		
	FTNB02512-P	2.5 X 0.45	12	3.5	3.5		60°		
	FTNB02514	2.5 X 0.45	14				60°		
a d a	FTNB02514-P						60°		
	FTNB0316	3 X 0.5					60°		
b	FTNB0316-P FTNB0319	3 X 0.5 3 X 0.5					60°		
	FTNB0319	3.5 X 0.6					60°		
	FTNB03524	3.5 X 0.6					60°		
	FTNB0426	4 X 0.7					60°		
	FTNB0528	5 X 0.8	28	6.5	7		60°		
	KHA0508	M5 X 0.8	8			2.5			
	KHA0510	M5 X 0.8	10			2.5			
	KHA0610	M6 X 1.0	10			3			
(d) a l	KHA0612	M6 X 1.0	12			3.0			
В	KHA0812	M8 X 1.25	12			4.0			
<u>→  □                                   </u>	KHA0815	M8 X 1.25							
	KHA1015 KHA1020	M10 X 1.5 M10 X 1.5		0.8         5.7         15         60         9.5         6.8         20         5.5           9.5         6.8         20         5.5         5.5         6.8         20         5.5           1.5         6.8         20         5.5         5.5         5.5         5.5         5.5         5.1         5.2         5.2         5.2         6.8         20         5.5         6.9         9.2         5.2         5.2         6.9         9.2         5.2         5.3         5.5         6.6         6.1         1.2         3.5         3.5         6.6         6.1         4.2         6.6         6.4         5.4         2.6         6.1         6.4         5.4         2.6         6.6         6.7         5.5         6.6         6.6         6.7         5.5         6.6         6.6         6.7         5.5         6.6         6.2         6.5         5.6         6.6         6.7         5.5         6.6         6.6         6.7         5.5         6.6         6.2         6.5         7.6         6.8         2.5         10         3.0         12         4.0         10         1.0         1.0         1.0         1.0         1.0         1.0					
	KHB0417	M10 X 1.5	17.2	4.5	25				
в а	KHB0406	M4 X 0.7							
	111120100								
<u> </u>									
b									
	1/1100540	145 1/ 0.0							
	KHC0510	M5 X 0.8					90°		
	KHC0610	M6 X 1.0					90°		
	KHC0812 KHC1016	M8 X 1.25 M10 X 1.5					90°		
B	KHC1020	M10 X 1.5					90°		
<del> </del>	101020	WITO X 1.5		10.0		0.0	- 50		
	KHD0510	M5 X 0.8	10	9	3	2.5			
	KHD0610	M6 X 1.0	10		4				
a d	KHD0810	M8 X 1.25	10	10	7.5	4			
В с									
b									
	LTX0512	M5 X 0.8	15.1	12	7.3	20			
d al	LTX0514	M5 X 0.8	17.1	14	7.3	20			
d a									
/T									
b									
	MHA0512	M5 X 0.8	17.0	10.8	8.0	4.0			
	MHB0310	M3 X 0.5	13.4						
	MHB0410	M4 X 0.7	14.0						
В С	MHB1055	M10 X 1.5	65						
<del>→                                     </del>	MHB1260	M12 X 1.75	72			d         B(T)           5.7         15           6.8         20           6.8         20           6.8         20           2.7            2.7            3.5            3.5            4.2            4.5            5.5            5.5            5.5            3.0         4.0           4.0         5.0           5.0         5.0           2.5         2           3.0         4.0           4.0         5.0           5.0         5.0           2.5         2           3.0         4.0           4.0         5.0           5.0         5.0           5.0         5.0           5.0         5.0           5.0         5.0           6.0         6.0           8.0         4.0           8.0         4.0           8.0         4.0           8.0         4.0           8.0 <t< td=""><td></td></t<>			
b b						d         B(T)           5.7         15           6.8         20           6.8         20           2.7         3.5           3.5         3.5           3.5         4.2           4.2         4.5           5.5         5.5           5.5         5.0           5.0         5.0           5.0         5.0           5.0         5.0           5.0         5.0           5.0         5.0           5.0         5.0           7.3         2           3         2.5           4         3           7.3         20           8.0         4.0           5.5         2.5           7.3         20           8.0         4.0           5.5         2.5           7.3         20           8.0         4.0           5.5         2.5           7.3         20           8.0         4.0           5.5         2.5           7.3         20           8.0         4.0           5.5         15 <td></td>			
<del>→                                     </del>	MHB1680	M16 X 2.0	96						
b	MHB1680 MHX0523	M16 X 2.0 M5 X 0.8	96 23.5	9.7	10	2.5			
<del>→                                     </del>	MHB1680 MHX0523 MHX0626	M16 X 2.0 M5 X 0.8 M6 X 1.0	96 23.5 25.8	9.7 10	10 11	2.5			
	MHB1680 MHX0523	M16 X 2.0 M5 X 0.8	96 23.5	9.7 10	10 11	2.5			
d a	MHB1680 MHX0523 MHX0626	M16 X 2.0 M5 X 0.8 M6 X 1.0	96 23.5 25.8	9.7 10	10 11	2.5			
b a	MHB1680 MHX0523 MHX0626	M16 X 2.0 M5 X 0.8 M6 X 1.0	96 23.5 25.8 30	9.7 10 12.5	10 11 10.5	2.5 3 4	92°		
	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0	96 23.5 25.8 30 8 10	9.7 10 12.5	10 11 10.5	2.5 3 4			
	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510 PTKA0407	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7	96 23.5 25.8 30 8 10 7	9.7 10 12.5 5 5 4.6	10 11 10.5 3.8 5 5.5	2.5 3 4 8 15	92°		
	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510 PTKA0407 PTKA0407	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5	96 23.5 25.8 30 8 10 7 7.3	9.7 10 12.5 5 5 4.6 3.8	10 11 10.5 3.8 5 5.5 6.5	2.5 3 4 8 15 15	92° 86° 91°		
	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510 PTKA0407 PTKA0407F PTKA0408	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.7	96 23.5 25.8 30 8 10 7 7.3 8	9.7 10 12.5 5 5 4.6 3.8 5.6	10 11 10.5 3.8 5 5.5 6.5 5.5	2.5 3 4 8 15 15 15	92° 86° 91° 86°		
	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.7	96 23.5 25.8 30 8 10 7 7.3 8 8.3	9.7 10 12.5 5 5 4.6 3.8 5.6 5.7	10 11 10.5 3.8 5 5.5 6.5 5.5 6.5	2.5 3 4 8 15 15 15 15	92° 86° 91° 86° 91°		
	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.7 M4 X 0.5 M4 X 0.7	96 23.5 25.8 30 8 10 7 7.3 8 8.3 9.3	9.7 10 12.5 5 4.6 3.8 5.6 5.7 6.7	10 11 10.5 3.8 5 5.5 6.5 6.5 6.5	2.5 3 4 8 15 15 15 15 15	92° 86° 91° 86° 91°		
d d a a	MHB1680 MHX0523 MHX0626 MHX0630 PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.7	96 23.5 25.8 30 8 10 7 7.3 8 8.3	9.7 10 12.5 5 4.6 3.8 5.6 5.7 6.7	3.8 5 5.5 6.5 6.5 6.5 6.5	2.5 3 4 8 15 15 15 15 15 15	92° 86° 91° 86° 91° 91°		
	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408 PTKA0409F PTKA0409F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.5 M4 X 0.5 M4 X 0.5	96 23.5 25.8 30 8 10 7 7.3 8 8.3 9.3 10.3	9.7 10 12.5 5 5 4.6 3.8 5.6 5.7 6.7	10 11 10.5 3.8 5 5.5 6.5 6.5 6.5 6.5 6.5	2.5 3 4 8 15 15 15 15 15 15 15	92° 86° 91° 86° 91° 91° 91°		
d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408F PTKA0409F PTKA0410F PTKA0410F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.7 M4 X 0.5 M4 X 0.5 M4 X 0.5 M4 X 0.5 M4 X 0.5 M4 X 0.5	96 23.5 25.8 30 8 10 7 7.3 8 8.3 9.3 10.3 11.3	9.7 10 12.5 5 4.6 3.8 5.6 5.7 6.7 7.7	10 11 10.5 3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5	2.5 3 4 8 15 15 15 15 15 15 15 15 15	92° 86° 91° 86° 91° 91° 91° 92°		
b d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408 PTKA0410F PTKA0411F PTKA0411F PTKA0412 PTKA0412 PTKA0413F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.5	8 10 7 7.3 8 8.3 9.3 10.3 11.3 12.3 13.3	5 5 4.6 3.8 5.7 7.7 8.7 7.5 9.7	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5	2.5 3 4 8 15 15 15 15 15 15 15 15 15 15	92° 86° 91° 86° 91° 91° 91° 92° 91°		
B d d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408 PTKA0410F PTKA0411F PTKA0411F PTKA0412 PTKA0412 PTKA0413F PTKA0512	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.5	8 10 7 7.3 8 8.3 9.3 10.3 11.3 12.3 13.3 12.3	9.7 10 12.5 5 5 4.6 3.8 5.6 6.7 7.7 8.7 7.5 9.7	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5	2.5 3 4 8 15 15 15 15 15 15 15 15 15 15 15 15 15	92° 86° 91° 91° 91° 92° 91° 92° 92° 92° 92°		
B d d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0409F PTKA0411F PTKA0411F PTKA0412 PTKA0412F PTKA0512 PTKA05508	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.6 M6 X 0.7 M6 X 0.5 M6 X 0.6 M7 X 0.5 M7 X 0.6 M7 X 0.6	8 10 7 7.3 8 8.3 9.3 10.3 11.3 12.3 12.3 12.8	9.7 10 12.5 5 5 4.6 3.8 5.6 7.7 8.7 7.5 9.7 10.7 7 5.3	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6	8 15 15 15 15 15 15 15 15 15 15 15 15 15	92° 86° 91° 91° 91° 91° 92° 92° 90°		
B d d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0409F PTKA0411F PTKA0412 PTKA0412 PTKA0412 PTKA0412 PTKA0412 PTKA0413F PTKA0512 PTMA0512 PTMA0510 PTMA0510	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.6 M6 X 0.6 M6 X 0.6 M6 X 0.6 M7 X 0.6 M7 X 0.6 M8 X 0.6	8 10 7 7.3 8 8.3 9.3 10.3 11.3 12.3 12.3 8 3.3	9.7 10 12.5 5 4.6 3.8 5.6 5.7 7.7 8.7 7.5 9.7 10.7 7 5.3 1.7	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6	8 15 15 15 15 15 15 15 15 15 15 15 15 15	92° 86° 91° 86° 91° 91° 91° 92° 91° 92° 90°		
B d d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408F PTKA0411F PTKA0411F PTKA0412 PTKA0412 PTKA0413F PTKA0413F PTMA03508 PTMA0403F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.6 M6 X 0.5 M6 X 0.5 M7 X 0.5 M8 X 0.5	96 23.5 25.8 30 8 10 7 7.3 8 8.3 10.3 11.3 12 12.3 13.3 12 8 3.3 4.3	9.7 10 12.5 5 4.6 3.8 5.6 5.7 7.7 7.5 9.7 10.7 7 5.3 1.7 2.7	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6	8 15 15 15 15 15 15 15 15 15 15 15 15 15	92° 86° 91° 91° 92° 91° 92° 91° 91° 91° 91° 91° 91° 91° 91° 91° 91		
	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0409 PTKA0411 PTKA04112 PTKA0412 PTKA0412 PTKA0512 PTKA0512 PTMA03508 PTMA0403F PTMA0403F PTMA0403F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.5	8 10 7 7.3 8 8.3 9.3 11.3 12.1 12.3 13.3 4.3 5.3	9.7 10 12.5 5 5 4.6 3.8 5.6 6.7 7.7 7.5 9.7 10.7 7 5.3 1.7 2.7 3.7	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6	8 15 15 15 15 15 15 15 15 15 15 15 15 15	92° 86° 91° 91° 91° 91° 92° 91° 91° 91°		
B d d a a	MHB1680 MHX0523 MHX0626 MHX0630  PTKA02508 PTKA03510 PTKA0407 PTKA0407 PTKA0408 PTKA0408F PTKA0411F PTKA0411F PTKA0412 PTKA0412 PTKA0413F PTKA0413F PTMA03508 PTMA0403F	M16 X 2.0 M5 X 0.8 M6 X 1.0 M2.5 X 0.45 M3.5 X 0.6 M4 X 0.7 M4 X 0.5 M4 X 0.6 M6 X 0.5 M6 X 0.5 M7 X 0.5 M8 X 0.5	96 23.5 25.8 30 8 10 7 7.3 8 8.3 10.3 11.3 12 12.3 13.3 12 8 3.3 4.3	9.7 10 12.5 5 4.6 3.8 5.6 5.7 7.7 7.5 9.7 10.7 7 5.3 1.7 2.7	3.8 5 5.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6.5 6	8 15 15 15 15 15 15 15 15 15 15 15 15 15	92° 92° 86° 91° 91° 91° 92° 91° 91° 91° 91°		

		Dimensions					
Geometry	Designation	а	b	C	d	B(T)	á
T pan. 8	FHGA0618	M4 X 0.7	11	6.9	6	15	u
R3.0 a	THOROUTO						
	FHGA0618	M6 X 1.0	18		8.5	4.0	61°
<u> </u>	PXMA0306	M3 X 0.5	5.9		5.7	2	90°
a d a a	SHX0310	M3 X 0.5	10		5.9	2	91°
	RHA0510	M5 X 0.8		10		4.0	
$\triangle$ $\square$	RHA0613	M6 X 1.0	16.3	13	10.5	4.0	
d 33 a	RHA0620	M6 X 1.0	24	20	10.5	4.0	
	VHX0509B	M5 X 0.8	9	4.15	5	2	
	VHX0512B	M5 X 0.8	12	6.5	5	2	
	VHX0512BN	M5 X 0.8	12	6.56	5	2	
	VHX0514	M5 X 0.8	14.5	8.25	5	2	
	VHX0613N	M6 X 1.0	13.4	7.5	5.93	2.5	
	VHX0617	M6 X 1.0	17	10	6	2.5	
	VHX0617N	M6 X 1.0	16.75	8.34	5.9	2.5	
	VHX0621	M6 X 1.0	21	14	6		
	VHX0817N	M8 X 1.0	17.05	7.98	7.9	3	
В с	VHX0820N	M8 X 1.0	20.7	7.98	7.9	3	
b	VHX0820AN	M8 X 1.0	20.5	10.36	7.9	3	
	VHX0821	M8 X 1.0	21	10	8	3	
	VHX0821N	M8 X 1.0	21.2	9.68	7.9	3	
	VHX0823N	M8 X 1.0	23.5	10.36	7.9	3	
	VHX0825	M8 X 1.0	25	12	8	3	
	VHX1027N	M10 X 1.0	27.2	14.4	9.8	5	
	VHX1236N	M12 X 1.0	36		11.8	5	
a d d	VHX0613A	M6 X 1.0	13.4	9.1	6.0	2.5	
<b>→</b> ∓⊓ —	SHXN0509F	M5 X 0.5	M3.5 X 0.6	8.65	6.3	3.5	
d ba	SHXN0609F	M6 X 0.75	M4 X 0.7	9	7.8	4	
	SHXN0610F	M6 X0.75	M4 X 0.5	10	7.8	4	
В с	SHXN0712F	M7 X0.75	M5 X 0.8	12	8.5	5	
	WTX0813	M8 X 1.25	17.2	4.9	8.5	25	
T C b	WTX0817	M8 X 1.25	22	4.9	8.5	25	

## Shim pin

Geometry	Designation	Dimensions					
Geometry	Designation	а	b	С	d		
_	SP3	5.5	3.5	5.9			
	SP3N	6.85	3.3	5.55			
	SP4	7.0	4.0	7.6			
с	SP4N	5.8	4.35	7.4			
<del>                                    </del>	SP5	8.5	4.5	8.8			
a a	SP5N	8.5	5.68	9			
1	SP6N	11.1	6.0	11.0			
	SP8N	12.0	10.0	15.35			
	SP2M	5	14	M5 X 0.8	6		
a	SP3M	3.5	19.5	M4 X 0.7	4		
	SP3M-1	3.5	16.5	M4 X 0.7	4		
	SP4M	5	19	M5 X 0.8	6		
-							

## Shim pin

Geometry	Designation	Dimensions						
Geometry	Designation	а	b	С	d			
	SP3D	3.7	13.1	UNF10-32	5.6			
	SP3D2	3.6	12	UNF10-32	5.5			
	SP3DS	3.7	11.54	UNF10-32	5.6			
a d c	SP4D	4.97	17.19	UNF1/4 28	7.12			
<u>*                                    </u>	SP4DL	5	17.1	UNF1/4 28	7			
b	SP4DS	4.97	13.26	UNF1/4 28				
	SP5D	6.21	21.9	UNF5/16-24	9.44			
	SP6D	7.75	21.9	UNF3/8-24	11.02			
	SP8D	9.02	29.63	UNF7/16-20	14.21			
	LSPS3	60	8.2	5.55				
b 4	LSPS4	65	10	7				
a	LSPS5	69	11.4	8.85				
	LSPS6	69	13	11				
	LSPS8	73	16.5	15.2				

## Spring

Geometry	Decimation		Di	mensio	ns
Geometry	Designation	a         b         c         d           4.0         2.8         12.6         0.4           0315         3.0         15           0415         4.0         15           9.2         12.5           4.0         11.0	d		
a d	SR2	4.0	2.8	12.6	0.4
D O O O O	SPR0315	3.0	15		
1\A\ A\ A\II	SPR0415	4.0	15		
- <del>      /     /                          </del>	SR3	9.2	12.5		
$\mathbb{D} \wedge \mathbb{A} = \mathbb{A}$	SR4	4.0	11.0		
b	SPR0714	7	14		
10 0 0 0 0 0 V	SPR0510	5	10		
a	SPR0714	7	14		
b	SPR0811	8	11		

### Wrench

Goometry	Decimation		Di	mensions
Geometry	Designation	а	b	B (T)
	HW20L	52	18	2
l <del>≺ a</del> BI	HW25L	58.5	20.5	2.5
	HW30L	66	23	3
b]	HW35L	72	25	3.5
<u> </u>	HW40L	74	29	4
	HW50L	85	33	5
b	HW40	82	80	4
	HW50	96	90	5
a a				
, a ,	SW50L	70	27.5	
b				
	TW06P	63		6
TI	TW07P	63		7
	TW08P	71		8
	TW09P	75		9
a	TW10P	78		10
	TW15P	82		15
	TW20P	86		20
<del> </del>	TW15L	60	21	15
· (	TW20L	60	21	20
b   W				

### Wrench

Coometry	Decimantian		Di	mensions	
Geometry	Designation	а	b	B (T)	
	TW07S	140	60	7	
	TW08S	150	76	8	
	TW09S	165	70	9	
b T	TW15S	190	90	15	
a	TW20S	195	91	20	
b • • • • • • • • • • • • • • • • • • •	TW20	75	80	20	
	TW25	74	80	25	
a	TW15-100	127	80	15	
	TW20-100	127	80	20	
₩ <u></u> † ⊤					
	SW15S	150	13		
b a a					

# Stop ring

Geometry	Designation		ns			
deometry	Designation	а	b	С	d	
П	CR03	4.8	2.6	0.4	3.0	
d	CR04	6.6	3.6	0.4	4.0	
	CR05	7.6	4.6	0.4	5.0	
b						
	ER03	7.0	2.6	0.6	3.0	
	ER04	9.0	3.5	0.6	4.0	
	ER05	11	4.3	0.6	5.0	

## Washer

Geometry	Designation	Dimensions				
Geometry	Designation	а	b	С		
	WA3	11.0	6.8	0.5~1.0		
a a c	WA4	10.0	5.3	0.5~1.0		


## Stopper

Geometry	Designation		ns		
Geometry	Designation	а	b	С	ď°
	STP5	11	10.2	11	30°
b 80° c					

### Nozzle

Geometry	Decimation		Dimensions	
deometry	Designation	а	b	
	CN0605	6	4.6	
a				





#### General Information I

 I 02 Workpiece Material Grades
 I 06 Steel, Non-ferrous Metal Symbol List
 I 07 SI unit Conversion Table
 I 08 Hardness Calculating Table
 I 09 Properties of Korloy Grades

#### **Technical Information**

I 10 Technical Information for Turning
 I 20 Technical Information for Milling
 I 24 Technical Information for Tapers
 I 27 Technical Information for Endmills
 I 30 Technical Information for Drills

#### **General Information II**

I 36 The comparision of chip breakers

I 37 KORLOY Grades

I 40 The comparision of grades for Turning/Milling

## **General Information I**

## O Carbon steel and alloy steel for structural use

	Korea	ISO	Japan	U.S.A	Great Britain	Germany	France	Russia
Туре	KS	ISO	JIS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
oon steel	SM10C	C10	S10C	1010	040A10 045A10	C10E C10R	XC10	-
	SM15C	C15E4	S15C	1015	045M10 055M15	C15E	-	-
	SM20C	-	S20C	1020	070M20 C22, C22E C22B	C22 C22E	C22 C22E C22B	-
	SM25C	C25 C25E4 C25M2	S25C	1025	C25 C25E	C25 C25E	C25 C25E	-
	SM30C	C30 C30E4 C30M2	S30C	1030	080A30 080M30 CC30 C30E	C30 C30E C30R	C30 C30E C30R	30 Г
	SM35C	C35 C35E4	S35C	1035	C35 C35E	C35 C35E C35B	C35 C35E	35 Γ
	SM40C	C40 C40E4 C40M2	S40C	1039 1040	080M40 C40 C40E	C40 C40E C40R	C40 C40E C40R	40 Г
	SM43C	-	S43C	1042 1043	080A42	-	-	40 Г
		C45 C45E4 C45M2		1045 1046	C45E C45R	C45 C45E C45R	C45 C45E C45R	45 F
	SM48C SM50C	- C50 C50E4 C50M2	S48C S50C	1049	080A47 080M50 C50 C50E C50B	- C50 C50E C50R	- C50 C50E C50R	45 F 50 F
	SM53C	-	S53C	1050 1053	-	-	-	50 Г
	SM55C	C55 C55E4 C55M2	S55C	1055	070M55 C55 C55E C55R	C55 C55E C55R	C55 C55E C55R	-
	SM58C	C60 C60E4 C60M2	S58C	1059 1060	C60 C60E	C60 C60E C60R	C60 C60E C60R	60 Г
Nickel chromium steel	SNC236 SNC415(H) SNC631(H) SNC815(H) SNC836	- - - 15NiCr13	SNC236 SNC415(H) SNC631(H) SNC815(H) SNC836	- - -	- - - 655M13(655H13)	- - - 15NiCr13		40XH - 30XH3A -
Nickel chromium molybdenum steel	SNCM220	20NiCrMo2 20NiCrMoS2	SNCM220	8615 8617(H) 8620(H) 8622(H)	805A20 805M20 805A22 805M22	20NiCrMo2 20NiCrMoS2	20NCD2	-
	SNCM240	41CrNiMo2 41CrNiMoS2	SNCM240	8637 8640	-	-	-	-
	SNCM420(H) SNCM431 SNCM439 SNCM447 SNCM616 SNCM625 SNCM630	-	SNCM420(H) SNCM431 SNCM439 SNCM447 SNCM616 SNCM625 SNCM630	- 4320(H) - 4340 - - -	-	- - - - -	-	- 20XH2M(20XHM - - - - -
Chromium	SCr415(H)	-	SCr415(H)	-	-	17Cr3	-	15X 15XA
2.501	SCr420(H)	20Cr4(H) 20CrS4	SCr420(H)	5120(H)	-	-	-	20X
	SCr430(H)	34Cr4 34CrS4	SCr430(H)	5130(H) 5132(H)	34Cr4 34CrS4	34Cr4 34CrS4	34Cr4 34CrS4	30X
	SCr435(H)	34Cr4 34CrS4 37Cr4	SCr435(H)	5135(H)	37Cr4 37CrS4	37Cr4 37CrS4	37Cr4 37CrS4	35X
	SCr440(H)	37Cr34 37CrS4 41Cr4 41CrS4	SCr440(H)	5140(H)	530M40 41Cr4 41CrS4	41Cr4 41CrS4	41Cr4 41CrS4	40X
	Nickel chromium steel  Nickel chromium molybdenum steel	SM10C   SM10C   SM15C   SM20C   SM25C   SM30C   SM35C   SM40C   SM45C   SM45C   SM45C   SM45C   SM55C   SM55C   SM55C   SM55C   SM55C   SM55C   SM56C   SM66C   SM66C   SM66C   SM6CM20   SM6M420   SM6M420   SM6M431   SM6M	SM15C	Nickel   SM50	Nickel	Non steel   SM10C	Vision   Sison   Sison   Sison   Sale   Bison   Different   Sison	Note   Note

 $<sup>{\:\</sup>raisebox{3.5pt}{\text{\circle*{1.5}}}}$  The above Alloy steel can supplied by domestic manufacturing

# **General Information I**

		Korea	ISO	Japan	U.S.A	Great Britain	Germany	France	Russia
	Туре	KS	KS ISO	JIS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
Allov	Chromium	SCM415(H)	-	SCM415(H)	-	-	-	-	-
steel	man lub danum	SCM418(H)	18CrMo4 18CrMoS4	SCM418(H)	-	-	18CrMo4 18CrMoS4	-	20XM
		SCM420(H)	-	SCM420(H)	-	708M20(708H20)	-	-	20XM
		SCM430	-	SCM430	4130	-	-	-	30XM 30XMA
	SCM432	-	SCM432	-	-	-	-	-	
		SCM435(H)	34CrMo4 34CrMoS4	SCM435(H)	(4135H) 4137(H)	34CrMo4 34CrMoS4	34CrMo4 34CrMoS4	34CrMo4 34CrMoS4	35XM
		SCM440(H)	42CrMo4 42CrMoS4	SCM440(H)	4140(H) 4142(H)	708M70 709M40 42CrMo4 42CrMoS4	42CrMo4 42CrMoS4	42CrMo4 42CrMoS4	-
		SCM445(H)	-	SCM445(H)	4145(H) 4147(H)	-	-	-	-
	Manganese	SMn420(H)	22Mn6(H)	SMn420(H)	1522(H)	150M19	-	-	-
	steel and Manganese	SMn433(H)	-	SMn433(H)	1534	150M36	-	-	30 Г 2 35 Г 2
	chromium steel	SMn438(H)	36Mn6(H)	SMn438(H)	1541(H)	150M36			35 Г 2 40 Г 2
		SMn443(H)	42Mn6(H)	SMn443(H)	1541(H)	-	-	-	40 Г 2 45 Г 2
		SMnC420(H) SMnC443(H)	-	SMnC420(H) SMnC443(H)	-	-	-	-	-
	Aluminum chromium molybdenum steel	SACM645	41CrAlMo74	SACM645	-	-	-	-	-

 $<sup>{\:\</sup>raisebox{3.5pt}{\text{\circle*{1.5}}}}$  The above Alloy steel can supplied by domestic manufacturing

# Tool steel

	Korea	ISO	Japan	U.S.A	Great Britain	Germany	France	Russia
Туре	KS	ISO	JIS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
High speed steel	SKH2	HS18-0-1	SKH2	T1				
	SKH3	-	SKH3	T4				
	SKH4	-	SKH4	T5				
	SKH10	-	SKH10	T15	BM 2	S6/5/2	Z 85 WDCV	
	SKH51	HS6-5-2	SKH51	M2				
	SKH52	HS6-6-2	SKH52	M3-1				
	SKH53	HS6-5-3	SKH53	M3-2				
	SKH54	HS6-5-4	SKH54	M4	BM 35	S6/5/2/5	6-5-2-5	
	SKH55	HS6-5-2-5	SKH55	M 35				
	SKH56	-	SKH56	M36				
	SKH57	HS10-4-3-10	SKH57	-		S2/9/2		
	SKH58	HS2-9-2	SKH58	M7		02.072		
	SKH59	HS2-9-1-8	SKH59	M42				
	STS11	1102-3-1-0	SKS11	F2				
Alloy tool steel	STS2	'	SKS2	12				
	STS21	-	SKS21					
		-		-				
	STS5	-	SKS5	-				
	STS51	-	SKS51	L6				
	STS7	-	SKS7	-				
	STS8	-	SKS8	-				
	STS4	-	SKS4	-				
	STS41	-	SKS41	-				
	STS43	105V	SKS43	W2-9 1/				
	STS44	-	SKS44	W2-8 1-2				
	STS3	-	SKS3	-		105WCr6	105WC13	
	STS31	105WCr1	SKS31	-				
	STS93	-	SKS93	-				
	STS94	-	SKS94	-				
	STS95	-	SKS95	-	BD3	X210Cr12	Z200C12	
	STD1	210Cr12	SKD1	D3				
	STD11		SKD11	D2	BA2	X100CrMoV5 1	Z100CDV5	
	STD12	100CrMoV5	SKD12	A2			2.000010	
	STD4	-	SKD4	-	BH21	X30WCrV9 3	Z30WCV9	
	STD5	X30WCrV9-3	SKD5	H21	SIL	7.004101400	2000000	
	STD6	X37CrMoV5-1	SKD6	H11	BH13	X40CrMoV5 1	Z40CDV5	
	STD61	X40CrMoV5-1	SKD61	H13	פוחט	A40UIVIUVO I	Z400DV3	
				H12				
	STD62	X35CrWMoV5	SKD62					
	STD7	32CrMoV12-28	SKD7	H10				
	STD8	-	SKD8	H19				
	STF3		SKT3	-		55NiCrMoV6	55NCDV7	
	STF4	55NiCrMoV7	SKT4	L6				

 $<sup>{\:\</sup>raisebox{3.5pt}{\text{\circle*{1.5}}}}$  The above Alloy steel can supplied by domestic manufacturing

# **General Information I**

	Korea	ISO	Japan	U.S.A	Great Britain	Germany	France	Russia
Туре	KS	ISO	JIS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
Free cutting	SUM11	-	SUM11	1110				
carbon steel	SUM12	-	SUM12	1109				
	SUM21	9S20	SUM21	1212				
	SUM22	11SMn28	SUM22	1213	230M07	9SMn28	S250	
	SUM22L	11SMnPb28	SUM22L	12L13		9SMnPb28	S250Pb	
	SUM23	-	SUM23	1215	240M07	9SMn36	S 300	
	SUM23L	-	SUM23L	-				
	SUM24L	11SMnPb28	SUM24L	12L14		9SMnPb36	S300Pb	
	SUM25	12SMn35	SUM25	-				
	SUM31	-	SUM31	1117				
	SUM31L	-	SUM31L	-				
	SUM32	-	SUM32	-				
	SUM41	-	SUM41	1137				
	SUM42	-	SUM42	1141				
	SUM43	44SMn28	SUM43	1144				
High carbon	STB1	-	SUJ1	-				
chromiom	STB2	B1	SUJ2	52100	534A99	100Cr6	100Cr6	
	STB3	B2	SUJ3	ASTM A				
				485				
				Grade 1				
	STB4	-	SUJ4	-				
	STB5	-	SUJ5	-				

 $<sup>{\</sup>mbox{\ensuremath{\bullet}}}$  The above Alloy steel can supplied by domestic manufacturing

# Stainless steel

_		Korea	ISO	Japan	U.	S.A	Great Britain	Germany	France	Russia
Т	уре	KS	ISO	JIS	UNS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
ainless	Austenitic	STS201	X12CrMnNiN17-7-5	SUS201	S20100	201	284S16	X12CrNi17-7	Z12CMN17-07Az	12X17·9AH4
	13.0101	STS202	X12CrMnNiN18-9-5	SUS202	S20200	202	301S21	X2CrNiN18-7		07X16H6
		STS301	X10CrNi18-8	SUS301	S30100	301		X12CrNi17-7	Z11CN17-08	
		STS301L	X2CrNiN18-7	SUS301L						
		STS301J1		SUS301J1			302S25			12X18H9
		STS302		SUS302	S30200	302		X10CrNiS18-9	Z12CN18-09	
		STS302B	X12CrNiSi18-9-3	SUS302B	S30215		303S21			
		STS303	X10CrNiS18-9	SUS303			303S41		Z8CNF18-09	12X18H10E
		STS303Se		SUS303Se	S30323		000011	X5CrNi18-10	200111 10 00	12711011102
		STS303Cu		SUS303Cu	000020	00000	304S31	7,00114110 10		08X18H10
		STS304	X5CrNi18-9	SUS304	S30400	304	001001	X2CrNi19-11	Z7CN18-09	00/(101110
		010004	X2CrNi18-9	000001	000100	001	304S11	AZONINI II	2/01/10-03	03X18H11
		STS304L	X2CrNi19-11	SUS304L	S30403	304L	004011	X2CrNiN18-10	Z3CN19-11	OOXTOITT
		STS304N1	X5CrNiN18-8	SUS304N1	S30451			AZGININ 10-10	Z6CN19-09Az	
		STS304LN	X2CrNiN18-8	SUS304LN	S30451			X5CrNi18-12	Z3CN18-10Az	
		STS304LN	ALONINTO	SUS304J1	330433	JU4LIN	305S19	ASCHNITO-12	ZOCIVIO-IUAZ	06X18H11
			X6CrNi18-12	SUS305	S30500	205	303519		7000140.40	00/10/11
		STS305	70011110-12	SUS309S	_	309S	040004	VEO-NEM-07-40-0	Z8CN18-12	107001110
		STS309S	X6CrNi25-20		S30908		310S31	X5CrNiMo27-12-2		10X23H18
		STS310S	X5CrNiMo17-12-2	SUS310S	S31008	310S	316S31	X5CrNiMo27-13-3		
		STS316	X3CrNiMo17-12-3	SUS316	S31600	316	0.00	X2CrNiMo17-13-2	Z7CND17-12-02	
		STS316L	X2CrNiMo17-12-2 X2CrNiMo17-12-3 X2CrNiMo18-14-3	SUS316L	S31603	316L	316S11	X2CrNiMo17-14-3	Z6CND18-12-03 Z3CND17-12-02 Z3CND17-12-03	03X17H14M
		STS316N		SUS316N	S31651	316N	317S16	X6CrNiTi18-10		
		STS317		SUS317	S31700		321S31	X6CrNiNb18-10		08X18H10T
		STS321	X6CrNiTi18-10	SUS321	S32100		347S31	7.00114114151010	Z6CNT18-10	08X18H12
		STS347	X6CrNiNb18-10	SUS347	S34700		047001	X6CrAl13	Z6CNNb18-10	COXTOTTLE
		STS384	X3NiCr18-16	SUS384	S38400	384	405S17	AUDIANIS	Z6CN18-16	
		STS405	X6CrAl13	SUS405	S40500	405	403017		Z8CA12	
	Ferritic	STS410L	7.00.7.1.0	SUS410L	040300	100		X6Cr17	Z3C14	
		STS429		SUS429	S42900	120	430S17	X7CrS18	23014	12X17
		STS430	X6Cr17	SUS430	S43000		430317	X6CrMo17-1	Z8C17	IZATI
		STS430F	X7CrS17	SUS430F	S43020		434S17	AOCHVIOT7-1	Z8CF17	
		STS430F STS434	X6CrMo17-1	SUS434	S43400		434317			
			X2CrMoTi18-2	SUS444	S44400				Z8CD17-01	
		STS444	AZONNOTTIO-Z	SUSXM27	S44400 S44627	444		V400-40	Z3CDT18-02	
		STSXM27		SUS403		400	440004	X10Cr13	Z1CD26-01	
	Martensitic	STS403	X12Cr13		S40300		410S21	1/000 10	7.00.0	
		STS410	X12CrS13	SUS410	S41000		416S21	X20Cr13	Z13C13	201/40
		STS416		SUS416	S41600		420S29	X20CrNi17-2	Z11CF13	20X13
		STS420J1	X20Cr13	SUS420J1	S42000		431S29		Z20C13	20X17H2
		STS431	X19CrNi16-2	SUS431					Z15CN16-02	
		STS440A	X70CrMo15	SUS440A	S44002			X7CrNiAl17-7	Z70C15	
	Precipitation	STS630	X5CrNiCuNb16-4	SUS630		S17400			Z6CNU17-04	09X17H7IO
	hardening	STS631	X7CrNiAl17-7	SUS631	S17700	S17700			Z9CNA17-07	
type		STS631J1		SUS631J1						

<sup>•</sup> The above Alloy steel can supplied by domestic manufacturing

# Casting or forging steel

		Korea	ISO	Japan	U.S.A	<b>Great Britain</b>	Germany	France	Russia
Туре		KS	ISO	JIS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
Casting Iron	Grey iron casting	GC100 GC150 GC200 GC250 GC350	100,150, 200, 250, 300, 350	FC100 FC150 FC200 FC250 FC350	No 20 B No 25 B No 30 B No 35 B No 45 B No 50 B No 55 B	Grade 150 Grade 220 Grade 260 Grade 300 Grade 350 Grade 400	GG 10 GG 15 GG 20 GG 25 GG 30 GG 35 GG 40	Ft 10 D Ft 15 D Ft 20 D Ft 25 D Ft 30 D Ft 35 D Ft 40 D	
	Spheroidal graphite iron casting	GCD400-15, GCD400-18 GCD450-10, GCD500-7 GCD600-3 GCD700-2	400-15, 400-18 450-10, 500-7 600-3 700-2	FCD400 FCD500 FCD600 FCD700	60-40-18 65-45-12 80-55-06 100-70-03	SNG 420/12 SNG 370/17 SNG 500/7 SNG 600/3 SNG 700/2	GGG 40 GGG 40.3 GGG 50 GGG 60 GGG 70	FCS 400-12 FGS 370-17 FGS 500-7 FGS 600-3 FGS 700-2	
	Austempered Spheroidal graphite iron casting	FCAD	-	FCAD	-	EN-GJS-	EN-GJS-	EN-GJS-	
	Austenitic iron casting	FCA- FCDA-	L-, S-	FCA- FCDA-	Type 1, 2, Type D-2, D-3A Class 1, 2	F1, F2, S2W, S5S	GGL-, GGG-	L-, S-	

# Non-ferrous alloy

		Korea	ISO	Japan	U.S.A	Great Britain	Germany	France	Russia
Type		KS	ISO	JIS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
Aluminum	Aluminum	AC1B	Al-Cu4MgTi	AC1B	204.0	-	-	A-U5GT	
lloy	alloy ingots	AC2A	-	AC2A	-	-	-	-	
шоу	for casting	AC2B	-	AC2B	319.0	-	-	-	
	ioi odomig	AC3A	-	AC3A	-	LM-6	-	-	
		AC4A	-	AC4A	-	-	G(GK)-AlSi9Cu3	-	
		AC4B	-	AC4B	-	-	-	-	
		AC4C	Al-Si7Mg(Fe)	AC4C	356.0	LM-25	G(GK)-AlSi7MG	A-S7G	
		AC4CH	Al-Si7Mg	AC4CH	A356.0	-	-	-	
		AC4D	Al-Si5Cu1Ma	AC4D	355.0	LM-16	-	-	
		AC5A	Al-Cu4Ni2Mg2	AC5A	242.0	-	G(GK)-AIMq5	A-U4NT	
		AC7A	-	AC7A	514.0	LM-5	-	-	
		AC8A	-	AC8A	-	LM-13	-	A-S12UNG	
		AC8B	-	AC8B	-	LM-26	-	A-S10UG	
		AC8C	-	AC8C	-	-	-	A-S10UG	
		AC9A	-	AC9A	-	LM-29	-	-	
		AC9B	-	AC9B	-	-	GD-AlSi12 (Cu)	A-S18UNG	
	Aluminum alloy die	ALDC1	Al-Si12CuFe	ADC1	A413.0	LM20	GD-AlSi10Ma	A-S13	
		ALDC2	-	ADC3	A360.0	-	GD-AlMq9	A-S9G	
	casting	ALDC3	-	ADC5	518.0	-	-	A-G6	
	casting	ALDC4	-	ADC6	-	-	GD-AlSi9Cu3	A-G3T	
		ALDC7	Al-Si8Cu3Fe	ADC10	A380.0	-	GD-AlSi9Cu3	-	
		ALDC7Z	Al-Si8Cu3Fe	ADC10Z	A380.0	LM24	-	-	
		ALDC8	-	ADC12	383.0	LM2	-	-	
		ALDC8Z	-	ADC12Z	383.0	LM2	-	-	
		ALDC9	-	ADC14	B390.0	LM30	EN AW-5052	-	
	Aluminum	A5052S	-	A5052S	5052	EN AW-5052	EN AW-5454	EN AW-5052	
	alloy	A5454S	-	A5454S	5454	EN AW-5454	EN AW-5083	EN AW-5454	
	extruded	A5083S	AlMq4.5Mn0.7	A5083S	5083	EN AW-5083	EN AW-5086	EN AW-5083	
	shapes	A5086S	-	A5086S	5086	EN AW-5086	EN AW-6061	EN AW-5086	
	Silapos	A6061S	AlMq1SiCu	A6061S	6061	EN AW-6061	EN AW-6063	EN AW-6061	
		A6063S	AlMq0.7Si	A6063S	6063	EN AW-6063	EN AW-7003	EN AW-6063	
		A7003S	-	A7003S	-	EN AW-7003	-	EN AW-7003	
		A7N01S	-	A7N01S	-	-	EN AW-7075	-	
		A7075S	AlZn5.5MgCu	A7075S	7075	EN AW-7075		EN AW-7075	

# Heat resistant steel

		Korea	ISO	Japan	U.	S.A	Great Britain	Germany	France	Russia
Туре		KS	ISO	JIS	UNS	AISI SAE	BS BS/EN	DIN DIN/EN	NF NF/EN	GOCT
Heat	Austenitic	STR31		SUH31			331S42		Z35CNWS14-14	
resistant	7 10010111110	STR35		SUH35			349S52	X53CrMnNi21-9	Z52CMN21-09-Az	
		STR36		SUH36			349S54		Z55CMN21-09-Az	
steel		STR37		SUH37	S63008		381S34			
		STR38		SUH38	S63017					
		STR309		SUH309			309S24	CrNi2520	Z15CN24-13	
		STR310		SUH310	S30900		310S24		Z15CN25-20	
		STR330		SUH330	S31000	309			Z12NCS35-16	
		STR660		SUH660	N08330	310			Z6NCTV25-20	
		STR661		SUH661	S66286	N08330		CrAl1205		
	Ferritic	STR21		SUH21	R30155			X6CrTi12		
	i Giillic	STR409	X6CrTi12	SUH409			409S19		Z6CT12	
		STR409L	X2CrTi12	SUH409L	S40900				Z3CT12	
		STR446		SUH446		409		X45CrSi9-3	Z12C25	
	Martensitic	STR1		SUH1	S44600		401S45		Z45CS9	
	Marterisitic	STR3		SUH3	S65007	446			Z40CSD10	
		STR4		SUH4			443S65		Z80CSN20-02	
		STR11		SUH11						
		STR600		SUH600						
		STR616		SUH616	S42200					

<sup>•</sup> The above Heat resistant steel can supplied by domestic manufacturing



# Steel, Non-ferrous metal symbol list

# **O** Comparison of workpiece material standards

Gı	roup	Standard term	Code	
		Rolled Steel for Welded Structure	SWS	
		Rerolled Steel	SBR	
	ctural	Rolled Steel for General Structure	SB	
S	teel	Light Gauge Steel for General Structure	SBC	
		Hot- rolled Steel Plate, Sheet/ Strip for Automobile Structural Use	SAPH	
S	teel	Cold-rolled Steel Sheet/Strip	SBC	
P	late	Hot-rolled Soft Steel Sheet/Strip	SHP	
		Carbon Steel Pipe for Ordinary Piping	SPP	
		Carbon Steel Pipe for Boiler and Heat Exchanger	STH	
		Seamless Steel Pipe for High Pressure Gas Cylinder	STHG	
		Carbon Steel Pipe for General Structural Use	SPS	
		Carbon Steel Pipe for Machine Structural Use	STST	
		Alloy Steel Pipe for Structural Use	STA	
_	teel ipe	Stainless Steel Pipe for Machine and Structural Use	STS-TK	
-	ihe	Carbon Steel Square Pipe for General Structural Use	SPSR	
		Alloy Steel Pipe	SPA	
		Carbon Steel Pipe for Pressure Service	SPPS	
		Carbon Steel Pipe for High Temperature Service	SPSR	
		Carbon Steel Pipe for High Pressure Service	SPPH	
		Stainless Steel Pipe	STSxT	
		Carbon Steel for Machine Structural Use	SMxxC, SMxxC	
		Aluminum Chromium Molybdenum Steel	SACM	
		Chromium Molybdenum Steel	SCM	
	ron and	Chromium Steel	SCr	
-	teel	Nickel Chromium Steel	SNC	
		Nickel Chromium Molybdenum Steel	SNCM	
		Manganese Steel and manganese Chromium Steel for Machine Structural Use	SMn, SMnC	
		Carbon Tool Steel	STC	
	Tool	Hollow Drill Steel	SKC	
	steel	Alloy Tool Steel	STS, STD, STF	
		High Speed Tool Steel	SKH	
Special steel	Stainless steel	Stainless Steel Bar	STS	
ecia	Heat	Heat Resisting Steel	STR	
တ္တ	resisting	Heat Resisting Steel Bar	STR	
	steel	Heat Resisting Steel Sheet	STR	
		Free cutting carbon steel	SUM	
		Special steel	STB	
		Spring steel	SPS	

Group	Standard term	Code
Forgod	Carbon Steel Forging	SF
Forged steel	Chromium Molybdenum Steel Forging	SFCM
	Nickel Chromium Molybdenum Steel Forging	SFNCM
	Gray Cast iron	GC
	Spheroidal Graphite Cast iron	GCD
Cast iron	Blackheart Malleable Cast iron	ВМС
	Whiteheat Malleable Cast iron	WMC
	Pearlitic Malleable Cast iron	PMC
	Carbon Cast Steel	SC
	High Tensile Strength Carbon Cast Steel & Low Alloy Cast Steel	HSC
Cast	Stainless Cast Steel	SSC
steel	Heat Resisting Cast Steel	HRSC
	High Manganese Cast Steel	HMnSC
	Cast Steel for High Temperature and High Pressure Service	SCPH
	Brass Casting	BsC
	High Strength Brass Casting	HBsC
	Bronze Casting	BrC
	Phosphoric Bronze Casting	PCB
	Aluminum Bronze Casting	AIBC
	Aluminum Alloy Casting	ACxA
Casting	Magnesium Alloy Casting	MgC
	Zinc Alloy Die Casting	ZnDC
	Aluminum Alloy Die Casting	A@ DC
	Magnesium Alloy Die Casting	MgDC
	White Metal	WM
	Aluminum Alloy Casting for Bearing	AM
	Brass Alloy Casting for Bearing	KM

# SI unit conversion table

# Major SI unit conversion table

### ■ Force

N	kgf	dyn
1	1.01972×10 <sup>-1</sup>	1×10 <sup>-5</sup>
9.80665	1	9.80665×10 <sup>5</sup>
1×10 <sup>-5</sup>	1.01972×10 <sup>-6</sup>	1

#### ■ Stress

Pa or N/m <sup>2</sup>	MPa or N/mm²	kgf/mm²	kgf/cm <sup>2</sup>	kgf/m²
1	1×10 <sup>-6</sup>	1.01972×10 <sup>-7</sup>	1.01972×10 <sup>-5</sup>	1.01972×10 <sup>-1</sup>
1×10 <sup>6</sup>	1	1.01972×10 <sup>-1</sup>	1.01972×10	1.01972×10 <sup>5</sup>
9.80665×10 <sup>6</sup>	9.80665	1	1×10 <sup>2</sup>	1×10 <sup>6</sup>
9.80665×10 <sup>4</sup>	9.80665×10 <sup>-2</sup>	1×10 <sup>-2</sup>	1	1×10 <sup>4</sup>
9.80665	9.80665×10 <sup>-6</sup>	1×10 <sup>-6</sup>	1×10 <sup>-4</sup>	1

### ■ Pressure

Pa	kPa	MPa	bar	kgf/cm <sup>2</sup>
1	1×10 <sup>-3</sup>	1×10 <sup>-6</sup>	1×10 <sup>-5</sup>	1.01972×10 <sup>-5</sup>
1×10³	1	1×10 <sup>-3</sup>	1×10 <sup>-2</sup>	1.01972×10 <sup>-2</sup>
1×10 <sup>6</sup>	1×10³	1	1×10	1.01972×10
1×10 <sup>5</sup>	1×10 <sup>2</sup>	1×10 <sup>-1</sup>	1	1.01972
9.80665×10 <sup>4</sup>	9.80665×10	9.80665×10 <sup>-2</sup>	9.80665×10 <sup>-1</sup>	1

# **■** Work, Energy, Calorie

J	kW∙h	kgf⋅m	kcal
1	2.77778×10 <sup>-7</sup>	1.01972×10 <sup>-1</sup>	2.38889×10 <sup>-4</sup>
3.60000×10 <sup>6</sup>	1	3.67098×10⁵	8.60000×10 <sup>2</sup>
9.80665	2.72407×10 <sup>-6</sup>	1	2.34270×10 <sup>-3</sup>
4.18605×10 <sup>3</sup>	1.16279×10 <sup>-3</sup>	4.26858×10 <sup>2</sup>	1

#### ■ Power

W	kW	kgf·m/s	PS	kcal/h
1	1×10 <sup>-3</sup>	1.01972×10 <sup>-1</sup>	1.35962×10 <sup>-3</sup>	0.860
1×10 <sup>3</sup>	1	1.01972×10 <sup>2</sup>	1.359 62	8.60000×10 <sup>2</sup>
9.81 65	9.80665×10 <sup>-3</sup>	1	1.33333×10 <sup>-2</sup>	8.433 71
7.355×10 <sup>2</sup>	7.355×10 <sup>-1</sup>	7.5×10	1	6.32529×10 <sup>2</sup>
1.16279	1.16279×10 <sup>-3</sup>	1.18572×10 <sup>-1</sup>	1.58095×10 <sup>-3</sup>	1

## ■ Specific heat

<b>J</b> /(kg⋅K)	kcal/(kg⋅°C) cal/(g⋅°C)
1	2.38889×10 <sup>-4</sup>
4.18605×10 <sup>3</sup>	1

## ■ Thermal conductivity

<b>W</b> /(m·k)	kcal/(h·m·°C)	
1	8.6000×10 <sup>-1</sup>	
1.16279	1	

# ■ Revolution per minute

min-1	<b>S</b> -1	r.p.m.
1	0.0167	1
60	1	60

# Hardness calculating table

# Work piece hardness calculating table

		nell gf HB		Rocl		Tensile strength		
Vickers 50kgf	Standard ball 10mm	Cemented carbide ball	particle	B scale 100kgf 1/16in ball	C scale 150kgf Diamond particle	D scale 100kgf Diamond particle	Shore	(approximate value)  MPa (1)
HV			HRA	HRB	HRC	HRD	HS	
940	-	-	85.6	-	68.0	76.9	97	
920	-	-	85.3	-	67.5	76.5	96	
900	-	-	85.0	-	67.0	76.1	95	
880	-	(767)	84.7	-	66.4	75.7	93	
860	-	(757)	84.4	-	65.9	75.3	92	
840	-	(745)	84.1	-	65.3	74.8	91	
820	-	(733)	83.8	-	64.7	74.3	90	
800	-	(722)	83.4	-	64.0	74.8	88	
780	-	(710)	83.0	-	63.3	73.3	87	
760	-	(698)	82.6	-	62.5	72.6	86	
740	-	(684)	82.2	-	61.8	72.1	84	
720	-	(670)	81.8	-	61.0	71.5	83	
700	-	(656)	81.3	-	60.1	70.8	81	
690	-	(647)	81.1	-	59.7	70.5	-	
680	-	(638)	80.8	-	59.2	70.1	80	
670	-	630	80.6	-	58.8	69.8	-	
660	-	620	80.3	_	58.3	69.4	79	
650	-	611	80.0	_	57.8	69.0	-	
640	-	601	79.8	-	57.3	68.7	77	
630	-	591	79.5	_	56.8	68.3	-	
620	-	582	79.2	-	56.3	67.9	75	
610	-	573	78.9	-	55.7		73	
600	-	564	78.6		55.2	67.5	74	
			78.4			67.0	-	0055
590	-	554		-	54.7	66.7		2055
580	-	545	78.0	-	54.1	66.2	72	2020
570	-	535	77.8	-	53.6	65.8	74	1985
560	(505)	525	77.4		53.0	65.4	71	1950
550	(505)	517	77.0	-	52.3	64.8	-	1905
540	(496)	507	76.7	-	51.7	64.4	69	1860
530	(488)	497	76.4	-	51.1	63.9	-	1825
520	(480)	488	76.1	-	50.5	63.5	67	1795
510	(473)	479	75.7	-	49.8	62.9	-	1750
500	(465)	471	75.3	-	49.1	62.2	66	1705
490	(456)	460	74.9	-	48.4	61.6	-	1660
480	488	452	74.5	-	47.7	61.3	64	1620
470	441	442	74.1	-	46.9	60.7	-	1570
460	433	433	73.6	-	46.1	60.1	62	1530
450	425	425	73.3	-	45.3	59.4	-	1495
440	415	415	72.8	-	44.5	58.8	59	1460
430	405	405	72.3	-	43.6	58.2	-	1410
420	397	397	71.8	-	42.7	57.5	57	1370
410	388	388	71.4	-	41.8	56.8	-	1330
100	379	379	70.8	-	40.8	56.0	55	1290
390	369	369	70.3	-	39.8	55.2	-	1240
380	360	360	69.8	(100.0)	38.8	54.4	52	1205
370	350	350	69.2	-	39.9	53.6	-	1170
360	341	341	68.7	(109.0)	36.6	52.8	50	1130
350	331	331	68.1	-	35.5	51.9	-	1095
340	322	322	67.6	(108.0)	34.4	51.1	47	1070
330	313	313	67.0	-	33.3	50.2	-	1035

Brinell									
		gf HB		Rockwell Tensile strength					
Vickers 50kgf	Standard ball 10mm	Cemented carbide ball	particle	B scale 100kgf 1/16in ball	C scale 150kgf Diamond particle	D scale 100kgf Diamond particle	Shore	(approximate value)  MPa (1)	
HV			HRA	HRB	HRC	HRD	HS	- (7	
320	303	303	66.4	(107.0)	32.2	49.4	45	1005	
310	294	294	65.8	-	31.0	48.4	-	980	
300	284	284	65.2	(105.5)	29.8	47.5	42	950	
295	280	280	64.8	-	29.2	47.1	-	935	
290	275	275	64.5	(104.5)	28.5	46.5	41	915	
285	270	270	64.2	-	27.8	46.0	-	905	
280	265	265	63.8	(103.5)	27.1	45.3	40	890	
275	261	261	63.5	-	26.4	44.9	-	875	
270	256	256	63.1	(102.0)	25.6	44.3	38	855	
265	252	252	62.7	-	24.8	43.7	-	840	
260	247	247	62.4	(101.0)	24.0	43.1	37	825	
255	243	243	62.0	-	23.1	42.2	-	805	
250	238	238	61.6	99.5	22.2	41.7	36	795	
245	233	233	61.2	-	21.3	41.1	-	780	
240	228	228	60.7	98.1	20.3	40.3	34	765	
230	219	219	-	96.7	(18.0)	-	33	730	
220	209	209	-	95.0	(15.7)	-	32	695	
210	200	200	-	93.4	(13.4)	-	30	670	
200	190	190	-	91.5	(11.0)	-	29	635	
190	181	181	-	89.5	(8.5)	-	28	605	
180	171	171	-	87.1	(6.0)	-	26	580	
170	162	162	-	85.0	(3.0)	-	25	545	
160	152	152	-	81.7	(0.0)	-	24	515	
150	143	143	-	78.7	-	-	22	490	
140	133	133	-	75.0	-	-	21	455	
130	124	124	-	71.2	-	-	20	425	
120	114	114	-	66.7	-	-	-	390	
110	105	105	-	62.3	-	-	-	-	
100	95	95	-	56.2	-	-	-	-	
95	90	90	-	52.0	-	-	-	-	
90	86	86	-	48.0	-	-	_	-	
85	81	81	-	41.0	-	-	-	-	

Note) 1.  $1MPa = 1N/m^2$ 

2. The number In the blank is not generally used ranges

# Properties of KORLOY grades

# Physical properties of KORLOY grades


Application	Classif	60 fication nbol	KORLOY grades	Specific gravity (g/cm²)	Hardness (HRA)	TRS (kgf/m²)	Compressive strength (kg/m²)	Young's modulus (10 <sup>3</sup> kgf/m²)	Thermal expansion coefficient (10-6/°C)	Thermal conductivity (cal/cmsec°C)
		P01	ST05	10.6	92.7	140	440	-	-	-
	Р	P10	ST10	10.0	92.1	175	460	48	6.2	25
	-	P20	ST20	11.8	91.9	200	480	56	5.2	42
		P30	ST30A	12.2	91.3	230	500	53	5.2	-
		M10	U10	12.9	92.4	170	500	47	-	-
Grades for cutting tools	M	M20	U20	13.1	91.1	210	500	-	-	88
cutting tools	IVI	M30	ST30A	12.2	91.3	230	500	53	5.2	-
		M40	U40	13.3	89.2	270	440	-	-	-
		K01	H02	14.8	93.2	185	-	61	4.4	105
	K	K10	H01	13.0	92.9	210	570	66	4.7	109
		K20	G10	14.7	90.9	250	500	63	-	105
Ultra fine	Z	Z10	FA1	14.1	91.4	290	-	58	5.7	-
grain alloy		Z20	FCC	12.5	91.3	235	-	-	-	-
		V1	D1	15.0	92.3	205	520	-	-	-
Grade for		V2	D2	14.8	90.9	250	150	-	-	-
tungsten carbide	V	V3	D3	14.6	89.7	310	410	-	-	-
wear parts		V4	G5	14.3	89.0	320	380	-	-	-
		V5	G6	14.0	87.7	350	330	-	-	-
		E1	GR10	14.8	90.9	220	-	-	-	-
Grade for mining		E2	GR20	14.8	90.3	240	-	-	-	-
and civil	E	E3	GR30	14.8	89.0	270	-	-	-	-
engineering tools	3	E4	GR35	14.8	88.2	270	-	-	-	-
		E5	GR50	14.5	87.0	300	-	-	-	-

# The physical properties of element

Element	Specific gravity (g/cm²)	Hardness (HB)	Young's modulus (×10³kgf/m²)	Thermal conductivity (cal/cmsec°C)	Thermal expansion coefficient (×10-6/°C)	Melting point (°C)
wc	15.6	2,150	70	0.3	5.1	2,900
TiC	4.94	3,200	45	0.04	7.6	3,200
TaC	14.5	1,800	29	0.05	6.6	3,800
NbC	8.2	2,050	35	0.04	6.8	3,500
TiN	5.43	2,000	26	0.07	9.2	2,950
Al203	3.98	3,000	42	0.07	8.5	2,050
cBN	3.48	4,500	71	3.1	4.7	-
Diamond	3.52	9,000	99	5.0	3.1	-
Co	8.9	-	10~18	0.165	12.3	1,495
Ni	8.9	-	20	0.22	13.3	1,455

# **Technical Information for Turning**

Insert shape and terminology




### • Relating angles between tool and workpiece

Cutting edge inclination	Terminology	Function	Effect		
Rake angle	angle angle control on tool life		(+): Excellent machine-ability(reducing cutting force, weakening cutting edge strength)     (+): When machining excellent machine-ability or thin workpiece     (-): When strong cutting edge is needed at interrupted condition or mill scale		
Relief angle	Relief angle Side relief angle	Only cutting edge contact with cutting face	• (-): Cutting edge is strong but has short tool life to make bad influence on flank wear		
	Cutting edge angle	Affects chip control and cutting force direction	• (+): Improved chip control because chip thickness is big		
Cutting edge angle	Side cutting edge angle	Affects chip control and cutting force direction	(+): Strong cutting edge due to distributed cutting force but chip control is bad by thin chip thickness     (-): Improved chip performance		
	End cutting edge angle	Prevent friction between cutting edge and cutting face	• (-): Cutting edge is strong but has short tool life to make bad influence on flank wear		

## Calculation formulas for machining

#### Cutting speed



$$vc = \frac{\pi \times D \times n}{1000} \text{ (m/min)}$$


- · vc: Cutting speed (m/min)
- π: Circular constant (3.14)
- · D: Diameter (mm)
- n: Revolution per minute (min<sup>-1</sup>)

### Feed

$$fn = \frac{vf}{n} \text{ (mm/rev)}$$

- fn: Feed per revolution (mm/rev)
- n: Revolution per minute (min-1)
- · vf: Table feed (mm/min)

## Surface finish



- Rmax: Profile depth(Maximum height roughness) (µ)
- fn: feed (mm/rev)
- r : nose radius

#### · Theoretical surface roughness

$$Rmax = \frac{fn^2}{8r} 1000(\mu m)$$

· Practical surface roughness

Steel: Rmax × (1.5~3) Cast iron: Rmax × (3~5)

#### Power requirement

$$P_{kv} = \frac{Q \times kc}{60 \times 102 \times r}$$

$$P_{HP} = \frac{P_{KW}}{0.75}$$

- Pkw: Power requirement [kW]
- Php: Power requirement (horse power) [HP]
- vc: Cutting speed [m/min]
- ap: Depth of cut [mm]

- fn: Feed per revolution [mm/rev]
- kc: Specific cutting resistance [kg/mm²]
- η: Machine efficiency rate (0.7~0.8)

#### Rough Kc Mild steel 190 Medium carbon steel 210 High carbon steel 240 Low alloy steel 190 High alloy steel 245 93 Cast iron Malleable cast iron 120 Bronze, Brass 70


#### Material removal rate

Q (cm<sup>3</sup>/min) = vc × ap × fn

- Q: Material removal rate [cm²/min] • ap: Depth of cut [mm]
- · vc: Cutting speed [m/min]
- fn: Feed per revolution [mm/rev]

## Machining time

### External face machining 1



## Constant revolution per minute


$$T = \frac{60 \times L}{fn \times n}$$

#### **Constant cutting speed**

$$T = \frac{60 \times \pi \times L \times D}{1000 \times \text{fn} \times \text{vc}}$$

- T: Machining time [sec]
- L: Cutting length [mm]
- fn: Feed per revolution [mm/rev]
- n: Revolution per minute [min-1]
- D: Diameter of workpiece [mm]
- vc: Cutting speed [m/min]

#### External face machining 2



#### Constant revolution per minute


$$T = \frac{60 \times L}{fn \times n} \times N$$

#### Constant cutting speed

$$T = \frac{60 \times \pi \times L \times (D_1 + D_2)}{2 \times 1000 \times fn \times vc} \times N$$

- T: Machining time [sec]
- L: Cutting length [mm]
- fn: Feed per revolution [mm/rev]
- n: Revolution per minute [min-1]
- D1: Maximum diameter of workpiece [mm]
- D2: Minimum diameter of workpiece [mm]
- vc: Cutting speed [m/min]
- N: The number of pass = (D1-D2)/d/2

#### Facing



## Constant revolution per minute

$$T = \frac{60 \times (D_1 - D_2)}{2 \times fn \times n} \times N$$


#### Constant cutting speed

$$T_1 = \frac{60 \times \pi \times (D_1 + D_2) \times (D_1 - D_2)}{4000 \times \text{fn} \times \text{vc}} \times N$$

#### T: Machining time [sec]

- T1: Machining time before the maximum rpm[sec]
- L: Width of machining [mm]
- fn: Feed per revolution [mm/rev]
- n: Revolution per minute [min-1]
- D1: Maximum diameter of workpiece [mm]
- D2: Minimum diameter of workpiece [mm]
- vc: Cutting speed [m/min]
- N: The number of pass = (D1-D2)/d/2

#### Grooving



#### Constant revolution per minute

$$T = \frac{60 \times (D_1 - D_2)}{2 \times fn \times n}$$


## Constant cutting speed

$$T_1 = \frac{60 \times \pi \times (D_1 + D_2) \times (D_1 - D_2)}{4000 \times fn \times vc}$$

## T: Machining time [sec]

- T1: Machining time before the maximum rpm[sec]
- L: Width of machining [mm]
- fn: Feed per revolution [mm/rev]
- n: Revolution per minute [min-1]
- D1: Maximum diameter of workpiece [mm]
- D2: Minimum diameter of workpiece [mm]
- vc: Cutting speed [m/min]

#### **Parting**



#### Constant revolution per minute

$$T = \frac{60 \times D_1}{2 \times fn \times n}$$

#### Constant cutting speed

$$T_1 = \frac{60 \times \pi \times (D_1 + D_3) (D_1 - D_3)}{4000 \times fn \times vc}$$

$$T_3 = T_1 + \frac{60 \times D_3}{2 \times fn \times n_{max}}$$

- T: Machining time [sec]
- T1: Machining time before the maximum rpm[sec]
- T3: Machining time till maximum RPM[sec]
- fn: Feed per revolution [mm/rev]
- n: Revolution per minute [min-1]
- nmax: Maximum revolution per minute [min-1]
- D1: Maximum diameter of workpiece [mm]
- D3: Maximum diameter at maximum RPM [mm]
- vc: Cutting speed [m/min]

# **Technical Information for Turning**

## The affects of cutting condition


The most desirable machining means short machining time, long tool life and good precision
 This is the reason that proper cutting condition for each tools should be selected according to material's properties, hardness, shapes, the efficiency of machine

## Cutting speed

Workpiece: S45C (180HB)Tool life criterion: VB = 0.2 mm

Depth of cut: 1.5 mmFeed: 0.3 mm/revHolder: PCLNR2525-M12

• Insert: CNMG120408, Dry cutting




Workpiece: STS304 (200HB)Tool life criterion: VB = 0.2 mm

Depth of cut: 1.5 mmFeed: 0.3 mm/rev

• Holder: PCLNR2525-M12

Insert: CNMG120408, Dry cutting




Workpiece: GC300 (180HB)Tool life criterion: VB = 0.2 mm

• Depth of cut: 1.5 mm • Feed: 0.3 mm/rev

· Holder: PCLNR2525-M12

· Insert: CNMG120408, Dry cutting



## Cutting Speed's effects

• When the cutting speed increases up to 20% in an application, the tool life respectively decreases down 50% Although inversely, if the cutting speed increases up to 50% the tool life decreases 20%. On the other hand if cutting speed is too low (20-40m/min) Tool life shortens due to vibration

#### Feed

• The feed rate in turning means the progressed interval of a distance in a work piece within 1 revolution The feed rate in a milling application means the table feed divided by number of teeth of cutter (feed rate per tooth)


#### The effects of feed

- · When the feed rate decreases the flank wear is increased. When the feed rate is too low, the tool life shortens radically
- · When the feed rate increases, the flank wear increases due to high temperatures, however the feed rates effects tool life less than the cutting speed. And higher feed rates improve machining efficiency

· Workpiece: SNCN431 · Grade: ST20

· Cutting speed: 200 m/min

• Depth of cut: 1.0 mm · Cutting time: 10 min



## Depth of cut


· Determined by the required allowances in machining a material and the capacity the machine can tolerate There are cutting limits according to the different shapes and sizes of the insert

· Workpiece: SNCN431

· Grade: ST20

· Cutting speed: 200 m/min


· Feed: 0.2 mm/rev · Cutting time: 10 min (Relationship between depth of cut and flank wear in steel turning)



# The effect of a depth of cut

- · The depth of cut does not have a big influence on tool life
- · When the depth of cut is small the work piece is not cut but rather rubbed. In these cases, machine off the work hardened parts that decrease tool life
- · When machining a cast skin or milling scale smaller depth of cuts usually cause chipping and abnormal wear because of hard impurities in the surface of the work piece

(Surface parts including mill scale Roughing)



# **Technical Information for Turning**

## Relief angle

· Relief angle avoids the friction between workpiece and relief face and makes cutting edge move along workpiece easily


#### • Relationship between various relief angle and flank wear

#### **Affects**

- 1. If relief angle is big Flank wear decreases
- 2. If relief angle is big Cutting edge strength weakens
- 3. If relief angle is small Chattering occurs

#### Selection system

- 1. Hard workpiece/When strong cutting edge is needed
  - Low relief angle
- 2. Soft workpiece/Workpiece turning to work hardening easily
  - High relief angle




· Workpiece: SNCM431 (HB)

Grade: P20Depth of cut: 1 mm

• Feed: 0.32 mm/rev

• Cutting time: 20 min




## Side cutting edge angle

 Side cutting edge angle has big influence on chip flow and cutting force therefore proper Side cutting edge angle is very important


#### Side cutting edge angle and chip thickness

- As side cutting edge angle is getting bigger chips are getting thinner and wider (refer to left picture)
- At the same feed and depth of cut with approach angle 0° Chip thickness is the same as feed (t = fn) and chip width is equal to depth of cut (W=ap)


 $t_1 = 0.97t$ ,  $W_1 = 1.04W$  $t_2 = 0.87t$ ,  $W_2 = 1.15W$ 



Approach angle 0°



② Approach angle 15°



3 Approach angle 30°

### • Side cutting edge angle and 3 cutting forces


#### **Affects**

- Big side cutting edge angle with the same feed makes chip attaching length longer and chip thickness thinner. So that cutting forces scatter to long cutting edge therefore tool life gets longer
- 2. Big side cutting edge angle for machining long bars can cause bending

#### Selection system

- 1.Deep depth of cut finishing/Long thin workpiece/Low machine rigidity
- Side cutting edge angle
- 2.Hard and high calorific power workpiece/Roughing big workpiece/ High machine rigidity - Side cutting edge angle

- Workpiece : SCM440 (HB250)
- · Grade: TNGA220412
- vc: 100 m/min
- ap: 4 mm
- fn: 0.45 mm/rev




## Side cutting edge angle and cutting load

# fn (mm/rev) fn (mm/rev) 2 "Force P is scattered to P1, P2." ① "Force P is loaded."

As approach angle gets bigger Back force gets bigger and feed force gets smaller

#### Side cutting edge angle and tool life



### Side cutting edge angle and cutting performance

Specification	Low  Approach angle  High
Wear rate	High   ← Low
Workpiece	Easy to cut material   Difficult to cut material
Machining power	Small ∢ Big
Chatter	Hard to occur
How to machine	Finishing   → Roughing
Workpiece rigidity	Long thin workpiece ◆ Thick workpiece
Machine rigidity	In case of low rigidity ◀────── In case of high rigidity

· Grade: P20

## End cutting edge angle

• It affects machined surface to prevent interference between surface of workpiece and insert


#### **Affects**

- 1. If end cutting edge angle reduces cutting edge get stronger but cutting heat generated by machining increases
- 2. Small end cutting edge angle can cause chattering due to the increases cutting force

#### Nose-R

- · Nose-R affects not only surface roughness but strength of cutting edge
- In general, It's desirable that Nose-R is 2~3 times bigger than feed


#### Nose R and surface finish



· Workpiece: SNCM439, HB200

· Grade: P20 • vc: 120 m/min • ap: 0.5 mm

#### Nose R and tool life




· Workpiece: SCM440, HB280

· Grade: P10

• vc: 100 m/min, ap: 0.5 mm

• fn: 0.3 mm/rev

## Nose R and wear of tool



· Workpiece: SNCM439, HB200

· Grade: P10

• vc: 140 m/min, ap: 2 mm

• fn: 0.2 mm/rev, T: 10 min



# **Technical Information for Turning**


### Nose-R

#### **Affects**

- 1. Big Nose-R improves surface finish
- 2. Big Nose-R improves cutting edge strength
- 3. Big Nose-R reduces flank wear and crater wear
- 4. Too big Nose-R causes chattering due to increased cutting force

#### Selection system

- For finishing with small depth of cut/long and thin workpiece/ When machine power is low - Small Nose-R
- 2. For applications that need strong cutting edge such as intermittent and machining mill scale/For roughing of big workpiece/When the machine power is strong eough Big Nose-R



### • Relationship between nose radius, feed and various surface roughness

Nose R Feed (mm/rev)	0.4	0.8	1.2
0.15			
0.26			
0.46			

## Cutting edge shape and the affects

#### • Rake angle (α)


Rake angle has big influence on cutting force, chip flow and tool life

#### **Affects**


- 1. High rake angle results in good suface finish
- 2. As the rake angle increases by 1° Machining power decreases by 1%.
- 3. High rake angle weakens cutting edge

#### Selection system


- For hard workpiece/For applications that need strong cutting edge such as interrupted and machining mill scale - Low rake angle
- For soft workpiece/Easy to cut material/When the rigidity of machine power and workpiece is low
   High rake angle




Principal force (kg)



### • Rake angle and the direction of chip flow



In order to prevent machined surface from damages Avoid nega, posi combination.  $\gamma : \text{nega (-)} \quad \lambda : \text{posi (+)}$ 



## Selecting proper tools

• Nowadays, It's very difficult to select the best tools in complicating tooling system and various cutting conditions However, It can be simplified by classifying basic factors below

#### Selection of inserts and tool holder

Listed below is the basic factors and choose B according to A

#### A: Basic factors

- · Workpiece material
- · Workpiece shape
- · Workpiece size
- · Hardness of workpiece
- · Surface roughness of workpiece (before machining)
- · Surface finish required
- · Type of lathe machine
- · Condition of lathe machine (rigidity, power etc)
- · Horse power of machine
- · Clamping method of workpiece

#### B: Selection system

- ① Select as big approach angle as possible
- 2 Select as big shank as possible
- 3 Select as strong cutting edge of insert as possible
- 4 Select as big nose radius as possible
- ⑤ In finishing, Select the insert using many corners
- 6 Select as small insert as possible
- ② Cutting speed should be determined carefully according to cutting conditions
- ® Select as deep depth of cut as possible
- 9 Select as fast feed as possible
- © Cutting condition should be determined within chip breaker application ranges

# **Technical Information for Turning**

# **○** Trouble shooting

	Tool failur	e	Cause	Solution
Crater wear			Improper grade     Excessive cutting condition	Choose harder grade     Decrease cutting condition
Fracture			Improper grade     Excessive feed     Shorten cutting edge strength     Insufficient rigidity of holder	Choose tougher grade Decrease feed Apply to large honed or chamfered edge Choose bigger size holder
Plastic deforma	ation		Improper grade     Excessive cutting condition     High cutting temperature	Choose harder grade Decrease cutting condition Choose grade wich heat conductivity are big
Wear on nose r (Flank wear)	radius		When the hardness of workpiece is too high compare with tool     When machinig surface hardened workpiece     Improper grade     Excessive cutting speed     Too small relief angle     Too low feed	Choose harder grade Decrease cutting speed Choose lager relief angle Increase feed
Thermal crack		Contract of the same	Expansion and shrinking by cutting temperature     Improper grade (*Specially milling operation)	Apply to dry cutting     (In case of wet cutting, use enough coolant)     Choose tougher grade
Chipping			<ul> <li>Improper grade</li> <li>Excessive feed</li> <li>Shorten cutting edge strength</li> <li>Insufficient rigidity of holder</li> </ul>	<ul><li>Choose tougher grade</li><li>Decrease feed</li><li>Apply to large honing or chamfer edge</li><li>Choose bigger size holder</li></ul>
Notch wear		Marin To	Surface hardened workpiece     Friction due to bad chip geometry     (Generate vibration)	Choose harder grade     Improve chip control form large rake angle
Flaking			Deposition on cutting edge     Bad chip control	Improve cutting performance fromd large rake angle     Apply to chip pocket with big size
Complete brea	akage		Unusable condition due to wear off the most parts of cutting edge by progress of wear	<ul> <li>Reduce the feed rate.</li> <li>Reduce the depth of cut.</li> <li>Select a tougher grade.</li> <li>Select a stronger chipbreaker.</li> <li>Select a thicker insert.</li> </ul>
Built-up edge		100	Slow cutting speed     Sticky materials	Increase cutting speed.     Use more positive rake geometry.     Use tougher grade

# Types of tool failure and trouble shooting

										Solu	ution								
		Cut	ting c	ondit	ions	Selec	cting i	nsert (	grade	Tool shape				Machine clamping					
Troubles	Causes	Cutting speed	Feed	Depth of cut	Coolant	Select harder grade	Select tougher grade	Select better heat-impact resistance grade	Select better adhesion resistance grade	Chip breaker valuation	Rake angle	Nose radius	Side cutting edge angle	Cutting edge strength Honing	Improving insert precision M class → G class	Improving holder rigidity	Clamping workpiece	Holder overhang	Machine vibration
Poor precision Unstable machining	Insert precision is variable														•				
size	Workpiece, Separation of tool									•	t	1				•	•	•	•
Cutting edge back thrust is big It's necessary to adjust	Flank wear increase					•						1							
because machining precision changes during operation.	Cutting condition is improper	1	1			•													
	Weakened cutting force by increasing wear of tool	1			Wet cutting				•	•	t	1		1	•				
	Cutting edge chipping		1	1			•			•		1		1			•	•	•
Poor surface roughness for	Adhesion, built-up edge	t	1		Wet cutting				•	•	t			1	•				
<b>finishing</b> Criterion of tool life.	Improper cutting conditions	1	1	1	Wet cutting														
	Improper tool and shape of cutting edge									•		1		1	•				
	Vibration, chattering	1	1	1	Wet cutting		•			•	t	1		1		•	•	•	•
Cutting heat generation Poor machining precision	Improper cutting conditions	1	1	1		•													
and short tool life by cutting heat	Improper tool and shape of cutting edge									•	t			1					
Burr, chipping, nap	Improper cutting conditions	1	1		Wet cutting	•													
steel, aluminum (burr)	Wear on the tool, improper shape of cutting edge								•	•	1	1		1					
Cast iron	Improper cutting conditions		1	1		•													
(Weak chipping)	Wear on the tool, improper shape of cutting edge									•	1	1		1		•	•	•	•
Soft atool (non)	Improper cutting conditions	1	1		Wet cutting	•													
Soft steel (nap)	Wear on the tool, improper shape of cutting edge								•	•	1			1					

**↑**: Increase **↓**: Decrease **•**: use **•**: Correct use

# **○** Tool life criterion

## • KS B0813


	0.2 mm	Precision light cutting , Finishing in nonferrous alloy		
Flank	0.4 mm	Machining special steel		
wear width	0.7 mm	General cutting in cast iron, steel etc		
	1~1.25 mm General cutting in cast iron, steel etc			
Depth of crater wear	In general 0.05~0.1 mm			

# • ISO (B8688)

Tool life criterion	Application
Complete breakage	Machining special steel
Flank wear width VB = 0.3 mm	Even flank wear of cemented carbides, Ceramic tool
VBmax = 0.5 mm	Uneven flank wear
Crater wear width KT = 0.06+0.3fmm (f:mm/rev)	Cemented carbides tool
Criterion by surface roughness 1, 1.6, 2.5, 4, 6.3, 10umRa	When surface roughness is important

# **Technical Information for Milling**

## Milling cutter shape and designation




## • The terminology and functions of cutting edge angle

No.	Tool failure	Symbol	Function	Effects
1	Axial rake angle	A.R	Chip flow direction, Adhesion	Positive: Excellent cutting, built-up edge prevented
2	Radial rake angle	R.R	Affecting on thrust	Negative: Excellent chip control
3	Approach angle	A.A	Chip thickness, Determines flow direction	(+): Chip thickness become thinner, cutting force could be reduced
4	True rake angle	T.A	Effective rake angle	(+): Better cutting. Preventing adhesion, Weakening cutting edge strength (-): Cutting edge strength increases, easy to adhere
5	Cutting edge inclination angle	I.A	Determines chip flow direction	(+): Good chip flow, cutting force could decreases, Comer edge strength weakens
6	Relief angle	F.A	Controlling cutting edge strenght, tool life and chattering	Surface roughness increases as F.A gets close to 0 degree

## Features by combination of rake angle

	Double positive angle	Double negative angle	Posi - Negative angle	Nega - Positive angle
Division	A-R(+)	A·R(-)	A·R(+)	A·R(-)
Use	General machining of steel, cast iron, stainless steel     Machining soft steel that brings about built-up edge easily     Machining material having tendency to poor surface roughness		Machining difficult to cut material     Roughing with deep depth of cut and wide width of cut in steel and cast iron	Chip flows to center of cutter body
Advantages	As for tough workpiece material It prevents built-up edge to improve surface roughness     Low cutting load and better machinability	Strong cutting edge     Roughing of workpiece that has bad surface condition containing sand, mill scale     Double sided inserts can be applied(Economical)     Good chip control	Good chip flow and machinability.     Suitable for machining of difficult-to-cut material	-
Disadvantages	Weak cutting edge strength     Only single sided inserts are available (No economical)     Machine and cutter need enough power and rigidity	Machine and cutter need enough power and rigidity	Only single sided inserts are available (No economical)	Since the chips flows toward the center of cutter. Chips scratch on machined surface     Bad chip flow     No economical

# Major cutting formulas



### Cutting speed

$$vc = \frac{\pi \cdot D \cdot n}{1000} (m/min)$$

- vc: Cutting speed (m/min)
- · D: Diameter of tool (mm)
- n: Revolution per minute (min-1)
- π: Circular constant (3.14)

#### Feed

$$fz = \frac{vf}{z \cdot n} (mm/t)$$

- fz: Feed per tooth (mm/t) vf: Feed per minute (mm/min)
- n: Revolution per minute (min-1)
- · z: Number of tooth

#### Chip removal amount

$$Q = \frac{Lxvfxap}{1000} (cm^3/min)$$

- Q: Chip removal amount (cm³/min)
- L: Width of cut (mm)
- vf: Table feed (mm/min)
- · ap: Depth of cut (mm)

## Power

$$P_{kw} = \frac{Q \times kc}{60 \times 102 \times \eta}$$

$$P_{hp} = \frac{P_{kw}}{0.75}$$

- Pc: Power requirement (kW)
- H: Horse power requirement (hp) (mm/min)
- Q: Chip removal amount (cm³/min)
- kc: Specific cutting resistance (kgf/mm³)
- η: Machine efficiency rate (0.7~0.8)

#### Machining time

$$T = \frac{60 \text{ x Lt}}{\text{vf}} \text{ (sec)}$$

- T: Machining time (sec)
- Lt: Total length of table feed (mm) (= Lw+D+2R)
- Lw: The length of workpiece (mm)
- D: The diameter of cutter body (mm)
- vf: Table feed (mm/min)
- R: Relief length (mm)

### True rake angle/Cutting edge inclination angle

True rake angle tan(T) = tan(R) x cos(AA) + tan(A) x sin(C)Cutting edge inclination angle tan(I) = tan(A) x cos(AA) - tan(R) x sin(C)



## Values of specific cutting resistance

Workniego	Tensile strength	Spe	cific cutti to vari	ng resista ous feed k	nce accord c(MPa)	ding
Workpiece	(kg/mm²) and - hardness	0.1 (mm/t)	0.2 (mm/t)	0.3 (mm/t)	0.4 (mm/t)	0.6 (mm/t)
Soft steel	52	220	195	182	170	158
Medium carbon steel	62	198	180	173	160	157
High carbon steel	72	252	220	204	185	174
Tool steel	67	198	180	173	170	160
Tool steel	77	203	180	175	170	158
Chrome manganese steel	77	230	200	188	175	166
Chrome manganese steel	63	275	230	206	180	178
Chrome molybdenum steel	73	254	225	214	200	180
Chrome molybdenum steel	60	218	200	186	180	167
Nickel Chrome molybdenum steel	94	200	180	168	160	150
Nickel Chrome molybdenum steel	HB352	210	190	176	170	153
Cast steel	52	280	250	232	220	204
Hardened cast iron	HRC46	300	270	250	240	220
Meehanite cast iron	36	218	200	175	160	147
Gray cast iron	HB200	175	140	124	105	97
Brass	50	115	95	80	70	63
Light alloy (AI - Mg)	16	58	48	40	35	32
Light alloy (Al - Si)	20	70	60	52	45	39

# Ohip removal amount (cm³/min) per rated horse power

Workpiece	lated horse power	5Нр	10Hp	20Hp	30Hp	40Hp	50Hp
	Soft	32	75	163	295	425	570
Steel	Medium	26	55	127	212	310	425
	hard	18	41	93	163	228	310
Cast	Soft	52	116	260	455	670	880
	Medium	32	75	163	295	425	570
iron	hard	26	55	127	212	310	425
Duame	Soft	77	163	390	670	980	1,280
Bronze	Medium	54	118	275	490	700	910
Brass	hard	26	55	127	245	325	425
Aluminum		90	195	440	780	1,110	1,500

## Selection of MILL-MAX diameter (D)


## Selection by machine rigidity

Machine horse power (PS)	10~15	15~20	Over 20
Proper cutter body specification (mm)	Ø80~Ø100	Ø125~Ø160	Ø160~Ø200


#### Selection by machine rigidity

Workpiece	E	δ
Steel	+20°~-10°	3:2
Cast iron	Under +50°	5:4
Light alloy	Under +40°	5:3

- D: External diameter of cutter body
- D<sub>1</sub>: Width of workpiece
- d: Projected part of cutter body
- E: Engage angle
- δ: Ratio of cutter body and width of workpiece (D: D1)



## Selection by machining time



## • Selection by number of tooth

Workpiece	Steel	Cast iron	Light alloy
Number of tooth	Dx (1~1.5)	Dx (1~4)	D×1+α

ex) D =  $\emptyset 100 \Rightarrow 4$ "  $x(1\sim1.5) = 4\sim6$ 

D is the size of cutter body converted into inch size

## Classification of surface roughness

Туре	Symbol	How to calculate	Measured value
Maximum height	Rmax	<ul> <li>The distance between the top of profile peak line and the bottom of profile valley line on this sampled portion is measured in the longitudinal magnification direction of roughness curve (Expressed by unit: μ)</li> <li>Exclude extraordinary values (too small or big) that look like grooves or mountains</li> </ul>	Rmax Rmax Rmax Rmax Rmax Rmax $\ell_2$ $\ell_3$ $\ell_4$ $\ell_5$
+10 point mean roughness	Rz	• Sampled from the roughness curve in the direction of its mean line, the sum of the average value of absolute value of the highest profile peaks and the depths of five deepest profile valleys measured in the vertical magnification is expressed by micro meter ( $\mu$ )	Measuring length £
Arithmetic mean roughness	Ra	<ul> <li>Sampling only the reference length from the roughness curve in the direction of mean line , taking X-axis in the direction of mean line and Y-axis in the direction of longitudinal magnification of this sampled part and is expressed by micro meter ( μ )</li> <li>Generally, Read measured value by Ra measurer</li> </ul>	Measured surface roughness curve f  Measuring length #  Measuring length #  Center line  Measuring length #

Finish m	ark	$\nabla\nabla\nabla\nabla$	$\nabla\nabla\nabla$	$\nabla\nabla$	$\nabla$	~
Cuufaaa	Rmax	0.8s	6.3s	25s	100s	
Surface roughness	Rz	0.8z	6.3z	25z	100z	Unspecified
rouginiess	Ra	0.2a	1.6a	6.3a	25a	

# Trouble shooting for milling

							Solution	s				
Trouble	Causes		Cutting o	condition	ns			Tool shap	ре		Inser	t grade
		Cutting speed	Depth of cut	Feed	Coolant	Rake angle	Relief angle	Approach angle	Chattering at cutting edge	Nose radius	Toughness	Hardness
Flank wear	Improper insert grade     Improper cutting conditions     Chattering	1		t			t	1		1		t
Crater wear	Improper cutting conditions     Improper insert grade	1	1	1	•	1	t			ţ		t
Chipping	Lack of insert toughness     Excessive feed     Excessive cutting load			1		1	1	1		1	t	
Built-up edge	Improper cutting conditions     Improper cutting edge shape     Improper insert grade	t	1			1				1		
Chattering	Improper cutting conditions     Lack of number of cutting teeth     Improper cutting edge shape     Bad chip flow     Unstable workpiece clamping		1	1	•	1		t	1	1		
Poor surface finish	Built-up edge     Improper cutting conditions     Chattering     Bad chip flow	t	1	1	•	1			1	t		
Thermal crack	Improper cutting conditions     Improper insert grade	1	1	1	•	1				<b>†</b>	t	
Fracture	Improper insert grade     Excessive cutting load     Bad chip flow     Chattering     Excessive overhang		ţ	•	•						1	

**↑**: Increase **↓**: Decrease **•**: use **•**: Correct use


# General formulas for milling

# Machine efficiency rate (η)

Power transmission mode	Efficiency rate (E)	Reference
Principal axis direct connection driving	0.90	
Belt driving	0.85	Double connection: 0.85 × 0.85 ≒ 0.70
Starting driving	0.75	
Oil pressure driving	0.60~0.90	


# **Technical Information for Tapers**

# Morse taper (Tang type)



														(111111)
MTNo.	Taper	Taper angle (a)	D	а	D <sub>1</sub>	<b>d</b> 1	Q1	Q2	<b>d</b> <sub>2</sub>	b	С	е	R	r
0	<u>1</u> 19.212	1°29′27″	9.045	3	9.201	6.104	56.5	59.5	6.0	3.9	6.5	10.5	4	1
1	20.047	1°25′43″	12.065	3.5	12.240	8.972	62.0	65.5	8.7	5.2	8.5	13.5	5	1.2
2	20.020	1°25′50″	17.780	5	18.030	14.034	75.0	80.0	13.5	6.3	10	16	6	1.6
3	19.922	1°26′16″	23.825	5	24.076	19.107	94.0	99.0	18.5	7.9	13	20	7	2
4	1 19.254	1°29′15″	31.267	6.5	31.605	25.164	117.5	124.0	24.5	11.9	16	24	8	2.5
5	19.002	1°30′26″	44.399	6.5	4.741	36.531	149.5	156.0	35.7	15.9	19	29	10	3
6	<u>1</u> 19.180	1°29′36″	63.348	8	63.765	52.399	210.0	218.0	51.0	19.0	27	40	13	4
7	<u>1</u> 19.231	1°29′22″	83.058	10	83.578	68.186	286.0	296.0	66.8	28.6	35	54	19	5

# Morse taper (Screw type)




MTNo.	Taper	Taper angle (a)	D	а	<b>D</b> <sub>1</sub>	d	Q1	$Q_2$	d₁	<b>d</b> <sub>2</sub>	k	t	r
0	<u>1</u> 19.212	1°29′27″	9.045	3	9.201	6.442	50	53	6	-		4	0.2
1	20.047	1°25′43″	12.065	3.5	12.230	9.396	53.5	57	9	M6	16	5	0.2
2	20.020	1°25′50″	17.780	5	18.030	14.583	64	69	14	M10	24	5	0.2
3	19.922	1°26′16″	23.825	5	24.076	19.759	81	86	19	M12	28	7	0.6
4	<u>1</u> 19.254	1°29′15″	31.267	6.5	31.605	25.943	102.5	109	25	M16	32	9	1
5	19.002	1°30′26″	44.399	6.5	4.741	37.584	129.5	136	35.7	M20	40	9	2.5
6	<u>1</u> 19.180	1°29′36″	63.348	8	63.765	53.859	182	190	51	M24	50	12	4
7	<u>1</u> 19.231	1°29′22″	83.058	10	83.578	70.058	250	260	65	M33	80	18.5	5

(mm)


(mm)

# Brown sharp taper (Screw type)



B&S No.	D	а	<b>D</b> <sub>1</sub>	d	d <sub>1</sub>	Q1	Q <sub>2</sub>	t	r	d <sub>2</sub>	K
4	10.221	2.4	10.321	8.890	8.0	31.0	34.2	2	0.2	-	-
5	13.286	2.4	13.386	11.430	10.0	44.4	46.8	3	0.2	-	-
6	15.229	2.4	15.330	12.700	11.0	60.0	62.7	3	0.2	M 8(1/4)	20
7	18.424	2.4	18.524	15.240	14.0	76.2	78.6	4	0.2	M10(3/8)	24
8	22.828	3.2	22.962	19.090	17.0	90.5	93.7	4	0.6	M12(1/2)	28
9	27.104	3.2	27.238	22.863	21.0	101.6	104.8	4	0.6	M12(1/2)	28
10	32.749	3.2	32.887	26.534	24.0	144.5	147.7	5	1.0	M16(5/8)	32
11	38.905	3.2	39.039	31.749	29.0	171.4	174.6	5	1.0	M16(5/8)	32
12	45.641	3.2	45.774	38.103	35.0	181.0	184.2	6	2.5	M20(3/4)	40
13	52.654	3.2	52.787	44.451	41.0	196.8	200.0	6	3.0	M20(3/4)	40
14	59.533	3.2	59.666	50.800	47.0	209.6	212.8	7	4.0	M24(1)	40
15	66.408	3.2	66.541	57.150	53.0	222.2	225.4	7	4.0	M24(1)	50
16	73.292	3.2	73.425	63.500	59.0	35.0	238.2	8	5.0	M30(11/8)	60

# **Brown sharp taper (Tang type)**




B&S No.	D	а	<b>D</b> <sub>1</sub>	<b>d</b> 1	$\mathbf{d}_2$	Q1	$Q_2$	b	С	е	R	r
4	10.221	2.4	10.321	8.458	8.1	42.1	44.5	5.5	8.7	14.4	7.9	1.3
5	13.286	2.4	13.386	10.962	10.7	55.6	58.0	6.3	9.5	16.2	7.9	1.5
6	15.229	2.4	15.330	12.167	11.7	73.0	75.4	7.1	11.1	18.0	7.9	1.5
7	18.424	2.4	18.524	14.675	14.2	89.7	92.1	7.9	11.9	20.3	9.5	1.8
8	22.828	3.2	22.962	18.453.	18.0	104.8	108.0	8.7	12.7	22.0	9.5	2.0
9	28.104	3.2	27.238	22.200	21.8	117.5	120.7	9.5	14.3	25.4	11.1	2.5
10	32.749	3.2	32.887	25.751	25.7	162.7	165.9	11.1	16.7	28.1	11.1	2.8
11	38.905	3.2	39.039	30.985	30.7	189.7	192.9	11.1	16.7	30.0	12.7	3.3
12	45.641	3.2	45.774	37.246	37.1	201.6	204.8	12.7	190	32.5	12.7	3.8
13	52.654	3.2	52.787	43.589	43.4	217.5	220.7	12.7	19.0	35.7	15.9	4.3
14	59.533	3.2	59.666	49.841	49.8	232.6	235.8	14.2	21.4	41.2	19.0	4.8
15	66.408	3.2	66.541	56.186	56.1	245.3	248.5	14.2	21.4	44.4	22.2	5.3
16	73.292	3.2	73.425	62.441	62.2	260.4	263.6	15.8	23.8	50.0	25.4	5.8


# **Technical Information for Tapers**

(mm)

## Standard taper of american milling machine




										(mm)
Dimensions	D	<b>D</b> <sub>1</sub>	L	Q <sub>1</sub>	М	$Q_2$	Qз	а	t	b
$1\frac{1}{4}$	31.750	17.40-0.29	70	20	UNC $\frac{1}{2}''$	24	50	1.6	15.9	6
$1\frac{3}{4}$	44.450	25.32 <sup>-0.30</sup> <sub>-0.384</sub>	95	25	UNC $\frac{5''}{8}$	30	60	1.6	15.9	22.5
$2\frac{3}{4}$	69.850	39.60 <sup>- 0.31</sup> <sub>- 0.41</sub>	130	25	UNC 1"	45	90	3.2	25.4	35
4 1/4	107.950	60.20 0.34 0.46	210	45	UNC 1 1"	56	110	3.2	25.4	60
	$1\frac{1}{4}$ $1\frac{3}{4}$ $2\frac{3}{4}$	$   \begin{array}{ccc}     1\frac{1}{4} & 31.750 \\     1\frac{3}{4} & 44.450 \\     2\frac{3}{4} & 69.850   \end{array} $	$ \begin{array}{c cccc} 1\frac{1}{4} & 31.750 & 17.40_{-0.36}^{-0.29} \\ 1\frac{3}{4} & 44.450 & 25.32_{-0.384}^{-0.31} \\ 2\frac{3}{4} & 69.850 & 39.60_{-0.41}^{-0.31} \end{array} $	$ \begin{array}{c ccccc} 1\frac{1}{4} & 31.750 & 17.40^{-0.29}_{-0.36} & 70 \\ 1\frac{3}{4} & 44.450 & 25.32^{-0.30}_{-0.384} & 95 \\ 2\frac{3}{4} & 69.850 & 39.60^{-0.31}_{-0.41} & 130 \end{array} $	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	$1\frac{1}{4}$ 31.750 17.40 $\frac{0.29}{0.36}$ 70 20 UNC $\frac{1}{2}$ 24 $1\frac{3}{4}$ 44.450 25.32 $\frac{0.30}{0.384}$ 95 25 UNC $\frac{5}{8}$ 30 $2\frac{3}{4}$ 69.850 39.60 $\frac{0.31}{0.41}$ 130 25 UNC 1" 45	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	$1\frac{1}{4}$ 31.750 17.40 $\frac{0.29}{0.36}$ 70 20 UNC $\frac{1}{2}$ 24 50 1.6 $1\frac{3}{4}$ 44.450 25.32 $\frac{0.30}{0.384}$ 95 25 UNC $\frac{5}{8}$ 30 60 1.6 $2\frac{3}{4}$ 69.850 39.60 $\frac{0.31}{0.41}$ 130 25 UNC 1" 45 90 3.2	Dimensions         D         D1         L $\ell_1$ M $\ell_2$ $\ell_3$ a         t $1\frac{1}{4}$ 31.750         17.40 $\frac{0.29}{0.36}$ 70         20         UNC $\frac{1}{2}$ 24         50         1.6         15.9 $1\frac{3}{4}$ 44.450         25.32 $\frac{0.30}{0.384}$ 95         25         UNC $\frac{5}{8}$ 30         60         1.6         15.9 $2\frac{3}{4}$ 69.850         39.60 $\frac{0.31}{0.41}$ 130         25         UNC 1"         45         90         3.2         25.4 $4\frac{1}{4}$ 107.950         60.20 $\frac{0.34}{0.046}$ 210         45         UNC 1 $\frac{1}{4}$ 56         110         3.2         25.4



BT No.	D <sub>1</sub>	$\mathbf{D}_2$	t <sub>1</sub>	<b>t</b> 2	<b>t</b> <sub>3</sub>	<b>t</b> 4	d <sub>1</sub>	d₃	L	М	<b>b</b> 1	<b>t</b> 5	<b>d</b> 5
35	53	43	22	10	14.6	2	38.1	13	56.5	M12×1.75	16.1	19.6	21.62
40	63	52	25	10	16.6	2	44.45	17	65.4	M16×2	16.1	22.6	25.3
45	85	73	30	12	21.2	3	57.15	21	82.8	M20×25	19.3	29.1	33.1
50	100	85	35	15	23.2	3	69.85	25	101.8	M24×3	25.7	35.4	40.1
60	155	135	45	20	28.2	3	107.95	31	161.8	M30×3.5	25.7	60.1	60.7


# HSK shank (DIN 69893)




																			(mm)
HSK No.	<b>b</b> <sub>1</sub>	$\mathbf{b}_2$	<b>b</b> 3	<b>d</b> 1	<b>d</b> <sub>2</sub>	<b>d</b> ₃	d <sub>4</sub>	<b>d</b> 5	<b>d</b> 6	<b>d</b> 7	d₃	<b>d</b> 9	<b>d</b> 10	<b>d</b> 11	<b>d</b> <sub>12</sub>	<b>d</b> 13	<b>d</b> <sub>14</sub>	<b>a</b> 1	<b>a</b> 2
50	10.54	12	14	50	38	36.90	42	43	59.3	7	26	32	29	M16X1	10	6.8	6.8	13.997	7.648
63	12.5	16	14	63	48	46.53	53	55	72.3	7	34	40	37	M18X1	12	8	8.4	17.862	9.25
100	20	20	14	100	75	72,80	85	92	109.75	7	53	63	58	M24X1.5	16	12	12	27.329	15.00

																										(mm)
HSK No.	<b>f</b> 1	<b>f</b> <sub>2</sub>	<b>f</b> <sub>3</sub>	<b>f</b> 4	<b>b</b> <sub>1</sub>	<b>b</b> <sub>2</sub>	$L_1$	L <sub>2</sub>	L <sub>3</sub>	L <sub>4</sub>	$L_5$	L <sub>6</sub>	L <sub>7</sub>	L	L <sub>9</sub>	L <sub>10</sub>	L <sub>11</sub>	<b>L</b> <sub>12</sub>	<b>r</b> 1	<b>r</b> 2	<b>r</b> 3	<b>r</b> 4	<b>ľ</b> 5	<b>r</b> 6	<b>ľ</b> 7	<b>r</b> 8
50	26	42	18	3.75	2	15.5	25	5	11	7.5	4.5	14.13	10	10	23	3	1	19	1	1.5	2.38	6	0.5	1	2	6
63	26	42	18	3.75	28.5	20	32	6.3	14.7	10	6	18.13	10	12	24.5	3	1	21	1.2	1.5	3	8	0.6	1.5	3	8
100	29	45	20	3.75	44	31.5	50	10	24	15	10	28.56	12.5	16	28	3	1.5	24	2	2	3	12	1	1.5	3	10

# **Technical Information for Tapers**




											(111111)
Shank No	D <sub>1</sub>	$D_2$	<b>D</b> <sub>3</sub>	D <sub>4</sub>	<b>D</b> <sub>5</sub>	Lı	L2	L <sub>3</sub>	L	b	M
30	50.0	44.3	31.75	13	17.8	47.8	16.4	19.0	33.5	16.0	M12×1.75
40	63.5	56.2	44.45	17	24.5	68.4	22.8	25.0	42.5	16.1	M16×2
45	82.5	57.2	57.15	21	33.0	82.7	29.1	31.3	52.5	19.3	M20×2.5
50	97.5	91.2	68.85	25	40.1	101.7	35.5	37.7	61.5	25.7	M24×3



										(mm)
Shank No	D <sub>1</sub>	$\mathbf{D}_2$	M	<b>d</b> 1	d <sub>2</sub>	d₃	L <sub>1</sub>	L <sub>2</sub>	L₃	G
CAT40	63.5	56.36	M16×2	44.45	16.28	21.84	68.25	28.45	4.78	5/8-11
CAT45	82.55	75.41	M20×25	57.15	19.46	27.69	82.55	38.1	4.78	3/4-10
CAT50	98.43	91.29	M24×3	69.85	26.19	35.05	101.6	44.45	6.35	1-8

# Standard of milling cutter hole (KSB3203)



## Type A


TypeA				
Diameter	øDH7	Е	F	r
8	8 <sup>+ 0.015</sup>	8.9 + 0.25	2 + 0.16 + 0.06	0.4
10	10 + 0.015	11.5 + 0.25	3 + 0.16 + 0.06	0.4
13	13 + 0.018	14.6 + 0.25	3 + 0.16 + 0.06	0.6
16	16 <sup>+ 0.018</sup>	17.7 + 0.25	4 + 0.19 + 0.07	0.6
19	19 <sup>+ 0.021</sup>	21.1 + 0.25	5 + 0.19 + 0.07	1
22	22 + 0.021	24.1 + 0.25	6 + 0.19 + 0.07	1
27	27 + 0.021	29.8 + 0.25	7 + 0.23 + 0.08	1.2
32	32 + 0.025	34.8 + 0.25	8 + 0.23 + 0.08	1.2
40	40 + 0.025	43.5 + 0.3	10 + 0.23 + 0.08	1.2
50	50 + 0.025	53.5 + 0.3	12 + 0.23 + 0.095	1.6
60	60 + 0.030	64.2 + 0.3	14 + 0.275 + 0.095	1.6
70	70 + 0.030	75.0 <sup>+ 0.3</sup> 0	16 + 0.275 + 0.095	2
80	80 + 0.030	85.5 <sup>+0.3</sup> 0	18 + 0.275 + 0.095	2
100	100 + 0.035	107.0 + 0.3	24 + 0.32 + 0.11	2.5

# ● Type B

Diameter	øDH7	E	F	r
1 2	12.70 + 0.018	14.17 + 0.25	2.38 + 0.31 + 0.13	0.5
<u>5</u> 8	15.875 <sup>+ 0.018</sup>	17.74 + 0.25	3.18 <sup>+ 0.31</sup> + 0.13	0.8
3 4	19.050 + 0.021	20.89 + 0.25	3.18 <sup>+ 0.31</sup> + 0.13	0.8
7 8	22.225 + 0.021	24.07 + 0.25	3.18 <sup>+ 0.31</sup> + 0.13	0.8
1	25.40 <sup>+ 0.021</sup>	28.04 + 0.25	6.35 <sup>+ 0.31</sup> + 0.13	1.2
1 1/4	31.750 <sup>+0.025</sup>	35.18 <sup>+ 0.25</sup>	7.94 <sup>+ 0.32</sup> + 0.14	1.6
$1\frac{1}{2}$	38.10 + 0.025	42.32 <sup>+ 0.25</sup>	9.53 <sup>+ 0.89</sup> + 0.25	1.6
1 3/4	44.450 <sup>+</sup> 0.025	49.48 + 0.25	11.11 <sup>+ 0.89</sup> <sub>+ 0.25</sub>	1.6
2	50.80 + 0.03	55.83 <sup>+ 0.25</sup>	12.7 + 0.89 + 0.25	1.6
2 1 2	63.50 + 0.03	69.42 + 0.25	15.81 <sup>+ 0.89</sup> 15.25	1.6
3	76.20 <sup>+ 0.03</sup>	82.93 + 0.25	19.05 <sup>+ 0.89</sup> <sub>+ 0.25</sub>	2.4
3 1 2	88.90 + 0.035	98.81 + 0.25	22.23 <sup>+ 0.89</sup> <sub>+ 0.25</sub>	2.4
4	101.60 + 0.035	111.51 <sup>+</sup> 0.25	25.4 <sup>+ 0.89</sup> + 0.25	2.4
4-1-2	114.30 + 0.035	125.81 + 0.25	25.58 <sup>+ 0.89</sup> <sub>+ 0.25</sub>	3.2
5	127.0 + 0.04	140.08 + 0.25	31.75 <sup>+0.89</sup> <sub>+0.25</sub>	3.2

# **Technical Information for Endmills**

## Endmill's shape and names



## The comparison according to number of flute

#### • Features of number of flute

Ø10 mm	2 flutes	3 flutes	4 flutes			
Shape						
Cross section	44 mm²	46 mm <sup>2</sup>	48 mm²			
Ratio	56%	58%	61%			
Advantages	Good chip flow	Good chip flow	High rigidity			
Disadvantages	Weak rigidity	Difficult to measure external diameter	Bad chip flow			
Usages	Side facing, Grooving	Side facing, Grooving	Side cutting			
Usages	Multi-functional	Medium, finishing	Finishing			

#### Affection of number of flute

Specification	Major features	2 flutes	4 flutes
Tool rigidity	Torsional rigidity	0	0
Tool rigidity	Bending rigidity	0	0
Surface finish	Surface roughness	0	0
Surface Illisti	Machining precision	0	0
Obin control	Chip clogging	0	0
Chip control	Chip evacuation	0	0
Creating	Chip evacuation	0	0
Grooving	Grooving	0	0
Cido fooing	Surface finish	0	0
Side facing	Vibration	0	0

©: Excellent ○: Good

## • The differences between general endmills and high speed endmills

	General endmills	High speed endmills						
Cross section shape	Features	Cross section shape	Features					
	- Applied for Low speed, High depth of cut, Low feed - Low hardness workpiece(general steel, cast iron)		- Applied for high speed, low depth of cut, high feed - Useful for hardened workpiece such as die steel					

# Calculations of cutting condition

# Calculations of Cutting speed

$$vc = \frac{\pi \times D \times n}{1000} \qquad n = \frac{1000 \times vc}{\pi \times D}$$

### Calculations of feed speed

 $vf = n \times fn \text{ or } n \times fz \times z$ 

$$fn = \frac{vf}{n}$$
  $fz = \frac{fn}{z}$  or  $\frac{vf}{n \times z}$ 

vc: Cutting speed (m/min)


π: Circular constant (3.141592)

- vf: Feed speed (m/min)
- fn: Feed per revolution (mm/rev)
- D: Endmill diameter (mm)
- fz: Feed per flute (mm/t)
- n: Revolution per minute (min-1) z: Number of flute

## Ball endmills cutting speed calculation formulas

Revolution per minute	$n = \frac{vc \times 1000}{D \times \pi}$				
Cutting speed	$vc = \frac{D \times \pi \times n}{1000}$				
Feed per tooth	$fz = \frac{vf}{z \times n}$				
Feed per revolution	$fn = fz \times z$				
Feed speed	$vf = fz \times z \times n$				
Chip removal rate	$Q = ae \times ap \times vf$				

Effective diameter of Ball Endmill



$$D_{eff} = 2 \times \sqrt{DXap-ap^2} \frac{Calculation}{Table}$$

 $D_{eff} = D \times sin \left[ \beta \pm arccos \left( \frac{D-2ap}{D} \right) \right]$ 


# The affection of flute length

## Expression of aspect ratio

- Aspect ratio
- Q/d
- Ex) 3D, 15D, 22D

### Deformation rate according to length

- Deformation rate is reaction force against external force
- · Proportional to the cube of length
- Set flute length and overall length as short as possible
- The more flute the better rigidity
- · When flute width rate is narrower drill's rigidity is higher



 $\delta$  = Deformation volume  $\ell$  = Length of cut

**P** = Cutting force **E** = Elasticity coefficient

I = Inertia moment (I = 
$$\frac{\pi Q^4}{64}$$

• 
$$\delta$$
1:  $\delta$ 1 =  $8\delta$ 1 =  $\delta$ 2

# Spindle revolution conversion table (RPM) - external diameter


vc							Cuttii	ng spee	d (vc, m	/min)						
External	20	30	40	50	60	70	80	90	100	120	140	150	180	200	250	300
0.2	31,831	47,746	63,662	79,577	95,493	111,408	127,324	143,239	159,155	190,986	222,817	238,720	286,479	318,310	397,887	477,465
0.3	21,221	31,831	42,441	53,052	63,662	74,272	84,883	95,493	106,103	127,324	148,545	159,155	190,986	212,207	265,258	318,310
0.4	15,915	23,873	31,831	39,789	47,746	55,704	63,662	71,620	79,577	95,493	111,408	119,366	143,239	159,155	198,944	238,732
0.5	12,732	19,099	25,465	31,831	38,197	44,563	50,930	57,296	63,662	76,394	89,127	95,493	114,592	127,324	159,155	190,986
0.6	10,610	15,915	21,221	26,526	31,831	37,136	42,441	47,746	53,052	63,662	74,272	79,577	95,493	106,103	132,629	159,155
0.7	9,095	13,642	18,189	22,736	27,284	31,831	36,378	40,926	45,473	54,567	63,662	68,209	81,851	90,946	113,682	136,419
0.8	7,958	11,937	15,915	19,894	23,873	27,852	31,831	35,810	39,789	47,746	55,704	59,683	71,620	79,577	99,472	119,366
0.9	7,074	10,610	14,147	17,684	21,221	24,757	28,294	31,831	35,368	42,441	49,515	53,052	63,662	70,736	88,419	106,103
1	6,366	9,549	12,732	15,915	19,009	22,282	25,465	28,648	31,831	38,197	44,563	47,746	57,296	63,662	79,577	95,793
1.5	4,244	6,366	8,488	10,610	12,732	14,854	16,977	19,099	21,221	25,465	29,709	31,831	38,197	42,441	53,052	63,662
2	3,183	4,775	6,366	7,958	9,549	11,141	12,732	14,324	15,915	19,099	22,282	23,873	28,648	31,831	39,789	47,746
2.5	2,546	3,820	5,093	6,366	7,639	8,913	10,186	11,459	12,732	15,279	17,825	19,099	22,918	25,465	31,831	38,197
3	2,122	3,183	4,244	5,305	6,366	7,427	8,488	9,549	10,610	12,732	14,854	15,915	19,099	21,221	26,526	31,831
3.5	1,819	2,728	3,638	4,547	5,457	6,366	7,276	8,185	9,095	10,913	12,732	13,642	16,370	18,189	22,736	27,284
4	1,592	2,387	3,183	3,979	4,775	5,570	6,366	7,162	7,958	9,549	11,141	11,937	14,324	15,915	19,894	23,873
4.5	1,415	2,122	2,829	3,537	4,244	4,951	5,659	6,366	7,074	8,488	9,903	10,610	12,732	14,147	17,684	21,221
5	1,273	1,910	2,546	3,183	3,820	4,456	5,093	5,730	6,366	7,639	8,913	9,549	11,459	12,732	15,915	19,099
5.5	1,157	1,736	2,315	2,894	3,472	4,051	4,630	5,209	5,787	6,945	8,102	8,681	10,417	11,575	14,469	17,362
6	1,061	1,592	2,122	2,653	3,183	3,714	4,244	4,775	5,305	6,366	7,427	7,958	9,549	10,610	13,263	15,915
6.5	979	1,469	1,959	2,449	2,938	3,428	3,918	4,407	4,897	5,876	6,856	7,346	8,815	9,794	12,243	14,691
7	909	1,364	1,819	2,274	2,728	3,183	3,638	4,093	4,547	5,457	6,366	6,821	8,185	9,095	11,368	13,642
7.5	849	1,273	1,698	2,122	2,546	2,971	3,395	3,820	4,244	5,093	5,942	6,366	7,639	8,488	10,610	12,732
8	796	1,194	1,592	1,989	2,387	2,785	3,183	3,581	3,979	4,775	5,570	5,968	7,162	7,958	9,947	11,937
8.5	749	1,123	1,498	1,872	2,247	2,621	2,996	3,370	3,745	4,494	5,243	5,617	6,741	7,490	9,362	11,234
9	707	1,061	1,415	1,768	2,122	2,476	2,829	3,183	3,537	4,244	4,951	5,305	6,366	7,074	8,842	10,610
9.5	670	1,005	1,340	1,675	2,010	2,345	2,681	3,016	3,351	4,021	4,691	5,026	6,031	6,701	9,377	10,052
10	637	955	1,273	1,592	1,910	2,228	2,546	2,865	3,183	3,820	4,456	4,775	5,730	6,366	7,958	9,549
11	579	868	1,157	1,447	1,736	2,026	2,315	2,604	2,894	3,472	4,051	4,341	5,209	5,787	7,234	8,681
12	531	796	1,061	1,326	1,592	1,857	2,122	2,387	2,653	3,183	3,714	3,979	4,775	5,305	6,631	7,958
13	490	735	979	1,224	1,469	1,714	1,959	2,204	2,449	2,938	3,428	3,673	4,407	4,897	6,121	7,346
14	455	682	909	1,137	1,364	1,592	1,819	2,046	2,274	2,728	3,183	3,410	4,093	4,547	5,684	6,821
15	424	637	849	1,061	1,273	1,485	1,698	1,910	2,122	2,546	2,971	3,183	3,820	4,244	5,305	6,366
16	398	597	796	995	1,194	1,393	1,592	1,790	1,989	2,387	2,785	2,984	3,581	3,979	4,974	5,968
17	374	562	749	969	1,123	1,311	1,498	1,685	1,872	2,247	2,621	2,809	3,370	3,745	4,681	5,617
18	354	531	707	884	1,061	1,238	1,415	1,592	1,768	2,122	2,476	2,653	3,183	3,537	4,421	5,305
19	335	503	670	838	1,005	1,173	1,340	1,508	1,675	2,010	2,345	2,513	3,016	3,351	4,188	5,026
20	318	477	637	796	955	1,114	1,273	1,432	1,592	1,910	2,228	2,387	2,865	3,183	3,979	4,775
21	303	455	606	758	909	1,061	1,213	1,364	1,516	1,819	2,122	2,274	2,728	3,032	9,789	4,547
22	289	434	579	723	868	1,013	1,157	1,302	1,447	1,736	2,026	2,170	2,604	2,894	3,617	4,341
23	277	415	554	692	830	969	1,107	1,246	1,384	1,661	1,938	2,076	2,491	2,768	3,460	4,152
24	265	398	531	663	796	928	1,061	1,194	1,326	1,592	1,857	1,989	2,387	2,653	3,316	3,979
25	255	382	509	637	764	891	1,019	1,146	1,273	1,528	1,783	1,910	2,292	2,546	3,183	3,820

# **ᢒ** Tool failure and trouble shooting

										Sc	olutio	ns							
				Cuttir	ng co	nditio	n			Tool	shap	е		Gr	ade		€	etc	
Trouble		Causes	Cutting speed	Feed	Depth of cut	Coolant	Up cut-down cut	Relief angle	Lead angle	Length of flute	Number of flute	Honing	Chip pocket	Toughness	Hardness	Machine rigidity	Machine vibration	Workpiece fixing	Overhang
	Excessive periphery cutting edge	Improper cutting condition	1	1		•											1		
Damage at cutting edge	Chipping	Improper cutting condition Generating built up edge Weak tool rigidity Improper grade		•			1	1				•		1			1	1	1
Dama	Fracture during operation	Improper cutting conditions Excessive cutting load Excessive overhang		1	1					1			1			1		1	1
		Generating built-up edge	1	1		•			1			•							
Po	oor surface finish	Chattering	1				1			1						1	1	1	1
		Poor straightness		1	1		1		1	1									1
	machining precision (Machined size, perpendicularity)	Improper cutting conditions Improper tool shape	1	1			1			1	1					1	1		1
Ва	d chip evacuation	Excessive cutting volume Improper chip pocket Improper cutting conditions		1	•						1		1						

↑: Increase ↓: Decrease •: use •: Correct use

# The shape of drills and the names




# Shape and the feature of cutting

Helix engle	Plays rake angle of c too big Drill rigidity de		angle increases Cutting force	decreases. On	the other hand If helix angle i					
Helix angle		Poor machinability	✓ low - Helix angle - high ▶	Smooth chip e						
	Hard wo	orkpiece (hardened steel)	◆ low - Helix angle - high ▶	Soft material	(aluminum etc)					
Length of flute		evacuation and cooling lu weakens drill rigidity and	bricant too small length of flute worser	ns chip evacuation	on to breakage					
	Point angle has big influe	ence on cutting performance.	It mainly depends on workpiece. In	n case of standard	d drills Point angle is generally 118					
Point angle	th	rust resistance decrease	Iow - Point angle - high ▶	thrust resistar	nce increase					
i onit angle	Torque increa	ase, Burr on exit increase	Iow - Point angle - high ▶	Torque decrea	ase, Burr on exit decrease					
	Sof	t material (aluminum etc)	Iow - Point angle - high ▶	Hard workpie	ce (hardened steel)					
Morain	While machining Marg		ween workpiece and drill's exter	nal. It prevents t	pending and plays guide's role					
Margin	Cutting force decrease  Poor guide  Poor guide  Small - Margin - big  Good guide  Cutting force increase  Good guide									
	Web is the part of center of drill and drill's rigidity depends on the web. Drill needs cutting edge, chisel edge, at the tip of dril because drill makes a hole at the beginning of drilling. When web thickness is big Thinning is needed to reduce cutting force									
Web thickness	Cutting force decrease									
	Rigidity decrease									
	Good chip evacuation  ◄ small - Web thickness - big ▶ Bad chip evacuation  Soft material (aluminum etc)  ◄ small - Web thickness - big ▶ Hard workpiece (hardened steel)									
		,			,					
Back taper	The decrease of diam		o shank in order to avoid the fr n 100mm generally becomes C tion have big back taper							
	is thin Drill rigidity wea	aken. Therefore without we	%. Chisel edge length depends by thickness change Thinning raisel and improves chip evacua	makes chisel ed	ge short or gives rake angle.					
	Types of	Edge shape	Featur	re	Korloy's drills					
Thinning	X type		Good centering High central thicknes Crank shaft	s	Mach solid drill (MSD) Vulcan drill (VZD)					
	S type		For wide use For general		Solid drill (SSD)					

# Major cutting formulas

Cutting speed	Feed	Helix angle	Machining time
$vc = \frac{\pi \cdot D \cdot n}{1000} \text{ (m/min)}$ • vc: Cutting speed (m/min) • D: Drill diameter (mm) • n: Revolution per minute (min <sup>-1</sup> ) • $\pi$ : Circular constant (3.14)	fn = \frac{vf}{n} \text{ (mm/rev)}  • fn: Feed per revolution (mm/rev)  • vf: Feed per minute (mm/min)  • n: Revolution per minute (min <sup>-1</sup> )	$\delta = tan^{-1} \left(\frac{\pi D}{L}\right)$ • $\delta$ : Helix angle • D: Drill diameter (mm) • L: Lead (mm) • $\pi$ : Circular constant (3.14)	tc = $\frac{\text{Id}}{\text{n·fn}}$ (min)  • tc: Machining time (min)  • n: Revolution per minute (min¹)  • Id: Drilling time (mm)  • fn: Feed (mm/rev)



### **Cutting torque and thrust (calculation formulas)**

$$Md = KD^2 \times (0.0631+1.686 \times fn) (kg \cdot cm)$$

T = 57.95KDfn<sub>0.85</sub>(kg)

• Md: Cutting torque (kg·cm)

• T: Cutting thrust (kg)
• D: Drill diameter (mm)

· K: Material coefficient

• fn: Feed per revolution (mm/rev)

Workp	iece material (SAE/AISI)	Tensile strength (kgf)	Hardness (HB)	Material coefficient K	
	Cast iron (Gray)	21	177	1.00	
Cast iron	Cast iron	28	198	1.39	
	Cast iron (Ductile)	35	224	1.88	
	1020(carbon steel C 0.2%)	55	160	2.22	
General steel	1112(C 0.12, S 0.2%)	62	183	1.42	
	1335(Mn 1.75%)	63	197	1.45	
	3115 (Ni 1.25, Cr 0.6, Mn 0.5)	53	163	1.56	
Nickel Chrome steel	3120 (Ni 1.25, Cr 0.6, Mn 0.7)	69	174	2.02	
31001	3140	88	241	2.32	
	4115 (Cr 0.5, Mo 0.11, Mn 0.8)	63	167	1.62	
Chrome molybdenum steel	4130 (Cr 0.95, Mo 0.2, Mn 0.5)	77	229	2.10	
morybuenum steel	4140 (Cr 0.95, Mo 0.2, Mn 0.85)	94	269	2.41	
Nickel	4615 (Ni 1.8, Mo 0.25, Mn 0.5)	75	212	2.12	
molybdenum steel	4820 (Ni 3.5, Mo 0.25, Mn 0.6)	140	390	3.44	
Chrome steel	5150 (Cr 0.8, Mn 0.8)	95	277	2.46	
Chrome	6115 (Cr 0.6, Mn 0.6, V 0.12)	58	174	2.08	
vanadium steel	6120 (Cr 0.8, Mn 0.8, V 0.1)	80	255	2.22	

### Cutting torque and thrust (empirical formula)

$$Md = K_1 d^2 \cdot fn^m$$

• Md: Cutting torque (kg\*cm)

• fn: Feed (mm/rev)

• d: Drill diameter (mm)

 $T = K_2 d \cdot fn^n$ • T: Thrust (kg) • K1, K2, m, n: Experimental Data Characteristic value

Workpiece	<b>K</b> 1	m	<b>K</b> 2	n
Soft steel	5.9	1.00	125.0	0.88
Rolled steel	3.5	1.00	55.0	0.88
7-3 brass	2.5	0.94	44.4	0.87
Aluminum	1.5	0.90	33.3	0.78
Zinc	1.4	0.88	27.0	0.74
Gun metal	2.0	0.94	21.6	0.75
Galvanized iron	0.3	0.57	6.4	0.55

# **Technical Information for Drills**

## Tool failures and solutions

Trouble										Sol	lution	ıs							
				Cuttir	ng cor	dition	1			Tools	shape	•		Gr	ade		e	tc	
Tro	uble	Causes	Cutting speed	Feed	Step feed	Initial feed	Coolant	Relief angle	Point angle	Thinning angle	Honing	Flute width rate	Thinning	Toughness	Hardness	Machine rigidity	Machine vibration	Guide bush	Clamping workpiece
		• Too sharp cutting edge (too big relief angle) (thinning edge is too sharp)						1		1	1			1					
Chip	ping	Excessive cutting speed	1				•												
		Built-up edge					•	1		1	1			1					
		Vibration and chattering	1													1	1		•
10/	ear	• Excessive cutting speed (Abnormal wear at margin)	1				•												
	<b>3</b> d1	Insufficient cutting speed     (Abnormal wear at center)	1				•												
		Long chip	1	1			•				1								
Cł	nip	Over lap	1	1															
		Chip burning	1				•												
		Tool clamping precision				1			1		1					1	1		•
	ision burr, ace finish	Excessive feed, sharp point angle		1					1		1								
		Excessive cutting speed     (Considered tool grade)	1				•	1	•						1				
	Breakage	Poor surface finish			•	1												•	
	on	Insufficient machine rigidity														1			•
Fracture	contact	Improper cutting condition	t	1															
	Breakage	Crooked hole	t						1				•				1	•	
	at hole bottom	Chip clogging		1	•							1							

**↑**: Increase **↓**: Decrease **•**: use **•**: Correct use

# Hole size for threading

## • Metric coarse screw threads

Specification	Hole diameter
M1 X 0.25	0.75
M1.1 X 0.25	0.85
M1.2 X 0.25	0.95
M1.4 X 0.3	1.1
M1.6 X 0.35	1.25
M1.7 X 0.35	1.35
M1.8 X 0.35	1.45
M2 X 0.4	1.6
M2.2 X 0.45	1.75
M2.3 X 0.4	1.9
M2.5 X 0.45	2.1
M2.6 X 0.45	2.2
M3 X 0.6	2.4
M3 X 0.5	2.5
M3.5 X 0.6	2.9
M4 X 0.75	3.25
M4 X 0.7	3.3
M4.5 X 0.75	3.8
M5 X 0.9	4.1
M5 X 0.8	4.2
M5.5 X 0.9	4.6
M6 X 1	5
M7 X 1	6
M8 X 1.25	6.8
M9 X 1.25	7.8
M10 X 1.5	8.5
M11 X 1.5	9.5
M12 X 1.75	10.3
M14 X 2	12
M16 X 2	14
M18 X 2.5	15.5
M20 X 2.5	17.5
M22 X 2.5	19.5
M24 X 3	21
M27 X 3	24
M30 X 3.5	26.5
M33 X 3.5	29.5
M36 X 4	32
M39 X 4	35
M42 X 4.5	37.5
M45 X 4.5	40.5
M48 X 5	43

### • Metric coarse screw threads


Specification	Hole diameter
M2.5 X 0.35	2.2
M3 X 0.35	2.7
M3.5 X 0.35	3.2
M4 X 0.5	3.5
M4.5 X 0.5	4
M5 X 0.5	4.5
M5.5 X 0.5	5
M6 X 0.75	5.3
M7 X 0.75	6.3
M8 X 1	7
M8 X 0.75	7.3
M9 X 1	8
M9 X 0.75	8.3
M10 X 1.25	8.8
M10 X 1	9
M10 X 0.75	9.3
M11 X 1	10
M11 X 0.75	10.3
M12 X 1.5	10.5
M12 X 1.25	10.8
M12 X 1	11
M14 X 1.5	12.5
M14 X 1	13
M15 X 1.5	13.5
M15 X 1	14
M16 X 1.5	14.5
M16 X 1	15
M17 X 1.5	15.5
M17 X 1	16
M18 X 2	16
M18 X 1.5	16.5
M18 X 1	17
M20 X 2	18.5
M20 X 1.3	19
M22 X 2	20
M22 X 1.5	20.5
M22 X 1.3	21
M24 X 2	22
M24 X 1.5	22.5
M24 X 1.3	23
M25 X 2	23
M25 X 1.5	23.5
M25 X 1.3	24
M26 X 1.5	24.5
M27 X 2	25
MEI V E	

## **Technical Information for Drills**

#### Cautions

#### Selection of drill chuck

• Collect chuck is favorable Because it has strong grip power (General drill-chuck and Keyless chuck don't have enough grip power.)




· Collect chuck

General drill-chuck

### Coolant supply


- · Supply enough coolant around hole entrance
- Standard cutting oil pressure: 3~5 kg/cm², Flux: 2~5 l/min



· Supply much coolant at hole entrance


## Mounting drill

- When mounting drill Periphery chattering should be within 0.02 mm
- · Flute should not be clamped



## How to clamp workpiece

• At high performance drilling High thrust, torque and horizontal cutting force work at the same time so that workpiece should be clamped strongly to




 Uniformed and strong clamping is needed (Right and left, up and down)  Strong clamping is needed because bending causes chipping

#### Notice

- 1) For better drill's life, small damage and wear are favorable to be regrinding
- 2) Damage and wear size should be within 1.5 mm for regrinding
- 3) If drill has crack, regrinding is impossible
- 4) Ordering for regrinding is acceptable or purchase regrinding machine

## Regrinding procedures

Regrinding mathod (Mach Drill)



#### 1) Preparation Determination of regrinding areas


- Check the cutting edge for damage and wear If large fracture is found, remove it by rough grinding





#### 2) Grinding operation Drills setting

- Drill is clamped to collet chuck Chattering is kept within 0.02 mm





## **Technical Information for Drills**


#### 3) Grinding operation-Grinding point


- Check damage and wear at the point and remove it completely
- The difference of the lip height is kept within 0.02 mm


Point angle (a): 140° Point relief angle (b)t: 8°~15°













#### 4) Grinding operation-Thinning grinding


- Considering N/L width Cutting edge length from the center of drill axis should be 0.03~0.08mm for balancing
- Set the wheel to tilt drill axis by 34°~40°.

Thinning angle (a)°: 155°~160° Thining open angle (b): 100°~105°
















#### 5) Grinding-N/L grinding and honing

- Using diamond chisel Grinds the width flat along point cutting edge
- After negaland operation Finishes with brush or handstone


N/L width (a): 0.05mm~0.16mm/N/L angle (b): 24°~26°





#### • TIP


- · Making point
- Without center drill, the point width should be below 0.10 mm
- · Recommended grinding condition
- Diamond wheel: 240~400 mesh
- Diamond chisel: 400~600 mesh
- Diamond hand stone: 800~1500 mesh



## Hexagonal socket bolt (clamping screw) size

### Counter boring and size of bolt hole for hexagonal socket bolt

ISO (d)	M3	M4	M5	M6	М8	M10	M12	M14	M16	M18	M20	M22	M24	M27	M30
Ød <sub>1</sub>	3	4	5	6	8	10	12	14	16	18	20	22	24	27	30
Ød'	3.4	4.5	5.5	6.5	8.5	11	14	16	18	20	22	24	26	30	33
ØD	5.5	7	8.5	10	13	16	18	21	24	27	30	33	36	40	45
ØD'	5	8	9.5	11	14	17.5	20	23	26	29	32	35	39	43	48
Н	3	4	5	6	8	10	12	14	16	18	20	22	24	27	30
H′	2.7	3.6	4.6	5.5	7.4	9.2	11.0	12.8	14.5	16.5	18.5	20.5	22.5	25	28
H"	3.3	4.4	5.4	6.5	8.6	10.8	13.0	15.2	17.5	19.5	21.5	23.5	25.5	29	32



# The comparison of chip breakers

		Applicat	tion	KORLOY	KYOCERA	TAEGUTEC	SUMITOMO	SANDVIK	KENNAMETAL	ISCAR	WLATER	MITSUBISHI	SECO	TUNGALLOY
			Ultra-	-	DP (G-class)	-	FA	PMC	FF (G-class)	SF	-	PK (G-class), FY	FF1	TF
			Finishing	VL	GP	FA	FL, FB	QF	UF	PF	NF3	FH, FS, SY	FF2	NS, ZF
			Finishing	VF, VB	PP	FG	LU, FE	PF, XF	FN	NF, SM	NF4	FP		NM, NS, SS
			Finishing	-	-	SF	SU	61	К	F3P	FP5	LP, SH, SA	MF2	TS, TSF
			Medium to	VC	HQ, CQ	MC	SE	НМ	LF, CT	TF	NS6	C(Cermet)		AS
			finishing	LP, CP	PQ, CJ	FC	SX	PMC	-	-	MP3	MV	MF5	ZM, AM
		Application	Medium	VM, HM	HK, GS, HS, PS	MP, MT	GU(UG)	QM, SM	MP, MN	PP, TF	NM4, NP5	MA, MH	M3, M5	TQ, TM
			machining	MP	PG	PC	GE, UX	PM, XM	-	МЗР	MP5	MP	-	DM, None C/B
			Roughing	B25				-	RP, MR	GN	-	GM, None C/B	M5	TH
	Р		riougiiiig	GR	PT, GT, HT, PH	RT	MU, ME, MX	PR, WR	RN, None C/B	R3P	RP5, NM9	GH, RP	MR5, MR6, MR7	THS
				GH	PX	HB, RH, RX	HG, MP	PR, XMR	RH	NR, HT	RP7, NR4, NRF	HZ	R4, R5	CH
			Heavy duty machining	VH	-	HZ, EH	HP	QR	RM	HR	NRR, NR8	HX	R6, R7, R8, PR6	THS, TRS
				VT	-	HT, HY, HD	HU, HW, HF	HR	MM	T3P	-	HV	PR9, R56, R57, R68	65, TUS
		Low carbon	Soft steel	VL	XF, XP, XP-T	SF	FL	LC	-	-	-	FY	-	-
i.		steel		-	XQ, XS	-	-	-	-	-	-	SY	-	-
Negative		I II aa la		VW	WP, WF	WS	LUW, SEW	WF, WL	FW	WF	NF	SW	FF2, MF2	AFW, FW
Ž		High feed	Wiper	LW	WQ, WE	WT	GUW	WM, WMX	MW	WG	NM	MW	MF5, M3	ASW, SW
				-	-	-	-	WR	RW	-	-	-	R4, R7	-
		Application	Shaft	SH	CJ, ST	FS, VF, FX	HM	К	-	-	-	ES	UX	P, S
			(long bar)	KNUX-	KNMX-	KNUX-	-	KNUX-71	-	-	-	KNMX-19	-	KNMX
		Ctoinlaga	Finishing	VP2, MP	MQ, GU, SK	EA, SF	SU, EF	MF, XF	FP, FF	SF, VL, F3M	NF4, FM5	SH, LM	FF1, MF1	SS, SF, SA
	M	Stainless steel	Medium cutting	MM	HU, TK, MS	MP, EM	EX, EG, GU	MM,XM,QM,MMC	MP, UP, MS	PP, TF, M3M	NM4, NR4	MS, GM, MM	MF3, MF4	SM
			Roughing	RM	MU	ET	MU, HM, EM	MR, XMR, MRR	RP, P	MR, R3M	RM5, NRS	MA, ES	MF5, M5	S, SH
		Cast	Finishing	MP	None C/B, C, KQ	MT	UZ	KF, PMC, XF	T-20, FN	TF	NM, MK5	LK, MA	M4	CF
	K	iron	Medium cutting	B25, MK	ZS, KG	RT, KT	UX, GZ	KM, XM	UN, RP	GN	NM5, RK5	MK, GK, None C/B	M5	CM, None C/B
			Roughing	-MA, RK	-MA, GC, KH	-MA	-MA	KR, XMR, KRR	MR, S-20, -MA	-MA, NR	-MA, RK7	RK, -MA	MR7	CH
			Ultra-finishing	VP1	MQ, SK	EA	EF	SF, SGF	FS (G-class) LF (G-class)	SF, PF	NF4	FJ(G-class)	M1	SF
	S	HRSA	Finishing	VP2	TK	ML	UP, EG	23.SR, XF, SMC	UP	PP	NFT	LS	MF1	HMM
			Medium cutting	VP3	MS	EM	EX	SM, SMR, XM	MS, GP, P, UN	TF	NMS, NMT	MS	MF4, MR3	HRF
			Roughing	VP4	MU	ET	MU	XMR	RP	MR	NRS, NRT FN2, PF2,	RS, GJ	MR4	HRM
	N	Alum	inium alloy	HA	AH	ML	AX	23	GP, MS	NF, PP	MN2, PM2	MJ	MF1	Р
			Finishing	FP	XP, PP	FA, FX	FC	PF, XF	11	PF	FP4	SMG (G-class), FV	FF1	01
				VL, VF	GP	-	FB, LU(FP, FK)	UF	UF	F3P	FK6	SV, FP	F1	PSF, PF
	Р		Medium cuttina	HMP	XQ	FG	LB, NF	PM, XM	LF, FP	14	MP4,FM2,FM4,MK4	LP	MF2	PSS
	M	Application		MP	HQ, GK	PC, FM	SU, SC	UM, PMC	MP, T-20	SM	FP6,MM4,FM6,RK4	MV	F2, M3	PS
	K		Roughing	C25	None C/B	MT	MU	PR, UR, XR	MF, GM, -C	19	RP4, RM4, RK6	None C/B, MP	M5	PM
e e			Wiper	-	WP	-	LUW	WL, WF	FW	WF	PM	SW	-	-
Positive			m	-	-	WT	SDW	WM, WMX	MW	WG	-	MW FJ (G-class),	-	-
Po	М	Stainless	Finishing Medium to	FS, MS, VP1	CF, GF, GQ	FG CA	FC, FM	MF, MM, MMC	11, UF, LF	PF	FM4, NM4	FM, LM	F1, MF2	PSF, PSS
	S	steel For HRSA	finish cutting Medium	FP, VL, LU	MQ	SA	LB, SI	MR, XR	MF	SM	RM4	MM None C/D	M3	PS
			cutting	MU	MF	- nc	- MII	SMC	-	M3M	- FVC	None C/B	M5	CM
	K	Cast iron	cutting	MP	HQ	PC MT	MU Nana C/B	KF, KM	LF	17	FK6	MK Nana C/D MW	M3	CM
	p.		Roughing	C25	GK	MT	None C/B	KR	MF, UF	19	MK4, RK6	None C/B, -MW	M5	None C/B
	N Hic		inium alloy on bar turning	AK, AR	AH	FL ON	AW, AG, AY	AL	HP, LF	AS, AF	PM2	AZ, FS	AL	AL IDD IDD
			class G&E)	KF, KM	FSF, USF, J, A3	GF, FF, GW	FY, FX, FZ	K, F, UM	GH	LF, RF, XL	-	F, SR, SS, SM	UX	JS, J10, JRP, JPP

# **⊙** KORLOY grades

Cat.		Grade	Р	N/I	IS K		N	Н	Turning	Multi functional	Threading	Milling	Endmill	Index drill	Solid drill	Brazed tools	Coating layer		
	CVD	NC3215		M	K	S	N	н	•	tools				uiii	uiii	10010		TiN —— Al2O3 —— MT-TiCN	
	CVD	NC3225							•	•								TiN Al2O3 MT-TICN	
																		MT-TICN  Al2O3 TIC	
	CVD	NC3120							•	•								MT-TICN	
	CVD	NC3030	P25-P35						•	•								Al2O3 TiC MT-TiCN	
	PVD	PC3030T	P35-P45	M25-M35							•							TIAIN	
	PVD	PC3035								•								★ New TiAIN fil (High hardnes Oxidation resistance	
	CVD	NC6310			K01-K10				•									TiN Al2O3 MT-TiCN	
	CVD	NC6315			K10-K20				•	•								Al2O3 MT-TiCN	
	PVD	PC8105		M05-M15		S01-S10			•									—— TiAlN	
	PVD	PC8110		M10-M20		S05-S15			•	•								—★ New TiAIN filr (High hardness) Oxidation resistance)	
	PVD	PC8115		M15-M25		S10-S20			•									—— TiAlN	
	PVD	PC8120				S15-S25			•									— ★ New Al203 filn — TiAIN	
	CVD	NC9115	w	M10-M20					•									TiN Al <sub>2</sub> O <sub>3</sub> MT-TiCN	
	CVD	NC9125	eW)	M20-M30		S10-S20			•									TiN Al2O3 MT-TiCN	
Coating	CVD	NC9135	<b>w</b>	M30-M40		S15-S25			•									TiN Al2O3 MT-TiCN	
ပိ	PVD	PC9030		M25-M35					•	•								—— TIAIN	
	PVD	PC9070T		M25-M35							•							—— TIAIN	
	PVD	PC2005						H01-H10				•						TiMeN	
	PVD	PC2010						H05-H15				•						TiMeN	
	PVD	PC2015						H10-H20				•						AICrN	
	PVD	PC2505						H01-H10				•						—★ New TiAIN file	
		1	eW)															(High hardness Dxidation resistance ★ New TiAIN film	
	PVD	PC2510						H05-H15				•	•					(High hardness Oxidation resistance — ★ New TiAIN filn	
	PVD	PC210F						H10-H20				•						(High hardness Oxidation resistance	
	CVD	NCM325	P30-P40									•		•				Al2O3 MT-TiCN	
	CVD	NCM335	P35-P45									•						Al2O3 MT-TiCN	
	PVD	PC3700	P25-P40									•		•				TiN TiAlCrN	
	CVD			M25-M35	K15-K25				•	•		•		•				TiN Al2O3 MT-TiCN	
	CVD	NCM535	P30-P40		K20-K30					•		•		•				TiN Al2O3 MT-TiCN	
	CVD	NCM545	P40-P50		K30-K40							•						TiN Al <sub>2</sub> O <sub>3</sub> MT-TiCN	
			1	1	1		1												

# **General Information II**

# **⊙** KORLOY grades

	at.	Grade	Р	M	IS K	50 S	N	Н	Turning	Multi functional	Threading	Milling	Endmill	Index drill	Solid drill	Brazed tools	Coating la	yer
	PVD	PC5300		M20-M30					•	•	•	•		•				—★ New TiAIN film (High hardness/
<u>B</u> L	PVD	PC5335	P30-P40	M20-M30										•				★ TiAlCrN film (Lubricative)
ng	PVD	PC5400	P35-P45	M30-M40	K25-K35	S25-S35			•			•						★ TiAlCrN film (Lubricative)
Coating	PVD	PC6510			K05-K15							•		•				TiN TiAIN
	PVD	PC9530		M25-M35								•						—— TiAIN
	PVD	PC9540		M35-M45		S30-S40						•						Al2O3 TiAIN
	PVD	CC1500	W P10-P20		K05-K15				•									—★ New TiAIN film (High hardness/
	PVD	CC2500	W P20-P30		K10-K15				•									—★ New TiAIN film (High hardness/
Cermet		CN1500	P10-P20		K10-K20				•									SAGULION TOSISILATOS)
ŏ		CN2500	P15-P30		K15-K25				•									
		CN30	P25-P35									•						
		ST10	P10-P15								•					•		
		ST20	P15-P20							•						•		
-		ST30A	P25-P35							•		•						
Uncoated		U20		M25-M30												•		
'n		H01			K05-K10	S01-S10	N10-N20	H05-H10	•	•		•	•	•		•		
		H05			K10-K15	S05-S15	N15-N25		•			•						
		G10				K15-K20			•			•				•		
	PVD	PC203F						H05-H15					•					—★ New TiAIN film (High hardness/ Oxidation resistance)
	PVD	PC210C					N10-N20						•					CrN
	PVD	PC215F	P20-P35										•					_★ New TiAIN film (High hardness/ Oxidation resistance)
	PVD	PC215G	P15-P30		K15-K30										•			—— TiAIN
	PVD	PC221F	P35-P45		K35*K45								•					★ New TiAIN film (High hardness/ Oxidation resistance)
Coating	PVD	PC230F	P05-P15	M05-M15	K05-K15											•		—★ New TiAIN film (High hardness/ Oxidation resistance)
O	PVD	PC303S	P05-P15		K05-K15			H05-H15					•					TiMeN TiAIN
	PVD	PC310U	P10-P20		K10-K20			H10-H20					•					TiMeN TiAIN
	PVD	PC315E	P20-P35		K20-K35								•					AICrN
	PVD	PC315G	P15-P30		K15-K30										•			TiAlCrN
	PVD	PC320	P20-P35		K20-K35								•					—— TiAIN

### **⊙** KORLOY grades

	Cat.				IS	0			Turning	Multi functional tools	Throading	Milling	Endmill	Index	Solid	Brazed	Coating la	row .
	val.	Grade	Р	M	K	S	N	Н	Turning	tools	Threading	wiiiing	Enamili	Index drill	Solid drill	Brazed tools	Coating lay	
	PVD	PC320S		M20-M30		S20-S30							•					TiMeN TiAIN
	PVD	PC320U	P01-P10		K05-K10								•					—— AICrN
Coating	PVD	SL				S25-S35							•					—— TiAIN
S	PVD	PC325T	<b>V</b>			S20-S30									•			TiMeN TiAIN
	PVD	PC325U	P20-P35	M20-M30	K20-K35										•			TiAlCrN
		H01					N10-N20						•					
5		H05S					N10-N20						•					
Uncoated		FCC			N15-N35								•					
ō		FG2	P05-P25				N05-N25								•			
		FA1	P05-P25				N05-N25								•			
		DBN500			K05-K15				•									
		DBN700A			K01-K10				•									
		DB7000	S01-S10						•									
		DB1000						H01-H10	•									
		DB2000						H05-H15	•									
cBN		DBNX20						H15-H25	•									
R		DBN250						H15-H25	•									
		DBN400						H15-H25	•									
	PVD	DNC100						H01-H10	•									→ New TiAIN film (High hardness)
	PVD	DNC250						H05-H15	•									TiN TiAIN
	PVD	DNC350						H25-H35	•									→ New TiAIN film (High hardness)
	PVD	DNC400	w)					H15-H25	•									TiN TiAIN
		DP90					N01-N20					•						
PCD		DP150					N05-N25					•						
		DP200					N10-N30					•						
DIA	CVD	ND2100					N2.5-N7.5		•			•	•		•			_ Dia Coating
۵	CVD	ND3000	<b>w</b> )				N01-N05		•			•	•					_ Dia Coating
DLC	PVD	PD1005					N05-N10		•			•	•					
DI	PVD	PD1010					N10-N15		•			•	•					

### The comparison of grade for turning

### **O** WC

- 1	SO	KORLOY	SUMITOMO	KYOCERA	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
		ST10	ST10			S1P			TX10S	STi10T	SRN5 WS20B	S1F		P10		
	Р	ST20	ST20			SM30			TX20	STi20T	0203			P20		
Turning		ST30A	ST30A ST40E	PW30	IC50M IC54	S30T S6	TTX TTM TTR	K45 KM K420	TX30 TX40	UTi20T	EX35 EX40 EX45	VC6 VC5 VC56		P30 P40		
Tur	М	U20	U10E U20 ST30A A40			H13A H10F	AT10 AT15 TTR	K2885 K2S	TU10 TU20 TU40	UTi20T	WAM10B EX35	VC27 VC28		M10 M20 M40		
	K	H01 H05 G10	H1 G10	KW10H	IC4 IC20 IC28	H1P H10F	THM THR	K68 K8735	TH03 TH10 KS20	HTi10T HTi20T	WH05 W10 WH20	VC3 VC2 VC1		K10 K20 K20M K30		

### CVD coated

IS	0	KORLOY	SUMITOMO	<b>KYOCERA</b>	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
			AC805P	CA5505 CA510		GC4305 GC4205	TP0500 TP0501	KCP05 KCP05B	T9105	UE6105				TT8105		
		NC3215★	AC810P AC700G AC900G	CA515 VP5115 CA5515	IC8150	GC4315 GC4215	TP1500 TP1501 TGP25	KCP10 KCP10B	T9115	UE6110 MY5015	HG8010	VP5515	WPP10S WKP13S	TT8110 LC215P TT8115		
	Р	NC3225★ NC3120	AC820P AC2000 AC8025P	CA525 VP5125 CA5525	IC8250	GC4325 GC4225	TP2500 TP2501 TGP35 TP3501	KCP25 KCP25B	T9125	MC6025 UE6020	HG8025	VP5525	WPP20S WKP23S	TT8120 LC225P TT8125	CP5	JC110V JC215V
ng		NC3030 NC5330	AC830P	CR9025 CA5535 CA530	IC8350	GC4335 GC4235	TP3500 TGP45	KCP30 KCP30B	T9135	MC6035 UE6035	GM8035	VP5535	WPP30S WKP33S	TT5100 TT8135		JC325V
Turning								KCP40 KCP40B		UH6400				TT7100		JC450
₽		NC9115*	AC610M	CA6515	IC6015	S05F GC2015	TM2000	KCM15 KCM15M	T6120	MC7015		VP8515	WAM10	TT9215		
	M	NC9125* NC9135*	AC630M AC6030M	CA6525	IC6025	GC2220 GC2025	TM4000	KCM25 KCM25B KCM35 KCM35B	T6130	MC7025 US7020 US735	GM25 GX30	VP8525	WMP20S WAM20 WAM30	TT9225 TT9235		
		NOCOAO	AC405K	CA4505	ICEOOF	GC3205	TK1001	KCK05 KCK05B	T5105	MC5005 UC5105	HG3505	VP1505	WKK10S	TT7005	CP2	JC105V
	K	NC6310* NC6315	AC415K	CA4010 CA4515 CA4115	IC5005	GC3210 GC3215 GC3225	TK2001 TGK1500	KCK15 KCK15B	T5115	MC5015 UC5115	HG3515	VP1510 VP1515	WKK20S	TT7505 TT7310 TT7015	CP5	JC110V JC215V
			AC420K	CA4120	IC5015	2.22.20		KCK20 KCK20B	T5125				WAK30	TT7025		

### PVD coated

IS	0	KORLOY	SUMITOMO	KYOCERA	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
	Р	PC8105* PC8110 PC8115* PC3035 PC5300		PR1005 PR915 PR1115 PR930 PR1025 PR630 PR660	IC507 IC808 IC830 IC908 IC3028	GC1025 GC4125	CP200 CP250 CP500	KU10T KU25T	AH710 GH730 AH330 AH740 AH120 GH330	VP15TF VP20MF	IP2000 IP3000	VC907 VC927 VC905	WTA43 WTA41	TT5030		JC5003 JC5015
Turning	М	PC8105* PC8110 PC8115* PC8120* PC5300* PC9030	AC510U EH510Z AC520U EH520Z AC530U	PR915 PR930 PR1125 PR630 PR660	IC808 IC907 IC3028 IC830	GC1005 GC1105 GC1020 GC1025 GC4125 GC2035	CP200 CP250 CP500	KC5010 KC5510 KC5025 KC5525	AH330 GH330 AH120 GH730 AH140 AH630	MP9005 VP10RT VP15TF VP20MF MP7035	IP50S IP100S	VC929 VC927 VC902 VC901 VC905	WSM10S WSM20S WSM30S WSM40S	TT5030	ZM3 QM3 VM1 TAS	JC5003 JC5015
	K	PC5300	EH510Z EH520Z		IC5100 IC810 IC220 IC908 IC228		CP200 CP250 CP500		AH110 GH110 AH120		CY110H	VC929 VC903 VC927 VC902 VC901 VC907		TT5030		
	S	PC8105 PC8110 PC8115 * PC8120 * PC5300 PC5400 *	AC510U AC520U	PR915 PR660 PR1325	IC808 IC907 IC3028 IC328	GC1105 GC1025 GC2035	TS2000 CP500 TS2500	KC5010 KC5025	AH110 AH120	VP05RT VP10RT VP15TF MP7035			WSM10 WSM20 WSM30	TT5030		

### **O CERMET**

IS	80		SUMITOMO	KYOCERA	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
Turning	P	CC1500 * CN1500 * CC2500 * CN2000 CN2500 *	T110A T2000Z* T1500A	PV30* TN30 PV7020* TN60 TN620 TN6020 TN90 PV90*	IC20N IC520N IC30N IC530N	CT5015 CT525 GC1525*	CM C15M TP1020 TP1030★	HT2 KT125 HT5 KT175 KT195M	NS520 GT530* NS530 NS9530 GT9530* NS540 NS730	NX2525 NX3035 UP35N* AP25N* NX335 MP3025*	CH350 CZ25* CH530 CH550 CH570	VC83	WTA43 <b>★</b> WTA41 <b>★</b>	PV3010 * CT3000	T3N T15 N20 C30 N40	LN10 CX50 CX75 CX90 CX99
	М															
	K	CN1500* CN2500*	T110A							NX2525				CT3000	T15	LN10 CX75

### The comparison of grade for milling

### CVD coated

IS	03	KORLOY	SUMITOMO	<b>KYOCERA</b>	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
			ACP100		IC5100	GC4210				FH7020			WKP25S			
	Р	NC5330 NCM325 NCM535★			IC5400	GC4220 GC4230	MP1500 MS2500 MP2500 MS2500 T350M MM4500	KCPM20 KCMP30	T3130	F7030		SM245	WKP25S WKP35S WKP35G	TT8525 TT7800		
		NCM335 NCM545★ NC5330						KC927M								
Milling		NC5340★					MP2500 MS2500		T3130	F7030						
W	M	NC5350 <b>★</b>	ACP400			GC2040	MM4500									
	V	NC5330	ACK200		IC5100		MK1500 MK2000 MS2500	KC907M KCK15 KC914M	T1115	MC5020			WAK15 WKK25 WKP25S	TT7515 TT6800		
	K	NCM535* NCM545*				GC3330 GC3040	T350M MK3000	KCPK30 KC917M KC924M	T1015				WKP35S WKP35G			


### PVD coated

IS	0	KORLOY	SUMITOMO	KYOCERA	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
		PC2005* PC2010* PC2015*				P20A					ATH80D PCA08M ACS05E PCA12M					
		PC2505* PC2510*				GC1010				AP20M GP20M	PC20M JX1005 TB6005 JX1020			TT2510		DH102
		PC3600 PC3700★	ACZ310		IC903		MP3000				CY9020		WKP25			JC5003
	Р		ACP200	PR730 PR830	IC908 IC950	GC1025	F25M F30M	KC522M KUC20M	GH330	MP6120 VP15TF	TB6045	VC935		TT7070 TT7080		JC5015
		PC210F	ACZ330	PR630	IC1008	GC1030		KC525M KUC30M	AH120	UP20M	CY250 PTH30E			TT7030	QM3	105000
		PC5300	ACP300							MP6130	JP4160		WKP35		ZM3	JC5030 JC5040
Milling		PC5400★	ACZ350	PR660	IC928	GC1030	F40M T60M	KC935M KC7140 KC720	AH3135	VP30RT	JM4160 PTH40H		WKP45	TT8020		
Ξ				PR730	IC903			KC5510 KC7020	AH120		JX1020 CY9020 JX1015 TB6020					JC5003
	M	PC210F PC5300	ACM100 ACP200 ACM300	PR1025 PR630	IC900 IC250	GC1125 GC1025 GC2030	F25M	KC522M KC725M KC735M		MP7130	CY250 JX1045	VC928 VC902 VC901		TT9030	QM3 ZM3	JC5015 JC5030
		PC9530	ACP300 ACZ350	PR630 PR660 PR1535	IC928	GC1030	F30M	KC735M KC7030	AH140		TB6045	VC901	WQM35 WSM35S	TT9080		JC5030 JC5040
		PC5400★ PC9540★		PR660	IC328		F40M	KC722	AH3135	MP7140	JX1060 TB6060		WSP45 WSM45S	TT8020		
	K	PC6510		PR510 PR905	DT7150 IC900 IC910		MK2050	KC510M KC915M		VP10MF VP15TF		VC903 VC928		TT6290		JC5003
		PC5300			IC950 IC350			KC520M	AH120	VP20RT		VC902 VC901		TT6030 TT6060		JC5015
	S	PC5300 PC5400* PC9540*	AC520U	PR620 PR660 PR1535	IC328 IC408	GC1025 GC1040 S40T	F40M MS2050	KC510M KCU30M		VP15TF VP30RT MP9130	ACS05E		WSM35S WSM45S	TT9030 TT8020 TT8080		

### **O CERMET**

IS	0	KORLOY	SUMITOMO	KYOCERA	ISCAR	SANDVIK	SECO	KENNAMETAL	TOSHIBA	MITSUBISHI	HITACHI	VALENITE	WALTER	TAEGUTEC	NTK	DIJET
g	P	CN2000 CN30	T250A	TN100M TC60M	IC30N			KT195M	NS540 NS740	NX2525 NX4545	CH550 CH570			CT3000 CT7000	C50	
Milling	M		T250A			CT530										
	K									NX2525						

# OLD-FASHIONED PRODUCT INFORMATION



### Old-fashioned product information

J02 Grade
J02 External Holder
J02 Fine Tool
J03 Threading Tool
J03 Mill-Max

J04 Cen-Mill
J04 Jip Drill

J04 LPD/SPD/NPD

### J

### Old-fashioned product information

### Grade

ISO materia	l code	Old grade	New grade
		NC5340	NCM535
		NCM325	INCINISSS
	Р	NCM335	NCM545
		NC5350	INCINI343
Coating grade		PC3530, PC3525, PC3535, PC3500, PC3600	PC3700
Coating grade	V	NC6215	NC6315
	K	NC6110, NC6210, NC6205	NC6310
	grade K	PC8010	PC8110
	DMKS	PC8520, PC215K	PC5300
	P, IVI, K, S	PC225F	PC205F
Cormo	grade	CN1000	CN1500
Cerme	rade  K  S  P, M, K, S	CT10, CN200	CN2500

<sup>·</sup> KORLOY always study and develops cutting-edge technology tools and grades which covers higher speed and feed conditions

### External holder

Decimation	Incort		Old par	ts name		Nove bolder	Dama
Designation	Insert	Wedge clamp	Screw	Washer	Others	New holder	Page
WTENN □□□-□16 (Old Type: MTEEN)	TN**1604	CMH5R1	MHX0523	WA4	Same as before	WTEEN 16	B179
WTJNR□□□□-□16 (Old Type: MTJNR)	TN**1604	CMH5R1	MHX0523	WA4	Same as before	WTJNR	B179
WTXNR□□□□-□16 (Old Type: MTXNR)	TN**1604	CMH5R1	MHX0523	WA4	Same as before	WTXNR 16	B179

<sup>•</sup> Old parts are not interchangeable with new type holder part

### Fine tool

Designation	Im	a aut	Old part	s name	Now holder	Dogo
Designation	Ins	sert	Screw	Wrench	New holder	Page
	FTIH08***	FTG08, FTT08, FTF08	PTKA02508	TW08P		
ETH	FTIH11***	FTG11, FTT11, FTF11	PTKA03510	TW15P	NETU	000
FTIH	FTIH14***	FTG14, FTT14, FTF14	PTKA0412	TW15P	NFTIH	C69
	FTIH16***	FTG16, FTT16, FTF16	PTKA0512	TW20P		

<sup>•</sup> Old inserts and parts are not interchangeable with new fine tool

 $<sup>\</sup>bullet \ \text{KORLOY} \ \text{guarantees} \ \text{better} \ \text{performance} \ \text{and} \ \text{wide} \ \text{stock-management} \ \text{range} \ \text{for the new} \ \text{grade}$ 

<sup>•</sup> Good performance and convenient use of New type holder gives customer best quality of service

 $<sup>\</sup>bullet \ \text{Good performance and convenient use of new fine tool gives customer best quality of service} \\$ 

### **○** Threading tool

					C	old parts nam	ne			
Designation	Ins	ert	Clamp	Clamp screw	Shim	Screw	C-ring	Wrench	New holder	Page
ETH	~ ETH3**R	ECTR3***	CH5R3	CHX0513	ST32C1	SHX0310	CR04	HW20L, HW25L	ED/LVL.	D04
EIN	~ ETH4**R	ECTR4***	CH6R4	CHX0621	ST42C1	SHX0310	CR05	HW20L, HW30L	ER(L)H-*	D31
	~ ITH2**R	ICTR2***	CH5R3	CHX0513	ST32C1	FTKA02565	CR04	TW07P		
ITH	~ ITH3**R	ICTR3***	CH5R3	CHX0513	ST32C1	SHX0310	CR04	TW15P, HW20L, HW25L	IR(L)H-*	D32
	~ ITH4**R	ICTR4***	CH6R4	CHX0621	ST42C1	SHX0310	CR05	HW20L, HW30L		

<sup>•</sup> Old inserts and parts are not interchangeable with threading holders

### Mill-Max

Designation Inc.		Old parts name					Name balden	Dawa
Designation	Insert	Locator	Wedge	Wedge screw	Locator screw	Wrench	New holder	Page
AD(ADM)4000	SD**1203	LAS4R/L	WASR/L	WTX0817	LTX0512	TW25	ADN(ADNM)4000	E47
AD(ADM)5000	SD**1504	LAS5R/L	WASR/L	WTX0817	LTX0512	TW25	ADM/ADMM/5000+	F40
ADN(ADNM)5000	SD**1504	LADN5R/L	WEPN5R/L	DHA0821F	LTX0514	HW40	ADN(ADNM)5000+	E48
EP(EPM)4000	SP**1203	LES4R/L LES4R1/L1 (Ø80 ~ Ø100)	WESR/L	WTX0817 WTX0813 (Ø80 ~ Ø100)	LTX0512	TW25	EPN(EPNM)4000	E53
EP(EPM)5000	SP**1504	LES5R/L LES5R1/L1 (Ø80 ~ Ø100)	WESR/L	WTX0817 WTX0813 (Ø80 ~ Ø100)	LTX0512	TW25	FDN/FDNIM/F000+	EE4
EPN(EPNM)5000	SP**1504	LEPN5R/L LEPN5R1/L1 (Ø80 ~ Ø100)	WEPN5R/L	DHA0821F DHA0817F (Ø80 ~ Ø100)	LTX0514	HW40	EPN(EPNM)5000+	E54
PP(PPM)4000	TP**2204	LPT4R/L LPT4R1/L1 (Ø80 ~ Ø100)	WESR/L	WTX0817 WTX0813 (Ø80 ~ Ø100)	LTX0512	TW25	PPN(PPNM)4000	E56

<sup>•</sup> Parts are not interchangeable with new mill-max cutters

 $<sup>\</sup>bullet \ \text{Good performance and convenient use of new fine tool gives customer best quality of service}\\$ 

<sup>•</sup> Good performance and convenient use of new mill-max gives customer best quality of service



### Old-fashioned product information

### Cen-Mill

Designation	Insert -		Old part	Now product	Done	
			Screw	Wrench	New product	Page
HE -	Ø25	MCMT080308EN ZCMT080308ER	FTNA0307	TW09P	- AMS****M	E185~E187
	Ø32, 40, 50	MCMT09T308EN ZCMT09T308ER	FTNA0408	TW15P		E103~E16/
LE (LEM)	LOCX1205ZZ		FTNB0411	TW15S	AMC***M	E172~E174
SE	Ø25	MPMT090308	FTNA0408	TW15S	- AMS***MH	E188~E189
5E	Ø32, 40	MPMT120408	FTNA0513	TW20S		
ТМ	1	150,200,300,400 ,150,200,300,400	FTNB0411(TM632R) FTNA0513	TW15L(TM632R) TW20L	TMS(I)	D49
PM	EDCW1604ZDF/TR		FTNA0513	TW20L	RM4Z	E118~E119
CE (Code changed)	SPG(M)N1203**				CE45-***R-S32 (New code)	E369~E371

- Old inserts and parts are not interchangeable with new milling product
- New product : Alpha mill which has unique alpha-curve edge guarantees wide range machining and good performance.
- Good performance and convenient use of new milling tool gives customer best quality of service

### Jip Drill

Designation	Insert		Old part	ts name	Now product	Page
			Screw	Wrench	New product	
~ JD200 ~ JD250	~ JD200	WCMT030208-C20	FTNA02565 TW07P	ETNIA 00 F CF TIM 0 TD		
	~ JD250	WCMT040208-C20		10076	K□D (KING-DRILL)	
JD	~ JD300	WCMT050308-C20	FTNA0307	TW09P		F11~F25
_	~ JD410	WCMT06T308-C20	FTGA03508			
	~ JD580	WCMT080408-C20	FTNA0408	TW15P		

- · Old inserts and parts are not interchangeable with new indexable drill
- · Good performance and convenient use of new indexable drill gives customer best quality of service


### **○** LPD/SPD/NPD

Designation	Insert		Old parts name		Now product	Domo
			Screw	Wrench	New product	Page
LPD	~ LPD135	LPMT040203-DF	FTNA0204	TW06P		
	~ SPD155	SPM(E)T050203-DM, DF, DS, DA	FTNA0204	TW06P		
SPD	~ SPD195	SPM(E)T060204-DM, DS, DR, DA	FTKA02206S	TW07S		
	~ SPD225	SPM(E)T070204-DM, DS, DR, DA	FTKA02565	TW07S		
	~ NPD245	NPM(E)T222408-DM, DS, DR, DA	FTKA02565	TW07S	K□D	F11~F25
	~ NPD285	NPM(E)T252808-DM, DS, DR, DA	FTKA0307	TW09S	(KING-DRILL)	FII~FZ3
NDD	~ NPD325	NPM(E)T293208-DM, DS, DR, DA	FTKA0307	TW09S		
NPD	~ NPD405	NPM(E)T334008-DM, DS, DR, DA	FTKA03508	TW15S		
	~ NPD505	NPM(E)T415008-DM, DS, DR, DA	FTKA0410	TW15S		
	~ NPD605	NPM(E)T516012-DM, DS, DR, DA	FTNC04511	TW20S		

- Old inserts and parts are not interchangeable with new indexable drill
- Good performance and convenient use of new indexable drill gives customer best quality of service







### **INDEX**

K02 Index by items

## K Index by items



Actual Designations of Milling Cutter and Arbor	Milling	E426
Aero Mill	Milling	E151
Aero Mill Mini	Milling	E154
Aero Mill Plus	Milling	E152
Alpha Mill	Milling	E164
Alpha Mill-X		E197
Alpha Mill-X	Milling	E145
Aluminum Insert (Positive)	Turning	B102
American ACME	Threading	D24
American Buttress (ABUT)	Threading	D28
American UN	Threading	D16
Angular Head		G86
API Buttress Casing (BUT)	Threading	D30
API Round Casing & Tubing (APIRD)	Threading	D30
Application Example	Multi functional Tools	C02
Application range of KORLOY Main Chip Breakers	Turning	B02
Auto Tools (Blade Type)	Turning	B136
Auto Tools (ISO Type)	Turning	B122
Auto Tools (KGT/MGT Type)	Turning	B142
Auto Tools (MSB Tool)	Turning	B145
Auto Tools (Multi Utility Type)	Turning	B139
Available Insert	Drills	F03
Available Insert for Fine Tools	Multi functional Tools	C68
Available Insert for K Notch	Multi functional Tools	C57
Available Insert for KGT	Multi functional Tools	C12
Available Insert for MGT	Multi functional Tools	C28
Available Insert for MGT Aluminum Wheel	Multi functional Tools	C44
Available Insert for TB/TB-M	Multi functional Tools	C51
Available Insert for TB/TB-M	Multi functional Tools	C50



Bearing Solution	Turning	B156
BFE	Milling	E331
Boring Bar Code System (ISO)	Turning	B204
BRE	Milling	E335
British Buttress (BBUT)	Threading	D28
British Standard Pipe Thread	Threading	D22
BT Tooling System (Alpha Mill)	Milling	E342
BT Tooling System (Mono-Tool)	Milling	E347



Cartridge		H03
Cartridge Code System (ISO)	Turnina	B241



cBN incerts grades	Grades & Chip Breakers	A31
cBN Insert	Turning	B110
Cen-Mill	Old-Fashioned Product Information	J04
Center Drill	Drills	F78
Ceramic Holder	Turning	B197
Cermet grades (Milling)	Grades & Chip Breakers	A24
Cermet grades (Turning)	Grades & Chip Breakers	A13
Chamfer Tool	Milling	E366
Chip breaker		H03
Chip breaker for drilling	Grades & Chip Breakers	A49
Chip breaker for milling	Grades & Chip Breakers	A42
Chip breaker for turning	Grades & Chip Breakers	A37
Chip Cover	Parts	H03
Clamp	Parts	H03
Clamp On System (Boring Bar)	Turning	B212
Clamp On System (Cartridge)	Turning	B243
Clamp On System (Holder)	Turning	B181
Coated cermet grades (Turning)	Grades & Chip Breakers	A15
Collet Chuck Series	Tooling System	G24
Compact Mini	Turning	B225
Coolant Bolt	Parts	H04
CVD coated grades (Milling)	Grades & Chip Breakers	A17
CVD coated grades (Turning)	Grades & Chip Breakers	A05



	G97
Tooling System	G66
Tooling System	G62
Multi functional Tools	C70
	G95
	G96
Tooling System	G23
Tooling System	G11
Tooling System	G07
Tooling System	G04
Grades & Chip Breakers	A29
Grades & Chip Breakers	A30
Turning	B208
Turning	B167
Milling	E62
Tooling System	G12
Tooling System	G30
Tooling System	G41
	Tooling System Multi functional Tools  Tooling System Tooling System Tooling System Tooling System Grades & Chip Breakers Grades & Chip Breakers Turning Turning Milling Tooling System Tooling System Tooling System



DTN	Tooling System	G44
DZC		G94



ER	Tooling System	G36
ER/L	Tooling System	G37
EXT Bar	Tooling System	G54
External Holder	Threading	D31
External Holder	Old-Fashioned Product Information	J02
External Tool Holder Code System (ISO)	Turning	B162
Extreme Line Casing (EL)	Threading	D30



FBC	Tooling System	G82
FBH/B	Tooling System	G55
Feature of Chip Breakers	Turning	B16
Fine Tool	Old-Fashioned Product Information	J03
Fine Tools Holder	Multi functional Tools	C69
FMA	Tooling System	G49
FMC	Tooling System	G50
FMR P-positive	Milling	E242
Future Mill	Milling	E216



GBE	Milling	G82
Gear Cutter	Milling	G55
Gear Cutter Order Form	Milling	B16
Gear Cutter Table	Milling	J03
GERC	Tooling System	C69
GFIP	Multi functional Tools	G49
Grade	Old-Fashioned Product Information	G50
Grades system	Grades & Chip Breakers	E242
GSK	Tooling System	E216



Hardness calculating table		1 08
HAVE (Single edge/Multi edge)	Milling	E339
HFM	Milling	E281
HFMD		E267
HFMD	Milling	E264
HRM	Milling	E300



HRMDouble	Milling	E289
HSK Tooling System	Turning	B231
HSK Tooling System (Alpha Mill)	Milling	E353
HSK Tooling System (Mono-Tool)	Milling	E358
HSK Tooling System (Pro-V Mill)	Milling	E363



IGH	Multi functional Tools	C70
Index for Boring Bar	Turning	B205
Index for Cartridge	Turning	B242
Index for External Holder	Turning	B163
Index for HSK Tooling System	Turning	B230
Index for KM Tooling System	Turning	B230
Indexable HOB	Milling	E440
Indexable HOB Order Form	Milling	E441
Indexable Reamer		F86
Instruction of Boring Bar assembly	Turning	B207
Instruction of External Holder	Turning	B166
Internal Holder	Threading	D32
ISO Metric	Threading	D12
Jip Drill	Old-Fashioned Product Information	J04



K Notch Holder	Multi functional Tools	C59
KED Plus Drill	Drills	F29
KGT Blade for Parting off	Multi functional Tools	C25
KGT Cartridge	Multi functional Tools	C41
KGT Holder	Multi functional Tools	C15
KGT/MGT Cartridge Holder	Multi functional Tools	C40
KHP Coolant	Turning	B127
KHP Coolant	Turning	B202
KING DRILL	Drills	F11
KING DRILL for large diameter drilling	Drills	F25
KING DRILL for through coolant system with a lathe	Drills	F21
KM Tooling System	Turning	B237
KMB	Tooling System	G70
KORLOY Cutters	Milling	E34
KORLOY Grades	Technical Information	I 37
KORLOY Modular Adaptors	Milling	E45
KORLOY Shanks	Milling	E42
KRLOY Drills	Drills	F02

## K Index by items



Laser Mill	Milling	E326
Lever	Parts	H04
Lever Lock System (Boring Bar)	Turning	B210
Lever Lock System (Holder)	Turning	B172
Locator	Parts	H05
LPD/SPD/NPD	Old-Fashioned Product Information	J04



MD	Tooling System	G52
Metric Buttress (SAGE)/API	Threading	D29
MGT Aluminum Wheel	Multi functional Tools	C45
MGT Cartridge	Multi functional Tools	C42
MGT Holder	Multi functional Tools	C31
MGT Holder (Face Grooving)	Multi functional Tools	C36
MGT Special Order Form for MGT	Multi functional Tools	C72
Milling grade selections	Grades & Chip Breakers	A16
Milling Insert Code System (ISO)	Milling	E02
Milling Inserts	Milling	E04
Mill-max	Milling	E47
Mill-Max	Old-Fashioned Product Information	J03
Mill-max Heavy	Milling	E58
Mill-max Plus	Milling	E48, 54
Modular Adaptor	Milling	E401
Multi Lock System (Boring Bar)	Turning	B213
Multi Lock System (Holder)	Turning	B183
Multi Turn	Turning	B154





National Pipe Thread	Threading	D22
National Pipe Thread-Dry seal	Threading	D23
Nozzle	Parts	H07
NPM	Tooling System	G20
NPU	Tooling System	G40
Nut	Parts	H05
O-Ring Cutter	Milling	E364
Others	Tooling System	G104



Partial Profile 55°	Threading	D11
Partial Profile 60°	Threading	D10
PCD Face Cutter	Milling	E156
PCD incerts grades	Grades & Chip Breakers	A36



PCD Insert	Turning	B113
Pin	Parts	H05
Power Buster	Milling	E68
Pro-A Mill	Milling	E385
Pro-L Mill	Milling	E394
Properties of Korloy grades	Technical Information	109
Pro-V Mill		E399
Pro-V Mill	Milling	E368
Pro-X Mill	Milling	E388
Pro-XL Mill	Milling	E398
PVD coated grades (Milling)	Grades & Chip Breakers	A18
PVD coated grades (Turning)	Grades & Chip Breakers	A10



RDC Bar	Tooling System	G54
Recommended Chip Breakers for workpiece	Turning	B04
Rich Mill	Milling	E99
Round DIN 405	Threading	D23
RTJW	Tooling System	G38



	G85
Turning	B119
Turning	B116
Turning	B115
Multi functional Tools	C61
Multi functional Tools	C65
Parts	H05
Turning	B215
Turning	B245
Turning	B190
Tooling System	G25
	H02
Parts	H02 H06
Parts Technical Information	
. 4.10	H06
Technical Information	H06
Technical Information Milling	H06 I 07 E411
Technical Information Milling Milling	H06 I 07 E411 E407
Technical Information Milling Milling Tooling System	H06 I 07 E411 E407 G47
Technical Information Milling Milling Tooling System Turning	H06 I 07 E411 E407 G47 B151
Technical Information Milling Milling Tooling System Turning Tooling System	H06 I 07 E411 E407 G47 B151 G68
	Turning Turning Multi functional Tools Multi functional Tools Parts Turning Turning Turning





Solid endmills grade selections	Grades & Chip Breakers	A25
Solid endmills grades	Grades & Chip Breakers	A26
Special Order Form for Bearing Inserts	Turning	B161
Special Order Form for V-Pulley Insert	Multi functional Tools	C73
Spring	Parts	H07
Steel, Non-ferrous metal symbol list	Technical Information	I 06
Stop Ring	Parts	H07
Stopper	Parts	H07
Stub ACME	Threading	D25



Tank Mill	Milling	E307
TBC	Tooling System	G79
TBCA	Tooling System	G74
TB-M/TB Holder	Multi functional Tools	C54
TCA Tap Adaptor	Tooling System	G46
T-Cutter	Milling	E374
Technical Information for Aero Mill	Milling	E147
Technical Information for Aero Mill Mini	Milling	E150
<b>Technical Information for Aero Mill Plus</b>	Milling	E149
Technical Information for Alpha Mill	Milling	E157
Technical Information for Alpha Mill Nick		E158
Technical Information for Alpha Mill-X		E193
Technical Information for Alpha Mill-X	Milling	E142
Technical Information for Auto Tools	Turning	B121
Technical Information for Bearing Solution	Turning	B155
Technical Information for BRE	Milling	E325
Technical Information for BT/HSK Tooling System	Milling	E341
Technical Information for Couple Mill	Milling	E421
Technical Information for Cube Mill	Milling	E420
Technical Information for Drills	Technical Information	I 30
Technical Information for Endmills	Technical Information	I 27
Technical Information for Fine Tools	Multi functional Tools	C67
Technical Information for FMR P-positive	Milling	E211
Technical Information for Future Mill	Milling	E201
Technical Information for GBE	Milling	E322
Technical Information for Gear Cutter Tools	Milling	E429
Technical Information for HAVE	Milling	E337
Technical Information for HFM	Milling	E277
Technical Information for HFMD		E262
Technical Information for HFMD	Milling	E260
Technical Information for Hihg feed Cutter	Milling	E418
Technical Information for HRMDouble	Milling	E284
Technical Information for HSK Tooling System	Turning	B228



Technical Information for Indexable Reamer		F82
Technical Information for K Notch	Multi functional Tools	C55
Technical Information for KED Plus Drill	Drills	F26
Technical Information for KGT	Multi functional Tools	C07
Technical Information for KGT/MGT Cartridge	Multi functional Tools	C39
Technical Information for KHP Coolant	Turning	B199
Technical Information for KING DRILL	Drills	F05
Technical Information for KING DRILL (for large diameter drilling)	Drills	F24
Technical Information for KING DRILL (for through coolant system with a lathe)	Drills	F20
Technical Information for Laser Mill	Milling	E317
Technical Information for MGT	Multi functional Tools	C26
Technical Information for MGT Aluminum Wheel	Multi functional Tools	C43
Technical Information for Milling	Technical Information	I 20
Technical Information for Mill-max Heavy	Milling	E57
Technical Information for Multi Functional Tools Series	Multi functional Tools	C04
Technical Information for Multi Turn	Turning	B152
Technical Information for Power Buster	Milling	E64
Technical Information for Pro-A Mill	Milling	E375
Technical Information for Pro-L Mill	Milling	E379
Technical Information for Pro-L Mill		E382
Technical Information for Pro-V Mill	Milling	E351
Technical Information for Pro-X Mill	Milling	E377
Technical Information for Pro-XL Mill	Milling	E381
Technical Information for Rich Mill	Milling	E71
Technical Information for Save Turn	Turning	B114
Technical Information for Saw man	Multi functional Tools	C60
Technical Information for Saw man-X	Multi functional Tools	C63
Technical Information for Shave Mill	Milling	E423
Technical Information for Shave Mill Ultra	Milling	E425
Technical Information for Side Milling Cutters	Milling	E405
Technical Information for Tapers	Technical Information	I 24
Technical Information for TB/TB-M	Multi functional Tools	C47
Technical Information for Thread Milling	Threading	D34
Technical Information for Threading	Threading	D03
Technical Information for TP2P	Milling	E308
Technical Information for TPDB Plus Drill	Drills	F54
Technical Information for TPDB-F		F63
Technical Information for TPDB-H	Drills	F68
Technical Information for TPDC Plus Drill	Drills	F37
Technical Information for Triple Mill		E254
Technical Information for Turning	Technical Information	I 10
Technical Information for Wind Mill	Milling	E414
Technical Information for WPDC	Drills	F75
Technical Information KM Tooling System	Turning	B229
TER Tap Collet	Tooling System	G43

### K Index by items



The Comparision of Grade for Milling	Technical Information	I 41
The Comparision of Grade for Turning	Technical Information	I 40
The Comparison of Chip Breakers	Technical Information	I 36
Thread Milling Holder	Threading	D49
Thread Milling Inserts	Threading	D44
Threading Holder Code System	Threading	D02
Threading Insert Code System	Threading	D02
Threading Insert with Chip Breaker	Threading	D09
Threading Tool	Old-Fashioned Product Information	J03
Tooling System Index	Tooling System	G02
TP2P	Milling	E311
TPDB Plus Drill	Drills	F57
TPDB-F		F66
TPDB-H	Drills	F71
TPDC Plus Drill	Drills	F47
Trapez DIN 103	Threading	D24
Triple Mill		E258
Turbo Mill	Milling	E59
Turning grade selections	Grades & Chip Breakers	A04
Turning Insert (Negative)	Turning	B36
Turning Insert (Positive)	Turning	B73
Turning Insert Code System (ISO)	Turning	B34



Uncoated carbide grades (Milling)	Grades & Chip Breakers	A23
Uncoated carbide grades (Turning)	Grades & Chip Breakers	A12
UNJ (Unified Constant Thread)	Threading	D26



Vertical Type Holder Threading D33



Washer	Parts	H07
Wedge Clamp System(Holder)	Turning	B179
Wind Mill	Milling	E416
With Worth	Threading	D18
Workpiece material grades	Technical Information	102
WPDC	Drills	F79
Wrench	Parts	H07
Wrench Bolt	Parts	H04





A		
ADKA	Milling insert (Indexable Endmill)	E04
ADKT-ML	Milling insert (Alpha Mill-X)	E04
ADKT-MM	Milling insert (Alpha Mill-X)	E04
ADLT	Milling insert (Tank Mill)	E04
ADN(M)4000	Mill-max	E47
ADN(M)5000+	Mill-max Plus	E48
ADS4000	Turbo Mill	E59
ADS5000	Turbo Mill	E60
AE(M)4000	Mill-max	E49
AE(M)5000	Mill-max	E50
AFO(M)4000	Double Mill	E62
AFO(M)5000	Double Mill	E63
AMC(M)1000S	Alpha Mill	E164
AMC(M)1000SE	Alpha Mill	E170
AMC(M)1500S	Alpha Mill	E165
AMC(M)2000M	Alpha Mill	E172
AMC(M)2000S	Alpha Mill	E166
AMC(M)2000SE	Alpha Mill	E170
AMC(M)3000M	Alpha Mill	E173
AMC(M)3000S	Alpha Mill	E167
AMC(M)3000SE	Alpha Mill	E171
AMC(M)3000S-K	Alpha Mill	E168
AMC(M)4000M	Alpha Mill	E174
AMC(M)4000S	Alpha Mill	E169
AMM1000	Alpha Mill	E190
AMM1500	Alpha Mill	E191
AMM2000	Alpha Mill	E192
AMS1000M	Alpha Mill	E185
AMS1000MH	Alpha Mill	E188
AMS1000S	Alpha Mill	E175
AMS1000SE	Alpha Mill	E183
AMS1500M	Alpha Mill	E185
AMS1500MH	Alpha Mill	E188
AMS1500S	Alpha Mill	E176
AMS2000M	Alpha Mill	E186
AMS2000MH	Alpha Mill	E189
AMS2000S	Alpha Mill	E178
AMS2000SE	Alpha Mill	E183
AMS3000MH(-K)	Alpha Mill	E189
AMS3000S	Alpha Mill	E179
AMS3000SE	Alpha Mill	E184
AMS3000S-K	Alpha Mill	E180
AMS4000M	Alpha Mill	E187
AMS4000S	Alpha Mill	E181
AMXCM-AD10/12	Alpha Mill-X	E197

AMXCM-AD17 Alpha Mill-X E199  AMXS-AD10/12 Alpha Mill-X E200  AMXS-AD17 Alpha Mill-X E200  APD(M)-A Aero Mill E151  APD(M)-PB Aero Mill-Plus E152  API Thread Insert D29  APKT Milling Insert (Alpha Mill) E04  APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06			
AMXS-AD10/12 Alpha Mill-X E199  AMXS-AD17 Alpha Mill-X E200  APD(M)-A Aero Mill E151  APD(M)-PB Aero Mill-Plus E152  API Thread Insert D29  APKT Milling Insert (Alpha Mill) E04  APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05			
AMXS-AD17 Alpha Mill-X E200  APD(M)-A Aero Mill E151  APD(M)-PB Aero Mill-Plus E152  API Thread Insert D29  APKT Milling Insert (Alpha Mill) E04  APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05	AMXCM-AD17	Alpha Mill-X	E198
APD(M)-A Aero Mill APD(M)-PB Aero Mill-Plus E152 API Thread Insert D29 APKT Milling Insert (Alpha Mill) E04 APKT-MA Milling Insert (Alpha Mill) E04 APKT-MA2 Milling Insert (Alpha Mill) E04 APKT-MA3 Milling Insert (Alpha Mill) E04 APKT-MF Milling Insert (Alpha Mill) E04 APKT-MF Milling Insert (Alpha Mill) E04 APKT-MM Milling Insert (Alpha Mill) E04 APKT-MM Milling Insert (Alpha Mill) E05 APMT-MA Milling Insert (Alpha Mill) E05 APMT-MA Milling Insert (Alpha Mill) E05 APMT-ML Milling Insert (Alpha Mill) E06	AMXS-AD10/12	Alpha Mill-X	E199
APD(M)-PB Aero Mill-Plus E152  API Thread Insert D29  APKT Milling Insert (Alpha Mill) E04  APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E05	AMXS-AD17	Alpha Mill-X	E200
API Thread Insert D29  APKT Milling Insert (Alpha Mill) E04  APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APLT Milling Insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05	APD(M)-A	Aero Mill	E151
APKT Milling Insert (Alpha Mill) E04  APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E05	APD(M)-PB	Aero Mill-Plus	E152
APKT-MA Milling Insert (Alpha Mill) E04  APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06	API	Thread Insert	D29
APKT-MA2 Milling Insert (Alpha Mill) E04  APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APLT Milling insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E05	APKT	Milling Insert (Alpha Mill)	E04
APKT-MA3 Milling Insert (Alpha Mill) E04  APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APLT Milling Insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06	APKT-MA	Milling Insert (Alpha Mill)	E04
APKT-MF Milling Insert (Alpha Mill) E04  APKT-MM Milling Insert (Alpha Mill) E04  APLT Milling insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E05	APKT-MA2	Milling Insert (Alpha Mill)	E04
APKT-MM Milling Insert (Alpha Mill) E04  APLT Milling insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06	APKT-MA3	Milling Insert (Alpha Mill)	E04
APLT Milling insert (Tank Mill) E05  APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06	APKT-MF	Milling Insert (Alpha Mill)	E04
APMT-MA Milling Insert (Alpha Mill) E05  APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06	APKT-MM	Milling Insert (Alpha Mill)	E04
APMT-ML Milling Insert (Alpha Mill) E05  APMT-MM Milling Insert (Alpha Mill) E06	APLT	Milling insert (Tank Mill)	E05
APMT-MM Milling Insert (Alpha Mill) E06	APMT-MA	Milling Insert (Alpha Mill)	E05
	APMT-ML	Milling Insert (Alpha Mill)	E05
APMT-MN Milling Insert (Alpha Mill) E06	APMT-MM	Milling Insert (Alpha Mill)	E06
	APMT-MN	Milling Insert (Alpha Mill)	E06

D		
BAMPR/L-XAF	Milling Insert (Aero Mill-Plus)	E07
BAMPR/L-XAW	Milling Insert (Aero Mill-Plus)	E07
BAMPR/L-XAWR	Milling Insert (Aero Mill-Plus)	E07
BF	Multi functional Insert (Grooving Tools)	C71
BFE	BFE	E331
BRE	BRE	E335
BT30	Modular Adaptor (BT)	E403
BT30 AM1000	BT Tooling System (Mono-Tool)	E347
BT30 AM1000HS	BT Tooling System (Alpha Mill)	E342
BT30 AM1500	BT Tooling System (Mono-Tool)	E348
BT30 AM2000	BT Tooling System (Mono-Tool)	E349
BT40	Modular Adaptor (BT)	E403
BT40 AM1000	BT Tooling System (Mono-Tool)	E347
BT40 AM1500	BT Tooling System (Mono-Tool)	E348
BT40 AM1500HS	BT Tooling System (Alpha Mill)	E343
BT40 AM2000	BT Tooling System (Mono-Tool)	E349
BT40 AM2000HS	BT Tooling System (Alpha Mill)	E344
BT50	Modular Adaptor (BT)	E403
BT50 AM3000	BT Tooling System (Mono-Tool)	E350
BT50 AM3000HS	BT Tooling System (Alpha Mill)	E345
BT50 AM4000	BT Tooling System (Mono-Tool)	E351
BT50 AM4000HS	BT Tooling System (Alpha Mill)	E346
BT50 HAT4000	BT Tooling System (Mono-Tool)	E352





CCET	Turning Insert_Positive (Carbide Shank Boring Bar)	B75
CCET-KF	Auto tools Insert (ISO type)	B130
CCET-KF	Auto tools Insert (ISO type)	B76
CCET-KM	Auto tools Insert (ISO type)	B131
CCET-KM	Auto tools Insert (ISO type)	B77
CCGT-AK	Aluminum Insert_Positive (Screw on System)	B103
CCGT-AR	Aluminum Insert_Positive (Screw on System)	B103
CCGT-FS	Auto tools Insert (ISO type)	B131
CCGT-FS	Turning Insert_Positive (Screw on System)	B74
CCGT-KF	Auto tools Insert (ISO type)	B130
CCGT-KF	Turning Insert_Positive (Screw on System)	B76
CCGT-KM	Auto tools Insert (ISO type)	B130
CCGT-KM	Turning Insert_Positive (Screw on System)	B77
CCGT-MS	Auto tools Insert (ISO type)	B131
CCGT-MS	Turning Insert_Positive (Screw on System)	B74
CCGT-VP1	Auto tools Insert (ISO type)	B131
CCGT-VP1	Turning Insert_Positive (Screw on System)	B75
CCLNR/L	Ceramic Holder	B197
ССМТ	PCD Insert_Positive	B113
CCMT-C25	Turning Insert_Positive (Screw on System)	B74
CCMT-FP	Turning Insert_Positive (Screw on System)	B73
ССМТ-НМР	Turning Insert_Positive (Screw on System)	B73
CCMT-MP	Turning Insert_Positive (Screw on System)	B73
CCMT-VF	Turning Insert_Positive (Screw on System)	B73
CCMT-VL	Turning Insert_Positive (Screw on System)	B73
CCMT-VP1	Turning Insert_Positive (Screw on System)	B74
CCMW	cBN Insert_Positive (Regrinding)	B112
CCMW	PCD Insert_Positive	B113
ССТ	Solid Chamfer Tool	E373
CD	Drill Insert (Center Drill)	F78
CDEW-NAF	Milling Insert (Aero Mill)	E07
CDEW-NAW	Milling Insert (Aero Mill)	E07
CDEW-XAF	Milling Insert (Aero Mill)	E07
CDEW-XAW	Milling Insert (Aero Mill)	E07
CDEW-XCF	Milling Insert (Aero Mill)	E07
CDH	Drill Insert (Center Drill)	F78
CE	Chamfer Tool (Back & Front Champer)	E369
CE	Chamfer Tool (Long Champer)	E370
CE	Chamfer Tool (Multi-functional)	E371
CET	Solid Chamfer Tool	E372
CKFNR/LRW	Bearing Solution	B159
CKGNRRW	Bearing Solution	B159
CKJNR/L	Holder (Clamp on System)	B181
CKNNR/L	Holder (Clamp on System)	B181
CKUNR/L	Boring Bar (Clamp on System)	B212



CMSNR/LB	Bearing Solution	B156
CMSNR/LF	Bearing Solution	B156
CNGG-VP1	Turning Insert_Negative (Multi Lock/Lever Lock System)	B40
CNGG-VP3	Turning Insert_Negative (Multi Lock/Lever Lock System)	B41
CNHQ	Milling Insert (Side milling cutter_Tangential type)	E07
CNMA	cBN Insert_Negative(Regrinding)	B112
CNMA	Turning Insert_Negative (Multi Lock / Lever Lock System)	B39
CNMG-B25	Turning Insert_Negative (Multi Lock/Lever Lock System)	B38
CNMG-CP	Turning Insert_Negative (Multi Lock/Lever Lock System)	B36
CNMG-GR	Turning Insert_Negative (Multi Lock/Lever Lock System)	B38
CNMG-HA	Turning Insert_Negative (Multi Lock/Lever Lock System)	B41
CNMG-HM	Turning Insert_Negative	B37
CNMG-LP	Turning Insert_Negative (Multi Lock/Lever Lock System)	B36
CNMG-LW	Turning Insert_Negative (Multi Lock/Lever Lock System)	B42
CNMG-MK	Turning Insert_Negative (Multi Lock/Lever Lock System)	B38
CNMG-MM	Turning Insert (SAVE TURN)	B115
CNMG-MM	Turning Insert_Negative (Multi Lock/Lever Lock System)	B40
CNMG-MP	Turning Insert (SAVE TURN)	B115
CNMG-MP	Turning Insert_Negative (Multi Lock/Lever Lock System)	B37
CNMG-RK	Turning Insert_Negative (Multi Lock/Lever Lock System)	B39
CNMG-RM	Turning Insert_Negative (Multi Lock/Lever Lock System)	B40
CNMG-VB	Turning Insert_Negative (Multi Lock/Lever Lock System)	B36
CNMG-VC	Turning Insert_Negative (Multi Lock/Lever Lock System)	B36
CNMG-VF	Turning Insert_Negative (Multi Lock/Lever Lock System)	B36
CNMG-VL	Turning Insert_Negative (Multi Lock/Lever Lock System)	B36
CNMG-VM	Turning Insert_Negative (Multi Lock/Lever Lock System)	B37
CNMG-VP1	Turning Insert_Negative (Multi Lock/Lever Lock System)	B40
CNMG-VP2	Turning Insert_Negative (Multi Lock/Lever Lock System)	B41
CNMG-VP3	Turning Insert_Negative (Multi Lock/Lever Lock System)	B41
CNMG-VP4	Turning Insert_Negative (Multi Lock/Lever Lock System)	B41
CNMG-VQ	Turning Insert (SAVE TURN)	B115
CNMG-VQ	Turning Insert_Negative (Multi Lock/Lever Lock System)	B38
CNMG-VR	Turning Insert_Negative (Multi Lock/Lever Lock System)	B39
CNMG-VW	Turning Insert_Negative (Multi Lock/Lever Lock System)	B41
CNMM	PCD Insert_Negative	B113
CNMM-GH	Turning Insert_Negative (Multi Lock / Lever Lock System)	B42
CNMM-GR	Turning Insert_Negative (Lever Lock System)	B42
CNMM-VH	Turning Insert_Negative (Lever Lock System)	B42
CNMM-VT	Turning Insert_Negative (Lever Lock System)	B42
CP Chip Breaker	Turning Chip Breaker	B16
CPGT	Turning Insert_Positive (Screw on System)	B78
CPGT-HMP	Turning Insert_Positive (Screw on System)	B78
СРМН	Milling Insert (T-Cutter)	E07
CPMT	Milling Insert (T-Cutter)	E08
CPMT-C25	Turning Insert_Positive (Screw on System)	B78



CPMT-VF	Turning Insert_Positive (Screw on System)	B78
CPMT-VL	Turning Insert_Positive (Screw on System)	B78
CRDNN	Ceramic Holder	B197
CRGNR/L	Ceramic Holder	B197
CSBNR/LBS	Bearing Solution	B160
CSDNN	Ceramic Holder	B197
CSDPN	Holder (Clamp on System)	B181
CSGNR/LRW	Bearing Solution	B159
CSKNR/L	Ceramic Holder	B198
CSKNR/LBS	Bearing Solution	B160
CSKPR/L	Holder (Clamp on System)	B182
CSKPR/L	Boring Bar (Clamp on System)	B212
CSKPR/L	Cartridge (Clamp on System)	B243
CSKPR/LB	Bearing Solution	B158
CTFNR/L	Ceramic Holder	B198
CTFPR/L	Holder (Clamp on System)	B182
CTFPR/L	Boring Bar (Clamp on System)	B212
CTFPR/L	Cartridge (Clamp on System)	B243
CTGNR/L	Ceramic Holder	B198
CTGNR/LBS	Bearing Solution	B160
CTGPR/L	Holder (Clamp on System)	B182
CTSPR/L	Cartridge (Clamp on System)	B244
CTTPR/L	Cartridge (Clamp on System)	B244

(D)		
DB	Multi functional Insert (Grooving Tools)	C70
DBH	Multi functional holder (Grooving Tools)	C70
DC	Multi functional Insert (Grooving Tools)	C70
DCBNR/L	Holder (Double clamp system)	B167
DCET-KF	Auto tools Insert (ISO type)	B132
DCET-KF	Turning Insert_Positive (Screw on System)	B81
DCET-KM	Auto tools Insert (ISO type)	B132
DCET-KM	Turning Insert_Positive (Screw on System)	B82
DCGT	PCD Insert_Positive	B113
DCGT-AK	PCD Insert_Positive  Aluminum Insert_Positive (Screw on System)	B113 B104
DCGT-AK	Aluminum Insert_Positive (Screw on System)	B104
DCGT-AK	Aluminum Insert_Positive (Screw on System)  Aluminum Insert_Positive (Screw on System)	B104 B104 B132
DCGT-AK DCGT-AR DCGT-FS	Aluminum Insert_Positive (Screw on System)  Aluminum Insert_Positive (Screw on System)  Auto tools Insert (ISO type)	B104 B104 B132
DCGT-AK DCGT-AR DCGT-FS DCGT-FS	Aluminum Insert_Positive (Screw on System)  Aluminum Insert_Positive (Screw on System)  Auto tools Insert (ISO type)  Turning Insert_Positive (Screw on System)	B104 B104 B132 B80
DCGT-AK DCGT-AR DCGT-FS DCGT-FS	Aluminum Insert_Positive (Screw on System)  Aluminum Insert_Positive (Screw on System)  Auto tools Insert (ISO type)  Turning Insert_Positive (Screw on System)  Auto tools Insert (ISO type)	B104 B104 B132 B80 B131
DCGT-AK DCGT-AR DCGT-FS DCGT-FS DCGT-KF	Aluminum Insert_Positive (Screw on System) Aluminum Insert_Positive (Screw on System) Auto tools Insert (ISO type) Turning Insert_Positive (Screw on System) Auto tools Insert (ISO type) Turning Insert_Positive (Screw on System)	B104 B104 B132 B80 B131 B81 B132

Cartridge (Clamp on System)

B245

CTWPR/L

D		
DCGT-MS	Turning Insert_Positive (Screw on System)	R80
DCGT-VP1	Auto tools Insert (ISO type)	B133
DCGT-VP1	Turning Insert_Positive (Screw on System)	
DCGW	cBN Insert_Positive (Regrinding)	B112
DCKNR/L	Holder (Double clamp system)	B167
DCLNR/L	Holder (Double clamp system)	B167
DCLNR/L	Boring Bar (Double clamp system)	B208
DCLNR/L	HSK Tooling System	B231, 235
DCLNR/L	KM Tooling System	B237
DCMNN	HSK Tooling System	B231
DCMNN	KM Tooling System	B237
DCMT	PCD Insert Positive	B113
DCMT-C25	Turning Insert Positive (Screw on System)	B80
DCMT-FP	Turning Insert_Positive (Screw on System)	B79
DCMT-HMP	Turning Insert_Positive (Screw on System)	
DCMT-MP	Turning Insert_Positive (Screw on System)	
DCMT-VF	Turning Insert_Positive (Screw on System)	B79
DCMT-VL	Turning Insert_Positive (Screw on System)	B79
DCMT-VP1	Turning Insert_Positive (Screw on System)	B80
DDJNR/L	Holder (Double clamp system)	B168
DDJNR/L	HSK Tooling System	B231
DDJNR/L	KM Tooling System	B237
DDNNN	HSK Tooling System	B231
DDNNN	KM Tooling System	B238
DDUNR/L	Boring Bar (Double clamp system)	B208
DF	Side Cutter	E413
DNGG-VP1	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B47
DNGG-VP3	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B47
DNMA	cBN Insert_Negative (Regrinding)	B112
DNMA	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B46
DNMG-B25	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B45
DNMG-CP	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B44
DNMG-GR	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B45
DNMG-HA	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B48
DNMG-HM	Turning Insert_Negative	B44
DNMG-LP	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B43
DNMG-LW	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B48
DNMG-MK	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B46
DNMG-MM	Turning Insert_SAVE TURN	B115
DNMG-MM	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	
DNMG-MP	Turning Insert_SAVE TURN	B115
DNMG-MP	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	
DNMG-RK	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	
DNMG-RM	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	
DNMG-VB	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B43





DNMG-VC	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B44
DNMG-VF	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B43
DNMG-VL	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B43
DNMG-VM	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B45
DNMG-VP1	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B47
DNMG-VP2	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B47
DNMG-VP3	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B47
DNMG-VP4	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B48
DNMG-VQ	Turning Insert_SAVE TURN	B115
DNMG-VQ	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B45
DNMG-VR	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B46
DNMG-VW	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B48
DNMM	PCD Insert_Negative/Positive	B113
DNMX-SH	Turning Insert_Negative (Multi Lock/Lever Lock, HSK Tooling System)	B48
DNMX-SR	Turning Insert_Negative	B48
DSBNR/L	Holder (Double clamp system)	B168
DSDNN	Holder (Double clamp system)	B169
DSKNR/L	Holder (Double clamp system)	B169
DSKNR/L	Boring Bar (Double clamp system)	B208
DSSNR/L	Holder (Double clamp system)	B169
DTFNR/L	Holder (Double clamp system)	B170
DTFNR/L	Boring Bar (Double clamp system)	B209
DTGNR/L	Holder (Double clamp system)	B170
DVJNR/L	Holder (Double clamp system)	B170
DVVNN	Holder (Double clamp system)	B171
DWLNR/L	Holder (Double clamp system)	B171
DWLNR/L	Boring Bar (Double clamp system)	B209



E2D	Drill (KED Plus-2D)	F29~30
E3D	Drill (KED Plus-3D)	F31~32
E4D	Drill (KED Plus-4D)	F33~34
E5D	Drill (KED Plus-5D)	F35~36
EF(M)4000	Mill-max	E51
EN(M)4000	Mill-max	E52
EPN(M)4000	Mill-max	E53
EPN(M)5000+	Mill-max Plus	E54
ER(L)	Thread I nsert	D10~30
ER(L)H	Thread External Holder (Screw on System)	D31
ER(L)H-C	Thread External Holder (Clamp on System)	D31
ERM	Thread Insert	D10~19
EV2525R/L-105-3	HSK Tooling System	B236
EV2525R/L-112	HSK Tooling System	B236
EV2525R/L-115	HSK Tooling System	B236



FGD	MGT Insert	C28
FGHH	MGT Holder (Face Grooving)	C37
FGM	MGT Insert	C28
FGVH	MGT Holder (Face Grooving)	C38
FMAC(M)3000	Future Mill	E216
FMAC(M)3000-A	Future Mill (Aluminum body)	E218
FMAC(M)4000	Future Mill	E217
FMAC(M)4000-A	Future Mill (Aluminum body)	E219
FMAS3000	Future Mill	E220
FMAS4000	Future Mill	E221
FMM	MGT Insert	C28
FMPC(M)3000	Future Mill	E222
FMPC(M)3000-A	Future Mill (Aluminum body)	E224
FMPC(M)4000	Future Mill	E223
FMPC(M)4000-A	Future Mill (Aluminum body)	E225
FMPS3000	Future Mill	E226
FMPS4000	Future Mill	E227
FMRC(M)3000	Future Mill	E228
FMRC(M)4000	Future Mill	E229
FMRC(M)4000	Future Mill P-Positive	E243
FMRC(M)5000	Future Mill	E230
FMRC(M)5000	Future Mill P-Positive	E244
FMRC(M)6000	Future Mill	E231
FMRC(M)6000	Future Mill P-Positive	E245
FMRCM3000	Future Mill P-Positive	E242
FMRM1000	Future Mill	E238
FMRM1500	Future Mill	E238
FMRM2000	Future Mill	E239
FMRM2500	Future Mill	E239
FMRM2500	Future Mill P-Positive	E250
FMRM3000	Future Mill	E240
FMRM3000	Future Mill P-Positive	E251
FMRM4000	Future Mill	E241
FMRM4000	Future Mill P-Positive	E252
FMRM5000	Future Mill	E241
FMRM5000	Future Mill P-Positive	E253
FMRS1000	Future Mill	E232
FMRS1500	Future Mill	E232
FMRS2000	Future Mill	E233
FMRS2500	Future Mill	E233
FMRS2500	Future Mill P-Positive	E246
FMRS3000	Future Mill	E234
FMRS3000	Future Mill P-Positive	E247
FMRS4000	Future Mill	E235
FMRS4000	Future Mill P-Positive	E248



F		
FMRS5000	Future Mill	E236
FMRS5000	Future Mill P-Positive	E249
FMRS6000	Future Mill	E237
FMRS6000	Future Mill P-Positive	E249
FP Chip Breaker	Turning Chip Breaker	B17
FS Chip Breaker	Turning Chip Breaker	B18

G		
GBE	GBE (Single edge type)	E332
GBEM	GBE (Modular type)	E334
GBE-M	GBE (Multi edge type)	E333
GFIP	Multi functional holder (Grooving Tools)	C71
GW	Multi functional Insert (Grooving Tools)	C71

HAVE (Multi Edge type)	E339
HAVE (Single Edge type)	E340
Mill-max Heavy	E58
Mill-max Heavy	E58
Milling Insert (High feed Cutter)	E08
HFMD (Cutter)	E273
HFMD (Cutter)	E272
HFMD (Modular)	E274
HFMD (Modular)	E275
HFMD (Modular)	E276
HFMD (Shank)	E267
HFMD (Shank)	E269
HFMD (Shank)	E271
HFMD (Modular)	E283
HFMD (Shank)	E281
Milling Insert (High feed Cutter)	E08
Milling Insert (High feed Cutter)	E08
HRM	E300
HRM	E301
HRMDouble	E289
HRMDouble	E290
HRMDouble	E291
HRMDouble	E297
HRMDouble	E298
	HAVE (Single Edge type)  Mill-max Heavy  Mill-max Heavy  Milling Insert (High feed Cutter)  HFMD (Cutter)  HFMD (Modular)  HFMD (Modular)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Heddular)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  HFMD (Shank)  Milling Insert (High feed Cutter)  HRM  HRM  HRM  HRM  HRM  HRMDouble  HRMDouble  HRMDouble

HRMDouble

HRMDouble

HRMDouble

HRMDouble

E299

E292

E293

E295

HRMDM 13

HRMDS06

HRMDS09

HRMDS13

HRMM08	HRM	E305
HRMM10	HRM	E306
HRMM13	HRM	E306
HRMS 08	HRM	E302
HRMS 10	HRM	E302
HRMS 13	HRM	E303
HRMS 15	HRM	E304
HSK100A	Modular Adaptor (HSK)	E404
HSK100A AM3000	HSK Tooling System (Mono-Tool)	E361
HSK100A AM4000	HSK Tooling System (Mono-Tool)	E362
HSK63A	Modular Adaptor (HSK)	E404
HSK63A AM1000	HSK Tooling System (Mono-Tool)	E358
HSK63A AM1000HS	HSK Tooling System (Alpha Mill)	E353
HSK63A AM1500	HSK Tooling System (Mono-Tool)	E359
HSK63A AM1500HS	HSK Tooling System (Alpha Mill)	E354
HSK63A AM2000	HSK Tooling System (Mono-Tool)	E360
HSK63A AM2000HS	HSK Tooling System (Alpha Mill)	E355
HSK63A AM3000HS	HSK Tooling System (Alpha Mill)	E356
HSK63A AM4000HS	HSK Tooling System (Alpha Mill)	E357
HSK63A/100A PAX5000	Pro-X Mill	E393
HSK-XD19	HSK Tooling System (Mono-Tool)	E363

IG	Multi functional Insert (Grooving Tools)	C70
IG	Multi functional holder (Grooving Tools)	C70
IR(L)	Thread Insert	D10~30
IR(L)H	Thread External Holder (Screw on System)	D32
IR(L)H-C	Thread External Holder (Clamp on System)	D32
IRB	Indexable Reamer (Stuffed hole)	F87
IRM	Thread Insert	D10~21
IRT	Indexable Reamer (Throughout hole)	F86

K2D	KING DRILL-2D	F11~12
K2D	KING DRILL (for through coolant system with a lathe)-2D	F21
K2D	KING DRILL (for large diameter drilling)-2D	F25
K3D	KING DRILL-3D	F13~15
K3D	KING DRILL (for through coolant system with a lathe)-3D	F22
K3D	KING DRILL (for large diameter drilling)-3D	F25
K3D*	KING DRILL (for machining a tap foundation hole)-3D	F13~14
K4D	KING DRILL-4D	F16~17
K4D	KING DRILL (for through coolant system with a lathe)-4D	F23
K4D	KING DRILL (for large diameter drilling)-4D	F25





K5D	KING DRILL-5D	F18~19
KCER/L	Multi functional (KGT Cartridge)	C41
KCFR/L	Multi functional (KGT Cartridge)	C41
KEL-ANN	Milling insert (Storm Mill)	E08
KEL-MF	Milling insert (Gear cutter)	E08
KEL-QNN	Milling insert (Storm Mill)	E08
KGEHR/L	Multi functional (KGT Holder)	C15
KGEHR/L-D00A	Multi functional (Auto Tool Holder)	C17
KGEHR/L-D00B	Multi functional (Auto Tool Holder)	C17
KGEHR/L-DOOA	Auto tools (KGT type)	B143
KGEHR/L-DOOB	Auto tools (KGT type)	B143
KGEHR/L-T00	Multi functional (KGT Holder)	C18
KGEUR/L	Multi functional (KGT Holder)	C20
KGEVR/L-T00	Multi functional (KGT Holder)	C19
KGFHR/L	Multi functional (KGT Holder)	C22
KGFVR/L	Multi functional (KGT Holder)	C21
KGGN-A	Multi functional Insert (KGT series)	C14
KGGN-B	Multi functional Insert (KGT series)	C13
KGGN-R	Multi functional Insert (KGT series)	C14
KGIUR/L	Multi functional (KGT Holder)	C23
KGIVR/L	Multi functional (KGT Holder)	C24
KGMI-T	Multi functional Insert (KGT series)	C13
KGML-LP	Auto tools Insert (KGT type)	B144
KGML-LP	Multi functional Insert (KGT series)	C13
KGML-RP	Auto tools Insert (KGT type)	B144
KGML-RP	Multi functional Insert (KGT series)	C13
KGMN-C	Auto tools Insert (KGT type)	B144
KGMN-L	Auto tools Insert (KGT type)	B143
KGMN-L	Multi functional Insert (KGT series)	C12
KGMN-R	Auto tools Insert (KGT type)	B143
KGMN-R	Multi functional Insert (KGT series)	C12
KGMN-T	Auto tools Insert (KGT type)	B143
KGMN-T	Multi functional Insert (KGT series)	C12
KGMR-LP	Auto tools Insert (KGT type)	B144
KGMR-LP	Multi functional Insert (KGT series)	C13
KGMR-RP	Auto tools Insert (KGT type)	B144
KGMR-RP	Multi functional Insert (KGT series)	C13
КСТВ	KGT Blade for Parting off	C25
KM-DCLNR/L	KM Tooling System	B240
KNB	Multi functional Insert (K Notch, Metric)	C57
KNG	Multi functional Insert (K Notch, Metric)	C57
KNG	Multi functional Insert (K Notch, Inch)	C58
KNGP	Multi functional Insert (K Notch, Metric)	C57
KNGP	Multi functional Insert (K Notch, Inch)	C58
KNR	Multi functional Insert (K Notch, Inch)	C58



KNRP	Multi functional Insert (K Notch, Inch)	C58
KNSR	Multi functional (K Notch Holder)	C59
KNT	Multi functional Insert (K Notch, Threading)	C57
KNUX-11	Turning Insert_Negative (Clamp on System)	B49
KNUX-12	Turning Insert_Negative (Clamp on System)	B49
KRGN-A	Multi functional Insert (KGT series)	C14
KRMI-C	Multi functional Insert (KGT series)	C12
KRMN-C	Auto tools Insert (KGT type)	B144
KRMN-C	Multi functional Insert (KGT series)	C12
KSPB	Multi functional (Saw Man-X, Blade)	C65
KSPH	Multi functional(Saw Man-X, Shank)	C66



LBE08/10/12/16/20/25/30/32	Laser Mill (Carbide Shank-Ball, Straight type)	E326
LBE08/10/12/16/20/25/30/32	Laser Mill (Steel Shank-Ball, Taper type)	E327
LBE12/16/20/25/30/32	Laser Mill (Steel Shank-Ball, Straight type)	E327
LBE-MHD	Laser Mill (Modular type)	E330
LBH	Milling Insert (Laser Mill)	E08
LBH-KF	Milling Insert (Laser Mill)	E08
LBH-KH	Milling Insert (Laser Mill)	E09
LBS	Milling Insert (Laser Mill)	E09
LCF	Milling Insert (Laser Mill)	E09
LDET	Milling Insert (Pro-XL Mill)	E09
LDET-MA	Milling Insert (Pro-XL Mill)	E10
LFH	Milling Insert (Laser Mill)	E09
LNCS	Milling Insert (Rich Mill)	E10
LNE	Milling Insert (Gear cutter)	E10
LNEX-MA	Milling Insert (Rich Mill)	E11
LNEX-MF	Milling Insert (Rich Mill)	E11
LNEX-MM	Milling Insert (Rich Mill)	E11
LNKT-MA	Milling Insert (TP2P)	E10
LNKT-ML	Milling Insert (TP2P)	E11
LNKT-MM	Milling Insert (TP2P)	E11
LNMX-MF	Milling Insert (Rich Mill)	E11
LNMX-MF	Milling Insert (HFMD)	E12
LNMX-ML	Milling Insert (HFMD)	E12
LNMX-MM	Milling Insert (Rich Mill)	E11
LNMX-MM	Milling Insert (HFMD)	E12
LP Chip Breaker	Turning Chip Breaker	B20
LPEW	Milling Insert (HFM)	E12
LPMT-MF	Milling Insert (HFM)	E12
LPMW	Milling Insert (HFM)	E13
LR	Milling Insert (Laser Mill)	E09
LRE10/12	Laser Mill (Steel Shank-Corner R, Taper type)	E329





LRE10/12/16/20/25/30/32	Laser Mill (Carbide Shank-Corner R, Straight type)	E328
LRE12/16/25/30/32	Laser Mill (Steel Shank-Corner R, Straight type)	E329
LRH	Milling Insert (Laser Mill)	E09
LW Chip Breaker	Turning Chip Breaker	B32
LXET-MA	Milling Insert (Pro-L Mill)	E13
LXET-ML	Milling Insert (Pro-L Mill)	E13



MAPD000HR/L-Z0	Aero Mill-Mini	E155
MAPDS000HR/L-Z0	Aero Mill-Mini	E154
MAT	Modular Adaptor (Steel Shank)	E401
MAT-C	Modular Adaptor (Carbide Shank)	E402
MBBR	Auto tools (MSB Tools_Back Boring)	B148
MBCR	Auto tools (MSB Tools_Copying)	B147
MBFR	Auto tools ((MSB Tools_Chamfering)	B148
MBR	Auto tools ((MSB Tools_Boring)	B147
МС	Multi functional Insert (Bearing Solution)	B156
MCER/L	HSK Tooling System (Cartridge)	B234
MCER/L	KM Tooling System (Cartridge)	B240
MCER/L	Multi functional (MGT Cartridge)	C42
MCFR/L	HSK Tooling System (Cartridge)	B235
MCFR/L	Multi functional (MGT Cartridge)	C42
MCHR/L	HSK Tooling System	B234
MCHR/L	KM Tooling System (Cartridge)	B239
MCHR/L	Multi functional (MGT Cartridge Holder)	C40
MCKNR/L	Holder (Multi Lock System)	B183
MCLNR/L	Holder (Multi Lock System)	B183
MCLNR/L	Boring Bar (Multi Lock System)	B213
MCMNN	Holder (Multi Lock System)	B183
MCRNR/L	Holder (Multi Lock System)	B184
MCVR/L	Multi functional (MGT Cartridge Holder)	C40
MDJNR/L	Holder (Multi Lock System)	B184
MDNNN	Holder (Multi Lock System)	B184
MDQNR/L	Holder (Multi Lock System)	B185
MDUNR/L	Boring Bar (Multi Lock System)	B213
MFMN	Multi functional Insert (MGT Cartridge, MGT)	C28
MGEHR/L	Auto tools (MGT type)	B144
MGEHR/L	Multi functional (MGT Holder)	C31
MGEHR/L	Multi functional (MGT for Aluminum Wheel)	C45
MGEHR/L-15	Multi functional (MGT for Aluminum Wheel)	C45
MGEUR/L	Multi functional (MGT Holder)	C32
MGEVR/L	Multi functional (MGT Holder)	C33
MGEXR/L	Multi functional (MGT for Aluminum Wheel)	C46
MGFHR/L	Multi functional (MGT Holder)	C36



MGFR	Auto tools (MSB Tools_Face Grooving)	B150
MGFVR/L	Multi functional (MGT Holder)	C36
MGGN-A	Multi functional Insert (MGT Cartridge, MGT)	C29
MGGN-M	Multi functional Insert (MGT Cartridge, MGT)	C28
MGIUR/L	Multi functional (MGT Holder)	C34
MGIUR/L-MR	Multi functional (MGT for Aluminum Wheel)	C45
MGIUR/L-MV	Multi functional (MGT for Aluminum Wheel)	C46
MGIVR/L	Multi functional (MGT Holder)	C35
MGIXR/L-MR	Multi functional (MGT for Aluminum Wheel)	C46
MGML-PS	Multi functional Insert (MGT Cartridge, MGT)	C30
MGML-PT	Multi functional Insert (MGT Cartridge, MGT)	C30
MGMN-G	Auto tools Insert (MGT type)	B144
MGMN-G	Multi functional Insert (MGT Cartridge, MGT)	C28
MGMN-L	Multi functional Insert (MGT Cartridge, MGT)	C29
мдми-м	Auto tools Insert (MGT type)	B144
MGMN-M	Multi functional Insert (MGT Cartridge, MGT)	C28
MGMN-R	Multi functional Insert (MGT Cartridge, MGT)	C29
MGMN-T	Multi functional Insert (MGT Cartridge, MGT)	C29
MGMR-PS	Multi functional Insert (MGT Cartridge, MGT)	C30
MGMR-PT	Multi functional Insert (MGT Cartridge, MGT)	C30
MGR	Auto tools (MSB Tools_Square Grooving)	B149
MGRR	Auto tools (MSB Tools_Round Grooving)	B150
MK Chip Breaker	Turning Chip Breaker	B24
MK Chip Breaker MM Chip Breaker	Turning Chip Breaker Turning Chip Breaker	B24 B22
MM Chip Breaker	Turning Chip Breaker	B22
MM Chip Breaker MP Chip Breaker	Turning Chip Breaker Turning Chip Breaker	B22 B21
MM Chip Breaker MP Chip Breaker MPMT	Turning Chip Breaker Turning Chip Breaker Milling Insert	B22 B21 E14
MM Chip Breaker MP Chip Breaker MPMT MRGN-A	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)	B22 B21 E14 C30
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)	B22 B21 E14 C30 C44
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)	B22 B21 E14 C30 C44 C30
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker	B22 B21 E14 C30 C44 C30 B19
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN	Turning Chip Breaker Turning Chip Breaker Milling Insert Multi functional Insert (MGT Cartridge, MGT) Multi functional Insert (MGT for Aluminum Wheel) Multi functional Insert (MGT Cartridge, MGT) Turning Chip Breaker Holder (Multi Lock System) Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B185
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT or Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B185
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B185 B186 B213
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSRNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B185 B186 B213
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSRNR/L MSRNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B186 B213 B186 B187
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSRNR/L MSRNR/L MSSNR/L MSSNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Multi functional (Multi Turn)	B22 B21 E14 C30 C44 C30 B19 B185 B185 B186 B213 B186 B187
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSKNR/L MSRNR/L MSRNR/L MSRNR/L MT	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B186 B213 B186 B213 B186 B187
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSRNR/L MSRNR/L MT MTENN MTFNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Multi functional (Multi Turn)  Holder (Multi Lock System)  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B185 B186 B213 B186 B213 B186 B187 B187
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSKNR/L MSRNR/L MSRNR/L MT MTENN MTFNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B186 B213 B186 B213 B186 B187 B154 B187 B187 B214
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSRNR/L MSRNR/L MT MTENN MTFNR/L MTFNR/L MTFNR/L MTGNR/L	Turning Chip Breaker Turning Chip Breaker Milling Insert Multi functional Insert (MGT Cartridge, MGT) Multi functional Insert (MGT for Aluminum Wheel) Multi functional Insert (MGT Cartridge, MGT) Turning Chip Breaker Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Boring Bar (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Holder (Multi Lock System) Boring Bar (Multi Lock System) Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B185 B186 B213 B186 B213 B186 B187 B154 B187 B154 B187
MM Chip Breaker MP Chip Breaker MPMT MRGN-A MRGN-A MRMN-M MS Chip Breaker MSBNR/L MSDNN MSKNR/L MSKNR/L MSRNR/L MSRNR/L MT MTENN MTFNR/L MTFNR/L MTGNR/L MTJNR/L	Turning Chip Breaker  Turning Chip Breaker  Milling Insert  Multi functional Insert (MGT Cartridge, MGT)  Multi functional Insert (MGT for Aluminum Wheel)  Multi functional Insert (MGT Cartridge, MGT)  Turning Chip Breaker  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Boring Bar (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)  Holder (Multi Lock System)	B22 B21 E14 C30 C44 C30 B19 B185 B186 B213 B186 B213 B186 B187 B154 B187 B154 B188 B188 B188







MVQNR/L	Holder (Multi Lock System)	B189
MVUNR/L	Boring Bar (Multi Lock System)	B214
MVVNN	Holder (Multi Lock System)	B189
MWLNR/L	Holder (Multi Lock System)	B189
MWLNR/L	Boring Bar (Multi Lock System)	B214



NFTFR/L	Multi functional Insert ( Fine Tools)	C69
NFTGR/L	Multi functional Insert ( Fine Tools)	C68
NFTIH	Multi functional (Fine Tools Holder)	C69
NFTTR/L	Multi functional Insert ( Fine Tools)	C68
NU-CCGW	cBN Insert_Positive (Multi-Corner Type)	B111
NU-CNGA	cBN Insert_Negative (Multi-Corner Type)	B110
NU-DCGW	cBN Insert_Positive (Multi-Corner Type)	B111
NU-DNGA	cBN Insert_Negative (Multi-Corner Type)	B110
NU-SNGA	cBN Insert_Negative (Multi-Corner Type)	B110
NU-TCGW	cBN Insert_Positive (Multi-Corner Type)	B111
NU-TNGA	cBN Insert_Negative (Multi-Corner Type)	B110
NU-TPGB	cBN Insert_Positive (Multi-Corner Type)	B111
NU-TPGN	cBN Insert_Positive (Multi-Corner Type)	B111
NU-TPGW	cBN Insert_Positive (Multi-Corner Type)	B111
NU-VBGW	cBN Insert_Positive (Multi-Corner Type)	B111
NU-VCGW	cBN Insert_Positive (Multi-Corner Type)	B111
NU-VNGA	cBN Insert_Negative (Multi-Corner Type)	B110



OFCN	Milling Insert (Double Mill)	E14
OFCW	Milling Insert (Double Mill)	E14
OFKR-MA	Milling Insert (Double Mill)	E14
OFKR-MF	Milling Insert (Double Mill)	E14
OFKR-MM	Milling Insert (Double Mill)	E14
OFKT-MA	Milling Insert (Double Mill)	E14
OFKT-MF	Milling Insert (Double Mill)	E14
OFKT-MM	Milling Insert (Double Mill)	E15
ONHX-MA	Milling Insert (Rich Mill)	E15
ONHX-MF	Milling Insert (Rich Mill)	E15
ONHX-ML	Milling Insert (Rich Mill)	E15
ONHX-MM	Milling Insert (Rich Mill)	E15
ONHX-W	Milling Insert (Rich Mill)	E15
ONMX-MF	Milling Insert (Rich Mill)	E15
ONMX-MM	Milling Insert (Rich Mill)	E15
ORC	O-ring Cutter	E365
ORG	Milling Insert (O-Ring Cutter)	E15



PAC(M)2000	Pro-A Mill	E385
PAC(M)4000	Pro-A Mill	E385
PALCM	Pro-L Mill	E394
PALS (Multi-edge)	Pro-L Mill	E397
PALS (Single-edge)	Pro-L Mill	E395
PAM2000	Pro-A Mill	E387
PAS2000	Pro-A Mill	E386
PAS4000	Pro-A Mill	E386
PAVCM-XD19	Pro-V Mill	E399
PAVS-XD19	Pro-V Mill	E400
PAXC(M)5000	Pro-X Mill	E388
PAXC(M)6000	Pro-X Mill	E389
PAXM5000	Pro-X Mill	E392
PAXS5000	Pro-X Mill	E390
PAXS6000	Pro-X Mill	E391
PBAC(M)5000	Power Buster	E68
PBPCM6000	Power Buster	E70
PBZC(M)5000	Power Buster	E69
PCBNR/L	Holder (SAVE TURN)	B116
PCBNR/L	Holder (Lever Lock System)	B172
PCKNR/L	Holder (Lever Lock System)	B172
PCLNR	Holder (KHP)	B202
PCLNR/L	Holder (SAVE TURN)	B116
PCLNR/L	Boring Bar (SAVE TURN)	B119
PCLNR/L	Holder (Lever Lock System)	B173
PCLNR/L	Boring Bar (Lever Lock System)	B210
PCLNR/L	HSK Tooling System	B232
PCLNR/L	KM Tooling System	B238
PCMNN	HSK Tooling System	B232
PCMNN	KM Tooling System	B238
PDF	PCD Face Cutter	E156
PDJNR	Holder (KHP)	B202
PDJNR/L	Holder (SAVE TURN)	B116
PDJNR/L	Holder (Lever Lock System)	B173
PDJNR/L	HSK Tooling System	B232
PDJNR/L	KM Tooling System	B239
PDNNN	HSK Tooling System	B232
PDNNN	KM Tooling System	B239
PDNNR/L	Holder (SAVE TURN)	B117
PDNNR/L	Holder (Lever Lock System)	B174
PDQNR/L	Holder (SAVE TURN)	B117
PDSNR/L	Boring Bar (Lever Lock System)	B210
PDUNR/L	Boring Bar (SAVE TURN)	B119
PDUNR/L	Boring Bar (Lever Lock System)	B210
PDZNR/L	Boring Bar (SAVE TURN)	B120





P		
PES2000	Turbo Mill	E61
PES3000	Turbo Mill	E61
PES4000	Turbo Mill	E61
PF(M)4000	Mill-max	E55
PNEJ	Milling Insert (Side Cutter)	E16
PNEJ-C	Milling Insert (Side Cutter)	E16
PPN(M)4000	Mill-max	E56
PRDCN	Holder (Lever Lock System)	B174
PRDCN	HSK Tooling System	B233
PRGCR/L	Holder (Lever Lock System)	B175
PRGCR/L	HSK Tooling System	B233
PSBNR/L	Holder (SAVE TURN)	B117
PSBNR/L	Holder (Lever Lock System)	B175
PSDNN	Holder (SAVE TURN)	B118
PSDNN	Holder (Lever Lock System)	B176
PSKNR/L	Holder (SAVE TURN)	B118
PSKNR/L	Boring Bar (SAVE TURN)	B120
PSKNR/L	Holder (Lever Lock System)	B176
PSKNR/L	Boring Bar (Lever Lock System)	B211
PSSNR	Holder (KHP)	B202
PSSNR/L	Holder (SAVE TURN)	B118
PSSNR/L	Holder (Lever Lock System)	B177
PT	Tap Series (Point Tap)	D80
PTFNR/L	Holder (Lever Lock System)	B177
PTFNR/L	Boring Bar (Lever Lock System)	B211
PTGNR/L	Holder (Lever Lock System)	B178
PTTNR/L	Holder (Lever Lock System)	B178
PWLNR	Holder (KHP)	B203
PWLNR/L	Holder (SAVE TURN)	B119
PWLNR/L	Boring Bar (SAVE TURN)	B120
PWLNR/L	Holder (Lever Lock System)	B178
PWLNR/L	Boring Bar (Lever Lock System)	B211
PXL(S)	Pro-XL Mill	E398
Q		
QCGT	Multi functional Insert (Multi Turn)	B154
QCMT	Multi functional Insert (Multi Turn)	B154
R		
RAFCB	Side Milling Cutter (Radial type-Full side cutter)	E409
RAFCP	Side Milling Cutter (Radial type-Full side cutter)	E409
RAHCB	Side Milling Cutter (Radial type-Half side cutter)	E410
RAHCP	Side Milling Cutter (Radial type-Half side cutter)	E410

R		
RC	Milling Insert (BFE)	E16
RCGT-AK	Aluminum Insert_Positive (Screw on System)	B105
RCGT-AR	Aluminum Insert_Positive (Screw on System)	B105
RCMT-VM	Turning Insert_Positive (Screw on System)	B83
RCMX	Turning Insert_Positive (Screw on System)	B83
RDCT-MA	Milling Insert (Future Mill)	E16
RDHW	Milling Insert (Future Mill)	E16
RDKT-MF	Milling Insert (Future Mill)	E17
RDKT-ML	Milling Insert (Future Mill)	E17
RDKT-MM	Milling Insert (Future Mill)	E17
RDKW	Milling Insert (Future Mill)	E17
REKR-MM	Milling Insert (Double Mill)	E17
RI	Drill (Indexable Reamer Insert)	F85
RK Chip Breaker	Turning Chip Breaker	B25
RM Chip Breaker	Turning Chip Breaker	B23
RM14XCM-XN06	Rich Mill	E142
RM16AC(M)6000	Rich Mill	E143
RM16AC(M)8000	Rich Mill	E144
RM3PC(M)3000	Rich Mill	E99
RM3PC(M)4000	Rich Mill	E100
RM3PC(M)5000	Rich Mill	E101
RM3PM3000	Rich Mill	E104
RM3PM4000	Rich Mill	E104
RM3PS3000	Rich Mill	E102
RM3PS4000	Rich Mill	E103
RM4PC(M)3000	Rich Mill	E105
RM4PC(M)4000	Rich Mill	E106
RM4PFCB3000	Rich Mill	E107
RM4PFCB4000	Rich Mill	E108
RM4PFCP3000	Rich Mill	E111
RM4PFCP4000	Rich Mill	E112
RM4PHCB3000	Rich Mill	E109
RM4PHCB4000	Rich Mill	E110
RM4PHCP3000	Rich Mill	E113
RM4PHCP4000	Rich Mill	E114
RM4PM3000	Rich Mill	E117
RM4PS3000	Rich Mill	E115
RM4PS4000	Rich Mill	E116
RM4ZC(M)3000	Rich Mill	E118
RM4ZC(M)4000	Rich Mill	E118
RM4ZM3000	Rich Mill	E119
RM4ZS3000	Rich Mill	E119
RM6PC(M)-WN08	Rich Mill	E121
RM6PCM-WN04	Rich Mill	E120
RM6PM-WN04	Rich Mill	E124





RM6PM-WN08	Rich Mill	E125
RM6PS-WN04	Rich Mill	E122
RM6PS-WN08	Rich Mill	E123
RM8AC(M)4000	Rich Mill	E126
RM8AC(M)5000	Rich Mill	E128
RM8EC(M)4000	Rich Mill	E130
RM8EC(M)5000	Rich Mill	E132
RM8QC(M)4000	Rich Mill	E134
RMH8AC(M)4000	Rich Mill	E127
RMH8AC(M)5000	Rich Mill	E129
RMH8EC(M)4000	Rich Mill	E131
RMH8EC(M)5000	Rich Mill	E133
RMH8QC(M)4000	Rich Mill	E135
RMRC(M)-RN12	Rich Mill	E145
RMRS-RN12	Rich Mill	E146
RMT8A(M)4000	Rich Mill	E136
RMT8A(M)5000	Rich Mill	E137
RMT8E(M)4000	Rich Mill	E138
RMT8E(M)5000	Rich Mill	E139
RMT8Q(M)4000	Rich Mill	E140
RMX8AC(M)-SA14	Rich Mill	E141
RNMG-B25	Turning Insert_Negative	B49
RNMX-ML	Milling Insert (Rich Mill)	E17
RPCT-MA	Milling Insert (Future Mill P-Positive)	E17
RPET-ML	Milling Insert (Future Mill P-Positive)	E18
RPGT	Multi functional Insert (Bearing Solution)	B158
RPMT-MF	Milling Insert (Future Mill P-Positive)	E18
RPMT-MM	Milling Insert (Future Mill P-Positive)	E18
RPMW	Milling Insert (Future Mill P-Positive)	E18
RT	Tap Series (Roll Tap)	D77, 82



SAGX-ML	Milling Insert (Rich Mill)	E18
SAGX-MM	Milling Insert (Rich Mill)	E18
SBBR/L	Auto Tools Insert (Blade type)	B137
SBCR/L	Auto Tools Insert (Blade type)	B138
SBGR/L	Auto Tools Insert (Blade type)	B137
SBHR/L	Holder (Auto Tools_Blade type)	B137
SBHR/L-X	Holder (Auto Tools_Blade type)	B137
SBR/L	Auto Tools Insert (Multi utility type)	B140
SBTR/L	Auto Tools Insert (Blade type)	B137
SCACR/L	Holder (Auto Tools_ISO type)	B123
SCACR/L	Holder (Screw on System)	B190
SCGT-AK	Aluminum Insert_Positive (Screw on System)	B106



SCGT-AR	Aluminum Insert_Positive (Screw on System)	B106
SCKN	Milling Insert (Mill Max Heavy)	E19
SCLCR/L	Holder (Auto Tools_ISO type)	B123
SCLCR/L	Holder (Auto Tools_KHP)	B129
SCLCR/L	Holder (Screw on System)	B190
SCLCR/L	Boring Bar (Screw on System)	B215
SCLCR/L	Compact Mini	B225
SCLPR/L	Boring Bar (Screw on System)	B216
SCMT-C25	Turning Insert_Positive (Screw on System)	B84
SCMT-FP	Turning Insert_Positive (Screw on System)	B84
SCMT-HMP	Turning Insert_Positive (Screw on System)	B84
SCMT-MP	Turning Insert_Positive (Screw on System)	B84
SCMT-VF	Turning Insert_Positive (Screw on System)	B84
SCMT-VL	Turning Insert_Positive (Screw on System)	B84
SCR/L	Auto Tools Insert (Multi utility type)	B140
SDACR/L	Holder (Screw on System)	B190
SDCN	Milling Insert (Mill-max, High feed Cutter)	E19
SDET-MA	Milling Insert (Future Mill)	E19
SDET-MF	Milling Insert (Future Mill)	E19
SDET-MM	Milling Insert (Future Mill)	E19
SDJCR/L	Holder (Auto Tools-ISO Type)	B123
SDJCR/L	Holder (Auto Tools-KHP)	B129
SDJCR/L	Holder (Screw on System)	B191
SDKN-CM	Milling Insert	E19
SDKN-MU	Milling Insert (Mill-Max)	E20
SDKN-SU	Milling Insert (Mill-max, Turbo Mill)	E20
SDKR-MX	Milling Insert (Mill-max, Turbo Mill)	E20
SDMT-MM	Milling Insert (Tank Mill, GBE)	E20
SDNCN	Holder (Auto Tools-ISO Type)	B124
SDNCN	Holder (Screw on System)	B191
SDQCR/L	Boring Bar (Screw on System)	B217
SDUCR/L	Boring Bar (Screw on System)	B218
SDXT-MA	Milling Insert (Future Mill)	E20
SDXT-MF	Milling Insert (Future Mill)	E20
SDXT-MM	Milling Insert (Future Mill)	E20
SDZCR/L	Boring Bar (Screw on System)	B219
SECA	Milling Insert	E20
SECN	Milling Insert (Mill-max)	E21
SEET-MA	Milling Insert (Future Mill)	E21
SEET-MF	Milling Insert (Future Mill)	E21
SEET-MM	Milling Insert (Future Mill)	E21
SEEW	Milling Insert (Future Mill)	E21
SEEW-W	Milling Insert (Future Mill)	E21
SEKN-SU	Milling Insert (Mill-max)	E21
SEKR-MX	Milling Insert (Mill-max)	E22







SEMN	Milling Insert	E22
SEXT-MF	Milling Insert (Future Mill)	E22
SEXT-MM	Milling Insert (Future Mill)	E22
SEXT-MR	Milling Insert (Future Mill)	E22
SFCN	Milling Insert (Mill-max)	E22
SGBR/L	Auto Tools Insert (Multi utility type)	B141
SGR/L	Auto Tools Insert (Multi utility type)	B141
SH Chip Breaker	Turning Chip Breaker	B33
SL	Sleeve	B151
SMBB	Multi functional(Saw Man_Block)	C61
SMBB	Multi functional(Saw Man-X_Block)	C65
SNCF-MF	Milling Insert (Rich Mill)	E22
SNCF-MM	Milling Insert (Rich Mill)	E23
SNCN	Milling Insert (Mill-max)	E23
SNEF	Milling Insert (High feed Cutter)	E23
SNEU-MF	Milling Insert (Shave Mill)	E23
SNEU-TBW	Milling Insert (Shave Mill)	E24
SNEU-WMF	Milling Insert (Shave Mill)	E24
SNEW	Milling Insert (Aero Mill-Mini)	E24
SNEW-NAF	Milling Insert (Aero Mill-Mini)	E24
SNEW-XAF	Milling Insert (Aero Mill-Mini)	E24
SNEX	Milling Insert (Cube Mill)	E24
SNEX-CU1	Milling Insert (Cube Mill)	E24
SNEX-MA	Milling Insert (Rich Mill)	E24
SNEX-MF	Milling Insert (Rich Mill)	E25
SNEX-ML	Milling Insert (Rich Mill)	E24
SNEX-MM	Milling Insert (Rich Mill)	E25
SNEX-W	Milling Insert (Rich Mill)	E26
SNGA	Turning Insert_Negative (Multi Lock/Lever Lock System)	B54
SNGG	Turning Insert_Negative (Multi Lock/Lever Lock System)	B53
SNGG-VP3	Turning Insert_Negative (Multi Lock/Lever Lock System)	B55
SNGN	Turning Insert_Negative (Lever Lock System/Ceramic Holder)	B56
SNGX	Turning Insert_Negative (Multi Lock/Lever Lock System)	B57
SNHT-WX	Milling Insert (Wind Mill)	E25
SNKN	Milling Insert (Mill-max)	E25
SNMA	Turning Insert_Negative (Multi Lock/Lever Lock System)	B53
SNMF-MF	Milling Insert (Rich Mill)	E22
SNMF-MM	Milling Insert (Rich Mill)	E23
SNMG-B25	Turning Insert_Negative (Multi Lock/Lever Lock System)	B52
SNMG-CP	Turning Insert_Negative (Multi Lock/Lever Lock System)	B50
SNMG-GR	Turning Insert_Negative (Multi Lock/Lever Lock System)	B52
SNMG-HA	Turning Insert_Negative (Multi Lock/Lever Lock System)	B56
SNMG-HM	Turning Insert_Negative	B51
SNMG-LP	Turning Insert_Negative (Multi Lock/Lever Lock System)	B50
SNMG-MK	Turning Insert_Negative (Multi Lock/Lever Lock System)	B53



SNMG-MM	Turning Insert (SAVE TURN)	B115
SNMG-MM	Turning Insert_Negative (Multi Lock/Lever Lock System)	B54
SNMG-MP	Turning Insert (SAVE TURN)	B115
SNMG-MP	Turning Insert_Negative (Multi Lock/Lever Lock System)	B51
SNMG-RK	Turning Insert_Negative (Multi Lock/Lever Lock System)	B54
SNMG-RM	Turning Insert_Negative (Multi Lock/Lever Lock System)	B55
SNMG-VB	Turning Insert_Negative (Multi Lock/Lever Lock System)	B50
SNMG-VC	Turning Insert_Negative (Multi Lock/Lever Lock System)	B50
SNMG-VF	Turning Insert_Negative (Multi Lock/Lever Lock System)	B50
SNMG-VL	Turning Insert_Negative (Multi Lock/Lever Lock System)	B50
SNMG-VM	Turning Insert_Negative (Multi Lock/Lever Lock System)	B51
SNMG-VP2	Turning Insert_Negative (Multi Lock/Lever Lock System)	B55
SNMG-VP3	Turning Insert_Negative (Multi Lock/Lever Lock System)	B55
SNMG-VP4	Turning Insert_Negative (Multi Lock/Lever Lock System)	B55
SNMG-VQ	Turning Insert (SAVE TURN)	B115
SNMG-VQ	Turning Insert_Negative (Multi Lock/Lever Lock System)	B52
SNMG-VR	Turning Insert_Negative (Multi Lock/Lever Lock System)	B54
SNMM-GH	Turning Insert_Negative (Multi Lock/Lever Lock System)	B57
SNMM-GR	Turning Insert_Negative (Multi Lock/Lever Lock System)	B57
SNMM-VH	Turning Insert_Negative (Lever Lock System)	B57
SNMM-VT	Turning Insert_Negative (Lever Lock System)	B57
SNMX	Turning Insert_Negative (Ceramic Holder)	B56
SNMX-MF	Milling Insert (Rich Mill)	E25
SNMX-MM	Milling Insert (Alpha Mill)	E18
SNMX-MM	Milling Insert (Rich Mill)	E25
SNUN	Turning Insert_Negative (Ceramic Holder)	B56
SP	Multi functional Insert (Saw Man)	C60
SP	Tap series (Spiral Tap)	D76, 81
SPB	Multi functional (Saw Man_Blades)	C61
SPB(M)	Side Cutter	E412
SPB-S	Multi functional (Saw Man_Blades)	C61
SPCN	Milling Insert (Mill-max)	E26
SPEN-WC	Milling Insert (High feed Cutter)	E26
SPET-ND	Drill Insert (KING DRILL)	F03
SPEX	Milling Insert (Mill-max)	E26
SPFN	Milling Insert (Side Cutter)	E26
SPGA	Turning Insert_Positive	B86
SPGH	Multi functional Insert (Bearing Solution)	B158
SPGN	PCD Insert_Positive	B113
SPGN	Turning Insert_Positive	B86
SPGR	Multi functional Insert (Bearing Solution)	B158
SPGR-F	Turning Insert_Positive (Clamp on System)	B85
SPGR-M	Turning Insert_Positive (Clamp on System)	B85
SPGT	Turning Insert_Positive (Screw on System)	B86
SPH	Multi functional (Saw Man_Holder)	C62





SPH-S	Multi functional (Saw Man_Holder)	C62
SPKN-MU	Milling Insert (Mill-max)	E27
SPKN-SU	Milling Insert (Mill-max)	E27
SPKR-MX	Milling Insert (Mill-max)	E27
SPMN	Milling Insert (Chamfer tools)	E27
SPMR-F	Turning Insert_Positive (Clamp on System)	B85
SPMR-M	Turning Insert_Positive (Clamp on System)	B85
SPMT	Milling Insert (Tank Mill, GBE, BT Tooling System)	E27
SPMT-KC	Milling Insert (Chamfer tools)	E27
SPMT-LD	Drill Insert (KING DRILL)	F03
SPMT-MM	Milling Insert (Tank Mill, GBE)	E27
SPMT-PD	Drill Insert (KING DRILL)	F03
SPMT-VF	Turning Insert_Positive (Clamp on System)	B85
SPMT-VL	Turning Insert_Positive	B85
SPP(M)	Side Cutter	E411
SPS	Side Cutter	E413
SPUN	Turning Insert_Positive	B85
SR	Tap series (Spiral Roll Tap)	D78, 83
SR Chip Breaker	Turning Chip Breaker	B33
SRCPR/LB	Bearing Solution	B157
SRDCN	Holder (Screw on System)	B191
SRGCR	Holder (KHP)	B203
SRGCR/L	Holder (Screw on System)	B192
SRGPR/LE	Bearing Solution	B157
SRGPR/LF	Bearing Solution	B157
SSBCR/L	Holder (Screw on System)	B192
SSDCN	Holder (Screw on System)	B192
SSKCR/L	Holder (Screw on System)	B193
SSKCR/L	Boring Bar (Screw on System)	B219
SSKCR/L	Cartridge (Screw on System)	B245
SSKPR/L	Boring Bar (Screw on System)	B219
SSKPR/LB	Bearing Solution	B158
SSSCR/L	Holder (Screw on System)	B193
SSSCR/L	Cartridge (Screw on System)	B246
ST	Tap series (Straight Tap)	D75, 79
STACR/L	Holder (Auto Tools-ISO Type)	B124
STACR/L	Holder (Screw on System)	B193
STFCR/L	Holder (Screw on System)	B194
STFCR/L	Boring Bar (Screw on System)	B220
STFCR/L	Cartridge (Screw on System)	B246
STFPR/L	Boring Bar (Screw on System)	B221
STGCR/L	Holder (Screw on System)	B194
STLBR/L	Compact Mini	B225
STMD1T	Solid Threading Endmills (ISO Metric)	D64, 68
STMD2L	Solid Threading Endmills (ISO Metric / UN)	D69~70
l	- ,	



STMD3T	Solid Threading Endmills (ISO Metric / UN)	D65~67
STMH	Solid Threading Endmills (ISO Metric)	D57~60
STMHC	Solid Threading Endmills (ISO Metric)	D51~56
STMS	Solid Threading Endmills (ISO Metric)	D61~63
STR/L	Auto Tools Insert (Multi utility type)	B141
STTCR/L	Holder (Screw on System)	B194
STTCR/L	Cartridge (Screw on System)	B247
STUBR/L	Compact Mini	B225
STUPR/L	Compact Mini	B226
STWCR/L	Cartridge (Screw on System)	B247
STWPR/L	Boring Bar (Screw on System)	B222
SVABR/L	Holder (Screw on System)	B195
SVACR/L	Holder (Auto Tools-ISO Type)	B124
SVAPR/L	Holder (Auto Tools-ISO Type)	B125
SVHBR/L	Holder (Screw on System)	B195
SVJBR	Holder (KHP)	B203
SVJBR/L	Holder (Auto Tools-ISO Type)	B125
SVJBR/L	Holder (Screw on System)	B195
SVJCR/L	Holder (Auto Tools-ISO Type)	B125
SVJCR/L	Holder (Auto Tools-KHP)	B129
SVJCR/L	Holder (Screw on System)	B196
SVJCR/L	Boring Bar (Screw on System)	B222
SVJPR/L	Holder (Auto Tools-ISO Type)	B126
SVPBR/L	HSK Tooling System	B233
SVQBR/L	Boring Bar (Screw on System)	B222
SVQCR/L	Boring Bar (Screw on System)	B223
SVUBR/L	Boring Bar (Screw on System)	B223
SVUCR/L	Boring Bar (Screw on System)	B223
SVVBN	Holder (Screw on System)	B196
SVVBN	HSK Tooling System	B233
SVVCN	Holder (Screw on System)	B196
SVVPN	Holder (Auto Tools-ISO Type)	B126
SWLCR/L	Boring Bar (Screw on System)	B224
SWUBR/L	Compact Mini	B227
SXGNR/L	Holder (Auto Tools_Multi utility type)	B140



TAFCB	Side Milling Cutter (Tangential type-Full side cutter)	E407
TAFCP	Side Milling Cutter (Tangential type-Full side cutter)	E407
ТАНСВ	Side Milling Cutter (Tangential type-Half side cutter)	E408
ТАНСР	Side Milling Cutter (Tangential type-Half side cutter)	E408
ТВ	Multi functional Insert (Grooving Tools)	C51
твст	Turning Insert_Positive (Compact Mini)	B87
ТВН	Multi functional (Grooving Tools)	C54



INDEX



U		
ТВ-М	Multi functional Insert (Grooving Tools)	C52
TBMT-VL	Turning Insert_Positive (Screw on System)	B87
ТВ-Р	Multi functional Insert (Grooving Tools)	C53
TCGT-AK	Aluminum Insert_Positive (Screw on System)	B107
TCGT-AR	Aluminum Insert_Positive (Screw on System)	B107
TCGT-FS	Auto tools Insert (ISO type)	B133
TOGT EQ	Turning Inport Popitive (Serow on System)	Doo

TB-M	Multi functional Insert (Grooving Tools)	C52
TBMT-VL	Turning Insert_Positive (Screw on System)	B87
ТВ-Р	Multi functional Insert (Grooving Tools)	C53
TCGT-AK	Aluminum Insert_Positive (Screw on System)	B107
TCGT-AR	Aluminum Insert_Positive (Screw on System)	B107
TCGT-FS	Auto tools Insert (ISO type)	B133
TCGT-FS	Turning Insert_Positive (Screw on System)	B89
TCGT-KF	Auto tools Insert (ISO type)	B133
TCGT-KF	Turning Insert_Positive (Screw on System)	B89
TCGT-VP1	Turning Insert_Positive (Screw on System)	B89
TCMT-C25	Turning Insert_Positive (Screw on System)	B89
TCMT-FP	Turning Insert_Positive (Screw on System)	B88
ТСМТ-НМР	Turning Insert_Positive (Screw on System)	B88
TCMT-MP	Turning Insert_Positive (Screw on System)	B88
TCMT-VF	Turning Insert_Positive (Screw on System)	B88
TCMT-VL	Turning Insert_Positive (Screw on System)	B88
TCMT-VP1	Turning Insert_Positive (Screw on System)	B89
T-CNMA	cBN Insert_Negative(Regrinding)	B112
T-DCGW	cBN Insert_Positive(Regrinding)	B112
TEC(E)N	Milling Insert (Turbo Mill)	E27
TEEN	Milling Insert (Turbo Mill)	E27
TFCN	Milling Insert (Mill-max)	E28
TFE	T-Cutter	E374
THE	Tank Mill	E307
тм	Thread Milling Inserts (ISO Metric)	D44~49
TNGA	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B62
TNGG	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B61
TNGG-SC	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B60
TNGG-VP3	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B63
TNGN	Turning Insert_Negative (Ceramic Holder)	B64
TNKT-ML	Milling Insert (Triple Mill)	E28
TNKT-MM	Milling Insert (Triple Mill)	E28
TNMA	cBN Insert_Negative(Regrinding)	B112
TNMA	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B61
TNMG-B25	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B60
TNMG-CP	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B58
TNMG-GR	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B60
TNMG-HA	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B63
TNMG-HM	Turning Insert_Negative	B59
TNMG-LP	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B58
TNMG-LW	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B64
TNMG-MK	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B61
TNMG-MM	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B62
TNMG-MP	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B59
TNMG-RK	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B62
	· · · · · · · · · · · · · · · · · ·	

TNMG-RM	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B63
TNMG-VB	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B58
TNMG-VC	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B59
TNMG-VF	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B58
TNMG-VL	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B58
TNMG-VM	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B59
TNMG-VP2	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B63
TNMG-VP3	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B63
TNMG-VP4	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B63
TNMG-VQ	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B60
TNMG-VR	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B62
TNMG-VW	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B64
TNMM-GH	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B65
TNMM-GR	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B65
TNMX	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B65
TNMX-NM	Milling Insert (Power Buster)	E28
TNMX-SH	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B64
TNMX-SR	Turning Insert_Negative	B64
ТОЕН	Turning Insert_Positive	B90
TP2PCM-LN08	TP2P	E311
TP2PCM-LN14	TP2P	E312
TP2PCM-LN17	TP2P	E313
TP2PS-LN08	TP2P	E314
TP2PS-LN14	TP2P	E315
TP2PS-LN17	TP2P	E316
TPCN	Milling Insert (Mill-max, Side cutter)	E28
TPD	Drill Insert (TPDC Plus Drill)	F47~49
TPD	Drill Insert (TPDB Plus Drill)	F57
TPD	Drill Insert (TPDB-F)	F66
TPD	Drill Insert (TPDB-H)	F71
TPDB-F(1.5D)	Drill (TPDB-F)	F67
TPDB-H(3D)	Drill (TPDB-H)	F72
TPDB-H(4D)	Drill (TPDB-H)	F73
TPDB-H(8D)	Drill (TPDB-H)	F74
TPDB-P(10D)	Drill (TPDB Plus)	F61
TPDB-P(12D)	Drill (TPDB Plus)	F62

TPDB-P(3D)

TPDB-P(5D)

TPDB-P(8D)

TPDC(1.5D)

TPDC(10D)

TPDC(12D)

TPDC(3D)

TPDC(5D)

TPDC(8D)

Drill (TPDB Plus)

Drill (TPDB Plus)

Drill (TPDB Plus)

Drill (TPDC Plus)

Drill (TPDC Plus)

Drill (TPDC Plus)

Drill (TPDC Plus)

Drill (TPDC Plus)

Drill (TPDC Plus)



F58

F59

F60

F51

F53

F53

F51

F52

F52



TPDX(3D)	Drill (TPDC Plus)	F50
TPDX(5D)	Drill (TPDC Plus)	F50
TPDX(8D)	Drill (TPDC Plus)	F50
TPGB	cBN Insert_Positive (Regrinding)	B112
TPGH	Turning Insert_Positive	B93
TPGN	PCD Insert_Positive	B113
TPGN	Turning Insert_Positive	B92
TPGR-F	Turning Insert_Positive (Clamp on System)	B91
TPGR-M	Turning Insert_Positive (Clamp on System)	B92
TPGT	Turning Insert_Positive (Screw on System)	B93
TPGW	PCD Insert_Positive	B113
TPGX	Turning Insert_Positive (Screw on System)	B93
TPKN-MU	Milling Insert (Mill-max)	E29
TPKN-SU	Milling Insert (Mill-max)	E29
TPKR-MX	Milling Insert (Mill-max)	E29
TPMCM-TN16	Triple Mill	E258
TPMCM-TN20	Triple Mill	E259
TPMR-F	Turning Insert_Positive (Clamp on System)	B91
TPMR-M	Turning Insert_Positive (Clamp on System)	B91
TPMS-TN11	Triple Mill	E260
TPMS-TN16	Triple Mill	E261
TPMT-FP	Turning Insert_Positive (Screw on System)	B90
TPMT-MP	Turning Insert_Positive (Screw on System)	B91
TPMT-VF	Turning Insert_Positive (Screw on System)	B91
TPMT-VL	Turning Insert_Positive (Screw on System)	B91
TPUN	Turning Insert_Positive	B92
T-TPGB	cBN Insert_Negative (Regrinding)	B112
T-VNMA	cBN Insert_Negative (Regrinding)	B112
TWX-KC	Milling Insert (Multi functional Chamfer Tool)	E29



D26 UNJ (Unified Constant Thread) Thread Insert



VB Chip Breaker	Turning Chip Breaker	B29
VBGT	Aluminum Insert_Positive (Screw on System)	B95
VBGT-AK	Aluminum Insert_Positive (Screw on System)	B108
VBGT-AR	Turning Insert_Positive (Screw on System)	B108
VBGT-FS	Auto tools Insert (ISO type)	B133
VBGT-FS	Turning Insert_Positive (Screw on System)	B95
VBGT-KF	Auto tools Insert (ISO type)	B133
VBGT-KF	Turning Insert_Positive (Screw on System)	B96
VBGT-KM	Auto tools Insert (ISO type)	B133



VBGT-KM	Turning Insert_Positive (Screw on System)	B96
VBGT-VP1	Turning Insert_Positive (Screw on System)	B95
VBGW	PCD Insert_Positive	B113
VBMT	PCD Insert_Positive	B113
VBMT	Turning Insert_Positive (Screw on System)	B95
VBMT-FP	Turning Insert_Positive (Screw on System)	B94
VBMT-HMP	Turning Insert_Positive (Screw on System)	B94
VBMT-MP	Turning Insert_Positive (Screw on System)	B94
VBMT-VB	Turning Insert_Positive (Screw on System)	B94
VBMT-VF	Turning Insert_Positive (Screw on System)	B94
VBMT-VL	Turning Insert_Positive (Screw on System)	B94
VBMT-VP1	Turning Insert_Positive (Screw on System)	B95
VBMW	cBN Insert_Positive (Regrinding)	B112
VC Chip Breaker	Turning Chip Breaker	B30
VCET-KF	Auto Tools Insert (ISO type)	B134
VCET-KF	Turning Insert_Positive (Screw on System)	B99
VCET-KM	Auto Tools Insert (ISO type)	B134
VCET-KM	Turning Insert_Positive (Screw on System)	B99
VCGT-AK	Aluminum Insert_Positive (Screw on System)	B109
VCGT-AR	Aluminum Insert_Positive (Screw on System)	B109
VCGT-FS	Auto Tools Insert (ISO type)	B134
VCGT-FS	Turning Insert_Positive (Screw on System)	B98
VCGT-KF	Auto Tools Insert (ISO type)	B133
VCGT-KF	Turning Insert_Positive (Screw on System)	B99
VCGT-KM	Auto Tools Insert (ISO type)	B134
VCGT-KM	Turning Insert_Positive (Screw on System)	B99
VCGT-MS	Auto Tools Insert (ISO type)	B134
VCGT-MS	Turning Insert_Positive (Screw on System)	B98
VCGT-VP1	Auto Tools Insert (ISO type)	B134
VCGT-VP1	Turning Insert_Positive (Screw on System)	B98
VCGX-VP1	Auto Tools Insert (ISO type)	B134
VCGX-VP1	Turning Insert_Positive (Screw on System)	B99
VCKT-MA	Milling Insert (Pro-A Mill)	E29
VCMT	PCD Insert_Positive	B113
VCMT-FP	Turning Insert_Positive (Screw on System)	B97
VCMT-HMP	Turning Insert_Positive (Screw on System)	B97
VCMT-MP	Turning Insert_Positive (Screw on System)	B97
VCMT-VF	Turning Insert_Positive (Screw on System)	B97
VCMT-VL	Turning Insert_Positive (Screw on System)	B97
VCMT-VP1	Turning Insert_Positive (Screw on System)	B97
VDKT-MA	Milling Insert (Pro-A Mill)	E29
VETR	Thread Insert (Vertical Type)	D33
VH Chip Breaker	Turning Chip Breaker	B31
VL Chip Breaker	Turning Chip Breaker	B29
VNGG-HA	Turning Insert_Negative (Multi Lock System)	B67







VNGG-VP3	Turning Insert_Negative (Multi Lock System)	B67
VNMA	cBN Insert_Negative (Regrinding)	B112
VNMG-CP	Turning Insert_Negative (Multi Lock System)	B66
VNMG-HM	Turning Insert_Negative	B66
VNMG-LP	Turning Insert_Negative (Multi Lock System)	B66
VNMG-MK	Turning Insert_Negative (Multi Lock System)	B67
VNMG-MM	Turning Insert_Negative (Multi Lock System)	B67
VNMG-MP	Turning Insert_Negative (Multi Lock System)	B66
VNMG-RM	Turning Insert_Negative (Multi Lock System)	B67
VNMG-VB	Turning Insert_Negative (Multi Lock System)	B66
VNMG-VC	Turning Insert_Negative (Multi Lock System)	B66
VNMG-VF	Turning Insert_Negative (Multi Lock System)	B66
VNMG-VL	Turning Insert_Negative (Multi Lock System)	B66
VNMG-VM	Turning Insert_Negative (Multi Lock System)	B67
VNMG-VP3	Turning Insert_Negative (Multi Lock System)	B67
VNMG-VQ	Turning Insert_Negative (Multi Lock System)	B67
VP1 Chip Breaker	Turning Chip Breaker	B26
VP2 Chip Breaker	Turning Chip Breaker	B26
VP3 Chip Breaker	Turning Chip Breaker	B27
VP4 Chip Breaker	Turning Chip Breaker	B27
VPET-KF	Turning Insert_Positive (Screw on System)	B100
VPET-KF	Auto Tools Insert (ISO type)	B135
VPET-KM	Turning Insert_Positive (Screw on System)	B100
VPET-KM	Auto Tools Insert (ISO type)	B135
VPGT-KF	Auto Tools Insert (ISO type)	B135
VPGT-KM	Auto Tools Insert (ISO type)	B135
VPGT-VP1	Turning Insert_Positive (Screw on System)	B100
VPGT-VP1	Auto Tools Insert (ISO type)	B135
VQ Chip Breaker	Turning Chip Breaker	B30
VT Chip Breaker	Turning Chip Breaker	B31
VTH	Vertical Type Holder	D33
VW Chip Breaker	Turning Chip Breaker	B32



WBGT	Turning Insert_Positive (Compact Mini)	B101
WCMT-C20N	Drill Insert (WPDC)	F04
WCMT-C21N	Drill Insert (WPDC)	F04
WDKT-MH	Milling Insert (HRM)	E29
WFSB(M)	Wind Mill (Boss type)	E416
WFSP(M)	Wind Mill (Plane type)	E417
WNGG-VP3	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B71
WNGX-MA	Milling Insert (Rich Mill)	E30
WNGX-ML	Milling Insert (Rich Mill)	E30
WNGX-MM	Milling Insert (Rich Mill)	E30



WNMA	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B70
WNMG-B25	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B69
WNMG-CP	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B68
WNMG-GR	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B69
WNMG-HA	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B72
WNMG-HM	Turning Insert_Negative	B69
WNMG-LP	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B68
WNMG-LW	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B72
WNMG-MK	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B70
WNMG-MM	Turning Insert (SAVE TURN)	B115
WNMG-MM	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B71
WNMG-MP	Turning Insert (SAVE TURN)	B115
WNMG-MP	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B69
WNMG-RK	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B70
WNMG-RM	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B71
WNMG-VB	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B68
WNMG-VC	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B68
WNMG-VF	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B68
WNMG-VL	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B68
WNMG-VM	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B69
WNMG-VP2	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B71
WNMG-VP3	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B71
WNMG-VP4	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B71
WNMG-VQ	Turning Insert (SAVE TURN)	B115
WNMG-VQ	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B70
WAIMC VD	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B70
WNMG-VR		
WNMG-VW	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B72
	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B72 B72
WNMG-VW		
WNMG-VW WNMM-B25	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B72
WNMG-VW WNMM-B25 WNMX-MF	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System)  Milling Insert (HRMDouble)	B72 E30
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML	Turning Insert_Negative (LeverLockWedge Clamp/Multi Lock System)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)	B72 E30 E30
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-MM	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)	B72 E30 E30 E30
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-MM WNMX-SH	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)  Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)	B72 E30 E30 E30 B72
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-MM WNMX-SH WNMX-SR	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)  Milling Insert (HRMDouble)  Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System)  Turning Insert_Negative	B72 E30 E30 E30 B72 B72
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-MM WNMX-SH WNMX-SR WPDC-5D	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type)	B72 E30 E30 E30 B72 B72 F79
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type)	B72 E30 E30 E30 B72 B72 F79
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-MM WNMX-SH WNMX-SR WPDC-5D WPDC-5D	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Single insert catridge type )	B72 E30 E30 E30 B72 B72 F79 F81
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D WPDC-5D WPDC-5D	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Single insert catridge type ) Drill (WPDC Standard type)	B72 E30 E30 E30 B72 B72 F79 F81 F80 F79
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D WPDC-5D WPDC-5D	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type)	B72 E30 E30 E30 B72 B72 F79 F81 F80 F79 F81
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D WPDC-5D WPDC-5D WPDC-6.5D WPDC-6.5D WPDC-6.5D	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Single insert cartridge type)	B72 E30 E30 E30 B72 B72 F79 F81 F80 F79 F81 F80
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D WPDC-5D WPDC-5D WPDC-6.5D WPDC-6.5D WPDC-6.5D WPDC-6.5D	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Single insert cartridge type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Single insert cartridge type) Drill (WPDC Standard type)	B72 E30 E30 B72 B72 F79 F81 F80 F79 F81 F80 F79
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D WPDC-5D WPDC-5D WPDC-6.5D WPDC-6.5D WPDC-6.5D WPDC-6.5D WPDC-6.5D	Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (Lever Lock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type)	B72 E30 E30 B72 B72 F79 F81 F80 F79 F81 F80 F79 F81
WNMG-VW WNMM-B25 WNMX-MF WNMX-ML WNMX-SH WNMX-SR WPDC-5D WPDC-5D WPDC-5D WPDC-6.5D WPDC-6.5D WPDC-6.5D WPDC-6.5D WPDC-8D WPDC-8D	Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Milling Insert (HRMDouble) Turning Insert_Negative (LeverLock/Wedge Clamp/Multi Lock System) Turning Insert_Negative Drill (WPDC Standard type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Single insert catridge type) Drill (WPDC Dual insert cartridge type) Drill (WPDC Single insert cartridge type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type) Drill (WPDC Standard type)	B72 E30 E30 B72 B72 F79 F81 F80 F79 F81 F80 F79 F81 F80







WTXNR/L	Holder (Wedge Clamp System)	B179
WWLNR/L	Holder (Wedge Clamp System)	B180



XCET-KC	Milling Insert (Chamfer Tool)	E31
XDET-MA	Milling Insert (Pro-V Mill)	E31
XEKT-MA	Milling Insert (Pro-X Mill)	E31
XEKT-ML	Milling Insert (Pro-X Mill)	E31
XNCT-MA	Milling Insert (Rich Mill)	E31
XNKT-ML	Milling Insert (Rich Mill)	E32
XNKT-MM	Milling Insert (Rich Mill)	E32
XNMX-ML	Milling Insert (Rich Mill)	E32
XOET-ND	Drill Insert (KING DRILL)	F04
XOMT-LD	Drill Insert (KING DRILL)	F03
XOMT-PD	Drill Insert (KING DRILL)	F03
XOMT-RD	Drill Insert (KING DRILL)	F04
ХРМТ-ММ	Milling Insert (HAVE)	E32



ZDMT-R-MM	Milling Insert (BRE)	E33
ZPET-MM	Milling Insert (GBE)	E33
ZPMT-MM	Milling Insert (BT Tooling System, Tank Mill)	E33
ZPMT-R-MM	Milling Insert (BRE)	E33
ZPMT-R-MR	Milling Insert (BRE)	E33



#### **Head Office**

Holystar B/D, 326, Seocho-daero, Seocho-gu, Seoul, 06633, Republic of Korea

Tel: +82-2-522-3181 Fax: +82-2-522-3184, +82-2-3474-4744



### Cheongju Factory

55, Sandan-ro, Heungdeok-gu, Cheongju-si, Chungcheongbuk-do, 28589, Korea

Tel: +82-43-262-0141 Fax: +82-43-263-8731



#### Jincheon Factory

54, Gwanghyewonsandan 2-gil, Gwanghyewon-myeon, Jincheon-gun, Chungcheongbuk-do, 27807, Korea Tel: +82-43-535-0141 Fax: +82-43-535-0144



#### **KORLOY America**

620 Maple Avenue, Torrance, CA 90503, USA

Tel: +1-310-782-3800 Toll free: +1-888-711-0001 Fax: +1-310-782-3885

E-mail: sales.kai@korloy.com



#### **KORLOY Europe**

Gablonzer Str. 25-27, 61440 Oberursel, Germany Tel: +49-6171-277-83-0 Fax: +49-6171-277-83-59

E-mail: sales.keg@korloy.com



### **KORLOY India**

Plot No. 415, Sector 8, IMT Manesar, Gurgaon 122051, Haryana, India Tel: +91-124-4391790 Fax: +91-124-4050032

E-mail: sales.kip@korloy.com



#### **KORLOY Brasil**

Av. Aruana 280, conj. 12, WLC, Alphaville, Barueri, CEP06460-010, SP, Brasil

Tel: +55-11-4193-3810 E-mail: sales.kbl@korloy.com



#### **KORLOY Turkey**

Serifali Mahallesi, Burhan Sokak NO: 34 Dudullu OSB/Umraniye/Istanbul, 34775, Turkey Tel: +90-216-415-8874 E-mail: sales.ktl@korloy.com



#### **KORLOY Chile**

Av. Providencia 1650, Office 1009, 7500027 Providencia-Santiago, Chile Tel: +56-229-295-490 E-mail: sales.kcs@korloy.com



#### **KORLOY Russia**

Krasivy Dom office No. 305, Bld. 5, Novovladykinskiy proezd 8, 127106, Moscow, Russia

Tel: +7-495-280-1458 Fax: +7-495-280-1459

E-mail: sales.krc@korloy.com



### **KORLOY Factory India**


Plot No. 415, Sector 8, IMT Manesar, Gurgaon 122051, Haryana, India Tel: +91-124-4391790 Fax: +91-124-4050032

E-mail: pro.kim@korloy.com



### **KORLOY Global Network**

### We stand to be the Global Top Manufacturer. Korea's Best. World's Best





#### **Head Office**

Holystar B/D, 326, Seocho-daero, Seocho-gu, Seoul, 06633, Republic of Korea

Tel: +82-2-522-3181 Fax: +82-2-522-3184, +82-2-3474-4744

#### R&D Institute Cheongju

55, Sandan-ro, Heungdeok-gu, Cheongju-si, Chungcheongbuk-do, 28589, Korea

Tel: +82-43-262-0141 Fax: +82-43-262-0711

### KORLOY AMERICA

620 Maple Avenue, Torrance, CA 90503, USA Tel: +1-310-782-3800 Toll Free: +1-888-711-0001 Fax: +1-310-782-3885 E-mail: sales.kai@korloy.com

### KORLOY INDIA

Plot No. 415, Sector 8, IMT Manesar, Gurgaon 122051, Haryana, India Tel: +91-124-4391790 Fax: +91-124-4050032 E-mail: sales.kip@korloy.com

### KORLOY TURKEY

Serifali Mahallesi, Burhan Sokak NO: 34 Dudullu OSB/Umraniye/Istanbul, 34775, Turkey 

### **(A)** KORLOY RUSSIA

Krasivy Dom office No. 305, Bld. 5, Novovladykinskiy proezd 8, 127106, Moscow, Russia

Tel: +7-495-280-1458 Fax: +7-495-280-1459 E-mail: sales.krc@korloy.com

### **(a) KORLOY FACTORY INDIA**

Plot No. 415, Sector 8, IMT Manesar, Gurgaon 122051, Haryana, India Tel: +91-124-4391790 Fax: +91-124-4050032 E-mail: pro.kim@korloy.com

### PRINTED WITH

SOY INK

친환경 식물성 콩기름 잉크 인쇄



#### Cheongju Factory

55, Sandan-ro, Heungdeok-gu, Cheongju-si, Chungcheongbuk-do, 28589, Korea

Tel: +82-43-262-0141 Fax: +82-43-263-8731

#### **Jincheon Factory**

54, Gwanghyewonsandan 2-gil, Gwanghyewon-myeon, Jincheon-gun, Chungcheongbuk-do, 27807, Korea

Tel: +82-43-535-0141 Fax: +82-43-535-0144

### KORLOY EUROPE

Gablonzer Str. 25-27, 61440 Oberursel, Germany Tel: +49-6171-277-83-0 Fax: +49-6171-277-83-59 E-mail: sales.keg@korloy.com

### KORLOY BRASIL

Av. Aruana 280, conj.12, WLC, Alphaville, Barueri, CEP06460-010, SP, Brasil

### KORLOY CHILE

Av. Providencia 1650, Office 1009, 7500027 Providencia-Santiago, Chile Tel: +56-229-295-490 E-mail: sales.kcs@korloy.com

### KORLOY MEXICO

Calle R. M. Clemencia Borja Taboada 522, Jurica Acueducto, 76230 Juriquilla, Qro., Mexico